REPORT

ON

The Meteorology of India

IN

1883.

BY

HENRY F. BLANFORD, F.R.S.,

METEOROLOGICAL REPORTER TO THE GOVERNMENT OF INDIA.

NINTH YEAR.

00134437

CALCUTTA:
PRINTED BY THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.
1885.



Digitized with financial assistance from
Government of Maharashtra
on 01 February, 2020

LITHOGRAPHED FOR THE METEOROLOGICAL REPORTER TO THE GOVT. OF INDIA
at the Survey of India Offices, July 1884.

REPORT

ON

THE METEOROLOGY OF INDIA

IN

1883.

BY

HENRY F. BLANFORD, F.R.S.,
METEOROLOGICAL REPORTER TO THE GOVERNMENT OF INDIA.

134437

NINTH YEAR.

26/47/9

CALCUTTA:
PRINTED BY THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.
1885.

LIBRARY OF THE BOMBAY BRANCH OF THE ROYAL ASIATIC SOCIETY.

CALCUTTA:
PRINTED BY THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA,
166, DHURRUMTOLLAH STREET.

CONTENTS.

	Pages.
Introduction	1—3
Description of the Stations	3—4
Table I.—*Latitudes, Longitudes, and Elevations of the Meteorological Observatories*	5—8
Meteorology of 1883	9—150
Solar Radiation	9—18
Table II.—*Average excess of insolation over the corresponding maximum shade temperatures*	12—14
Table III.—*Comparison of excess sun (over-shade) temperatures in 1883, with the averages of Table II*	15—17
Duration of Bright Sunshine	18—19
Nocturnal Radiation	19—26
Table IV.—*Average depression of monthly mean nocturnal radiation temperatures below mean minimum shade temperatures*	20—22
Table V.—*Comparison of mean monthly depression of nocturnal radiation temperatures in 1883, with the averages of Table IV*	22—25
Temperature of the Ground	26—28
Table VI.—*Average monthly mean temperatures of the ground at the surface and at 3 feet deep*	28
Table VII.—*Comparison of the monthly mean temperatures of the ground in 1883, with the averages of Table VI*	28
Temperature of the Air	28—46
Table VIII.—*Average monthly mean temperatures of 128 stations in India, Ceylon, &c.*	32—35
Table IX.—*Comparison of monthly mean temperatures in 1883, with the averages of Table VIII*	35—39
Table X.—*Geographical Summary of the differences of Table IX*	39—40
Atmospheric Pressure	47—66
Table XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*	50—55
Table XIIA.—*Comparison of monthly mean pressures in 1883, with the averages of 9 years or less than 9 years, in the previous table*	55—58
Table XIIB.—*Comparison of monthly mean pressures in 1883, with the averages of more than 9 years*	59—60
Table XIII.—*Geographical Summary of the differences of Table XIIA*	60—61
Table XIV.—*Average differences of pressure at hill and plains stations*	62
Table XV.—*Comparison of pressure differences in 1883, with the averages of Table XIV*	62
Winds	66—70
Hygrometry	70—91
Table XVI.—*Average monthly mean vapour tension of 123 stations in India, Ceylon, &c.*	72—75
Table XVII.—*Average monthly mean relative humidity of 123 stations in India, Ceylon, &c.*	75—79
Table XVIII.—*Comparison of monthly mean vapour tension in 1883, with the averages of Table XVI.*	79—82
Table XIX.—*Comparison of the monthly mean relative humidity in 1883, with the averages of Table XVII*	83—86
Table XX.—*Geographical Summary of the differences of Table XVIII*	86—87
Table XXI.—*Geographical Summary of the differences of Table XIX*	87—88
Cloud Proportion	91—103
Table XXII.—*Average proportion of clouded sky in each month, deduced from the registers of past years*	92—95
Table XXIII.—*Comparison of mean cloud proportion in each month of 1883, with the averages of Table XXII*	95—99
Table XXIV.—*Geographical Summary of the differences of Table XXIII*	99—100

CONTENTS.

	Pages.
Rainfall	104—147
Table XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.*	106—116
Table XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*	117—128
Table XXVII.—*Geographical Summary of rainfall anomalies in 1883*	146
Table XXVIII.—*Annual anomaly of the rainfall of India (exclusive of the Burmese peninsula) from 1864 to 1883, inclusive*	147
Summary	148—150
Appendix.—*Abstract of Meteorological Registers for the year 1883*	1—305
Table I.—*Equilibrium temperatures of solar radiation in 1883 (111 stations)*	1—28
Table II.—*Duration of bright sunshine in 1883 (2 stations)*	29
Table III.—*Temperatures of nocturnal radiation in 1883 (107 stations)*	30—56
Table IV.—*Temperatures of the ground in 1883 (4 stations)*	57—58
Table V.—*Mean and extreme air-temperatures in the shade in 1883 (134 stations)*	59—92
Table VI.—*Sea-level equivalents of monthly mean air-temperatures in 1883 (112 stations)*	93—95
Table VII.—*Monthly means and extremes of pressure in 1883 (125 stations)*	96—127
Table VIII.—*Monthly means of pressure in 1883, reduced to their sea-level values*	128—130
Table IX.—*Direction and mean movement of winds in 1883 (127 stations)*	131—209
Table X.—*Temperature of evaporation in 1883 (124 stations)*	210—240
Table XI.—*Tension of atmospheric vapour in 1883 (130 stations)*	241—255
Table XII.—*Mean relative humidity of the air in 1883 (130 stations)*	256—268
Table XIII.—*Mean proportion of clouded sky in 1883 (127 stations)*	269—279
Table XIV.—*Inches of rainfall in each month of 1883 (462 stations)*	280—292
Table XV.—*Number of days on which rainfall was measured in 1883 (462 stations)*	293—305

REPORT

ON THE

METEOROLOGY OF INDIA IN 1883.

INTRODUCTION.

IN the following report I give an analysis of the meteorological features of the year 1883 in India and its dependencies; this being the ninth that has been issued, since the re-organization of the Meteorological Department, in 1875, rendered it for the first time possible to treat the subject as an organic whole. In its general plan, the report differs but little from its predecessors; the general principle of the discussion being to compare each meteorological feature of each station and subdivision of the country, month by month, with its corresponding average, as deduced from the records of as many past years as possible; and, regarding the differences which result from this comparison as the anomalies of the year, to draw attention to such coincidences or sequences as appear to shew the operation of a law, or to be explicable by the accepted laws of physical action.

Since the year 1877, when there was a complete failure of the rains over a large area in the North-Western Provinces and Rajputana, India has been unvisited by any severe and extensive drought, although scarcely a year passes, in which, in some part or other of the vast area, a greater or less loss of the crops is not brought about by the local deficiency of the rainfall. Such was the case in the year reviewed in these pages. The rainfall of North-Western and Western India was interrupted for a space of from three to five weeks in the months of July and August, and the country was saved from a repetition of the disaster of 1877 only by the timely resumption of the rains at the end of the latter month, and a drenching, if not prolonged, downpour in the early part of September. In Behar and Bengal, especially the northern districts, the rainfall was scanty throughout; and this, in conjunction with an early cessation of the rains, caused a widespread loss of agricultural produce, though not of such severity as to demand the adoption of extraordinary measures of famine relief.

A recent investigation of the records of rainfall for the past 20 years has brought to light some peculiarities in the relative precariousness of the rainfall in different parts of

India, which have much interest, both from an economic and a scientific point of view, and their detection may prove to be only the first step towards a more complete explanation of the meteorological and geographical conditions which determine the occurrence of drought and famine.

As a general rule, the rainfall is most variable in those regions where the average rainfall is smallest, such as are Sind and Cutch, and the desert tract of Western Rajputana; and least so, in the tracts of heaviest rainfall. But to this rule there are some striking and most instructive exceptions. The average rainfall of the Gangetic plain is not much less than double than that of the Punjab province, but the variability of the rainfall of the North-Western Provinces and Oudh, from year to year, is second only to that of the rainfall of Sind and the western desert, and nearly twice as great as that of the Punjab and Eastern Rajputana; and Behar stands next to it. On the other hand, the rainfall of Nagpur, although only about 1-7th greater on an average than that of Behar, has a mean variability only about half as great, and is as regular as that of Lower Bengal.

Periods of drought in the North-Western Provinces are now known to be those, during which dry westerly or north-westerly winds displace the more usual easterly winds of the rainy season; and it is to the unseasonable irruption of these winds, more frequently in the North-Western Provinces than elsewhere, that the frequent vicissitudes of the rainfall of the Gangetic plain are mainly to be attributed. But north-west winds operate in the same way in Rajputana, Central India, Gujarat, and even down to the Concan and Deccan, where winds of the same character are the normal winds of the spring season.

It has been shewn in former reports, more especially that for 1878, that years of severe and prolonged drought have been those in which the pressure of the atmosphere has been unduly high, and there is in all probability a direct connection between this condition and the persistence of the dry winds in those years. But there is evidently some other condition which operates in producing these winds, and in retarding or interrupting the rainfall in years such as 1883, when the atmospheric pressure does not exceed the average and may even be below it. The dry winds in such seasons are less lasting, but for a time they are as strongly marked as in famine years. I have given elsewhere[1] my reasons for believing that in such cases they are due to an unusual extent and thickness of snow on the North-Western Himalaya.

For some years past, either the spring snowfall has been light or at all events has not continued till late in the season. But in 1883 it was comparatively heavy, and a late fall took place on the last days of May, though restricted to the outer ranges. Judging therefore from previous experience, it appeared probable that the rains would be retarded in the Upper Provinces, and a note to that effect was published in the *Gazette of India* of the 2nd June. The result was that described in the following pages. It was not exactly in accordance with the terms of the forecast, inasmuch as the setting-in of the rains in the Upper Provinces took place only a few days later than on the average, and rather more than a fortnight of rainy weather preceded the period of drought which set in on the 19th July. But there were indications that throughout this rainy interval the influence of the snows was operative. On the North-Western Himalaya, the rain of the first half of July was accompanied with frequent thunder-storms and hail-storms (always a sign of an unsteady monsoon); and in clear intervals, the upper clouds could

[1] Proc. Royal Soc., No. 232, 1884.

be seen drifting steadily from the north-west, proving the existence, at no great height, of the dry current, which, about the 19th, descended and replaced the monsoon, prevailing over the whole of Northern India and Rajputana, and influencing the winds down to the Deccan on the south, and to Behar on the east.

Reviewing all the circumstances, there seems good reason for the conclusion that the experience of this season confirms the validity of the view on which the forecast was based.

DESCRIPTION OF THE STATIONS.

Excepting Tura, the Seychelles and Kailang, the registers of which appear for the first time in the present report, and also Ghazipur, all the stations which have contributed data for 1883 have been described more or less completely in former reports. Of the Tura, Seychelles and Ghazipur observatories, no descriptions have been received. Of Kailang I give below a brief notice, and also more detailed descriptions than have hithertofore been published of some other observatories.

Kailang.—In Lahoul, a native hill state in the North-Western Himalaya. Kailang is a station of the Moravian Mission under the direction of the Reverend A. W. Heyde, to whose kindly volunteered co-operation the establishment of the observatory is due. The station is situated in the upper valley of the Chandra Bhaga or Chenab river, at an elevation of about 10,000 feet above the sea, and to the north of two snowy ranges, *viz.*, the Dhaoladhar, and that between the Ravi and Chenab, which is crossed by the Rotang pass. It is, therefore, very completely shut off from the plains of India, and represents more truly than any other station, except Leh, the climate of the mountain region.

Sibsagar.—On the alluvial plain of Upper Assam, rather more than 8 miles south of the main stream of the Brahmaputra. The country between the station and the river is chiefly a mud swamp covered with tall grass and other swamp vegetation, with only occasional patches of tree-jungle. Immediately to the south of the station the ground has been cleared and is much occupied by tea-gardens, and about 20 miles off rise the Naga hills, some points of which attain to 6,500 feet.

The station is built on the artificial *band*, or dyke, surrounding a large square tank, half a mile in the side, the water level of which stands above that of the surrounding country. The dyke is broad, and is traversed along its whole length by a good road, on the outside of which are the houses and their compounds, and the reverse slope descends to a broad moat, which has been excavated to furnish materials for the embankment: water is, therefore, abundant in all directions, and the climate is very damp. In the cold season, fogs frequently prevail till midday. The observatory is situated on the north side of the dyke, on ground formerly occupied by the jail. The thermometer shed is built on the upper part of the outer slope, 4 or 5 feet below the summit, and is somewhat shut in by the old jail buildings, in one of which is the barometer; the wind-vane and anemometer being mounted on the parapet of the same building. As the building is about 20 feet high and is situated on the top of the *band*, with no large trees in the immediate neighbourhood, the exposure is fairly good.

Silchar.—The geographical position of this station has been described in the Report for 1875, page 27. The site of the present observatory, which was established there in 1880, is in front of the jail, on rather high ground, having a fairly good exposure, and overlooking a low flat, on all sides except the east. The jail building, on the same level, is 100 yards off to the south-east, and somewhat overtops the wind-vane and anemometer, which are set up on two posts within the observatory enclosure. There is a high tree 300 or 400 yards off to the east, and, at a distance of half a mile to the south-west, the plain is bounded by a low hill ridge (a *tila*), which, with the trees on it, is somewhat higher than the observatory. With these exceptions, there is nothing to dominate the observatory. The thermometer shed, a large thatched shed, 27 feet × 22 feet in the eaves, the barometer room, the anemometer, and wind-vane posts, and the small railed enclosure for the exposed thermometers, all stand within an oblong railed space, about 90 feet long from north to south and 40 feet broad.

Kurnool.—Situated at the junction of the Hindey and Tungabadra rivers, in the somewhat elevated country to the west of the Eastern Ghâts, about 900 feet above the sea, and 141 miles distant therefrom. The country around is undulating and thinly wooded; the ground dry and the soil stony, with rock near the surface. The station is situated in a hollow, the view to the east being terminated by a low range of hills about 5 miles distant; and on the west and north the ground rises gently for about 1½ miles. On the south it also rises to the base of a long low hill, about 4 miles distant; other hills are the Eramullies, 20 miles off to the south, and the Nullamullies, a range of the Eastern Ghâts, 48 miles off to the east. Seventeen miles up the river, a large expanse of water is held back by the annicut across the Tungabadra, but there is no large body of water near the station, other than the two rivers, the expanse and volume of which vary according to the season.

The observatory is situated at the Post Office, the situation of which, with respect to the town, is not described. The barometer is in the signal-room of the office, hung against the north wall, and illuminated by a sky-light. The thermometer shed is on a piece of open ground, 200 feet × 130 feet, a furlong off, and bounded on the north and east by a public road, on the west by a bye-road, and on the south by a store-building of the Public Works Department. There is no obstruction within 50 feet of the shed all round. The sun thermometer is exposed in the open ground opposite the shed, in the centre of a fenced enclosure, 32 feet × 10 feet, and 10 feet from the south end of the shed. The rain-gauge is in the same enclosure, 24 feet from the shed.

The anemometer and wind-vane were not set up at the date of the report, of which the above is an abstract.

Table I on the following pages gives the latitude and longitude of each station to the nearest minute of arc, and the elevation of the barometer; which, with very few exceptions, has been determined by spirit-levelling, either to datum levels, fixed by the spirit-levelling operations of the Survey of India, to stations measured by the Great Trigonometrical Survey, or to the levels of the railway lines.

At the following stations the barometer has been removed to a level different from that which it occupied previously; and the change of elevation must, therefore, be

allowed for, in comparing the barometric registers of 1883 with those given in previous reports:—

Stations.	Former elevation.	Present elevation.	Date of change.
Katmandu	4,361 feet	4387·80 feet	10th March 1883.
False Point	20·60 „	17·48 „	9th „ „
	17·48 „	20·60 „	1st April „
Sambalpur	451 „	463 „	3rd October „
Khandwa	1024·20 „	1043·71 „	1st July „
Kurnool	914·41 „	934·53 „	9th February „

The elevation of Pachbudra has been re-computed from the barometric registers since March 1883, which there is reason to regard as more trustworthy than those that furnished the data for the former determination. The comparison has been made, first with Bickaneer and Deesa, and secondly with Ajmere, Jacobabad, and Hyderabad. The first pair of stations gave a mean value of 373 feet for the Pachbudra barometer; the second triad 388 feet. The value formerly obtained was 398·5 feet.

TABLE I.—*Latitudes, Longitudes, and Elevations of the Meteorological Observatories.*

Provinces.	Stations.	Latitude, north.	Longitude, east.	Elevation in feet above mean sea-level.	Level determined.	How determined.	Authority for Elevations.
Africa	Seychelles	...	...	25·3	Bar. cistern	.....	Government Surveyor of Seychelles.
	Zanzibar	−6° 10′	39° 11′	22·6	Ditto	Above half-tide.	Dr. C. T. Peters.
Arabia	Aden	12° 45′	45° 3′	94·2	Barometer	Determined from the 9′ mark on the tide gauge.	Assistant Resident, Aden.
Persia	Bushire	28° 59′	50° 49′	25′	Ditto	.....	Colonel Ross.
Beloochistan.	Quetta	30° 11′	67° 3′	5,500	Ground, approximately.	.....	Surgeon-Major T.S. Veale.
Cashmere	Leh	34° 10′	77° 42′	11,502·96	Bar. cistern	By spirit-level to G. T. Survey B. M.	J.-B. Morris, Esq., C.E.
	Kailang	32° 34′	77° 4′	10,087	Ditto	By barometer, from Leh and Simla 1 year.	H. F. Blanford.
Punjab	Mooltan	31° 10′	71° 33′	420·19	Mercury of bar. cistern.	Levelled from G. T. Survey B. M.	J. D. Davis, Esq., C.E.
	Dera Ismail Khan.	32° 0′	71° 5′	572·56	Ditto Ditto	By spirit-level to G. T. Survey B. M.	Major Thorold.
	Peshawar	34° 2′	71° 37′	1,110·4	Bar. cistern, Police Hospital.	By spirit-level to G. T. Survey B. M.	Bomford Lovett, Esq., Ex. Engr., Hazara Division.
	Murree	33° 40′	73° 8′	6,343·86	Mercury of bar. cistern.	By spirit-level to G. T. Survey B. M., on Prospect Hill, 1·48 miles distance.	A. Grant, Esq., Assistant Engineer.
	Rawalpindi	33° 4′	73° 5′	1,652·24	Bar. cistern, Civil Dispensary.	.....	J. B. Morris, Esq., C.E.
	Sialkot	32° 29′	74° 35′	829·47	Plinth of City Hospital.	Levelled ½ mile to bridge	Major-General J. D. Campbell, R.E.
	Lahore	31° 34′	74° 20′	731·89	Bar. cistern	Measured from G. T. Survey B. M.	Lala Sagur Mull.
	Ludhiana	30° 55′	75° 54′	811·86	Ditto	Levelled from milestone No. 3 from Ludhiana.	Ex. Engr., Umballa and Ludhiana Road, 1st Division.
	Simla	31° 6′	77° 12′	7,020·	Mercury of bar. cistern.	Levelled to ground level of former site.	B. Parkes, Esq., C.E.
	Delhi	28° 40′	77° 16′	717·81	Ditto Ditto	Levelled from B. M., Cabul Gate.	J. C. Sarkar, Ex. Engr.
	Sirsa	29° 32′	75° 6′	661·61	Ditto, Jail Dispensary-room.	By spirit-level to G. T. Survey B. M.	R. K. Mukerji, Supervisor.
N.-W. Provinces and Oudh.	Chakrata	30° 40′	77° 55′	7,051·58	Mercury of bar. cistern.	Levelled from G. T. Survey B. M.	Government, N.-W. Provinces, P. W. D.
	Mussooree (St. Fidelis).	30° 26′	78° 8′	5,857·5	Ditto	Ditto ditto	S. A. Hill, Esq., B Sc.'
	Dehra	30° 20′	78° 8′	2,232·4	Ditto	G. T. Survey, by spirit-level.	J. B. N. Hennessy, Esq.
	Paori	30° 8′	78° 55′	5,103·1	Bar. cistern	Barometrically from one year's registers.	S. A. Hill, Esq., B.Sc.
				5,230·19	Ditto	By spirt-levelling from G. T. B. M. at Paori.	J. Thornhill, Esq., C.E.

TABLE I.—*Latitudes, Longitudes, and Elevations of the Meteorological Observatories*—contd.

PROVINCES.	STATIONS.	Latitude, north.	Longitude, east.	Elevation in feet above mean sea-level.	Level determined.	How determined.	Authority for Elevation.
N.-W. PROVINCES AND OUDH—*contd.*	Roorkee	29° 52′	77° 56′	886·63	Mercury of bar. cistern.	By spirit-level to two G. T. Survey spirit-level B. M.	Ex. Engr., Saharanpur.
	Ranikhet	29° 38′	79° 29′	6,068·75	Ditto	From G. T. Survey B. M.	Ex. Engr., Military Works.
	Pithoragarh	29° 35′	80° 15′	5,373·15	Bar. cistern	Barometrically from one year's registers.	S. A. Hill, Esq., B.Sc.
	Meerut	29° 41′	77° 41′	737·48	Mercury of bar. cistern.	From G. T. Survey B. M.	Ex. Engr., Meerut Division.
	Bareilly	28° 21′	79° 27′	568·47	Ditto	Level from G. T. Survey B. M.	Commissioner of Rohilkhand.
	Agra	27° 10′	78° 5′	555·44	Top of bar. cistern	By spirit-level to B. M. of G. T. Survey.	Sub-Overseer, Mustag Ahmed.
	Lucknow	26° 50′	81° 0′	369·4	Bar. cistern	By measurement to G.T. Survey B. M., on Museum building.	Dr. Bonavia.
	Gorakhpur	26° 46′	83° 18′	255·93	Ditto	Level from Trigonometrical level.	Government, N.-W. Provinces, P. W. D.
	Jhansi	25° 27′	78° 37′	855·4	Bar. cistern of Dispensary.	From the levels of the Bundelkhand Irrigation Works.	Commissioner of Jhansi.
	Allahabad	25° 26′	81° 52′	306·68	Bar. cistern	By spirit-level to G. T. Survey B. M., in fort.	Secretary, Dept. P. W., N.-W. Provinces.
	Benares	25° 20′	83° 2′	266·97	Bottom of bar. cistern.	By spirit-level to G. T. Survey, spirit-level B. M.	Secretary, Dept. P. W., N.-W. Provinces.
	Ghazipur	25° 35′	83° 39′	219·74	Bar. cistern	By levelling from the B. M. at Collector's kachari.	Sub-divisional Officer, P. W. Dept.
NEPAL	Katmandu	27° 42′	85° 12′	4,361′ / 4,387·8a	Top of bar. cistern / At Dispensary	.....	C. E. R. Girdlestone, Esq., C.S., Resident in Nepal.
ASSAM	Sibsagar	26° 59′	94° 40′	333′	Bar. cistern	Measured from G. T. Survey B. M.	M. Mookerjea.
	Dhubri	26° 7′	89° 50′	115·34	Mercury of bar. cistern.	Determined from the trigonometrical pillar by levelling.	Mr. Clancy, Assistant Enginer, Dhubri.
	Silchar	24° 49′	92° 50′	104·3	Bar. cistern	Level taken by the P. W. Department.	Dr. J. J. Monteath.
	Tura	25° 30′	90° 17′				
BENGAL	Darjeeling (St. Paul's School).	27° 3′	88° 18′	7,421·1	Ditto	By spirit-level to G. T. Survey B. M.	Captain H. T. Harman, R.E.
	Purneah	25° 50′	87° 34′	125′	(?)	By spirit-level to church.	Dr. Picachy.
	Durbhunga	26° 0′	86° 0′	166·32	Bar. cistern	Levelled from B. M. quarter of a mile distant.	Superintending Engineer, Raj Durbhunga.
	Patna	25° 37′	85° 8′	182·84	Ditto	By levelling from the old position.	W. H. King, Esq., C.E.
	Gya	24° 42′	85° 2′	374·9	Ditto	Levelled from G. T. Survey spirit-level, B.M. at Bankipore Railway Station.	M. P. B. Duell, Esq., C.E.
	Hazaribagh	24° 0′	85° 24′	2,007·12	Ditto	.....	Assistant Engineer, P. W. Dept.
	Berhampore	24° 6′	88° 17′	66·45	Ditto	By spirit-level to Irrigation Department B. M.	G. Pearson, Esq.
	Burdwan	23° 14′	87° 54′	99·09	Ditto	.....	Dr. Joubert.
	Jessore	23° 9′	89° 7′	33·29	Ditto	By spirit-level to B. M. on 73rd milestone from Calcutta.	Babu Nobo Gopal Dutt.
	Dacca	23° 43′	90° 27′	35	Ditto	Measured above ground level, G. I. Estimated.	H. F. Blanford.
	Chittagong	22° 21′	91° 50′	86·7	Ditto	.....	Ditto.
	Demagiri	22° 27′	92° 15′				
	Calcutta (Alipore).	22° 32′	88° 20′	21·38	Ditto	By spirit-level to Kydd's Dock B. M.	Ditto.
	Calcutta (Chowringhee).	22° 33′	88° 21′				
	Saugor Island	21° 39′	88° 5′	25·3	Ditto	.....	Telegraph Master.
	Cuttack	20° 29′	85° 54′	80	Ditto	By spirit-level to Irrigation Department B. M.	T. S. Isaac, Esq., C.E.
	False Point	20° 20′	86° 47′	20·60	Ditto	By levelling	Major Rogers in charge of the Levelling and Tidal Operations, Survey of India.

a Changed to 4387·8 feet on the 10th March 1883. The barometer was removed to the Dispensary-room.

Table I.—Latitudes, Longitudes, and Elevations of the Meteorological Observatories—contd.

Provinces.	Stations.	Latitude, north.	Longitude, east.	Elevation in feet above mean sea-level.	Level determined.	How determined.	Authority for Elevations.
Bengal—*contd.*	False Point	...	...	17·48[a]	Bar. cistern	Determined from the former height.	E. Workman, Meteorological Observer.
	Sambalpur	21° 31′	81° 1′	451°	Ditto	By spirit-level from Top. Survey B. M.	Dr. Townshend, Honorary Surgeon-Major.
	"	...	...	463[b]	Ditto	Determined from the former height.	J. E. Harrison.
	Raipur	21° 15′	81° 41′	960	Ditto	By spirit-level, from Nagpur, 175 miles.	Dr. Townshend.
	Nagpur	21° 9′	79° 11′	1,025	Ditto	By spirit-level from G.T. Survey B. M. and Railway.	Ditto.
	Seoni	20° 6′	79° 6′	2,030	Ditto	By spirit-level from G.T. Survey B. M.	Ditto.
Central Provinces	Jubbulpore	23° 9′	79° 59′	1,340·75	Ditto	By levelling between former and present situation.	D. P. W.
	Saugor	23° 49′	78° 48′	1,768·9	Ditto	Levelled from Revenue B. M.	Exe. Engineer, Saugor.
	Pachmarhi	22° 28′	78° 28′	3,528°	Ditto	.....	Exe. Engr., Hoshangabad Division.
	Hoshangabad	22° 45′	77° 46′	1,020	Ditto	By spirit-level from Itarsi Railway Station, 11 miles.	Ditto, ditto.
	Khandwa	21° 49′	76° 23′	1,024·23	Ditto	From the former height.	Dr. P. Cullen, M.D.
				1,043·71[c]	Ditto	Ditto ditto	Ditto.
	Chanda	19° 56′	79° 19′	651·89	Ditto at Police Hospital.	By spirit-level to railway at Wardah Station, G. I. P. Railway.	T. S. O'Callaghan, Esq., C.E.
	Sironcha	18° 51′	80° 0′	401·29	Bar. cistern	Levelled from G. T. Survey B. M.	Exe. Engr., Nagpur Division.
	Chikalda	21° 24′	77° 22′	3,656·	Ditto	.....	F. Chambers, Esq.
				3,656·21[d]	Ditto at Dispensary room.	Determined from the former height.	Heralal, Metgl. Observer.
Berars	Buldana	20° 34′	76° 14′	2,131·76	Barometer	By spirit-level to rails at Mulkapur Station.	F. Chambers, Esq.
	Akola	20° 42′	77° 4′	930	Ditto	By spirit-level to rails of Railway Station.	J. F. Pope, Esq.
	Amraoti	20° 55′	77° 43′	1,213·38	Ditto	By spirit level to rails at Baduera station,	F. Chambers, Esq.
Central India	Neemuch	24° 25′	75° 0′	1,639·36	Bar. cistern	.....	Ditto.
	Nowgong	25° 2′	79° 29′	757·04	Ditto	Levelled to G. T. Survey B. M. on Mow Hill.	Exe. Engr., Bundelkhund Roads.
	Sutna	24° 34′	80° 52′	1,040·1	Barometer	By spirit-level to railway station.	Dr. S. J. Goldsmith.
	Indore	22° 44′	75° 53′	1,823·2	Bar. cistern	From the former height.	Meteorological Observer.
Rajputana	Bickaneer	27° 59′	73° 14′	743·5	Ditto	Ground-level by G. T. Survey.	F. Chambers, Esq.
	Jeypore	26° 55′	75° 50′	1,430·6	Ditto	Spirit-levelling to G. T. Survey level.	Agency Surgeon, C. R. S. Agency, Jeypore.
	Sambhar	26° 55′	75° 14′	1,253·52	Ditto	.....	S. A. Hill, Esq., B. Sc.
	Ajmere	28° 26′	74° 37′	1,611	Ditto	From the previous height	Ditto.
	Mount Abu	24° 36′	72° 45′	3,945	Ditto	.....	F. Chambers, Esq.
	Pachbudra	25° 55′	72° 18′	380	Ditto	By barometer (see page 5).	H. F. Blanford.
Bombay	Jacobabad	28° 24′	68° 18′	185·9	Ditto	.....	F. Chambers, Esq.
	Hyderabad	25° 25′	68° 27′	134·4	Ditto	From B. M. on the Wadoo Canal.	Mr. A. Banks, Supervisor, P. W. D.
	Kurrachee	24° 47′	67° 4′	49°	Ditto	.....	F. Chambers, Esq.
	Bhuj	23° 15′	69° 42′	395·12	Ditto	By spirit-level to base of pillar No. 4, in cantonment.	Joggernath Sadashib, Esq.
	Rajkot	22° 17′	70° 52′	428·83	Ditto	Determined from G. T. Survey B. M.	Mr. R. B. Booth, Agency Engr.
	Deesa	24° 16′	72° 14′	465·5	Ditto	Measured from G. T. Survey B. M.	N. Hennessy, Esq.
	Surat	21° 13′	72° 46′	36.	Ditto	.....	E. Chambers, Esq.
	Malegaon	20° 34′	74° 22′	1,430·12	Ditto	By spirit-level to B. M., distant 8,620 feet from the Observatory.	A. T. Anderson, Esq., Exe. Engr., Northern Division.

[a] From the 9th to 31st March 1883 the barometer was temporarily removed to a different position.

[b] Changed to 463 feet on the 3rd October 1883. The Observatory was removed to a new site on this date.

[c] Changed to 1,043·71 feet on the 1st July 1883. The barometer was removed to another room.

[d] Changed to 3,656·21 on the 1st June 1883. The barometer was removed to the Dispensary-room.

TABLE I.—*Latitudes, Longitudes, and Elevations of the Meteorological Observatories.*—contd.

PROVINCES.	STATIONS.	Latitude, north.	Longitude, east.	Elevation in feet above mean sea-level.	Level determined.	How determined.	Authority for Elevations.
BOMBAY—*contd.*	Bombay	18° 54′	72° 49′	37	Bar. cistern	.....	C. Chambers, Esq.
	Poona	18° 28′	74° 10′	1,849·2	Ditto	.....	F. Chambers, Esq.
	Sholapur	17° 41′	75° 56′	1,589·56	Ditto	Levelled to B. M. distant about 200 feet from the Military Hospital.	Mr. G. B. Dante, Overseer, P. W. Dt.
	Ratnagiri	17° 6′	73° 23′	110·	Ditto	Levelled to B. M. on School of Industry.	C. Brereton, Esq.
	Belgaum	15° 52′	74° 42′	2,550	Ditto	.....	Surgeon-Major B. Buckland.
	Karwar	14° 8′	74° 2′	43·87	Ditto	Levelled to G. T. Survey B. M.	W. J. Listor, Esq., Exe. Engr., Karwar.
MADRAS, MYSORE, AND COORG.	Vizagapatam	17° 42′	83° 22′	31	Ditto	.....	A. V. Nursing Rao, Esq.
	Masulipatam	16° 9′	81° 12′	10·16	Barometer	Levelled from half-tide level.	Lieutenant D. Campbell, R.E.
	Secunderabad	17° 27′	78° 33′	1,786·69	Bar. cistern	By spirit-level.	Exe. Engr., Secunderabad.
	Kurnool	15° 50′	78° 7′	934·53	Ditto	.....	J. Carnac, Esq., Offg. Exe. Engr., Kurnool.
	Bellary	15° 9′	76° 57′	1,455·4	.....	.....	.....
	Mangalore	12° 52′	74° 54	52·03	Ditto	.....	B. C. Baily, Esq.
	Mercara	12° 26′	75° 48′	3,694·5	Ditto	Levelled from G. T. Survey B. M. on Kumdonmoti Hill.	E. Morton, Esq., Supervisor.
	Bangalore	12° 59′	77° 38′	2,981·46	Ditto	By spirit-level to G. T. Survey B. M. near the Observatory.	Colonel Mdberly, District Engr., Bangalore.
	Madras	13° 4′	80° 14′	22	Ditto	.....	N. R. Pogson, Esq.
	Salem	11° 39′	78° 12′	939·91	Ditto	By spirit-level from G. T. Survey B. M.	District Engr., Salem.
	Wellington	10° 22′	76° 50′	6,200	Barometer	Reduced from Kumdanugi Peak.	Major Morant, R.E.
	Coimbatore	11° 0′	77° 0′	1,347·64	Bar. cistern	From rail-level at Coimbatore Station.	Colonel C. Wilkinson, R.E.
	Trichinopoly	10° 50′	78° 44′	274·85	Ditto	Levelled from S. D. R. B. M.	Capt. H. F. Morris, R.E.
	Negapatam	10° 46′	79° 53′	15	Barometer	By spirit-level to high-water mark, half-tide estimated.	Supdt., Metgl. Observatory, Negapatam.
	Madura	9° 55′	78° 10′	447·97	Bar. cistern	Levelled from Railway Station.	Major A. Scott, R.E.
	Cochin	9° 58′	76° 17′	11·03	Ditto	Levelled from mean sea-level.	P. W. Dept.
CEYLON	Colombo	6° 56′	79° 52′	40	Ditto	By levelling	J. Stoddart, Esq.
	Jaffna	9° 40′	79° 56′	9	Ditto	Ditto	Colonel A. B. Fyers, R.E.
	Trincomalee	8° 33′	81° 15′	175	Ditto	By barometric readings.	Ditto.
	Batticaloa	7° 43′	81° 44′	26	Ditto	.....	Ditto.
	Hambantota	6° 7′	81° 7′	40	Ditto	.....	Ditto.
	Galle	6° 1′	80° 14′	48	Ditto	By levelling	J. Stoddart, Esq.
	Kandy	7° 18′	80° 40′	1,696	Ditto	Ditto	Colonel A. B. Fyers, R.E.
	Newera Eliya	6° 59′	80° 47′	6,240	Ditto	Ditto	Ditto.
BURMA	Akyab	20° 28′	92° 57′	20·44	Ditto	Above half-tide level by spirit-level.	H. F. Blanford.
	Thayetmyo	19° 22′	95° 12′	134	Ditto	Levelled to highest flood of the Irawaddy.	Lieut. R. O. Lloyd, R.E.
	Tounghoo	18° 57′	96° 24′	169·20	Ditto	By spirit-level to B. M. of railway on Fort wall.	Ex. Engr., Tounghoo Division.
	Bassein	16° 4′	94° 50′	35	Ditto	By aneroid to half-tide level of river.	Dr. Baker.
	Diamond Island	15° 52′	94° 19′	41	Ditto	Levelled to mean tide-level.	Mr. Luke, Asst. Supdt., E. T. D.
	Rangoon	16° 46′	96° 12′	40·69	Ditto	Level to half-tide level	Dr. A. Crombie.
	Moulmein	16° 29′	97° 40′	93·79	Ditto	Levelled to G. T. Survey B. M. on Oozina Hill.	Ex. Engineer, Tenasserim Division.
	Mergui	12° 11′	98° 38′	96·27	Ditto	Levelled to half the highest spring-tide.	Ex. Engineer, Tenasserim Division.
BAY ISLANDS	Port Blair	11° 41′	92° 2′	61·16	Ditto	Above half-tide level by spirit-level.	Capt. DeWolski, R.E.
	Nancowry	8° 0′	93° 46′	81	Ditto	Ditto	Ex. Engr., Andamans and Nicobars.

METEOROLOGY OF 1883.

The Meteorology of the year is described under the following heads :—

TEMPERATURE OF SOLAR RADIATION.	ANEMOMETRY.
DURATION OF SUNSHINE.	HYGROMETRY.
TEMPERATURE OF NOCTURNAL RADIATION.	CLOUD PROPORTION.
,, OF THE GROUND.	RAINFALL.
,, OF THE AIR.	SUMMARY.
ATMOSPHERIC PRESSURE.	

The average distribution of temperature and pressure, and the mean resultant wind directions in each month, are shewn on the Charts II to V.

The tables, giving an abstract of the observations of all stations, form the Appendix. The full registers of the six stations, Calcutta, Lucknow, Lahore, Nagpur, Bombay, and Madras, which in the first four annual reports formed a second Appendix, are now published in a separate form.

SOLAR RADIATION.

The solar radiation thermometer, employed at Indian stations,[1] is a self-registering mercurial thermometer, having the bulb and half an inch of the stem coated with lamp-black, and enclosed in a large tube, from which the greater part of the air is exhausted. Excepting at some of the Madras stations, all the instruments in use during the past year have been compared, directly or indirectly, with an arbitrary standard instrument of the same construction, (Casella No. 9174) by thirty readings or more, taken, when the instruments compared and the standard were exposed, under similar conditions, to the sun's rays; and the mean difference of the readings, thus ascertained, has been applied as a correction to all recorded readings of the former.[2] In some cases this correction amounts to as much as 15° or 20°, and no registers can be regarded as comparable which have not been subjected to this precautionary correction.

The temperature shewn by these instruments being that of equilibrium, when the heat received in each second from the sun and from surrounding objects, is exactly

[1] Any exceptions are noted in the tables.

[2] The circumstances on which these differences depend have lately been investigated by Mr. G. M. Whipple, F.R.S., the Superintendent of the Kew Observatory. He finds that the temperatures shewn by thermometers, which are alike in the size, thickness and material of the enclosing jacket, and in the degree of exhaustion, are greatly affected by, 1st, the thickness of the black coating; and, 2nd, small differences in the size of the thermometer bulbs. The thicker the coating and the larger the bulb, the higher is the temperature shewn by the thermometer. Moreover, it appears that, as the difference of insulation (over shade) temperature increases, the temperature shewn by large bulbs and thickly-coated bulbs increases more rapidly than that of smaller bulbs and those less thickly coated. Hence the correction to be applied to any thermometer is not constant, but is a function of the temperature (or of the excess temperature).—See Quart. journ. R. Meteorological Society, Vol. X., page 45.

equal to that radiated away in the same interval to the sky and objects around, in order that the excess of this temperature above that of the atmosphere may be taken as a measure of the solar effect, it is obvious that surrounding objects and their distance from the instrument must remain unchanged. Hence the readings, even of one and the same sun thermometer are not comparable *inter se* if the place of its exposure has been changed. The considerable and constant differences, shewn between the maximum recorded temperatures of different stations, are probably mainly due to unavoidable differences in the circumstances of the exposure. In order to minimize the effect of small unavoidable variations in the character of the ground immediately below the instrument, stands, 4 feet high, have been provided at all stations established within the last eight years: also at the majority of the older stations. At some few only of the latter, it has been deemed of more importance to preserve uniformity with the practice of former years than to introduce this improvement. The use of the stand is, in all cases, noticed in the tables. It is to be observed that, at some of the stations, the stand has been fixed rather deeper in the ground than at others, so that the height of the instrument is not uniformly 4 feet as was intended; but the difference is rarely more than a few inches.

The air temperature, which is deducted from that of the solar thermometer, in order to obtain the excess due to radiation, is that shewn by the maximum shaded thermometer. The residue is probably somewhat less than the actual effect of the sun's rays, since the maximum air temperature is produced an hour or two later than the maximum solar effect; but, on an average, the error arising from this source may be regarded as uniform; and, in any case, the most accurate observation can be only a relative measure of the solar effect.

The above precautions, if strictly observed, should give observations that are fairly comparable with each other at one and the same station; but, in some instances, it has been found that the substitution of a new thermometer for one that has been injured or accidentally destroyed, has been followed by such a change in the average value of the readings as to induce a suspicion that some uneliminated error affects the readings of the substituted instrument. In order, therefore, to distinguish those registers that are not open to any suspicion of this kind, I have given in the reports for the three previous years lists of all the changes, both of the instruments employed and of their position or mode of exposure, that have been made in the eight years 1875-82, as far as the necessary information exists in the Office.

The following is a similar list for the year 1883:—

Dates of any change of the instruments used for registering solar temperature or of the circumstances locally affecting them.

Stations.	Date of change.	Remarks.
Mooltan	23rd November 1883 . . .	New thermometer substituted.
Peshawar	23rd January „ . . .	Ditto.
„	18th November „ . . .	Ditto.
Sialkot	20th February „ . . .	Ditto.

Dates of any change of the instruments used for registering solar temperature or of the circumstances locally affecting them—concluded.

Stations.	Date of change.	Remarks.
Chakrata	9th October 1883	New thermometer substituted.
Katmandu	2nd April „	Removed to a different site.
Raipur	5th April „	New thermometer substituted
Jubbulpore	27th February „	Ditto.
Mount Abu	1st January „	Ditto.
Poona	22nd March „	Ditto.
Kurnool	27th November „	Ditto.
Bellary	18th November „	Ditto.

Table I (Appendix) gives abstracts of the registers of 111 stations, *viz.*, the means of all readings and the highest and lowest readings in each month; the mean excess of the sun-thermometer readings above those of the maximum thermometer in shade, and the greatest and the least differences. Of these data, the mean of all the readings and their mean excess both depend, mainly, on the frequency and quantity of cloud and haze. These temperatures afford a rough criterion of the average intensity of isolation at the earth's surface. The mean temperature, being partly dependent on that of the air, shews a regular annual variation. The mean excess temperature shews an annual variation of, in general, much smaller range, and of a different character, varying, more or less, at different stations. Its chief feature is that the maximum intensity of solar radiation occurs, as a rule, some time in the winter half of year (October to March), when the sun is in southern declination, and the thickness of the absorbing atmosphere traversed by the sun's rays is at a maximum; while its minimum falls about midsummer (in May, June, and July). This coincidence is, doubtless, in part due to the fact that, over a large part of India, the atmosphere is most cloudy in the summer and autumn months; but not entirely so; for if, instead of taking the mean excess of isolation temperature on all days in the month, we select those on which, at 10 A.M. and 4 P.M., the sky is free from visible clouds, or on which the average cloud proportion does not exceed one-fifth of the sky expanse (= 2, cloud proportion), an annual variation, almost identical in character, and not always even of smaller range, still presents itself. Illustrations of this fact were given in the report for 1880. Since then, a very interesting discussion of the solar thermometer temperatures at Allahabad, by Mr. S. A. Hill, Meteorological Reporter to the Government of the North-Western Provinces and Oudh, has been communicated to the Asiatic Society of Bengal, and published in the Society's Journal for 1883. In this, Mr. Hill has shewn that, making certain assumptions as to the thickness of the haze in different months, and assuming a constant value for the unabsorbed solar radiation, the annual variation of the excess, shewn by the sun-thermometer on clear days, may be approximately computed from the readings of the hygrometer and the sun's altitude; in other words, that the variation of the atmospheric absorption, throughout the annual period, is dependent

mainly on the proportion of the water vapour constituent and the thickness of the atmosphere traversed by the solar beams. It will be of interest to verify this conclusion by investigating the case of other stations.

Table II, below, gives the average monthly excess temperature of the sun-thermometer, derived from the registers of three years and upwards, the conditions being that the instrument has been exposed in the same place and the same position throughout. Except in a few cases, in which the substitution of a new instrument has been followed by such a change in the average value of the readings as to render the assumption obviously unjustified, it has been assumed that variations in the instruments, used at different times, are approximately eliminated by the correction of their readings to a common standard, in the manner noticed in the first paragraph of this section.

Table III gives the difference of the mean excess insulation temperature in each month of 1883, from the corresponding values in Table II. Some of these seem of doubtful value, although all have been struck out that, on the grounds of internal evidence, could be inferred faulty.

TABLE II.—*Average excess of insolation over the corresponding maximum shade temperatures.*

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar . .	3—4	66·7	65·5	68·1	69·5	66·5	72·5	71·8	71·1	71·2	69·4	68·5	68·2	69·1
Aden . .	3—4	53·1	P	P	P	47·6	46·3	45·5	45·4	50·7	50·5	50·0	50·7	?
Bushire . .	4—7	66·9	70·5	70·4	70·8	66·5	65·5	64·6	65·6	64·2	63·3	64·4	65·6	66·5
Quetta . .	4—5	65·3	69·2	65·9	64·6	61·1	58·4	60·7	59·8	59·8	60·1	61·8	61·3	62·3
Mooltan . .	5—7	51·8	54·6	55·5	54·0	52·8	49·7	52·1	52·9	51·4	52·0	54·9	53·6	52·9
Dera Ismail Khan .	4—7	56·3	58·5	63·3	63·0	59·6	54·8	55·9	56·3	56·4	54·9	55·4	53·0	57·3
Peshawar . .	6—7	53·3	57·6	59·7	58·9	57·8	54·0	52·9	55·7	55·8	55·7	53·5	52·2	55·6
Murree . .	6—7	62·2	67·2	67·5	66·6	66·8	64·1	65·7	67·1	65·5	61·9	58·6	59·8	64·4
Rawalpindi .	6—8	50·7	53·5	59·7	62·3	60·4	58·5	59·5	60·1	57·3	55·4	54·7	50·8	56·9
Sialkot . .	6—8	36·4	41·5	48·7	51·8	52·2	50·1	51·9	51·1	49·3	44·8	38·6	33·1	45·8
Lahore . .	7—8	51·0	54·4	57·3	57·8	55·2	53·0	55·3	55·9	55·7	54·3	53·3	50·8	54·5
Ludhiana . .	5—6	50·9	57·3	61·0	61·0	55·9	53·0	54·8	56·9	57·1	56·8	55·5	52·4	56·1
Simla . . .	3—4	62·0	72·3	66·6	70·3	64·6	63·1	56·8	58·8	65·9	66·3	64·5	63·4	64·6
Delhi . . .	6—8	54·0	56·9	57·3	57·9	55·6	51·2	54·5	57·2	56·5	54·7	53·7	52·8	55·2
Sirsa . . .	6—8	59·7	64·0	64·0	63·6	60·8	58·7	61·9	63·5	61·9	60·2	59·8	59·3	61·5
Chakrata . .	4—6	70·5	70·0	69·6	68·1	69·7	67·0	61·2	65·1	70·2	66·9	65·7	65·2	67·4
Roorkee . .	4—5	56·6	59·7	58·3	57·2	55·0	53·9	57·9	58·5	58·2	57·4	57·3	56·3	57·2
Ranikhet . .	6—7	61·5	63·0	65·9	63·3	62·1	60·3	56·4	59·9	65·8	63·3	63·6	61·0	62·2
Meerut . .	6—7	54·0	58·6	58·9	58·5	58·6	56·9	58·2	58·5	57·1	53·7	52·0	51·7	56·4
Bareilly . .	4—6	49·9	53·2	52·4	52·0	53·5	53·8	55·6	54·5	54·4	50·4	49·3	47·5	52·2

TABLE II.—*Average excess of insolation over the corresponding maximum shade temperatures*—continued.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Agra	5—6	60·6	63·2	64·2	63·4	61·0	58·4	57·7	59·0	61·6	61·2	60·9	59·3	60·9
Lucknow	7—8	59·7	63·5	62·7	59·7	58·9	60·1	57·9	61·9	63·0	59·2	59·9	60·5	60·6
Gorakhpur	4—5	55·9	59·0	59·3	57·2	56·7	55·9	54·9	56·3	58·8	57·9	56·8	55·7	57·0
Jhansi	5—7	59·3	60·6	60·2	61·1	61·6	61·4	59·9	60·3	61·9	60·2	58·5	58·5	60·3
Allahabad	8	58·7	59·9	58·9	57·6	57·0	57·5	57·9	59·1	60·0	57·9	57·8	58·5	58·4
Benares	5	57·0	59·5	59·9	58·3	57·4	56·8	56·1	57·3	60·1	55·7	55·0	55·4	57·4
Katmandu	4—5	57·0	59·7	61·7	59·9	63·3	62·5	64·2	62·6	62·1	61·0	56·2	54·7	60·4
Sibsagar	3—4	53·9	55·1	53·6	51·1	56·8	57·7	56·7	58·3	58·2	60·6	60·5	56·7	56·6
Dhubri	3	?	?	?	52·2	54·9	54·4	59·0	55·8	53·4	53·4	51·6	50·2	?
Purneah	3—4	?	?	55·8	54·7	55·2	52·2	55·7	55·0	56·7	58·5	53·4	51·1	?
Durbhunga	3	45·1	48·7	51·7	51·3	?	?	?	?	?	?	47·7	45·0	?
Patna	3	?	?	?	?	?	?	?	?	47·2	45·7	45·7	44·9	?
Gya	5—7	47·0	50·4	52·4	53·7	53·0	48·2	48·6	50·5	49·5	48·8	45·1	41·3	49·0
Burdwan	6	59·8	58·9	58·4	57·0	59·6	59·9	61·9	62·9	63·1	61·9	61·4	58·9	60·3
Jessore	4—5	55·1	56·1	53·2	53·0	55·7	53·0	55·4	54·6	56·2	56·8	56·5	53·9	55·0
Dacca	4—5	58·4	58·2	59·1	60·9	63·4	57·8	62·0	0·9	61·8	62·8	63·0	59·5	60·7
Chittagong	3—4	61·8	60·6	61·0	62·0	61·6	56·2	61·7	62·2	64·6	62·8	58·5	60·1	61·1
Calcutta (*Alipore*)	6—7	55·2	56·4	56·9	57·6	58·4	53·7	56·5	55·0	56·8	57·0	55·9	54·0	56·9
Saugor Island	3—4	58·6	57·9	57·9	58·6	57·8	52·2	53·3	51·9	56·8	57·8	60·3	57·3	56·7
Cuttack	12—14	55·2	55·3	55·1	55·7	57·5	53·7	54·7	56·4	58·9	59·1	56·1	54·4	56·0
Sambalpur	4—5	61·8	63·9	63·4	63·5	62·3	54·5	56·5	56·3	61·9	64·3	61·4	56·7	60·5
Raipur	5—6	50·9	51·3	55·6	56·0	57·2	54·9	58·6	58·4	60·0	57·5	54·1	51·0	55·5
Nagpur	4—6	59·0	59·3	58·5	59·9	59·3	58·2	55·2	61·1	63·8	62·9	61·0	59·1	59·8
Seoni	6—7	57·9	58·5	58·0	58·7	58·4	55·8	54·4	57·8	62·7	61·7	60·2	58·9	58·6
Jubbulpore	6—7	62·5	64·5	62·0	62·7	62·0	59·8	61·4	64·2	65·6	64·5	62·5	62·8	62·9
Saugor	6—7	62·3	63·4	62·8	62·8	60·5	62·1	60·2	63·9	64·8	61·0	59·7	60·7	62·1
Pachmarhi	6—8	61·8	62·5	62·5	61·8	60·0	59·5	53·5	58·5	63·7	63·1	62·0	61·6	60·9
Hoshangabad	4—7	57·5	59·3	59·4	60·2	57·3	59·2	53·9	57·4	58·2	59·4	58·0	56·8	58·3
Khandwa	3—4	58·9	59·8	59·9	59·4	57·3	57·1	56·4	59·9	60·7	61·6	59·5	58·3	59·1
Chanda	6—7	46·4	47·4	48·8	51·4	52·3	52·5	52·1	52·9	54·6	52·4	48·1	45·5	50·4
Sironcha	7—8	57·3	56·2	55·0	56·6	55·5	54·3	53·3	57·4	60·7	61·2	60·5	56·7	57·0
Chikalda	3—4	?	66·7	66·3	67·7	66·2	64·4	59·4	67·2	69·9	71·5	68·5	66·3	?
Buldana	6—7	49·2	51·6	55·0	56·3	57·4	56·8	58·2	58·4	56·0	55·0	49·7	46·4	54·2
Akola	5—7	60·0	59·4	59·6	58·7	57·7	56·6	54·1	58·6	61·4	62·1	60·1	59·7	59·0

TABLE II.—*Average excess of insolation over the corresponding maximum shade temperatures*—concluded.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Amraoti	5—7	56·7	55·9	55·2	55·5	54·5	52·7	51·9	55·1	59·6	59·1	57·2	57·1	55·9
Neemuch	5—6	63·3	63·9	61·5	59·6	57·9	59·0	59·5	63·2	63·4	61·9	63·0	64·1	61·7
Nowgong	3	?	?	?	?	?	?	?	?	?	56·8	?	?	?
Sutna	7—8	59·0	60·7	59·7	58·8	57·8	58·4	58·1	61·2	63·6	59·8	58·6	58·5	59·5
Indore	4—6	60·3	62·1	61·6	59·5	58·0	58·5	56·2	59·5	63·1	63·1	59·8	59·2	60·1
Bickaneer	3—4	?	?	?	70·8	66·3	64·1	67·3	?	?	69·9	72·2	71·7	?
Jeypore	3	55·4	58·2	60·4	59·5	57·7	58·0	56·0	61·1	59·7	56·1	54·8	53·6	57·5
Sambhar	3—4	57·1	62·1	64·6	64·7	63·0	61·8	65·0	60·7	59·6	56·9	56·3	53·8	60·5
Ajmere	3—4	56·3	57·9	58·2	58·9	56·4	55·3	56·7	56·4	58·1	52·2	53·7	52·6	56·1
Mount Abu	3—6	62·8	65·8	65·9	64·4	60·8	60·8	57·4	58·6	64·6	63·8	63·8	63·4	62·7
Pachbudra	3	64·0	66·5	65·1	66·1	?	?	?	?	65·7	61·4	62·3	62·1	?
Jacobabad	4—7	61·1	62·6	62·1	62·1	59·7	55·7	57·1	59·8	59·8	58·7	59·1	58·1	59·7
Hyderabad	5—6	61·9	64·2	63·6	62·7	58·4	59·3	60·0	62·5	60·1	59·3	60·7	60·7	61·1
Kurrachee	6—8	63·5	66·3	68·3	68·1	67·0	67·7	67·8	67·9	67·2	64·3	63·2	62·4	66·1
Bhuj	6—7	64·5	66·3	64·7	62·2	60·5	63·6	63·1	63·3	66·1	62·5	62·5	63·1	63·5
Rajkot	3—4	?	?	?	56·5	53·0	54·9	50·2	56·0	59·9	58·9	60·4	60·3	?
Dessa	5—6	54·4	56·7	56·1	53·8	50·6	53·6	54·9	55·6	56·3	52·7	53·3	53·0	54·3
Surat	5—7	56·7	57·8	56·4	55·8	55·9	55·3	55·0	59·1	60·8	56·9	56·5	55·8	56·8
Malegaon	5—7	59·2	58·7	58·5	56·6	54·9	54·3	55·0	57·0	61·3	61·5	60·2	57·2	57·9
Bombay	7—8	58·0	58·7	57·8	57·4	56·2	50·1	46·2	50·8	55·7	57·1	56·8	57·1	55·2
Poona	3—5	55·2	54·8	55·3	54·4	51·1	51·4	55·3	56·0	58·4	57·4	54·7	54·5	54·9
Sholapur	4	64·5	62·3	64·0	64·2	62·3	61·3	61·4	62·3	67·1	70·4	64·9	65·0	64·1
Ratnagiri	6—7	57·5	58·3	57·8	56·9	55·9	50·6	50·4	53·7	58·9	58·9	57·0	56·7	56·1
Belgaum	4—5	62·4	62·4	62·5	61·6	60·1	61·7	60·4	62·2	67·7	67·5	63·5	62·5	62·9
Karwar	3—4	62·3	63·6	63·7	63·5	62·9	51·9	48·7	59·2	61·6	64·0	61·4	62·4	60·4
Mangalore	3—4	62·1	62·6	62·2	60·5	60·0	53·9	52·9	59·3	65·8	64·3	62·9	61·4	60·7
Mercara	3—4	67·3	67·4	68·8	67·7	67·8	59·3	50·4	61·3	64·9	69·5	68·5	66·2	64·9
Thayetmyo	5—7	50·4	49·8	51·1	52·6	57·0	63·1	63·3	62·9	59·6	57·0	54·2	50·7	56·0
Tounghoo	5—7	58·1	58·0	55·0	55·2	58·3	59·3	59·1	59·4	62·2	62·0	58·9	58·6	58·7
Bassein	6—7	56·3	55·6	53·6	54·0	54·1	52·7	49·8	52·5	56·7	59·2	58·6	58·0	55·1
Rangoon	5—7	59·8	57·6	56·2	58·8	58·8	56·9	55·7	56·6	62·4	62·1	59·4	60·1	58·7
Moulmein	5—8	53·4	54·2	55·6	58·1	57·9	56·7	47·8	53·8	57·7	58·8	53·1	50·1	54·8
Mergui	3—6	60·1	60·1	59·8	59·7	58·3	51·9	51·6	56·1	55·4	59·8	58·9	57·7	56·7
Port Blair	7—8	55·2	54·2	55·6	55·1	49·8	47·9	48·0	51·3	50·1	53·8	52·5	53·0	52·2
Nancowry	7—8	58·5	60·0	60·8	57·4	53·2	51·2	52·2	54·7	53·9	55·4	56·1	55·5	55·7

TABLE III.—*Comparison of excess sun (over shade) temperatures in 1883, with the averages of Table II.*

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	+1·0	+2·6	+1·2	+3·1	−1·4	−0·7	−3·3	−0·8	−2·0	−1·3	−2·8	−1·9	−0·5
Aden	+0·1	?	?	?	−1·0	−0·9	−1·1	+2·1	−2·4	−1·3	−2·0	−2·5	?
Bushire	+0·5	+0·7	+4·5	−0·2	−2·7	−1·8	−0·9	−3·2	−1·5	−0·4	−1·2	−0·3	−0·5
Quetta	−3·9	−6·2	−2·1	−1·9	−4·7	−3·8	−3·3	−5·1	−5·8	−4·4	−5·6	−8·6	−4·6
Mooltan	+3·4	+5·4	+5·3	+4·5	+3·7	+5·3	+8·8	+1·7	+4·1	+2·7	?	−1·8	?
Dera Ismail Khan	0	−0·2	−2·8	−2·8	−4·8	−3·9	−3·0	−4·8	−3·9	−3·3	?	?	?
Peshawar	?	+1·2	−0·5	+0·7	−2·4	+1·7	+2·9	+0·3	−3·0	−2·1	+0·4	−2·8	?
Murree	−2·8	+9·4	+0·6	+1·3	0	+1·3	+1·2	−0·3	−0·8	+2·2	+5·4	−1·3	+1·4
Rawalpindi	−1·3	+4·2	+0·4	−1·6	−2·1	−0·4	−0·3	−0·3	+1·5	+0·9	+0·4	+1·9	+0·3
Sialkot	?	?	−2·4	−1·9	−1·9	−4·2	−5·8	−5·6	−3·8	−7·2	−8·4	−6·8	?
Lahore	+0·4	+2·5	+2·8	+1·6	−0·1	+0·7	+1·8	+1·5	−1·0	+0·6	+0·5	+0·6	+1·0
Ludhiana	−0·6	+3·1	+2·0	−2·3	−0·8	+2·2	−0·1	+0·9	−5·1	−2·4	−3·1	−2·7	−0·7
Simla	−1·6	+0·1	+0·3	−1·4	+0·3	−0·8	+3·2	−1·3	−3·6	−0·2	−2·9	−1·0	−0·7
Delhi	−0·6	−0·2	+0·5	−1·5	+1·1	+1·1	+1·5	+2·3	+1·4	0	−1·8	−2·5	+0·1
Sirsa	+3·2	+3·3	+3·5	+0·3	+2·3	+0·5	+0·8	+0·5	+1·0	+3·3	+2·9	+0·7	+1·9
Chakrata	?	?	?	?	?	?	?	?	?	−4·0	−3·4	−1·3	?
Roorkee	+0·7	+0·5	+1·7	−0·9	−0·3	−1·3	−3·8	−1·7	−0·8	−0·3	−1·1	−0·5	−0·7
Ranikhet	−3·5	+4·1	+2·8	+0·6	−1·9	+2·1	+1·7	+1·4	+1·8	+1·9	−1·2	−0·9	+0·7
Meerut	−4·2	−3·6	−2·8	−4·8	−3·7	−6·8	?	?	?	?	+1·1	−1·1	?
Bareilly	+3·4	+3·8	+2·9	−1·7	+1·3	−0·2	−0·4	−3·9	−1·0	−2·7	−4·3	−1·3	−0·3
Agra	−4·1	−4·3	−2·7	−4·3	−2·7	−4·2	−6·6	+0·2	−2·5	−3·3	−5·5	−5·3	−3·8
Lucknow	−1·4	−1·1	−2·9	−1·5	−0·1	−0·8	−4·3	+0·7	−1·5	−1·7	−2·0	−2·4	−1·6
Gorakhpur	−1·3	+0·6	−0·9	−4·4	−3·7	−2·4	+2·1	+1·0	0	−1·3	−2·0	−2·3	−1·2
Jhansi	−0·7	−2·1	−4·8	−0·5	+0·3	?	?	?	?	?	−4·0	−2·6	?
Allahabad	−4·0	−1·8	−1·0	−2·4	−2·5	0	−3·4	−0·1	−1·7	−3·4	−2·2	−3·3	−2·2
Benares	−0·3	0	+0·8	−0·6	−1·9	−2·7	−4·6	+1·7	−4·3	−3·6	−1·1	−2·2	−1·6
Katmandu	+4·8	+3·6	+1·4	−1·6	−3·6	−3·5	−3·2	−6·8	−3·5	−6·9	−6·8	−7·1	−2·8
Sibsagar	+2·2	−2·8	+2·6	+2·6	+0·8	+0·8	+2·6	+1·4	+3·8	+2·5	−0·8	−2·0	+1·1
Dhubri	?	?	?	−6·5	−6·4	−0·2	−3·5	−5·1	+1·2	−1·3	−2·9	−4·5	?
Purneah	?	?	−0·7	−1·1	−1·1	+1·8	−1·3	−7·3	−0·4	−3·4	−3·0	−3·0	?
Durbhunga	+1·6	+3·3	−0·8	−0·4	?	?	?	?	?	?	?	?	?
Patna	?	?	?	?	?	?	?	?	+1·0	−0·1	+0·2	+0·2	?
Burdwan	−0·6	−0·4	−0·3	−1·7	−2·9	+1·1	−3·3	−1·0	+1·0	−1·3	−3·1	−3·4	−1·3
Jessore	−2·8	−2·8	−1·8	−3·3	−2·3	−2·3	−1·1	+0·1	+0·8	−2·2	−5·6	−6·0	−2·4

TABLE III.—*Comparison of excess sun (over shade) temperatures in 1883, with the averages of Table II*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Dacca	+1·8	−0·7	−0·7	−0·9	−0·9	−1·1	−0·5	+0·6	+0·7	+2·3	−2·6	−5·7	−0·6
Chittagong	+1·0	−0·5	+1·4	−2·4	−0·6	−0·4	−3·9	−1·9	−1·3	−2·7	+3·6	−5·4	−1·1
Calcutta *(Alipore)*	−0·2	−2·4	+1·3	−0·6	+2·5	+1·9	+1·5	+5·1	+4·4	+1·1	−1·8	−3·2	+0·8
Saugor Island	+1·2	−0·6	+1·1	+1·0	+0·2	+1·9	−4·1	+0·1	+2·8	+1·4	−0·4	−3·9	+0·1
Cuttack	+1·5	+0·1	+3·0	+0·4	0	−2·3	−1·5	+1·5	−0·6	−1·1	+0·4	−4·1	−0·2
Raipur	−2·4	−0·1	?	−3·4	+2·4	+2·3	−8·0	+0·5	−2·9	−3·5	−2·3	−1·4	?
Nagpur	+1·1	+0·3	+2·8	+2·0	+0·6	+2·1	−2·2	+1·8	−0·4	−0·6	−0·3	−0·7	+0·5
Seoni	+3·3	+1·4	+2·8	+2·3	+1·4	+3·3	−0·9	+2·0	−1·7	−2·4	+3·0	+2·7	+1·4
Jubbulpore	−3·0	?	−5·2	−4·1	−0·9	−0·8	+4·0	+5·6	+4·2	+5·8	+5·9	+4·9	
Saugor	−2·2	+0·3	−0·2	−1·5	−4·3	−5·4	−8·0	−2·2	−2·5	−1·5	+1·2	+4·0	−1·9
Pachmarhi	−2·4	−3·0	−3·5	−2·8	−2·6	+1·6	−2·8	+2·1	−6·7	−3·4	+1·1	+0·3	−1·8
Hoshangabad	−2·3	−1·5	−1·8	−5·3	−7·4	−5·5	−1·0	0	−6·3	−3·3	−4·0	−3·9	−3·5
Khandwa	+0·6	+0·4	+0·5	+0·1	−0·4	+2·2	+0·5	−1·5	−3·9	−2·0	−0·9	−1·0	−0·5
Chanda	+1·2	−0·8	+0·6	−1·8	−2·5	−2·0	−2·9	−2·4	−4·1	−3·9	−3·1	−3·0	−2·1
Sironcha	−0·4	−2·2	+0·1	−4·5	−5·3	−4·0	−6·0	−3·9	−5·3	−2·8	−1·2	−1·0	−3·0
Chikalda	?	−0·5	+0·1	−3·0	−4·9	−0·6	0	−5·1	−10·4	−5·7	+0·7	0	?
Buldana	−1·1	−0·2	−0·5	+0·5	−1·3	+0·9	−4·2	−5·4	−3·3	−2·6	−2·3	−1·8	−1·8
Akola	+0·1	−0·2	−1·1	−0·5	−2·4	+1·3	−1·0	−4·5	−0·5	−1·0	+0·5	+0·3	−0·8
Amraoti	0	−1·7	−0·4	−1·3	−2·9	+1·9	−2·8	−0·5	−5·2	−1·4	−0·3	−1·3	−1·3
Neemuch	+0·6	+0·9	+0·2	+0·2	−0·8	−0·3	+1·5	+0·6	−2·0	+3·3	−0·3	−0·1	+0·3
Nowgong	?	?	?	?	?	?	?	?	?	−0·1	?	?	?
Sutna	+1·1	+2·1	−0·6	−1·0	−1·0	+2·1	+1·4	+0·7	−1·5	−0·5	+1·2	0	+0·3
Indore	−1·1	−2·3	−3·1	−2·1	−1·1	−0·3	+0·8	−1·8	−6·5	−4·4	−2·6	−1·9	−2·2
Bickaneer	?	?	?	+3·9	+5·6	+4·4	+5·6	?	?	?	+1·3	+2·9	?
Jeypore	+0·4	−0·3	+1·5	−0·7	+0·2	−0·2	+1·2	+0·8	+3·2	+2·4	+0·9	0	+0·8
Sambhar	−1·1	−3·2	−2·7	−6·3	−4·6	−5·7	−7·3	−5·5	−5·4	−2·2	−3·6	−2·6	−4·2
Ajmere	−3·5	−5·2	−5·0	−8·9	−8·1	−6·3	−5·9	−5·8	−3·7	−0·1	−1·7	−4·3	−4·9
Mount Abu	+2·9	+2·8	+2·2	−2·3	−1·0	−2·5	−3·9	+0·2	−8·4	−0·1	−0·2	+1·3	−0·8
Pachbudra	−1·4	−1·3	+1·6	−2·7	?	?	?	?	+4·0	+5·1	+1·7	+2·4	?
Jacobabad	+4·6	+3·9	+4·8	+1·4	+4·2	+1·3	+3·8	−1·0	+0·4	+0·9	−0·2	−2·6	+1·8
Hyderabad	−1·9	−2·2	+0·5	−2·8	−2·4	−3·7	−3·5	−5·0	−2·5	−1·0	−2·3	−3·6	−2·5
Kurrachee	−2·5	−0·4	+0·2	+0·1	−1·0	+0·1	+0·8	+2·1	+1·9	+1·1	+4·0	+3·9	+0·9
Bhuj	+0·4	+1·0	−0·7	−0·7	+1·9	+2·8	+0·2	+3·1	+0·4	0	−1·0	−2·4	+0·4
Rajkot	?	?	?	−1·3	−1·0	−0·9	+3·1	−0·8	−0·6	−0·4	−0·5	+0·7	?

TABLE III.—*Comparison of excess sun (over shade) temperatures in 1883, with the averages of Table II*—concluded.

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Deesa	+1·5	+0·4	+1·0	—1·8	+1·2	—1·3	+0·2	—2·4	—5·0	—1·4	—3·2	—3·1	—1·4
Surat	—2·4	—1·8	—1·1	—1·4	—0·3	—1·8	+1·5	—3·6	—2·0	—1·4	—3·5	—3·5	—1·8
Malegaon . .	+0·9	+0·2	—0·3	+1·1	—0·8	—0·1	—2·4	—2·8	—2·8	—1·3	+0·5	—6·4	—1·2
Bombay	—4·2	—3·7	—2·9	—3·9	—2·2	—1·5	—2·4	—6·8	—5·5	—5·0	—3·8	—6 1	—4·0
Poona	—1·8	—0·9	?	+3·6	+3·1	+4·2	—2·7	—5·3	—4·8	—2·5	—0·3	+0·4	?
Sholapur . . .	—2·7	—1·4	—0·3	—1·6	—2·9	—2·1	+0·3	—7·8	—2·5	—2·0	+0·3	+1·3	—1·8
Ratnagiri . . .	—1·2	—1·0	—0·7	—1·5	0	—1·2	—5·2	—3·2	—5·7	—4·1	0	—1·0	—2·1
Belgaum . . .	—0·1	—1·4	—0·6	—3·0	—2·6	—2·2	—1·5	—1 9	—2·5	—2·6	—2·4	—0·8	—1·8
Karwar	+0 3	—1·0	+0·7	—0·7	—0 1	—1·2	—3·3	—0·3	2·7	—2·2	0	—3·9	—1·2
Mangalore . . .	—1·5	—1·4	—1·1	0	—0·7	+1·5	—1·4	—2 7	—1·2	—0·8	—2·5	—1·5	—1·1
Mercara	+2·2	+0·8	+1·2	+0·6	+1·2	+0·2	—1·4	—0·5	+0·7	—2·0	—1·5	—1·2	0
Thayetmyo . . .	—4 3	—3·5	—1·9	—2·5	—0·2	+0 2	—0·5	—2·2	+0·6	—5·6	—8·1	—4·6	—2·7
Tounghoo . . .	+1·0	+2·0	—0·4	—3·1	—2·0	—5·0	—3·6	—3·4	—2·4	—3·8	—7·8	—3·6	—2·7
Bassein	+1·4	—0·4	+0·2	—1·6	—0·8	—2·0	+1·1	+0·3	?	?	?	—2·1	?
Rangoon . . .	—0·2	+1·2	+1·4	—2·5	+0·8	—0·5	+0·2	+0·2	—8·2	—3·9	—6·3	—1·4	—1·6
Moulmein . . .	+3·6	+1·7	+1·5	—1·0	+3 5	—6·5	+7·8	+5·4	—1·8	+0·3	+1·3	+7·1	+1·9
Mergui	+2·5	+4·3	+1·2	—1·1	—0·5	—4·8	—6·4	—1·5	—3·8	—4·3	—5 1	—1·7	—1·0
Port Blair . . .	—6·0	—3·7	—2·5	—1·2	—3·7	—1·4	—5·1	—7·2	—2·5	—3·8	—8·2	—8·2	—4·5
Nancowry . . .	+0·2	+1·1	—0·2	+3·7	—1·1	—5·4	—3·0	—0·8	—2·6	+4·7	—1·6	—4·0	—0·8

Taking the sums of the figures in each monthly column of Table III (with the exclusion of the first four stations), and dividing by the number of stations recording (from 72 to 79) in each month, we obtain the following figures:—

January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
— 0·3	0	0	—1·4	—1·0	—0·8	—1·2	—1·2	—1·8	—1·3	—1·5	—1·8

The result, which is obtained after eliminating all figures, which there is any good reason to regard as untrustworthy, is somewhat striking. In every month, except February and March (which were average months), the mean intensity of the insulation, as shewn by the maximum reading of the sun-thermometer daily, was below the average, and except in the first three months and June, by an amount of between one and two degrees, the mean deficiency of the whole year being—1·0. There is no reason to doubt the general trustworthiness of this result. Some of the most trustworthy observatories, such as Allahabad and Bombay, exhibit it in a very marked degree, and the large

majority of the stations furnish concurrent testimony. Partial exceptions to the prevailing rule are to be noticed in the Punjab, the dry region of Western India, the Central Provinces and Bengal, and also in Burma during the earlier months of the year, but the exceptions are comparatively few. The deficiency was greatest in the later months of the year, and not improbably, at least in part, it may be the effect of the sheet of finely-divided matter (whether of volcanic or meteoric origin), to which are attributed the remarkable sky phenomena, the after-glows, the solar coronas, &c., which have attracted so much attention during the greater part of the last twelve months. Mr. Hennessey informed me, some time since, that it appeared from the actinometric measurements which he has carried on at Mussooree and Dehra, whenever possible, during the greater part of the past year, that the solar intensity was lower than that shewn by his former measurements, and so far therefore, the actinometer confirms the evidence of the sun-thermometer.

It must be noticed that, in 1882, the solar intensity was below the average in most months, as was also the case in 1881, whereas it was steadily above it in 1880. The mean variation in these four years was as follows :—

1880 +0·4 1881 −0·3 1882 −0·6 1883 −1·0

shewing therefore a steady decrease of the heating effect during the four years,—a result which accords with that obtained by Mr. Hill from his investigation of the Allahabad registers from 1878 to 1882, and noticed in the Report for 1882.

DURATION OF BRIGHT SUNSHINE.

Registers of the duration of bright sunshine appear for the first time in the present report. The registration is effected by means of the sunshine recorder, an instrument originally devised and first employed by Mr. Campbell of Islay, subsequently modified in such manner as to furnish a trace capable of ready measurement, and finally improved to its present form by Professor G. Stokes and Mr. Whipple. It consists of a spherical glass lens mounted on a brass support, which also carries a curved brass plate fixed beneath the sphere; of such curvature and at such distance from the spherical surface, that the focal point in which the sun's rays converge, travels across the surface of the plate between sunrise and sunset. A slip of card, with printed divisions, corresponding to the hours, is inserted in grooves in the brass plate, and, as the radiant focus moves along the card, it burns a line, which is either continuous or interrupted according to the state of the sky, and the measurement of which is a record of the time during which the sun has shone with sufficient intensity to burn the surface of the card.

The instrument has hitherto been employed only at Allahabad and Calcutta, and for a month or two, at the close of the year, at Jeypore. It promises to be a most valuable adjunct to the sun-thermometer; perhaps even more important than that instrument, since the duration of sunshine is a more direct measure of the amount of solar heat reaching the earth's surface than the register of its mean maximum intensity. The traces are measured to tenths of an hour; but in summing the daily totals for each month, residual

decimals are omitted, and in Table II, Appendix, the totals are given to integral hours only.

The table gives the data of the two recording stations for each month of 1883. In the first column, the sum of the measured traces; in the second the total number of hours that the sun is above the horizon, and in the third the ratio of the first to the second in the form of a percentage.

As might be anticipated from the consideration of its inland situation, the duration of sunshine at Allahabad exceeds that at Calcutta in most months of the year, and especially in June, August, and September. The percentage at the former station, relatively to the latter, was greatest in April and November; and only in two months, *viz.*, January and October, does the Calcutta register shew the greater absolute and relative duration of sunshine.

NOCTURNAL RADIATION.

The tables of nocturnal radiation comprise the registers of 107 stations. Of these, however, not less than 35 are imperfect, owing, in the majority of cases, to the destruction of the instruments, either in this or the preceding year, and to the stock being insufficient to replace them without loss of time. The provinces, the registers of which are most defective, are Burma 4 stations, Bombay 8, Central India and Rajputana 5, Bengal and Assam 7. The least defective is the North-Western Provinces, where only one station out of 13 sends a defective register.

The Table III (Appendix) shews the mean temperature registered by the exposed minimum thermometer, (in nearly all cases corrected for instrument errors), and the highest and lowest temperatures in each month, with the dates on which they occurred; also the depression of the first below the mean temperatures of the minimum shaded thermometer, about 4 feet from the ground; and the greatest and least depression. At most stations in Northern India; the thermometers, which are spirit thermometers, with spherical bulbs, about half an inch in diameter (or cylindrical bulbs, $\frac{1}{4}$ inch diameter), are laid on a thick pad of common country blanket. Thus, a tolerably uniform radiating surface is secured, which would not be the case were the usual practice followed, *viz.*, that of placing the instrument on grass (or the bare ground).

The present method has been followed only during the last six or seven years, and, as it has not been deemed desirable to include in the computation of average values, the results obtained under the old varied conditions of exposure: moreover the interruptions, from the causes noticed above, have been very numerous. The Table IV of averages, which follows, still shew a few hiatus, though fewer than the corresponding tables in previous years. Table V gives the differences of the mean depression in 1883, and the averages of Table IV.

TABLE IV.—*Average depression of monthly mean nocturnal radiation temperatures below mean minimum shade temperatures.*

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	4	?	6·2	6·6	5·2	5·0	7·0	7·0	8·8	10·2	9·9	8·3	6·6	?
Aden	3—4	3·9	3·5	3·0	4·4	3·5	4·4	2·5	2·9	4·1	4·5	4·9	4·2	3·8
Quetta	3	?		10·9	14·6	17·9	?	?	13·9	?	17·0	15·1	12·6	?
Leh	4—5	10·2	8·7	9·3	9·3	8·7	8·8	7·8	7·3	8·2	10·3	11·9	10·9	9·3
Mooltan	5—6	8·3	9·0	9·3	12·1	12·0	11·0	9·0	7·9	8·2	9·5	8·5	9·0	9·5
Dera Ismail Khan	3—6	10·8	10·6	9·5	10·8	12·2	9·3	7·2	7·0	9·3	10·7	10·7	10·9	9·9
Peshawar	6—7	9·4	8·6	7·8	8·0	9·6	8·4	5·3	5·5	7·1	9·6	10·5	9·4	8·3
Murree	4—7	13·9	11·1	11·5	10·6	11·5	10·7	6·9	7·3	12·9	15·9	16·1	12·8	11·8
Rawalpindi	4—7	4·1	4·6	5·1	6·6	8·3	6·7	5·3	4·3	5·2	6·4	5·4	5·3	5·6
Sialkot	4—5	7·3	6·5	6·8	7·6	7·7	6·8	3·4	3·4	5·0	7·5	8·0	6·3	6·4
Lahore	6—7	9·2	8·0	8·5	7·8	8·0	5·6	3·8	4·0	5·4	8·5	9·3	8·2	7·2
Ludhiana	4—7	11·4	10·2	9·6	8·5	8·4	7·4	4·4	4·5	6·7	11·9	12·2	11·4	8·9
Delhi	4—6	8·6	10·0	9·9	10·4	9·0	6·1	3·8	3·7	5·6	9·7	10·9	10·2	8·2
Sirsa	5—6	9·3	9·7	8·6	7·9	5·7	5·1	4·5	4·6	7·5	11·1	10·6	10·6	7·9
Chakrata	5—7	10·3	8·6	8·5	8·7	7·6	5·3	2·9	4·1	6·1	12·5	12·3	13·5	8·4
Roorkee	6—7	7·3	6·8	7·2	7·8	5·8	3·1	1·8	2·3	3·7	6·7	7·8	7·3	5·6
Ranikhet	7	13·5	12·8	12·6	13·9	11·8	7·3	4·3	5·0	8·1	14·2	16·1	16·8	11·4
Meerut	5—7	4·4	4·4	4·9	5·6	4·5	4·0	3·9	4·4	5·0	5·8	5·8	4·9	4·8
Bareilly	5—7	9·1	8·8	10·0	11·8	11·3	8·3	3·7	3·7	4·9	8·9	10·6	9·2	8·4
Agra	4—7	10·7	11·1	11·4	11·0	9·1	6·8	4·0	3·9	5·5	9·7	11·4	10·8	8·8
Lucknow	6—7	9·8	9·4	8·4	9·3	6·8	4·9	3·0	3·1	4·2	8·5	10·8	11·1	7·4
Gorakhpur	4—6	10·2	9·2	9·6	10·3	8·3	5·0	5·3	2·5	5·9	9·6	10·4	10·5	8·1
Jhansi	5—7	4·0	5·0	5·9	7·9	7·4	4·8	2·2	2·2	2·3	4·1	5·0	3·9	4·6
Allahabad	7	11·0	11·1	11·7	10·7	7·9	4·9	2·7	3·0	4·3	8·7	11·4	11·6	8·3
Benares	7	9·9	9·8	9·9	10·0	7·5	4·9	2·8	2·8	4·0	7·7	10·5	11·0	7·6
Sibsagar	5—7	4·7	4·9	4·8	4·6	4·4	4·4	3·5	3·2	2·9	3·6	5·0	5·1	4·3
Dhubri	3	?	?	?	?	?	?	2·5	2·5	2·7	5·0	6·8	6·4	?
Silchar	3—5	8·7	7·8	5·7	3·8	3·2	2·2	2·0	2·4	3·1	4·5	8·0	8·5	5·0
Purneah	4—6	7·2	5·9	6·1	5·6	2·8	2·3	2·9	2·5	3·3	5·3	7·7	6·5	4·8
Durbhunga	4—7	8·9	8·8	11·8	10·9	6·1	5·0	4·6	5·3	6·8	8·1	9·7	10·2	8·0
Patna	6—7	4·3	4·0	5·8	6·1	3·7	3·3	2·4	2·2	2·6	3·7	4·2	4·3	3·9
Gya	3—5	9·5	9·5	8·8	6·2	6·4	6·0	4·9	4·5	4·8	6·3	8·6	9·5	7·1
Hazaribagh	5—7	9·2	8·4	8·1	7·3	4·8	2·3	1·0	1·4	2·2	7·0	9·6	9·6	5·9
Burdwan	5—7	11·9	10·6	10·3	7·6	5·2	4·3	4·1	3·7	4·4	7·0	10·0	11·6	7·6

TABLE IV.—*Average depression of monthly mean nocturnal radiation temperatures below mean minimum shade temperatures*—continued.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Jessore	4—7	10·8	10·0	9·0	6·7	4·6	3·5	2·6	2·5	3·2	6·0	8·4	10·4	6·5
Dacca	6—7	10·7	10·8	8·4	5·7	4·0	2.3	2·4	2·4	3·5	6·9	9·8	10·1	6·4
Chittagong	3—4	?	7·0	5·0	4·3	3·2	1·8	2·2	2·3	2·0	3·4	5·2	5·6	?
Calcutta *(Alipore)*	6—7	9·2	8·6	7·5	5·2	3·6	2·3	2·1	2·2	3·1	5·5	8·5	9·8	5·6
Saugor Island	5—7	8·9	8·4	6·8	5·2	4·2	3·3	3·0	2·6	3·3	5·0	7·2	8·1	5·5
Cuttack	6—7	11·7	10·2	8·9	7·4	5·9	4·5	3·9	4·0	4·7	6·9	9·1	10·9	7·3
Sambalpur	5	9·3	8·6	10·6	11·8	10·8	7·4	4·5	4·6	5·0	6·4	8·0	9·0	8·0
Raipur	3—7	7·5	7·1	7·1	6·5	4·8	5·1	4·2	5·0	7·6	5·0	6·6	6·9	6·1
Nagpur	5—7	12·8	12·2	11·9	11·4	10·3	4·0	2·7	4·1	4·2	8·7	11·6	14·5	9·0
Seoni	5—7	10·5	9·8	11·2	9·8	7·9	4·3	2·6	2·9	4·1	7·5	9·5	10·6	7·6
Jubbulpore	6—7	8·8	8·0	9·7	10·3	8·9	3·7	2·1	2·4	3·4	5·7	8·7	8·2	6·7
Saugor	5—7	11·2	11·8	12·1	9·8	8·7	5·8	2·6	2·6	4·1	7·7	12·1	12·1	8·4
Pachmarhi	4—6	14·0	14 8	14·7	14·1	9·4	3 9	1·7	1·9	4·2	9·6	13·1	13·6	9·6
Hoshangabad	6—7	7·8	8·4	9·7	9·5	7·8	4·2	2·4	2·5	3·0	6·3	9·0	9·0	6·6
Khandwa	5—7	7·3	7·8	8·4	8·1	6·6	2·9	2·3	2·5	2·8	5·8	8·0	7·1	5·8
Chanda	5—7	9·2	9·0	9·1	9·9	9·0	3·8	2·7	2·8	2·9	4·8	6·5	8·3	6·5
Sironcha	5	10·5	9·9	10·0	9·1	7·1	3·9	3·1	3·1	3·6	6·5	7·8	10·7	7·1
Chikalda	4—6	17·0	14·3	11·3	9·7	7·8	3·4	1·7	1·4	2·9	10·5	16·2	19·6	9·7
Buldana	6—7	14·9	14·1	13·2	10·4	6·3	3·1	2·9	3·2	3·3	10·6	13·4	15·4	9·2
Akola	6—7	10·1	10·0	10·6	10·4	6·9	2·7	2·7	2·7	3·3	6·9	8·2	9·8	7·0
Amraoti	4—6	11·3	10·8	11·5	11·7	9·5	3·9	3·0	3·7	4·6	9·2	10·8	10·5	8·4
Neemuch	3—6	12·2	12·2	12·6	13·0	9·4	6·9	5·2	5·1	5·9	13·0	16·0	15·0	10·5
Nowgong	3—5	11·6	12·2	?	?	10·8	7·1	3·0	5·2	5·7	9·7	11·7	11·4	?
Sutna	5—7	5·9	6·0	5·8	5·8	3·9	3·1	1·8	1·9	2·9	5·2	6·2	6·2	4·6
Indore	4—5	15·7	14·8	14·6	14·3	9·4	3·7	2·8	3·8	5·7	10·0	14·2	13·9	10·2
Bickaneer	3—5	12·4	10·7	10·6	9·4	7·1	4·5	3·9	4·4	5·2	10·9	11·4	12·2	8·6
Jeypore	3	10·5	10·4	9·3	?	?	?	2·1	3·3	4·3	9·2	11·0	10·9	?
Sambhar	3—4	9·4	11·2	10·5	11·7	7·5	5·1	5·7	5·2	6·3	10·6	11·6	10·8	8·8
Ajmere	3	7·9	7·2	7·4	6·9	5·6	?	?	5·1	5.6	7·6	8·0	8·7	?
Mount Abu	3—7	18·4	12·3	15·1	13·3	8·9	4·3	2·5	3·0	6·4	14·0	19·1	18·1	11·3
Pachbudra	3	?	?	?	?	?	?		?	?	9·7	7·0	9·7	?
Jacobabad	3—6	12·2	13·5	10·9	11·6	10·6	7·4	5·7	5·7	7·2	10·3	11·1	11·0	9·8
Hyderabad	3—6	8·2	8·8	8·5	6·3	4·6	2·6	2·3	1·7	2·9	6·8	8·6	9·8	5·9
Kurrachee	6—7	8·5	9·2	9·3	8·2	6·1	3·7	2·4	2·4	3·9	7·8	9·1	8·3	6·6

TABLE IV.—*Average depression of monthly mean nocturnal radiation temperatures below mean minimum shade temperatures*—concluded.

STATIONS.	Year.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Bhuj	5—7	16·0	14·7	13·4	11·2	7·1	5·0	4·8	5·5	7·3	12·1	18·5	18·0	11·1
Rajkot	5—7	12·4	11·4	10·8	9·5	5·3	3·0	2·1	2·5	3·8	8·4	12·0	12·0	7·8
Deesa	3—6	9·5	9·9	10·4	10·2	7·5	3·7	2·6	3·4	4·5	8 3	9·4	8·7	7·3
Surat	4—6	11·7	11·6	9·5	8·4	6·8	3·5	2·9	3·9	4·6	7·0	10·2	12·2	7·7
Malegaon	6—7	9·0	9·7	9·6	9·3	6·2	2·8	2·4	3·0	3·2	6·0	7·9	8·8	6·5
Bombay	9	9·2	8·2	7·2	5·9	4·3	2·7	2·4	2·7	3·1	6·1	9·2	10·7	6 0
Poona	4—7	13·5	13·6	13·9	12·7	9·7	5·2	4·4	4·8	5·2	8·0	11·1	12·1	9·5
Sholapur	4—6	7·4	7·9	7·5	6·5	4·8	3·0	3·0	3·2	3·3	6·3	8·6	12·6	6·2
Ratnagiri	6—7	9·8	8·7	7·6	6·2	5·1	2·6	2·4	2·6	3·0	4·9	8·8	9·9	6·0
Belgaum	4—7	13·7	13·0	11·5	8·6	6·3	3·2	2·4	2·8	3·8	6·2	11·1	12·6	7·9
Karwar	3—4	6·0	5·2	3·9	4·7	5·0	4·3	?	?	?	4·7	5·9	6·2	?
Mangalore	3—4	8·5	7·6	?	3·3	3·3	2·2	2·1	1·9	2·6	5·0	4·6	7·1	?
Mercara	3—4	9·2	10·8	8·5	6·8	4·4	1·9	1·1	1·7	2·8	5·3	5·9	8·2	5·6
Akyab	5—6	7·9	8·5	8·2	6·2	3·6	1·9	1·2	1·3	2·4	3·9	5·5	6·5	4·8
Thayetmyo	4—7	7·8	7·7	6·6	4·7	3·8	1·9	3·5	2·1	2·2	2·7	4·2	5·6	4·4
Tounghoo	3—6	6·1	6·4	6·3	6·3	3·7	4·2	3·3	3·1	3·1	3·6	4·3	5·1	4·6
Bassein	3—5	?	8·5	7·5	5·5	4·7	2·1	2·1	2·2	2·6	3·8	4·6	6·3	?
Rangoon	4—7	8·3	7·2	5·9	4·9	4·4	2·7	2·6	2·9	3·9	4·5	6·1	7·5	5·1
Moulmein	3—5	8·3	7·9	7·9	6·4	6·1	5·3	3·2	2·1	1·4	3·6	5·6	?	?
Mergui	6—7	5·7	4·8	4·2	4·1	3·3	2·7	2·7	2·8	3·0	3·3	4·6	5·5	3·9
Port Blair	6—7	5·2	6·4	6·2	5·6	5·2	3·4	3·5	3·7	3·4	4·2	4·1	4·4	4·6
Nancowry	5—7	5·5	6·2	5·8	4·9	4·6	3·8	4·1	4·0	4·0	4·4	4·5	5·0	4·7

TABLE V.—*Comparison of mean monthly depression of nocturnal radiation temperatures in 1883 with the averages of Table IV.*

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	?	−0·5	−1·0	+0·2	−0·8	−0·6	−0·6	+1·4	+0·8	+1·0	+1·2	−0·3	?
Aden	−0·4	−0·4	−0·7	−1·9	−0·8	+0·1	−0·8	0	+0·5	+0·5	−1·2	−0·7	−0·5
Quetta	?	?	?	?	?	?	?	−0·3	?	−1·4	−1·3	+0·8	?
Leh	+0·6	+1·1	+1·2	+1·8	+2·1	+2·1	+2·5	+2·2	+0·2	−0·3	−1·5	+1·1	+1·1
Mooltan	−1·6	−1·2	−1·7	−1·8	−1·9	−1·2	−1·2	+1·0	+1·6	+1·3	0	−0·5	−0·6

TABLE V.—*Comparison of mean monthly depression of nocturnal radiation temperatures in 1883 with the averages of Table IV*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Dera Ismail Khan . .	P	−0·6	−0·8	−2·4	P	P	−2·6	−2·7	−3·0	−2·5	−3·0	−2·7	P
Peshawar . . .	−2·1	−0·4	+0·3	−0·3	0	−0·3	−0·6	−0·9	−0·7	−0·4	−0·9	−0·5	−0·6
Murree	−4·6	P	−0·8	−0·9	−0·1	+1·5	P	P	−1·2	P	P	P	P
Rawalpindi . . .	P	P	+2·1	+2·2	P	P	−0·7	−0·4	+1·1	+1·4	+2·7	+3·3	P
Sialkot	P	P	−0·6	−1·7	−0·2	+0·4	P	P	−1·9	−4·0	−2·0	−1·4	P
Lahore	−1·4	+2·6	0	+0·2	+2·0	+0·4	−0·2	0	−0·3	0	−0·7	0	+0·2
Ludhiana . . .	+1·8	+1·4	+1·6	+0·4	−1·2	P	−1·1	−1·9	−2·8	−4·7	−3·5	−3·3	P
Delhi	P	+2·8	+1·2	+1·4	+0·5	+0·6	+0·7	+1·5	+0·6	+0·2	+1·6	+2·4	P
Sirsa	+1·5	+4·3	+2·0	+1·0	+2·6	+0·7	−1·4	−1·2	+0·8	+2·3	+2·8	+4·6	+1·7
Chakrata . . .	−0·4	+3·2	+1·8	+3·7	+0·6	+1·1	+0·1	+0·2	0	−1·0	−2·1	−2·2	+0·4
Roorkee . . .	+1·1	+0·9	+1·2	+1·3	+1·6	−0·3	−0·4	−0·2	−1·2	−0·4	−0·3	+0·4	+0·3
Ranikhet . . .	−2·0	+1·8	−0·5	0	−0·5	−0·8	−0·9	+0·2	−0·2	+1·8	−0·5	−0·3	−0·2
Meerut	+0·7	+1·2	+1·2	P	P	P	P	P	P	+0·1	−0·1	−0·2	P
Bareilly	+0·8	+0·9	−0·7	+0·5	0	−2·8	+0·1	+0·9	−0·1	+1·5	−0·3	−0·5	0
Agra	+1·0	+1·6	+0·4	+0·5	+0·9	−0·2	−0·7	+0·8	+0·4	−0·4	+0·9	+2·2	+0·6
Lucknow . . .	−1·1	−0·6	−0·8	+0·7	+1·3	−0·2	−0·8	+0·7	−0·7	−0·3	−1·3	−1·5	−0·4
Gorakhpur . . .	P	P	P	P	P	P	−2·8	0	−2·4	−1·1	−0·9	−0·7	P
Jhansi	−2·1	−1·8	−1·8	+0·7	+0·5	0	−0·1	+0·4	−0·7	−1·5	−0·9	+0·6	−0·6
Allahabad . . .	−1·4	+0·4	−0·6	−0·1	+1·2	−0·1	−0·2	+1·0	−1·0	−1·2	−1·1	−0·6	−0·3
Benares . . .	+0·5	+0·6	−0·3	−0·2	+0·1	+0·2	0	+1·0	+0·7	+1·5	+1·0	+1·4	+0·5
Sibsagar . . .	+1·1	+1·2	+1·2	+2·0	+2·2	+2·4	+1·9	+1·5	+0·6	+1·1	+1·7	−0·1	+1·4
Dhubri	P	P	P	P	P	P	+0·3	+0·2	+0·3	+0·8	+0·6	+0·8	P
Purneah . . .	−0·3	0	−0·3	+0·3	−0·3	+0·3	−1·4	−0·9	−0·5	+2·2	+1·2	P	P
Durbhunga . . .	+1·0	+2·4	−0·4	−0·8	−1·0	−0·8	−2·0	−3·4	−3·2	−0·8	−4·5	P	P
Patna	+2·8	+3·5	+2·9	+2·4	P	−0·1	+0·1	−0·1	−0·2	+0·2	+0·3	−0·3	P
Hazaribagh . . .	−0·3	−0·7	−1·3	−0·2	+0·3	+0·4	+0·6	+1·1	+0·7	+2·0	+1·8	+3·3	+0·6
Burdwan . . .	−3·4	−1·7	−2·2	−1·3	−1·0	+0·8	+0·4	−0·6	−0·6	0	+0·5	−2·0	−0·9
Jessore	−1·5	−0·1	0	P	−1·4	−0·7	−0·2	+0·1	+0·2	+1·2	−0·9	−1·2	P
Dacca	+0·4	+1·0	−0·6	−1·0	−1·0	−0·3	0	0	−0·4	−0·1	+0·3	−0·3	−0·2
Chittagong . . .	P	+0·7	−1·1	+0·5	−0·8	−0·3	−0·3	−1·0	−0·2	+0·8	+1·1	−0·1	P
Calcutta (*Alipore*) .	+1·0	+1·3	+1·2	+0·8	+0·2	+0·5	+0·4	+0·8	+0·5	+1·6	+1·9	+0·2	+0·9
Saugor Island . .	P	+1·2	+2·2	+1·0	+0·6	+0·8	+1·0	P	P	P	P	P	P
Cuttack	−0·8	+0·4	−0·1	−0·5	−1·3	−1·3	−1·0	−0·7	+0·1	+0·6	−0·9	−0·4	−0·5
Sambalpur . . .	−2·8	−1·5	−2·5	+2·3	+1·2	+2·6	+1·8	+1·8	+1·2	−0·1	−0·8	−1·3	+0·2

TABLE V.—*Comparison of mean monthly depression of nocturnal radiation temperatures in 1883 with the averages of Table IV*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Raipur	?	?	−0·2	−0·1	−1·5	−1·9	−0·4	−2·5	−5·5	−2·3	+0·7	+1·9	?
Nagpur	+0·3	+1·5	+1·3	+1·2	+0·9	−0·6	+0·6	+1·7	−0·7	−0·2	+2·8	+3·1	+1·0
Seoni	−0·9	+0·4	+2·3	+2·1	+1·6	−1·1	0	+1·6	−0·5	+0·5	+0·9	+3·4	+0·9
Jubbulpore	+1·6	+3·2	+3·9	+3·4	+5·8	+1·3	−0·7	+0·3	−1·3	−1·2	+0·1	+2·1	+1·5
Saugor	−2·4	−1·7	−3·0	+3·7	+0·3	−3·1	−0.7	+0·3	−1·6	+0·3	−0·2	−0·2	−0·7
Pachmarhi	−1·0	−1·0	−0·3	+1·5	?	?	−0·5	?	−2·1	−3·0	−2·3	−0·6	?
Hoshangabad	−1·3	−1·2	+0·7	+1·0	+0·4	−0·6	+0·1	+1·1	−0·7	+0·1	+2·9	+2·7	+0·4
Khandwa	−2·7	−2·1	−1·4	−1·7	−2·2	−0·7	+0·5	+0·8	−0·7	−1·8	−1·1	+1·8	−0·9
Chanda	−0·6	+1·4	+0·7	+1·8	+1·2	−0·7	+0·3	+0·5	−0·3	−1·1	+0·6	−0·6	+0·3
Sironcha	−1·0	+0·8	−0·8	+1·0	−0·3	−0·9	−0·1	+0·4	0	−0·9	+2·3	+0·5	+0·1
Chikalda	−3·7	−1·3	−1·8	?	?	?	?	?	?	?	?	?	?
Buldana	−4·1	+1·5	−0·9	+2·0	−0·2	−0·7	−0·7	−0·5	−2·0	−3·4	+1·4	+1·8	−0·5
Akola	−0·9	−0·5	−1·4	−0·3	−1·4	−0·4	−0·2	+0·8	−1·2	−0·3	+1·7	+2·1	−0·2
Amraoti	+0·4	+0·2	+0·8	+4·0	+3·4	−1·1	−0·5	+2·1	+0·5	−2·1	−1·5	−0·1	+0·5
Neemuch	−1·6	+0·2	−0·1	+2·5	+4·3	+1·6	+1·5	+2·8	+1·5	−1·0	−0·8	+3·2	+1·2
Nowgong	+0·9	+1·7	?	?	+2·8	+0·5	+0·7	+0·1	−0·9	−0·5	−0·4	+1·5	?
Sutna	?	−0·5	−0·4	+0·4	+0·5	−0·1	−0·5	+0·1	−1·0	−0·8	−0·2	+0·6	?
Indore	−2·3	−0·4	+1·2	+2·2	?	?	?	?	?	?	?	?	?
Bickaneer	−0·1	+3·8	0	−0·3	−1·2	−0·2	−0·3	+0·6	+1·4	+1·6	−0·2	+2·7	+0·7
Jeypore	+0·8	+2·0	+0·4	?	?	?	+0·7	+1·2	−0·7	−0·2	−0·4	+0·3	?
Sambhar	−0·7	−0·7	−2·8	−5·0	−3·0	−1·4	−2·5	−1·4	−1·3	−1·4	0	+0·3	−1·7
Ajmere	+3·0	+3·5	+3·1	+3·5	−0·7	?	?	+0·9	−0·9	+0·8	+1·8	+1·2	?
Mount Abu	?	?	+7·1	+6·6	+1·5	+0·7	+1·9	+2·8	+1·8	+2·5	+4·8	+5·0	?
Pachbudra	?	?	?	?	?	?	?	?	?	−4·0	−1·0	−3·6	?
Jacobabad	?	−0·5	−0·8	−1·7	−1·4	−1·5	−2·2	−2·3	−2·0	−1·5	−2·5	−2·5	?
Hyderabad	−1·1	+2·2	+1·1	+1·2	?	?	?	?	?	?	?	?	?
Kurrachee	+0·5	+2·6	+1·8	+1·7	+0·6	+0·5	+0·8	+0·9	?	?	+1·6	+2·6	?
Bhuj	−1·4	+0·3	−1·0	−0·3	−2·1	−0·9	?	−0·4	−1·5	−0·5	−3·0	−1·8	?
Rajkot	−1·9	−0·9	−2·3	−1·2	−0·6	−0·3	−0·8	−0·1	−1·5	−2·3	−0·9	+0·5	−1·0
Deesa	−0·1	+0·1	−0·4	−0·2	?	?	?	+1·8	−1·3	−1·4	+0·2	−0·9	?
Surat	−1·8	0	−0·1	+0·1	+3·2	?	?	?	?	?	?	?	?
Malegaon	−1·0	−1·5	−1·1	+0·2	+0·3	+1·0	−0·1	+1·5	+0·1	−2·0	−0·7	?	?
Bombay	+1·8	+0·8	+1·0	+0·8	+0·6	−0·7	−0·7	+0·3	−0·7	−0·6	+0·9	+3·7	+0·6
Poona	−0·9	0	−1·0	−1·4	−0·4	−1·9	−1·0	?	−1·2	−2·3	−1·2	−0·6	?

TABLE V.—*Comparison of mean monthly depression of nocturnal radiation temperatures in 1883, with the averages of Table IV*—concluded.

Stations	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Sholapur . . .	?	?	?	?	?	?	?	?	?	?	?	+4·2	?
Ratnagiri . . .	+0·3	+1·2	+0·3	+0·6	+0·4	−0·7	−0·4	+0·5	−0·2	−0·6	−0·3	+0·3	+0·1
Belgaum . . .	−2·5	−0·8	−1·8	−0·2	−1·4	−1·7	−1·7	−1·0	−1·2	−2·7	−2·4	−0·3	−1·5
Karwar	−2·6	−2·1	+0·4	−0·1	−1·5	−0·6	?	?	?	+0·4	−0·1	−1·4	?
Mangalore . . .	−0·7	−0·8	?	−1·7	+0·8	+0·6	+0·6	−0·3	+1·0	−0·9	+0·3	−1·6	?
Mercara	−0·3	+0·6	−0·1	+0·1	+0·7	0	−0·4	0	+0·8	−0·7	+2·3	+0·5	+0·3
Akyab	−0·7	−0·2	−2·2	−0·8	+0·4	+0·1	+0·7	+0·6	+0·7	+0·6	+0·8	−0·5	0
Thayetmyo . . .	?	?	−2·9	−1·6	−1·3	−1·0	−2·0	−0·3	−0·3	+0·4	+0·3	−0·4	?
Tounghoo . . .	−0·3	+0·3	+0·3	?	?	+2·5	+0·9	−0·4	−0·2	−0·7	−1·1	−0·2	?
Bassein	?	−0·6	−0·5	−0·2	−0·8	?	?	+0·3	?	?	?	−0·8	?
Rangoon . . .	?	+1·0	+2·0	+1·4	−0·5	−0·9	−0·7	−1·1	−1·1	+0·1	−1·0	−0·8	?
Moulmein . . .	+0·9	−0·1	+0·2	+1·5	+1·0	+2·2	+4·5	−0·7	−0·9	−1·2	?	?	?
Mergui	−2·5	−4·1	−2·1	−0·1	−1·4	−1·4	−1·4	−1·4	−1·5	−1·7	?	?	?
Port Blair . . .	+0·8	+1·3	+2·0	+1·9	+1·2	+2·7	+2·4	+2·4	+1·6	+1·9	?	?	?
Nancowry . . .	−0·3	0	−1·7	−1·0	−0·8	−0·5	?	?	?	?	?	+1·2	?

There is but little that is characteristic or anomalous in the variations of the nocturnal radiation shewn in the above table. The departures from the mean normal values are in general small, and by no means uniform at different stations in the same province. In the case of some stations, the constancy of the same algebraical sign throughout, or, at all events, its improbable preponderance, seems to throw some doubt on the exactitude of the register, but all figures have been struck out which indicate so large an anomaly as to warrant their rejection. The net result obtained by taking the average of all the figures in each monthly column probably fairly represents the mean monthly anomaly of the entire area. This is as follows, each monthly mean being derived from the registers of from 64 to 77 stations:—

January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
−0·6	+0·5	0	+0·6	+0·3	−0·1	−0·2	+0·2	−0·6	−0·5	−0·1	+0·4

On the average of the whole year, the opposite variations of different months cancel each other, and the mean result is exactly normal.

The following is a comparative table of the mean depression of the nocturnal radiation thermometer at those stations that have afforded continuous registers for the last two years:—

Stations.	1882.	1883.	Stations.	1882.	1883.
Leh	9·4	10·4	Seoni	7·8	8·4
Mooltan	9·1	8·9	Jubbulpore . . .	6·5	8·2
Peshawar . . .	8·8	7·7	Hoshangabad . .	7·7	7·1
Lahore	6·9	7·4	Khandwa . . .	5·7	4·9
Chakrata . . .	8·5	8·8	Sironcha . . .	6·8	7·2
Dehra	6·4	6·4	Buldana . . .	10·8	8·8
Roorkee . . .	6·6	5·9	Akola	7·9	6·8
Ranikhet . . .	10·6	11·2	Jeypore . . .	8·7	8·1
Lucknow . . .	6·9	7·1	Sambhar . . .	8·0	7·1
Jhansi	4·0	3·6	Bombay . . .	6·7	6·6
Allahabad . . .	8·4	7·9	Ratnagiri . . .	6·4	6·1
Benares	8·2	8·1	Belgaum . . .	7·6	6·5
Berhampore . . .	9·1	7·7	Vizagapatam . .	8·6	9·2
Burdwan . . .	6·3	6·6	Secunderabad . .	5·8	4·0
Dacca	6·6	6·3	Mercara . . .	5·3	5·8
Calcutta . . .	5·8	6·5	Bangalore . . .	2·8	2·7
Cuttack	7·2	6·9	Madras	2·3	2·5
Sambalpur . . .	7·3	8·2	Salem	3·3	3·2
Nagpur	9·1	10·0	Coimbatore . . .	3·9	3·5
			Mean of 38 stations .	7·0	6·9

TEMPERATURE OF THE GROUND.

Observations of the temperature of the ground have been recorded during the whole of the year at the four stations, Calcutta, Allahabad, Dehra, and Jeypore.

The thermometers used for the purpose are verified standard mercurial thermometers, with attached scales of porcelain, the scale being engraved also on the tube. At Alipore (Calcutta), with the exception of the newly-installed thermometer at 6 feet, they are read three times daily, at equal intervals of eight hours; at Allahabad and Jeypore four times daily, at intervals of six hours; and at Dehra once daily, *viz.*, at 3 P.M.

The thermometers, with the exception of those on the surface (or at Allahabad $\frac{1}{2}$ inch deep), have the bulb protected with a pointed copper shoe, which rests on the ground, at the bottom of a wooden tube, buried in the ground to the specified depth, and projecting 6 inches above it; the upper end being closed by a cap of metal or wood.

Those, at depths below one foot, are attached to the lower end of a stout wooden bar, of about half the diameter of the tube. Those, at one foot, have a brass ring attached to the top of the wooden frame of the thermometer, by which it is lifted; and, in all these the lower part of the frame around the bulb has been cut away and the lower end fitted with the copper shoe above mentioned.

Table IV (Appendix) gives the monthly means of the readings at the hours of observation and those of the day in 1883. In the case of Dehra, only the former are available.[1]

At Alipore (Calcutta), two thermometers are used for obtaining the temperature at one foot deep. The object of this was explained in the Report for last year.[2] The instrument (here designated the old thermometer), which has been in use since April 1880, is inserted in a wooden tube about 2 inches wider than the slip of wood to which the thermometer is attached. The mean temperature of the year, shewn by this instrument, is lower than either that of the surface thermometer or that at 3 feet deep, and it was found that the means, as computed from three observations, correctly represented the true diurnal means. It was, therefore, inferred that the anomaly might probably be due to the nocturnal connection of cold air within the tube, and a consequent reduction of the temperature of the thermometer bulb below that of the ground or that depth. To test this view, and also to obtain a more trustworthy register, a second thermometer, here called the new thermometer, was installed at a few inches distance from the former, similarly mounted, but in a tube of such dimensions, that the wooden mounting, with a strip of cloth around it above the bulb, loosely fits the section of the tube, and all convection is thus prevented. A comparison of a complete year's registers of the two thermometers has entirely confirmed the original surmise. While the afternoon ($13\frac{3}{4}$h.) temperatures, shewn by the new thermometer, are either the same as those of the old thermometer or slightly lower, the early morning ($5\frac{3}{4}$h.) and late evening ($21\frac{3}{4}$h.) readings are almost invariably higher, and especially so in the cold season and in clear weather, when the nocturnal radiation is greatest. In some months this difference exceeds 1°, and the mean of the day, on the average of the whole year, as shewn by the new thermometer, is 0·3° higher than that of the old thermometer, and is in excess of the mean surface temperature by the same amount, being 1° lower than that of the thermometer at 3 feet deep.

The 1-foot thermometers at Allahabad and Jeypore shew an anomaly similar to that of the old 1-foot thermometer at Alipore, and doubtless due to the same cause.

The registers of both the 1-foot thermometers will be continued until they shall suffice for the determination of a correction to be applied to the past registers of the old instrument; those of the new being regarded as true values.

From the registers of the surface, 1 foot (new) and 3 feet thermometers at Alipore, it now appears as a consistent result, that not only is the temperature of the ground surface, on an average, 3·3° higher than that of the air, but there is a further rapid increase downwards, amounting on an average to 1° in 3 feet. This, of course, can only be attri-

[1] The depths of the Dehra thermometers given in the headings of the table are, strictly speaking, those at which the thermometers were originally inserted. Except in the case of the two deeper holes, these depths are apparently unchanged, but with respect to the latter, Mr. Hennessey writes (12th August 1884); "My two deep holes have [been] gradually silting up, so that since 1882 my 25·6' hole has gradually filled some 20 inches and the 12·8 foot hole has filled to the extent of 11 inches. The depths are measured at intervals.

[2] Report on the Meteorology of India in 1882, page 26.

buted to the existence of an abnormal source of heat at some moderate depth below the ground surface. And there is no difficulty in indicating such, in the decomposing organic matter with which certain beds in the alluvium are highly charged. Especially at a depth of 40 feet, beneath Calcutta, and in some places probably less, is a bed of quick-sand of a dark colour and strong fetid smell, which, if I may speak from recollection, as I have seen it exposed in excavations, is distinctly warm to the touch.

The Allahabad ground temperatures shew a downward increase of about half the amount registered at Alipore, *viz.*, 0·7°, on the average of nearly four years. This I should hardly have anticipated, as the ground at the Allahabad observatory, although alluvial, is that known as the old alluvium of the Gangetic plain, and is, to all appearance, very free from organic matter. At Jeypore, on the other hand, the surface temperature of the single year, for which we have a complete register, is 3° higher than that at 3 feet deep.

Calcutta and Allahabad are the only stations at which ground temperatures have been recorded for more than three years, the minimum period from which even an approximate determination of normal or standard values is admitted in these reports. These averages and the monthly departures from them in 1883 are given in the following tables VI and VII :—

TABLE VI.—*Average monthly mean temperatures of the ground at the surface and at 3 feet deep.*

		Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Calcutta (*Alipore*)	Surface	5—6	64·4	71·2	82·7	91·3	90·4	87·5	86·2	85·9	86·0	83·2	73·3	64·8	80·6
	3 feet deep	5—6	72·5	74·1	78·4	84·5	87·1	87·2	86·4	86·1	86·1	85·2	81·0	75·1	82·0
Allahabad	½ inch „	3—4	62·8	68·2	78·9	92·8	97·3	93·5	86·8	87·4	87·3	82·2	70·1	62·6	80·8
	3 feet „	3—4	69·7	70·6	76·2	83·6	89·2	91·0	88·1	87·3	87·1	84·7	78·2	71·8	81·5

TABLE VII.—*Comparison of the monthly mean temperatures of the ground in 1883 with the averages of Table VI.*

		January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Calcutta (*Alipore*)	Surface	+0·4	−1·9	−0·8	−0·7	+2·9	+0·2	+0·4	+0·9	+1·1	+0·5	−2·9	−2·7	−0·2
	3 feet deep	−0·3	−1·3	−1·1	−0·7	0	+0·5	−0·1	+0·2	+0·5	+0·5	−0·6	−1·7	−0·3
Allahabad	½ inch „	−0·6	−5·5	−3·3	−1·3	−0·7	−0·5	+0·1	+1·0	+0·2	−0·4	+0·9	−0·5	−0·9
	3 feet „	+0·2	−2·5	−2·2	−1·6	−1·2	−1·6	−0·7	+0·1	0	−0·5	−0·2	−1·0	−0·9

TEMPERATURE OF THE AIR.

At the large majority of stations,[1] the temperature of the air is observed only at 10 A.M. and 4 P.M., and these readings, together with those of the maximum and mini-

[1] At Dehra, in the North-Western Provinces, the observationswere recorded at 9h. 30m. and 15h. 30m., instead of 10h. and 16.

mum self-registering thermometers, afford the data for the deduction of the mean temperature. At stations in the Madras Presidency, readings are also recorded at 10 P.M.; at Lahore, Allahabad, Saugor Island, and Vizagapatam, 4 A.M. and 10 P.M. are additional hours; and at Calcutta (Alipore), Bombay, and at Leh during the last four months of 1883, 6 A.M. and 10 P.M.

At stations in India and Burma generally, the instruments are suspended in a cage, consisting of a narrow frame, with wire net-work at front and back, which is affixed to one of the uprights supporting the ridge-pole of a thatched shed, open all round, at such a height, that the bulbs of the several thermometers range from 4 feet to 4 feet 6 inches above the ground level. The shed and cage, of the approved form, are depicted in Part I of the Indian Meteorologist's Vade Mecum; and although it appears that, at some stations, this pattern is not strictly adhered to, the variations are not great. At Lucknow, Roorkee, Saugor, Seoni, Jubbulpore, Akola, and Amraoti, the sheds are smaller, and more or less enclosed by lattice-work or louvres, but the readings of the instruments are apparently not much affected thereby.

With very few exceptions (all of which are noted in the tables), all the thermometers for air-temperatures have been verified either at Calcutta, Bombay, or Madras; at the freezing points (by immersion in crushed melting ice), and at higher temperatures, comprehending the whole range of observation, by comparison with a Kew standard thermometer. All the readings are corrected to their true values.

The thermometers in use in Ceylon have been verified at Colombo, at various temperatures, by comparison with a standard thermometer, tested at the Greenwich observatory.

Table V (Appendix) gives the monthly and annual means and extreme temperatures at 134 observatories (four more than in 1882). Three stations, *viz.*, Dehra, Calcutta, and Sambalpur, furnish duplicate registers, so that the number of stations represented is 131. The duplicate register for the last two months of the year at Sambalpur is that of a new observatory which will supersede the old observatory, as soon as one year's comparative registers have been secured. The registers of Kailang, the Seychelles, and Tura appear in the present report for the first time, and also that of the new observatory at Karnool. The observatory at this station has been in abeyance since April 1876. Owing to various causes the following are more or less incomplete:—

Seychelles.	Sambalpur (new observatory).
Kailang.	Bhuj.
Mussooree.	Gopalpore.
Dehra (Forest School).	Karnul.
Paori.	Bassein.
Tura.	Nancowry.
Darjeeling.	

The tabulated data are the means of each hour of observation, those of the maximum and minimum temperatures respectively, and the extreme temperatures of each month and year, together with the mean daily and the extreme monthly and annual ranges; also the mean temperature of each month and that of the year, which have been computed in the following manner:—

(*a*)—At Calcutta (Alipore) they are the means of the observations deduced from the hourly measurements of the thermograph trace.

(*b*)—At Leh, the means of the observations at 6h., 10h., 16h. and 22h., without further corrections.

(*c*)—At Bombay, the means of the observations at 6h., 10h., 14h., 16h., and 22h., with additive corrections, derived from the Colaba hourly observations in past years.

(*d*)—At Lahore, Allahabad, Jeypore, Vizagapatam, and Saugor Island, the means of the four sets of readings at 4h., 10h., 16h., and 22h., without further corrections.

(*e*)—At stations in the Punjab (excepting Lahore), the Central Provinces, and Berar, and also at Dhubri, Tura, Demagiri, False Point, Port Blair, Nancowry, Katmandu, Leh (January to August), Quetta, Bushire, Zanzibar, Aden, the Seychelles, the Burmese stations (excepting Akyab); at stations in Rajputana (excepting Ajmere and Jeypore), Central India and Bombay (excepting those specified in (*b*) and (*g*), and at Gopalpore, Mangalore, and Mercara, they are the means of the 16-hour readings and the minimum temperatures.

(*f*)—At the Madras stations, including Bangalore and Secunderabad, but not Vizagapatam, Gopalpore, Karnool, Mercara, and Mangalore, the means of the 10h., 16h., and 22h., and minimum observations, corrected by range factors, derived from the Madras registers in past years.

(*g*)—At the stations in Bengal (excepting those named in *a*, *d*, and *e*), in the North-Western Provinces (except at Allahabad), at Ajmere, Sambhar, Karnool, and Akyab, the means of the 10h., and 16h., and minimum observations, corrected by range factors, derived from the six-hourly observations at the same or neighbouring stations in past years. In the case of Dehra, the Roorkee factors have been used; in that of Sibsagar, the Goalpara factors. The Monghyr factors are employed for Purneah, the Patna factors for Durbhanga, and those of Calcutta for Berhampore, Jessore, and Burdwan. In the case of Paori and Pithoragarh, the Raniket range factors have been used. In that of Sambhar the Ajmere factors.

(*h*)—At Deesa, Kurrachee, Poona, and Belgaum, they are the means of the observations, with additive or subtractive corrections derived from the hourly observations of past years.

(*i*)—At Mongpoo (Bengal) and the Ceylon stations, they are those of the maximum and minimum temperatures.

Table VI, in the Appendix, gives the data from which the isotherms of each month in Plates II to IV have been drawn. These are the adopted sea-level equivalents of the mean monthly temperatures in Table V (omitting hill stations). The reduction to sea-level values has been made, by adding 1° temperature for every 450 feet of elevation.

Table VIII, below, gives the average temperatures of all the stations, the records of which afford data for three years and upwards, derived from the registers of past years, by the same or equivalent methods as are the means of Table V (Appendix) I; and Table IX shews the variation, in 1883, above or below these averages.[1] Table X is a geographical summary of the data of Table IX.

In a very carefully worked out discussion of the temperature registers of North-Western India, published in Part II of the second volume of the *Indian Meteorological*

[1] Owing to changes of site, the temperatures of Saugor Island, False Point, and Ajmere are not strictly comparable with those recorded in former years, prior to the removal of the observatories; and since comparative readings, recorded simultaneously at the former and present sites, are not available as a basis for determining the amount of change thus effected in the registers, it has been necessary to resort to other and indirect methods for this purpose. The object of the change having been to improve the exposure of the instruments in all cases, the effect has been a reduction of the mean normal temperature, but this varies in amount at different seasons, and it has therefore been necessary to ascertain it separately for each month.

At Saugor Island, from February 1868 to the end of January 1880, the thermometers were suspended in a louvred enclosure, a space between the piles on which was erected the wooden structure forming the Telegraph Officers' quarters. They have since been exposed under a shed of the ordinary pattern. The mean temperature of the four years 1880-83 is 1·3° lower than that of the 12 years preceding, but the whole of this difference cannot be attributed to the change of site; since the mean temperature of the same four years at Calcutta is 0·6° below the general average of the place for 24 years (after all due corrections), and at Jessore 0·3° below the average of the last 15 years at the same station. Assuming that at Saugor Island 0·4° of the observed difference is the real difference of the mean temperature before and after the removal of the observatory, the residual difference due

Memoirs, Mr. S. A. Hill has determined what are probably more accurate average monthly and annual temperatures, for a number of the stations here included, than those adopted in Table VIII. And he has further given range factors, by the use of which the crude means of the same stations in Table IV may be corrected to values of the same order. As, however, the difference of the values in Mr. Hill's table and those here given is, in most cases, very small, and after all, the former can be considered only as a closer approximation to an unknown absolute mean, I have considered it better to adhere to the methods hitherto followed, and so preserve the continuity of the records. The tempera-

to the removal is 0°9. But this is not the same at all seasons. Month by month the differences of the averages of the two periods of 12 and 4 years are as follow, as shown by the registers:—

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
(12−4 years)	+1°6	+1°6	+1°0	+0°2	+1°2	+1°5	+1°3	+1°3	+1°3	+0°7	+1°6	+2°1

Shewing a very decided annual variation with two maxima and two minima. Deducting from each of the above the amount of the probable real temperature depression *viz.*, 0°4, which is assumed to be constant throughout, and then smoothing the residual monthly values, by substituting for each the mean of those consecutive terms, of which that substituted is the middle term, we obtain the following figures:—

January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
+1°4	+1°0	+0°5	+0°4	+0°6	+0°9	+1°0	+0°9	+0°7	+0°8	+1°1	+1°4

which, with changed signs, may be applied as corrections to the monthly mean temperatures of the 10 years' registers recorded at the original site to render them comparable with those of the present observatory.

At False Point, up to November 1877, the thermometers were suspended in a room in the light-house. They were then removed to the Telegraph Office, several miles from the light-house, when they were exposed under a shed of the usual kind; and finally, in August 1882, they were brought back to the light-house and exposed under a similar shed. It appears on a comparison of the registers previous to 1877 with those recorded with the shed exposure, that not only was the range of temperature in the light-house less, but also the mean temperature was too high. No valid comparison can be made between these earlier and the later records. Since the adoption of the shed exposure the conditions have been more uniform, and, although the change in the site of the observatory has probably introduced some small change in the normal value of the temperature readings, the conditions of the two sites are not so dissimilar, as in all probability seriously to impair that value.

The Ajmere observatory was removed in January 1880, from the position it had occupied since 1867, to the present site in a much more open position. No comparative observations were made at the time nor since, "and in order to ascertain the amount of change in the normal temperature due to the change of site, I have compared the Ajmere mean temperatures before and after the removal, with those recorded in the same years (1869 to 1879, and 1880 to 1883) at the not very distant station Jeypore, the situation of which is not dissimilar from that of Ajmere, and which has furnished a continuous register since 1869.

A comparison of the mean temperature of the 10 years 1869-1879 at the old Ajmere observatory, with that of the Jeypore observatory, and a similar comparison of the means of the 4 years 1880-1883 at the new Ajmere observatory month by month, give the following results, the differences of which, given in the 3rd line, are assumed as representing the change due to the removal:—

Jeypore Temperature minus Ajmere Temperature.

	January.	February.	March.	April.	May.	June.	July.	August	September.	October.	November.	December.
Old Observatory	+0°6	−3°3	−0°8	−3°3	−1°6	−0°3	+0°6	+0°5	+1°1	−1°4	+0°9	+0°2
New Observatory	+2°9	+3°0	+3°4	+3°0	+3°1	+3°2	+3°4	+3°3	+3°3	+3°1	+3°6	+3°1
Difference	−2°3	−6°3	−4°2	−6°3	−4°7	−3°5	−2°8	−2°8	−2°2	−4°5	−2°7	−2°9

The figures of the last line have been applied as corrections to the temperatures recorded prior to 1880 in order to deduce the averages given in the Table.

tures of 60 stations, extracted from Mr. Hill's table, were given in the report for 1882 (p. 31).

TABLE VIII.—*Average monthly mean temperatures of 128 stations in India, Ceylon, &c.*

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	3—4	81·2	81·6	82·4	80·6	78·4	78·4	76·7	76·7	77·6	78·6	79·7	81·0	79·4
Aden	3—4	75·2	76·3	78·9	81·8	85·4	87·0	84·1	84·6	86·2	82·1	77·5	75·6	81·2
Mauritius	12—13	79·2	78·9	78·1	76·7	73·3	70·3	68·8	69·1	70·3	72·5	75·3	77·9	74·2
Bushire	6—7	57·4	57·0	62·7	71·7	81·2	84·2	88·1	88·9	85·2	77·8	69·1	60·7	73·7
Quetta	5—6	40·5	40·5	50·6	58·6	67·7	74·3	76·8	75·2	66·8	56·4	45·3	41·3	57·8
Leh	8—13	17·1	19·9	31·1	41·1	46·9	56·2	61·6	59·6	52·0	39·6	30·3	23·1	39·9
Mooltan	13—15	54·3	58·3	70·4	79·9	88·7	94·4	91·5	89·0	86·5	77·0	66·0	56·3	76·0
Dera Ismail Khan	15—17	52·1	56·4	66·4	77·3	87·0	93·1	91·2	89·5	85·8	75·0	61·6	53·7	74·1
Peshawar	7—8	50·3	52·3	62·5	71·3	81·6	89·5	88·7	87·1	81·3	71·3	58·2	50·9	70·4
Murree	13—14	39·0	39·4	48·7	57·6	65·2	71·7	68·2	66·5	65·5	58·7	49·1	43·4	56·1
Rawalpindi	16—17	48·5	51·9	61·3	71·6	81·4	89·2	86·6	83·9	80·2	69·7	57·1	50·4	69·3
Sialkot	16—17	51·9	56·3	65·5	77·0	85·1	90·9	86·4	85·2	83·0	74·7	61·9	52·9	72·6
Lahore	15—17	54·0	59·0	69·5	81·3	88·8	93·7	89·0	88·0	84·7	77·0	64·6	55·4	75·4
Ludhiana	14—16	52·0	57·1	67·6	78·3	85·4	90·8	85·9	85·8	82·9	74·9	62·4	54·1	73·1
Simla	9—12	40·4	41·4	49·4	58·8	64·1	67·4	64·2	63·0	61·3	55·9	48·6	45·1	55·0
Delhi	8—9	58·3	62·3	74·4	84·6	89·6	93·7	87·0	86·7	84·7	79·1	68·4	60·2	77·4
Sirsa	6—8	55·6	59·9	71·3	82·4	89·1	93·6	88·9	88·6	85·5	78·6	67·9	56·8	76·3
Chakrata	15—16	42·3	43·4	51·0	60·0	64·4	67·4	64·3	64·1	63·1	57·9	51·4	46·4	56·3
Mussooree (*St. Fidelis.*)	3—6	45·4	46·7	54·7	64·4	67·9	69·5	66·6	66·0	65·1	61·5	52·6	50·0	59·2
Dehra	17—18	55·0	57·6	66·4	76·7	82·2	83·5	79·8	79·0	77·7	70·9	62·2	56·2	70·6
Paori	3	P	P	P	P	P	73·3	71·3	70·7	70·0	62·3	52·7	P	P
Roorkee	21	56·4	60·6	70·2	81·7	87·6	90·3	84·8	83·9	82·6	75·1	64·2	56·9	74·5
Ranikhet	13—14	46·3	48·5	56·5	65·5	68·0	70·9	67·8	67·3	66·2	61·2	54·8	49·7	60·2
Pithoragarh	3	P	P	P	P	68·8	70·7	70·7	70·6	70·5	64·8	56·5	53·1	P
Meerut	16—18	56·6	62·0	72·7	83·0	88·9	91·7	86·2	85·3	83·5	76·2	65·5	57·7	75·8
Bareilly	17—18	57·3	62·2	72·4	83·1	87·8	89·1	84·1	83·4	82·5	76·3	65·6	57·9	75·1
Agra	20—21	60·0	65·3	76·4	87·9	93·7	94·6	87·0	85·5	84·3	79·6	69·7	61·9	78·8
Lucknow	17—18	60·7	66·2	76·8	87·4	91·8	92·0	86·3	85·5	84·7	79·0	68·9	61·1	78·4
Gorakhpur	16—18	60·5	65·2	76·1	85·8	87·8	88·0	84·1	83·7	83·7	79·1	69·2	61·8	77·1
Jhansi	16—18	63·1	68·1	78·7	88·7	94·7	93·0	83·8	82·8	82·6	80·8	73·1	64·7	79·5
Allahabad	16—18	60·6	65·7	78·0	87·6	92·1	91·2	85·1	83·9	83·1	77·9	67·9	60·6	77·8
Benares	18—20	60·8	66·1	77·1	87·1	91·3	91·4	85·1	84·3	83·3	78·1	68·5	60·9	77·8

TABLE VIII.—*Average monthly mean temperatures of 128 stations in India, Ceylon, &c.*—contd.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Katmandu	4—5	47·7	50·3	59·0	64·1	67·5	72·4	72·9	72·3	71·6	64·5	53·5	48·0	62·0
Sibsagar	10	58·9	63·0	68·4	73·9	78·0	83·0	83·7	83·0	81·9	77·1	68·9	61·0	73·4
Dhubri	3	?	?	?	79·0	77·9	80·3	82·5	81·0	80·0	77·5	71·0	64·6	?
Silchar	14—15	63·6	67·3	73·3	78·0	79·6	81·7	82·3	81·9	81·7	79·7	73·1	65·8	75·7
Darjeeling (St. Paul's School.)	15—16	39·4	41·2	47·8	53·8	55·9	59·6	60·9	60·7	58·5	54·5	47·9	41·9	51·8
Mongpoo	6	53·8	55·7	62·7	68·2	69·0	71·8	72·9	72·2	71·8	67·9	61·3	55·2	65·2
Purneah	6—9	61·9	66·4	76·1	84·0	83·4	84·3	84·0	83·8	83·3	79·1	71·1	63·1	76·7
Durbhunga	6—8	62·1	64·9	75·0	83·8	84·7	85·2	84·3	83·6	83·7	79·5	71·3	63·0	76·8
Patna	15—16	61·1	65·9	77·5	86·8	88·5	88·1	84·8	84·0	84·0	79·7	70·3	62·4	77·8
Gya	12—14	64·3	69·6	80·3	89·4	91·6	89·4	84·4	83·9	84·2	80·3	71·7	64·6	79·5
Hazaribagh	15—16	61·0	65·1	74·9	83·4	85·2	82·3	78·4	77·8	77·7	74·1	67·2	60·9	74·0
Berhampore	16	64·5	69·2	78·1	85·3	85·0	84·2	83·2	82·8	83·0	80·5	73·0	65·6	77·9
Burdwan	10—11	66·1	70·5	79·6	85·7	84·8	84·6	83·6	82·8	83·1	80·6	73·3	66·4	78·4
Jessore	15—16	65·2	70·1	78·8	83·1	83·7	83·3	82·5	82·2	82·4	80·2	72·9	65·7	77·5
Dacca	14—16	66·7	71·7	79·3	83·0	83·3	83·7	83·6	83·6	83·6	81·8	75·2	68·4	78·7
Chittagong	15—16	66·7	71·1	77·3	81·5	82·3	81·3	80·7	80·6	81·1	79·8	74·5	68·1	77·1
Demagiri	5—7	62·4	64·4	72·8	78·0	79·1	79·3	78·5	78·8	79·0	78·4	73·1	65·2	74·1
Calcutta (*Alipore*)	6—7	65·1	70·9	79·0	84·4	84·8	84·5	83·0	82·4	82·4	80·1	72·5	64·9	77·8
Do. (*Chowringhee*)	3—4	67·3	71·6	78·9	84·3	83·9	82·9	82·2	81·6	82·3	80·1	72·9	66·2	77·9
Saugor Island	15—16	67·4	73·0	80·1	83·8	85·2	84·9	82·9	82·7	82·8	80·3	73·7	66·8	78·6
Cuttack	16	71·5	76·1	82·8	87·5	88·7	86·2	83·3	83·2	83·1	81·4	75·1	69·8	80·7
False Point	14—16	69·5	73·9	79·6	83·2	85·4	85·4	83·5	83·2	83·5	81·7	74·4	68·3	79·3
Sambalpur	12—13	67·5	72·9	80·7	89·5	92·6	87·4	80·5	80·5	81·7	79·3	71·8	66·4	79·2
Raipur	14—15	67·0	71·6	79·7	88·1	92·4	85·7	79·0	79·2	79·6	77·2	70·1	65·9	78·0
Nagpur	14—15	68·6	73·8	81·9	88·8	93·1	85·7	79·1	79·3	79·1	77·2	70·7	67·1	78·7
Seoni	12	63·9	68·6	77·2	84·3	87·7	82·2	76·3	75·8	76·0	72·7	66·2	62·7	74·5
Jubbulpore	15	61·9	66·4	75·8	84·8	90·6	86·5	78·8	78·3	78·6	74·1	65·7	61·0	75·2
Saugor	13—14	63·3	67·7	77·6	85·3	88·8	85·2	77·6	76·6	77·3	75·5	69·5	64·0	75·7
Pachmarhi	11—12	58·1	62·5	71·7	79·6	83·5	77·9	70·5	69·	70·3	66·9	59·5	56·3	68·9
Hoshangabad	14—15	66·0	70·4	79·3	88·0	92·7	87·4	79·1	78·5	79·4	77·2	70·2	66·1	77·9
Khandwa	8—9	66·8	71·0	80·1	87·7	92·1	86·7	79·7	78·9	78·5	76·8	69·6	65·4	77·8
Chanda	13—14	68·5	74·4	82·3	89·7	93·2	86·6	80·0	79·7	79·4	76·8	70·2	66·1	78·9
Sironcha	7—8	71·4	78·4	85·6	91·8	93·9	87·0	81·1	80·6	80·3	79·4	73·3	69·0	81·0
Chikalda	7—8	64·0	67·7	75·3	81·2	82·3	75·2	69·1	68·3	68·5	69·0	64·9	62·4	70·7
Buldana	9—10	68·7	73·0	80·8	86·5	87·3	80·1	75·7	74·6	74·5	75·3	70·3	67·5	76·2

TABLE VIII.—*Average monthly mean temperatures of 128 stations in India, Ceylon, &c.*—contd.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Akola	10—11	68·6	73·5	81·7	89·3	93·1	85·4	79·7	79·1	78·6	76·6	70·3	66·4	78·5
Amraoti	11	69·5	74·1	82·2	88·9	90·9	84·0	78·7	77·7	77·7	76·5	71·1	68·1	78·3
Makhla	4—5	65·1	68·8	77·3	83·7	85·6	75·3	70·8	70·4	70·1	70·1	65·2	63·8	72·2
Neemuch	6—7	62·5	65·6	75·9	84·5	88·4	86·4	79·1	78·3	78·0	76·4	67·7	62·7	75·5
Nowgong	6—7	59·9	65·5	76·6	87·4	92·5	91·9	83·4	82·9	82·4	77·5	66·3	59·9	77·2
Sutna	7—8	60·5	65·1	75·8	85·4	90·0	89·4	81·7	81·2	80·7	76·1	66·2	60·1	76·0
Indore	6	64·5	67·6	75·7	83·3	87·5	82·9	76·7	76·2	75·9	74·6	66·4	62·6	74·5
Bickaneer	5—7	60·3	63·6	77·5	87·7	93·7	95·7	90·0	87·3	87·6	83·9	70·6	61·9	80·0
Jeypore	14—15	60·7	63·5	75·9	85·4	90·1	90·6	84·0	82·1	82·7	77·6	69·3	61·9	77·0
Sambhar	3—4	59·1	63·4	73·0	86·4	91·1	90·8	82·4	82·0	81·4	77·6	65·2	59·3	76·0
Ajmere	17	57·5	61·3	72·2	83·3	89·2	87·6	82·0	79·5	80·9	74·7	66·2	58·9	74·4
Mount Abu	6—8	58·2	59·9	69·1	75·6	78·8	75·4	69·7	68·1	69·1	70·1	63·4	59·2	68·1
Pachbudra	3—5	61·4	64·5	76·5	86·5	91·3	92·0	86·1	83·6	84·1	80·0	66·9	61·4	77·9
Jacobabad	5—7	57·5	61·8	74·3	83·4	91·9	95·9	93·6	90·5	87·7	78·3	64·8	58·0	78·1
Hyderabad	5—7	63·3	66·1	78·3	86·1	91·2	90·6	87·9	85·4	85·7	82·8	71·3	63·2	79·3
Kurrachee	8—9	65·3	68·2	76·4	80·4	85·4	86·6	83·9	81·8	82·0	79·6	72·2	67·2	77·4
Bhuj	6—8	66·9	70·0	78·5	83·9	86·8	86·4	82·8	81·2	81·4	81·5	73·5	67·6	78·4
Rajkot	5—7	66·8	70·3	77·9	84·2	88·1	86·3	81·8	80·5	80·1	80·1	72·6	67·3	78·0
Deesa	9	67·3	70·9	81·2	88·1	92·0	90·0	83·1	81·9	82·0	80·3	73·5	68·9	79·9
Surat*	6—7	70·5	72·9	79·4	84·5	85·7	84·2	81·2	80·8	80·5	79·9	74·7	70·7	78·8
Malegaon	6—7	68·2	72·1	79·7	85·5	87·8	82·3	78·2	77·4	77·1	76·4	70·4	66·3	76·8
Bombay	37	73 9	75·4	79·0	82·5	85·0	83·1	80·9	80·1	80·0	81·0	78·9	76·0	79·7
Poona	8—9	71·9	76·3	82·7	85·8	84·9	78·8	75·2	74·9	75·0	77·8	75·2	71·7	77·5
Sholapur	7	71·9	76·9	83·5	88·1	88·9	81·1	78·7	77·9	77·1	77·3	73·9	70·3	78·8
Ratnagiri	7	75·1	75·5	78·7	82·1	83·7	80·2	78·7	78·1	77·9	78·8	77·5	75·3	78·5
Belgaum	8—9	72·0	76·1	79·9	80·9	79·7	73·3	70·9	70·4	70·6	74·1	73·1	71·4	74·4
Karwar	5—6	76·1	76·2	79·9	82·2	83·5	78·5	77·5	77·1	76·8	77·7	76·9	75·1	78·1
Vizagapatam	14	75·9	78·9	83·3	86·3	87·9	87·7	85·2	85·3	84·8	83·3	79 3	75·1	82·8
Masulipatam	13—14	74·6	76·9	80·9	84·8	87·9	87·1	84·0	83·7	82·6	81·1	77·6	74·4	81·3
Secunderabad	13—14	70·5	75·8	82·1	87·1	88·8	81·8	77·1	77·2	76·4	76·0	71·9	69·0	77·8
Kurnool	7—8	74·7	79·8	86·1	90·8	89·5	84.1	80·2	80·8	79·6	79·1	76·2	73·4	81·2
Bellary	13—14	73·3	78·6	85·3	89·1	88·1	83·1	80·7	80·7	79·8	78·8	75·3	72·5	80·4
Mangalore	3—4	77·0	77·9	80·7	83·4	82·7	77·9	76·6	76·6	77·2	78·3	78·5	76·9	78·6
Mercara	3—4	64·6	67·7	70·3	71·6	70·5	65·2	63·7	64·5	64·3	66·1	65·7	64·1	66·5
Bangalore	13—14	67·5	71·9	76·8	80·1	78·5	74·1	72·1	72·1	71·9	71·9	69 9	67·3	72·8

TABLE VIII.—*Average monthly mean temperatures of 128 stations in India, Ceylon, &c.*—concld.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Madras . .	24	75·8	77·4	81·0	85·1	87·4	87·7	85·5	84·5	84·2	81·3	78·4	76·1	82·0
Salem . . .	13—14	75·7	79·0	83·7	86·1	85·1	82·6	81·0	80·4	80·2	79·0	77·0	75·0	80·4
Wellington . .	10—12	55·3	58·3	62·7	65·1	65·6	63·4	62·5	62·4	61·9	60·6	58·3	55·6	61·0
Coimbatore . .	14	73·8	77·0	81·2	83·2	81·2	78·0	76·7	76·9	77·2	76·9	75·7	73·7	77·6
Trichinopoly . .	13—14	75·8	78·6	83·3	87·2	87·7	86·2	85·1	83·8	83·0	80·5	77·9	75·6	82·1
Negapatam . .	13—14	76·6	78·1	81·7	84·9	85·9	85·6	84·3	83·1	82·5	81·0	78·5	76·4	81·6
Madura . .	14	77·2	79·2	82·8	85·7	85·7	85·0	84·3	83·4	83·0	80·7	78·8	77·1	81·9
Cochin . .	12—13	78·8	80·1	82·5	83·8	81·8	78·3	77·3	77·7	78·1	78·8	79·4	78·8	79·6
Colombo . .	14—15	79·5	80·5	82·0	83·2	82·9	81·6	81·1	80·6	81·4	80·8	80·3	79·9	81·2
Jaffna . . .	12	78·1	79·8	83·5	85·9	85·4	84·2	83·1	83·0	82·8	82·1	79·9	78·2	82·2
Trincomalee . .	11—14	78·4	79·8	81·9	84·5	85·2	84·9	84·8	84·4	83·5	81·6	79·3	78·4	82·2
Batticaloa . .	13—14	78·2	79·1	81·2	83·6	84·6	85·2	84·8	83·9	83·4	82·1	79·7	78·4	82·0
Hambantota . .	14	78·8	79·6	81·1	82·7	82·1	81·5	81·1	80·9	80·8	80·6	79·9	79·3	80·7
Galle . . .	14—15	78·2	79·5	81·2	82·1	81·9	80·6	79·9	80·0	80·1	79·9	79·2	78·6	80·1
Kandy . . .	13—14	74·1	76·1	78·7	79·1	79·0	76·4	75·7	75·8	75·9	75·9	75·4	74·5	76·4
Newera Eliya .	12—14	57·5	57·4	59·0	60·1	61·2	59·3	58·5	58·8	58·8	59·0	58·7	58·0	58·9
Akyab . . .	14—16	69·5	73·0	78·6	83·6	84·2	81·6	80·6	80·9	81·7	81·4	77·6	71·6	78·7
Thayetmyo . .	5—7	68·9	73·6	82·1	87·6	85·6	80·5	80·6	80·4	81·0	80·7	76·7	71·6	79·1
Tounghoo . .	4—7	70·7	74·8	80·3	84·8	82·9	78·8	78·4	78·0	79·7	80·3	77·7	73·0	78·3
Bassein . .	6—7	71·9	75·5	79·9	82·7	82·5	79·0	78·2	78·2	78·4	78·8	77·9	74·3	78·1
Diamond Island .	5—6	75·7	77·3	79·6	82·5	82·7	79·7	78·7	78·7	78·7	79·9	79·0	77·3	79·2
Rangoon . .	7—8	75·3	77·6	81·3	83·8	82·4	79·0	78·0	78·0	78·5	80·1	78·4	76·2	79·1
Moulmein . .	7—8	75·3	77·7	81·3	82·9	81·6	77·9	76·9	77·3	77·6	79·8	78·4	76·3	78·6
Mergui . .	6—7	76·8	79·5	80·4	80·7	80·1	76·8	76·4	76·8	76·6	77·6	77·5	76·7	78·0
Port Blair . .	15—16	79·1	79·6	81·6	83·3	81·3	80·7	80·0	79·7	79·2	79·6	80·0	79·2	80·3
Nancowry . .	10—11	79·5	80·8	81·9	82·4	81·3	80·3	80·0	79·4	79·5	78·7	79·0	78·8	80·2

TABLE IX.—*Comparison of monthly mean temperatures in 1883 with the averages of Table VIII.*

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar . . .	+0·2	0	+0·5	+0·4	0	+0·6	+0·1	+0·6	−0·1	0	+0·1	+0·1	+0·2
Aden	+0·3	−0·8	−0·2	−0·2	−1·1	+0·1	−2·6	−0·3	−0·6	−0·2	−0·6	−1·2	−0·6
Mauritius . . .	−0·5	−0·7	−0·1	−0·4	0	+0·9	+0·5	+0·2	−0·5	−1·4	−1·2	−1·2	−0·4
Bushire . . .	+0·4	+1·0	−0·3	+0·9	+1·8	+1·5	+0·5	+1·6	+0·2	+1·8	+1·2	+0·3	+0·9

TABLE IX.—*Comparison of monthly mean temperatures in 1883 with the averages of Table VIII*—continued.

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Quetta	−2·9	−0·7	−2·2	+1·3	−0·5	+1·8	−0·5	−0·2	+1·6	−1·6	−1·4	−0·4	−0·5
Leh	+2·3	−0·4	−1·9	+2·5	−0·7	+0·7	+3·9	+3·0	+4·3	−0·7	−3·2	−3·4	+0·5
Mooltan	+1·2	−1·3	−1·6	+2·3	−2·0	+0·4	−2·2	+0·7	+0·8	+0·4	−2·3	−0·5	−0·4
Dera Ismail Khan	+1·9	−1·3	−0·4	+2·3	+0·1	+2·9	−0·6	+2·6	+1·3	+1·0	−0·3	+0·9	+0·9
Peshawar	−0·4	−1·1	−1·9	+2·1	+2·7	+2·4	−0·1	+1·4	+2·0	−0·2	−1·0	−0·5	+0·5
Murree	−2·7	−2·7	−3·1	+0·7	−0·7	+1·6	+1·3	+0·6	−0·6	−1·9	−3·5	−2·2	−1·1
Rawalpindi	+0·4	−2·5	−2·3	+1·9	−0·5	+1·2	−0·4	+0·6	−0·6	+0·1	−2·1	−2·0	−0·5
Sialkot	+2·0	−1·6	−0·5	+3·8	+1·9	+3·9	+2·1	+2·1	0	+1·2	+0·3	+0·8	+1·3
Lahore	+1·0	−2·8	−0·8	+2·5	+0·6	+2·3	+2·7	+3·9	−1·2	−0·8	−2·3	−1·0	+0·3
Ludhiana	+1·7	−2·3	+0·2	+3·3	+2·7	−0·3	+0·9	+4·1	−0·4	+0·1	−0·5	0	+0·8
Simla	−2·2	−0·7	−1·3	+1·9	+1·1	−0·7	+0·3	+0·3	+0·5	0	−1·9	−3·0	−0·5
Delhi	+1·1	−1·5	−1·8	+2·9	+2·4	0	+1·3	+4·8	+1·3	+0·6	−2·0	−1·0	+0·7
Sirsa	+0·2	−2·3	−2·4	+2·3	−0·3	+0·5	+0·3	+3·6	−1·1	−1·1	−2·0	−0·9	−0·3
Chakrata	−2·8	−0·9	−1·6	+2·1	+2·0	−1·7	−0·1	0	+0·1	−0·1	−4·2	−2·9	−0·8
Mussooree (*St. Fidelis*)	−3·4	−1·4	−2·0	+1·8	+1·9	−0·4	−0·3	+0·2	−0·4	−1·6	−2·8	?	?
Dehra	−1·3	−2·2	−2·6	+2·1	+1·2	−0·4	0	+0·2	−0·8	−1·6	−2·9	−2·9	−0·9
Paori	?	?	?	?	?	+0·9	+0·4	+0·4	−0·6	−1·1	−1·0	?	?
Roorkee	+0·3	−3·5	−2·1	+2·5	+0·5	−1·0	−0·1	+1·4	−0·7	−1·0	−1·5	−1·7	−0·6
Ranikhet	−2·8	−0·3	−2·8	+1·9	+0·9	−0·8	0	+0·2	0	−0·5	−3·2	−3·3	−0·9
Pithoragarh	?	?	?	?	+1·9	+0·9	+0·8	+0·6	−0·3	−1·0	−1·4	−3·8	?
Meerut	+0·1	−4·0	−2·4	+2·0	−0·1	−0·2	+0·5	+3·1	+0·2	−0·7	−2·7	−2·1	−0·5
Bareilly	+1·6	−2·3	−1·5	+2·3	+0·6	+1·7	+0·6	+2·6	+1·5	+0·5	−0·8	−1·9	+0·4
Agra	+2·2	−2·5	−0·3	+3·0	+1·2	0	−0·5	+5·7	+3·3	+2·7	−0·2	−1·0	+1·1
Lucknow	+1·2	−3·5	−2·1	+1·6	+0·9	−0·2	−0·8	+1·4	+0·5	−1·2	−2·3	−2·6	−0·6
Gorakhpur	−0·6	−4·0	−1·6	−0·5	+1·3	−1·9	+0·5	+1·7	+1·3	+1·0	−1·5	−1·7	−0·5
Jhansi	+0·4	−3·6	−1·5	+2·8	+0·8	+1·0	−0·4	+3·5	+1·3	+0·5	−1·5	−2·3	+0·1
Allahabad	−0·4	−3·9	−2·4	+1·4	+1·3	−0·4	−0·4	+1·9	−0·1	−0·7	−1·6	−2·4	−0·6
Benares	+0·8	−2·9	−1·1	+1·1	+1·3	−3·0	−0·4	+1·8	+0·9	+0·3	−1·0	−2·4	−0·4
Katmandu	−0·3	−0·5	−1·1	−0·6	+0·6	−0·4	0	−0·4	−0·5	−0·9	−0·2	−2·3	−0·6
Sibsagar	0	−1·3	−0·6	+0·5	+0·3	+0·5	+1·2	+0·2	+0·3	+0·1	−0·5	−1·3	−0·1
Dhubri	?	?	?	+0·3	−0·9	+0·7	+0·5	+0·2	+0·6	+0·3	−0·7	−2·1	?
Silchar	+0·1	−1·7	+0·6	−0·2	−3·4	−0·1	+1·5	−0·2	0	−0·4	−0·4	−1·3	−0·5
Darjeeling (*St. Paul's School*).	−1·5	−1·9	?	?	?	?	+0·9	+0·1	+0·9	−0·4	−1·7	−0·7	?
Mongpoo	−1·0	−1·2	−0·6	+0·1	+0·2	+0·4	+0·6	0	−0·5	−1·0	−1·4	−2·2	−0·6

TABLE IX.—*Comparison of monthly mean temperatures in 1883 with the averages of Table VIII*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Purneah . . .	+0·1	?	−1·3	−0·9	+0·2	0	+0·9	−0·4	+0·1	−0·3	−2·4	−3·5	?
Durbhunga . . .	+0·3	−1·4	−0·3	−0·2	+0·4	−0·2	+0·6	+0·2	+0·2	+0·3	−1·8	−1·2	−0·3
Patna	+1·0	−1·9	−0·8	+0·5	+1·6	−1·9	−0·4	+0·2	+0·7	+0·7	−0·7	−1·6	−0·2
Gya	−0·3	−3·0	−0·9	+2·4	+3·8	−1·6	−0·3	+1·8	+1·1	+1·2	−0·8	−2·5	+0·1
Hazaribagh . . .	−0·6	−2·7	−1·7	+2·6	+4·0	−0·9	−0·8	+0·6	+0·4	+1·2	−2·1	−2·9	−0·2
Berhampore . . .	−0·7	−2·7	−1·5	−0·6	−0·7	−1·6	−0·8	−1·2	−0·1	−0·3	−2·1	−3·3	−1·3
Burdwan . . .	−1·4	−3·1	−2·3	−1·5	+0·5	−1·1	−1·0	−1·1	−0·2	−0·4	−2·2	−3·4	−1·4
Jessore	−1·3	−2·9	−1·3	−1·3	0	−0·7	−0·1	0	−0·3	+0·2	−1·9	−2·4	−1·0
Dacca	−0·9	−2·7	−0·2	+0·4	+0·3	−0·6	+0·3	+0·1	+0·2	+0·8	−1·2	−2·0	−0·5
Chittagong . . .	−1·2	−2·5	−1·6	−1·5	−0·9	−1·3	−0·4	−0·7	−0·7	+0·1	−0·6	−1·7	−1·1
Demagiri . . .	−0·9	−3·0	−1·2	+0·4	−0·7	+0·2	−0·6	+1·2	−1·0	+1·2	+0·4	−0·6	−0·4
Calcutta (*Alipore*) . .	−1·2	−3·4	−1·1	−0·6	+1·3	−0·6	−0·2	0	+0·3	0	−2·7	−2·5	−0·9
Do. (*Chowringhee*) .	−0·7	−2·2	−0·1	−0·6	+1·7	+0·5	+0·2	+0·2	+0·2	+0·8	−1·2	−2·0	−0·3
Saugor Island . .	−0·7	−3·4	−1·0	−0·1	+0·6	−0·2	0	−0·2	−0·2	+0·6	−1·2	−2·2	−0·7
Cuttack	+0·6	−0·3	+0·3	+0·7	+0·8	−2·1	−0·5	0	+0·2	+0·9	−1·2	−3·8	−0·4
False Point . . .	−2·6	−4·2	−1·7	−2·1	−2·6	−3·4	−2·8	−2·5	−2·1	−1·9	−4·0	−5·7	−3·0
Sambalpur . . .	+1·2	+1·2	+0·1	+1·5	+3·9	+0·3	−0·1	+1·8	+0·2	+0·4	−2·7	−4·6	+0·3
Raipur	+0·7	+1·1	+0·9	+2·8	+4·2	−2·6	+0·1	+2·6	−1·0	−0·4	−1·9	−5·4	+0·1
Nagpur	+0·1	+0·1	−0·1	+1·7	+2·5	−2·6	+0·6	+2·8	−0·9	−0·5	−1·5	−4·7	−0·2
Seoni	+0·5	+0·3	+0·1	+2·0	+2·6	−2·2	+0·2	+2·3	−0·4	+0·2	−1·0	−4·0	+0·1
Jubbulpore . . .	+2·1	+0·4	+1·2	+2·7	+3·9	−0·8	−0·1	+2·3	−0·4	−0·3	−1·1	−5·2	+0·4
Saugor	+1·0	−1·6	−1·5	+2·5	+1·7	−0·8	+0·7	+2·5	+0·2	−1·1	−2·1	−3·9	−0·2
Pachmarhi . . .	+0·3	−0·2	−0·7	+1·6	+1·3	−0·8	−0·2	+1·7	−0·5	−0·7	−1·8	−5·1	−0·4
Hoshangabad . .	+1·0	−0·9	−0·4	+1·4	+0·4	−1·1	−0·1	+1·3	−1·1	−1·8	−2·9	−6·9	−0·9
Khandwa . . .	+1·1	−0·2	−0·8	+1·8	+0·5	−2·3	−0·6	+0·9	−0·7	−1·7	−2·2	−6·1	−0·9
Chanda . . .	+0·5	+1·6	+0·3	+2·1	+3·8	−1·6	+0·8	+1·9	−0·8	+0·6	−2·6	−5·6	+0·1
Sironcha . . .	+0·4	+0·3	−0·8	+0·6	+3·5	−2·9	−0·9	+0·4	−1·3	+0·2	−1·9	−3·7	−0·5
Chikalda . . .	−0·6	+1·1	−1·1	+1·8	+0·4	−1·7	−0·4	+1·0	−1·7	−1·7	−1·4	−3·6	−0·7
Buldana . . .	−0·3	+1·0	−1·4	+1·5	+1·0	−1·3	−1·1	−0·1	−2·2	−2·6	−1·9	−4·3	−1·0
Akola	+0·8	+0·7	−0·1	+1·1	+1·0	−2·0	−0·6	+1·1	−1·4	−1·0	−1·6	−5·5	−0·6
Amraoti . . .	+0·5	+1·4	−0·4	+1·3	+1·7	−2·3	−1·1	+2·2	−2·0	−1·6	−1·8	−4·2	−0·5
Makhla	−0·6	0	−1·8	+1·2	−0·4	0	0	+0·6	−1·4	−1·7	−1·7	−0·7	−0·5
Neemuch . . .	+0·1	−2·5	−2·2	+1·7	−0·9	−0·8	−1·0	+1·2	−1·4	−2·2	−1·7	−3·7	−1·1
Nowgong . . .	+0·9	−3·3	−1·6	+0·1	−0·2	−0·7	−1·2	+0·9	−0·3	−1·3	−1·0	−3·1	−0·9

TABLE IX.—*Comparison of monthly mean temperatures in 1883 with the averages of Table VIII*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Sutna	−0·3	−2·9	−1·7	+1·0	+1·3	−0·4	−0·6	+1·3	−0·4	−1·1	−1·6	−3·2	−0·7
Indore	−0·3	−2·2	−1·9	+1·4	−0·1	−1·2	−0·4	+0·4	−1·2	−3·0	−2·1	−5·2	−1·3
Bickaneer	−0·3	−0·7	−3·3	+1·8	−0·9	+1·3	−0·8	+4·3	−0·6	−0·9	−1·3	−0·8	−0·2
Jeypore	+0·1	−1·5	−2·3	+2·3	−0·9	−1·7	−1·5	+3·7	−0·1	+0·7	−2·6	−2·5	−0·5
Sambhar	−1·3	−3·2	−0·8	+1·1	−0·1	−0·2	+0·6	+3·9	+0·8	−0·8	−1·3	−3·2	−0·4
Ajmere	+0·9	−1·1	−0·7	+2·8	−0·4	+0·2	−1·2	+4·2	−0·7	+0·6	−2·8	−2·8	−0·1
Mount Abu	−0·8	−0·9	−2·9	+2·6	−1·2	0	−0·6	+1·4	−1·2	−1·7	−3·0	−3·2	−1·0
Pachbudra	−2·0	−1·7	−2·6	+1·4	−0·7	+1·0	−0·1	+3·9	−0·8	0	−0·6	−2·4	−0·4
Jacobabad	+0·2	−1·7	−1·6	+4·2	+1·7	+2·1	−2·3	+0·4	+0·9	−1·9	−1·5	−0·9	0
Hyderabad	−0·9	−1·0	−2·4	+1·4	+0·3	+0·6	−1·6	−0·2	−1·3	−0·1	−2·1	−0·8	−0·7
Kurrachee	+0·5	−0·4	−1·8	+0·6	−0·2	+1·0	−0·5	−0·9	−0·7	+0·6	−1·9	−1·3	−0·4
Bhuj	+0·2	−1·6	−2·2	+1·9	−1·0	+1·5	?	+0·7	−1·7	+1·1	−2·1	−2·4	?
Rajkot	+0·8	−2·0	−1·6	+1·6	−0·1	+0·7	−0·9	+1·8	−1·8	−1·2	−2·3	−3·1	−0·7
Deesa	+0·7	−0·7	−2·2	+3·0	−1·0	+0·8	−0·9	+2·5	−0·5	−0·1	−2·2	−2·7	−0·3
Surat	−0·3	−1·3	−2·0	−0·4	+0·4	−1·0	−0·3	+0·7	−2·0	−1·2	−2·0	−3·2	−1·1
Malegaon	−0·1	−0·8	−2·3	+0·7	+0·5	−1·0	−0·7	−0·6	−1·4	−1·4	−2·5	−5·7	−1·3
Bombay	+1·6	−0·4	−0·9	0	−0·5	−1·1	−0·4	+0·1	−1·5	−0·9	−1·1	−2·7	−0·7
Poona	+0·3	+1·8	−1·5	+1·1	+0·8	−2·1	−0·6	+0·2	−2·0	−2·1	−2·2	−4·5	−0·9
Sholapur	−1·6	+0·4	−1·5	−0·5	−0·4	−3·4	−0·3	0	−0·6	+0·3	+0·5	−2·7	−0·8
Ratnagiri	−0·5	0	−1·3	−0·2	+0·6	−1·1	−0·4	+0·4	−0·9	−0·5	−1·6	−2·5	−0·7
Belgaum	−2·1	+0·3	−1·0	−0·5	+0·5	−1·2	−0·7	+0·9	−0·7	−1·4	−2·6	−3·7	−1·0
Karwar	−0·9	−0·4	−1·7	−0·6	−0·1	−0·1	−0·8	+0·1	−0·6	−1·2	−2·4	−2·4	−1·0
Vizagapatam	−0·6	+0·4	+0·3	−0·2	+0·8	−0·3	+0·3	+0·6	0	+0·3	−2·6	−2·3	−0·3
Masulipatam	−0·6	−1·1	−0·1	−0·8	+1·1	−1·6	−1·2	+0·2	+1·4	−0·5	−2·2	−3·0	−0·7
Secunderabad	−1·0	+1·0	−1·6	+0·6	+3·1	−1·9	−0·3	−0·1	−1·1	−0·6	−2·7	−3·4	−0·7
Kurnool	?	−0·6	−0·6	−0·7	+1·3	−1·8	−0·6	−1·1	−0·4	−1·0	−2·9	−4·6	?
Bellary	−1·4	−1·1	−1·0	+0·3	+1·9	+0·2	0	−0·5	+1·1	−1·1	−2·5	−3·3	−0·6
Mangalore	−0·3	+0·8	0	−0·9	+0·2	+0·4	−0·1	+0·6	+0·6	−0·8	−1·1	−1·5	−0·2
Mercara	−0·7	−0·2	−0·7	−0·9	0	+0·3	+0·3	+1·0	+0·2	−0·2	−1·5	−2·3	−0·4
Bangalore	−1·2	−0·8	+0·4	+0·2	+0·8	+0·6	−0·9	+0·4	+0·5	−1·2	−2·5	−2·9	−0·6
Madras	−0·2	−1·0	−0·3	−1·4	+0·1	−1·1	−2·3	−0·6	+0·5	−2·7	−2·1	−2·5	−1·1
Salem	−0·5	−1·5	−0·7	0	+0·5	−1·2	−1·4	−1·7	+0·3	−2·2	−3·0	−3·2	−1·3
Wellington	−0·2	−0·7	−0·2	+0·6	+1·2	+0·2	+0·7	+0·7	+0·1	−0·5	−1·0	−0·7	0
Coimbatore	+0·3	−0·2	+0·1	+0·1	+0·2	+0·4	−0·1	+0·1	+0·5	−0·8	−1·6	−1·6	−0·2

TABLE IX.—*Comparison of monthly mean temperatures in 1883 with the averages of Table VIII*—concluded.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Trichinopoly . . .	+0·6	—0·7	+0·8	+1·5	+0·7	+0·2	—0·2	+0·4	+1·5	—1·4	—1·4	—1·2	+0·1
Negapatam . . .	—0·1	—0·7	—0·3	—0·1	+0·3	—0·9	—0·3	+0·4	+0·4	—1·8	—1·7	—1·8	—0·6
Madura	+0·6	—0·7	+0·7	+0·3	+0·6	+0·7	—0·9	+0·2	+1·0	—1·2	—1·8	—1·6	—0·2
Cochin	+0·5	—0·4	—0·1	—0·5	+0·4	+0·6	—0·1	+0·4	+1·4	—0·5	—1·1	—1·7	—0·1
Colombo . . .	+0·2	—0·4	—0·3	—0·4	—0·2	—0·5	+0·1	—1·4	+0·5	—0·3	—1·6	—1·8	—0·5
Jaffna	—0·9	—2·3	—1·4	—0·3	—0·9	—0·3	—0·8	+0·5	+0·2	—2·3	—2·2	—2·1	—1·1
Trincomalee . . .	+0·1	—0·5	0	+0·5	—0·8	—1·5	—1·1	—0·8	+0·8	—0·1	—1·1	—0·8	—0·4
Batticaloa . . .	—0·2	—2·0	—0·5	—0·5	+0·1	—0·4	+0·2	+1·2	+0·3	—1·4	—2·4	—1·8	—0·6
Hambantota . . .	+0·1	—1·4	—0·7	—1·1	—1·0	—0·5	—0·6	+0·3	+0·5	—0·3	—1·2	—0·8	—0·6
Galle	—0·6	—1·2	—0·4	—0·2	—0·3	+0·1	+0·3	+0·4	+0·6	—0·6	—1·3	—1·2	—0·4
Kandy	—0·4	—2·0	—0·1	—0·3	+0·6	+0·2	+0·4	+0·3	+0·4	—0·8	—1·4	—1·1	—0·4
Newera Eliya . . .	—0·7	—1·0	—1·5	—0·4	+0·3	—1·0	+0·3	—0·5	—0·3	—0·9	—0·2	—1·3	—0·6
Akyab	+0·3	—1·5	+0·1	—0·5	—1·0	—0·4	0	—0·8	—0·4	+1·0	—0·8	—0·5	—0·4
Thayetmyo . . .	?	?	—0·2	—0·6	—1·4	—0·4	—0·2	+0·2	0	+0·4	—1·7	—1·8	?
Tounghoo . . .	—1·5	—1·2	—0·8	?	?	—1·0	—0·8	—0·3	—1·3	+0·4	—1·6	—1·9	?
Bassein	—1·0	—0·1	+0·3	0	+0·5	—0·7	—0·2	+0·5	?	?	?	—1·6	?
Diamond Island . .	—1·2	—1·2	—1·1	—1·3	—0·4	—1·1	—0·7	—0·4	—0·8	+0·5	—1·5	—1·3	—0·9
Rangoon . . .	—0·9	—0·2	+0·1	—0·7	—0·6	0	—0·8	+0·1	—0·3	+0·9	—0·5	—1·2	—0·3
Moulmein . . .	—1·3	+0·8	—0·3	—0·2	—0·4	—0·6	—0·2	+0·3	—0·3	+0·8	—0·9	—0·8	—0·3
Mergui	—0·4	+1·1	0	—0·4	—0·4	—0·5	—0·6	—0·7	—0·8	—0·6	—0·7	—1·6	—0·5
Port Blair . . .	+0·2	+0·1	0	+0·4	+0·9	+0·1	—0·6	+0·1	—0·7	+0·9	—0·4	—1·2	0
Nancowry . . .	+0·2	—0·4	—0·8	+0·1	+1·4	+0·8	?	?	?	?	?	?	?

TABLE X.—*Geographical Summary of the differences of Table IX.*

AREAS.	Station.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
North West Himalaya.	6—8	—1·9	—1·1	—2·1	+1·8	+0·9	+0·1	+0·8	+0·7	+0·4	—0·9	—2·7	—3·1	—0·6
Sikkim Himalaya and Nepal.	2—3	—0·9	—1·2	—0·8	—0·3	+0·4	0	+0·5	—0·1	0	—0·8	—1·1	—1·7	—0·5
Punjab plains .	9	+1·0	—1·9	—1·3	+2·6	+0·7	+1·5	+0·4	+2·6	+0·2	+0·1	—1·4	—0·5	+0·3
Gangetic plains .	11—12	+0·4	—2·9	—1·5	+1·2	+0·9	—0·6	0	+1·7	+0·6	0	—1·6	—2·1	—0·3
Western Rajputana, Sind, Cutch, Gujarat, &c.	9	—0·2	—1·2	—2·3	+2·1	—0·3	+1·0	—0·9	+1·5	—0·9	—0·5	—1·9	—2·0	—0·5
Eastern Rajputana and Central India.	9	+0·2	—2·4	—1·6	+1·7	+0·1	—0·5	—0·6	+2·4	—0·2	—0·9	—1·9	—3·3	—0·6

TABLE X.—*Geographical Summary of the differences of Table IX*—concluded.

AREAS.	Station.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Nerbudda valley .	3	+1·4	—0·2	0	+2·0	+1·6	—1·4	—0·3	+1·5	—0·7	—1·3	—2·1	—6·1	—0·5
South Behar and Chutia Nagpur.	2	—0·4	—2·9	—1·3	+2·5	+3·9	—1·2	—0·5	+1·2	+0·7	+1·2	—1·4	—2·7	—0·1
Lower Bengal .	7	—1·0	—2·9	—1·1	—0·6	+0·5	—0·6	—0·2	—0·3	0	+0·2	—1·8	—2·5	—0·9
Assam and Cachar	2—3	0	—1·5	0	+0·2	—1·3	—0·1·	+1·1	+0·1	+0·3	0	—0·5	—1·6	—0·3
Orissa and Sambalpur.	3	+0·4	—0·8	0	+0·3	+1·4	—1·2	—0·5	+0·4	0	+0·1	—2·2	—4·4	—0·5
South Central Provinces and Berar.	11	+0·2	+0·7	—0·5	+1·6	+2·0	—1·8	—0·2	+1·5	—1·2	—0·8	—1·7	—4·3	—0·4
Konkan . .	4	0	—0·5	—1·5	—0·3	+0·1	—1·1	—0·5	+0·3	—1·2	—1·0	—1·8	—2·7	—0·9
Malabar Coast .	2	+0·1	+0·2	0	—0·7	+0·3	+0·5	—0·1	+0·5	+1·0	—0·7	—1·1	—1·6	—0·1
Deccan, Hyderabad, Mysore, &c.	8—9	—1·0	0	—1·1	0	+0·9	—1·1	—0·4	0	—0·5	—1·0	—2·1	—3·7	—0·8
East Coast and Carnatic.	8	—0·1	—0·7	+0·1	—0·1	+0·4	—0·4	—0·8	—0·1	+0·7	—1·3	—2·1	—2·2	—0·6
Ceylon . . .	7	—0·2	—1·4	—0·5	—0·3	—0·3	—0·4	—0·2	+0·1	+0·5	—0·8	—1·6	—1·4	—0·5
Arakan and Pegu .	6—7	—0·9	—1·1	—0·5	—0·8	—0·6	—0·7	—0·4	—0·2	—0·5	+0·5	—1·0	—1·4	—0·6
Tenasserim . .	2	—0·8	+1·0	—0·2	—0·3	—0·4	—0·5	—0·4	—0·2	—0·5	+0·1	—0·8	—1·2	—0·3
Bay Islands . .	1—2	+0·2	—0·2	—0·4	+0·3	+1·2	+0·5	—0·6	+0·1	—0·7	+0·9	—0·4	—1·2	0

January.—In the preceding month, the temperature had been unusually high all over Northern India, and even more so on the North-Western Himalaya than on the plains. In the Report on the Meteorology of 1882, this was attributed to the absence of rain, combined with the prevalence of southerly winds. The dry weather lasted through the first few days only of January. On the 10th, the usual cold weather showers set in, with a great fall of temperature; and, during the remainder of the month, frequent snow storms occurred in all parts of the hills. Especially from the night of the 24th to that of the 27th, snow fell almost without intermission, and down to levels at which it has rarely been known, and rain was general on the plains. The coolness which was the consequence of this rain and snow in the latter part of the month, in a great measure counterbalanced the high temperature prevailing before the rainfall, and in Beloochistan and on the outer North-Western Himalaya, where the former effect was greatest, the mean temperature of the month was between 2° and 3° below the general average of past years. But at Leh this was not the case, and in the Central Himalaya the reduction of temperature was less than in the more westerly part of the range.

In the Punjab, the excess of temperature in the early part of the month predominated, to the average amount of 1°, and to about half that amount in the North-Western Provinces. Eastwards, the excess disappeared; and, throughout Bengal, the mean temperature of the month was less than usual. In Assam it was about the average; but in Orissa and all through the Central Provinces it was more or less above it, and slightly so in Gujarat, and Cutch. In Western Rajputana and Central India there was, on the other hand, a slight and not universal depression, and this was also the case in the Deccan, and a great part of the Peninsula and Ceylon. In Burma the depression was somewhat greater, amounting generally to about 1°.

Throughout Northern India, except at some stations in Bengal, the lowest temperatures were on the last days of the month, and these were in general surpassed by those of the earlier days of February. This was also the case throughtout the Central Provinces and Berar, in the Konkan and North Deccan, but further south the lowest temperatures generally fell about the end of the first week.

February.—The snow and rain, at the end of January, produced a depression of temperature, which culminated in the first week of this month; and, as these falls were repeated subsequently on the hills, the general temperature of the month was considerably below the average, throughout Northern India. On the Himalaya, indeed, (save at Murree) and in Beluchistan, the abnormal depression was trifling (under —1°); but, on the plains of the Punjab, it amounted to between —2° and —3° at Lahore, Rawalpindi, Ludhiana, and Sirsa; and on the average of the province, to nearly —2°. Further east, on the Gangetic plains, it was even greater, *viz.*, —4° at Meerut and Gorakhpur, —3·9° at Allahabad, —3·5 at Roorkee and Lucknow, and —2·9° on the average of the province; and it was greatest in Lower Bengal, where it amounted to —4·1° at Saugor Island and to —3·2° on the mean of all stations. In Assam it was only about half as great. To the south of the Ganges, as far as the Nerbudda Valley, the unusual coolness was nearly as striking as to the north of that river; and in the desert region of Western India but little less than in the Punjab. But south of the Satpura range it disappeared, and in Orissa, the Central Provinces and Berar, and on the plateau of the Deccan, the temperature was slightly excessive, exceeding 1° at Sambalpur, Raipur, Chanda, many of the Berar stations, Poona and Secunderabad. In the Konkan indeed there was a slight depression, greatest at Surat and diminishing and disappearing southwards. The region over which the depression prevailed is precisely that swept by the northerly winds, which are the outflow of the air from Himalaya and the northern plains.

On the east coast and Carnatic, the region of the north-east monsoon, there was an abnormal depression, averaging —0·7°. In Ceylon it was twice as great; but to the east of the Bay, in Tenasserim and the Andamans, there was a small excess, while Pegu and Arakan shared the prevailing coolness.

The lowest temperatures of the month and in the most cases of the year in Northern India, were registered on the first few days. The following are some selected instances:—

Station.	Date.	Minimum temperature.	Station.	Date.	Minimum temperature.
Quetta	Feb. 1st	15·1	Darjeeling	Feb., 1st	19·9
Leh	„ 1st	3·3	Purneah	„ 6th	43·3
Dera Ismail Khan	„ 1st	28·0	Patna	„ 7th	42·9
Peshawar	„ 1st	29·2	Hazaribagh	„ 3rd	41·9
Murree	„ 19th	20·3	Berhampore	„ 7th	45·4
Rawalpindi	„ 6th	30·9	Burdwan	„ 4th & 6th	44·7
Lahore	„ 1st & 6th	35·0	Jessore	„ 4th	43·1
Sirsa	„ 2nd	32·9	Calcutta (Alipore)	„ 8th	46·2
Simla	„ 1st	19·7	Saugor Island	„ 3rd	49·7
Roorkee	„ 1st & 2nd	37·0	Cuttack	„ 4th & 6th	55·4
Meerut	„ 2nd	33·7	Nagpur	„ 3rd	50·1
Bareilly	„ 7th	38·6	Seoni	„ 2nd	43·7
Lucknow	„ 2nd	38·8	Saugor	„ 2nd	40·1
Allahabad	„ 7th	38·6	Sutna	„ 7th	38·3

March.—Falls of snow were repeated on the hills, and rain was frequent on the plains during the first half of the month, and this period was characterized by a depression of temperature, as general as that in February, and on the whole not much less in degree. On the North-Western Himalaya, and at Quetta and Leh, it considerably exceeded that of the previous month, and this was also the case in the western desert tract and Sind, where it averaged —2·3°; but it was less in the Punjab, on the Gangetic plain, on the plateau of Eastern Rajputana and Central India, and especially in Lower Bengal, where the averages were respectively —1·3°, —1·5°,— 1·7°, and —1·3°; and disappeared in Assam. In the Central Provinces south of the Satpuras and Berar, the slight excess of the previous month had disappeared at nearly all stations, and in the Konkan the deficiency had increased to —1·5°, and on the plateau of the Peninsula to —1·2°. It was less in Ceylon, and in the Carnatic the temperature had become normal. In Burma and at the Bay Islands there was a slight but general depression.

April.—April was a dry month and the temperature rose rapidly in consequence, so that throughout Northern India, excepting only in Bengal, Assam, and on the Central Himalaya, the mean temperature of the month ranged more or less above the average. On the North-Western Himalaya the excess amounted to 2°, and at Quetta to 2·5°. On the plains of the Punjab it averaged 2·6°, and at Sialkot and Ludhiana amounted to between 3° and 4°. On the Gangetic plain it diminished eastwards from Agra, where it reached 3°, to Patna where it was only 0·5°, and beyond which it disappeared. In Bengal there was still a slight depression outstanding from the previous month. In Western Rajputana and Sind, it varied from 0·6° at Kurrachee to 3·0° at Deesa, and averaged 2·1°, and in Eastern Rajputana and Central India amounted to 1·7°. In Chutia Nagpur, Orissa, and the Central Provinces and Berar, a similar excess prevailed, greatest in South Behar and Chutia Nagpur; but it did not extend much to the south of Poona on the west, though it obtained slightly at Secunderabad and Bellary. On the Konkan and Malabar coasts, in the Carnatic and Ceylon, the temperature was slightly below the average. Such was also the case in the Burmese peninsula, but not at the Bay Islands.

May.—The first two-thirds of May was also rainless, the heat become excessive, and the dryness of the air in North-Western India was such as is unusual even at this season. But a few days after the middle of the month, rainy weather set in in Northern India, and a fresh fall of snow took place on the outer Himalaya down to comparatively low levels. The great heat of the earlier part of the month was, therefore, in a great measure counterbalanced by the coolness of the latter part, but, except in Rajputana, Gujarat and Kutch, and also in Assam and Cachar, the compensation was not complete; and in all the peninsular region about the Tropic of Cancer, *viz.*, the Nerbudda Valley, Chutia Nagpur, the Central Provinces, Berar and Orissa, the outstanding excess amounted to from 1·5° to 4° at different stations. In the remainder of the peninsula, the excess was small, averaging less than 1°, and equally so in the Punjab, the Gangetic plain, and Bengal. In Ceylon and Burma there was a slight depression, as in April; but at the Bay Islands there was a decided excess, amounting to 1·4° at Nancowry.

The highest temperatures in Northern India were those recorded just before the

the change of weather which took place after the 20th, of which the following are examples. In the Punjab these were surpassed by the June maxima.

Station.	Date.	Maximum temperature.	Station.	Date.	Maximum temperature.
Mooltan . . .	20th	111·9	Allahabad . .	19th	116·4
Dera Ismail Khan .	20th	113·5	Benares . . .	19th	114·6
Rawalpindi . .	20th	107·5	Patna . . .	7th	110·0
Sirsa . . .	20th	116·2	Gya . . .	19th	115·8
Lahore . . .	20th	112·5	Hazaribagh . .	12th	108·3
Ludhiana . . .	19th	114·3	Berhampore . .	7th	105·2
Delhi . . .	19th	116·6	Calcutta . . .	25th	102·0
Roorkee . . .	18th & 19th	112·5	Cuttack . . .	11th	109 4
Meerut . . .	20th	111·6	Sambalpur . .	21st	116·1
Bareilly . . .	19th	113·2	Raipur . . .	22nd	114·2
Agra . . .	20th	116·5	Nagpur . . .	20th	117·7
Lucknow . . .	19th	115·0	Amraoti . . .	20th	114·3
Jhansi . . .	21st	115·0	Bickaneer . . .	20th	115·1
			Pachbudra . .	20th	119·5

June.—The greater part of this month was fine, with occasional dust storms or thunder storms in North-Western India, but in Bengal cloudy from the beginning, and the monsoon rains set in in that province on the 13th and extended inland as far as Behar. On the Bombay side, the monsoon did not set in till 10 or 11 days later. In the Punjab and in Western Rajputana, Gujarat, &c., the temperature was consequently high, averaging 1° to 1·5° above the normal temperature of the month; but elsewhere, except on the Himalaya, the variation was more or less in the opposite direction, the depression exceeding 1° in the Nerbudda Valley, Chutia Nagpur, the Central Provinces, the Konkan and Deccan; and being greatest in the Central Provinces and Berar. On the Malabar coast and at the Bay Islands the temperature was half a degree above the average.

As already mentioned, the highest June temperatures at many of the Punjab stations and also in Sind, exceeded those of May. This was the case at the following stations:—

Stations.	Date.	Maximum temperature.	Stations.	Date.	Maximum temperature.
Quetta . . .	27th	102·3	Sialkot . . .	12th, 24th & 25th	114·9
Leh . . .	30th	92·2	Lahore . . .	23rd	115·0
Dera Ismail Khan .	26th & 27th	117·5	Ludhiana . .	11th	114·8
Peshawar . .	24th	116·5	Sambhar . . .	10th	112·7
Murree . . .	24th	90·9	Jacobabad . . .	10th	118·2
Rawalpindi . .	25th	114·0	Hyderabad . .	1st	116·2

. That registered at Jacobabad on the 10th of the month, *viz.*, 118·2, was the highest recorded in India during the year, excepting that in May at Pachbudra, if indeed this last be quite trustworthy. It was one or two degrees lower than some recorded in previous years at the same station.

July.—During the first half of July, rain was frequent and heavy on the North-Western Himalaya; and in the Eastern Punjab there were heavy local showers, but no continuous rain; but over the greater part of the country, there was rain of the usual character during the first 20 days. On the Himalaya and in the Punjab the temperature was slightly above the average, but everywhere else, except in Assam, it was either about the average or a little below it; the mean difference, except at a few individual stations, nowhere amounting to one degree. With the drought that set in, all over North-Western India and far down Western India and even into the Deccan, in the latter part of the month, the temperature rose and remained high during the greater part or the whole of August.

August.—Except in Bengal and on the Central Himalaya, this was a dry month, the drought, which had set in in the latter part of July, lasting nearly to its close. Consequently, the temperature was unduly high over the greater part of India, the average excess amounting to 2·6° in the Punjab, 2·4° in Eastern Rajputana and Central India (the tracts that suffered longest and most severely), and between 1° and 2° in the Gangetic plain, Western Rajputana, Gujarat, &c., the Nerbudda Valley, Chutia Nagpur, and the Central Provinces and Berar. The Burmese peninsula being unaffected by the drought, a slight depression of temperature was maintained, but less than in the previous months.

September.—In the early part of September, rain was very heavy and general, but it ceased after the 10th in the Punjab, and after the 18th in the North-Western Provinces, and the latter part of the month, being dry, was also unduly warm. On the average of the whole month, temperature was slightly excessive on the North-Western Himalaya, in the Punjab and the North-Western Provinces, but deficient in Gujarat and Western and Central India generally, where the rains continued later. In Southern India and Ceylon, also, it exceeded the average, but in Burma the depression was somewhat greater than in the preceding month.

October.—The rains ceased in Bengal before the middle of the month, and set in about the same time in the Carnatic. In general, the temperature was more or less below the normal degree. But there was a marked exception in Chutia Nagpur, and only less pronounced in Orissa and at some stations in Eastern Bengal. On the Central India plateau and in the Nerbudda Valley, the depression exceeded 1°, and also in the Carnatic; and amounted to about 1° in the Konkan, and throughout the interior of the peninsula. In a diminished degree, it extended to Ceylon, but in the Burmese peninsula and at the Bay Islands there was a certain excess of temperature.

November.—In Northern India, the early part of November was dry and warm; but after the first week, some heavy falls of snow took place in the North-Western Himalaya, and these were immediately succeeded by a great fall of temperature over the whole of Northern India, the effect of which lasted up to the end of the year. On the North-Western Himalaya, there was, on the mean of the month, a depression of nearly —3°, and over the whole of India, one of —1° to —2° on an average. It amounted to —2° over nearly the whole of the peninsula, being least on the Malabar coast; and even in Ceylon it was not

less than —1·6°. In Burma it did not exceed —1° and in Tenasserim —0·8°, and diminished at the Bay Islands to —0·4°.

December.—Notwithstanding that this month, like that which preceded it, was rainless over the greater part of Northern India, the abnormal depression of temperature, which I attribute to the heavy Himalayan snowfall of November, was even greater than in November. On the Himalaya it amounted to —3·1° on the general average of the stations. In the Punjab it was less than elsewhere, being only —0·5°, but on the Gangetic plain it exceeded —2° and in Lower Bengal, where there were one or two rainy days in the beginning of the month, it amounted to —2·5°. It was still greater on the Central Indian plateau *viz.* —3·3°, and was at its maximum in the Nerbudda Valley —6·1°. In the north of the peninsula, in the Central Provinces, Berar and Orissa, it exceeded —4°, and varied between —2·5° and —4·5°, at stations on the Deccan and Mysore plateau. In the Carnatic, it amounted to —2·2° on an average, and where least, *viz.*, on the Malabar, coast, was not less than—1·6°. It was nearly as great in Ceylon, and to the east of the Bay in Arakan, Pegu, Tenasserim.

On the whole, 1883 was the coolest year in India that has occurred since the temperature of the whole country has been systematically registered, *i.e.*, since 1874. In April, May, and August, all of which were dry months, the temperature ranged above the average, in all others below it, and conspicuously so in November and December. The abnormal depression of the last month was greater and more general than that of any previously recorded in our registers. The monthly anomalies, on the mean of all the Indian, Burmese, and insular stations, were as follow :—

January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
—0·2	—1·2	—1·1	+0·8	+0·5	—0·4	—0·2	+0·9	—0·2	—0·5	—1·7	—2·5

and the mean anomaly of the twelve months —0·48°, which, as already remarked, is greater than that of any year yet recorded. The temperature variations of the last nine years as deduced in the annual reports are as follow :—

Years.	1875.	1876.	1877.	1878.	1879.	1880.	1881.	1882.	1883.
Number of stations .	72	72	74	74	70	106	110	113	122
Mean anomaly . .	—0·29°	—0·08°	+0·17°	+0·62°	—0·13°	+0·13°	—0·01°	—0·11°	—0·48°
Progressive variation .	...	+0·21°	+0·25°	+0·45°	—0·75°	+0·26°	—0·14°	—0·10°	—0·37°

In the Report for 1879 (page 40) it was remarked that, up to that time, the progressive variation of the annual mean temperature had conformed to that found by Gautier and Köppen for land stations in the tropics generally, *viz.*, that it had increased steadily as the sun-spot period approached its minimum. It is therefore of great interest to find that, with the exception of the opposite oscillation between 1879 and 1880, the subsequent variation has been equally confirmatory of the conclusion of these authors; since, during the last three years, in which the number of sun-spots has been increasing, the mean annual temperature has steadily declined.

The general coincidence of this variation of the mean temperature of the last four years with that of the insolation excess temperature, already noticed at page 17, is very striking, but when we compare the anomalies of the same two elements in the several months of 1883, the coincidence fails entirely, and precisely the same result was noticed in comparing the corresponding anomalies of the year 1882; (see Report, p. 47). To render this obvious, the monthly anomalies of temperature and insolation are juxtaposed in the following table, and I have also added those of nocturnal radiation :—

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
Air temperature . . .	—0·2	—1·2	—1·1	+0·8	+0·5	—0·4	—0·2	+0·9	—0·2	—0·5	—1·7	—2·5
Insolation	—0·3	0	0	—1·4	—1·0	—0·8	—1·2	—1·2	—1·8	—1·3	—1·5	—1·8
Nocturnal radiation . . .	—0·6	+0·5	0	+0·6	+0·3	—0·1	—0·2	+0·2	—0·6	—0·5	—0·1	+0·4

From what has been said in the previous description, and indeed as a general conclusion from the facts set forth and discussed at length in previous reports, more particularly in that for 1879, it is obvious that the air-temperature of any short period, apart from the normal influence of season, is much more affected by cloud, the evaporation following rainfall, and the direction of the prevailing wind, than upon the direct intensity of the sun, and there is, therefore, no necessary inconsistency between the two results above indicated; since, in taking the mean temperature of a whole year, the former fugitive effects are, to a considerable extent, eliminated, and, moreover, the duration of sunshine, which is much more influential on air-temperature than its momentary intensity, affects only in a minor degree the mean value of the maximum insolation temperatures. The sun thermometer may mark as high a temperature on a day of one or two hours only of bright sunshine, as on one that is cloudless from sunrise to sunset, but the mean temperature of the latter will almost certainly be higher than that of the former.

It is, then, not improbable that the somewhat striking variation of temperature, from year to year, shewn by the Indian registers since 1875, inclusive, may be mainly the effect of a coincident variation of the insolation, such as is shewn by the sun-thermometer registers of the last four years; but it would still remain an open question whether the latter is an indication of a similar variation in the sun's energy, or of that of some absorptive medium interposed between the sun and the terrestrial surface.

In conclusion, it may be noticed that the two most northerly stations in the table, *viz.*, Leh and Bushire, had a mean annual temperature above the average, as also did Zanzibar. Aden, on the other hand, had a mean temperature below the average of the last few years, and that of Mauritius also is below the average of many years, as is shewn in the following table, for which I am indebted to the kindness of Mr. Meldrum :—

Comparative Table of Mauritius Temperature.

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
1883	78·7	78·2	78·0	76·3	73·3	71·2	69·3	69·3	69·8	71·1	74·1	76·7	73·8
Average . . .	79·2	78·9	78·1	76·7	73·3	70·3	68·8	69·1	70·3	72·5	75·3	77·9	74·2
1883, Difference . .	— 0·5	— 0·7	— 0·1	— 0·4	0	+ 0·9	+0·5	+ 0·2	— 0·5	— 1·4	— 1·2	— 1·2	—0·4

ATMOSPHERIC PRESSURE.

With the exceptions noted in the footnote[1] below, all the barometers, the registers of which are here given, are mercurial barometers on Fortin's principle; and, excepting those in Ceylon and some in Madras,[2] all have been carefully compared, either directly or indirectly, with the Calcutta standard. Those in Bombay, Rajputana (excepting at Ajmere, Sambhar, and Pachbudra), Central India (except at Nowgong and Sutna), and Berar, have been compared by Mr. F. Chambers with the Bombay standard, which, according to a lengthened comparison with two verified barometers, sent from Calcutta, reads ·012 inch lower than the old Calcutta standard. All the registers (except those of some of the Madras stations, which exceptions do not include Vizagapatam, Mangalore, and Mercara,) have been corrected to the readings of the latter instrument. The Ceylon barometers have been verified at Colombo, by comparison with a standard tested by Messrs. Negretti and Zambra, who compare with the standard at Kew. A correction of +·011 inch has been applied to the registers, therefore, to bring them up to the values of the Calcutta standard. Those of Madras, with the exceptions above noted, are corrected to the Madras observatory standard.

With a view to rendering the barometric data, published in previous reports, as far as possible trustworthy and comparable with those now and henceforth to be registered,

[1] Casella's observatory barometers on the Kew principle (*i.e.*), with a contracted scale to compensate changes of level in the cistern, were in use at the following stations:—

Aden.	Jhansi.	Saugor.	Akyab.
Bushire.	Gya (from 5th June).	Nowgong.	Bassein.
Mooltan.	Chittagong.	Sambhar.	Tounghoo.
Ludhiana.	False Point (from 9th January).	Pachbudra.	Thayetmyo.
Sialkot.		Gopaipore.	
Lucknow.	Hoshangabad.	Mangalore.	
Gorakhpur.	Seoni.	Mercara.	

At Bombay, Calcutta, Madras, and Rangoon, large Newman's standards, with adjustable scales and tubes of more than 0·5" diameter.

Casella's small observatory standards on Fortin's principle, with tubes of 0·4inch in diameter, were in use at the following stations:—

Zanzibar.	Allahabad.	Hazaribagh.	Buldana.
Dera Ismail Khan.	Benares.	Berhampore.	Sutna.
Peshawar	Sibsagar.	Burdwan.	Ajmere.
Murree.	Dhubri.	Jessore.	Kurrachee.
Rawalpindi.	Silchar.	Dacca.	Moulmein.
Lahore.	Darjeeling.	Saugor Island.	Diamond Island.
Delhi.	Purneah.	Cuttack.	Mergui.
Meerut.	Durbhunga.	False Point (from 30th March).	Port Blair.
Bareilly.	Patna.		Nancowry.
Agra.	Gya.	Nagpur.	

At stations in the Central Provinces, Central India, Rajputana, and Bombay, other than those named above, portable mountain barometers on Fortin's principle, with tubes about 0·25 inch diameter, are used.

[2] The instruments at the following Madras stations have been compared, either directly or indirectly with the Calcutta standard, and their readings are corrected to the latter:—

Vizagapatam; Mangalore, Mercara.

I here give a list, in part repeated from the last year's report, of all those known or believed to be erroneous, together with the needful corrections, where these have been ascertained. The following are certainly erroneous and must be rejected :—

Mooltan, 1875 and 1876.
Simla, from January 1876 to February 1877, and untrustworthy up to the end of April 1880.
Rawalpindi, all up to the end of 1881 untrustworthy.
Chakrata, January to August 1875, and very doubtful up to the end of 1876.
Jhansi, January to April 1875.
Benares, February 1876.
Sambalpur, 1876.
Saugor, Central Provinces, all published up to December 1879; also January, March, May, July, and September 1880, and February and April 1881.
Buldana, 1876.
Amraoti, 1875.
Chikalda, from November 1879 to August 1881.
Bickaneer, up to the end of 1879.
Mount Abu, January 1878, and from April to December 1882.
Pachbudra, all published up to 1881 inclusive.
Malegaon, either all prior to April 1881, or all subsequently; at present doubtful.
Trincomallee, 1877.
Moulmein, 1878 and 1879.
Tounghoo, 1882.

And the following corrections are to be made to the tables published in previous reports :—

Quetta, from 27th March to end of 1881	—0·005
Simla, from 14th October 1880 to end of 1881	
Mussooree, from 3rd February to ditto	
Paori, from 2nd ditto to ditto	
Gorakhpur, from October 1877 to December 1879	+0·016
Sambalpur, from July to December 1882	+ ·029
Raipur, from 22nd October to end of 1881	—0·005
Hoshangabad, from June to December 1880	+0·034
Ditto, from June to December 1882	+0·008
Pachmarhi, from 16th July 1880 to December 1880	—0·005
Sutna, from 30th March to ditto	
Deesa, from the 10th April to the end of 1877 and from the 16th May 1879 to 14th April 1880	—0·050
Thayetmyo, from 24th January to 14th October 1881	—0·005
Bassein, a correction increasing from 0 in January 1877 to a maximum in December 1879 of	+0·006
Rangoon, a correction increasing from 0 in January 1876 to a maximum in December 1879 of	+0·007
Mergui, from the beginning of the registers in September 1877 to December 1879	+0·021

In addition to the above, it is to be noticed that there are inconsistencies in the registers of former years, at the following stations, which remain to be explained :—

Mount Abu, 1882, with those of previous years.
Buldana, 1882 and 1883, ditto
Newera Eliya, from July 1873 to January 1879, with those before and after.

In all cases, except those of Dehra and Bickaneer, the barometers are kept in a masonry building, to protect them as much as possible from changes of temperature. At these two stations alone, they are suspended in the thermometer sheds. The elevations of all barometers have been ascertained with such accuracy as was possible. In the large majority of cases they have been referred to datum levels, determined by the Great Trigonometrical Survey of India; in Northern India, for the most part, by lines of spirit levels, connected with the main line of levels between Kurrachee and Calcutta. Elsewhere, the elevations of the Great Trigonometrical Survey stations, measured trigonometrically, or those of the lines of railway, have been adopted as reference data; only those of Pachbudra, Paori, and Pithoragarh have been barometrically determined. For some further details the reader is referred to Table I, pages 5-8.

Table VII (Appendix) gives an abstract of the barometric observations of 1882, *viz.*, the monthly means of the readings at each hour of observation and that of the day, the monthly mean diurnal range (between 10 A.M. and 4 P.M.), the highest and lowest readings in each month, and in the year; and the extreme monthly and annual ranges. The mean pressures have been obtained in the following manner:—

(*a*)—At Calcutta (Alipore), the means of the hourly measurements of the barograph trace, reduced to the corresponding values of the old Calcutta standard.

(*b*)—At Bombay (Colaba) and at Leh (from September) the means of the four readings, at the same hours as furnish the data for temperature means, with additive corrections, deduced from the hourly readings at the same observatories in past years.

(*c*)—At Lahore, Jeypore, Allahabad, Saugor Island and Vizagapatam, the means of the four readings at 4h., 10h., 16h., and 22h., without further corrections.

(*d*)—At Leh (from January to August), at stations in the North-Western Provinces (excepting Mussooree and Allahabad), Ajmere and Sambhar in Rajputana, and stations in Bengal and Assam (except Calcutta, Saugor Island, and Dhubri), the means of the 10h. and 16h. observations, corrected by range factors, derived from the six-hourly readings at the same or neighbouring stations in past years. In the latter cases, the factors are taken from the same stations as in the case of temperature means (see *ante*, page 30).

(*e*)—At the four Bombay stations, Belgaum, Poona, Deesa and Kurrachee, the means of the 10h. and 16h. observations, with additive corrections, derived from the hourly observations of the same stations in past years.

(*f*)—At the stations in Madras, including Bangalore and Secunderabad, (but excepting Vizagapatam, Mercara, Kurnool, and Mangalore) the means of the three readings at 10h., 16h. and 22h., corrected by means of range factors, derived from the Madras hourly observations in past years. At Kurnool the means of the 10h. and 16h. observations only similarly corrected.

(*g*)—At all other stations the crude means of the 10h. and 16h. observations without correction.

Table VIII (Appendix) gives the mean pressure of each month, reduced to sea-level values, from the elevations given in Table I (*ante*), at the temperatures obtained by taking the means of those in Tables V and VI of the Appendix. The readings of the hill stations are not included in this table. The isobars on the charts, plates II to IV, are laid down from these values.

Table XI, on the next page, gives the average monthly annual pressure at 123 stations, *viz.*, all that have furnished trustworthy readings, corrected to the Calcutta, Madras, or Ceylon standards, during three years and upwards. In instances in which,

during the period included, there has been any change in the elevation of the barometer, a correction has been applied to the former means, to bring all to their equivalent values at the actual levels. These cases are not numerous, nor, as a rule, are the changes more than a very few feet.

The table gives, for nearly all stations, the average pressure of the last nine years, and also, in the case of the Bengal stations and some of those in the North-Western Provinces, the Punjab, Madras, and other provinces, those of longer periods. This double form has been adopted, because the high pressures which prevailed during two years from the spring of 1876 to the autumn of 1878, brought prominently to notice in the reports for 1877 and 1878, render the averages of a large number of stations, for which more prolonged registers are not available, somewhat too high, in comparison with those deduced from longer periods. Some of the stations, for which nine years' averages are given, have not actually furnished registers for the whole period. But, as there exist, in nearly all parts of the country, some stations, from which the complete series is forthcoming, it has been possible, in the case of the defective registers, to interpolate values for the deficiencies; in computing which, the nearest stations, in all directions, have been taken into account, with weights proportional to their respective distances, where there is much variation in this respect.

Tables XII A and B below shew the differences of the means of 1883 and the above averages, respectively.

Table XIII gives a geographical summary of the anomalies of Table XIIA, uniformly with the table of temperature anomalies (Table X).

TABLE XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar . .	6—8	29·873	29·872	29·875	29·903	29·980	30·059	30·078	30·060	30·039	29·986	29·921	29·896	29·962
Aden . . .	3—4	29·963	29·910	29·875	29·799	29·713	29·618	29·580	29·594	29·685	29·830	29·903	29·963	29·786
Mauritius . .	22—23	29·944	29·924	29·970	30·009	30·083	30·167	30·204	30·210	30·196	30·136	30·069	29·999	30·076
Bushire . .	5—6	30·114	30·044	29·969	29·845	29·712	29·533	29·452	29·507	29·675	29·893	30·029	30·085	29·822
Quetta . .	3—5	24·678	24·630	24·630	24·596	24·544	24·435	24·399	24·454	24·542	24·683	24·721	24·704	24·585
Leh . . .	8—9	19·640	19·590	19·672	19·675	19·690	19·643	19·605	19·634	19·691	19·730	19·716	19·699	19·665
Mooltan . .	9	29·636	29·586	29·473	29·335	29·199	29·038	29·030	29·108	29·238	29·440	29·589	29·654	29·360
Dera Ismail Khan .	9	29·482	29·433	29·339	29·191	29·054	28·891	28·889	28·956	29·090	29·286	29·436	29·507	29·213
Peshawar . .	9	28·953	28·912	28·824	28·685	28·549	28·383	28·368	28·442	28·586	28·779	28·906	28·968	28·696
Murree . .	9	23·878	23·840	23·857	23·824	23·790	23·720	23·699	23·747	23·829	23·916	23·924	23·916	23·828
Rawalpindi . .	9	28·298	28·254	28·189	28·078	27·977	27·841	27·833	27·963	28·032	28·191	28·291	28·328	28·101
Sialkot . .	9	29·204	29·131	29·048	28·912	28·796	28·652	28·662	28·730	28·846	29·023	29·145	29·202	28·946
Lahore .	9	29·294	29·249	29·142	29·002	28·880	28·738	28·747	28·816	28·936	29·116	29·248	29·313	29·040
	10—11	29·298	29·249	29·142	29·015	28·886	28·737	28·748	28·822	28·935	29·115	29·269	29·320	29·045

TABLE XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*—contd.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Ludhiana	9	29·221	29·171	29·070	28·930	28·821	28·684	28·688	28·758	28·879	29·048	29·174	29·232	28·973
Simla	9	23 318	23·285	23·302	23·288	23·249	23·180	23·152	23·201	23·280	23·357	23·349	23·342	23·275
Delhi	9	29·310	29·258	29·151	29·015	28·905	28·775	28·778	28 850	28·958	29·138	29·264	29·327	29·061
Sirsa	9	29·380	29·326	29·219	29·077	28·958	28·826	28·823	28·893	29·016	29·196	29·323	29·387	29·119
Chakrata	9	23 250	23·227	23·245	23·235	23·199	23·133	23·108	23·155	23·226	23·301	23·308	23·297	23·224
Mussooree (*Saint Fidelis*).	3—6	24·307	24·293	24·294	24·254	24·219	24·127	24·113	24·147	24·223	24·314	24·335	24·356	24·249
Dehra	9	27·743	27·706	27·635	27·542	27·467	27·349	27·353	27·410	27·499	27·649	27·737	27·768	27·572
Paori	9	?	?	?	?	?	24·759	24·756	24·813	24·853	24·977	25·026	?	?
Roorkee	9	29·114	29·068	28·962	28·835	28·742	28·609	28·623	28·690	28·789	28·961	29·076	29·129	28·883
	16—17	29·117	29·060	28·968	28·850	28·742	28·616	28·631	28·694	28·794	28·960	29·091	29·140	28·889
Ranikhet	9	24·111	24·086	24·083	24·059	24·015	23·935	23·928	23·959	24·027	24·110	24·142	24·136	24·049
	10—11	24·111	24·085	24·079	24·062	24·011	23·936	23·932	23·961	24·029	24·112	24·151	24·141	24·051
Pithoragarh	9	?	?	?	?	24·625	24·539	24·533	24·560	24·630	24·724	24·779	24·775	?
Meerut	9	29·283	29·230	29·119	28·991	28·883	28·750	28·765	28·831	28·930	29·111	29·233	29·291	29·035
	10—11	29·286	29·229	29·118	28·996	28·879	28·756	28·767	28·835	28·932	29·110	29·243	29·295	29·037
Bareilly	9	29·447	29·387	29·281	29·150	29·059	28·933	28·943	29·006	29·104	29·277	29·396	29·464	29·204
Agra	9	29·481	29·430	29·324	29·186	29·077	28·958	28·962	29·034	29·135	29·310	29·436	29·500	29·236
Lucknow	9	29·669	29·614	29·499	29·361	29·269	29·144	29·152	29·221	29·318	29·494	29·617	29·684	29·420
	11—12	29·669	29·612	29·499	29·364	29·267	29·144	29·153	29·224	29·318	29·493	29·628	29·686	29·421
Gorakhpur	9	29·774	29·712	29·592	29·454	29·381	29·257	29·264	29·328	29·423	29·601	29·724	29·791	29·525
Jhansi	9	29·161	29·120	29·024	28·894	28·781	28·674	28·672	28·739	28·834	29·004	29·117	29·172	28·933
Allahabad	9	29·731	29·675	29·555	29·421	29·321	29·197	29·210	29·278	29·372	29·551	29·675	29·745	29·478
Benares	9	29·772	29·717	29·599	29·456	29·359	29·237	29·249	29·317	29·411	29·589	29·713	29·785	29·517
	15—16	29·778	29·714	29·608	29·475	29·370	29·252	29·261	29·306	29·418	29·590	29 728	29·792	29·524
Katmandu	3	25·717	25·669	25·644	25·576	25·542	25·413	25·426	?	?	25 659	25·716	25·710	?
Sibsagar	9	29·736	29·670	29·594	29·500	29·431	29·298	29·281	29·334	29·423	29·565	29·667	29·728	29·519
	10	29·737	29·670	29·590	29·503	29·426	29·302	29·285	29·334	29 421	29·561	29·669	29·729	29·519
Dhubri	9	?	?	?	29·668	29·608	29·490	29·482	29·534	29·625	29·770	29·852	29·923	?
Silchar	9	29·941	29·895	29·814	29·725	29·662	29·539	29·526	29·579	29·656	29·777	29·857	29·920	29·741
	13—15	29·933	29·887	29·808	29·725	29·648	29·539	29·530	29·580	29·659	29·775	29·878	29·935	29·741
Darjeeling (*Saint Paul's School*).	14—16	22·960	22 940	22·943	22 943	22·916	22·861	22·859	22·898	22·954	23·016	23·034	23·005	22·944
Purneah	9	29·904	29·840	29·730	29·614	29·551	29·435	29·434	29·486	29·583	29·732	29·835	29·899	29·670
	10	?	?	?	?	?	29·436	29·436	?	?	?	?	?	?
Durbhunga	9	29·875	29·811	29·695	29·571	29·504	29·378	29·381	29·439	29·535	29·700	29·810	29·878	29·631

TABLE XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*—contd.

STATIONS.	Year.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Patna	9	29·870	29·805	29·679	29·546	29·471	29·343	29·356	29·418	29·514	29·683	29·804	29·876	29·614
	15—16	29·865	29·801	29·681	29·558	29·468	29·346	29·357	29·422	29·512	29·678	29·815	29·879	29·615
Gya	9	29·676	29·608	29·507	29·379	29·296	29·165	29·184	29·245	29·334	29·502	29·625	29·687	29·434
	11—13	29·673	29·605	29·500	29·379	29·283	29·164	29·181	29·242	29·330	29·496	29·628	29·685	29·431
Hazaribagh	9	27·980	27·942	27·865	27·767	27·685	27·574	27·569	27·623	27·710	27·865	27·951	27·988	27·793
	16—17	27·969	27·935	27·865	27·772	27·684	27·574	27·568	27·624	27·706	27·861	27·964	27·996	27·794
Berhampore	9	29·965	29·907	29·794	29·677	29·618	29·493	29·493	29·559	29·647	29·796	29·902	29·963	29·735
	16	29·961	29·896	29·791	29·678	29·599	29·481	29·488	29·554	29·642	29·785	29·909	29·968	29·729
Burdwan	9	29·936	29·879	29·764	29·653	29·583	29·458	29·455	29·523	29·612	29·762	29·871	29·937	29·703
	10—11	29·939	29·879	29·761	29·654	29·575	29·463	29·460	29·522	29·610	29·758	29·881	29·940	29·704
Jessore	9	29·999	29·946	29·838	29·735	29·674	29·549	29·539	29·602	29·691	29·828	29·928	29·991	29·777
	16—17	29·999	29·941	29·842	29·742	29·667	29·548	29·543	29·601	29·687	29·827	29·947	30·003	29·779
Dacca	9	29·998	29·946	29·848	29·745	29·686	29·566	29·557	29·616	29·701	29·827	29·920	29·989	29·783
	15—17	29·991	29·937	29·845	29·751	29·678	29·565	29·559	29·611	29·694	29·820	29·935	29·995	29·782
Chittagong	9	29·948	29·906	29·833	29·743	29·674	29·564	29·558	29·608	29·679	29·785	29·865	29·931	29·758
	12—13	29·947	29·905	29·831	29·747	29·669	29·563	29·560	29·607	29·680	29·780	29·874	29·934	29·758
Calcutta (*Alipore*)	9	30·019	29·964	29·859	29·747	29·677	29·548	29·541	29·606	29·695	29·841	29·946	30·010	29·788
	31	30·017	29·950	29·856	29·752	29·659	29·544	29·538	29·598	29·683	29·831	29·962	30·021	29·784
Sangor Island	9	30·007	29·955	29·859	29·753	29·676	29·547	29·538	29·601	29·685	29·831	29·939	30·008	29·783
	16—17	30·004	29·943	29·859	29·757	29·668	29·544	29·535	29·591	29·675	29·818	29·949	30·014	29·780
Cuttack	9	29·952	29·897	29·800	29·689	29·607	29·494	29·497	29·549	29·625	29·777	29·890	29·958	29·728
	16	29·959	29·894	29·804	29·696	29·609	29·502	29·504	29·556	29·635	29·778	29·909	29·966	29·734
False Point	9	30·027	29·977	29·878	29·768	29·686	29·578	29·561	29·617	29·693	29·843	29·962	30·031	29·802
	17	30·029	29·973	29·888	29·784	29·692	29·578	29·573	29·628	29·699	29·840	29·976	30·037	29·808
Sambalpur	9	29·547	29·480	29·370	29·250	29·153	29·069	29·087	29·133	29·212	29·362	29·474	29·538	29·306
Raipur	9	29·038	28·993	28·900	28·783	28·681	28·596	28·603	28·660	28·729	28·893	28·999	29·046	28·827
Nagpur	9	28·968	28·918	28·835	28·726	28·631	28·564	28·572	28·620	28·680	28·833	28·933	28·983	28·772
	15	28·959	28·911	28·826	28·722	28·630	28·553	28·559	28·615	28·670	28·818	28·937	28·982	28·765
Seoni	9	27·962	27·923	27·854	27·770	27·674	27·583	27·569	27·623	27·696	27·850	27·934	27·974	27·784
	13	27·958	27·920	27·853	27·776	27·681	27·582	27·570	27·623	27·691	27·841	27·939	27·973	27·784
Jubbulpore	9	28·678	28·628	28·546	28·432	28·333	28·234	28·232	28·292	28·370	28·537	28·640	28·688	28·468
	14—15	28·669	28·624	28·540	28·434	28·334	28·228	28·226	28·291	28·362	28·527	28·645	28·683	28·463
Saugor	3—4	?	28·172	28·130	?	?	27·808	?	27·872	?	28·123	28·201	28·258	?
Pachmarhi	9	26·528	26·503	26·470	26·395	26·318	26·219	26·193	26·249	26·313	26·458	26·517	26·544	26·392
Hoshangabad	9	29·005	28·954	28·876	28·765	28·673	28·581	28·585	28·646	28·707	28·866	28·964	29·015	28·803

TABLE XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*—contd.

STATIONS.	Year.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Khandwa . .	9	28·940	28·893	28·825	28·729	28·637	28·557	28·557	28·617	28 686	28·827	28·915	28·957	28·762
Chanda . .	9	29·371	29·312	29·225	29·116	29 021	28·969	28·988	29·031	29·087	29·226	29·329	29·386	29·172
Sironcha . .	9	29·628	29·592	29·503	29·398	29·303	29·265	29·299	29·306	29·355	29·476	29·576	29·635	29·445
Chikalda . .	7—8	26·432	26·400	26·370	26·290	26·217	26·127	26·114	26·151	26·213	26·342	26·395	26 430	26·290
Buldana . .	9	27·845	27·813	27·765	27·679	27·610	27·532	27·531	27·578	27·638	27·759	27·829	27·865	27·704
Akola . . .	9	29·062	29·016	28 940	28·838	28·756	28·684	28·693	28·745	28·804	28·937	29·028	29·079	28·882
Amraoti . .	9	28·777	28 728	28·649	28·550	28·464	28 396	28·401	28·449	28·509	28·650	28·741	28·789	28·592
Neemuch . .	9	28·363	28·320	28 248	28·150	28·053	27·953	27·938	28·011	28 095	28·255	28·337	28·376	28·175
Nowgong . .	9	29·280	29·236	29·121	28 991	28·881	28·759	28·774	28·841	28·930	29·101	29·227	29·287	29·036
Sutna . . .	9	28·973	28·934	28·831	28 702	28·593	28·480	28·483	28·550	28·640	28·817	28·930	28·986	28·743
Indore . . .	9	28·163	28·135	28·072	27·982	27·896	27·804	27·794	27·854	27·927	28·071	28·144	28·182	28·002
Bickaneer . .	9	29·294	29·234	29·118	28·991	28·863	28·745	28 727	28·808	28·924	29·104	29·226	29·292	29 027
Jeypore . . .	9	28·578	28·535	28·447	28·342	28·240	28·126	28·119	28·191	28·284	28·454	28·549	28·600	28·372
Sambhar . .	9	28·752	28·728	28·623	28·508	28·398	28·307	28·279	28·341	28·429	28·611	28·722	28·767	28·539
Ajmere . .	9	28·406	28·365	28·281	28·177	28·074	27·979	27·954	28·025	28·111	28·290	28·389	28·431	28·207
Mount Abu . .	3—6	26·150	26·107	26·076	26·033	25·954	25·858	25·815	25 858	25·951	26·084	26·122	26·121	26·009
Jacobabad . .	9	29·879	29·824	29·695	29·556	29·407	29 261	29·240	29·334	29·466	29·669	29 822	29·896	29·587
Hyderabad . .	9	29·982	29·927	29·801	29·677	29·541	29·406	29·379	29·471	29·602	29·776	29·913	29·989	29·765
Kurrachee . .	9	30·012	29·979	29·884	29·782	29·646	29·524	29·493	29·582	29·694	29·860	29·961	30·028	29 787
Bhuj . . .	9	29·635	29·595	29·513	29·410	29·308	29·188	29·164	29·246	29·341	29·488	29·577	29·636	29·425
Rajkot . . .	9	29 588	29·551	29·483	29·390	29·296	29·183	29·174	29·248	29·334	29·460	29·531	29 582	29·402
Deesa . . .	9	29·539	29·500	29·427	29·323	29·224	29·126	29·104	29·180	29·275	29·419	29·502	29·545	29·347
Surat . . .	9	29·967	29·941	29·884	29·791	29·726	29·629	29·607	29·673	29·741	29·842	29·912	29·963	29·806
Malegaum . .	7	28·539	28·507	28·446	28·360	28·219	28·219	28·218	28·273	28·330	28·444	28·520	28·547	28 391
Bombay . .	9	29·953	29·929	29·885	29·806	29·760	29·685	29·683	29·731	29·784	29·846	29·898	29·945	29·826
	37	29·949	29·921	29·875	29 809	29·764	29·688	29·667	29·726	29·782	29·841	29·909	29·946	29·821
Poona . .	9	28·125	28·086	28·049	27·983	27·937	27 873	27·873	27·915	27·966	28·042	28·092	28·138	28·007
Sholapur . .	9	28·391	28·356	28·298	28·207	28·149	28·118	28·120	28·153	28·198	28·278	28·341	28·394	28·250
Ratnagiri . .	9	29·856	29·833	29·795	29·718	29·677	29·631	29·641	29·677	29·719	29·753	29·790	29·837	29·744
Belgaum . .	9	27·433	27·416	27·382	27·321	27·285	27·253	27·257	27·278	27·325	27·361	27·394	27·434	27·345
Karwar . .	6	29 923	29·910	29·880	29·812	29·766	29·753	29·768	29·780	29·820	29·830	29·851	29·905	29·833
Gopalpore . .	9	29·993	29·940	29·849	29·746	29·654	29·546	29·545	29·597	29·670	29·813	29·926	29·994	29·773
Vizagapatam .	9	30·001	29·959	29·883	29·784	29·690	29·592	29·598	29·636	29·695	29·820	29·925	29·990	29·798
	14	29·988	29·947	29·877	29·786	29·684	29·593	29·593	29 636	29·694	29·810	29·930	29·993	29·794

TABLE XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*—contd.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Masulipatam	9	30·017	29·983	29·914	29·817	29·720	29·666	29·688	29·704	29·752	29·851	29·944	30·005	29·838
	13—14	30·005	29·969	29·904	29·812	29·707	29·656	29·675	29·700	29·742	29·835	29·945	30·003	29·829
Secunderabad	9	28·188	28·160	28·108	28·030	27·961	27·918	27·916	27·944	27·985	28·077	28·143	28·190	28·052
	13—14	28·180	28·154	28·101	28·028	27·951	27·910	27·912	27·944	27·981	28·068	28·144	28·193	28·047
Bellary	9	28·502	28·465	28·410	28·333	28·285	28·282	28·297	28·312	28·345	28·398	28·453	28·499	28·382
	13	28·496	28·461	28·407	28·335	28·289	28·276	28·294	28·313	28·341	28·393	28·460	28·501	28·381
Mangalore	6	29·893	29·890	29·867	29·805	29·766	29·773	29·785	29·798	29·832	29·826	29·836	29·882	29·829
Mercara	9	26·279	26·281	26·268	26·222	26·197	26·182	26·192	26·196	26·220	26·233	26·253	26·272	26·233
Bangalore	9	27·010	26·996	26·967	26·904	26·862	26·849	26·858	26·869	26·898	26·929	26·962	27·000	26·925
	14	27·006	26·992	26·962	26·905	26·861	26·845	26·856	26·870	26·896	26·925	26·969	27·004	26·924
Madras	9	29·995	29·974	29·914	29·820	29·731	29·705	29·728	29·746	29·781	29·846	29·911	29·974	29·844
	24	29·988	29·966	29·908	29·819	29·733	29·699	29·721	29·747	29·772	29·837	29·919	29·974	29·840
Salem	9	29·048	29·035	28·985	28·905	28·863	28·858	28·873	28·883	28·913	28·944	28·984	29·035	28·944
	14	29·044	29·027	28·981	28·908	28·864	28·857	28·873	28·885	28·909	28·932	28·994	29·040	28·943
Wellington	10—12	24·256	24·263	24·265	24·227	24·193	24·157	24·160	24·166	24·185	24·204	24·232	24·256	24·214
Coimbatore	9	28·604	28·586	28·550	28·483	28·449	28·453	28·466	28·472	28·498	28·520	28·552	28·593	28·519
	13—14	28·599	28·578	28·544	28·481	28·443	28·442	28·458	28·466	28·486	28·507	28·553	28·592	28·512
Trichinopoly	9	29·709	29·701	29·649	29·564	29·517	29·504	29·522	29·532	29·562	29·598	29·646	29·699	29·600
	13—14	29·704	29·694	29·654	29·566	29·520	29·497	29·513	29·526	29·550	29·586	29·646	29·698	29·596
Negapatam	9	29·970	29·956	29·910	29·821	29·755	29·743	29·760	29·776	29·806	29·846	29·890	29·941	29·848
	14	29·963	29·948	29·906	29·823	29·753	29·737	29·757	29·775	29·801	29·837	29·897	29·947	29·845
Madura	9	29·503	29·495	29·454	29·377	29·330	29·318	29·334	29·347	29·373	29·404	29·439	29·478	29·404
	13—14	29·492	29·480	29·441	29·367	29·318	29·305	29·323	29·336	29·359	29·389	29·440	29·480	29·394
Cochin	9	29·936	29·930	29·913	29·853	29·841	29·864	29·875	29·877	29·901	29·894	29·895	29·915	29·891
	12—13	29·925	29·922	29·907	29·855	29·837	29·858	29·874	29·878	29·898	29·891	29·903	29·922	29·889
Colombo	9	29·886	29·887	29·875	29·819	29·806	29·828	29·840	29·840	29·864	29·859	29·858	29·872	29·853
	14—15	29·878	29·880	29·867	29·818	29·804	29·819	29·834	29·835	29·860	29·855	29·856	29·871	29·848
Jaffna	9	29·963	29·953	29·912	29·829	29·778	29·773	29·789	29·796	29·828	29·856	29·891	29·933	29·858
	13	29·961	29·945	29·907	29·830	29·777	29·766	29·785	29·793	29·821	29·847	29·891	29·934	29·855
Trincomalee	9	29·780	29·781	29·744	29·662	29·608	29·601	29·615	29·621	29·650	29·679	29·707	29·739	29·682
	13—15	29·773	29·771	29·738	29·662	29·606	29·593	29·607	29·616	29·640	29·669	29·717	29·751	29·679
Batticaloa	9	29·945	29·945	29·912	29·837	29·793	29·793	29·808	29·810	29·838	29·855	29·879	29·909	29·860
	13—14	29·941	29·937	29·905	29·834	29·788	29·781	29·799	29·804	29·825	29·845	29·878	29·912	29·854
Hambantota	9	29·854	29·854	29·847	29·808	29·781	29·787	29·792	29·794	29·815	29·818	29·834	29·846	29·819
	12—13	29·853	29·852	29·845	29·808	29·778	29·782	29·786	29·788	29·808	29·814	29·837	29·847	29·817

TABLE XI.—*Average monthly mean pressures of 123 stations in India, Ceylon, &c.*—concld.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Galle	9	29·861	29·860	29·850	29·797	29·787	29·806	29·819	29·816	29·843	29·837	29·834	29·842	29 829
	13—15	29·855	29·855	29·844	29·796	29·787	29·796	29·812	29·812	29·837	29·833	29·832	29·846	29·825
Kandy	9	28·224	28·222	28·206	28·156	28·136	28·157	28·166	28·165	28·184	28·186	28·186	28·207	28·183
	13—14	28·215	28·214	28·199	28·154	28·135	28·149	28·161	28·157	28·177	28·178	28 184	28·203	28·177
Newera Eliya	9	?	?	?	?	?	23·978	23·981	23·975	23·990	23·995	24·015	24·009	?
	12—14	24·009	24·025	24·030	24·003	23·993	23·981	23·980	23·979	23·991	23·997	24·016	24·013	24·001
Akyab	9	30·001	29·963	29·914	29·826	29·764	29·675	29·666	29·708	29·761	29·850	29·922	29·981	29·836
	16—17	29·998	29·951	29·902	29·830	29·758	29·678	29·673	29·708	29·761	29·845	29·935	29·987	29·836
Thayetmyo	8—9	29·841	29·784	29·732	29·637	29·602	29·575	29·569	29·595	29·641	29·720	29·788	29·843	29·694
Tounghoo	9	29·840	29·780	29·710	29·640	29·600	29·581	29·574	29·598	29·639	29·704	29·768	29·814	29·687
Bassein	9	29·971	29·925	29·884	29·810	29·765	29·729	29·727	29·749	29·781	29·839	29·891	29·946	29·835
Diamond Island	9	29·970	29·938	29·902	29·828	29·773	29·731	29·728	29·753	29·785	29·838	29·893	29·941	29·840
Rangoon	9	29·951	29·909	29·864	29·792	29·747	29·727	29·727	29·748	29·785	29·832	29·887	29·932	29·825
Moulmein	9	29·883	29·845	29·817	29·744	29·702	29 687	29·686	29·700	29·724	29·763	29·805	29·855	29·768
Mergui	9	29·868	29·868	29·834	29·774	29·748	29·743	29·739	29·751	29·776	29·794	29·815	29·845	29·796
Port Blair	9	29·906	29·898	29·877	29·805	29·757	29·736	29·744	29·758	29·787	29·812	29·838	29·878	29·816
	14—16	29·894	29·888	29·864	29·800	20·749	29·728	29·736	29·749	29·775	29·802	29·839	29·873	29·808
Nancowry	9	29·858	29·863	29·851	29·799	29·775	29·772	29·779	29·783	29·809	29·812	29·818	29·836	29·813
	10—11	29·856	29·858	29·844	29·798	29·767	29·759	29·769	29·777	29·801	29·804	29·817	29·836	29·807

TABLE XII A.—*Comparison of monthly mean pressures, in 1883, with the averages of 9 years or less than 9 years, in the previous table.*

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	—·024	—·002	—·011	—·006	—·006	+·003	+·015	+·007	+·029	+·018	0	+·033	+·005
Aden	—·032	+·005	—·008	—·018	+·010	—·016	—·009	0	+·006	+·005	—·018	+·042	—·003
Mauritius	—·023	—·016	—·007	+·001	+·002	—·041	+·012	—·054	—·002	+·003	—·055	—·013	—·016
Bushire	—·049	+·016	+·011	—·007	—·009	—·006	+·003	+·025	+·005	+·031	—·012	+·050	+·005
Quetta	—·031	+·017	—·027	+·001	—·018	—·005	0	—·001	—·015	+·033	—·007	+·060	0
Leh	—·073	—·054	—·056	+·009	—·043	0	—·025	—·031	—·025	+·009	—·050	+·019	—·027
Mooltan	—·015	+·016	—·002	—·002	—·029	—·033	+·016	—·015	—·011	+·037	—·027	+·063	0
Dera Ismail Khan	—·004	+·007	+·007	+·004	—·019	—·010	+·001	—·017	—·002	+·052	—·028	+·046	+·003
Peshawar	—·027	—·010	—·020	—·002	—·062	—·045	—·014	—·030	—·034	+·025	—·044	+·037	—·019

TABLE XII A.—*Comparison of monthly mean pressures, in 1883, with the averages of 9 years or less than 9 years, in the previous table*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Murree	—·047	—·005	—·018	+·033	—·030	0	+·002	—·001	—·006	+·026	—·044	+·025	—·005
Sialkot	—·037	+·009	—·006	+·001	—·042	—·019	—·009	—·009	—·004	+·032	—·037	+·046	—·006
Lahore	—·017	+·009	+·001	+·001	—·042	—·025	—·013	—·024	—·002	+·039	—·034	+·053	—·005
Ludhiana	—·018	+·004	—·007	—·003	—·051	—·014	—·003	—·022	—·016	+·031	—·036	+·048	—·007
Simla	—·028	—·028	—·039	—·012	—·039	—·020	—·008	—·011	—·021	+·014	—·044	—·002	—·020
Delhi	—·006	+·009	+·004	—·020	—·047	—·011	+·004	?	?	?	?	?	?
Sirsa	—·018	+·025	—·004	—·008	—·041	—·010	+·008	—·009	—·006	+·052	—·023	+·063	+·002
Chakrata	—·033	—·024	—·036	—·011	—·044	—·022	—·020	—·024	—·031	+·021	—·042	+·006	—·022
Dehra	—·002	—·013	—·009	—·017	—·054	+·002	—·002	—·009	—·009	+·044	—·024	+·047	—·004
Paori	?	?	?	?	?	—·016	—·019	—·037	+·002	+·032	—·044	?	?
Roorkee	—·006	—·008	—·007	—·034	—·058	—·009	—·008	—·016	—·015	+·033	—·026	+·050	—·009
Ranikhet	—·022	—·024	—·026	—·019	—·040	—·019	—·020	—·015	—·013	+·024	—·038	+·016	—·016
Pithoragarh	?	?	?	?	—·033	—·009	—·006	—·003	+·003	+·040	—·030	+·033	?
Meerut	—·009	+·002	—·022	—·030	—·069	—·022	—·021	—·032	—·033	+·029	—·027	+·046	—·016
Bareilly	+·018	+·005	—·001	—·028	—·059	—·008	—·007	—·013	—·009	+·048	—·014	+·054	—·001
Agra	—·006	+·018	0	—·016	—·041	—·012	+·006	—·010	—·012	+·042	—·029	+·055	0
Lucknow	—·002	+·008	+·002	—·024	—·058	+·002	—·005	—·008	—·013	+·041	—·022	+·050	—·002
Gorakhpur	+·009	+·003	+·002	—·009	—·053	+·019	—·005	—·003	—·006	+·041	—·032	+·045	+·001
Jhansi	—·014	+·009	—·002	—·009	—·015	+·002	+·012	+·011	—·012	+·038	—·029	+·051	+·004
Allahabad	0	+·008	—·002	—·021	—·054	+·002	—·008	—·005	—·013	+·048	—·021	+·052	—·001
Benares	+·007	+·010	+·002	—·021	—·056	+·007	—·011	—·007	—·018	+·046	—·021	+·055	—·001
Sibsagar	+·009	—·012	—·026	—·019	—·049	—·009	—·027	—·014	—·011	+·030	—·035	+·050	—·009
Dhubri	?	?	?	—·019	—·046	—·011	—·033	—·015	—·014	+·029	—·024	+·058	?
Silchar	+·006	—·015	—·029	—·021	—·056	—·018	—·047	—·027	—·014	+·022	—·048	+·033	—·018
Purneah	+·013	—·009	—·021	—·022	—·057	—·023	—·027	—·008	—·012	+·042	—·021	+·064	—·007
Durbhunga	+·030	+·006	—·006	—·008	—·049	—·002	—·016	—·001	—·008	+·044	—·020	+·061	+·003
Patna	+·013	+·002	—·004	—·012	—·063	+·007	—·011	—·003	—·013	+·040	—·028	+·054	—·002
Hazaribagh	+·007	—·006	—·002	—·015	—·052	—·011	—·011	—·004	—·017	+·046	—·029	+·039	—·005
Berhampore	+·019	+·001	—·009	—·018	—·065	—·007	—·021	—·008	—·014	+·038	—·032	+·054	—·005
Burdwan	+·015	0	0	—·025	—·063	—·012	—·016	—·005	—·015	+·039	—·029	+·049	—·005
Jessore	+·022	—·001	—·006	—·016	—·066	—·020	—·031	—·009	—·017	+·037	—·027	+·049	—·007
Dacca	+·022	—·001	—·010	—·006	—·055	—·010	—·025	—·006	—·003	+·038	—·032	+·049	—·003
Chittagong	+·013	—·008	—·005	—·002	—·032	—·035	—·029	—·007	+·001	+·033	—·037	+·040	—·006

TABLE XII A.—*Comparison of monthly mean pressures, in 1883, with the averages of 9 years or less than 9 years, in the previous table*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Calcutta (*Alipore*)	+·007	—·006	—·010	—·026	—·069	—·029	—·032	—·018	—·027	+·032	—·036	+·041	—·014
Saugor Island	+·012	—·003	+·002	—·009	—·048	—·014	—·007	+·004	—·008	+·048	—·020	+·046	0
Cuttack	+·007	—·008	—·004	—·017	—·049	—·016	—·023	—·004	—·017	+·043	—·028	+·046	—·006
False Point	+·009	—·011	—·004	—·011	—·051	—·034	—·026	—·001	—·013	+·046	—·030	+·041	—·007
Sambalpur	—·018	—·021	+·013	—·006	—·047	—·011	—·021	—·002	—·016	+·032	—·029	+·037	—·007
Raipur	—·009	—·024	—·001	—·005	—·032	—·009	—·007	—·010	—·012	+·041	—·027	+·055	—·003
Nagpur	—·007	—·017	—·011	—·016	—·026	—·007	—·013	—·019	—·006	+·034	—·027	+·049	—·006
Seoni	—·004	—·010	—·004	—·013	—·022	—·002	+·011	+·006	—·006	+·040	—·021	+·045	+·002
Jubbulpore	—·011	—·005	—·003	—·002	—·022	—·005	+·005	—·005	—·006	+·049	—·023	+·055	+·002
Saugor	P	P	P	P	P	+·001	P	—·005	P	+·021	—·030	+·027	P
Pachmarhi	—·005	—·003	—·009	+·004	—·007	+·008	+·001	+·009	—·001	+·043	—·013	+·048	+·006
Hoshangabad	—·024	—·013	—·012	—·018	—·028	—·011	—·013	—·014	—·010	+·033	—·024	+·052	—·007
Khandwa	—·010	+·002	+·011	—·007	—·008	—·003	+·008	+·010	+·012	+·029	—·027	+·066	+·007
Chanda	—·012	—·025	—·015	—·024	—·034	—·014	—·022	—·035	—·006	+·029	—·026	+·047	—·011
Chikalda	—·040	—·035	—·039	—·021	—·028	—·028	—·028	—·013	—·018	+·018	—·029	+·023	—·020
Buldana	+·006	—·005	0	—·002	—·007	—·002	+·017	+·019	+·019	+·044	—·005	+·061	+·012
Akola	—·012	—·020	—·008	—·018	—·027	—·010	—·006	—·009	+·006	+·032	—·023	+·054	—·003
Amraoti	—·021	—·026	—·017	—·023	—·031	—·018	—·015	—·023	—·007	+·025	—·031	+·045	—·012
Neemuch	—·028	+·008	—·015	—·008	—·021	—·008	+·006	—·001	—·006	+·028	—·026	+·059	—·001
Nowgong	—·012	+·002	+·003	—·008	—·024	+·008	+·010	+·005	—·013	+·059	—·020	+·056	+·006
Sutna	+·002	+·004	+·005	—·013	—·032	0	—·006	+·007	—·002	+·052	—·020	+·057	+·005
Indore	—·023	—·018	—·012	—·017	—·024	—·018	—·011	—·003	—·014	+·023	—·027	+·048	—·008
Bickaneer	—·040	+·006	0	—·014	—·028	—·011	+·014	—·004	—·003	+·044	—·018	+·058	0
Jeypore	—·019	+·011	—·001	—·012	—·031	—·006	+·006	—·006	—·005	+·039	—·025	+·052	0
Sambhar	—·015	—·001	—·006	—·009	—·023	—·012	+·011	+·009	+·013	+·044	—·019	+·064	+·005
Ajmere	—·024	+·009	—·002	—·009	—·016	+·001	+·007	+·003	+·006	+·044	—·012	+·057	+·005
Jacobabad	—·013	+·018	+·012	—·019	—·035	—·031	+·011	—·024	—·012	+·037	—·028	+·050	—·002
Hyderabad	—·028	+·002	0	—·016	—·034	—·018	+·002	—·014	—·015	+·023	—·026	+·054	—·006
Kurrachee	—·003	+·018	+·011	+·004	—·041	—·032	—·008	+·009	—·006	+·012	—·024	+·057	0
Bhuj	—·036	—·004	—·006	—·023	—·039	—·036	—·016	+·003	—·006	+·007	—·023	+·066	—·010
Rajkot	—·026	—·002	—·001	—·014	—·029	—·027	—·009	—·002	—·002	+·012	—·017	+·062	—·005
Deesa	—·025	+·002	0	—·022	—·027	—·028	—·007	—·009	—·006	+·020	—·018	+·074	—·004
Surat	—·006	—·007	+·007	—·004	—·018	—·032	+·001	+·011	+·016	+·029	—·006	+·075	+·006
Bombay	—·011	—·019	+·008	—·004	—·019	—·035	—·001	—·002	+·014	+·011	—·018	+·056	—·002

TABLE XII A.—*Comparison of monthly mean pressures, in 1883, with the averages of 9 years or less than 9 years, in the previous table*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Poona	—·011	—·004	+·011	—·001	—·009	—·013	+·009	+·004	+·022	+·023	—·010	+·055	+·006
Sholapur	—·004	—·009	+·003	+·009	—·001	—·011	—·008	—·015	—·011	+·005	—·039	+·033	—·004
Ratnagiri	—·015	—·021	+·006	+·002	—·009	—·026	+·009	—·012	+·019	+·010	—·015	+·053	0
Belgaum	—·017	—·025	—·016	—·015	—·029	—·035	—·017	—·031	+·001	—·001	—·027	+·034	—·015
Karwar	—·005	—·019	+·003	—·004	—·005	—·014	+·009	—·013	+·027	+·015	—·010	+·044	+·002
Gopalpore	+·008	—·014	—·008	—·013	—·047	—·010	—·023	—·018	—·018	+·044	—·022	+·041	—·001
Vizagapatam	+·002	—·020	—·009	—·015	—·034	—·011	—·020	—·012	0	+·045	—·020	+·036	—·005
Masulipatam	—·028	—·012	?	?	?	?	?	?	?	?	?	?	?
Secunderabad	—·004	—·021	—·021	—·023	—·041	—·024	—·010	—·021	+·007	+·024	—·019	+·038	—·010
Bellary	—·014	—·018	—·022	—·015	—·025	—·029	—·017	—·035	+·003	+·005	—·030	+·029	—·014
Mangalore	+·005	—·010	+·005	+·005	—·003	—·007	+·021	—·015	+·032	+·024	—·005	+·053	+·009
Mercara	—·002	—·009	+·002	0	—·014	—·012	+·001	—·025	+·020	+·005	—·030	+·034	—·003
Bangalore	—·007	—·010	—·006	—·008	—·017	—·015	—·006	—·032	+·013	+·002	—·028	+·025	—·007
Madras	—·005	—·015	—·013	—·010	—·022	—·009	—·004	—·028	+·010	+·030	—·005	+·040	—·003
Salem	—·009	—·009	—·009	—·002	—·021	—·017	—·006	—·036	+·009	+·012	—·024	+·023	—·007
Coimbatore	—·002	—·010	0	+·009	—·007	0	+·006	—·020	+·026	+·019	—·016	+·043	+·004
Trichinopoly	+·018	+·010	+·011	+·015	+·001	+·008	+·018	—·010	+·029	+·031	—·004	+·050	+·015
Negapatam	—·011	—·029	+·001	0	—·021	—·002	+·003	—·020	+·017	+·018	—·013	+·036	—·002
Madura	—·005	—·007	—·007	—·027	—·017	—·013	+·002	—·034	+·015	+·009	—·017	+·017	—·007
Cochin	—·019	—·018	—·007	—·002	—·020	—·010	+·012	—·015	+·022	+·004	—·030	+·041	—·004
Colombo	—·016	—·011	+·001	+·004	—·012	—·006	+·002	—·024	+·002	+·005	—·031	+·047	—·003
Jaffna	+·004	+·001	+·001	+·002	—·013	—·002	+·009	—·021	+·024	+·012	—·021	+·039	+·003
Trincomalee	—·028	—·033	—·022	—·018	—·014	—·012	—·002	—·023	+·007	—·005	—·028	+·025	—·013
Batticaloa	—·037	—·034	—·010	—·017	—·033	—·025	—·021	—·043	+·012	+·016	0	?	?
Hambantota	+·025	+·018	+·023	+·008	—·008	—·009	+·003	—·021	+·015	+·001	—·040	+·019	+·003
Galle	+·004	+·008	+·020	+·021	+·004	+·011	+·019	—·019	+·033	+·017	—·017	+·065	+·014
Kandy	—·008	—·008	+·002	+·004	—·005	+·001	—·005	—·018	—·005	+·008	—·022	+·039	—·001
Akyab	+·012	—·017	—·014	—·006	—·015	—·012	—·020	—·007	+·012	+·030	—·030	+·050	—·001
Thayetmyo	+·030	—·003	—·013	—·005	—·010	—·012	—·021	—·012	+·016	+·034	—·026	+·073	+·004
Tounghoo	?	?	?	?	—·013	—·020	—·029	—·033	—·012	—·015	—·055	+·029	?
Bassein	+·004	—·019	—·003	—·007	—·023	—·014	—·020	—·024	+·008	+·014	—·035	+·045	—·007
Diamond Island	—·003	—·020	—·017	—·012	—·019	—·011	—·021	—·015	+·018	+·016	—·049	+·037	—·008
Rangoon	?	?	?	?	?	—·002	—·029	—·014	+·007	+·019	—·028	+·057	?
Moulmein	—·001	—·032	—·034	—·030	—·039	—·027	—·030	—·037	—·005	—·010	—·046	+·034	+·022
Mergui	+·003	—·050	—·023	—·019	—·024	+·008	+·004	—·013	+·011	+·003	—·031	+·043	—·007
Port Blair	—·004	—·015	—·014	—·001	—·003	+·007	+ 001	—·010	+·028	+·012	—·035	+·043	+·001
Nancowry	—·019	—·045	— 027	—·029	—·016	+·002	+·003	—·025	—·005	—·028	—·050	+·021	—·018

TABLE XII B.—*Comparison of monthly mean pressures, in 1883, with the averages of more than 9 yeass.*

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Lahore	—·021	+·009	+·001	—·012	—·048	—·024	—·014	—·030	—·001	+·040	—·055	+·046	—·009
Roorkee	—·009	0	—·013	—·049	—·058	—·016	—·016	—·020	—·020	+·034	—·041	+·039	—·014
Ranikhet	—·022	—·023	—·022	—·022	—·036	—·020	·024	—·017	—·015	+·022	—·047	+·011	—·018
Meerut	—·012	+·003	—·020	—·035	—·065	—·028	—·023	—·036	—·035	+·030	—·037	+·042	—·018
Lucknow	—·002	+·010	+·002	—·027	—·059	+·002	—·006	—·011	—·013	+·042	—·033	+·048	—·004
Benares	+·001	+·013	—·007	—·040	—·067	—·008	—·023	+·004	—·025	+·045	—·036	+·048	—·008
Sibsagar	+·008	—·012	—·022	—·022	—·044	—·013	—·031	—·014	—·009	+·034	—·037	+·049	—·009
Silchar	+·014	—·007	—·023	—·021	—·042	—·018	—·051	—·028	—·017	+·024	—·069	+·018	—·018
Darjeeling	+·014	—·012	—·013	—·005	—·021	+·004	+·001	—·009	+·011	+·032	—·032	+·035	0
Purneah	P	P	P	P	P	—·024	—·029	P	P	P	P	P	P
Patna	+·018	+·006	—·006	—·024	—·060	+·004	—·012	—·007	—·011	+·045	—·039	+·051	—·003
Hazaribagh	+·008	+·001	—·002	—·020	—·051	—·011	—·010	—·005	—·013	+·050	—·042	+·031	—·005
Berhampore	+·023	+·012	—·006	—·019	—·046	+·005	—·016	—·003	—·009	+·049	—·039	+·049	0
Burdwan	+·012	0	+·003	—·026	—·055	—·017	—·021	—·004	—·013	+·043	—·039	+·046	—·006
Jessore	+·022	+·004	—·010	—·023	—·050	—·019	—·035	—·008	—·013	+·038	—·046	+·037	—·009
Dacca	+·029	+·008	—·007	—·012	—·047	—·009	—·027	—·001	+·004	+·045	—·047	+·043	—·002
Chittagong	+·014	—·007	—·003	—·006	—·027	—·034	—·031	—·006	0	+·038	—·046	+·037	—·006
Calcutta (*Alipore*)	+·009	+·008	—·007	—·031	—·051	—·025	—·029	—·010	—·015	+·042	—·052	+·030	—·011
Saugor Island	+·015	+·009	+·002	—·013	—·040	—·011	—·004	+·014	+·002	+·061	—·030	+·040	+·004
Cuttack	0	—·005	—·008	—·024	—·051	—·024	—·030	—·011	—·027	+·042	—·047	+·038	—·012
False Point	+·007	—·007	—·014	—·027	—·057	—·034	—·038	—·012	—·019	+·049	—·044	+·035	—·013
Nagpur	+·002	—·010	—·002	—·012	—·025	+·005	0	—·014	+·004	+·049	—·031	+·050	+·001
Seoni	0	—·007	—·003	—·019	—·029	—·001	+·010	+·006	—·001	+·049	—·026	+·046	+·002
Jubbulpore	+·007	—·001	+·003	—·004	—·023	+·001	+·012	—·004	+·002	+ 059	—·028	+·060	+·007
Bombay	—·008	—·011	+·018	—·007	—·017	—·018	+·015	+·003	+·016	+·016	—·029	+·055	+·003
Vizagapatam	+·015	—·008	—·003	—·017	—·028	—·012	—·015	—·012	+·001	+·055	—·025	+·033	—·001
Masulipatam	—·016	+·002	P	P	P	P	P	P	P	P	P	P	P
Secunderabad	+·004	—·015	—·014	—·021	—·031	—·016	—·008	—·021	+·011	+·033	—·020	+·035	—·005
Bellary	—·008	—·014	—·019	—·017	—·020	—·023	—·014	—·036	+·007	+·010	—·037	+·027	—·013
Bangalore	—·003	—·006	—·001	—·009	—·016	—·011	—·004	—·033	+ 015	+·009	—·035	+·021	—·006
Madras	+ 002	—·007	—·007	—·009	—·024	—·003	+·003	—·029	+·019	+·039	—·013	+·040	+·001
Salem	—·005	—·001	—·005	—·005	—·022	—·016	—·006	—·038	+·015	+·024	—·034	+·018	—·006
Wellington	+·002	+·004	+·008	+ 011	+·002	+·014	+·019	0	+·037	+·024	—·018	+·019	+·010

TABLE XII B.—*Comparison of monthly mean pressures, in 1883, with the averages of more than 9 years*—concluded.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Coimbatore	+·003	—·002	+·006	+·011	—·011	+·011	+·014	—·014	+·038	+·032	—·017	+·044	+·010
Trichinopoly	+·023	+·017	+·006	+·013	—·002	+·015	+·027	—·004	+·041	+·043	—·004	+·051	+·019
Negapatam	—·004	—·021	+·005	—·002	—·019	+·004	+·006	—·019	+·022	+·027	—·020	+·030	+·001
Madura	+·006	+·008	+·006	—·023	—·005	0	+·013	—·023	+·029	+·024	—·018	+·015	+·003
Cochin	—·008	—·010	—·001	—·004	—·016	—·004	+·013	—·016	+·025	+·007	—·038	+·034	—·002
Colombo	—·008	—·004	+·009	+·005	—·010	+·003	+·008	—·019	+·006	+·009	—·029	+·048	+·002
Jaffna	+·006	+·009	+·006	+·001	—·012	+·005	+·013	—·018	+·031	+·021	—·021	+·038	+·007
Trincomalee	—·021	—·023	—·016	—·018	—·012	—·004	+·006	—·018	+·017	+·005	—·038	+·013	—·009
Batticaloa	—·033	—·026	—·012	—·014	—·028	—·013	—·012	—·037	+·021	+·026	+·001	P	P
Hambantota	+·026	+·020	+·025	+·008	—·005	—·004	+·009	—·015	+·022	+ 005	—·043	+·018	+·006
Galle	+·010	+·013	+·026	+·022	+·004	+·021	+·026	—·015	+·039	+·021	—·015	+·061	+ 018
Kandy	+·001	0	+·009	+·006	—·004	+·009	0	—·010	+·002	+·016	—·020	+·043	+·004
Akyab	+·015	—·005	—·002	—·010	—·009	—·015	—·027	—·007	+·012	+ 035	—·044	+·044	—·001
Port Blair	+·008	—·005	—·001	+·004	+·005	+·015	+·009	—·001	+·040	+·022	—·036	+·048	+·009
Nancowry	—·017	—·040	—·020	—·028	—·008	+·015	+ 013	—·019	+·003	—·020	—·049	+·021	—·012

TABLE XIII.—*Geographical Summary of the differences of Table XII A.*

PROVINCES.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
North-Western Himalaya	5–7	—·041	—·027	—·035	0	—·038	—·012	—·014	—·017	—·013	+·024	—·042	+·016	—·017
Sikkim Himalaya	14–16	+·014	—·012	—·013	—·005	—·021	+·004	+·001	—·009	+·011	+·032	—·032	+·035	0
Punjab plains	7–8	—·018	+·009	—·003	—·004	—·042	—·021	—·001	—·018	—·011	+·038	—·033	+·051	—·004
Gangetic plains	12	+·005	+·003	—·006	—·020	—·056	—·003	—·010	—·010	—·013	+·041	—·024	+·053	—·003
Western Rajputana, Sind, Cutch and Gujarat	7	—·024	+·006	+·002	—·015	—·033	—·026	—·002	—·006	—·007	+·022	—·022	+·061	—·004
Eastern Rajputana and Central India.	8–9	—·017	+·003	—·004	—·011	—·023	—·004	+·004	+·002	—·004	+·039	—·024	+·053	+·001
Nerbudda valley	3	—·015	—·005	—·001	—·009	—·019	—·006	0	—·003	—·001	+·037	—·025	+·058	+·001
Chutia Nagpur	1	+·007	—·006	—·002	—·015	—·052	—·011	—·011	—·004	—·017	+·046	—·029	+·039	—·005
Lower Bengal	6	+·016	—·002	—·006	—·017	—·061	—·015	—·022	—·007	—·014	+·039	—·029	+·048	—·006
Assam and Cachar	2–3	+·007	—·013	—·027	—·020	—·050	—·013	—·036	—·019	—·013	+·027	—·036	+·047	—·012
Orissa and Sambalpur	4	+·002	—·014	—·001	—·012	—·049	—·018	—·023	—·006	—·016	+·041	—·027	+·041	—·007
Central Provinces, South and Berar.	9	—·012	—·018	—·012	—·013	—·024	—·009	—·007	—·008	—·003	+·034	—·022	+·047	—·004

TABLE XIII.—*Geographical Summary of the differences of Table XII* —concluded.

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Konkan	4	−·009	−·016	+·006	−·003	−·013	−·027	+·004	−·004	+·019	+·016	−·012	+·057	+·002
Malabar Coast . . .	2	−·007	−·014	−·001	+·001	−·011	−·008	−·016	−·015	+·027	+·014	−·017	+·047	+·003
Deccan, Hyderabad and and Mysore.	7	−·008	−·014	−·007	−·008	−·019	−·020	−·007	−·022	+·008	+·009	−·026	+·035	−·007
East Coast and Carnatic .	7—8	−·005	−·011	−·004	−·004	−·017	−·006	0	−·023	+·015	+·023	−·014	+·035	−·001
Ceylon	6—7	−·008	−·008	+·001	0	−·012	−·006	+·001	−·024	+·013	+·008	−·023	+·039	−·002
Arakan and Pegu . .	5—7	+·011	·013	−·010	−·006	−·018	−·014	−·023	−·015	+·008	+·020	−·036	+·048	−·004
Tenasserim . . .	2	+·001	−·041	−·028	−·024	−·031	−·010	−·013	−·025	+·003	−·003	−·040	+·038	−·014
Bay Islands . . .	2	−·011	−·030	−·020	−·015	−·009	+·004	+·002	−·017	+·011	−·007	−·042	+·032	−·009

The above tables shew the variations in the horizontal distribution of pressure. Its variations in a vertical direction, or, in other words, the varying density of the lowest stratum which lies between the level of the plains and that of the hill stations, is shewn approximately by the differences of pressure on the former and at the latter; observing, however, that, as there must always be an interval of some miles between any hill station and the nearest station on the plains, these differences must also be affected to some small extent by a horizontal difference, of an amount not accurately determinable. If the pairs of stations are well selected, this horizontal difference will, however, not be large, when a comparison is made of the average pressures of a whole month; and if considerable accuracy is required, an approximate correction may be deduced, by considering the course of the isobars on the monthly charts, and the relative positions of the stations. For the present purpose, which is merely to compare the barometric weights of the lower air stratum in each month with that furnished by the average of many years, this precaution may be dispensed with; since the variations in the average course of the isobars, in the corresponding months of different years, are not sufficiently great, in most parts of India, appreciably to affect the results of such a comparison.

The following tables, XIV and XV, give the average differences of pressure at seven hill stations, and the nearest stations on the plains below, *viz.*, four Himalayan hill stations and three in peninsular India, the averages being in no case taken from a less average than three years. The pairs of stations selected, together with their horizontal distances and differences of elevation, are as follow:—

Pairs of Stations.		Horizontal distance.	Elevation in Feet.		Difference.
Hills.	Plains.		Upper.	Lower.	
I.—Simla . . .	Ludhiana	80 miles.	7,020	819	6,201
II.—Chakrata . . .	Roorkee	58 „	7,052	886	6,166
III.—Ranikhet . . .	Bareilly	90 „	6,069	568	5,501
IV.—Darjeeling . . .	Dhubri	116 „	7,421	115	7,206
V.—Pachmarhi . . .	Hoshangabad . . .	48 „	3,504	1,020	2 484
VI.—Chikalda . . .	Amraoti	40 „	3,656	1,213	2,443
VII.—Wellington . . .	Coimbatore . . .	20 „	6,200	1,348	4,852

TABLE XIV.—*Average differences of pressure at hill and plains stations.*

	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
I	9	5·903	5·886	5·768	5·642	5·572	5·504	5·536	5·557	5·599	5·691	5·825	5·890
II	9	5·855	5·841	5·717	5·600	5·543	5·476	5·515	5·535	5·563	5·660	5·768	5·832
III	9	5·336	5·301	5·198	5·091	5·044	4·998	5·015	5·047	5·077	5·167	5·254	5·328
IV	9	?	?	?	6·725	6·692	6·629	6·623	6·636	6·671	6·754	6·818	6·918
V	9	2·477	2·451	2·406	2·370	2·355	2·362	2·392	2·397	2·394	2·408	2·447	2·471
VI	7—8	2·345	2·328	2·279	2·260	2·247	2·269	2·287	2·298	2·296	2·308	2·346	2·359
VII	9	4·348	4·323	4·285	4·256	4·256	4·296	4·306	4·306	4·313	4·316	4·320	4·337

TABLE XV.—*Comparison of pressure differences in 1883, with the averages of Table XIV.*

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
I	+·010	+·032	+·032	+·009	—·012	+·006	+·005	—·011	+·005	+·017	+·008	+·050
II	+·027	+·016	+·029	—·023	—·014	+·013	+·012	+·008	+·016	+·012	+·016	+·044
III	+·040	+·029	+·025	—·009	—·019	+·011	+·013	+·002	+·004	+·024	+·024	+·038
IV	?	?	?	—·014	—·025	—·015	—·034	—·006	—·025	—·003	+·008	+·023
V	—·019	—·010	—·003	—·022	—·021	—·019	—·014	—·025	—·009	—·010	—·011	+·004
VI	+·019	+·009	+·022	—·002	—·003	+·010	+·013	—·010	+·011	+·007	—·002	+·022
VII	—·004	—·014	—·008	—·002	—·009	—·014	—·013	—·020	—·011	—·005	+·002	+·024

January.—In the final months of 1882, the pressure of the atmosphere over the North-West Himalaya, and especially at Leh, had been somewhat excessive; but owing to the high temperature and consequent low density of the lower atmospheric stratum, the pressure on the plains was considerably less than the average, not only in the Punjab, but also over the whole of Northern India. On the Himalaya also, from Kumaon eastwards, there was a decided deficiency. In January 1883, this slight excess on the North-West Himalaya disappeared, and was succeeded by a very marked depression, which also was much greater at Leh than at the stations on the outer Himalaya. This fall of pressure ushered in the usual winter rainfall, which, in its turn, brought about that reduction of the temperature noticed in the previous section; and while it diminished the pre-existing deficiency of pressure on the Punjab plains and the western half of the Gangetic plains, it brought about an excessive pressure to the east of Allahabad, which was greatest in Lower Bengal. In Rajputana, Gujarat, and Central India, on the other hand, the previous deficiency was increased, and a slight anomalous depression prevailed over the whole of the peninsula. In Burma, as in Eastern India, the pressure was slightly in excess of the average.

February.—The rainy weather at the end of January, and the resulting fall of tem-

perature on the plains of North-Western India, caused the pressure on the Punjab plains, the North-Western Provinces, Rajputana and Central India, to be somewhat in excess of the average, while the excess of the previous month in North-Eastern India, as well as in the Eastern Peninsula, tended to disappear. In Pegu and Tenasserim, indeed, it gave place to a marked deficiency, greatest in Tenasserim; and this extended over the south of the Bay of Bengal, diminishing westwards. In the Indian Peninsula the deficiency was rather greater than in January.

March.—On the North-West Himalaya the anomalous deficiency which had been most marked in January and had been but slightly less in February, was maintained, and on the plains of Northern India the slight excess of February disappeared, except in Sind and Gujarat, and at a few stations in Central India. In general, with this exception and that of the Konkan, the pressure was slightly, but very slightly, below the average, over the whole of India proper and in Burma, but the deficiency was more pronounced in Assam on the one hand and in Tenasserim and the south-east of the Bay on the other.

April.—The temperature of this month being generally high, an anomalous deficiency of pressure was almost universal on the plains of India, and generally greater than in March, but still nowhere exceeding —·020 inch, except perhaps in Tenasserim. The only exceptions, and those but slight, were one or two stations in the Punjab, and on the Malabar Coast and in Ceylon. In Tenasserim and the south-east of the Bay, the anomalous depression had diminished since February, but was still as marked as in any other part of the area. On the Himalaya the depression was less than on the plains, and at Murree there was a large local excess.

May.—The excessive temperature, combined with great dryness of the atmosphere, that prevailed during the first three weeks of May, caused a further reduction of the pressure below the normal average; and this both on the hills and the plains. Towards the end of the month the pressure rose, in consequence of the cooling effect of the wet weather that then set in; but not to such a degree as to compensate more than a small part of the deficiency of the earlier portion of the month. On the mean of the whole month, the average deficiency on the Punjab plains was —·042 inch, on the Gangetic plains —·036 inch, in Western Rajputana, Sind and Gujarat —·033 inch, and in Chutia Nagpur —·052 inch. It was greatest in Lower Bengal, *viz.*, —·061 inch; and in Orissa, Assam and Cachar —·050 inch. But it was less in the Central Provinces, Berar, Eastern Rajputana and Central India, *viz.*, —·023 inch, and in the Nerbudda valley only —·019 inch. In the peninsula it was equally general, and exceeded that of April, but was less than in Northern India. It was greatest in the Carnatic and least on the west coast, where it amounted to little more than —·010 inch. In Arakan, Pegu and Tenasserim also it was greater than in April, but not at the Bay Islands.

June.—In June the oscillations of pressure were very considerable. During the first few days the barometer remained unduly high, but a fall then took place, and it remained below the average till after the middle of the month, when the rains set in in Bengal. It then again rose, and except for a day or two, near the end of the month, just before rain set in in the Punjab, it remained above the normal average. The anomalies were therefore in a great measure mutually compensated; but, on the whole, the pressure of the whole region was slightly deficient, and most so in Western India (including the Konkan), and on the plateau of the peninsula. Only in the south-east of the Bay the depression of the previous month had disappeared.

July.—In the Eastern Punjab and the North-Western Provinces, the pressur remained more or less above the normal average through the first half of July; during which time, rain fell in heavy but partial showers; but in the latter part of the month, when a general break took place all over North-Western and Western India, the pressure fell and remained low up to, and beyond the end of the month. In Bengal, the Central Provinces, and Bombay, as well as in the Western Punjab, the oscillations were similar in phase, but the mean pressure was lower with reference to the normal average; except indeed in Bombay, where it remained above the average in the latter part of the month.

Thus, over a great part of India, the mean pressure of the month varied but little from the average. Indeed the only exceptions of importance were in Assam, where the deficiency amounted to —·036 inch; Bengal, Orissa and Arakan and Pegu, where it averaged from —·022′ to—·024 inch. In Rajputana and Central India, on the Konkan and Malabar coasts and in Ceylon, a slight excess of pressure prevailed.

August.—This was a dry month over the greater part of Northern India, the break in the rains which set in in the latter half of July having been prolonged nearly to the end of the month. At the beginning of the month the pressure was low, but it then rose, and notwithstanding the prevailing high temperature, due to the dryness of the air, an excessive pressure prevailed through the middle of the month for between two and three weeks, coinciding with the period of the greatest and most wide-spread drought. As in the previous month, the opposite phases of the oscillation nearly compensated each other, and in nearly all, the mean of the month differed but very little from the normal average. The relative local anomalies were almost the same as in July. In general, there was a very slight deficiency, but there was a very slight excess at some stations in Rajputana and Central India and on the coasts of Bombay, and the greatest abnormal depression (in Northern India) was in Bengal, but this was only about half as great as in July. In the peninsula and Ceylon, on the other hand, the deficiency was greater, amounting, in the Carnatic and Ceylon, to —·025, and it was about the same in Tenasserim.

September.—In September the barometric anomalies were in general no greater than in August, but their geographical distribution was different. A slight excess of pressure prevailed in the peninsula, greatest on the west coast, and especially in Malabar, while a slight deficiency obtained in Northern India, greatest on the Himalaya and Gangetic plain, Bengal and Assam. Thus, the whole anomaly was such as accompanies an unusual prevalence of westerly winds, and such really occurred, as will be seen in the next section of this report. In the Burmese Peninsula, the anomalies were as in India, a slight excess in the south, a slight deficiency in Assam.

October.—For the first time since May 1882, the mean pressure of nearly the whole Indian area ranged above the normal average of the month; the sole exceptions being in the south-east of the Indian region, in Tenasserim, and the adjacent portion of the Bay of Bengal. On the North-West Himalaya the excess was greatest in Kumaon, and diminished to the north-west, being only +·009 inch at Leh. In the Punjab it averaged +·038, inch, and was greatest at Sirsa and Dera Ismail Khan. On the Gangetic plain it averaged +·041 inch, and was nearly the same in Bengal and southward to the Satpuras. In the peninsula it was less, and especially on the Deccan plateau, at some stations on which it was evanescent. But it was greater in the Carnatic and Ceylon, where it averaged +·020 inch and upwards.

November.—In this month the pressure again fell below the normal average in all parts of the area, and most so over the North-West Himalaya and in Tenasserim and the south-east of the Bay; in both of which regions the deficiency amounted to —·040 or upwards. At Leh it was as much as —·050 inch. On the plains of India it was greatest in Assam and the Punjab. *viz.*, between —·030 inch and —·040 inch, and in the remainder of Northern India it varied between —·022 and —029 inch. In the peninsula and Ceylon it was almost as great, except on the west coast, where it was less than —·020 inch.

December.—December was cold and dry, in most parts of India a rainless month, and the pressure was remarkably high, the abnormal excess being greater than in October, and obtaining not only throughout the Indian area, but with equal magnitude at Bushire, Aden and Zanzibar. The Mauritius was beyond the limits of the area thus affected, in so far that the pressure was there somewhat (·013 inch) below the average, but the oscillations of this and the two previous months were similar in general character to those of India.

On the Himalaya, the excess of pressure was less than on any part of the plains, where it was in part due to the low temperature and high density of the lower atmosphere, and indeed, at Simla, the pressure was normal in amount. The greatest excess was at Deesa and Surat, where it amounted to ·075 inch, but it exceeded ·050 inch over the whole of Western and Central India, and was only slightly below that amount in Bengal and Chutia Nagpur, Assam and Orissa. It was least in the Carnatic, where it averaged ·031 inch, and was about the same in Ceylon and at the Bay Islands.

Taking the mean anomaly of all Indian and Burmese stations enumerated in Table XII A for each month of the year, the result is as follows:—

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
No. of stations	102	102	102	102	105	107	108	107	107	106	106	103
Mean anomaly	—·007	—·008	—·007	—·010	—·032	—·012	—·008	—·013	—·002	+·027	—·027	+·042

In every month of the year therefore, excepting October and December, the mean pressure was more or less below the average, and especially so in May and November. In October and December, the excess was such as in a great measure to compensate the deficiency of the remaining months, and, as the net result, the pressure of the whole year differed only by —·005 from the normal average of the whole area.

This deficiency was entirely due to the condition of the higher atmospheric strata. This results from several facts, shewn by the comparative tables of temperature and pressure. In the first place it has been shown that the temperature of the lower atmosphere was steadily below the average, except in the four months May to August; and even in May, when the deficiency of pressure was greatest, the temperature was only equal to the normal average. On the whole, therefore, it follows that the lower atmosphere was

denser than usual, and this conclusion is confirmed by the figures in Tables XV and XII A, the first of which shews that the barometric weight of the stratum of the North-Western Himalaya (about 6,000 feet in thickness) was ·013″ in excess (the evidence of the peninsular stations is too conflicting to be accepted as trustworthy); while the latter shews that above the level of the North-West Himalaya the deficiency was more than three times as great as on the plains of the Punjab. This result is entirely in accordance with the experience of former years, and it follows as a corollary, that the condition of the higher atmospheric strata is a factor of primary importance in influencing the general character of Indian weather. It affords also one more evidential proof of the general law which has been deduced from the statistics of former years that, as a general rule in India, the barometric condition of the lower atmospheric strata varies inversely with that of the higher strata; the former being more dense than the average, when the higher are less dense, and *vice versâ*.

WINDS.

The anemometric data consist of observations of the wind direction at 10 h. and 16 h. (10 A.M. and 4 P.M.) at the large majority of stations in Northern, Central, and Western India and Burma, at the extra Indian stations, Zanzibar, Aden, Bushire, &c., and at Mangalore and Mercara in Madras. At other Madras stations (except Vizagapatam), and also at Bangalore and Secunderabad, an observation at 22 h. (10 P.M.) is substituted for that at 4 P.M. At Leh (after August), Lahore, Mussooree, Dehra, Roorkee, Lucknow, Allahabad, Dhubri, Chittagong, Calcutta, Saugor Island, Cuttack, Hazaribagh, Nagpur, Pachmarhi (after August), Jeypore, Deesa, Bombay, Poona, Vizagapatam, and Rangoon, the directions are given for four diurnal periods, *viz.*, 4 h. (or 6 h. in the case of Calcutta, Leh, and Bombay), 10 h., 16 h., and 22 h., and at all these stations, except Vizagapatam, Allahabad, Leh, and Lahore, are taken from the traces of autographic instruments. At nearly all stations the total movement of the air, in 24 hours, is recorded by an anemometer. At Calcutta, Madras, Rangoon, Saugor Island, Chittagong, Lucknow, Roorkee, Mussooree, Nagpur, Pachmarhi, Bombay, and Deesa, the instruments are large Beckley's anemographs, of the Kew pattern; at Dehra, a smaller instrument of similar construction; at Dhubri, Cuttack, Hazaribagh, and Poona, Casella's embossing anemographs; and at other stations small anemometers with Robinson's cup and ball motors; in some cases with trains of five recording wheels, in others with two (Casella's improved pattern). A list of the elevations of the instruments at most stations in Northern India was given in the report for 1876, and some others are noticed in the description of the stations in previous reports.

Table VIII (Appendix) gives an abstract of the data, thus derived, for 127 stations, in 1883 (2 more than in the previous report). The abstract consists of the number of times that each of eight wind directions and calms was observed at each hour of record, and the total in each month; the trigonometrical resultant of these observations, computed by Lambert's formula (an equal value being given to each observation); and the mean diurnal movement of the air; also the average monthly values of the last two data, computed

from as many years (exceeding two) as have furnished anemometric registers at each station. The charts, Plates II to IV, shew these wind resultants by arrows, the lengths of which indicate the comparative excess of wind prevalence in the direction shewn, on a scale such that five-eighths of an inch would represent a wind blowing continuously in the same direction throughout the month, or 100 per cent. of the observations.

At Sirsa, the anemometer was removed from its former position on a post 23 feet above the ground to the roof of the Jail buildings 29 feet above the ground in January or February 1882. Up to June of the same year, the average value of the readings seems to have been but little affected by the change. But since July of that year, the average readings have been very low, the cause of which remains unexplained.

January.—In this month, the wind system of Northern and Central India was in many respects very different from that which is usually characteristic of January. In the Punjab, while the most striking feature of the season is the prevailing calmness of the atmosphere, such slight movement as there is, is, as a rule, predominantly from somewhat west of north, except towards the eastern limits of the Province, where it becomes more steady from between north-west and west-north-west, and preserves this character down the Gangetic plain to Lucknow and Allahabad and across Chutia Nagpur to Bengal. On the Bundelkhand plateau and in the Indus valley, it is chiefly from the north, and turns to north-east in the Central Provinces, and across the Satpuras to Berar and the Northern Deccan. To the west of the Aravallies the prevailing direction is between north-north-east and north-east, and the movement here is very strong and steady.

In the present year the northerly and westerly components in the Punjab and North-West Provinces were either in very small excess, or were outweighed by those from the opposite quarters. At Sialkot and Lahore easterly directions prevailed over westerly, and at Rawalpindi, Murree, Simla, Ludhiana, Sirsa, Delhi, and Agra, south or south-east winds were in actual excess, and largely so at the hill stations. So also at Neemuch, Indore, Khandwa, Saugor, Jubbulpore, in Berar, and especially on the Satpuras, where southerly winds were very dominant. In the Gangetic plain, west and north-west elements were in the ascendant, but very slightly so ; and in Bundelkhand the preponderance of northerly winds was much less than usual. Down the east coast of the peninsula, the north-east monsoon was of normal steadiness only to the south of the Kistna delta, and throughout was more easterly than usual, or less northerly.

Everywhere throughout India the feebleness of the northerly winds and the undue predominance of those from south and south-east was strongly manifested.

February.—In February, with the fall of temperature which followed on the heavy snowfall and rain at the end of January, the winds became rather such as normally characterise the latter month. In the Eastern Punjab and down the Gangetic plain, they were very steady from between west-north-west and west, becoming a little southerly at Benares, Ghazipur and Gorakhpur. In Bundelkhand and the Saugor and Nerbudda territories, they were pretty steady from between north and north-east ; and in Lower Bengal from north-west. Only in Berar and the Godavery valley, south or south-east winds continued to predominate, while, further south, both in the interior of the peninsula and on the east coast, south-east winds were in more than usual excess. Down the eastern side of the Bay of Bengal, north and north-east winds blew with quite the normal persistency.

March.—In general, the wind system of this month differed but little from the average of past years. In the upper part of the Gangetic valley there was rather less than the usual steadiness in the north-west and west winds, while in Bengal west winds were more than usually prevalent, and in Western Bengal stronger than usual. Down the west coast of the peninsula, west-north-west winds were very steady, with somewhat more than the usual northing, and northerly winds were also more than usually prevalent in the Deccan at Sholapur. In other respects there was but little noteworthy.

April.—The winds of April also were generally such as are usual in this month. In the Punjab and upper part of the Gangetic plain, the characteristic north-west and west winds were slightly more steady than on the general average of past years; and in Gujarat, Central India, Berar and the North Deccan, the directions were rather more northerly than usual; while in Bengal, Chutia Nagpur, and Sambalpur, they were very persistent from the south-west, and in Northern Bengal rather more easterly than usual.

May.—The chief characteristic of May was the remarkable steadiness of westerly winds throughout Northern and Central India. This is shewn equally on the Central Indian plateau and the Satpura region, where the normal direction is between north-west and west-north-west, and in the Gangetic delta, where, in this month, easterly elements, as a rule, rather predominate. In Northern Bengal, however, easterly winds were quite as prevalent as usual, and at Patna north-east winds much more so. Elsewhere the directions were such as are normal in this month.

June.—At Murree and Rawalpindi there was a large and unusual preponderance of winds from between south and south-west, at Simla from between west and north-west, and at Chakrata and Ranikhet from west-south-west or south-west. But, along the foot of the hills, in Oudh, and at Allahabad and Benares, easterly, and in the latter instances north-east winds, were more than usually prevalent; while to the south of the Ganges, in Bundelkhand, at Saugor and Jubbulpore, and also at Pachmarhi, they were very steady from between north-west and west, and more northerly than usual. At Bikaneer and Ajmere (especially the latter) they were more westerly and less southerly than in most years.

July.—Instead of the easterly or south-easterly winds, which, in general, preponderate largely in July at the stations in the north and east of the Punjab, the directions were very variable. In the Derajat they were chiefly north-east, at Rawalpindi south, at Lahore west or east, and on the whole northerly; and at Sirsa west or southerly. In the Gangetic valley also, above Gorakhpur, similar characteristics prevailed, and on the plateau of Rajputana and Central India the directions were more west and less south-west than usual. There was a marked abnormal preponderance of westerly winds also in the Central Provinces, especially the eastern districts, and at Calcutta; but in Northern Bengal the directions were more normal and easterly. On the west coast of the peninsula also, there was more than the usual preponderance of westerly winds, and a similar feature was apparent at many stations in the interior, *e.g.*, Poona, Secunderabad, Belgaum, Bellary and Bangalore. In some instances, and especially at Sholapur and Bangalore, the mean movement of the wind was greatly in excess of the general average of former years.

August.—Except in Western Rajputana and the Indus valley, the undue prevalence and predominance of winds from the west and north-west were a strongly-marked feature of this month throughout North-Western and Central India, and indeed further south, in the

Konkan and the Western Deccan. Even in Bengal, easterly winds, although preponderant, were considerably less so than in most years, and at Hazaribagh there was a large excess of north and north-west winds.

In the remarkable prevalence of winds of this character, is to be found the immediate explanation of the atmospheric dryness and the deficient rainfall, which, as will be seen in the subsequent sections of this report, characterised the greater part, or the whole of August.

September.—In this month the winds were less anomalous. There was still an undue excess of winds from west or north-west, and a deficiency of those from south-west, at Pachbudra, Bikaneer, Ajmere, Delhi, Roorkee, Meerut, in Berar, and to some extent in the Central Provinces, except the southern districts; and especially an excess of north-west over easterly winds at Sambalpore and Hazaribagh. But at Chanda and Sironcha, at Cuttack, Vizagapatam and Masulipatam, southerly winds, and in the interior of the peninsula, at Hyderabad and Sholapur, south-westerly winds either predominated or were more than usually prevalent. At Dacca, Chittagong, and on the Arakan coast, they were very steady from between south and south-east, less easterly and much more southerly than usual; and on the coast of Pegu they were more than usually steady from the south-west. This was also the case at Port Blair and Nancowry.

October.—At most of the Punjab stations, and in Western Rajputana, the winds were very light and variable, and in contrast to the preceding months, north-west winds were less predominant than usual, except at Pachbudra, where the usual excess of south-west winds failed. On the Gangetic plain, on the other hand, as far down as Patna, north-west winds were more than usually prevalent, and to the south of the Ganges, in Bundelkhand and at Raipur and Sambalpur, north and north-east winds were unduly predominant. At Indore and in the Nerbudda valley, on the Satpuras, and in Berar and Nagpur, north-east and easterly elements were in unusual excess, and this was also the case very prominently at Hyderabad and Sholapur, and to a certain extent even further south. On the east coast of the peninsula, the winds were more easterly than usual, and in the south of the peninsula, the north-east monsoon prevailed with marked predominance. On the Arakan coast and in Pegu, northerly winds were in decided excess, which is not the rule in this month. In general, therefore, the northerly winds were established throughout Central and Eastern India earlier than usual.

At Port Blair, south-east winds were in more than usual excess, and at Nancowry, instead of the usual large predominance of south-west winds, the directions were chiefly from south-east.

November.—In the Punjab, the anomalous characteristic of the atmosphere was the same as in the previous month, but much more pronounced. Instead of the usual decided predominance of light north-west winds, the atmosphere was remarkably calm, and such slight air movement as there was, was extremely variable in direction. On the North-West Himalaya, where the movement was greater, its direction was equally unsteady, but there was a slight excess of north-west winds at Simla, Chakrata and Paori, and of south-west winds at the more eastern stations of Ranikhet and Pithoragarh.

On the Gangetic plain, there was a decided prevalence of north-west winds in the upper part, and west winds in the lower half, but the former had less than their usual steadiness; while at Agra and to the south of the Ganges, at Ajmere, Jhansi and Now-

gong, north-west winds were more steady than usual; and at the latter stations north and north-east winds less so. The east-north-east current which usually prevails steadily in the region of the Nerbudda and the Satpuras, and in Berar and Nagpur, was less so than usual, while in the eastern districts of the Central Provinces the directions were unusually steady from the north.

In Bengal the winds were more of the normal character, only somewhat more northerly, and down the east coast of the peninsula the north-east monsoon prevailed with more than the usual steadiness. In the interior of the peninsula also, north-east winds were somewhat more than usually prevalent, and this feature was especially marked at Bangalore, Salem, and Madura.

On the west coast of the peninsula the directions were less easterly than usual, and at Karwar there was a considerable excess of north-west winds.

At Port Blair the prevailing winds were from the east rather than from north-east, and not very steady, and at Nancowry somewhat more southerly than usual.

December.—The winds of this month differed less from the normal system than did those of the preceding months. In the Central and Southern Punjab, and on the North-West Himalaya, the atmosphere was still characterized by great calmness, much as in November; but down the Gangetic plain, except near the hills, the north-west winds blew very steadily, and in the Nerbudda and Satpura regions north-east and east winds were more than usually dominant; while, to the south of Bikaneer, the north-east current set very steadily to the west of the Satpuras. In the eastern half of the peninsula, winds from between north and north-east blew very steadily at all stations, and the same is true of the monsoon on the east coast. Throughout the interior of the peninsula, the prevailing direction was east-north-east, being more northerly than usual, a feature more especially marked in Hyderabad and the Deccan; and a certain unusual easterly, or off-shore, tendency was also displayed by the winds on the west coast.

On the Arakan Coast, in Pegu, and at Port Blair, there was a marked abnormal preponderance of easterly winds. But at Nancowry the direction was more normal, chiefly from the south-east and east.

HYGROMETRY.

The hygrometric data for the year are given in Tables X, XI, and XII of the Appendix. The first of these gives the monthly means of the readings of the wet-bulb thermometer, at each hour of observation, that of the minimum wet-bulb the mean range, and the adopted mean wet-bulb temperature of each month; which, in nearly all cases, is the average of the 10h., 16h., and minimum readings; also the difference of these several values and the corresponding air temperatures. The mode of exposure adopted for the hygrometers has been already described in the section on air temperature, and is such that the wet-bulb is freely exposed to the winds. This is an essential condition; and when a gentle, or even moderately strong breeze is blowing, it has been found that the temperature of the wet-bulb thermometer approximates very closely to that assumed in Regnault's hygrometric formula; but in a perfectly calm state of the atmosphere, the vapour which is given off from the wet-bulb is not removed with

sufficient rapidity, and the temperature marked is somewhat too high. The free exposure of the thermometer, under an open shed, reduces this cause of error to a minimum; but at certain seasons of the year, and at certain stations, it probably still affects the readings to some small extent.

The second table (XI of the Appendix) shows the mean vapour-tensions of the several months, and those of hours of observation, and also those deduced from the readings of the minimum dry and wet bulbs; and the third table (XII of Appendix) the mean relative humidities similarly obtained. In all cases, including those of the Ceylon stations, the hygrometric data are taken from the tables accompanying the *Vade-mecum*, which are computed to the vapour-tension of latitude 22°, by means of Regnault's modification of August's formula. In this, a constant barometric pressure is assumed for the same station, *viz.*, 29·7 inches for stations up to 1,000 feet elevation; 27·7 inches for stations between 1,000 and 3,000 feet; 25·8 inches for those between 3,000 feet and 5,000 feet; and 23·5 inches for the hill stations of the Nilgiris and the Himalayas, all of which are beteewn 6,000 and 8,000 feet.

The four tables which follow, (Tables XVI to XIX) show the average vapour-tension and relative humidity, computed from as many years as have yielded comparable data, and the differences of these averages and those of the year 1883. In these tables of averages for 123 stations in India, Burma, &c., I have included only two classes of data, namely, those deduced from the 10h., 16h., and minimum readings, and those formerly recorded at six-hourly intervals at certain stations. The difference of the results obtained by these two methods is insufficient, seriously to affect the general validity of the averages; and they may be used as a fair approximation for the purpose of comparison, until such time as the discussion of the hourly observations recorded for some years past at several of the leading stations, shall afford the means of correcting the whole, more accurately, to a common standard.

In the case of the Ceylon stations, the averages given are those of the observations of 9 h. 30 m. and 15 h. 30 m. only.

Tables XX and XXI give a geographical summary of the data of Tables XVIII and XIX, on a plan similar to that adopted in the case of Tables X and XIII, in previous sections of this report.

TABLE XVI.—*Average monthly mean vapour-tension of 123 Stations in India, Ceylon, &c.*

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar . .	3—4	·820	·842	·855	·840	·782	·694	·679	·657	·683	·732	·792	·813	·766
Aden . . .	3—4	·628	·639	·706	·744	·857	·833	·768	·782	·824	·703	·624	·631	·728
Mauritius . .	12—13	·744	·750	·736	·703	·610	·544	·510	·521	·527	·560	·618	·707	·628
Bushire . .	5—7	·349	·324	·394	·504	·648	·751	·891	·937	·820	·638	·500	·384	·595
Quetta . . .	4—6	·154	·159	·217	·244	·267	·319	·410	·329	·211	·194	·146	·141	·233
Leh . . .	3	·064	·070	·088	·103	·127	·188	·266	·271	·189	·099	·074	·070	·134

TABLE XVI.—*Average monthly mean vapour-tension of 123 Stations in India, &c.*—continued.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Mooltan . .	7—9	·255	·256	·369	·439	·598	·765	·855	·876	·798	·537	·342	·261	·529
Dera Ismail Khan .	7—8	·225	·222	·324	·400	·462	·662	·831	·857	·691	·425	·282	·231	·468
Peshawar . .	7—8	·220	·221	·322	·408	·438	·518	·694	·741	·593	·367	·261	·227	·418
Murree . .	6—7	·133	·144	·183	·241	·274	·378	·527	·541	·430	·239	·164	·137	·283
Rawalpindi . .	8—9	·244	·264	·348	·437	·531	·642	·778	·804	·673	·426	·301	·243	·474
Sialkot . . .	6—9	·292	·302	·379	·391	·443	·627	·845	·869	·748	·471	·320	·295	·499
Lahore . . .	9	·259	·279	·353	·384	·437	·596	·842	·838	·726	·462	·311	·277	·480
Ludhiana . .	6—9	·266	·302	·364	·432	·514	·627	·852	·844	·780	·492	·302	·268	·504
Simla . . .	3—6	·163	·160	·206	·276	·323	·446	·543	·536	·481	·267	·192	·141	·311
Delhi . . .	6—9	·274	·281	·340	·370	·525	·695	·859	·826	·751	·471	·313	·261	·497
Sirsa . . .	6—8	·228	·245	·318	·366	·455	·588	·799	·775	·668	·367	·247	·227	·440
Chakrata . .	6—8	·152	·157	·192	·229	·285	·413	·539	·536	·477	·274	·197	·145	·300
Mussooree (*St. Fidelis*)	3—6	·192	·193	·233	·265	·346	·484	·617	·602	·566	·361	·286	?	?
Paori . . .	3	?	?	?	?	?	·568	·654	·637	·591	·352	·258	?	?
Roorkee . .	7—8	·281	·294	·347	·340	·434	·644	·866	·847	·768	·495	·331	·276	·494
Ranikhet . .	8	·185	·188	·230	·267	·332	·469	·575	·569	·517	·330	·238	·184	·340
Pithoragarh . .	3	?	?	?	?	·371	?	?	?	·587	·366	·250	·205	?
Meerut . .	6—8	·279	·311	·389	·452	·532	·682	·863	·845	·746	·494	·329	·278	·517
Bareilly . .	7—8	·308	·319	·401	·431	·558	·747	·911	·892	·814	·559	·369	·295	·550
Agra . . .	8	·278	·276	·321	·350	·462	·664	·893	·864	·775	·473	·299	·268	·494
Lucknow . .	8	·293	·307	·380	·442	·575	·757	·909	·898	·829	·565	·344	·290	·549
Gorakhpur . .	6—8	·344	·350	·443	·472	·681	·865	·943	·942	·908	·684	·428	·348	·617
Jhansi . . .	8	·272	·269	·316	·355	·461	·674	·841	·829	·766	·484	·289	·256	·484
Allahabad . .	8—10	·340	·346	·387	·429	·565	·779	·953	·942	·900	·635	·409	·340	·585
Benares . .	7—8	·311	·315	·346	·385	·558	·769	·921	·921	·872	·661	·390	·305	·563
Katmandu . .	3—4	·256	·251	·304	·367	·514	·653	·697	·689	·634	·486	·323	·274	·454
Sibsagar . .	9	·418	·449	·532	·665	·777	·914	·938	·931	·909	·780	·587	·443	·695
Dhubri . .	3	?	?	?	·660	·776	·905	·951	·929	·902	·776	·572	·475	?
Silchar . . .	9	·424	·448	·581	·725	·792	·912	·933	·919	·906	·808	·620	·475	·712
Darjeeling (*St. Paul's School*) .	7—8	·199	·205	·250	·323	·400	·503	·520	·508	·487	·365	·268	·209	·353
Purneah . .	6—9	·365	·378	·457	·604	·781	·924	·979	·970	·946	·767	·518	·410	·675
Durbhunga . .	6—8	·392	·380	·452	·553	·760	·918	·962	·959	·947	·774	·526	·424	·671
Patna . . .	8—9	·354	·369	·416	·474	·709	·881	·948	·947	·916	·700	·447	·362	·627
Gya . . .	8—9	·316	·318	·380	·575	·721	·860	·932	·925	·898	·670	·425	·329	·612

TABLE XVI.—*Average monthly mean vapour-tension of 123 Stations in India, Ceylon, &c.*—contd.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Hazaribagh	8—9	·262	·259	·303	·325	503	·692	·819	·801	·769	·544	·352	·261	·491
Berhampore	8—9	·384	·403	·527	·650	·809	·927	·949	·938	·930	·784	·545	·419	·689
Burdwan	8—9	·413	·432	·568	·702	·847	·959	·976	·968	·960	·816	·558	·423	·719
Jessore	8—9	·420	·458	·620	·785	·888	·975	·982	·969	·960	·851	·590	·440	·745
Dacca	8	·433	·450	·628	·799	·879	·974	·980	·974	·971	·863	·621	·478	·754
Chittagong	7—8	·463	·514	·679	·818	·861	·793	·910	·913	·921	·855	·686	·524	·745
Calcutta (*Alipore*)	6—7	·433	·513	·667	·821	·886	·976	·971	·970	·962	·849	·585	·440	·756
Ditto (*Chowringhee*).	3—4	·451	·495	·657	·814	·899	·978	·979	·967	·965	·840	·562	·452	·755
Saugor Island	15—16	·533	·642	·823	·942	·991	1·031	1·008	1·002	·988	·869	·639	·506	·831
Cuttack	7—8	·463	·523	·647	·753	·828	·898	·901	·910	·905	·790	·582	·446	·721
False Point	4—6	·520	·629	·744	·868	·926	·949	·927	·933	·934	·831	·601	·462	·777
Sambalpur	7—8	·467	·511	·564	·606	·734	·850	·913	·924	·922	·785	·566	·436	·690
Raipur	8—9	·356	·377	·381	·441	·500	·738	·833	·833	·819	·660	·454	·346	·562
Nagpur	8—9	·342	·337	·330	·360	·438	·705	·805	·788	·776	·579	·399	·330	·516
Seoni	7	·320	·327	·323	·367	·452	·686	·763	·753	·721	·534	·368	·301	·493
Jubbulpore	8—9	·316	·325	·338	·345	·407	·688	·810	·803	·785	·572	·364	·294	·504
Saugor	5—7	·247	·248	·282	·323	·361	·568	·747	·778	·735	·492	·276	·246	·442
Pachmarhi	8—9	·262	·244	·247	·245	·361	·596	·672	·663	·637	·436	·290	·257	·409
Hoshangabad	7—8	·327	·316	·314	·335	·458	·737	·822	·816	·798	·598	·385	·328	·520
Khandwa	7—9	·332	·348	·324	·367	·501	·717	·778	·765	·752	·548	·353	·321	·509
Chanda	7—8	·408	·417	·427	·456	·517	·746	·811	·823	·824	·701	·508	·397	·586
Sironcha	7—8	·447	·473	·509	·561	·612	·781	·826	·846	·840	·725	·563	·448	·636
Chikalda	7—8	·309	·316	·323	·277	·370	·575	·648	·639	·627	·468	·366	·298	·435
Buldana	6—8	·311	·311	·310	·360	·490	·675	·707	·695	·698	·557	·409	·339	·489
Akola	7—8	·303	·286	·293	·275	·404	·679	·753	·740	·737	·563	·382	·306	·477
Amraoti	7—8	·316	·333	·326	·366	·448	·701	·757	·739	·728	·530	·378	·308	·494
Neemuch	6—7	·210	·221	·259	·280	·407	·611	·725	·717	·686	·433	·241	·214	·417
Nowgong	4—7	·271	·286	·307	·407	·418	·737	·862	·844	·803	·528	·313	·282	·505
Sutna	7—8	·251	·234	·239	·271	·374	·621	·815	·812	·763	·498	·277	·226	·448
Indore	5—6	·233	·236	·242	·256	·424	·668	·750	·739	·721	·495	·279	·215	·438
Bickaneer	3—7	·179	·261	·309	·396	·506	·680	·779	·786	·739	·469	·247	·184	·461
Jeypore	3	·284	·278	·332	·326	·461	·716	·853	·773	·704	·415	·267	·281	·474
Sambhar	3—4	·250	·242	·309	·371	·508	·648	·803	·740	·688	·400	?	·234	?
Ajmere	7—8	·261	·264	·334	·400	·535	·663	·756	·762	·704	·468	·300	·264	·476

TABLE XVI.—*Average monthly mean vapour-tension of 123 Stations in India, Ceylon, &c.*—contd.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Mount Abu	6—8	·183	·176	·202	·246	·336	·546	·620	·586	·547	332	·221	·207	·350
Pachbudra	3—5	·237	·190	·297	·427	·648	·801	·819	·752	·701	·443	·227	·223	·480
Jacobabad	5—7	·212	·218	·355	·445	·537	·687	·808	·825	·722	·485	·309	·244	·487
Hyderabad	4—7	·285	·273	·390	·504	·647	·764	·801	·804	·774	·522	·407	·287	·538
Kurrachee	8—9	·353	·415	·604	·701	·886	·958	·909	·850	·840	·661	·449	·395	·668
Bhuj	6—8	·278	·301	·400	·492	·665	·789	·801	·763	·736	·529	·292	·283	·527
Rajkot	5—7	·195	·220	·302	·352	·559	·719	·779	·744	·730	·500	·252	·220	·464
Deesa	9	·264	·245	·334	·362	·603	·734	·824	·789	·756	·452	·289	·275	·494
Surat	6—7	·375	·382	·484	·562	·731	·819	·858	·829	·836	·703	·493	·417	·624
Malegaon	6—7	·251	·318	·294	·320	·510	·702	·715	·694	·694	·541	·357	·303	·475
Bombay	37	·579	·611	·717	·820	·883	·930	·914	·884	·870	·846	·698	·622	·781
Poona	8—9	·323	·303	·330	·394	·511	·688	·695	·681	·669	·539	·415	·314	·489
Sholapur	6—7	·331	·302	·319	·360	·429	·599	·628	·636	·647	·559	·468	·356	·470
Ratnagiri	7	·572	·609	·730	·812	·839	·858	·868	·854	·844	·809	·674	·562	·753
Belgaum	8—9	·360	·343	·418	·522	·599	·660	·669	·656	·645	·582	·477	·370	·525
Karwar	4—6	·603	·662	·776	·844	·876	·840	·823	·835	·813	·819	·733	·604	·769
Vizagapatam	14	·587	·644	·749	·848	·915	·888	·858	·881	·887	·815	·659	·547	·774
Masulipatam	8—9	·620	·668	·782	·889	·931	·859	·836	·852	·846	·828	·734	·630	·790
Secunderabad	9	·404	·396	·427	·454	·480	·622	·660	·668	·684	·587	·473	·394	·521
Bellary	8—9	·405	·344	·367	·472	·560	·654	·653	·655	·654	·614	·545	·452	·531
Mangalore	3—4	·598	·669	·789	·870	·867	·857	·839	·834	·828	·826	·763	·633	·781
Mercara	3—4	·423	·394	·499	·603	·626	·604	·580	·589	·577	·580	·551	·444	·539
Bangalore	8—9	·394	·393	·459	·545	·593	·617	·606	·610	·598	·586	·532	·444	·531
Madras	9	·620	·643	·750	·842	·835	·762	·750	·779	·779	·794	·741	·664	·747
Salem	9	·543	·520	·591	·693	·748	·745	·734	·749	·739	·749	·687	·611	·676
Wellington	6—7	·302	·277	·342	·395	·442	·441	·416	·438	·418	·438	·410	·333	·388
Coimbatore	8—9	·484	·472	·574	·667	·692	·670	·654	·674	·655	·681	·641	·556	·618
Trichinopoly	9	·599	·610	·661	·715	·730	·705	·686	·708	·715	·756	·723	·650	·688
Negapatam	8—9	·683	·683	·774	·880	·856	·774	·754	·787	·796	·811	·774	·714	·774
Madura	6—8	·625	·612	·662	·717	·740	·712	·683	·708	·708	·746	·722	·672	·692
Cochin	9	·696	·753	·844	·889	·893	·854	·837	·829	·831	·833	·811	·734	·817
Colombo	14	·760	·776	·825	·884	·907	·878	·859	·852	·853	·839	·820	·777	·836
Jaffna	13	7 2	·746	·842	·953	1·008	·963	·923	·932	·937	·912	·860	·804	·885
Trincomalee	11—13	·748	·760	·822	·841	·831	·810	·794	·793	·785	·804	·827	·792	·801

TABLE XVI.—*Average monthly mean vapour-tension of 123 Stations in India, Ceylon, &c* —concld.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Batticaloa	13—14	.796	·805	·857	·900	·902	·857	·851	·856	·859	·874	·852	·827	·853
Hambantota	12—14	·826	·843	·873	·912	·923	·891	·875	·878	·878	·877	·872	·849	·875
Galle	14—15	·839	·845	·870	·909	·933	·924	·916	·904	·918	·904	·883	·854	·892
Kandy	13—14	·647	·629	·679	·742	·766	·735	·718	·713	·712	·718	·710	·684	·704
Newera Eliya	12—14	·382	·347	·367	·405	·444	·450	·431	·433	·430	·437	·420	·405	·413
Akyab	6—8	·492	·533	·693	·831	·894	·924	·918	·918	·918	·886	·758	·601	·781
Thayetmyo	5—7	·482	·454	·619	·726	·828	·890	·901	·894	·894	·864	·743	·582	·740
Tounghoo	4—7	·540	·551	·630	·722	·806	·852	·866	·867	·877	·869	·778	·656	·751
Bassein	6—7	·578	·607	·708	·797	·865	·906	·896	·898	·896	·896	·826	·696	·797
Diamond Island	5—6	·643	·696	·792	·872	·908	·899	·889	·885	·881	·883	·813	·718	·823
Rangoon	7—8	·576	·583	·674	·804	·877	·908	·889	·900	·901	·905	·810	·694	·793
Moulmein	6—7	·569	·616	·717	·793	854	·870	·859	·866	·867	·867	·771	·669	·777
Mergui	6—7	·705	·789	·831	·885	·900	·865	·855	·866	·863	·858	·797	·724	·828
Port Blair	6—8	·805	·832	·885	·934	·952	·918	·904	·902	·897	·915	·892	·852	·891
Nancowry	8—9	·793	·810	·841	·885	·890	·880	·867	·855	·854	·865	·857	·815	·851

TABLE XVII—*Average monthly mean relative humidity of 123 Stations in India, Ceylon, &c.*

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	3—4	77	79	78	81	81	73	76	73	74	76	78	78	77
Aden	3—4	70	69	71	67	69	63	66	65	64	62	65	70	67
Mauritius	12—13	75	76	77	76	74	73	72	73	72	71	71	74	74
Bushire	5—7	73	69	67	63	59	61	64	65	65	63	67	70	66
Quetta	4—6	63	64	57	48	38	36	45	39	33	39	48	55	47
Leh	3	58	58	50	39	38	35	46	48	43	38	45	54	46
Mooltan	7—9	59	52	51	45	45	50	59	63	62	56	52	56	54
Dera Ismail Khan	7—8	55	50	48	45	38	44	60	64	56	47	50	55	51
Peshawar	7—8	60	56	56	53	41	38	52	58	55	47	55	61	53
Murree	6—7	53	59	51	50	45	47	73	78	67	45	44	48	55
Rawalpindi	8—9	70	69	63	57	50	49	65	72	66	56	63	67	62
Sialkot	6—9	70	67	58	42	37	44	67	72	65	53	56	68	58
Lahore	15—18	59	56	48	36	31	36	58	60	54	45	46	55	49

TABLE XVII.—*Average monthly mean relative humidity of 123 Stations in India, Ceylon, &c.*—contd.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Ludhiana . .	6—9	63	63	55	49	45	48	68	68	66	54	52	60	58
Simla . . .	3—6	58	56	53	50	49	66	88	90	82	52	52	45	62
Delhi . . .	6—9	57	50	43	33	40	46	68	65	64	48	47	50	51
Sirsa . . .	6—8	53	49	43	35	35	39	60	59	55	37	38	50	46
Chakrata . .	7—9	62	63	53	46	52	67	91	91	83	59	58	50	65
Mussooree (*St. Fidelis*).	3—6	58	58	53	43	51	68	92	91	87	61	59	?	?
Paori . . .	3	?	?	?	?	?	70	85	85	80	61	65	?	?
Roorkee . .	14—16	65	62	51	35	36	52	76	76	72	59	56	62	59
Ranikhet . .	9	60	59	53	45	53	64	85	86	80	61	57	54	63
Pithoragarh . .	3	?	?	?	?	56	?	?	?	79	58	56	55	?
Meerut . .	8—9	62	57	52	41	42	48	71	71	66	55	54	61	57
Bareilly . .	8—9	65	61	54	40	45	56	77	77	73	61	58	62	61
Agra . . .	8—9	56	48	39	29	33	44	72	71	66	47	43	51	50
Lucknow . .	8—9	59	53	44	36	43	54	74	76	72	60	53	57	57
Gorakhpur . .	7—9	65	60	52	42	56	68	79	81	78	69	59	63	64
Jhansi . . .	8—9	48	42	35	28	31	46	74	74	70	47	39	44	48
Allahabad . .	8—9	68	58	44	34	41	55	80	81	80	68	63	67	62
Benares . .	13—	63	56	43	35	41	58	80	81	79	66	61	63	61
Katmandu . .	3—4	75	69	63	60	71	78	80	83	79	74	73	74	73
Sibsagar . .	9	85	81	79	81	82	83	83	84	85	84	83	85	83
Dhubri . .	3	?	?	?	69	81	87	85	87	88	82	75	78	?
Silchar . .	12—14	75	71	73	76	81	85	85	86	85	82	77	77	79
Darjeeling (*St. Paul's School*).	15—16	79	78	72	75	87	95	95	94	95	80	95	74	85
Purneah . .	5—8	67	61	55	56	69	79	85	85	83	77	69	70	71
Durbhanga . .	6—8	70	63	54	51	66	77	83	84	83	77	69	74	71
Patna . . .	12—14	67	59	47	42	56	68	81	82	80	70	61	64	65
Gya . . .	11—12	55	46	38	40	50	64	80	81	78	66	56	56	59
Hazaribagh . .	14—16	51	44	36	32	43	66	85	85	82	65	54	51	58
Berhampore . .	14—16	69	64	58	61	72	82	86	86	85	78	73	71	74
Burdwan . .	8—9	66	59	56	58	69	78	84	85	83	76	65	65	70
Jessore . .	13—14	68	63	63	68	76	84	87	87	86	81	72	69	75
Dacca . . .	15—16	69	65	68	74	80	87	87	87	86	81	72	71	77
Chittagong . .	15—16	72	70	73	77	80	85	87	87	86	83	78	75	79
Calcutta (*Alipore*) .	6—7	70	69	69	72	77	85	88	89	88	84	74	72	78

TABLE XVII.—*Average monthly mean relative humidity of 123 Stations in India, Ceylon, &c.*—contd.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Calcutta (*Chowringhee*)	3—4	67	64	67	69	77	87	89	89	87	81	69	69	76
Saugor Island	14—16	76	77	79	80	80	84	86	87	86	82	74	74	80
Cuttack	15—16	65	63	62	63	65	74	81	82	82	76	68	66	71
False Point	13—16	79	80	83	85	83	83	85	85	84	80	72	74	81
Sambalpur	7—8	67	61	53	46	51	67	83	85	82	75	70	67	67
Raipur	8—9	54	49	39	36	36	63	82	82	79	68	61	55	59
Nagpur	8—9	50	41	31	27	29	60	79	77	76	60	53	50	53
Seoni	7	52	46	35	31	35	63	81	81	77	62	54	51	56
Jubbulpore	8—9	58	51	38	30	29	58	81	81	79	65	57	56	57
Saugor	5—7	44	38	31	28	28	46	75	81	77	54	40	41	49
Pachmarhi	8—9	51	42	32	25	32	64	89	89	83	61	52	52	56
Hoshangabad	8	51	44	33	26	31	58	81	83	79	63	53	54	55
Khandwa	7—9	50	45	33	29	35	59	77	78	77	58	49	50	53
Chanda	7—8	59	51	41	34	34	60	77	79	80	72	67	61	60
Sironcha	7—8	60	52	45	40	42	65	78	81	81	72	68	64	62
Chikalda	7—8	50	45	36	26	35	69	91	92	89	62	55	50	58
Buldana	6—8	43	38	30	30	39	66	79	80	81	62	52	48	54
Akola	7—8	44	35	27	21	27	58	73	74	74	60	50	48	49
Amraoti	7—8	43	39	31	28	32	62	77	76	75	56	48	44	51
Neemuch	6—7	39	36	30	24	32	51	73	75	71	47	35	39	46
Nowgong	4—7	54	48	36	32	35	52	76	75	72	55	50	55	53
Sutna	7—8	48	40	29	24	28	48	75	76	72	54	43	44	48
Indore	5—6	38	36	29	23	33	61	81	81	80	55	42	41	50
Bickaneer	3—7	36	42	34	30	33	42	56	62	58	41	34	35	42
Jeypore	3	53	46	42	28	35	54	80	71	66	44	42	50	51
Sambhar	3—4	49	42	40	32	37	47	73	68	64	41	?	44	?
Ajmere	9	49	46	41	36	39	49	69	73	68	50	44	49	51
Mount Abu	6—8	37	34	29	28	36	65	85	85	75	43	36	40	49
Pachbudra	3—5	45	36	37	38	49	56	67	67	62	44	37	43	48
Jacobabad	5—7	43	38	42	40	37	43	53	58	55	47	45	48	46
Hyderabad	4—7	50	42	41	42	46	54	61	65	63	47	51	49	51
Kurrachee	8—9	55	59	66	68	73	75	78	78	76	65	55	58	67
Bhuj	6—8	42	41	42	44	52	61	70	70	68	50	35	41	51
Rajkot	5—7	30	30	33	34	45	58	71	72	73	47	30	32	46

TABLE XVII.—*Average monthly mean relative humidity of 123 Stations in India, Ceylon, &c.*—contd.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Deesa . . .	8—9	37	32	32	28	41	53	74	73	69	43	35	38	46
Surat . . .	6—7	51	48	50	49	58	68	79	78	79	64	55	54	61
Malegaon . .	6—7	36	37	29	26	40	63	72	72	72	56	46	42	49
Bombay . .	28	69	69	73	75	74	82	88	87	86	81	71	70	77
Poona . . .	8—9	41	33	30	31	43	70	79	79	76	57	46	39	52
Sholapur . .	6—7	41	34	30	28	34	58	64	66	69	59	54	47	49
Ratnagiri . .	7	60	63	70	70	70	81	86	85	85	77	65	59	73
Belgaum . .	8—9	47	39	41	50	60	81	89	88	86	70	59	48	63
Karwar . .	4—6	69	73	75	73	75	85	87	88	87	85	78	69	79
Vizagapatam .	14	65	64	66	68	69	68	71	73	74	72	66	63	68
Masulipatam .	8—9	72	73	73	74	72	67	71	75	76	78	77	74	74
Secunderabad .	9	55	45	40	36	36	59	71	72	75	65	60	56	56
Bellary . .	8—9	49	36	33	34	42	58	62	63	64	63	63	57	52
Mangalore . .	3—4	62	67	72	74	76	88	90	89	87	83	77	66	78
Mercara . .	3—4	69	58	65	75	80	94	97	95	93	87	84	74	81
Bangalore . .	8—9	60	52	50	54	62	73	77	78	77	75	73	67	67
Madras . .	9	70	70	72	71	66	60	64	69	69	76	78	75	70
Salem . . .	9	61	53	49	55	63	67	69	73	72	75	75	71	65
Wellington . .	6—7	69	57	60	64	70	75	73	78	75	83	84	75	72
Coimbatore . .	8—9	58	51	54	59	65	70	71	73	70	74	72	67	65
Trichinopoly . .	9	67	62	58	55	56	56	57	61	64	72	76	73	63
Negapatam . .	8—9	75	71	72	73	70	64	64	70	72	77	81	80	72
Madura . .	6—8	66	61	59	58	61	59	57	62	63	72	74	72	64
Cochin . . .	9	71	72	76	77	81	88	88	87	85	83	81	75	80
Colombo . .	13—14	75	74	76	77	80	81	81	81	80	80	80	77	79
Jaffna . . .	13	77	73	73	76	83	82	81	83	84	84	84	83	80
Trincomalee . .	11—13	77	74	75	71	68	67	65	68	69	74	82	81	73
Batticaloa . .	13—14	82	81	81	79	76	70	71	74	75	80	84	85	78
Hambantota . .	12—14	83	83	83	82	86	84	82	83	83	84	86	83	84
Galle . . .	13—14	86	83	83	84	87	89	90	89	90	89	88	87	87
Kandy . .	13—14	76	71	69	75	76	81	80	80	79	80	80	80	77
Newera Eliya .	11—13	81	73	73	79	83	89	88	86	86	87	84	83	83
Akyab . . .	13—15	72	70	74	75	79	87	89	88	86	83	81	77	80
Thayetmyo . .	5—7	67	57	56	56	67	82	84	84	82	80	78	72	72

TABLE XVII.—*Average monthly mean relative humidity of 123 Stations in India, Ceylon, &c.*—concld.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Tounghoo . .	5—7	70	64	61	?	?	84	87	88	84	81	80	78	?
Bassein . .	6—7	71	68	68	69	75	88	89	90	89	87	83	78	80
Diamond Island .	5—6	71	72	76	76	79	86	88	87	87	84	80	75	80
Rangoon . .	7—8	66	63	64	68	77	89	90	91	89	85	80	74	78
Moulmein . .	6—7	63	63	66	70	77	89	90	90	87	81	74	69	77
Mergui . .	6—7	72	75	76	80	84	90	89	90	90	86	80	75	82
Port Blair . .	6—8	77	78	78	79	85	87	86	86	88	87	85	82	83
Nancowry . .	8—9	75	74	74	77	80	82	82	82	81	84	82	79	79

TABLE XVIII.—*Comparison of monthly mean vapour-tension in 1883 with the averages of Table XVI.*

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar . . .	—·003	—·009	—·006	—·008	—·009	—·014	+·016	—·005	+·017	+·001	—·023	—·029	—·006
Aden	+·024	—·038	0	—·006	—·010	—·042	—·082	—·086	—·024	+·008	+·005	—·010	—·015
Mauritius . . .	—·015	—·013	—·005	+·023	+·019	—·001	—·008	—·006	—·011	—·015	—·003	—·011	—·004
Bushire	+·020	+·032	—·003	—·004	+·010	+·020	—·011	+·008	—·003	+·021	+·031	+·014	+·011
Quetta	+·010	—·022	—·037	+·023	+·015	—·026	+·008	—·061	+·002	—·042	—·021	—·009	—·013
Leh	+·001	—·003	—·005	+·007	—·001	—·038	—·037	—·026	+·004	+·014	+·008	—·003	—·007
Mooltan	—·001	—·047	—·039	+·042	+·022	+·027	+·031	—·010	+·013	—·160	—·044	—·037	—·017
Dera Ismail Khan . .	+·022	—·048	—·036	+·053	—·021	—·081	+·017	—·093	+·024	—·041	—·005	—·010	—·018
Peshawar . . .	+·002	—·030	—·041	+·014	—·074	—·040	+·042	—·044	+·021	—·048	+·005	—·006	—·017
Murree	+·020	+·012	+·010	+·051	—·013	—·005	+·002	—·018	—·007	—·026	—·016	—·007	0
Rawalpindi . . .	+·041	+·003	+·004	+·014	—·007	+·066	+·037	+·027	—·031	—·030	+·039	—·016	—·012
Sialkot	+·003	—·029	—·030	—·007	—·064	?	—·092	—·108	?	?	?	?	?
Lahore	+·022	—·040	—·021	+·027	—·017	+·010	—·024	—·074	+·042	—·037	+·013	—·026	—·010
Ludhiana . . .	+·015	—·046	—·004	+·043	+·096	?	+·023	—·041	—·012	—·093	+·015	—·033	?
Simla	—·020	—·022	—·049	—·069	—·031	—·014	—·003	—·036	—·018	—·063	—·025	—·015	—·030
Delhi	+·020	—·062	0	—·015	—·127	—·012	—·013	—·100	—·016	—·084	—·040	—·064	—·043
Sirsa	+·039	—·042	+·029	+·068	+·027	—·037	—·010	—·104	+·033	—·009	—·009	—·041	—·005
Chakrata . . .	+·007	—·011	—·005	—·002	—·032	+·026	+·016	—·019	+·018	—·049	—·008	—·005	—·005
Mussooree (*St. Fidelis*) .	—·012	—·024	—·021	—·027	—·020	+·062	+·015	—·013	—·008	—·053	—·044	?	?
Paori	?	?	?	?	?	—·034	+·006	—·019	—·005	—·050	—·001	?	?

TABLE XVIII.—*Comparison of monthly mean vapour-tension in 1883 with the averages of Table XVI*—continued.

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Roorkee	—·029	—·039	?	—·013	—·080	+·046	0	—·054	+·009	—·102	—·021	—·052	?
Ranikhet	—·011	—·037	—·026	—·002	—·039	+·036	—·002	—·023	+·018	—·053	—·019	—·019	—·015
Pithoragarh	?	?	?	?	—·049	?	?	?	—·006	—·043	—·011	—·026	?
Meerut	+·006	—·075	—·058	—·095	—·140	—·050	—·028	—·107	—·048	—·103	—·034	—·059	—·066
Bareilly	—·003	—·040	+·004	+·004	—·006	+·079	—·017	—·018	+·011	—·125	—·046	—·052	—·017
Agra	+·031	—·033	—·009	—·023	—·091	—·021	—·016	—·084	—·030	—·113	—·051	—·054	—·041
Lucknow	+·016	—·055	—·055	+·021	+·053	+·022	+·007	—·029	+·019	—·080	—·027	—·038	—·012
Gorakhpur	?	—·022	—·034	+·033	+·013	+·004	+·038	+·026	+·039	—·066	—·034	—·029	?
Jhansi	+·048	—·023	+·033	—·023	+·017	+·017	—·007	—·036	+·024	—·012	—·044	—·049	—·005
Allahabad	+·041	—·048	—·044	—·036	—·068	+·007	—·009	—·028	+·024	—·066	—·054	—·053	—·028
Benares	+·036	—·058	—·035	+·016	—·036	+·026	—·013	—·039	+·004	—·143	—·046	—·051	—·028
Katmandu	+·010	—·012	—·007	+·009	+·043	—·004	—·003	—·009	—·011	—·047	—·018	—·066	—·010
Sibsagar	+·003	—·009	—·003	+·005	+·033	+·015	+·011	+·017	+·017	—·001	—·026	—·005	+·005
Dhubri	?	?	?	—·018	+·003	+·015	—·001	+·011	+·005	—·018	—·031	—·033	?
Silchar	—·005	—·045	+·006	—·024	—·013	+·010	+·013	+·013	+·013	—·001	+·001	+·005	—·002
Darjeeling (*St. Paul's school.*)	+·008	+·008	?		?	?	+·005	—·002	0	+·034	—·010	—·018	?
Purneah	+·007	?	—·085	—·057	+·026	—·029	+·012	—·002	+·007	—·035	—·062	—·064	?
Durbhunga	+·026	—·028	—·021	+·042	+·054	—·011	+·042	+·057	+·065	—·005	—·061	—·053	+·009
Patna	+·018	—·059	—·061	—·019	—·021	—·033	+·005	0	+·023	—·078	—·057	—·054	—·028
Gya	+·024	—·062	—·086	—·255	—·165	—·041	—·008	—·012	—·004	—·125	—·050	—·075	—·070
Hazaribagh	+·034	—·035	+·040	—·009	—·055	+·048	+·009	—·003	+·017	—·101	—·049	—·032	—·011
Berhampore	+·014	—·079	—·093	—·035	+·076	+·008	+·022	+·009	+·011	—·028	—·071	—·037	—·017
Burdwan	—·038	—·079	—·076	—·070	+·027	—·054	—·033	—·053	—·032	—·104	—·128	—·076	—·060
Jessore	—·023	—·082	—·063	—·046	+·033	—·012	—·004	+·008	+·004	—·040	—·092	—·018	—·028
Dacca	—·006	—·052	—·019	—·019	+·061	—·002	—·009	+·010	—·005	—·014	—·042	+·001	—·008
Chittagong	—·024	—·091	+·005	—·027	+·018	+·095	+·002	?	?	?	?	?	?
Calcutta (*Alipore*)	—·018	—·066	—·008	+·019	+·058	—·016	+·001	—·006	+·006	—·030	—·075	—·035	—·014
Do. (*Chowringhee*)	+·001	—·031	—·001	+·024	+·058	—·006	+·007	+·001	+·011	—·007	—·039	—·024	—·001
Saugor Island	—·054	—·093	—·045	—·032	—·004	—·057	—·034	—·035	—·023	—·041	—·095	—·057	—·048
Cuttack	+·020	+·010	+·024	+·033	+·038	—·004	+·002	+·010	+·020	+·017	—·028	—·035	+·008
False Point	+·021	—·013	+·078	+·058	+·055	—·006	+·006	—·005	+·002	—·001	—·041	—·031	+·010
Sambalpore	0	—·053	+·067	—·048	0	+·008	—·005	+·006	—·001	—·030	—·075	—·071	—·017
Raipur	+·003	—·049	+·028	?	—·096	+·019	—·022	—·018	—·012	—·013	—·038	—·105	?
Nagpur	+·032	—·042	—·032	—·032	—·035	+·045	+·003	—·026	+·024	+·030	—·016	—·098	—·012

TABLE XVIII.—*Comparison of monthly mean vapour-tension in 1883, with the averages of Table XVI*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Seoni	+·027	—·052	—·028	—·021	—·074	+·011	—·016	—·022	—·005	—·018	—·066	—·110	—·031
Jubbulpore	+·041	—·060	—·059	—·086	—·030	+·017	+·002	—·024	+·021	—·010	—·029	—·081	—·025
Saugor	+·076	—·017	+·010	—·032	?	?	+·048	—·020	+·062	?	?	?	?
Pachmarhi	+·012	—·021	—·018	—·024	—·008	+·044	+·008	+·009	+·037	+·029	—·008	—·084	—·002
Hoshangabad	+·022	—·057	—·036	—·063	—·015	+·019	+·005	—·021	+·020	+·009	—·016	—·087	—·018
Khandwa	—·024	—·107	—·055	—·055	—·002	+·023	+·007	—·019	+·006	+·055	—·041	—·121	—·028
Chanda	—·008	—·049	—·020	—·107	—·118	+·034	—·025	—·028	—·023	+·020	—·009	—·084	—·035
Sironcha	+·022	—·020	+·053	—·040	—·040	+·026	+·014	0	+·002	+·033	—·043	—·075	—·006
Chikalda	—·010	—·039	—·067	—·039	+·016	+·068	+·011	+·003	+·016	+·034	—·026	—·086	—·009
Buldana	?	?	?	?	?	+·080	+·023	—·006	+·013	+·089	+·037	—·026	?
Akola	+·008	—·043	—·043	—·043	—·015	+·070	+·019	—·024	+·023	+·084	+·005	—·078	—·003
Amraoti	+·003	+·001	+·017	—·032	—·069	+·042	+·015	—·017	+·037	+·076	—·013	—·092	—·003
Neemuch	+·047	—·019	—·017	—·033	—·071	—·002	+·048	—·008	+·070	+·055	—·043	—·037	—·001
Nowgong	+·067	—·007	?	?	?	+·045	+·002	—·032	+·018	—·020	—·018	—·059	?
Sutna	+·056	—·029	+·005	—·047	—·047	+·019	—·003	—·033	+·045	—·017	—·021	—·049	—·010
Indore	+·055	—·027	+·005	—·018	—·004	+·042	+·005	—·021	+·020	+·077	+·013	—·006	+·012
Bickaneer	—·006	—·093	—·010	+·054	+·049	+·059	+·024	—·058	—·006	—·055	+·008	—·028	—·005
Jeypore	+·043	—·037	—·008	—·009	+·040	+·023	—·050	—·084	+·019	—·032	—·013	—·057	—·014
Sambhar	+·021	+·029	·030	—·058	?	?	—·015	—·073	+·007	?	?	—·036	?
Ajmer	+·015	—·058	—·030	—·050	+·005	+·028	+·046	—·036	+·036	—·036	—·011	—·027	—·010
Mount Abu	+·020	—·017	+·028	+·049	—·006	+·017	—·022	—·048	+·025	+·052	—·002	—·026	+·006
Pachbudra	—·039	—·065	+·045	—·060	—·054	—·059	—·042	—·091	+·021	—·048	—·025	—·075	—·041
Jacobabad	+·003	—·072	—·102	—·064	—·110	—·021	+·057	—·073	—·029	—·117	—·068	—·012	—·051
Hyderabad	—·028	—·075	—·077	+·051	—·030	?	+·014	—·081	—·034	+·054	—·005	—·035	?
Kurrachee	0	+·003	+·005	+·141	+·078	+·061	+·004	—·025	—·017	—·052	—·095	—·098	0
Bhuj	—·013	—·074	+·015	—·027	—·015	—·034	?	—·034	+·007	—·030	—·041	—·071	?
Rajkot	+·020	—·020	+·020	+·017	—·008	+·017	+·007	—·060	+·020	+·034	—·017	—·054	—·002
Deesa	+·010	—·057	+·007	+·007	—·014	+·016	+·014	—·084	+·008	+·051	—·027	—·070	—·012
Surat	+·075	+·002	+·049	—·007	—·122	—·156	—·141	—·099	—·059	—·021	—·005	—·033	—·043
Malegaon	+·011	+·075	—·020	—·035	—·010	—·024	—·028	—·066	—·020	+·060	—·014	+·068	0
Bombay	+·002	—·028	—·043	+·028	—·003	—·002	—·005	—·019	—·013	—·001	—·024	—·122	—·019
Poona	—·015	—·020	—·008	+·019	—·004	+·037	+·004	—·027	—·009	+·082	+·003	—·079	—·001
Sholapur	—·011	+·003	+·092	+·093	+·083	—·013	—·015	—·003	+·004	+·081	+·119	—·009	+·035
Ratnagiri	—·040	—·039	—·067	—·017	—·019	—·011	—·016	—·020	—·019	—·006	—·024	—·093	—·031
Belgaum	—·001	—·008	?	—·012	+·010	+·009	—·005	—·009	—·025	+·038	—·025	—·062	?

TABLE XVIII.—*Comparison of the monthly mean vapour-tension in 1883 with the averages of Table XVI*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Karwar	−·053	−·011	−·059	−·021	−·030	+·002	+·010	+·019	+·005	−·003	−·049	−·067	−·021
Vizagapatam	−·012	−·019	−·006	−·021	+·005	−·049	−·042	−·017	−·034	−·003	−·083	−·083	−·030
Masulipatam	−·022	−·020	+·042	+·049	+·145	+·154	+·085	+·005	−·035	+·042	−·050	−·029	+·031
Secunderabad	+·019	−·017	+·068	−·008	+·003	+·065	+·034	+·037	+·019	+·070	−·038	−·086	+·014
Bellary	+·022	+·002	+·084	−·024	−·003	−·022	−·012	+·016	−·060	+·066	−·049	−·073	−·004
Mangalore	−·002	+·020	−·021	+·019	+·022	+·011	+·010	+·014	+·002	0	−·046	−·049	−·002
Mercara	+·011	+·010	+·015	−·008	+·021	+·008	+·011	+·017	−·004	+·001	−·045	−·010	+·002
Bangalore	+·014	0	+·056	−·038	+·008	−·012	+·006	+·001	−·045	+·006	−·048	−·034	−·007
Madras	+·016	+·046	+·055	+·038	+·077	+·086	+·067	+·076	−·010	+·053	−·018	−·012	+·040
Salem	−·042	+·023	+·048	+·034	+·036	+·052	+·058	+·070	+·036	+·009	−·007	+·002	+·026
Wellington	+·043	+·004	+·017	+·002	+·009	−·018	+·015	+·021	−·004	+·024	−·018	+·006	+·008
Coimbatore	+·025	+·014	+·038	+·042	+·054	+·014	+·024	+·023	+·005	+·016	+·007	+·005	+·022
Trichinopoly	+·022	−·024	−·014	−·024	+·043	+·062	+·057	+·035	−·013	+·028	−·030	−·026	+·010
Negapatam	−·003	−·037	−·024	−·024	−·024	−·014	−·010	+005	−·026	−·024	−·071	−·043	−·025
Madura	−·014	−·008	?	?	?	−·002	+·049	+·068	+·065	+·052	+·026	−·012	?
Cochin	−·006	−·024	+·003	−·012	+·009	+·015	+·010	+·028	+·009	−·003	−·025	−·031	−·002
Colombo	−·037	−·082	−·057	−·081	−·063	−·062	−·065	−·024	−·058	−·067	−·070	−·077	−·062
Jaffna	+·004	−·060	−·067	−·042	−·057	−·062	−·057	−·014	−·066	−·039	−·056	−·052	−·047
Trincomalee	−·002	−·052	−·023	−·015	−·010	+·083	+·014	+·017	+·006	−·013	−·038	−·026	−·005
Batticaloa	+·045	−·044	−·001	+·015	+·083	−·004	−·070	−·054	−·037	−·065	−·141	−·075	−·029
Hambantota	−·033	−·048	−·016	−·007	−·011	−·002	−·011	−·012	+·006	−·009	−·044	−·048	−·020
Galle	−·024	−·065	−·041	−·020	−·003	+·001	−·012	+·014	−·004	−·011	−·007	−·031	−·017
Kandy	+·002	−·030	−·030	−·035	−·023	−·032	−·019	−·014	−·048	−·020	−·015	−·028	−·024
Newera Eliya	+·010	+·007	−·015	−·010	+·010	−·011	+·006	−·004	−·012	−·020	+·020	−·032	−·004
Akyab	+·009	−·022	−·018	−·009	+·010	−·035	−·022	−·028	−·039	−·004	−·060	−·018	−·020
Thyetmio	?	?	−·111	+·061	+·036	+·008	0	−·008	+·012	+·017	−·008	+·017	?
Tounghoo	−·066	−·074	−·025	?	?	−·060	−·039	−·031	−·037	−·022	−·029	−·043	?
Bassein	−·016	−·044	−·050	−·022	+·014	−·009	−·009	−·002	?	?	?	−·035	?
Diamond Island	−·033	−·043	−·038	−·040	−·011	−·016	−·017	0	−·022	−·002	−·015	−·036	−·023
Rangoon	−·048	−·005	+·028	+·029	+·024	−·016	−·013	−·011	−·032	−·030	−·029	−·064	−·014
Moulmein	−·054	+·030	+·014	+·010	+·008	−·007	−·001	+·001	−·016	−·031	−·024	−·076	−·012
Mergui	+·013	+·007	−·018	−·015	−·014	−·005	−·004	+·009	−·026	−·042	−·031	−·057	−·015
Port Blair	−·053	−·042	−·042	−·012	+·004	+·006	−·023	+·005	−·012	−·007	−·024	−·030	−·019
Nancowry	−·045	−·059	−·053	−·036	−·012	−·019	?	?	?	?	?	?	?

TABLE XIX.—*Comparison of the monthly mean relative humidity in 1883 with the averages of Table XVII.*

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	0	− 1	− 2	− 1	− 1	− 3	+ 1	− 1	+ 1	− 1	− 2	− 3	− 1
Aden	+ 2	− 3	0	+ 1	+ 1	− 3	− 2	0	− 1	+ 1	+ 1	+ 1	0
Mauritius	0	+ 1	− 1	+ 4	+ 3	− 2	− 2	− 1	− 1	+ 1	+ 3	+ 2	+ 1
Bushire	+ 4	− 1	0	− 3	− 2	0	− 1	− 2	− 1	− 1	+ 2	+ 2	0
Quetta	+ 9	− 5	− 4	+ 2	+ 4	− 3	+ 1	−6	− 2	− 3	− 5	− 2	− 1
Leh	+ 1	0	− 1	+ 1	+ 2	− 3	−10	− 5	+ 1	+12	−11	+ 8	+ 1
Mooltan	0	− 5	− 3	− 1	+ 4	− 1	+ 5	− 1	0	−10	− 3	− 7	− 2
Dera Ismail Khan	+ 2	−10	− 2	0	− 2	− 8	− 0	−12	0	− 5	− 2	− 2	− 3
Peshawar	+ 2	− 3	− 2	− 3	− 8	− 6	+ 4	− 6	− 2	− 6	0	0	− 3
Murree	+18	+ 8	+ 8	+ 7	− 2	− 3	− 1	− 4	− 1	− 2	+ 1	0	+ 2
Rawalpindi	+10	+ 3	+ 5	− 4	− 3	− 2	0	− 4	− 3	− 6	+11	0	+ 1
Sialkot	+ 2	− 1	+ 1	− 4	− 5	P	−11	−11	P	P	P	P	P
Lahore	+ 8	0	+ 3	+ 2	+ 4	+ 2	0	− 6	+15	+ 4	+15	+6	+ 4
Ludhiana	+ 3	− 4	− 2	− 2	+ 4	P	+ 1	−11	− 1	− 8	+ 5	− 3	P
Simla	+ 3	− 5	− 7	− 3	− 2	− 3	− 1	− 6	− 1	− 9	− 1	+ 1	− 3
Delhi	+ 3	− 7	+ 3	− 4	− 3	0	− 3	−15	− 5	−10	− 5	− 9	− 5
Sirsa	+ 6	− 5	+ 5	0	+ 1	− 3	− 2	−14	+ 5	+ 1	+ 5	− 7	− 1
Chakrata	+ 8	− 8	+ 3	− 5	− 8	+ 3	+ 1	− 4	+ 2	−13	+ 1	+ 1	− 2
Mussooree (*St. Fidelis*)	+ 5	− 6	− 1	− 8	− 7	+ 6	+ 2	− 3	− 1	− 7	+ 3	P	P
Paori	P	P	P	P	P	− 6	− 1	− 3	+ 1	− 6	+ 2	P	P
Roorkee	− 9	− 4	P	− 6	− 7	0	− 3	−11	− 1	−13	− 3	−12	P
Ranikhet	+ 3	−14	− 1	− 5	− 7	+ 4	0	− 5	+ 2	−10	0	− 2	− 3
Pithoragarh	P	P	P	P	− 8	P	P	P	0	− 4	0	− 2	P
Meerut	+ 3	− 3	− 3	−10	−12	0	− 3	−14	− 4	− 9	− 1	− 6	− 5
Bareilly	− 1	− 5	+ 3	− 3	− 2	+ 2	− 1	− 6	− 1	−12	− 5	− 7	− 3
Agra	+ 2	− 1	+ 1	− 3	− 6	− 2	+ 1	−14	− 5	−12	− 5	− 7	− 4
Lucknow	+ 2	− 5	− 0	− 1	+ 1	+ 2	+ 2	− 6	0	− 6	− 2	− 4	− 1
Gorakhpur	P	0	0	+ 1	− 3	+ 4	+ 3	− 1	+ 3	− 7	− 1	− 2	P
Jhansi	+ 9	+ 2	+ 7	− 1	+ 2	+ 3	0	− 8	0	+ 2	− 3	− 5	+ 1
Allahabad	+ 7	− 1	− 1	− 3	− 5	+ 3	+ 1	− 6	+ 3	− 5	− 6	− 5	− 1
Benares	+ 3	− 8	− 3	− 2	− 3	+ 4	− 3	− 9	− 4	−11	− 9	−10	− 5
Katmandu	+ 1	− 2	0	+ 2	+ 4	0	+ 1	0	− 3	− 5	− 4	− 8	− 1
Sibsagar	+ 2	+ 2	+ 1	− 1	+ 3	+ 1	− 2	0	+ 1	0	− 2	+ 2	+ 1
Dhubri	P	P	P	− 2	+ 3	0	− 1	0	− 2	− 3	− 2	0	P

TABLE XIX.—*Comparison of the monthly mean relative humidity in 1883 with the averages of Table XVII*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Silchar	− 2	− 5	− 1	− 1	+ 6	+ 1	− 2	+ 1	0	− 1	0	+ 2	0
Darjeeling (*St. Paul's School*).	+10	+ 8	?	?	?	?	− 1	0	0	+ 9	−14	− 1	?
Purneah	+ 4	?	− 6	− 3	+ 3	− 2	− 1	+ 1	+ 1	− 3	− 3	− 1	?
Durbhunga	+ 5	− 1	0	+ 5	+ 3	0	+ 2	+ 4	+ 4	− 2	− 4	− 6	+ 1
Patna	+ 1	− 5	− 4	− 3	− 3	+ 2	+ 1	0	0	− 8	− 6	− 5	− 3
Gya	+ 5	− 4	− 4	−14	−12	+ 2	− 1	− 6	− 3	−12	− 5	− 8	− 5
Hazaribagh	+ 5	− 4	+ 4	− 6	−10	+ 3	+ 3	− 3	− 1	−14	− 5	− 3	− 3
Berhampore	+ 5	− 5	− 3	− 5	+ 4	+ 4	+ 3	+ 3	0	− 3	− 5	+ 2	0
Burdwan	− 3	− 4	− 1	− 3	0	− 1	− 1	− 1	− 2	− 8	− 8	− 4	− 3
Jessore	− 1	− 6	− 4	− 3	0	0	0	0	0	− 5	− 7	+ 2	− 2
Dacca	0	− 4	− 4	− 4	+ 1	0	− 1	0	− 1	− 2	− 2	+ 4	− 1
Chittagong	0	− 6	+ 3	+ 1	+ 2	+ 2	+ 1	?	?	?	?	?	?
Calcutta (*Alipore*)	+ 1	− 2	+ 2	+ 2	− 1	− 2	− 1	− 2	− 1	− 4	− 3	+ 1	− 1
Do. (*Chowringhee*)	+ 2	0	0	+ 4	+ 1	− 2	0	0	+ 1	− 3	− 2	+ 1	0
Saugor Island	− 2	− 2	− 1	− 1	0	− 2	0	0	+ 1	− 4	− 5	0	− 1
Cuttack	0	− 1	+ 2	− 2	− 1	+ 3	0	− 1	0	− 2	0	+ 4	0
False Point	+ 1	+ 1	+ 1	− 2	0	+ 1	+ 1	+ 1	+ 2	− 2	0	− 2	0
Sambalpur	− 2	− 7	+ 5	− 8	− 7	0	+ 3	− 2	+ 2	− 3	− 4	− 3	− 2
Raipur	0	− 7	+ 3	?	−10	+ 5	− 2	− 8	+ 2	0	− 1	− 6	?
Nagpur	+ 5	− 4	− 1	− 3	− 4	+ 7	0	− 7	+ 5	+ 5	0	− 7	0
Seoni	+ 5	− 6	− 2	− 5	− 7	+ 4	− 1	− 7	+ 1	− 2	− 7	−11	− 3
Jubbulpore	+ 1	− 9	− 7	−10	− 4	+ 2	+ 1	− 7	+ 4	0	− 2	− 6	− 3
Saugor	+10	− 1	+ 3	− 6	?	?	+ 7	− 6	+ 5	?	?	?	?
Pachmarhi	+ 3	− 2	− 1	− 4	− 1	+ 6	+ 2	− 4	+ 7	+ 6	+ 1	− 9	0
Hoshangabad	+ 3	− 7	− 4	− 6	− 1	+ 5	+ 2	− 5	+ 5	+ 5	+ 1	− 6	− 1
Khandwa	− 4	−11	− 4	− 5	0	+ 5	+ 2	− 3	+ 3	+ 9	− 1	− 8	− 1
Chanda	− 1	− 6	− 1	− 9	−11	+ 7	− 3	− 7	0	+ 2	+ 3	0	− 2
Sironcha	+ 2	− 1	− 6	− 2	− 7	+ 6	+ 3	− 1	+ 3	+ 2	0	− 1	0
Chikalda	+ 1	− 7	− 5	− 5	+ 2	+ 9	+ 3	− 3	+ 6	+ 9	− 1	− 9	0
Buldana	?	?	?	?	?	+10	+ 5	+ 1	+ 8	+14	+ 7	+ 1	?
Akola	0	− 5	− 2	− 4	− 1	+ 9	+ 4	− 3	+ 7	+11	+ 4	− 3	+ 1
Amraoti	0	− 3	− 1	− 5	− 6	+ 7	+ 4	− 4	+ 8	+11	+ 2	− 8	0
Neemuch	+ 8	0	+ 2	− 3	− 2	+ 1	+ 6	− 5	+10	+ 9	− 2	− 3	+ 2
Nowgong	+10	+ 3	?	?	?	+ 2	+ 2	− 6	+ 2	0	− 1	− 5	?

TABLE XIX.—*Comparison of the monthly mean relative humidity in 1883 with the averages of Table XVII*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Sutna	+11	0	+ 4	— 5	— 4	+ 1	+ 1	— 6	+ 5	+ 1	— 1	— 4	0
Indore	+ 9	— 2	+ 2	— 3	+ 1	+ 5	+ 1	— 4	+ 4	+ 9	+ 5	+ 3	+ 3
Bickaneer	— 2	—13	+ 1	+ 3	+ 4	+ 1	+ 3	—11	— 1	— 4	+ 3	— 4	— 2
Jeypore	+ 9	— 1	+ 1	— 4	+ 5	+ 3	— 7	—14	+ 1	— 3	— 1	— 5	— 1
Sambhar	+ 5	+ 6	— 2	— 4	?	?	— 3	—13	— 1	?	?	— 5	?
Ajmere	+ 5	— 6	0	— 7	+ 4	+ 4	+ 7	—10	+ 3	— 4	0	— 2	— 1
Mount Abu	+ 5	— 3	+ 8	+ 3	+ 1	+ 1	— 1	—10	+ 7	+ 9	+ 4	— 1	+ 2
Pachbudra	— 3	— 9	+ 1	—11	— 5	— 6	— 4	—13	+ 2	— 4	— 4	— 9	— 5
Jacobabad	+ 1	— 9	— 9	—10	— 8	— 4	+ 7	— 5	— 4	— 9	—12	+ 1	— 5
Hyderabad	— 5	—10	— 4	+ 2	— 1	?	+ 4	— 7	0	+ 3	+ 1	— 4	?
Kurrachee	— 1	+ 1	+ 4	+11	+ 7	+ 3	+ 2	0	+ 1	— 6	— 8	—11	0
Bhuj	— 2	— 7	+ 6	— 4	— 1	—	?	— 5	+ 3	— 5	— 3	— 8	?
Rajkot	+ 3	— 2	+ 5	0	0	+ 1	+ 3	—10	+ 3	+ 6	+ 2	— 3	+ 1
Deesa	+ 3	— 7	+ 3	— 2	0	0	+ 2	—13	+ 3	+ 5	— 1	— 6	— 1
Surat	+ 9	0	+ 6	— 1	—10	—10	—13	—11	— 1	+ 3	+ 3	+ 1	— 2
Malegaon	+ 2	+ 8	+ 2	— 2	0	+ 1	— 1	— 5	+ 3	+11	+ 3	?	?
Bombay	— 3	— 2	— 3	+ 2	0	+ 2	0	— 3	+ 2	+ 1	0	— 7	— 1
Poona	— 2	— 4	0	+ 1	— 1	+ 9	+ 3	— 4	+ 6	+13	+ 4	— 4	+ 2
Sholapur	+ 2	— 1	+ 7	+ 8	+ 7	+ 4	0	+ 2	+ 3	+ 8	+13	+ 2	+ 5
Ratnagiri	— 2	— 4	— 3	— 1	— 3	+ 2	0	— 2	0	+ 1	+ 1	— 5	— 1
Belgaum	+ 2	— 2	?	0	0	+ 4	+ 1	— 3	— 1	+ 7	+ 1	— 3	?
Karwar	— 4	0	— 2	+ 1	— 3	+ 1	+ 1	+ 1	+ 1	+ 1	— 1	— 3	— 1
Vizagapatam	+ 1	— 1	— 1	— 1	— 1	— 3	— 4	— 3	— 3	— 1	— 4	— 5	— 2
Masulipatam	— 1	0	+ 5	+ 6	+ 8	+16	+11	— 1	— 6	+ 5	0	+ 4	+ 4
Secunderabad	+ 4	— 3	+ 8	— 2	— 3	+ 9	+ 5	+ 4	+ 5	—10	0	— 8	+ 1
Bellary	+ 5	+ 1	+ 6	— 2	— 2	— 2	— 1	+ 3	— 8	+ 9	— 2	— 5	0
Mangalore	+ 1	+ 1	— 1	+ 4	+ 1	— 1	+ 1	0	— 2	+ 2	— 3	— 2	0
Mercara	+ 3	+ 3	+ 3	+ 1	+ 3	0	+ 1	— 1	— 2	+ 1	— 3	+ 3	+ 1
Bangalore	+ 3	0	+ 5	— 5	— 2	— 3	+ 3	— 2	— 7	+ 4	— 2	0	— 1
Madras	+ 2	+ 6	+ 5	+ 5	+ 4	+ 8	+ 8	+ 4	— 1	+11	+ 1	+ 3	+ 5
Salem	— 4	+ 5	+ 7	+ 4	+ 3	+ 8	+ 9	+11	+ 3	+ 7	+ 6	+ 7	+ 6
Wellington	+10	+ 2	+ 3	— 1	— 1	— 3	+ 1	+ 1	— 1	+ 6	— 2	+ 2	+ 1
Coimbatore	+ 2	+ 2	+ 3	+ 3	+ 5	0	+ 3	+ 2	0	+ 3	+ 4	+ 4	+ 3
Trichinopoly	+ 1	— 1	— 3	— 6	+ 2	+ 5	+ 5	+ 3	— 4	+ 7	0	0	+ 1

TABLE XIX.—*Comparison of the monthly mean relative humidity in 1883 with the averages of Table XVII*—concluded.

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Negapatam	− 1	− 2	− 2	− 2	− 3	0	0	− 1	− 4	+ 2	− 5	− 2	− 2
Madura	− 2	+ 1	?	?	?	− 1	+ 7	+ 5	+ 3	+ 7	+ 7	+ 3	?
Cochin	− 2	0	0	0	+ 1	0	+ 2	+ 2	− 1	+ 3	0	+ 1	+ 1
Colombo	− 2	− 7	− 5	− 5	− 4	− 4	− 6	+ 3	− 7	− 6	− 4	− 4	− 4
Jaffna	+ 3	0	− 5	− 2	− 3	− 4	− 3	− 3	− 7	+ 2	0	0	− 2
Trincomalee	− 1	− 3	− 1	− 3	+ 1	+11	+ 5	+ 2	− 2	0	− 1	0	+ 1
Batticaloa	+ 5	0	− 2	− 2	+ 7	+ 1	− 7	− 8	− 4	− 2	− 8	− 3	− 2
Hambantota	− 3	− 1	0	+ 3	0	0	+ 1	− 1	− 7	0	− 2	− 2	− 1
Galle	0	− 3	− 4	− 2	0	+ 6	− 2	− 4	− 2	+ 1	+ 3	0	− 1
Kandy	+ 3	0	− 2	− 3	− 3	− 4	− 3	− 3	− 6	0	+ 3	0	− 2
Newera Eliya	+ 4	+ 5	+ 1	− 1	+ 1	+ 1	0	+ 2	− 1	− 1	+ 5	− 3	+ 1
Akyab	− 2	− 3	− 3	0	+ 1	− 2	− 1	0	− 2	− 3	− 5	0	− 2
Thayetmyo	?	?	− 7	+ 5	+ 4	+ 2	+ 1	− 2	+ 1	+ 1	+ 4	+ 8	?
Tounghoo	− 6	−10	− 2	?	?	− 5	− 2	− 2	− 1	− 4	0	− 3	?
Bassein	0	− 5	− 4	− 1	+ 1	+ 1	0	− 2	?	?	?	0	?
Diamond Island	− 1	− 2	− 2	0	− 1	+ 1	− 1	+ 1	0	− 2	+ 2	0	0
Rangoon	− 4	− 1	+ 2	+ 5	+ 3	− 1	0	− 2	− 1	− 5	0	− 4	− 1
Moulmein	− 1	+ 5	+ 2	+ 2	+ 2	+ 1	+ 1	− 1	+ 2	− 6	+ 1	− 2	+ 1
Mergui	+ 4	− 1	− 1	− 1	0	+ 1	+ 3	+ 2	0	− 2	− 1	− 1	0
Port Blair	− 3	− 2	− 1	− 2	− 1	− 1	0	+ 1	0	− 2	− 1	+ 2	− 1
Nancowry	− 3	− 4	− 2	− 4	− 4	− 4	?	?	?	?	?	?	?

TABLE XX.—*Geographical summary of the differences of Table XVIII.*

Areas.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
North-West Himalaya.	6—8	−·003	−·014	−·016	−·007	−·026	+·005	0	−·022	0	−·040	−·015	−·013	−·013
Sikkim Himalaya and Nepal.	1—2	+·009	−·002	−·007	+·009	+·043	−·004	+·001	−·006	−·006	−·007	−·014	−·042	−·002
Punjab Plains	7—9	+·018	−·038	−·015	+·027	−·018	−·010	+ 001	−·061	+·009	−·063	−·003	−·029	−·015
Gangetic Plains	10—11	+·015	−·046	−·040	−·023	−·030	+·004	+·002	−·028	+·012	−·092	−·049	−·056	−·028
Western Rajputana, Sind, Cutch, Gujarat, &c.	8—9	−·004	−·052	−·008	+·019	−·012	+·007	+·007	−·062	−·001	−·012	−·030	−·052	−·017
Eastern Rajputana, and Central India.	6—9	+·048	−·021	−·004	−·034	−·010	+·025	+·008	−·038	+·033	+·002	−·020	−·040	−·004
Nerbudda Valley	3	+·013	−·075	−·050	−·068	−·016	+·020	+·005	−·021	+·016	+·018	−·029	−·096	−·024

TABLE XX.—*Geographical summary of the differences of Table XVIII*—concluded.

AREAS.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
South Behar and Chutia-Nagpur.	2	+·029	—·049	—·023	—·122	—·110	+·004	+·001	—·008	+·007	—·113	—·050	—·054	—·041
Lower Bengal .	7	—·018	—·069	—·044	—·023	+·044	—·020	—·007	—·009	—·004	—·038	—·077	—·036	—·025
Assam and Cachar .	2—3	—·001	—·027	+·002	—·012	+·008	+·013	+·008	+·014	+·012	—·007	—·019	—·011	—·002
Orissa and Sambalpur.	3	+·014	—·019	+·056	+·014	+·031	—·001	+·001	+·004	+·007	—·005	—·048	—·046	+·001
South Central Provinces and Berar.	8—10	+·009	—·035	—·012	—·042	—·049	+·044	+·003	—·013	+·011	+·036	—·018	—·084	—·011
Konkan . .	4	—·004	—·019	—·030	—·004	—·044	—·042	—·038	—·030	—·022	—·008	—·026	—·079	—·029
Malabar Coast .	2	—·004	—·002	—·009	+·004	+·016	+·013	+·010	+·021	+·006	—·002	—·036	—·040	—·002
Deccan, Hyderabad, Mysore &c.	7—8	+·006	+·006	+.041	—·002	+·014	+·006	—·001	—·004	—·018	+·048	—·007	—·036	+·004
East Coast and Carnatic.	7—8	—·004	—·003	+·020	+·013	+·048	+·034	+·036	+·033	—·002	+·022	—·028	—·025	+·012
Ceylon . .	7	—·006	—·054	—·034	—·026	—·012	—·011	—·031	—·012	—·029	—·032	—·053	—·048	—·029
Arakan and Pegu .	5—7	—·030	—·047	—·030	—·001	+·015	—·005	—·014	—·013	—·024	—·008	—·028	—·030	—·018
Tenasserim . .	2	—·021	+·019	—·002	—·003	—·003	—·006	—·003	+·005	—·021	—·037	—·028	—·067	—·014
Bay Islands . .	1—2	—·049	—·051	—·048	—·024	—·004	—·007	—·023	+·005	—·012	—·007	—·024	—·030	—·023

TABLE XXI.—*Geographical summary of the differences of Table XIX.*

AREAS.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
North-West Himalaya.	6—8	+ 6	— 4	0	— 2	— 5	0	— 1	— 4	0	— 5	+ 2	+ 1	— 1
Sikkim, Himalaya and Nepal.	1—2	+ 6	+ 3	0	+ 2	+ 4	0	0	0	— 2	+ 2	— 9	— 5	0
Punjab Plains .	7—9	+ 4	— 4	+ 1	— 2	— 1	— 3	— 1	— 9	+ 1	— 5	+ 4	— 3	— 2
Gangetic Plains .	10—11	+ 2	— 3	— 1	— 3	— 3	+ 1	0	— 6	0	— 8	— 4	— 6	— 3
Western Rajputana, Sind, Cutch, Gujarat, &c.	8—9	0	— 7	— 2	— 1	0	— 1	+ 2	— 8	+ 2	— 1	— 2	— 5	— 2
Eastern Rajputana and Central India	6—9	+ 8	0	+ 2	— 4	+ 1	+ 3	+ 2	— 8	+ 3	+ 2	0	— 3	+ 1
Nerbudda Valley .	3	0	— 9	— 5	— 7	— 2	+ 4	+ 2	— 5	+ 4	+ 5	— 1	— 7	— 2
South Behar and Chutia-Nagpur.	2	+ 5	— 4	0	—10	—11	+ 3	+ 1	— 5	— 2	—13	— 5	— 6	— 4
Lower Bengal .	7	0	— 3	— 2	— 1	+ 1	0	0	0	0	— 4	— 5	+ 1	— 1
Assam and Cachar	2—3	0	— 2	0	— 1	+ 4	+ 1	— 2	0	0	— 1	— 1	+ 1	0
Orissa and Sambalpur.	3	0	— 2	+ 3	— 4	— 3	+ 1	+ 1	— 1	+ 1	— 2	— 1	0	— 1
South Central Provinces and Berar.	8—10	+ 2	— 5	— 2	— 4	— 5	+ 7	+ 2	— 4	+ 5	+ 6	+ 1	— 5	0
Konkan . .	4	0	— 2	— 1	0	— 4	— 1	— 3	— 4	+ 1	+ 2	+ 1	— 4	— 1
Malabar Coast .	2	— 1	+ 1	— 1	+ 2	+ 1	— 1	+ 2	+ 1	— 2	+ 3	— 2	— 1	0
Deccan, Hyderabad, Mysore, &c.	7—8	+ 2	0	+ 4	0	0	+ 3	+ 1	— 1	0	+ 5	+ 2	— 2	+ 1

TABLE XXI.—*Geographical summary of the differences of Table XIX*—concluded.

AREAS.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
East Coast and Carnatic.	7—8	0	+ 1	+ 2	+ 1	+ 3	+ 4	+ 5	+ 3	— 2	+ 5	+ 1	+ 2	+ 2
Ceylon . .	7	+ 1	— 2	— 3	— 2	0	+ 1	— 2	— 2	— 5	— 1	— 1	— 1	— 1
Arakan and Pegu .	5—7	— 2	— 5	— 2	+ 2	+ 2	0	0	— 1	— 1	— 3	0	0	— 1
Tenasserim . .	2	+ 1	+ 2	+ 1	+ 1	+ 1	+ 1	+ 2	+ 1	+ 1	+ 4	0	— 2	+ 1
Bay Islands . .	1—2	— 3	— 3	— 2	— 3	— 3	— 3	0	+ 1	0	— 1	— 1	+ 1	— 1

January.—In January, the air was both absolutely and relatively damper than usual, (the latter more specially) throughout the greater part of Northern India, and most so on the Rajputana and Central India plateau. The chief exception was in Lower Bengal, where the proportion of vapour in the air was less than usual; and, relatively to saturation, only in about the normal proportion.

In the peninsula generally, the humidity differed but little from the normal proportion according to either estimation, but the air was relatively damper in the interior than near the coasts. In Pegu, the air was considerably drier than usual.

February.—In this month, the proportion of vapour was considerably below the average in all parts of Northern and Central India, excepting on the plains of the Punjab; and notwithstanding the prevailing low temperature, the air was drier than usual, and more particularly so in Western Rajputana, Sind, and the Nerbudda valley. In the peninsula the conditions were more normal, but in Ceylon and the south of the Bay there was a great deficiency, and in Pegu it was greater than in January. In Tenasserim, however, there was a certain excess.

March.—This was also in general a dry month, as regards the absolute proportion of vapour, but less so than February; and in Orissa and the eastern districts of the Central Provinces, in the Deccan, Mysore and a part of the Carnatic, and also in Gujarat, there was more or less excess of humidity. In the Konkan, however, the air was deficient in vapour, and in Ceylon, and the Eastern Peninsula, except Tenasserim, the dryness was only somewhat less than in February. At the Bay Islands, it was about the same as in the previous month.

April.—In April, with the prevailing high temperature, there was a certain excess of vapour on the plains of the Punjab and in the maritime portion of Western India, but in the Nerbudda valley, and still more in South Behar, (if the Gya register can be trusted), the dryness was very great. In Orissa the absolute humidity was somewhat high, and equally so in the Carnatic. But there was still a deficiency in Ceylon and in the south of the Bay, while in the Eastern Peninsular the quantity varied but little from the normal average.

May.—In Northern India, the only region in which the vapour proportion much exceeded the average was the Central Himalaya and Lower Bengal. In South Behar and Chutia-Nagpur, however, the abnormal dryness was but little less than in April, and

in part of the Central Provinces it was greater. But in Orissa, as in Lower Bengal, there was an excess of moisture, and in the Carnatic (except the southern districts) it was even greater than in Lower Bengal, or than in the previous month in this province. In the Deccan and Mysore, the vapour proportion was also above the average at most stations, and also on the Malabar coast; but in the Konkan the air was abnormally drier than in any previous month, and also in Berar and Nagpur. In Ceylon, there was but a slight deficiency, and in Arakan and Pegu a slight excess, while at the Bay Islands the amount was normal. The relative humidity of the air varied in a nearly similar manner.

June.—In Northern India, with the exception of the Punjab and Lower Bengal, the vapour-tension was, in general, either about the average or somewhat above it, and most so in Eastern Rajputana and Central India. In the peninsula, in Berar and Nagpur, it was very excessive and but little less so in the Carnatic. On the Malabar coast there was a slight excess, and in Ceylon and the Burmese peninsula nearly an average proportion.

The relative humidity of the air was also generally either about the average or more or less in excess of it, the latter more especially in the region immediately south of the Satpura range, and more or less on the plateau and in the Nerbudda valley to the north of it.

July.—In this month also the absolute humidity of the air was in general slightly above the average, except on the North-Western Himalaya, in Lower Bengal, in Ceylon and the Eastern Peninsula; but the anomalies were small, except in the Carnatic, where the excess was as great as in June. In the earlier part of the month, the excess was more considerable in Northern India, but the break in the rains, which set in in the latter part of the month, was attended with great and increasing dryness.

August.—The very general suspension of the rains over a large part of Northern and Central India, and even in the Konkan and Deccan, which occurred during this month, was accompanied with abnormal dryness of the atmosphere. Not only was the absolute proportion of vapour considerably below the average, but, in virtue of the high temperature, it was still more deficient relatively to saturation. The abnormal dryness was greatest in the Punjab, Rajputana, and Central India, and in the upper portion of the Gangetic plain. Lower Bengal, Assam, and Cachar were beyond the influence of the dry winds, and, in the south, there was a certain excess of humidity, both on the Malabar coast and in the Carnatic, as in the preceding months. In Ceylon there was still a small deficiency and also in the Eastern Peninsula, but this was comparatively trivial.

September.—With the resumption of the rains towards the end of August, the air returned to its normal condition, and in the first part of September was damper than usual. Indeed, on the mean of the month, the vapour proportion was slightly excessive in the greater part of Northern and Central India, and the relative humidity somewhat more so, especially in Central India and the Central Provinces, both north and south of the Satpuras. But the excess did not extend far into the peninsula. In the Carnatic there was only about an average proportion of vapour, and in Ceylon a marked deficiency. This was also the case throughout the Burmese peninsula, and to some extent in the south-east of the Bay.

October.—Owing to the early cessation of the rains in Northern India, October was a very dry month. The abnormal deficiency of vapour was greatest in the Punjab, the

Gangetic plain, Behar, and Lower Bengal. On the other hand, the humidity of Berar, Nagpur, the Deccan, and Hyderabad was excessive, as was also that of the northern districts of the Carnatic; and indeed the greater part of Southern India had more than the average humidity. But in Ceylon the deficiency was not less than in September. In Arakan and Pegu there was also a certain deficiency, increasing towards the south, and reaching its maximum at Mergui.

November.—In this month, the vapour-tension was unusually below the average, except during the first week or ten days, and with some local exceptions in the Punjab, but owing to the abnormal coolness, the relative humidity of the air was less deficient, and both on the North-West Himalaya and plains of the Punjab it was damper than usual relatively to saturation. On the west coast also, and in some parts of the Deccan and the Carnatic, there was an excess of relative humidity. The greatest abnormal deficiency of vapour was in Bengal, Behar and Orissa, and it was scarcely less in the North-Western Provinces, and apparently also in Ceylon. A similar, but smaller, deficiency prevailed throughout the Burmese peninsula, and it was very marked in the south-east of the Bay.

December.—In December, except in Bengal and Assam, the absolute humidity was even more below the average than in November, or indeed than in any previous month of the year, in most parts of India. The greatest deficiency was in the Central Provinces both north and south of the Satpuras, and in Berar, the Konkan, and on the Deccan plateau. The only province in which the deficiency was insignificant was Assam. And, notwithstanding the unusually low temperature, the relative humidity of the atmosphere was also unduly low, save in the North-West Himalaya, in Bengal, Assam, Arakan, Pegu and the Carnatic; and most so in the Nerbudda Valley, the Gangetic plain and Chutia Nagpur. This was undoubtedly due to the steady persistency of northerly and north-westerly winds, and the consequent entire absence of rain in Northern, Western, and Central India; the only exceptions to the former being Bengal and Assam. In Ceylon and Tenasserim the deficiency of vapour was as marked as elsewhere, and was considerable, even in the south-east of the Bay.

On a general review of the foregoing data, it appears that 1883, like its predecessor, was a comparatively dry year, as regards the proportion of vapour in the atmosphere. Taking the mean of all the Indian stations in Table XVIII, month by month, the following result is obtained :—

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
Number of stations . . .	113	113	109	109	109	110	115	115	114	110	110	111
Mean anomaly . . .	+·004	—·030	—·013	—·009	—·006	+·006	0	—·019	0	—·016	—·029	—·045

and the mean of vapour tension anomaly of the whole year is —·013. There was therefore more or less deficiency in eight months out of the twelve, and an excess, and that but slight, in only two. The deficiency was greatest in December, November, and Febru-

ary, all months of the cold weather, and it was not inconsiderable in March, August, and October. It would appear to have been greatest in South Behar, but this rests on the evidence of a single station, not among the most trustworthy. Next thereto, it was most pronounced in Bengal, the Konkan, Ceylon, the Gangetic plain, the Nerbudda valley and in the south-east of the Bay of Bengal. The eastern coast districts of the Peninsula, and especially the Carnatic, were an exception to the rule, except in the early and closing months of the year. In August and October, owing to the unseasonable prevalence of dry north-western winds, the deficiency in north-western India (and, in the latter month, also in Western Bengal) was greater than at any other season, either there or elsewhere, but this local effect was in part compensated by the higher humidity of the eastern districts in the former case and of the central region of the peninsula in the latter.

The deficiency in the relative humidity of the atmosphere was somewhat less general and pronounced, owing to the prevailing depression of temperature, but still was very decided.

CLOUD PROPORTION.

The proportion of cloud is estimated, in the usual way, in tenths of the sky expanse, an overcast sky being denoted by 10, a cloudless sky by 0. From the very nature of the observations it follows that the estimated amounts at different stations must be affected, to some extent, by the personal equation of the observer; and doubtless some of the differences to be observed in the tables, especially the somewhat anomalous average figures for Jhansi, are, in a measure, to be attributed to this cause; and the general excess of the present year at Demagiri, Saugor and Pachbudra, and high deficiency of Ajmere, Salem, and of some stations in Ceylon and Burma in certain months, are probably due in part to a change in the personal equation of the observer; but, on the whole, the observations are fairly accordant, and the general result of a number of stations, similarly situated, may be accepted with considerable confidence as indicating the variation of cloudiness in different months, or in different parts of the country.

Table XIII (Appendix) gives the monthly means of the observations of stations for the hours of observation (except in the case of the Ceylon stations), and also the daily averages of these. At the large majority of the stations, the hours are 10 h. and 16 h. only (10 A.M. and 4 P.M.), but at Calcutta, Bombay, Allahabad, Jeypore, Lahore, Leh (after August), Vizagapatam, and Saugor Island the observations are recorded four times daily, *viz.*, at the two first mentioned stations and Leh at 6 h. and 22 h. (6 A.M. and 10 P.M.), and the remainder at 4 h. and 22 h., in addition to those of the forenoon and afternoon. At the Madras stations, 10 P.M. is substituted for 4 P.M. Whatever the hours, the figures in the column of means are the averages of those in the subsequent columns, without correction—a practice which has been followed also in previous reports.

Table XXII below, gives the averages similarly obtained from the observations of several years at 117 stations, the averages being in no case taken for less than three years; and Tables XXIII and XXIV shew the differences for the year 1883, in excess or

defect of these averages, first at the individual stations, and second as summarized for the geographical divisions adopted in previous sections of this report.

TABLE XXII.—*Average proportion of clouded sky in each month, deduced from the registers of past years.*

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	3—4	5·74	5·48	5·81	6·54	6·74	4·67	5·99	5·18	5·04	5·40	5·53	4·90	5·59
Quetta	5	3·52	4·02	4·68	3·32	1·63	1·08	1·85	1·47	0·59	0·32	0·91	3·21	2·22
Leh	10	6·07	6·73	6·35	6·16	6·25	4·80	5·04	5·05	3·70	3·83	3·98	5·28	5·27
Mooltan	12	2·44	2·63	2·46	1·64	1·23	1·03	2·34	2·19	1·05	0·26	0·80	1·87	1·66
Dera Ismail Khan	12	2·90	2·90	3·21	2·80	1·69	1·38	2·41	1·98	0·93	0·46	1·46	2·30	2·04
Peshawar	7—8	4·23	4 18	4·56	4·39	2·75	2·07	2·67	2·86	1·69	1·43	1·98	3·45	3·02
Murree	12	5·48	5·36	5·94	5·38	4·22	3·73	6·31	5·75	3·51	2·19	2·98	4·50	4·62
Rawalpindi	12	4·12	4·25	4·26	3·72	2·69	2·16	4·08	3·74	1·95	1·24	1·91	3·04	3·10
Sialkot	12	4·43	4·36	4·49	3·84	2·84	2·42	4·04	4·64	2·61	1·07	2·05	3·22	3·41
Lahore	12	3·05	3·58	3·13	2·37	2·32	2·94	4·45	3·73	1·65	0·83	1·36	2·14	2·63
Ludhiana	12	3·46	3·68	3·75	2·60	1·95	2·84	5·72	4·85	2·66	0·80	1·46	2·55	3·03
Simla	3—4	4·35	5·11	5·33	4·12	3·57	6·38	8·69	8·22	5·07	0·74	1·80	3·62	4·83
Delhi	9—10	3·19	3·06	2·97	2·44	1·95	3·23	5·81	5·57	3·50	0·71	0·79	1·66	2·91
Sirsa	7—8	3·47	4·07	4·24	3·52	2·78	3·30	5·53	5·31	3·00	0·94	1·38	2·63	3·35
Chakrata	12—13	4·35	4·78	4·29	3·56	3·71	5·18	8·72	8·60	6·65	1·81	1·58	3·40	4·72
Dehra	12—13	3·71	4·12	3·54	2·87	2·95	4·40	7·74	7·32	4·74	0·96	1·18	2·48	3·83
Paori	3	?	?	?	?	?	4·04	7·94	7·36	4·67	0·61	1·18	?	?
Roorkee	12—13	3·16	3·51	2·50	2·24	1·86	3·28	6·64	6·14	4·29	0 83	0·89	2·21	3·13
Ranikhet	12—13	3·63	4·53	3·83	3·26	3·69	5·58	8·62	8·40	5·99	1·54	1·24	2·59	4·41
Pithoragarh	3	?	?	?	?	4·15	6·21	7·43	7·18	5·45	1·74	1·15	2·15	?
Meerut	11—13	2·81	2·74	2·56	2·03	1·85	3·13	6·82	6·11	4·12	0·59	0·61	1·67	2·92
Bareilly	12—13	2·79	3·02	2·61	1·70	1·83	3·82	6·82	6·63	4·42	0·75	0·65	1·64	3·06
Agra	12—13	1·87	2·41	1·87	1·40	1·36	3·50	6·28	5 95	3·93	0·70	0·57	1·23	2·59
Lucknow	12—13	2·75	3·16	2·85	2·08	2·02	4·64	7·56	7·23	5·44	1·42	0·87	1·71	3·48
Gorakhpur	11—13	1·68	1·98	1·63	1·18	1·89	4·14	5·60	5·48	4·43	1·76	0·75	0·87	2·62
Jhansi	9—13	0·70	0·68	0·38	0·38	0 65	1·72	4·37	3·70	1·99	0·26	0·31	0·28	1·20
Allahabad	12—13	1·86	2·15	1·87	1·40	1·60	4·53	7·76	7·23	5·36	1·54	0·95	1·45	3·14
Benares	12—13	2·17	2·30	2·13	1·77	1·98	4·98	7·58	7·23	5·47	2·28	1·23	1·47	3·38
Katmandu	4—5	2·92	3·16	3·71	3·74	4·98	6·34	6·61	7·32	6·21	3·79	1·87	2·52	4·43
Sibsagar	10	5·59	6·25	6·68	7·47	8·40	8·86	8·88	8·91	8·43	7·04	4·98	4·74	7·19
Dhubri	3	?	?	?	3·15	5·11	7·44	6·40	7·38	6·64	2·36	1·26	0·91	?

TABLE XXII.—*Average proportion of clouded sky in each month, deduced from the registers of past years*—continued.

Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Silchar	14—15	2·75	3·04	4·06	5·01	6·03	7·54	7·57	7·50	6·93	4·59	3 10	2·79	5·08
Darjeeling (*St. Paul's School.*)	14—15	5·52	5·05	5·21	6·06	7·21	8·73	8·68	8·58	8·22	5·18	4·16	4·03	6·44
Purneah	8—10	1·21	1·20	1·57	1·61	3·38	5·88	7·04	7·00	5·98	3·31	1·01	1·03	3·35
Durbhunga	6—8	1·52	2·12	1·95	1·52	2·34	5·10	6·55	6·30	5·80	3·46	1·01	1·07	3·23
Patna	14—15	2·47	2·68	3·09	2·23	3·00	6·32	8·06	7·94	6·98	3·70	1·77	1·84	4·17
Gya	12—14	1·81	2·44	2·22	1·59	2·03	6·60	8·23	8·35	6·87	3·42	1 83	1·66	3·97
Hazaribagh	14—15	2·25	2·09	2·57	2·57	3·28	7·24	8·91	8·42	7·55	4·05	2·21	1·86	4·42
Berhampore	14—15	2·20	1·96	2·84	3·17	5·30	8·24	8·74	8·68	8·06	4·81	2·57	1·89	4·87
Burdwan	10—11	1·75	1·95	2·27	2·51	3·95	7·45	8·10	8·09	7·08	4 32	2·52	1·80	4·32
Jessore	15	1·58	1·83	2·83	3·50	4·97	7·67	8·25	7·79	7·35	4·61	2·24	1·45	4·51
Dacca	15	1·66	1·88	3·10	4·01	5·42	7·78	8·10	7·88	6·93	4·08	2·01	1·32	4·51
Chittagong	15	1·26	1·61	2·86	3·93	4·90	7·38	7·41	7·11	6·40	4·21	2·57	2·08	4·31
Demagiri	5—7	0·27	0·71	1·10	1·61	2·52	4·04	4·24	4·00	3·14	1·55	0·85	0·93	2·08
Calcutta (*Alipore*)	6—7	1·32	1·98	2·34	2·87	4·63	7·17	8 01	8·06	7·03	4·20	2·34	1·95	4·33
Saugor Island	14—15	1·73	1·92	3·48	4·63	5·49	7·45	7 86	7·40	6·66	4·46	2·49	1·87	4·62
Cuttack	15	1·74	1·71	2·30	2·95	3·89	6·64	7·48	6·92	6·17	4·18	2·28	1·61	3·99
False Point	7—8	2·02	2·52	2·78	3·05	4·25	6·63	7·78	7·55	6·41	4·43	3·23	2·49	4·43
Sambalpur	13	1·29	1·47	1·66	2·24	2·57	4·99	6·45	6·21	5·13	2·71	2·25	1·64	3·22
Raipur	15	1·32	1·07	1·63	2·08	3·25	6·20	8·04	7 53	6·23	2·91	1·85	1·19	3·61
Nagpur	15	2·30	1·92	2·51	3·05	4·23	7·12	8·56	8 27	7·43	3·97	2·57	2·20	4·51
Seoni	13—15	3·74	3·81	3·41	3·75	3·50	4·02	4·60	4·29	3·87	4·02	3·82	3·67	3·88
Jubbulpore	15	2·20	2·28	2·39	2·18	3·39	6·48	8·63	8·04	6·45	2·71	1·79	1·84	4·03
Saugor	12—14	1·28	1·49	1·24	1·20	1·92	3·79	5·83	5·48	4·09	1·23	1 04	0·83	2·43
Pachmarhi	13	2·15	2·07	2·05	2·09	2·83	6·54	8·57	8·18	7·27	2·86	1·95	1·91	4·04
Hoshangabad	13—14	1·75	1·61	1·86	2·09	2·73	5·90	8·06	7·24	5·93	2·11	1·34	1·27	3·49
Khandwa	10—13	1·45	1·39	1·55	1·71	2·35	5·97	7·90	7·32	5·30	1·99	1·47	1·53	3·33
Chanda	13—14	2·15	2·07	2·40	2·97	3·95	7·17	8·68	8·19	7·27	3·74	2·84	2·45	4·49
Sironcha	7—8	1·34	1·37	1·72	1·92	2·58	5·92	7·31	6·95	6·15	3·30	2·66	1·56	3·57
Chikalda	7—8	1·64	1·24	1·65	1·77	2·37	6·35	8·90	8·51	7·40	2·96	1·86	1·42	3·84
Buldana	7—9	2·39	2·06	2·31	2·24	2·85	6 34	7·92	7·36	6·98	4·37	2·74	2·43	4·17
Akola	9	1·38	1·71	1·18	1·21	1·96	6·38	8·43	7·87	6·33	2·45	1·37	1·17	3·45
Amraoti	9	1·82	1·77	1·79	2·19	3·35	7·00	8·48	7·96	7·20	3·77	2·21	2·15	4·14
Makhla	5	2·02	2·47	2·48	2·56	3·34	7·86	9·45	8·97	8·68	3·83	2·84	1·64	4·68
Neemuch	6—7	2·08	2·97	2·53	2·04	2·28	5·04	8·05	7·56	5·79	2·09	0·83	1·48	3·56

TABLE XXII.—*Average proportion of clouded sky in each month, deduced from the registers of past years*—continued.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Nowgong	6—7	2·13	3·21	2·46	2·03	3·01	5·07	8·23	7·61	5·44	2·28	1·04	1·42	3·66
Sutna	7—8	2·26	2·52	2·37	2·33	2·96	5·27	7·16	6·68	5·56	2·32	1·35	1·37	3·51
Indore	6—7	2·05	1·97	2·09	1·56	2·56	6·35	8·29	8·15	6·80	3·14	1·50	1·52	3·83
Bickaneer	4—7	2·84	4·14	4·09	2·89	2·69	2·84	6·17	6·26	4·01	1·48	0·96	2·43	3·40
Jeypore	3	2·40	2·78	2·89	2·04	2·36	3·90	7·64	5·88	4·16	1·41	0·81	1·56	3·15
Sambhar	3—4	2·54	2·26	2·44	1·32	1·75	3·23	6·83	5·26	3·96	1·14	0·62	1·65	2·75
Ajmere	12—13	2·37	2·49	2·58	2·20	1·87	3·66	6·50	6·28	3·59	0·91	0·94	1·36	2·90
Mount Abu	6—8	2·80	3·31	3·13	2·66	2·17	5·54	8·72	8·14	6·49	2·45	1·24	1·87	4·04
Pachbudra	4—5	1·70	2·13	1·77	1·20	1·43	2·43	5·78	5·18	3·52	1·14	0·62	1·39	2·36
Jacobabad	5—7	2·02	3·03	3·14	2·79	1·31	0·97	2·31	2·37	0·81	0·29	1·06	2·02	18·4
Hyderabad	5—7	1·77	2·44	2·08	1·31	0·77	1·49	3·01	3·29	1·67	0·42	0·85	1·16	1·69
Kurrachee	8—9	2·57	3·12	3·32	2·26	2·37	4·62	7·31	6·90	4·67	1·13	1·44	2·22	3·49
Bhuj	6—8	1·06	1·41	1·13	0·84	1·42	3·45	6·40	5·96	4·06	1·10	0·57	0·78	2·35
Rajkot	5—7	1·35	2·07	1·73	1·37	1·58	5·65	8·24	7·86	6·40	2·26	0·98	1·21	3·39
Deesa	9	2·03	2·31	2·40	1·55	1·39	4·27	7·69	7·26	5·15	1·46	1·16	1·49	3·18
Surat	6—7	0·71	0·70	0·70	0·86	1·51	5·44	7·98	6·80	5·64	2·16	0·56	0·68	2·81
Malegaon	6—7	1·67	1·24	1·83	1·78	2·07	5·67	7·49	7·19	6·41	3·22	1·94	1·57	3·51
Bombay	37	1·59	1·34	1·83	2·34	4·15	7·98	9·13	8·85	7·51	4·31	2·22	1·77	4·42
Poona	8—9	1·99	1·63	2·53	2·31	3·05	7·75	9·07	8·85	8·13	5·00	2·87	2·51	4·64
Sholapur	7	2·41	1·95	2·59	3·13	4·01	7·26	8·11	7·98	8·15	5·75	3·70	2·65	4·81
Ratnagiri	7	0·62	0·67	0·72	0·73	1·70	6·81	7·50	7·22	6·38	3·40	1·26	0·85	3·16
Belgaum	8—9	1·88	1·42	2·20	2·58	3·53	7·68	8·76	8·46	7·83	5·62	3·82	2·72	4·71
Karwar	6	1·11	0·93	2·24	2·63	3·43	7·58	7·53	7·16	6·49	4·73	2·94	1·35	4·01
Gopalpore	3	0·97	1·12	1·12	2·23	2·61	5·14	6·64	?	?	?	?	?	?
Vizagapatam	14	1·76	1·39	1·81	2·66	4·12	5·82	6·64	6·25	5·57	4·44	3·22	2·34	3·84
Masulipatam	13—14	3·27	3·13	3·44	3·90	4·89	6·57	6·86	6·44	6·09	5·28	4·81	3·82	4·88
Secunderabad	11—13	1·74	1·30	1·58	1·72	2·41	5·14	6·41	5·75	5·59	3·91	2·81	1·88	3·35
Bellary	13—14	2·52	1·54	2·43	3·34	5·01	7·48	8·08	7·48	7·34	6·34	4·87	3·34	4·98
Mangalore	3—4	2·04	1·62	2·33	3·35	4·64	7·90	7·46	7·10	6·37	5·47	4·43	2·18	4·57
Mercara	3—4	3·37	2·30	4·04	5·62	6·91	9·74	9·90	9·55	9·14	7·80	7·29	4·47	6·68
Bangalore	13—14	2·84	2·31	2·69	3·53	4·64	5·91	6·41	6·36	6·12	5·74	4·95	3·97	4·62
Madras	14	4·08	2·83	2·56	3·05	4·02	6·56	7·19	6·50	6·22	6·17	6·30	5·31	5·07
Salem	14	2·75	1·94	2·28	3·71	4·84	6·19	6·54	6·42	5·90	5·98	5·29	4·07	4·66
Wellington	10—12	3·38	2·88	3·07	4·51	5·60	7·46	7·67	7·46	7·02	7·19	7·20	5·56	5·75

TABLE XXII.—*Average proportion of clouded sky in each month, deduced from the registers of past years*—concluded.

STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Coimbatore	14	3·53	2·57	3·09	4·52	5·56	6·80	6·74	6·32	5·84	6·30	6·15	4·80	5·19
Trichinopoly	13—14	4·32	2·99	3·32	4·64	5·67	7·46	7·85	7·90	7·48	7·70	7·33	5·77	6·04
Negapatam	14	4·54	3·70	3·23	3·44	4·24	5·02	5·18	5·30	5·19	5·81	6·36	5·88	4·82
Madura	14	4·40	4·08	4·08	4·68	5·09	5·60	5·48	5·47	5·17	5·47	5·70	5·18	5·03
Cochin	12—13	2·46	2·50	3·29	3·96	5·67	7·74	7·13	6·17	5·53	5·83	4·73	3·22	4·85
Colombo	13—14	4·94	4·21	4·94	5·59	6·73	7·48	6·93	7·16	6·95	6·71	6·22	5·81	6·14
Jaffna	13	4·28	3·00	2·72	3·68	3·92	5·56	5·51	5·52	5·05	5·55	6·34	5·90	4·75
Trincomalee	13—14	5·67	4·44	4·00	4·09	5·00	6·18	5·71	5·67	5·70	5·88	6·05	6·34	5·39
Batticaloa	13—14	6·70	5·78	5·14	5·40	5·22	6·20	6·31	6·79	6·39	6·35	6·76	6·69	6·14
Hambantota	14	6·87	6·63	6·19	7·11	7·24	7·99	7·76	7·88	7·62	7·41	7·36	6·79	7·24
Galle	14	5·66	4·90	5·15	5·99	6·79	7·12	6·65	6·69	6·56	6·84	6·49	5·60	6·20
Kandy	13—14	5·06	4·29	4·66	5·33	5·66	6·76	6·47	6·50	6·42	6·30	5·92	5·86	5·77
Newera Eliya	11—14	5·01	3·80	3·88	5·06	5·68	7·97	7·46	7·14	6·57	6·48	5·88	5·66	5·88
Akyab	13—15	1·69	1·08	1·95	3·07	5·45	6·88	8·53	8·08	7·04	4·86	3·18	2·57	4·53
Thayetmyo	5—6	1·96	0·79	1·16	2·30	4·42	5·76	5·97	5·57	5·23	4·71	3·36	2·67	3·66
Tounghoo	5—6	0·76	0·24	0·39	1·63	4·52	7·32	7·50	8·01	6·37	3·80	2·48	1·80	3·74
Bassein	7	2·11	0·83	0·94	3·38	6·62	8·73	8·96	8·77	8·34	6·86	4·18	3·43	5·26
Diamond Island	5—6	2·79	2·34	2·63	3·70	5·60	7·58	7·53	7·34	7·07	5·69	4·63	3·60	5·04
Rangoon	7—8	2·46	2·15	2·60	3·95	6·90	8·80	8·86	8·94	8·39	6·34	4·42	3·33	5·60
Moulmein	4—5	0·86	0·70	0·78	2·98	5·75	8·70	8·76	8·60	6·91	3·71	1·07	1·61	4·28
Mergui	5—6	1·94	2·29	3·14	5·26	7·02	8·94	8·83	8·44	8·50	7·10	4·73	3·10	5·77
Port Blair	14—15	3·47	2·83	2·92	4·23	6·16	6·91	7·07	6·86	6·94	5·83	5·00	4·55	5·23
Nancowry	10—11	5·20	4·49	4·66	5·40	6·65	7·49	6·95	6·98	6·96	7·11	6·83	5·88	6·22

TABLE XXIII.—*Comparison of mean cloud proportion in each month of 1883 with the averages of Table XXII.*

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	−0·79	−2·13	−1·17	−1·78	−0·23	−0·57	−0·04	−0·29	−0·70	−1·01	−1·40	−1·11	−0·94
Quetta	+1·68	+0·46	+0·74	+2·37	−0·01	+0·30	+1·06	−0·45	−0·14	+0·01	−0·29	+0·05	+0·48
Leh	+1·14	+0·36	+0·49	+0·38	+1·66	−0·65	−1·52	−0·86	−0·26	+0·93	+1·55	−0·09	+0·26
Mooltan	+0·62	+0·10	+0·27	+0·04	−0·26	−0·73	−0·44	−1·21	−0·15	+0·18	−0·37	−0·90	−0·24

XXIII.—*Comparison of mean cloud proportion in each month of 1883 with the averages of Table XXII*—continued.

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Ismail Khan	+0·38	−0·63	+0·08	+0·73	+0·75	+1·36	−0·29	−0·52	+0·36	+0·41	−0·51	−0·33	+0·15
Kasar	+1·66	−0·64	+0·48	+1·01	−0·99	+0·48	+0·52	−0·33	+0·08	+0·68	−0·13	−0 41	+0·20
Kohat	+1·54	−0·88	+0·29	+1·22	+0·11	−0·30	−0·97	−0·18	+0·31	+0·78	+0·01	−0·56	+0·11
Kushalgarhindi	+0·56	−1·25	−0·68	−0·02	−0·64	−0·49	−1·13	−1·11	+0·10	+0·65	+0·64	−0·78	−0·35
Sialkot	+1·57	−0·84	+0·05	+0·73	+0·1	−0·95	−1·44	−1·41	+0·33	+0·06	+0·27	−0·01	−0·12
Lahore	+0·29	−0·95	−0·44	+0·39	−0·37	−0·31	−0·99	−1·15	+0·28	−0·39	−0·21	−0·61	−0·37
Ludhiana	+0·87	−0·61	−0·04	−0·12	−0·57	−1·14	−1·09	−1·32	+0·58	+0 14	+0·24	−0·0	−0·26
Simla	+1·91	−0·75	+0·22	−0·42	+0·17	−1·91	−0·63	−1·57	−0·10	+0·92	+1·42	−1·35	−0·17
Delhi	−0·46	−1·15	−0·20	−1·32	−0·45	−0·44	+0·27	−1·46	+0 42	+0·50	+0·66	−0·40	−0·34
Sirsa	+1·31	−0·80	+0·29	−0·45	−0·73	−0·26	−0·43	−1·92	+1·15	+0·22	+0·44	−0·61	−0·15
Chikrata	+1·67	−1·61	+0·52	−0·36	−1·00	−0·43	+0·11	−0·92	+0·42	−0·87	+1·10	−1·06	−0·20
Dehra	+1·45	−1·26	+0·99	−0·30	−0·95	−0·30	+0·10	−0·92	+0·78	−0·14	+0·99	−0·20	+0·02
Paori	?	?	?	?	?	+0·03	+0·31	−0·86	+1·01	+0·58	+1·09	?	?
Roorkee	+1·57	−0·83	−2·15	−0·42	−0·10	−0·66	+0·49	−1·21	−0·29	−0·15	+0·63	−0·71	−0 32
Ranikhet	+1·56	−1·48	+0·52	−1·42	−0·46	−0·64	+0·54	−1·19	+0·43	+0·06	+0·70	−0·99	−0·20
Pithoragarh	?	?	?	?	−0·46	−1·21	+0·22	−0·28	+0·57	+0·09	+0·68	−0 26	?
Meerut	+0·90	−0·28	+0·70	−0·99	−0 04	−0·78	−0·56	−1·71	−0·74	−0·30	+0·53	−0·60	−0·32
Bareilly	+0·37	−0·21	+0·64	−0·72	−0·13	−1·58	+0·18	−0·69	+0·48	−0·14	−0 05	−0·96	−0·23
Agra	+1·34	+0·05	+1·52	−0·67	+0·64	+0·15	+0·93	−1·48	+0·60	+0·24	+0·20	−0·94	+0·22
Lucknow	+0·09	−0·67	+0·22	−1·34	−0·86	−0·48	−0·06	−0·61	−0·86	−0·24	−0·78	−1·26	−0·57
Gorakhpur	+0·15	−0·41	+0·71	−0·43	−1·07	+0·18	−0·63	−0·98	−0·26	−0·32	−0·75	−0·55	−0·36
Jhansi	+1·13	−0·34	+0·14	−0·38	−0·24	+0·28	−0·55	−1·54	−0·12	+0·48	−0·31	−0·28	−0·14
Allahabad	+0·39	+0·56	+0·46	−0·72	−0·27	+0·74	−0·39	−0·82	−0·10	+0·78	−0·74	−0·89	−0·08
Benares	+0 51	+0·20	0	−1·12	−0·83	+0·75	−0·05	−0·37	+0·07	−0·04	−0·86	−0·68	−0·20
Katmandu	+2·31	−0·80	+0·95	+2·16	+0·86	+0·18	−0·03	+0·68	+0·84	−0·80	−0·10	−0·35	+0·49
Sibsagar	−0·12	−0·64	−0·05	−1·68	−0·46	+0·01	−1·17	−0·08	−0·43	−2·50	−0·61	−0·05	−0·65
Dhubri	?	?	?	−0·03	+0·65	−0·19	+0·27	−0·03	−0·56	−0·90	−0·84	+0·71	?
Silchar	−0·39	−0·54	+0·38	−0·72	+1·96	+1·03	+0·16	+0·96	+0·72	−0·42	+0·85	+1·00	+0·42
Darjeeling (*St. Paul's* School).	−1·13	−1·05	−0·65	−0·20	−0·10	−0·13	−0·30	+1·04	+0·50	+0·04	−0·50	−1·64	−0·34
Purneah	+0·46	+0·05	+0·43	−0·06	+0·40	+1·09	+1·19	+1·66	+1·27	−0·16	−0·56	+0·20	+0·50
Durbhunga	+0·61	−0·63	−0·17	−0·64	−0·23	+0·62	−0·09	−0·25	−0·23	−1·00	−0·76	−0·79	−0·30
Patna	+0·61	+0·09	+0·22	−1·39	−1·16	+0·92	+0·65	+0·24	−0·61	−0·38	−1·27	−0·90	−0·25
Gya	+1·76	+1·19	+1·20	−0·99	−1·05	+0·70	+1·16	+1·62	+1·13	−0·52	−0·83	−1·12	+0·35
Hazaribagh	+0·27	+0·48	+0·96	−1·18	+0·41	+1·28	+0·50	+1·33	+0 82	−1·10	−0·79	+0·05	+0·25

TABLE XXIII.—*Comparison of mean cloud proportion in each month of 1883 with the average of Table XXII*—continued.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Berhampore	−0·49	−0·05	−0·03	−0·40	+0·56	+0·45	+0·39	+0·79	−0·33	−1·48	−1·14	+0·24	−0·12
Burdwan	+0·40	+0·43	+0·60	+0·01	+0·54	+0·30	+0·86	+1·20	+0·74	−1·30	−0·80	+0·36	+0·28
Jessore	+0·09	+0·37	+0·85	+0·68	+1·79	+1·05	+1·44	+1·55	+1·15	−1·06	+0·70	+1·51	+0·48
Dacca	−0·66	−0·07	−0·58	+0·07	+1·00	−0·14	−1·45	−0·17	−0·64	−1·63	−0·04	+1·10	−0·27
Chittagong	+0·07	+0·43	+1·32	+0·72	+0·96	+0·22	+0·17	+0·20	+0·30	−1·08	+0·45	+1·73	+0·46
Demagiri	+0·06	+0·56	+1·38	+1·14	+3·59	+3·23	+2·91	+3·50	+3·56	+1·65	+1·25	+1·60	+2·04
Calcutta (*Alipore*)	+0·34	+0·45	+1·08	+0·25	−0·14	+0·77	+0·75	+0·72	+1·14	−1·10	−0·53	+0·08	+0·32
Saugor Island	−0·48	+0·58	−0·29	−0·37	−0·23	−0·49	+0·04	+0·80	+0·62	−0·52	−0·58	+1·12	+0·02
Cuttack	+0·26	+1·08	+1·32	−0·36	−0·15	+1·18	+0·96	+0·55	+0·78	+0·15	−0·84	+0·59	+0·46
False Point	−0·25	+1·00	−0·13	+0·27	−0·30	+0·99	+0·72	+0·49	+0·91	+0·61	−0·33	+0·11	+0·34
Sambalpur	+0·38	+0·09	+0·39	−0·85	−0·57	+1·18	+1·39	+0·79	+0·86	−0·30	−2·12	−0·24	+0·08
Raipur	+0·62	+0·34	+0·95	−0·08	−1·49	+1·65	+0·69	−0·22	+1·87	+0·51	−0·40	−0·54	+0·33
Nagpur	+0·67	+1·28	+0·36	+0·20	−0·57	+0·85	+0·10	−0·79	+0·99	−0·11	−1·48	−1·42	+0·01
Seoni	−0·48	−1·13	−0·45	−0·88	−0·48	+0·62	+0·34	−0·56	+0·98	−0·77	−1·55	−1·43	−0·48
Jubbulpore	+0·77	+0·40	+0·63	+0·64	−1·13	−0·26	+0·52	−1·33	+1·14	+1·10	−0·27	−0·68	+0·13
Saugor	+2·64	+1·60	+2·10	+1·29	+0·62	+1·79	+1·35	+0·44	+1·56	+2·30	+0·14	+0·01	+1·32
Pachmarhi	+1·31	+0·74	+0·24	+0·91	−0·60	+0·84	+0·77	−0·26	+1·55	+1·55	−0·23	−0·70	+0·51
Hoshangabad	+0·98	−0·05	+0·16	+0·05	−0·70	−0·37	+0·02	−0·51	+1·59	+1·70	−0·54	−0·56	+0·15
Khandwa	+1·71	+0·95	+0·74	+0·06	−0·17	+0·76	+0·16	−0·40	+2·40	+2·46	−0·17	−0·35	+0·68
Chanda	−0·20	−0·12	−0·07	−0·85	−1·84	+0·30	−0·87	−1·01	+0·26	−0·72	−1·30	−0·38	−0·57
Sironcha	+0·71	−0·24	+1·40	−0·15	−0·26	+1·43	+0·16	−0·27	+1·20	+0·19	−1·28	+0·43	+0·28
Chikalda	+1·18	+0·26	−0·13	+0·58	−0·51	+1·95	+0·30	−2·01	+1·60	+1·25	−0·49	−0·35	+0·30
Buldana	+0·93	+0·39	+0·21	+0·08	−0·81	+0·56	−0·08	−0·31	+0·94	+0·40	−0·42	−0·51	+0·12
Akola	+0·77	−0·57	−0·16	+0·08	−0·67	+0·64	−0·88	−1·29	+1·67	+0·65	−0·52	−0·93	−0·10
Amraoti	+1·12	+0·86	+0·31	−0·02	−1·09	+0·68	+0·08	−0·58	+1·24	+0·77	−1·07	−0·54	+0·15
Makhla	+1·56	+0·19	−0·02	+1·71	−0·62	+0·53	−0·37	−0·95	+0·66	+1·01	+0·03	+0·78	+0·38
Neemuch	+1·52	+0·85	+1·25	−0·54	−0·19	+0·63	+0·86	−1·06	+1·56	+1·33	+0·22	+0·09	+0·54
Nowgong	+1·79	+0·11	+0·93	+0·07	+0·35	+0·88	+0·45	−0·19	+0·61	+0·98	−0·27	−0·29	+0·45
Sutna	+0·85	−0·23	−0·37	−0·79	−1·34	−0·65	−0·37	−1·10	−0·76	+0·16	−1·00	−0·74	−0·53
Indore	+1·26	+0·25	+0·33	+0·26	−0·88	+1·12	+0·95	+0·17	+1·47	+1·25	−0·85	−0·84	+0·37
Bickaneer	+1·19	−0·42	+0·51	−0·32	−0·21	−0·85	+0·11	−2·97	+1·71	+1·65	+0·31	−1·01	−0·03
Jeypore	+0·66	+0·28	+0·18	−0·56	−0·39	−0·41	−0·67	−2·20	+0·77	+1·20	+0·52	−0·76	−0·12
Sambhar	+0·64	+0·26	+0·11	−0·38	−0·52	−0·29	−0·94	−1·98	+0·66	+0·41	+0·33	−0·96	−0·22
Ajmere	−0·54	−0·99	−1·14	−1·75	−1·29	−2·06	−2·06	−4·31	+0·11	+0·48	−0·25	−0·99	−1·23

TABLE XXIII.—*Comparison of mean cloud proportion in each month of 1883, with the averages of Table XXII*—contd.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Mount Abu	+0·35	−0·38	+0·16	−1·51	−0·15	−0·51	+0·28	−2·44	+0·55	+0·07	0	−0·92	−0·38
Pachbudra	+0·20	−0·36	+0·10	−0·83	+0·52	+0·27	+0·04	+0·05	+2·41	+1·39	+0·58	−0·18	+0·35
Jacobabad	−0·08	−0·42	−0·91	−1·44	−0·83	−0·72	+0·01	−1·90	−0·23	+0·26	+0·18	+0·21	−0·49
Hyderabad	−0·25	−0·40	−1·13	−0·71	−0·24	−0·30	+0·28	−2·33	−0·03	−0·18	−0·26	−0·24	−0·48
Kurrachee	−0·05	+0·67	−0·43	−0·63	+0·47	−0·43	+0·58	−0·09	+0·71	−0·24	−0·42	−0·54	−0·03
Bhuj	+0·72	+0·65	+1·66	−0·30	−0·13	+0·40	+2·44	+1·75	+2·89	+0·21	+0·68	−0·18	+0·90
Rajkot	−0·30	−0·82	+0·03	−0·85	−0·26	−0·48	−0·04	−1·34	+0·60	−0·53	−0·44	−0·88	−0·44
Deesa	−0·01	0	−0·58	−1·03	−0·11	−0·38	+0·51	−0·84	+1·69	+0·75	−0·12	−0·62	−0·06
Surat	+0·11	−0·31	−0·10	−0·29	+0·43	+1·06	+0·21	−0·43	+1·23	+0·26	−0·39	−0·31	+0·12
Malegaon	+0·72	+0·01	+0·19	+0·19	−0·26	+2·62	+1·14	+0·28	+2·24	+1·48	−1·10	−1·57	+0·50
Bombay	−0·25	0	−0·19	−0·80	−1·56	+1·03	+0·11	−0·62	+1·25	+0·11	−1·42	−0·16	−0·21
Poona	+0·49	+0·73	−0·05	+0·43	+0·18	+1·37	−0·52	−0·80	−0·08	+0·44	−0·57	−0.67	+0·08
Sholapur	−0·79	−0·65	−0·78	−0·53	−1·45	+1·77	+0·46	−0·30	−0·43	−0·94	−2·00	−0·10	−0·48
Ratnagiri	−0·25	−0·31	+0·44	+0·22	−0·31	+1·84	+0·65	−0·57	+0·59	−0·51	+0·29	+0·43	+0·21
Belgaum	+1·21	+0·30	+0·98	−0·28	+0·28	+1·19	+·050	+0·02	+0·31	+1·08	−0·70	+1·06	+0·50
Karwar	−0·04	−0·23	−0·08	−0·05	−0·57	+0·22	−0·41	−1·53	−1·12	+0·05	−1·30	+0·44	−0·39
Gopalpore	+0·01	+0·58	+0·54	+0·42	+0·86	+0·90	+0·35	?	?	?	?	?	?
Vizagapatam	+0·01	−0·35	+0·92	+0·01	−0·72	+0·97	+0·34	−0·08	+0·43	−0·49	−1·78	+0·57	−0·01
Masulipatam	−1·16	−0·21	+0·48	+0·37	−0·71	+0·43	−0·33	−0·84	−1·85	−1·16	+0·84	+1·81	−0·19
Secunderabad	+1·26	+0·33	+1·66	+1·13	+1·34	+2·65	+1·57	+1·51	+2·03	+2·26	−0·41	+0·85	+1·35
Bellary	−0·19	−0·58	+0·38	+0·04	−0·81	+1·07	+0·36	+0·31	−0·94	+0·95	−1·76	0	−0·10
Mangalore	+0·43	+0·11	+0·83	−0·23	+1·02	+1·02	+1·08	+0·77	−0·30	+0·95	−1·48	+0·31	+0·38
Mercara	+1·46	+0·54	+1·19	+0·50	+0·90	+0·06	+0·05	−0·31	−0·31	+1·19	−1·41	+0·99	+0·40
Bangalore	+0·20	+0·03	+0·16	−0·38	−0·86	−0·60	+0·12	−0·56	−1·36	+0·02	−0·37	+0·46	−0·26
Madras	+0·56	−0·19	+0·52	+0·10	−0·40	+0·13	+0·31	−0·63	−0·17	+1·49	−0·20	+1·44	+0·25
Salem	−0·41	−0·24	−0·56	−1·47	−2·16	−3·31	−2·92	−2·45	−2·78	−0·97	−1·29	−0·28	−1·57
Wellington	+1·90	−0·66	+0·93	0	−0·44	−0·55	−0·40	+0·23	−1·45	+0·01	−0·39	+1·63	+0·07
Coimbatore	−0·02	−0·79	−0·06	−1·63	−1·65	−1·39	−0·96	−1·07	−1·99	−0·61	−0·80	+0·15	−0·90
Trichinopoly	−0·28	−0·12	−1·35	−1·28	−0·93	−1·74	−0·75	−1·86	−2·07	+0·47	−0·75	+0·85	−0·82
Negapatam	+0·72	+0·48	+0·55	+0·04	+0·87	+0·73	+0·62	+0·07	+0·10	+0·95	+0·64	+0·61	+0·53
Madura	+0·12	+0·08	−0·08	−0·01	+0·02	−0·97	−1·11	−0·43	−0·14	+0·84	+0·27	+0·57	−0·09
Cochin	+1·14	+0·12	+0·61	+1·53	+1·45	+0·85	+1·05	+0·67	−0·43	+1·09	+0·37	+0·09	+0·71
Colombo	+0·86	+0·49	−0·64	+0·51	+0·47	+0·52	+0·87	+0·64	+1·25	+1·69	+2·18	+1·69	+0·88
Jaffna	+0·32	+0·20	−0·82	+0·02	+0·28	−0·16	+1·49	+0·58	+0·05	+1·95	+1·56	+1·20	+0·56

TABLE XXIII.—*Comparison of mean cloud portion in each month of 1883 with the averages of Table XXII*—concluded.

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Trincomalee	+1·83	+2·86	+0·90	+1·81	−0·10	−0·58	−0·51	+0·13	−0·40	+1·02	+2·25	+0·96	+0·85
Batticaloa	+0·90	+0·22	−0·34	−0·20	+1·08	+1·00	+0·99	+1·41	+1·41	+2·25	+2·24	+2·31	+1·11
Hambantota	−0·27	−1·13	−0·79	−1·01	−0·94	−1·39	−1·26	−0·68	−1·22	−0·01	+0·74	−0·49	−0·65
Galle	+0·04	−0·30	−0·15	−1·19	−0·29	−0·92	−0·55	−1·19	−0·66	−0·84	−0·09	−1·00	−0·60
Kandy	+0·24	+1·11	+0·34	+0·37	+0·64	+0·54	+0·53	+0·70	−0·42	+0·80	+0·98	+0·54	+0·53
Newera Eliya	+0·99	−0·30	+0·62	+0·84	−0·38	−0·17	+0·14	+0·96	+0·03	+1·32	+1·92	+1·94	+0·66
Akyab	−0·66	−0·17	+0·45	+0·10	+0·36	+1·58	+0·38	+0·86	+0·11	−1·42	+0·04	+1·64	+0·27
Thayetmyo	−0·47	−0·30	+0·55	−0·07	+0·21	+1·67	+1·31	+1·46	+1·37	+0·10	+1·31	+1·36	+0·71
Tounghoo	−0·76	−0·24	−0·24	+0·22	+0·63	+1·70	+1·82	+1·60	+1·51	+0·19	+1·57	+0·70	+0·73
Bassein	−1·06	−0·79	−0·54	−0·81	+0·27	−0·26	−0·12	+0·15	+0·26	−1·17	+1·82	+2·36	+0·01
Diamond Island	−0·29	−0·36	+0·23	−0·41	−0·39	+0·67	+0·20	+0·41	+0·06	−1·14	+0·72	+0·74	+0·04
Rangoon	−0·94	−0·17	−0·21	−0·60	−0·25	−1·75	−2·10	−1·63	−0·56	−2·08	+0·70	−0·33	−0·83
Moulmein	−0·86	−0·11	+0·20	−0·79	−0·84	−0·12	−0·24	−1·36	−0·64	−1·58	+0·53	−0·77	−0·55
Mergui	−1·13	+1·02	+0·72	+1·69	+1·35	+0·45	+0·48	+0·69	+0·64	+0·39	+2·42	+1·34	+0·84
Port Blair	+0·95	−1·13	−0·66	−0·26	+0·60	+0·79	+0·74	+0·50	+0·28	−0·30	+0·55	+2·16	+0·35
Nancowry	+0·33	−0·34	+1·00	+1·07	+0·39	+0·32	+0·28	−0·40	+0·19	−0·24	+1·04	+1·20	+0·80

TABLE XXIV.—*Geographical summary of the differences of Table XXIII.*

Areas.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
North-West Himalaya.	5—7	+1·56	−0·87	+0·41	−0·12	0	−0·73	−0·28	−0·84	+0·34	+0·36	+0·94	−0·72	0
Sikkim Himalaya and Nepal.	2	+0·59	−0·93	+0·15	+0·98	+0·38	+0·03	−0·17	+0·86	+0·67	−0·38	−0·30	−1·00	+0·07
Punjab plains	9	+0·76	−0·75	−0·02	+0·11	−0·34	−0·28	−0·56	−1·18	+0·35	+0·27	+0·11	−0·46	−0·17
Gangetic plains	12	+0·70	−0·28	+0·30	−0·73	−0·38	+0·05	+0·15	−0·60	+0·01	−0·15	−0·29	−0·69	−0·16
Western Rajputana, Sind, Cutch, Gujarat, &c.	9	+0·20	−0·16	−0·07	−0·85	−0·10	−0·33	+0·47	−1·12	+1·14	+0·38	+0·06	−0·48	−0·07
Eastern Rajputana and Central India.	9	+1·11	+0·20	−0·39	−0·31	−0·43	+0·14	−0·11	−1·31	+0·65	+0·95	−0·16	−0·53	−0·05
Nerbudda Valley	3	+1·15	+0·43	+0·51	+0·25	−0·67	+0·04	+0·23	−0·75	+1·71	+1·75	−0·33	−0·53	+0·32
South Behar and Chutia Nagpur.	2	+1·02	+0·84	+1·08	−1·09	−0·32	+0·99	+0·83	+1·48	+0·98	−0·81	−0·81	−0·54	+0·30
Lower Bengal	6	−0·13	+0·29	+0·27	+0·04	+0·59	+0·32	+0·34	+0·82	+0·45	−1·18	−0·40	+0·74	+0·18
Assam and Cachar	2—3	−0·26	−0·59	+0·17	−0·81	+0·72	+0·28	−0·25	+0·28	−0·09	−1·27	−0·20	−0·55	−0·12
Orissa and Sambalpur.	3—4	+0·10	+0·69	+0·53	−0·13	−0·04	+1·06	+0·86	+0·61	+0·85	+0·15	−1·10	+0·15	+0·31

TABLE XXIV.—*Geographical Summary of the differences of Table XXIII* —concluded.

Areas.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
South Central Provinces and Berar.	11	+0·74	+0·18	+0·24	+0·14	—0·81	+0·91	−0·05	—0·75	+1·18	+0·43	—0·79	—0·51	+0·08
Konkan . .	4	—0 11	—0·21	+0·02	—0·23	—0 50	+1·04	+0·14	—0·79	+0·49	—0·02	—0·71	+0·10	—0·07
Malabar Coast .	2	+0·79	+0·12	+0·72	+0·65	+1·24	+0·94	+1·07	+0·72	—0·37	+1·02	−0·56	+0·20	+0 55
Deccan, Hyderabad, Mysore, &c.	8	+0·55	+0·09	+0·47	+0·14	—0·09	+1·27	+0·46	+0·02	+0·18	+0·81	—1·04	+0 13	+0·25
East Coast and Carnatic.	8	—0·06	—0·17	+0·05	—0·48	—0·71	—0·64	−0·60	—0·91	—1·06	+0·07	—0·38	+0·72	—0·35
Ceylon . . .	7	+0·56	+0·49	—0·21	+0·04	+0·16	—0·14	+0·22	+0·31	0	+0·98	+1·41	+0·74	+0·38
Arakan and Pegu .	7	—0·59	—0·23	+0·22	—0·12	+0·26	+0·55	+0·24	+0·44	+0·44	—0·94	+0·94	+1·17	+0·20
Tenasserim . .	2	—1·00	+0·46	+0·46	+0·45	+0·26	+0·17	+0·12	−0·34	0	—0·60	+1·48	+0·29	+0·15
Bay Islands . .	2	+0·64	—0·74	+0 17	+0·41	+0·50	+0·56	+0·51	+0·05	+0·24	+0·27	+0·80	+1·68	+0·38

January.—Except in Assam and Bengal, this was generally a cloudy month in Northern India, and especially so on the North-Western Himalaya, and on the plateau lying south of the Gangetic plain. In the peninsular region, this was also the case in Nagpur and Berar, in the west of the Deccan, in the neighbourhood of the Ghats and in Mysore and the Malabar coast, but not apparently in the Konkan, nor generally on the Central plateau and the Carnatic. In Ceylon, however, there was, as a rule, more than the usual amount of cloud, while everywhere in the Eastern Peninsula the skies were comparatively clear.

The general prevalence of cloudy weather in Northern India was, doubtless, dependent in a considerable degree on that of southerly and south-easterly winds, or conversely, to the weakness and unsteadiness of the usual northerly monsoon. It was also intimately connected with the prevailing high humidity of North-Western India, as in Bengal and still more in the Eastern Peninsula, a certain deficiency of cloud was associated with the opposite condition of the atmosphere.

February.—In this month, too, the variation of the serenity of the skies with the prevalence of north-western or west winds and a dry atmosphere was very marked. The cloud proportion was less than usual on the Himalaya and throughout North-Western India and the western half of the Gangetic plain; but there was still a slight excess on the plateau south of the Ganges, and at Allahabad and Benares, in Bengal, and particularly in Orissa. Generally, in the peninsula the anomalies were small or local, but there was still a small excess on the Malabar coast, and not in the Konkan. In Arakan and Pegu, the abnormal serenity was less marked than in January, and in Tenasserim there was an excess of cloud.

March.—Save on the Punjab plains and in Western Rajputana, the Indus region and Gujarat in Northern India, and in the Southern Carnatic and Ceylon in the south, there was a general, though for the most part slight excess of cloud; greatest in Chutia Nagpur, Cuttack, and the western districts of Bengal, and also in Chittagong. The former of

these regions was one in which the humidity of the air was abnormally highest, and, in general, the variations of the two elements were fairly concomitant: but in Arakan and Pegu, where the air was dry, there was a small excess of cloud, and, on the other hand, in Gujarat, where the humidity was somewhat above the average of the month, the cloud proportion was slightly below it. The differences, however, were not great.

April.—April was somewhat less cloudy, and there was a marked deficiency in Sind and Gujarat, the Konkan, Rajputana, Central India, the Gangetic plains, Behar and Chutia Nagpur, and in Assam and Cachar, but not in the Gangetic delta. In the Carnatic also there was less than the average, but not on the Malabar coast nor in the Northern Circars and Hyderabad. In the Eastern Peninsula there was a small deficiency in Pegu, but a considerable excess in Tenasserim and also at the Nicobars.

May.—Except in Bengal, Assam, and Cachar, and on the Sikkim Himalaya in Northern India, and on the Malabar coast in Southern India, May was generally a comparatively serene month. The deficiency of cloud was greatest in Berar and Nagpur, and not much less in the Central India region, the Konkan, and in the Carnatic. On the North-Western Himalaya, on the Punjab and Gangetic plains, there was about an average proportion, and in Bengal and Assam a considerable excess. The excess was still greater on the Malabar coast; and there was a slight excess in Arakan and the northern part of Pegu, and a greater excess at Mergui and the Bay Islands, while the intermediate region had rather less than the average.

June.—The proportion of cloud was much below the average on the North-West Himalaya, and in a less degree on the Punjab plains and in the dry region of Western India generally. On the Gangetic plain and the Central India plateau, there was about the normal amount, and in the Central Provinces and Chutia Nagpur, the Konkan and Malabar coast, and throughout the peninsula, except in the Carnatic, a considerable excess. In Bengal and Assam the excess was less pronounced, and also in the Eastern peninsula, where, however, it was much greater in Arakan and Northern Pegu than further south.

July.—On the North-West Himalaya the deficiency of cloud was less than in June, but on the Punjab plains it was considerably greater, and there was a certain deficiency in some parts of Eastern Rajputana and Central India; whereas in Western Rajputana, Gujarat and Sind, there was either an average proportion or an abnormal excess. The greatest excess was in Chutia Nagpur and Orissa, and the eastern districts of Nagpur, but it was less in Bengal, and in Assam there was a certain deficiency. In Nagpur and Berar there was only about an average, or at some stations considerably less, but in the Konkan, and with some local exceptions on the Deccan plateau, the cloud proportion ranged more or less above the average of the month. On the Malabar coast the abnormal excess was as great as in the two previous months, but in the Carnatic, as a general rule, the serenity of the previous months continued to prevail. In Ceylon, except on the south and east coast, in Burma, save at Bassein, Rangoon and Moulmein, and at the Bay Islands, the cloud proportion was somewhat above the average.

August.—The drought, which prevailed over North-Western and Central India in this month, was as strongly manifested in the abnormal diminution of cloud as in the dryness of the atmosphere and the comparative absence of rainfall. This is well seen in the

134457

August column of the preceding Table XXIV, the figures of which, when compared with those of the normal averages, are as follow, in the provinces chiefly affected :—

Area.	Average.	Anomaly, 1883.
North-West Himalaya	7·22	—0·84
Punjab plains	3·87	—1·18
Gangetic plains	6·71	—0·60
Western Rajputana, &c.	5·91	—1·12
Eastern Rajputana, Central India, &c.	6·29	—1·31
Nerbudda valley	7·23	—0·75
South Central Provinces and Berar	7·64	—0·75
Konkan	7·80	—0·79

On the other hand, in the more eastern provinces, which were unaffected by the drought, in Chutia Nagpur, Orissa, Bengal and Assam, the cloud proportion was more or less considerably above the normal average. In the Northern Deccan, which was included in the area of the drought, the deficiency of cloud was very pronounced, but further south, at Secunderabad, Bellary, &c., there was a certain excess. In the Carnatic, the proportion was almost universally below the average, and in a marked degree, but on the Malabar coast the cloudiness was still excessive. In Ceylon, also, there was an excess at most stations, stations on the south coast alone being exceptions. In Arakan and Pegu (except apparently at Rangoon and Moulmein) an excess also prevailed, and the same at Mergui and Port Blair, but not at Nancowry.

September.—The break in the rains came to an end in the latter part of August, and in September the cloud proportion was either about equal to the average or else exceeded it in all parts of Northern and Central India proper. In the Gangetic plain and Bengal, there was a slight deficiency at a few stations, but this was compensated by a slight excess at others, and in Western Rajputana and Cutch, and in the Central Provinces and Berar, the excess was considerable, and only somewhat less so on the Central India plateau, in Chutia Nagpur, Orissa and Bengal. In the Konkan the cloud was also above the average proportion, but on the Malabar coast, for the first time during the year, there was a certain deficiency, and in the Carnatic and on the east coast it was greater than in any previous month and universal. In Arakan and Pegu there was an excess of cloud, except at Rangoon and Moulmein, and the same at the Bay Islands.

October.—In October the anomalies of cloud distribution varied. On the North-West Himalaya and in the Punjab, in Rajputana, Gujarat, Central India, the Nerbudda region and the Central Provinces, the proportion more or less exceeded the average; whereas in Sind and Katiwar, in the Gangetic plain, Chutia Nagpur, Orissa, Bengal, the Sikkim Himalaya and Assam,—that is, throughout North-Eastern India,—the skies were unusually serene. On the central plateau of the peninsula and on the Malabar coast there was a considerable excess; and also in the Carnatic, except in the western districts

and in Ceylon. But in the Eastern Peninsula, the skies shared the serenity of the north-east of India, and to a slight extent this was the case also at the Bay Islands.

November.—Except on the North-West Himalaya, and to a slight extent in the Punjab and Western Rajputana, November was a very serene month throughout the whole of India. On the North-West Himalaya, however, the cloud proportion was not far short of double the usual amount, and there was a large excess also in Ceylon, in Pegu, Tenasserim, and in the south-east of the Bay.

December.—With the exception of Lower Bengal and Orissa, where there was more than the usual amount of cloud, especially in the early part of the month, all Northern and Central India had very clear skies also in December; the North-West Himalaya and the Punjab being no longer exceptions to the rule. This abnormal serenity, however, did not extend far down the peninsula. In the Deccan and Hyderabad, and in the Carnatic, there was a marked excess of cloud; and on the west coast, although less excessive, the proportion was above the average. In Ceylon, at nearly all stations, in Burma and at the Bay Islands, there was also a decided excess.

The final column of Table XXIV shows that in North-Western and Western India generally, in Assam and Cachar, and in the Carnatic, the proportion of cloud was slightly below the average; elsewhere slightly above it, and most so apparently on the Malabar coast. Taking the mean of each column in Table XXIII, the variation from month to month for the whole Indian area is as follows:—

	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.
No. of stations	118	118	117	118	119	120	121	120	120	120	120	119
Mean anomaly	+0·53	+0·04	+0·25	−0·14	−0·12	+0·24	+0·11	−0·36	+0·40	+0·02	−0·03	0

and the mean anomaly of the twelve months +0·07. Hence the serenity of North-Western India and the Carnatic was rather more than compensated by the greater cloudiness of Bengal and Orissa, the Central Provinces, the Deccan, Malabar and Ceylon, and the Eastern Peninsula. Inasmuch as the absolute humidity of the atmosphere has been shewn to be rather below the average, it would appear that there was no direct dependence of the former on the latter. But, on comparing the anomalous variations of the two elements in the successive months, it will be found that, as a general rule, they rise and fall simultaneously. January and June were the dampest months, as they were the most cloudy, the comparison being in both cases with the averages of the season. And August, in which the anomalous serenity was greatest, although not that in which the anomalous dryness of the atmosphere was greatest, had a drier atmosphere than any other month of the rainy season.

RAINFALL.

In the present report the rainfall of India and its dependencies is represented by 462 stations (5 more than were given in the report for 1882), and for 18 of these two independent registers are given. I also give the registers of the extra-Indian stations Zanzibar, Aden, Mahé (Seychelles), Bushire, and Singapore. The monthly and annual totals of these 481 registers are shewn in Table XIV in the Appendix, classified under their respective administrative divisions, according to the following scheme:—

Provinces.	Stations.	Registers.
Seychelles	1	1
Zanzibar	1	1
Arabia	1	1
Persian Gulf	1	1
Beluchistan	1	1
Kashmir	1	1
Punjab	35	41
Rajputana	24	24
Central India States	18	19
North-Western Provinces	46	47
Oudh	12	12
Nepal	1	1
Bengal	82	84
Assam	15	15
Central Provinces	27	27
Berars	9	10
Hyderabad	23	26
Bombay	50	52
Madras	75	78
Mysore and Coorg	9	9
Ceylon	12	12
British Burma	15	15
Bay Islands	2	2
Singapore	1	1

The stations, the registers of which are now given for the first time, are Mahé in the Seychelles; Kailang in the Himalayan State of Lahoul on the Chandra Bhaga, or upper waters of the Chenab river; Barmer and Jeysulmere in the desert region of Western Rajputana; and Lohardugga in Chutia Nagpur. The register of Kilba in the Himalayan State of Bussahir, on the upper waters of the Sutlej, was given for the first time in the report of 1882, but without special mention in the text.

All the above Indian stations are situated in those parts of the country that were either unrepresented, or but insufficiently represented, in previous reports, *viz.*, two in the inner Himalaya, behind the Snowy Range, two in the Indian desert, and one in Chutia Nagpur.

The map, Plate I, shews the positions of all the stations in India and its dependencies, the registers of which are given in Table XIV (Appendix). The rain-gauges in use in Bengal, Bombay, Madras, the Central Provinces and Berar generally, and at the meteor-

ological observatories in the North-Western Provinces, the Punjab, Burma, and other provinces, are either those of Symon's pattern, 5 inches in diameter, or Glashier's, 8 inches in diameter, furnished with graduated measure glasses, into which the collected rain-water is poured. The gauges are placed on the ground; the mouth, in general, about one foot above the ground level. At the rain-gauge stations in the Punjab and N.-W. Provinces (not being observatories), other forms of gauge are used; generally Fleming's float-gauges the mouth of which stands 3 feet above the ground, and the registers of which must generally be regarded as much less exact.

At the majority of stations, as far as is known, the rainfall is measured at 6 P.M. Many stations in Rajputana, Hyderabad, Madras, and Burma are exceptions to this rule; and, at most of them, it appears to be the practice to measure the rainfall at some morning hour, frequently at 6 A.M., and, in Madras, at noon. It is much to be desired that this practice should be discontinued.

Table XV (Appendix) gives the number of days on which the rainfall has been measured at 462 stations. From this table it appears that the wettest station was Galle, where rain fell on not less than 216 days, and next thereto Newera Ellya, with rain on 198 days, Ratnapura 196 days, and Shillong in the Khasi Hills with 191 rainy days. The driest station was Dera Ghazi Khan in the Punjab, with rain on only 4 days, amounting to a total of 1·25 inches. Shikarpur had but little more, *viz.*, 1·57 inches on 5 days, and Mozuffergarh in the Punjab had but 4 rainy days, but the rain was heavier, amounting to 3·70 inches. The rainfall of Cherrapunji[1] was only 372 inches, and next in order came Mahableshwar with 297 inches; Baura fort, also on the Western Ghats, with 264 inches; and Matheran near Bombay with 241 inches. Quantities exceeding 200 inches were also registered at Sandaway in Arakan (223 inches), and at Buxa in the Bhotan Doars (210 inches).

The following Table, XXV, gives the average rainfall, as deduced from the registers of past years, at 451 stations (including two stations at Alipore, Calcutta), and two in Bombay:—

Provinces.	Stations.	Provinces.	Stations.
Zanzibar	1	Assam	15
Arabia	1	Central Provinces	26
Persian Gulf	1	Berar	9
Beluchistan	1	Hyderabad	23
Kashmir	1	Bombay, Gujarat, and Sind	50
Punjab	33	Madras	75
Rajputana	22	Mysore and Coorg	9
Central India States	16	Ceylon	12
North-Western Provinces	44	Burma	15
Oudh	12	Bay Islands	2
Nepal	1	Singapore	1
Bengal, Behar, and Orissa	81		

and Table XXVI gives the differences in the fall in each month of 1883, as compared with the averages of Table XXV.

[1] According to the earlier registers, the average rainfall of this station greatly exceeded that to be deduced from the registers since 1862, and more especially from those since 1870. This is to be accounted for by the fact that the rain-gauge has occupied at least four different positions in the station, and, as might be anticipated, when regard is had to the very peculiar topography of the place, different parts of the little plateau are very unequally exposed to the rain-bearing current.

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.*

Provinces.	Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Africa	Zanzibar	9	2·42	4·60	5·41	13·01	7·70	1·26	2·43	1·94	1·33	3·35	6·31	6·41	56·17
Arabia	Aden	3	0·30	0·12	0·19	0·52	0·37	...	...	0·15	...	...	0·20	0·32	2·17
Persian Gulf	Bushire	6—7	1·90	3·11	0·70	0·59	...	...	...	...	...	...	2·09	4·48	12·87
Beluchistan	Quetta	6	0·94	1·67	1·90	0·94	0·31	0·17	1·00	0·57	0·21	...	...	0·53	8·24
Cashmere	Leh	8	0·20	0·12	0·15	0·09	0·10	0·14	0·60	0·50	0·18	0·52	0·04	0·08	2·72
Punjab	Peshawar	25—26	1·37	1·27	1·64	1·81	0·57	0·36	1·82	2·11	0·83	0·26	0·65	0·61	13·30
	Kohat	23—25	1·29	1·28	1·88	1·57	1·25	1·10	4·43	2·94	1·73	0·65	0·82	0·56	19·50
	Bannu	21—22	0·65	0·98	1·35	1·42	0·72	1·10	2·01	3·11	0·80	0·15	0·26	0·40	12·95
	Dera Ismail Khan	21—22	0·34	0·73	0·83	0·79	0·37	0·64	1·79	1·75	0·59	0·15	0·13	0·35	8·46
	Dera Ghazi Khan	21—22	0·33	0·36	0·70	0·37	0·43	0·57	2·12	1·30	0·35	0·07	0·12	0·31	7·03
	Muzaffargarh	23—24	0·27	0·27	0·39	0·35	0·32	0·33	1·33	1·48	0·67	0·10	0·07	0·30	5·88
	Mooltan	22	0·32	0·30	0·48	0·37	0·46	0·33	2·27	1·23	0·87	0·12	0·05	0·27	7·07
	Jhang	21—22	0·40	0·44	0·83	0·50	0·49	0·92	3·97	2·07	0·79	0·21	0·05	0·37	11·04
	Montgomery	23—24	0·49	0·68	0·57	0·25	0·45	1·07	3·22	2·18	1·05	0·17	0·06	0·27	10·46
	Shahpur	29—30	0·80	1·11	0·89	0·60	0·63	1·21	3·73	3·46	1·70	0·18	0·25	0·41	14·97
	Rawalpindi	25—26	2·16	2·00	1·73	2·37	1·38	1·71	7·63	6·90	3·31	0·53	0·95	1·12	31·79
	Jhelum	22—23	1·48	1·28	1·59	1·05	0·63	1·98	7·39	5·26	2·30	0·49	0·38	0·81	24·64
	Gujrat	21—22	1·73	1·60	2·32	1·33	0·65	2·54	8·50	7·13	2·86	0·52	0·36	0·73	30·27
	Sialkot	25—26	1·23	1·87	1·83	1·67	1·14	2·88	11·82	9·52	3·07	0·57	0·40	0·85	36·85
	Gujranwala	22	1·09	1·48	1·23	0·91	0·72	1·68	8·32	6·22	2·51	0·54	0·29	0·64	25·63
	Gurdaspur	26—27	1·53	1·81	1·49	0·52	0·77	3·59	9·29	6·92	3·61	0·64	0·20	0·96	31·33
	Lahore	24—26	0·62	1·16	1·08	0·59	0·87	1·71	7·25	4·68	2·49	0·54	0·16	0·49	21·64
	Amritsar	23—24	1·07	1·20	0·83	0·68	0·86	2·26	8·54	6·73	2·88	0·50	0·27	0·70	26·52
	Ferozepur	33—34	1·09	0·83	0·78	0·62	0·62	2·25	7·15	5·40	2·62	0·60	0·06	0·51	22·53
	Jullundur	31—32	1·34	1·37	1·24	0·64	0·84	2·43	8·38	7·27	3·68	0·51	0·10	0·54	28·34
	Hoshiarpur	25—27	1·54	1·74	1·47	0·71	0·91	3·40	10·25	9·29	4·36	0·34	0·08	1·19	35·28
	Ludhiana	25—28	1·25	1·30	1·67	0·94	1·21	2·33	9·75	6·59	4·38	1·17	0·10	0·87	31·56
	Umballa	32—34	1·36	1·59	1·11	0·67	1·02	3·93	11·55	8·38	4·07	0·54	0·24	0·68	35·14
	Sirsa	32—33	0·68	0·33	0·54	0·43	0·63	2·21	3·65	3·56	2·13	0·25	0·03	0·36	14·78
	Hissar	32—33	0·58	0·47	0·58	0·28	0·68	1·93	4·50	3·93	1·84	0·32	0·07	0·36	15·54
	Rohtak	30—32	0·66	0·61	0·63	0·29	0·66	2·78	5·81	4·56	2·93	0·47	0·03	0·37	19·80
	Delhi	33—35	0·81	0·55	0·79	0·39	0·67	3·03	8·64	6·69	4·40	0·52	0·08	0·35	26·92
	Gurgaon	32—33	0·83	0·33	0·57	0·18	0·75	2·48	8·99	6·53	4·69	0·46	0·03	0·30	26·14
	Karnal	27—28	1·24	1·32	0·97	0·52	1·01	4·11	9·64	6·06	3·58	0·39	0·09	0·41	29·34
	Abbottabad	24—25	2·93	3·76	4·27	3·20	3·13	3·04	8·60	8·62	3·15	1·06	1·02	2·25	45·03
	Murree	9	1·17	2·66	2·55	4·39	3·25	2·69	11·72	14·02	5·58	2·25	2·18	1·13	53·59
	Dharmsala	24—25	4·22	4·76	4·25	2·19	2·78	10·84	40·44	38·08	13·09	1·63	0·39	2·23	124·90
	Simla	21—22	2·60	2·92	3·11	2·98	4·72	8·21	19·83	18·09	6·31	1·16	0·35	0·96	71·24
Rajputana	Bickaneer	6	0·29	0·28	0·08	0·26	1·80	1·77	4·82	3·27	1·43	0·05	0·12	0·02	14·19
	Ulwur	12	0·24	0·48	0·21	0·11	1·30	3·33	8·82	7·62	4·55	1·23	0·18	0·44	28·51
	Bhurtpore	16	0·38	0·22	0·16	0·16	0·66	1·79	8·85	7·57	4·02	0·59	0·02	0·25	24·67
	Jeypore	15—17	0·24	0·19	0·20	0·24	0·72	3·50	9·43	5·66	2·74	0·22	0·09	0·45	23·68

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
RAJPUTANA—*contd.*	Sambhar	8—9	0·19	0·12	0·22	0·17	1·21	1·50	7·19	5·02	3·71	0·64	0·21	0·38	20·56
	Beawar	27—28	0·23	0·14	0·17	0·11	0·43	2·09	7·83	5·98	2·91	0·22	0·16	0·21	20·48
	Pachbudra	4—5	0·64	0·05	0·11	0·01	1·24	0·50	2·87	4·02	2·51	0·04	0·01	0·07	12·07
	Jodhpore	10	0·27	0·22	0·05	0·02	0·57	0·84	3·46	5·21	2·55	0·28	0·05	0·04	13·56
	Ajmere	21	0·20	0·34	0·43	0·11	0·71	2·29	7·08	7·37	3·34	0·26	0·13	0·29	22·55
	Nusseerabad	18	0·10	0·51	0·12	0·04	0·70	1·63	7·16	6·16	3·29	0·28	0·13	0·27	20·39
	Tonk	12	0·09	0·27	0·20	0·05	0·44	2·27	9·52	8·30	3·25	0·97	...	0·14	25·50
	Deoli	22	0·27	0·19	0·16	0·19	1·15	4·44	11·31	10·43	5·34	0·55	0·14	0·18	34·35
	Kotah	12	0·07	0·31	0·08	...	0·97	3·03	10·43	9·03	5·85	0·58	0·01	0·23	30·59
	Jhalrapatam	13	0·15	0·46	0·22	0·01	0·71	4·08	16·51	8·68	6·88	0·49	0·10	0·38	38·67
	Kotra	14	0·05	0·24	0·02	0·03	0·78	2·97	12·02	9·14	6·05	0·59	0·10	0·10	32·09
	Oodeypore	9—10	0·01	0·22	0·04	...	0·61	2·24	8·72	5·88	7·19	0·74	...	0·06	25·71
	Kherwara	26—27	0·08	0·18	0·04	0·03	0·46	4·01	8·94	7·70	4·84	0·66	0·04	0·08	27·06
	Banswara	10—11	0·53	0·19	...	...	0·35	3·58	12·89	10·71	11·06	0·41	...	0·51	40·23
	Mount Abu	24	0·22	0·40	0·15	0·05	1·08	5·04	22·02	22·86	8·63	2·31	0·20	0·25	63·21
	Erinpura	16	0·07	0·30	0·07	0·04	0·50	0·90	5·25	4·18	2·76	0·38	0·10	0·15	14·70
	Shahpoora	11	0·07	0·26	0·21	0·04	0·98	2·80	6·60	6·69	5·25	0·70	0·06	0·19	23·85
	Partabgarh	3—4	0·20	0·14	0·05	...	0·80	6·34	13·05	9·66	8·94	0·68	...	0·05	39·91
CENTRAL INDIA	Neemuch	16—17	0·09	0·17	0·13	0·10	0·59	3·80	11·94	10·51	6·12	0·88	0·03	0·24	34·60
	Sirdarpore	16	0·18	0·28	0·02	0·01	0·20	5·48	10·51	6·57	8·22	0·69	0·10	0·15	32·41
	Agar	15—16	0·10	0·38	0·04	0·04	0·53	4·73	11·69	9·79	8·35	0·54	0·07	0·32	36·58
	Rutlam	16	0·19	0·27	0·01	...	0·47	5·72	12·51	10·83	9·79	0·78	0·01	0·13	40·71
	Indore	16	0·34	0·29	0·02	0·13	0·42	6·52	10·59	8·06	8·68	0·92	0·17	0·14	36·28
	Bhopal	16	0·46	0·16	0·07	0·01	0·33	6·11	18·05	11·80	9·97	1·26	0·30	0·24	48·76
	Goona	13	0·35	0·21	0·18	0·06	0·62	7·00	12·01	11·01	6·03	0·27	0·35	0·05	38·14
	Morar	12	0·29	0·35	0·28	0·13	0·54	2·73	10·49	9·74	6·14	0·42	0·02	0·35	31·48
	Nowgong	15—16	0·58	0·26	0·19	0·11	0·33	5·00	15·07	11·32	6·63	0·89	0·08	0·15	40·61
	Sutna	12	0·76	0·62	0·27	0·07	0·33	6·27	15·40	10·83	5·15	1·47	0·22	0·06	41·45
	Nagode	21	0·80	0·38	0·22	0·22	0·44	4·91	16·47	12·13	6·79	2·22	0·14	0·21	44·93
	Maihar	5—6	0·49	0·42	0·32	0·02	0·54	6·61	13·94	8·34	4·72	1·58	0·76	0·04	37·78
	Rewah	12	0·73	1·03	0·22	0·29	0·45	10·02	19·25	14·64	6·79	1·85	0·28	0·03	55·58
	Chandia	3	?	?	?	?	?	?	?	11·37	3·46	1·39	0·60	...	?
	Ramnagar	3	?	?	?	?	?	?	?	8·99	3·63	1·89	0·35	...	?
	Sihawal	3	?	?	?	?	?	?	?	13·80	6·60	1·81	0·55	...	?
N.-W. PROVINCES	Chakrata	15	1·86	2·65	3·27	1·81	2·92	7·70	17·58	15·41	5·58	0·53	0·28	1·01	60·60
	Mussooree	19—31	2·09	3·08	2·95	1·82	2·56	9·82	30·35	29·71	10·03	0·96	0·29	1·06	94·72
	Ranikhet	13	1·73	2·29	2·06	1·45	3·09	5·97	13·00	10·31	6·42	0·54	0·29	0·92	48·07
	Naini Tal	33—34	2·99	2·95	2·51	1·65	2·89	15·34	24·99	23·98	10·78	1·60	0·20	1·29	91·17
	Almora	38—40	1·88	1·98	1·73	1·03	2·29	5·87	9·73	7·82	4·71	0·86	0·20	0·62	38·72
	Dehra Dun	34—36	2·15	1·93	1·37	0·72	1·45	8·55	24·93	23·27	9·18	0·71	0·15	0·50	74·91
	Saharanpur	34—36	1·42	1·46	1·18	0·41	0·78	4·40	12·39	9·29	3·92	0·44	0·19	0·48	36·36

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
N.-W. PROVINCES —*contd.*	Roorkee	29—30	2·00	1·56	1·07	0·37	1·18	4·99	12·66	11·56	5·00	0·63	0·20	0·35	41·57
	Muzaffarnagar	34—36	1·38	0·99	1·02	0·43	0·92	3·74	10·39	7·80	4·46	0·38	0·09	0·31	31·83
	Meerut	34—36	0·88	0·79	0·74	0·43	0·77	3·54	9·45	6·62	3·82	0·42	0·05	0·34	27·85
	Bulundshahr	33—35	0·80	0·88	0·49	0·27	0·58	2·77	8·52	6·45	3·94	0·54	0·05	0·41	25·70
	Aligarh	35—37	0·74	0·50	0·43	0·21	0·47	3·12	9·16	6·66	3·97	0·48	0·02	0·30	26·06
	Bijnor	34—36	1·13	1·16	0·92	0·50	0·75	4·75	10·57	9·29	5·77	0·47	0·07	0·33	35·71
	Moradabad	34—36	1·17	1·07	0·76	0·36	0·94	5·25	14·10	9·37	5·84	0·65	0·12	0·36	39·99
	Bareilly	34—36	0·98	0·82	0·67	0·28	0·86	5·92	14·70	8·45	6·66	1·16	0·07	0·24	40·81
	Budaun	34—36	0·87	0·57	0·46	0·13	0·52	3·52	11·09	7·86	5·84	0·74	0·06	0·28	31·94
	Shajahanpore	34—36	0·82	0·70	0·58	0·19	1·11	5·35	12·34	8·44	6·95	1·16	0·09	0·29	38·02
	Muttra	34—36	0·47	0·33	0·22	0·20	0·56	2·66	9·46	6·50	4·17	0·43	0·01	0·27	25·28
	Agra	35—37	0·55	0·30	0·23	0·16	0·70	2·75	9·69	6·33	4·35	0·33	0·03	0·24	25·66
	Mainpuri	34—36	0·76	0·30	0·30	0·13	0·43	2·93	9·38	7·42	5·46	0·67	0·05	0·37	28·20
	Farrukhabad	34—36	0·69	0·31	0·41	0·08	0·57	3·26	9·67	7·48	5·49	1·03	0·05	0·30	29·34
	Etawah	34—36	0·49	0·21	0·43	0·15	0·42	2·58	8·65	7·99	4·72	1·01	0·09	0·24	26·98
	Etah	23—24	0·41	0·22	0·53	0·11	0·46	2·67	9·88	8·44	4·20	0·70	0·02	0·25	27·89
	Cawnpore	34—36	0·73	0·46	0·25	0·14	0·43	3·35	9·67	8·06	4·86	1·01	0·07	0·16	29·19
	Fatehpur	33—36	0·69	0·40	0·23	0·17	0·33	3·51	9·53	8·28	5·52	1·27	0·10	0·12	30·15
	Banda	34—36	0·79	0·32	0·28	0·12	0·36	3·90	11·74	8·77	6·04	1·18	0·23	0·12	33·85
	Allahabad	34—36	0·78	0·44	0·44	0·15	0·33	4·46	12·09	9·61	6·84	2·19	0·24	0·11	37·68
	Hamirpur	34—36	0·51	0·33	0·22	0·09	0·32	4·16	11·52	8·11	5·29	0·81	0·14	0·22	31·72
	Jaunpur	31—33	0·70	0·42	0·33	0·14	0·89	4·52	11·85	11·35	7·91	3·01	0·16	0·08	41·36
	Azamgarh	34—36	0·58	0·48	0·35	0·18	0·97	5·28	11·27	9·94	7·67	2·42	0·10	0·11	39·35
	Mirzapur	34—36	0·76	0·69	0·62	0·14	0·57	4·59	12·96	11·72	6·93	2·05	0·28	0·10	41·41
	Dudhi	10	0·40	0·68	0·36	0·27	0·75	4·94	10·67	13·19	6·13	3·41	0·44	0·03	41·27
	Robertsganj	20	0·74	0·56	0·39	0·27	0·87	5·41	13·36	10·45	7·07	2·73	0·23	0·13	42·21
	Benares	34—36	0·74	0·53	0·35	0·17	0·52	4·77	12·99	10·90	6·38	2·00	0·15	0·06	39·56
	Gorakhpur	34—36	0·73	0·59	0·39	0·33	1·49	7·64	13·30	11·85	8·71	2·85	0·18	0·09	48·15
	Basti	17—18	0·76	0·50	0·24	0·24	1·38	6·25	14·04	10·88	8·25	2·22	0·01	0·11	44·88
	Ghazipur	34—36	0·74	0·59	0·33	0·14	0·75	4·36	11·02	9·14	7·10	2·81	0·32	0·07	37·37
	Jalaun	22—23	0·43	0·20	0·21	0·07	0·25	2·63	10·44	10·33	5·43	0·67	0·02	0·20	30·88
	Jhansi	23—24	0·56	0·21	0·41	0·13	0·24	4·02	13·63	10·01	5·11	0·62	0·02	0·12	35·08
	Lalitpur	23—24	0·55	0·24	0·33	0·14	0·57	4·55	13·18	11·05	6·24	0·88	0·08	0·18	37·99
	Srinagar	20	2·19	3·16	2·34	1·02	2·22	4·40	8·68	7·99	3·06	0·49	0·22	0·71	36·48
	Pithoragarh	3	?	?	?	?	4·10	8·57	11·46	12·99	2·51	0·07	0·06	0·03	?
	Pauri	33—34	2·56	2·87	2·35	1·30	2·69	5·40	13·75	12·35	4·93	0·57	0·30	0·68	49·75
	Rudarpur	24	1·19	1·28	0·94	0·28	1·18	5·79	15·10	10·92	5·44	0·86	0·06	0·38	43·42
OUDH	Lucknow	16—17	0·92	0·29	0·30	0·14	0·80	4·30	10·99	10·21	7·00	1·29	0·01	0·34	36·59
	Unao	16—17	0·79	0·36	0·28	0·13	0·56	4·79	10·18	8·77	5·16	1·48	0·01	0·28	32·79
	Nawabganj	16—17	1·03	0·31	0·41	0·26	0·81	5·00	10·55	7·69	8·87	0·93	...	0·42	36·28
	Sitapur	16—17	0·86	0·45	0·49	0·31	1·19	5·46	11·33	9·14	6·12	1·61	0·03	0·27	37·26

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
OUDH—*contd.*	Hardoi	16—17	0·68	0·32	0·75	0·22	0·57	3·83	11·72	8·46	5·74	1·75	...	0·44	34·48
	Kheri	16—17	1·18	0·86	0·63	0·28	1·19	6·39	10·71	10·07	8·18	1·65	...	0·37	41·51
	Fyzabad	16—17	0·85	0·41	0·41	0·26	1·06	5·27	13·34	9·86	8·09	1·57	0·03	0·09	41·24
	Bahraich	16—17	0·88	0·97	0·42	0·36	1·81	6·02	14·51	8·58	7·94	1·63	0·04	0·32	43·48
	Gonda	16	0·74	0·50	0·24	0·09	1·25	6·47	12·07	10·11	8·92	1·43	0·05	0·16	42·03
	Rai Bareli	15—17	0·59	0·27	0·25	0·14	0·27	3·87	9·91	8·01	7·70	1·03	0·02	0·12	32·18
	Sultanpur	16—17	0·73	0·34	0·21	0·24	0·80	5·83	12·18	10·00	8·46	1·62	0·04	0·11	40·56
	Partabgarh	16—17	0·75	0·41	0·26	0·07	0·48	4·56	10·81	9·64	7·73	1·83	0·06	0·10	36·70
NEPAL	Katmandu	28—33	0·76	1·16	1·27	2·01	3·92	10·06	13·92	13·90	7·19	2·19	0·20	0·19	56·77
BENGAL	Burdwan	23—24	0·30	0·84	1·27	2·59	4·99	10·04	12·42	12·33	7·90	4·92	0·58	0·17	58·35
	Bankoora	26—29	0·34	1·16	1·51	1·61	3·34	9·92	12·62	11·64	8·78	4·67	0·43	0·15	56·17
	Soory	21—24	0·46	1·07	0·61	0·84	3·06	10·54	12·72	12·97	9·36	3·73	0·13	0·16	55·65
	Midnapore	18—20	0·80	0·87	1·53	1·74	5·08	10·37	11·33	11·51	8·41	5·28	0·39	0·29	57·60
	Tumlook	13	0·40	1·29	2·07	1·86	5·04	8·88	11·80	13·23	8·06	4·97	0·26	0·27	58·13
	Hooghly	19—20	0·46	1·39	1·81	2·98	5·74	10·49	11·86	12·34	7·83	4·20	0·38	0·29	59·77
	Howrah	15—16	0·56	1·49	1·92	2·30	4·66	11·30	12·98	12·76	9·09	4·45	0·34	0·31	62·16
	Saugor Islapd	16—17	0·31	0·82	1·20	1·50	4·72	11·43	15·64	15·73	11·98	9·49	0·75	0·32	73·89
	Alipore Jail	13—14	0·62	1·72	1·59	2·02	5·25	10·03	13·33	13·33	9·12	4·61	0·38	0·39	62·39
	Alipore (Observatory).	6—7	0·04	1·53	1·13	1·84	5·84	9·42	13·31	13·16	9·03	3·39	0·41	0·90	60·00
	Calcutta (Chowringhee).	54—55	0·44	0·97	1·31	2·37	5·48	11·77	12·96	13·94	9·92	5·42	0·60	0·32	65·50
	Busseerhat	13—14	0·46	0·94	1·82	1·97	6·43	10·51	12·86	12·43	8·19	4·43	0·44	0·26	60·74
	Kishnaghur	20—23	0·46	1·14	1·03	2·67	6·62	9·84	10·12	11·10	7·36	4·68	0·43	0·15	55·60
	Jessore	24—29	0·49	0·76	1·93	4·71	7·56	13·30	11·44	11·62	8·92	5·76	0·92	0·21	67·02
	Khoolna	12—13	0·68	1·26	1·75	3·48	6·10	12·31	12·04	12·65	9·09	4·52	0·51	0·41	64·80
	Berhampore	29—31	0·44	1·02	1·06	1·93	4·86	9·95	16·39	10·70	9·47	5·46	0·31	0·12	55·71
	Dinagepore	24—26	0·28	0·68	0·81	2·26	7·10	17·58	15·20	13·38	12·83	5·15	0·24	0·10	75·61
	Maldah	26—28	0·70	0·82	0·91	1·47	3·56	10·02	10·60	9·92	10·53	4·34	0·24	0·38	53·49
	Beauleah	25—29	0·30	1·02	1·20	1·75	5·59	10·90	11·64	10·97	10·88	5·16	0·31	0·09	59·81
	Rungpore	23—27	0·39	0·45	1·00	2·95	10·34	21·45	16·79	13·12	13·16	5·20	0·32	0·12	85·29
	Bogra	21—24	0·47	1·13	0·75	3·66	8·72	15·29	16·75	12·98	12·08	5·05	0·90	0·14	77·92
	Pubna	20—22	0·40	1·27	1·59	3·68	7·20	12·24	10·73	13·06	10·91	4·67	0·37	0·12	66·24
	Darjeeling	23—26	0·74	1·11	2·35	3·72	7·10	25·25	29·86	26·19	17·66	6·50	0·21	0·16	120·85
	Mongpoo	10—11	0·85	0·67	2·02	3·94	9·49	31·43	30·65	27·15	16·68	5·32	0·13	0·10	128·43
	Julpigoree	14—15	0·46	0·39	1·79	3·95	11·20	29·90	25·08	25·69	24·80	5·74	0·13	0·08	129·21
	Baxa	14—15	0·93	0·90	3·01	9·23	21·58	47·17	48·52	43·80	33·72	11·03	0·41	0·61	220·91
	Cooch Behar	12—13	0·39	0·36	1·23	5·72	13·98	35·50	23·07	21·86	23·44	5·19	0·05	0·10	130·89
	Dacca	33—35	0·29	0·97	2·45	5·84	9·25	13·25	12·93	12·38	10·19	5·40	0·68	0·23	73·86
	Furreedpore	17	0·34	1·27	2·79	4·40	8·33	13·30	12·94	12·38	9·92	4·55	0·54	0·14	70·90
	Burrisal	18—19	0·58	0·98	2·08	3·98	7·33	17·25	16·68	13·17	11·06	4·45	0·81	0·31	78·68
	Mymensingh	22 24	0·37	1·29	1·95	5·57	11·74	20·82	17·26	14·96	14·30	5·51	0·84	0·14	94·75
	Atia	13—14	0·39	1·23	1·40	3·58	7·11	14·39	11·33	12·48	10·40	5·12	0·29	0·12	67·84

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.*—continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Kishorgunj	13—14	0·67	1·02	3·21	4·48	10·83	19·29	13·84	13·48	13·49	5·52	0·45	0·41	86·60
	Chittagong	25—29	0·46	1·19	1·36	4·60	9·10	23·28	22·42	20·23	13·91	5·74	1·45	0·64	104·58
	Cox's Bazar	13—14	0·47	0·34	1·58	2·53	10·47	36·15	40·85	24·60	15·07	7·65	1·50	0·39	141·60
	Demagiri	6—7	0·54	1·70	2·05	4·80	13·56	20·46	17·41	21·45	19·87	7·96	1·82	1·35	112·97
	Noakholly	25—27	0·47	0·86	2·58	4·01	9·50	24·86	20·74	22·44	16·89	7·48	1·48	0·44	111·75
	Tipperah	26—27	0·64	0·90	2·89	6·54	10·44	18·49	18·35	16·47	11·40	5·28	1·34	0·30	93·04
	Rangamatia Hill	15	0·43	1·21	2·58	3·91	10·37	18·54	19·61	19·12	13·23	7·83	1·62	0·69	99·14
	Agartalla	11—12	0·93	1·13	4·86	3·99	11·13	14·13	11·94	14·37	10·80	4·96	0·97	0·55	79·76
	Patna	31—32	0·70	0·52	0·35	0·31	1·60	7·24	10·74	9·87	7·79	2·82	0·22	0·13	42·29
	Barh	13—14	0·50	0·59	0·35	0·11	2·16	5·58	12·26	9·73	7·29	3·26	0·26	0·03	42·12
	Gya	22—24	0·70	0·59	0·41	0·37	1·23	6·49	11·65	9·43	6·66	2·46	0·21	0·09	40·20
	Arrah	25—28	0·88	0·63	0·50	0·60	1·33	6·90	12·44	10·12	8·42	2·74	0·23	0·06	44·85
	Sasseram	13—14	0·46	0·66	0·21	0·14	1·01	5·54	12·46	11·32	6·53	3·63	0·25	0·08	42·29
	Buxar	15—16	0·81	0·42	0·29	0·18	0·75	4·92	11·62	9·76	6·91	3·07	0·18	0·13	39·04
	Morufferpore	25—28	0·82	0·56	0·46	0·53	2·25	6·76	10·84	10·20	8·15	2·94	0·09	0·04	43·64
	Durbhunga	13	0·47	0·57	0·28	0·61	2·23	8·20	11·90	11·32	8·92	2·70	0·08	0·11	47·39
	Chupra	28—31	0·70	0·51	0·40	0·41	1·24	6·42	10·19	9·04	7·27	2·72	0·22	0·03	39·15
	Sewan	13—14	0·77	0·66	0·28	0·32	1·75	7·54	11·76	10·23	8·63	3·98	0·12	0·06	46·10
	Motiharee	24—26	0·48	0·33	0·58	0·62	2·44	8·14	10·68	12·50	7·89	3·75	0·09	0·10	47·60
BENGAL—*contd.*	Monghyr	29—32	0·40	0·72	0·45	0·46	1·83	6·86	11·36	10·85	7·87	3·96	0·28	0·08	45·12
	Jamooee	12—14	0·69	0·82	0·34	0·60	2·01	6·74	12·27	10·86	7·28	2·37	0·09	0·04	44·11
	Bhagalpur	29—30	0·49	0·72	0·38	0·90	2·48	8·27	11·16	10·70	7·23	4·20	0·24	0·08	46·85
	Muddehpoora	13—14	0·42	0·73	0·35	1·04	3·69	8·62	12·29	12·14	10·06	4·56	0·07	0·06	54·03
	Purneah	13—14	0·38	0·73	0·41	1·38	3·34	11·92	14·68	14·16	14·32	3·96	0·09	0·17	64·94
	Kissengunge	12—13	0·52	0·60	0·78	1·24	5·33	16·27	16·25	15·37	13·31	3·28	0·06	0·14	73·15
	Nya Doomka	13	0·53	0·86	0·65	1·14	3·34	9·91	13·65	13·88	9·61	4·60	0·22	0·23	58·62
	Godda	11—12	0·32	0·76	0·37	0·41	2·42	7·43	11·28	11·91	9·86	3·05	0·11	0·14	48·06
	Cuttack	23—26	0·40	0·47	0·93	1·44	3·09	10·30	12·77	11·41	9·71	5·79	1·03	0·48	57·82
	Banki	3— 4	0·03	0·07	0·93	0·47	4·06	8·80	12·42	8·59	10·92	3·62	1·84	0·36	52·11
	Barreepudda	5	0·32	0·46	1·56	1·58	4·52	9·56	12·98	11·63	11·71	4·39	0·60	0·15	59·46
	Dhenkanal	3	0·20	0·36	1·41	1·03	2·37	10·74	19·19	11·35	11·27	4·43	0·49	0·03	62·87
	Angul	3—4	...	1·57	0·62	1·83	2·64	10·98	15·12	13·17	8·20	6·75	1·14	0·41	62·43
	Bispara	3	0·11	0·27	0·82	0·25	2·04	13·38	12·53	7·23	8·82	4·15	0·76	0·39	50·75
	Kunjabangar	3	?	?	1·95	4·36	3·20	8·00	12·28	14·80	15·25	5·61	2·11	0·08	?
	Talcher	3	0·38	0·66	1·07	1·29	2·21	11·25	20·93	9·71	7·63	3·17	0·66	0·07	59·03
	Keonjhar	3—4	...	0·07	0·47	1·53	1·27	2·97	17·02	5·42	2·11	0·75	0·90	0·10	32·61
	False Point	16—17	0·41	0·72	1·21	2·80	3·17	10·17	14·38	14·51	11·12	10·91	2·30	0·68	72·38
	Pooree	26—29	0·24	0·95	0·59	1·05	2·52	8·22	10·40	11·37	9·93	8·14	1·90	0·67	55·98
	Balasore	24—25	0·76	1·19	1·74	3·25	4·78	9·92	11·61	12·53	12·55	7·21	1·20	0·24	66·98
	Jellasore	10—11	0·89	1·28	0·92	1·63	3·63	7·62	15·82	11·98	10·25	5·38	0·45	0·05	59·90

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
BENGAL—*concld.*	Bhuddruck	13—14	0·35	1·39	0·88	2·04	4·86	8·82	12·98	10·88	10·04	4·70	1·02	0·41	58·37
	Hazaribagh	22—24	0·48	0·80	0·69	0·40	1·53	8·23	12·92	12·48	7·80	3·21	0·35	0·13	49·02
	Ranchee	26—28	0·79	1·14	1·40	0·69	1·97	7·50	12·12	11·75	8·12	3·15	0·31	0·15	49·09
	Palamow	13—14	0·58	0·54	0·72	0·38	1·11	6·20	13·11	11·56	7·33	2·45	0·53	0·23	44·74
	Sirguja	3	?	?	?	?	?	?	?	?	6·87	1·28	2·42	...	?
	Chybassa	14—15	0·79	0·97	1·48	0·87	3·67	8·41	14·31	14·06	8·89	3·14	0·25	0·27	57·11
	Purulia	19—21	0·39	1·03	1·04	0·92	2·62	9·28	11·04	12·53	7·64	3·89	0·17	0·21	50·76
	Gobindpur	12—13	0·57	1·15	0·53	0·68	2·06	8·22	12·79	13·25	7·02	4·35	0·13	0·19	50·94
ASSAM	Silchar	26—27	0·61	2·63	7·78	12·58	15·93	19·20	20·22	17·82	13·81	6·48	1·07	0·72	118·85
	Sibsagar	27—29	1·16	2·25	4·44	10·09	10·81	14·66	15·80	16·17	11·48	5·14	1·36	0·53	93·89
	Sylhet	27—31	0·39	1·59	5·74	13·73	21·64	32·02	25·48	25·69	20·05	8·31	1·18	0·30	156·12
	Goalpara	22	0·38	0·58	2·12	6·32	13·26	24·72	17·68	12·78	11·95	4·87	0·23	0·26	94·55
	Tura	13—14	0·62	1·04	1·85	5·56	15·96	23·14	23·79	21·27	21·24	8·79	0·39	0·15	123·80
	Gauhati	32—35	0·58	0·96	2·43	5·82	10·33	12·98	12·63	11·12	8·25	3·21	0·66	0·29	69·26
	Kulsi	3	0·18	0·61	2·66	4·58	14·54	14·47	12·97	13·70	10·76	6·48	0·09	0·23	81·37
	Tezpur	26—30	0·64	0·90	2·36	6·16	10·34	14·05	15·89	12·87	9·63	3·02	0·93	0·65	77·44
	Chardner	3	0·96	1·22	2·10	5·25	7·66	14·09	14·15	20·94	15·47	5·71	0·35	0·80	88·70
	Nowgong	28—31	0·87	1·12	2·44	5·61	9·81	13·32	16·00	14·82	10·89	4·27	0·53	0·31	79·99
	Dibrugarh	20—23	1·32	2·60	5·71	9·75	13·80	18·97	19·92	18·40	14·25	6·33	1·58	0·90	113·53
	Shillong	17—18	0·39	0·92	2·01	3·63	10·33	16·85	14·02	14·93	15·44	6·48	1·06	0·36	86·42
	Cherra Poonjee	21—27	0·72	2·63	8·79	29·72	51·46	114·06	122·53	79·55	56·24	13·74	2·01	0·35	481·80
	Kohima	5	0·66	1·30	3·38	3·02	9·34	16·67	17·63	14·66	9·49	2·95	0·81	0·99	80·90
	Dhubri	12—14	0·33	0·61	1·44	5·16	16·40	27·10	15·81	11·69	12·84	4·76	0·03	0·19	96·36
CENTRAL PROVINCES	Nagpur	36—37	0·61	0·42	0·63	0·45	0·83	8·99	12·94	8·82	7·92	2·15	0·41	0·34	44·51
	Bhandara	19—21	1·04	0·62	0·49	0·57	1·18	8·40	16·71	12·76	9·46	1·60	0·31	0·08	53·22
	Chanda	19—21	0·19	0·81	1·23	0·73	2·67	6·81	14·54	11·62	8·80	2·52	0·86	0·17	50·95
	Brahmapuri	17	0·52	0·15	0·66	0·38	0·85	8·70	18·16	12·48	9·69	2·14	0·35	0·25	54·33
	Wardha	19—21	0·37	0·29	0·36	0·34	0·81	6·69	12·14	9·24	8·06	2·06	0·37	0·12	40·85
	Arvi	14—15	0·72	0·16	0·54	0·17	0·64	5·88	8·82	7·90	7·92	1·73	0·32	0·29	35·09
	Balaghat	17	0·54	0·59	0·28	0·54	1·80	12·50	22·33	16·69	9·51	1·38	0·41	0·15	65·92
	Sironcha	19—21	0·10	0·42	0·49	0·41	1·92	6·80	12·37	10·81	8·66	2·42	0·57	0·06	45·03
	Jubbulpore	38—40	0·58	0·46	0·50	0·24	0·39	8·17	18·15	13·67	8·38	1·42	0·34	0·16	52·46
	Saugor	25—28	0·57	0·53	0·19	0·19	0·63	6·02	16·73	11·03	7·64	1·08	0·39	0·28	45·28
	Damoh	25—27	0·60	0·41	0·22	0·20	0·36	6·07	16·40	12·71	7·31	1·35	0·34	0·23	46·20
	Seoni	25—27	0·69	0·92	0·47	0·60	0·90	9·73	14·82	10·86	7·95	2·07	0·38	0·47	49·86
	Mandla	24—27	0·53	0·55	0·79	0·54	0·56	9·07	18·38	11·86	6·55	1·38	0·26	0·19	50·66
	Badnur	27—31	0·42	0·32	0·69	0·31	0·49	7·63	13·26	8·93	7·83	1·69	0·37	0·30	42·24
	Chhindwara	20—21	0·76	0·32	0·49	0·29	0·74	10·24	12·05	8·52	8·44	2·09	0 32	0·22	44·48
	Hoshangabad	25—29	0·32	0·15	0·25	0·04	0·54	6·13	15·09	12·86	10·37	0·99	0·39	0·26	47·39
	Narsinghpur	26—29	0·34	0·32	0·25	0·27	0·52	8·05	15·32	11·89	8·54	1·47	0·24	0·21	47·42

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
CENTRAL PROVINCES—*contd.*	Khandwa	18—20	0·28	0·33	0·09	0·08	0·32	6·45	10·33	7·51	6·54	1·04	0·10	0·22	33·29
	Pachmarhi	12—13	0·47	0·30	0·37	0·29	0·63	9·98	29·11	19·17	15·15	1·63	0·46	0·29	77·85
	Raipur	19—21	0·36	0·22	0·63	0·58	0·78	9·67	13·80	12·65	7·79	1·76	0·88	0·14	49·26
	Dhamtari	17	0·27	0·32	0·34	0·23	1·39	8·23	14·82	10·12	7·40	2·18	0·40	0·10	45·80
	Sambalpur	21—23	0·67	0·60	0·71	0·51	1·54	13·10	17·68	15·54	8·21	2·52	0·31	0·28	61·73
	Raigarh	3	?	?	?	?	?	10·26	19·89	21·49	8·88	0·87	0·93	0·36	?
	Sarangarh	5	...	0·04	0·72	0·34	0·36	8·62	16·02	14·90	5·67	3·96	0·30	...	50·93
	Bilaspur	19—21	0·50	0·26	0·91	0·82	1·09	9·07	13·25	11·59	7·48	1·72	0·39	0·21	47·29
	Saragaon	13—14	0·27	0·12	0·37	0·51	0·32	7·47	17·54	11·27	8·77	1·43	0·33	0·08	48·48
	Makhla	5—6	0·02	0·36	0·20	0·02	0·23	12·20	20·62	14·65	14·37	3·38	0·51	...	66·56
BERARS	Chikalda	12—13	0·48	0·08	0·40	0·12	0·36	11·75	16·71	15·56	12·56	4·32	0·39	0·42	63·15
	Ellichpur	23—24	0·42	0·10	0·43	0·21	0·36	5·97	7·95	5·77	5·37	1·75	0·41	0·18	28·92
	Amraoti	24—25	0·51	0·21	0·34	0·23	0·65	6·87	8·76	7·34	5·23	1·50	0·21	0·24	32·09
	Akola	22—23	0·53	0·16	0·46	0·11	0·21	5·22	7·10	6·75	5·70	1·99	0·45	0·31	28·99
	Buldana	22—23	0·71	0·14	0·28	0·28	0·48	6·49	7·58	7·54	6·32	2·18	0·35	0·22	32·57
	Basim	18	0·37	0·07	0·22	0·35	0·60	8·49	10·91	8·25	7·64	1·80	0·71	0·28	39·69
	Yeotmal	19	0·26	0·12	0·47	0·24	0·97	7·85	13·01	9·44	7·37	2·23	0·49	0·15	42·60
	Wun	17—19	0·31	0·16	0·67	0·13	0·61	6·01	11·30	10·85	6·57	1·57	0·80	0·20	39·18
HYDERABAD	Bolarum	14	0·14	0·24	0·50	0·54	1·14	3·58	5·80	6·70	5·77	3·17	0·46	0·40	28·44
	Secunderabad	40—41	0·30	0·24	0·78	0·71	1·41	3·65	5·72	5·62	5·18	3·30	0·75	0·22	27·88
	Hyderabad	15	0·15	0·08	0·34	0·68	0·80	4·42	5·42	6·17	7·20	3·37	0·93	0·67	30·22
	Lingsugur	8	...	0·01	0·01	0·71	0·90	3·24	2·60	4·45	5·76	4·51	1·60	0·25	24·04
	Aurangabad	9	0·10	0·03	0·02	0·05	0·90	6·82	6·55	6·80	7·32	2·48	0·60	0·22	31·89
	Hingoli	20	0·50	0·10	0·24	0·48	0·75	6·72	9·99	8·46	7·39	2·08	0·76	0·24	37·71
	Jalna	5	...	...	0·05	...	0·72	8·53	5·94	5·75	8·46	2·63	1·12	0·07	33·27
	Mominabad	3—4	...	...	0·25	0·50	0·30	9·00	4·23	7·76	13·41	2·03	1·60	...	39·08
	Ibrahimpatan	8	0·02	0·09	0·77	0·61	1·36	5·64	5·93	7·69	5·80	2·97	1·38	0·23	32·49
	Medack	8	0·04	0·21	0·47	0·92	0·51	4·17	6·76	9·39	7·08	2·49	0·50	0·08	32·62
	Indur	8	...	...	0·36	0·33	0·26	3·85	8·54	9·46	7·02	2·55	1·13	0·06	33·56
	Yelgandal	8	0·03	0·24	0·40	0·65	1·31	4·46	6·34	6·77	7·71	2·66	0·94	0·08	31·59
	Khamam	8	...	0·34	1·17	0·48	0·91	4·78	6·11	6·99	6·02	2·19	1·55	0·26	30·80
	Nalgonda	8	0·09	0·01	0·42	0·36	1·74	3·10	4·41	4·93	6·27	3·92	1·99	0·07	27·31
	Nagad Karnul	8	0·03	0·04	0·53	0·50	1·33	4·35	5·86	7·11	5·44	2·52	0·71	0·35	28·77
	Beeder	8	...	...	0·46	0·79	0·49	6·97	9·28	11·15	9·11	3·62	0·91	0·04	42·82
	Naldurg	8	...	...	0·26	0·25	0·91	7·95	4·58	8·94	9·85	2·67	0·69	0·16	36·26
	Nanded	8	0·22	...	0·19	0·30	0·73	6·78	7·69	9·08	7·18	3·10	0·73	0·57	36·57
	Gulbarga	8	0·03	0·19	0·32	0·74	1·41	5·05	4·53	7·36	6·45	2·77	0·56	...	29·61
	Shorapur	7—8	...	...	0·18	0·24	0·37	3·12	4·12	5·36	5·19	3·53	0·96	0·13	23·20
	Raichur	8	0·06	...	0·36	0·77	0·74	4·46	3·67	5·22	4·91	4·12	0·62	0·02	24·95
	Bheer	8	0·25	0·03	0·12	0·21	0·37	6·01	5·50	5·99	8·71	2·29	1·10	0·07	30·65
	Purbhani	8	0·02	...	0·14	0·20	0·18	6·49	7·43	7·86	8·71	1·88	0·92	0·01	33·84

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylone, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Dhulia	14—23	0·37	0·07	...	0·02	0·37	4·76	4·59	4·08	4·35	1·66	0·55	0·15	20·97
	Nasik	23—27	0·07	0·04	0·02	0·08	0·61	6·13	7·26	5·13	5·19	3·64	0·53	0·21	28·91
	Igatpuri	14—21	0·17	0·12	0·06	0·09	1·16	22·25	44·70	33·60	17·04	4·52	0·30	0·18	124·19
	Malegaon	14—23	0·24	0·20	0·02	0·24	0·74	5·26	4·11	4·35	6·18	2·13	0·40	0·36	24·23
	Ahmednagar	27	0·41	0·08	0·19	0·48	1·37	5·02	3·11	4·13	6·94	2·94	0·90	0·13	25·70
	Poona	40	0·24	0·04	0·18	0·56	1·64	5·87	6·59	4·21	4·24	3·87	0·75	0·19	28·38
	Lonavala	10	0·06	0·02	0·15	0·02	0·51	29·68	64·16	41·47	24·33	4·43	0·24	0·06	165·13
	Satara	28—29	0·34	0·08	0·08	0·90	1·37	7·85	13·00	7·34	4·53	3·39	1·62	0·39	40·89
	Mahableshwar	27—29	0·40	0·05	0·39	0·88	1·28	47·85	99·75	68·24	33·11	5·25	1·03	0·26	258·49
	Sholapur	30—31	0·05	0·12	0·28	0·71	1·21	4·85	4·35	6·09	7·50	3·32	0·72	0·16	29·36
	Kolhapur	22—24	0·03	0·02	0·08	1·39	2·07	7·56	11·49	7·17	4·07	4·92	0·67	0·12	39·59
	Bavda	10—12	0·20	0·01	0·02	0·65	2·50	55·00	89·44	58·82	36·39	9·79	2·32	0·14	255·28
	Belgaum	31—32	0·07	0·02	0·50	2·04	2·83	9·60	15·05	8·97	3·66	4·60	1·24	0·29	48·87
	Gokak	15—22	0·05	...	0·33	1·00	1·74	3·38	1·96	2·27	3·20	5·87	0·93	0·68	21·41
	Dharwar	17—24	0·15	0·02	0·32	1·36	2·89	5·45	6·30	5·13	3·32	5·80	2·24	0·40	33·39
	Hubli	13—20	0·05	...	0·28	1·50	2·47	4·38	4·41	3·27	3·21	5·59	1·05	0·24	26·45
	Nandgad	13—20	0·18	0·13	0·23	0·84	2·01	2·96	2·05	3·17	4·02	5·52	0·69	0·27	22·07
	Mandargi	10	0·41	...	0·22	0·70	1·76	1·87	2·21	2·31	3·69	4·34	1·28	0·03	18·82
	Kalghatgi	13—20	0·06	...	0·28	1·23	1·63	5·45	7·12	4·48	3·54	4·90	0·79	0·33	29·81
	Kaladgi	15—18	0·10	0·15	0·22	0·48	1·41	3·33	2·09	3·18	5·46	4·55	0·69	0·40	22·06
BOMBAY	Bijapur	14—22	0·04	0·03	0·21	0·53	0·71	3·60	2·51	4·24	6·09	4·25	1·23	0·77	24·21
	Karwar	22—23	0·17	...	0·07	0·34	3·00	34·54	37·07	21·73	12·48	4·78	1·72	0·13	116·03
	Honavar	20—22	0·27	...	0·16	0·30	3·62	40·68	42·63	27·46	15·93	5·79	1·10	0·14	138·08
	Vengurla	15—22	0·19	...	0·07	0·07	1·92	34·74	35·53	21·71	11·75	3·91	0·95	0·05	110·89
	Ratnagiri	15—27	1·11	0·02	...	0·17	1·49	31·85	33·17	19·60	12·93	3·33	0·83	0·05	104·55
	Colaba (Observatory).	37—67	0·12	0·02	...	0·03	0·56	20·80	24·52	14·99	10·74	1·78	0·48	0·04	74·08
	Byculla J. J. Hospital.	15—22	0·16	...	0·02	...	0·44	21·91	27·18	17·35	12·43	2·63	0·04	...	82·16
	Thana	15—26	0·03	0·08	0·01	...	0·42	25·24	35·59	20·94	12·76	2·76	0·03	0·01	97·87
	Matheran	15—18	0·02	0·01	0·02	0·01	0·45	43·07	98·09	63·46	34·38	5·25	0·47	0·01	245·24
	Surat	15—21	0·04	0·03	...	...	0·12	9·78	13·36	9·82	7·35	1·31	0·09	0·03	41·93
	Broach	15—22	0·07	0·02	0·01	0·01	0·10	7·03	15·06	8·81	6·84	1·48	0·16	0·03	39·62
	Kaira	15—23	0·03	0·24	...	0·06	0·37	4·04	13·52	8·90	4·62	0·46	0·15	0·07	32·46
	Godhra	15—18	0·06	0·17	0·01	0·01	0·46	5·21	17·13	11·32	8·44	0·74	0·04	0·07	43·66
	Ahmedabad	15—23	0·01	0·09	0·02	0·04	0·71	3·34	11·06	9·00	4·42	0·65	0·03	0·05	29·42
	Bariya	15	0·07	0·35	0·01	...	0·19	5·48	17·95	10·95	10·59	0·70	0·08	0·14	46·51
	Idar	14—16	0·01	0·20	...	0·02	0·76	3·27	16·32	11·34	7·05	0·34	0·11	0·04	39·46
	Palanpur	12—16	0·06	0·25	0·06	0·01	0·79	2·29	10·26	11·95	4·60	0·84	...	0·09	31·20
	Rajkot	17—23	0·05	0·08	0·02	0·01	0·35	5·29	9·48	6·39	4·44	0·78	0·24	0·07	27·20
	Bhuj	14—23	0·04	0·13	0·13	0·19	0·17	2·34	4·89	3·61	2·41	0·90	0·01	0·03	14·85
	Rhahpur	6	0·04	...	0·17	0·12	0·04	0·71	9·42	3·22	3·46	1·60	...	...	18·78
	Kurrachee	26—28	0·60	0·26	0·15	0·18	0·05	0·19	2·97	1·87	0·86	0·07	0·07	0·20	7·47

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Sehwan	18—19	0·41	0·22	0·23	0·23	0·11	0·01	2·13	2·83	0·87	...	0·09	0·17	7·30
	Tatta	15	0·20	0·13	0·15	0·56	0·03	0·97	3·65	1·48	1·30	...	0·12	0·06	8·65
	Hyderabad	17—21	0·21	0·15	0·09	0·24	0·04	0·44	2·94	3·27	0·75	0·01	0·06	0·01	8·21
	Umarkot	15—19	0·14	0·06	0·14	0·17	0·09	0·94	3·68	4·39	1·18	0·29	...	0·01	11·09
BOMBAY—*contd.*	Nagar	19—21	0·13	0·07	0·06	0·03	0·30	1·89	5·34	6·00	1·92	0·40	...	0·03	16·17
	Shikarpur	19—21	0·30	0·27	0·40	0·19	0·02	0·13	1·28	1·70	0·18	...	0·05	0·13	4·65
	Rohri	22—23	0·35	0·51	0·47	0·31	0·22	0·34	1·35	1·23	0·32	0·02	0·08	0·21	5·41
	Jacobabad	23	0·23	0·23	0·33	0·16	0·11	0·09	1·32	1·39	0·26	0·01	0·09	0·11	4·33
	Deesa	26—28	0·12	0·20	0·10	0·05	0·18	2·26	9·27	8·47	3·05	0·91	0·07	0·04	24·72
	Ganjam	20—21	0·18	0·49	0·95	0·96	1·62	5·61	5·13	5·88	8·79	9·18	1·26	0·81	40·86
	Gopalpore	3—4	0·34	0·01	1·12	1·42	2·55	10·40	8·63	8·18	8·27	10·93	4·42	1·00	57·27
	Aska	20—21	0·23	0·42	1·29	1·63	3·35	5·97	6·76	8·82	8·55	6·79	1·82	0·48	46·11
	Vizianagram	21	0·19	0·47	0·80	0·43	2·78	4·30	5·03	6·29	7·19	8·16	1·73	1·28	38·65
	Bimlipatam	24	0·30	0·53	0·16	0·20	1·97	3·22	3·64	4·04	6·25	8·01	2·18	1·13	31·63
	Royaghadda	3	...	0·02	1·33	2·22	5·25	6·90	9·33	10·55	4·28	5·53	2·30	0·30	48·01
	Nourangapur	3	?	?	0·77	0·98	1·67	9·47	22·73	17·93	9·03	2·25	0·67	0·05	?
	Gunipur	3	?	?	?	?	?	?	?	?	6·70	4·53	1·60	0·38	?
	Kotipad	3	...	...	0·60	0·38	1·15	10·55	20·90	14·13	10·60	3·27	1·28	0·03	62·89
	Koraput	3	...	...	0·15	0·91	1·00	8·60	17·70	12·30	9·18	4·05	1·63	0·23	55·75
	Malkanagiri	3	?	?	?	?	0·74	10·10	19·67	11·98	19·33	1·78	1·05	...	?
	Narsapatnam	14	0·39	0·39	0·67	1·04	3·93	4·69	4·78	5·47	8·27	8·28	3·33	0·90	42·14
	Vizagapatam	18	0·38	0·28	0·34	0·63	3·34	4·59	4·84	6·12	7·27	10·93	4·08	2·22	45·02
	Coconada	21	0·25	0·24	0·17	0·49	2·22	3·96	5·17	5·09	6·45	8·60	3·59	0·93	37·16
	Rajahmundry	22	0·17	0·28	0·22	1·04	3·16	4·30	6·97	6·24	7·08	6·40	1·69	0·01	37·56
MADRAS	Ellore	21	0·28	0·09	0·38	0·67	1·56	3·90	5·40	6·38	7·55	6·05	2·56	0·37	35·19
	Masulipatam	21	0·25	0·08	0·34	0·05	1·75	4·12	5·53	5·65	6·64	8·58	4·11	0·48	37·58
	Guntur	24	0·38	0·16	0·51	0·66	1·77	3·44	4·60	6·38	5·81	6·91	2·38	0·25	33·25
	Vinukonda	14	0·36	0·02	0·08	0·47	1·44	2·47	2·49	4·20	4·44	6·24	2·72	0·78	25·71
	Ongole	21	0·28	0·03	0·14	0·17	1·39	1·50	2·48	3·53	4·24	6·88	4·86	0·96	26·46
	Nellore	20—21	0·53	0·11	0·28	0·13	1·35	1·58	2·24	3·17	3·16	9·84	10·17	3·41	35·97
	Udayagiri	14	0·43	0·26	0·35	0·40	1·97	1·47	1·61	2·12	2·59	8·24	7·27	1·75	28·46
	Tada	14	0·91	0·81	0·35	0·18	2·43	2·57	2·95	4·43	3·50	9·50	11·53	3·29	42·45
	Kurnool	23—24	0·04	0·04	0·50	0·76	2·10	3·28	5·03	6·21	6·31	3·79	0·79	0·17	29·02
	Cumbum	14	0·12	0·06	0·56	0·21	2·07	2·33	3·01	2·97	4·16	5·58	3·38	0·35	24·80
	Nandayal	14	0·05	0·03	0·22	0·43	1·51	4·71	5·37	7·41	10·06	4·81	1·03	0·26	35·89
	Bellary	30	0·10	0·04	0·60	0·82	1·86	1·71	1·38	2·34	3·76	3·76	1·01	0·26	17·64
	Gooty	27—28	0·04	0·07	0·07	0·49	1·87	2·66	2·88	4·07	4·40	4·07	1·09	0·08	21·79
	Adoni	14	...	...	0·04	0·50	1·58	4·03	4·32	5·73	5·77	4·94	0·65	0·04	27·60
	Dharmavaram	14	0·02	0·21	0·25	0·43	2·12	2·64	1·34	3·28	4·58	5·39	1·96	0·16	22·38
	Cuddapah	30—31	0·11	0·01	0·25	0·35	1·58	2·61	3·45	5·21	5·89	5·15	2·91	0·55	28·07
	Madanapalle	14	0·20	0·14	0·55	0·85	3·01	2·35	1·95	3·26	4·90	7·20	4·15	0·76	29·32

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.* —continued.

PROVINCES.	STATIONS.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
MADRAS—*contd.*	Chittoor	21	0·37	0·24	0·42	0·47	3·44	2·31	2·98	5·68	6·17	6·57	4·73	1·69	35·07
	Vellore	20—21	0·72	0·37	0·14	0·52	2·94	2·44	3·39	5·41	5·50	6·74	6·25	2·15	36·57
	Chandragiri	14	0·39	0·30	0·35	0·61	2·38	2·65	2·71	4·10	5·50	6·51	6·71	1·24	33·45
	Arcot	20—21	0·48	0·64	0·45	0·57	2·58	2·36	3·42	6·11	5·32	5·39	5·87	1·69	34·88
	Madras	71	0·95	0·30	0·42	0·65	2·24	2·02	3·82	4·51	4·74	10·80	13·40	5·04	48·89
	Palmaner	21	0·24	0·21	0·35	0·54	2·75	2·38	2·72	4·74	5·20	6·10	4·47	1·30	31·00
	Saidapet	5	0·85	0·49	0·42	...	0·75	1·50	3·97	4·74	5·06	11·84	17·47	5·63	52·72
	Chingleput	19—21	0·48	0·35	0·17	0·16	1·60	2·06	3·14	4·60	5·10	6·78	8·45	3·08	35·97
	Conjeeveram	20—21	0·59	0·46	0·16	0·39	2·02	2·18	4·09	6·06	6·10	6·58	7·85	2·47	38·95
	Tindivanam	20—21	0·41	0·66	0·28	0·54	2·61	2·00	3·01	6·84	6·44	7·87	7·92	2·66	41·24
	Cuddalore	22—23	0·87	0·31	0·34	1·03	1·43	1·30	2·26	4·67	4·65	7·75	12·52	4·73	41·86
	Vriddhachalam	20	0·45	0·36	0·15	0·52	1·91	1·34	2·70	5·02	4·85	5·92	6·51	2·68	32·41
	Udayarpalaiyam	19	0·84	0·38	0·10	0·79	3·23	1·76	2·88	5·05	4·65	7·26	7·27	3·83	38·04
	Salem	23—24	0·37	0·08	0·92	2·13	4·53	3·13	3·94	5·78	6·08	7·22	2·65	0·70	37·53
	Atur	21	0·43	0·27	0·71	1·53	4·58	1·32	2·87	3·94	5·29	7·67	5·06	1·12	34·79
	Shevaroy Hills	20—21	0·42	0·19	0·77	2·61	6·33	4·75	7·70	10·08	8·50	10·41	6·03	2·81	60·60
	Kambakonum	20—21	0·73	0·55	0·47	0·74	1·87	2·03	2·41	4·38	4·56	8·26	8·63	5·28	39·91
	Tirupatur	14	0·16	0·39	0·60	0·75	5·77	2·67	3·89	5·21	7·17	6·86	4·41	0·52	38·40
	Hosur	14	0·30	0·34	0·77	1·37	5·00	1·88	2·74	5·42	5·01	5·75	3·61	0·77	32·96
	Tranquebar	20—21	1·14	0·40	0·08	1·20	1·51	1·10	1·97	3·80	3·60	8·85	13·96	9·50	47·11
	Negapatam	20—21	1·18	0·82	0·13	1·08	1·79	1·18	1·27	3·33	3·84	7·96	13·85	9·84	46·27
	Tanjore	20—21	0·73	0·48	0·51	0·91	1·63	1·22	1·78	3·99	4·22	5·60	5·54	3·71	30·32
	Putukota	14	1·30	0·95	0·32	1·29	2·24	2·05	1·70	5·58	3·48	5·79	7·44	5·34	37·48
	Trichinopoly	30—32	1·09	0·56	0·74	2·02	3·58	1·31	2·16	4·43	5·56	7·86	5·23	2·92	37·46
	Karur	20—21	0·29	0·13	0·35	1·91	3·93	1·37	1·35	3·32	3·49	6·14	2·96	1·31	26·55
	Coimbatore	21—23	0·27	0·14	0·61	1·94	2·58	1·79	1·35	1·23	1·23	5·90	3·33	0·97	21·34
	Kollegal	14	0·27	0·06	0·67	1·64	6·08	1·75	2·62	5·57	6·19	8·40	2·44	0·60	36·29
	Dindigul	21	0·66	0·35	0·30	1·80	3·13	1·59	1·59	2·25	2·86	6·20	5·09	2·20	28·02
	Madura	23	0·80	0·45	0·65	2·25	2·72	1·52	1·59	4·67	4·39	8·88	5·37	2·04	35·33
	Pasumali	27—32	0·81	0·49	0·80	2·32	3·12	0·96	2·29	4·32	4·22	7·88	5·05	2·15	34·41
	Vattanum	13—14	1·38	1·19	0·81	3·29	1·58	0·74	0·83	2·02	1·89	6·26	8·76	5·93	34·68
	Periyakulam	13—14	0·85	0·98	1·80	2·28	2·83	1·07	0·69	1·87	2·33	6·18	5·39	1·05	27·32
	Tinnevelly	22—23	1·41	1·01	1·58	1·92	1·63	0·69	0·31	0·57	0·87	6·07	9·61	2·94	28·61
	Tuticorin	20—21	1·23	0·65	0·87	1·39	0·94	0·13	0·21	0·37	0·50	3·40	7·47	2·28	19·44
	Setur	14	0·41	0·75	1·17	1·60	2·14	0·51	0·92	1·45	1·67	5·69	4·28	1·71	22·30
	Cochin	27—28	1·03	0·79	2·23	4·46	12·91	31·10	22·62	12·48	9·31	11·42	4·70	1·97	115·02
	Palghat	21	0·07	0·12	0·52	2·10	4·31	18·59	20·65	10·79	6·12	6·74	3·60	0·85	74·46
	Wellington	7—9	0·92	0·41	2·42	3·44	4·03	3·69	3·12	3·80	3·56	8·12	8·61	3·25	45·37
	Manantoddy	16	0·29	0·37	1·22	2·77	5·08	22·66	32·04	16·76	7·89	5·95	2·40	0·74	98·17
	Calicut	22—23	0·18	0·16	1·00	3·05	9·80	35·17	29·77	14·30	8·09	8·60	3·37	1·55	115·04
	Tellicherry	20—21	0·45	0·08	0·39	3·03	8·96	38·94	36·27	16·83	9·94	6·87	3·00	0·90	125·66

TABLE XXV.—*Average monthly and annual rainfall of 451 stations in India, Ceylon, &c.*, —concluded.

Provinces.	Stations.	Years.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Madras—*concld.*	Cannanore	22—23	0·56	0·26	0·17	2·41	6·86	41·58	39·49	18·47	9·14	7·44	2·87	0·43	129·68
	Mangalore	25—32	0·18	0·09	0·13	2·19	8·56	38·64	37·86	23·36	11·43	8·01	1·86	0·56	132·87
Mysore and Coorg.	Bangalore	47—48	0·22	0·15	0·59	1·34	4·95	3·20	4·03	6·09	6·34	6·31	1·80	0·65	35·67
	Mysore	45—47	0·09	0·14	0·71	2·23	5·65	1·82	2·34	3·24	3·89	6·32	1·65	0·46	28·54
	Shimoga	46—47	0·07	0·15	0·33	1·78	3·28	4·42	6·67	4·13	2·92	5·00	1·15	0·36	30·26
	Mercara	20	0·33	0·65	1·18	2·27	6·05	26·38	43·27	24·86	12·80	7·71	2·74	0·57	128·21
	Kolar	14	0·34	0·03	0·76	0·88	3·71	3·63	3·31	5·00	4·81	6·26	2·64	0·77	32·14
	Tumkur	38	0·17	0·26	0·38	1·29	4·59	3·86	3·46	5·18	5·34	7·15	1·31	0·33	33·32
	Chitaldroog	14	0·36	0·02	0·16	1·18	3·73	3·15	2·77	3·32	3·51	5·12	1·99	0·43	25·74
	Chikmagalur	14	0·42	0·16	0·97	1·82	5·32	4·38	6·51	3·25	3·04	6·98	2·49	0·57	35·91
	Hassan	13	1·39	0·17	0·70	1·20	4·07	4·32	4·87	2·83	2·12	4·61	1·56	0·57	28·41
Ceylon	Jaffna	13	2·26	1·46	1·45	2·32	2·11	0·49	0·56	1·32	2·67	7·79	14·96	8·98	46·37
	Mannaar	13—14	2·60	2·14	2·25	2·42	3·04	0·56	0·12	0·45	0·73	6·35	9·42	7·27	37·35
	Trincomalee	13—14	6·61	2·63	1·47	1·79	2·28	2·02	2·30	4·34	4·46	8·25	13·61	12·93	62·69
	Batticaloa	13—14	8·58	3·68	3·43	1·55	1·60	1·33	0·74	2·98	2·07	5·22	13·34	14·45	58·97
	Hambantota	14	3·68	2·04	2·35	2·02	3·58	2·06	1·35	1·64	2·72	5·37	6·38	3·76	36·95
	Galle	14	4·34	3·67	5·02	9·09	11·36	7·90	5·50	5·65	7·63	12·37	11·68	6·51	90·72
	Ratnapura	14	5·32	4·55	7·92	11·91	18·98	20·04	12·10	14·14	14·46	18·11	14·93	8·80	151·26
	Colombo	14	3·39	1·94	5·71	9·46	13·09	7·52	5·63	4·99	4·72	12·36	12·82	6·11	87·74
	Kandy	14	5·33	2·96	2·94	7·50	6·39	8·87	7·60	5·92	5·85	10·78	11·97	8·70	84·81
	Newera Eliya	13—14	5·98	2·71	3·12	6·04	8·51	14·70	14·57	9·36	9·18	10·41	9·48	7·74	101·89
	Puttalam	13—14	1·75	1·52	3·06	6·18	4·28	1·53	0·42	0·96	1·17	5·85	10·77	5·77	43·26
	Anuradhapura	13—14	3·28	1·59	3·31	7·21	3·51	1·25	0·87	2·68	2·72	5·86	12·24	8·55	53·07
Burma	Akyab	26—27	0·16	0·20	0·50	1·74	12·42	53·05	51·71	37·92	23·26	12·30	3·69	0·66	197·61
	Kaukpyu	18	0·10	0·06	0·33	0·90	10·37	41·81	46·13	39·20	21·23	9·95	4·18	0·53	174·79
	Sandaway	21—23	0·08	0·07	0·15	1·30	14·04	50·83	59·05	47·05	24·59	11·36	3·31	0·20	212·03
	Rangoon	14	0·17	0·06	0·06	2·08	11·37	18·24	21·07	17·98	16·28	8·21	3·63	0·07	99·22
	Bassein	14	0·14	0·04	0·08	1·48	8·09	18·35	25·20	20·71	15·26	8·12	4·20	0·13	101·80
	Diamond Island	5—6	0·54	0·05	0·02	2·37	9·56	22·65	25·60	20·51	20·11	11·67	7·95	2·00	123·03
	Henzada	13	0·06	0·09	...	0·70	6·45	16·01	19·97	16·46	11·13	4·70	2·36	0·05	77·98
	Myanaung	9—10	0·01	...	0·02	1·04	5·38	10·66	10·31	10·44	9·80	5·19	2·31	0·20	54·76
	Prome	14	0·02	...	0·01	0·83	6·17	9·59	9·68	11·47	8·22	5·41	2·16	0·04	53·00
	Thayetmyo	14	...	0·02	0·07	0·75	5·85	8·19	7·85	9·02	7·92	5·59	2·06	0·05	47·37
	Toungoo	14	0·02	...	0·02	1·48	6·61	12·94	17·32	17·91	11·76	7·49	1·41	0·24	77·20
	Moulmein	34	0·01	0·04	0·13	3·24	20·22	38·48	43·41	43·03	30·99	8·38	1·42	0·02	189·37
	Tavoy	26—27	0·10	0·57	0·72	4·40	17·27	39·04	45·74	41·77	34·35	10·59	2·32	0·15	197·02
	Mergui	19—20	0·41	1·40	2·37	6·00	16·88	29·40	30·63	27·31	26·11	13·24	3·32	0·60	157·76
	Shwegyin	15	0·02	0·31	0·39	2·54	11·86	30·93	33·68	31·93	19·50	10·65	1·98	0·12	143·91
Bay Islands	Port Blair	16	1·03	1·47	0·45	2·60	16·23	18·71	17·06	15·19	19·32	12·10	8·55	5·67	118·38
	Nancowry	10—11	3·11	0·98	2·15	6·02	11·74	13·00	12·08	11·07	10·55	14·21	12·48	11·52	108·91
Straits Settlements.	Singapore	15	7·73	6·16	6·52	7·06	7·01	6·72	5·84	5·46	6·88	8·68	10·69	9·89	91·64

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883 with the averages of Table XXV.*

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
AFRICA	Zanzibar	+ 0·07	+ 1·53	— 2·97	— 1·36	— 0·44	— 1·26	+ 4·78	— 1·41	— 0·20	— 2·30	— 3·15	— 5·58	— 12·29
ARABIA	Aden	— 0·25	— 0·03	— 0·19	+ 0·36	+ 0·75	0	0	+ 0·16	0	0	+ 0·41	— 0·32	+ 0·89
PERSIAN GULF	Bushire	+ 2·11	+ 2·44	— 0·23	+ 0·47	0	0	0	0	0	0	— 0·07	+ 4·41	+ 9·21
BELUCHISTAN	Quetta	+ 1·38	— 1·41	+ 1·93	— 0·25	+ 0·37	— 0·04	+ 0·46	— 0·57	— 0 21	0	0	— 0·34	+ 1·52
CASHMERE	Leh	+ 0·13	+ 0·03	+ 0·01	— 0·02	+ 0·02	— 0·14	— 0·60	— 0·18	— 0·11	— 0·34	+ 0·19	— 0·06	— 1·07
PUNJAB	Peshawar	+ 0·61	— 0·53	— 0·75	— 1·28	— 0·41	— 0·26	+ 2·75	— 2·04	— 0·59	— 0·19	+ 1·25	— 0·41	— 1·85
	Kohat	— 0·09	— 1·08	— 0·38	— 0·27	— 1·15	— 0·70	+ 1·27	— 0·24	— 1·73	— 0·05	+ 0·98	— 0·56	— 4·00
	Bannu	+ 0·05	— 0·98	— 0·75	— 1·22	— 0·62	— 0·10	+ 1·49	— 1·71	— 0·60	— 0·15	— 0·06	— 0·40	— 5·05
	Dera Ismail Khan	— 0·13	— 0·70	— 0·64	— 0·38	+ 0·21	— 0·59	+ 0·23	— 0·76	— 0·33	+ 0·56	+ 0·68	— 0·35	— 2·20
	Dera Ghazi Khan	+ 0·17	— 0·36	— 0·65	— 0·37	— 0·43	+ 0·03	— 2·02	— 1·30	— 0·35	— 0·07	— 0·12	— 0·31	— 5·78
	Muzaffargarh	+ 0·03	— 0·27	— 0·31	— 0·35	— 0·22	— 0·33	+ 1·97	— 1·48	— 0·67	— 0·10	— 0·07	— 0·30	— 2·18
	Mooltan	+ 0·68	— 0·30	— 0·30	— 0·37	+ 1·13	— 0·33	+ 1·29	— 1·23	+ 1·16	— 0·12	— 0·03	— 0·27	+ 1·29
	Jhang	+ 0·60	— 0·44	— 0·83	— 0·50	+ 0·42	— 0·32	— 1·47	— 2·03	— 0·79	— 0·21	— 0·03	— 0·37	— 6·04
	Montgomery	+ 0·61	— 0·68	— 0·57	— 0·25	+ 1·45	— 0·17	— 1·02	— 0·78	+ 2·63	— 0·17	+ 0·14	— 0·27	+ 0·94
	Shapur	+ 1·90	— 1·11	— 0·89	— 0·60	— 0·33	— 1·21	+ 5·37	— 1·26	— 1·70	— 0·18	+ 1·15	— 0·41	+ 0·73
	Rawalpindi	+ 4·28	— 1·26	+ 0·20	— 1·99	+ 0·66	— 1·37	— 2·22	— 2·85	— 2·91	+ 0·21	+ 2·47	— 0·67	+ 0·13
	Jhelum	+ 2·42	— 1·08	+ 0·91	— 0·13	+ 1·97	+ 1·82	— 0·59	— 3·46	+ 0·90	— 0·49	+ 3·92	— 0·61	+ 5·56
	Gujrat	+ 2·47	— 1·10	— 1·32	— 0·73	+ 0·55	+ 0·66	— 6·20	— 3·63	+ 2·24	— 0·52	+ 4·24	— 0·73	— 4·07
	Sialkot	+ 1·52	— 1·68	— 0·79	— 1·54	+ 0·07	— 2·51	— 3·47	— 1·18	+ 1·55	— 0·57	+ 0·69	— 0·70	— 8·61
	Gujranwala	+ 2·01	— 1·38	— 0·53	— 0·61	— 0·02	— 1·58	— 0·12	— 3·02	+ 5·19	— 0·54	+ 2·67	— 0·64	+ 1·37
	Gurdaspur	+ 1·37	— 1·81	— 1·49	— 0·52	— 0·47	— 2·99	— 6·69	— 2·42	+ 2·89	— 0·64	— 0·12	— 0·96	— 13·85
	Lahore	+ 1·77	— 0·83	— 0·65	— 0·41	+ 2·18	— 1·13	— 4·98	— 3·98	+ 8·23	— 0·53	+ 0·50	— 0·41	— 0·26
	Amritsar	+ 1·63	— 1·20	— 0·53	— 0·08	+ 0·44	— 2·26	— 2·44	— 2·53	+ 4·92	— 0·59	+ 0·93	— 0·70	— 2·32
	Ferozepore	+ 0·81	— 0·83	— 0·68	+ 0·28	— 0·12	— 2·25	— 4·35	— 5·00	+ 6·58	— 0·60	+ 0·54	— 0·51	— 6·13
	Jullunder	+ 1·56	— 1·17	— 0·68	— 0·53	— 0·30	— 2·07	— 7·38	— 6·17	+ 2·12	— 0·51	— 0·10	+ 0·66	— 15·17
	Hoshiarpur	+ 1·80	— 1·71	— 1·43	— 0·71	— 0·41	— 3·10	— 7·35	— 6·49	+ 5·34	— 0·34	+ 0·12	— 0·99	— 15·21
	Ludhiana	+ 2·19	— 0·87	— 0·74	— 0·84	— 0·21	— 0·81	+ 2·91	— 6·19	+ 8·83	— 1·17	+ 0·62	— 0·12	+ 3·60
	Umballa	+ 0·84	— 1·59	— 0·81	— 0·67	+ 0·38	— 2·73	— 5·35	— 7·58	+ 0·93	— 0·54	+ 1·66	— 0·58	— 16·04
	Sirsa	+ 1·30	— 0·33	+ 1·06	— 0·38	+ 1·20	— 0·93	— 0·43	— 3·56	+ 5·02	— 0·19	+ 0·18	— 0·36	+ 2·58
	Hissar	+ 1·32	— 0·47	+ 0·62	— 0·28	+ 0·72	— 1·23	— 0·50	— 3·83	+ 0·16	— 0·12	+ 0·13	— 0·36	— 3·84
	Rohtak	+ 0·04	— 0·61	— 0·23	— 0·29	+ 0·44	— 1·08	— 2·11	— 4·26	+ 2·27	— 0·37	+ 0·27	— 0·37	— 6·30
	Delhi	+ 0·89	— 0·55	+ 1·00	— 0·24	+ 0·01	+ 0·50	— 6·07	— 6·69	+ 2·13	— 0·52	+ 0·01	— 0·34	— 9·87
	Gurgaon	— 0·03	— 0·33	+ 0·63	— 0·18	— 0·38	+ 0·65	— 2·89	— 6·53	+ 2·51	— 0·46	— 0·03	— 0·30	— 7·34
	Karnal	+ 1·66	— 1·22	+ 0·43	— 0·42	+ 0·69	— 1·11	— 6·01	— 5·46	+ 3 92	— 0·39	— 0·66	— 0·01	— 7·89
	Abbottabad	+ 4·07	— 0·96	— 3·37	— 0·90	+ 6·57	— 2·04	— 0·30	— 5·02	+ 0·35	— 0·75	+ 2·78	— 1·50	+ 1·92
	Murree	+ 4·38	— 2·31	+ 0·13	— 2·85	+ 1·14	— 2·26	— 3·53	— 7·20	+ 2·67	— 1·00	+ 3·23	— 0·85	— 7·41
	Dharmsala	+ 2·28	— 3·36	— 2·23	— 1·37	— 0·98	— 3·44	— 15·74	— 13·98	+ 1·01	— 1·63	+ 1·81	— 1·73	— 39·40
	Simla	+ 2·14	— 2·3	— 0·13	— 2·11	+ 6·20	— 0·82	— 5·42	— 1·66	— 0·37	— 0·31	+ 4·67	— 0·76	— 0·28
RAJPUTANA	Bickaneer	+ 0·29	— 0·28	— 0·0	— 0·26	+ 1·82	— 1·77	+ 0·30	— 3·17	+ 0·12	— 0·02	+ 0·54	— 0·02	— 2·49
	Ulwar	+ 0·42	— 0·48	+ 0·66	— 0·04	— 0·21	— 1·89	+ 0·55	— 6·02	+ 2·73	— 1·23	— 0·18	— 0·41	— 6·72
	Bhurtpore	+ 1·61	— 0·22	+ 0·10	— 0·16	— 0·3	+ 0·47	— 3·31	— 6·44	+ 1·28	— 0·39	+ 0·03	— 0·25	— 7 85

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883 with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
RAJPUTANA—*contd.*	Jeypore	+ 0·98	— 0·19	+ 0·01	— 0·24	+ 1·33	— 0·35	— 2·23	— 4·71	+ 4·99	+ 0·11	— 0·09	— 0·45	— 0·84
	Sambhar	+ 0·19	— 0·12	— 0·22	— 0·17	+ 1·25	— 0·82	+ 1·50	— 4·44	— 1·04	— 0·64	— 0·21	— 0·38	— 5·10
	Beawar	+ 0·07	— 0·14	— 0·17	— 0·11	+ 0·73	— 1·49	— 2·83	— 5·68	+ 2·29	— 0·02	— 0·16	— 0·21	— 7·72
	Pachbudra	— 0·14	— 0·05	+ 0·19	— 0·01	+ 0·77	— 0·30	— 1·41	— 3·99	+ 1·95	+ 0·01	+ 0·03	— 0·07	— 3·02
	Jodhpore	+ 0·39	— 0·10	+ 0·16	— 0·02	+ 1·56	— 0·53	— 1·28	— 5·19	+ 1·33	+ 2·30	— 0·05	— 0·04	— 1·47
	Ajmere	+ 0·18	— 0·34	— 0·41	— 0·11	+ 1·48	— 1·20	+ 2·16	— 6·92	+ 0·57	— 0·26	— 0·13	— 0·29	— 5·27
	Nusseerabad	+ 0·15	— 0·46	— 0·11	— 0·04	+ 1·85	— 0·02	— 1·31	— 4·02	+ 0·12	+ 0·18	— 0·13	— 0·27	— 4·06
	Tonk	+ 0·45	— 0·27	— 0·20	— 0·05	+ 1·84	+ 0·33	— 4·94	— 4·43	+ 1·89	— 0·37	0	— 0·14	— 5·89
	Deoli	+ 0·02	— 0·13	+ 0·92	— 0·19	+ 1·17	— 0·78	— 4·15	— 8·99	— 1·99	— 0·55	— 0·14	— 0·18	— 14·99
	Kotah	+ 0·41	— 0·31	+ 0·37	0	+ 0·71	+ 1·59	— 5·65	— 3·97	+ 4·98	— 0·34	— 0·01	— 0·23	— 2·45
	Jhalrapatam	+ 0·49	— 0·46	+ 0·20	— 0·01	+ 0·58	+ 2·30	— 11·64	— 3·74	+ 8·02	— 0·30	— 0·10	— 0·38	— 5·04
	Kotra	+ 0·11	— 0·24	+ 0·22	— 0·03	+ 2·09	— 0·14	+ 1·60	— 6·93	+ 6·28	+ 0·42	— 0·10	— 0·10	+ 3·18
	Oodeypore	?	?	— 0·04	0	+ 1·29	— 0·44	— 3·30	— 2·72	+ 1·07	— 0·37	0	— 0·06	?
	Kherwara	+ 0·16	— 0·18	— 0·04	— 0·03	+ 5·58	— 0·69	— 0·36	— 5·69	— 2·02	— 0·21	— 0·04	— 0·08	— 3·60
	Banswara	+ 0·12	— 0·19	0	0	+ 3·15	— 1·29	— 2·45	— 5·03	— 4·37	+ 0·39	0	— 0·51	— 10·18
	Mount Abu	+ 0·25	— 0·40	+ 0·21	— 0·05	+ 3·88	— 1·92	+ 3·51	— 22·11	+ 3·52	— 0·16	— 0·16	— 0·25	— 13·68
	Erinpura	+ 0·23	— 0·30	— 0·02	— 0·04	+ 1·70	+ 0·16	— 0·60	— 4·18	+ 3·18	+ 2·11	— 0·10	— 0·15	+ 1·99
	Shahpoora	+ 0·43	— 0·25	+ 0·13	— 0·04	+ 4·08	— 1·09	— 1·78	— 6·31	+ 5·49	— 0·60	— 0·06	— 0·19	— 0·19
	Partabgarh	+ 0·41	— 0·14	— 0·05	0	+ 1·41	+ 1·73	— 5·75	+ 1·83	+ 1·67	+ 0·47	0	— 0·05	+ 1·53
CENTRAL INDIA	Neemuch	+ 0·18	— 0·17	+ 0·18	— 0·10	+ 2·16	— 0·29	— 7·59	— 3·91	+ 5·09	+ 0·39	— 0·03	— 0·24	— 4·33
	Sirdarpore	— 0·18	— 0·28	— 0·02	— 0·01	+ 0·23	— 1·51	+ 1·56	— 4·44	+ 0·25	+ 0·86	— 0·10	— 0·15	— 3·79
	Agar	+ 0·38	— 0·38	— 0·04	— 0·04	+ 2·18	+ 2·61	— 3·42	— 4·70	+ 4·13	+ 2·55	— 0·07	— 0·32	+ 2·88
	Rutlam	+ 0·39	— 0·27	— 0·01	0	+ 1·90	+ 3·25	+ 1·74	— 3·26	+ 1·59	+ 0·47	— 0·01	— 0·13	+ 5·66
	Indore	— 0·16	— 0·29	— 0·02	— 0·13	— 0·05	+ 0·38	— 3·10	— 4·05	— 4·20	+ 1·41	— 0·17	— 0·14	— 10·52
	Bhopal	— 0·07	— 0·16	— 0·07	— 0·01	+ 1·14	+ 2·89	— 5·05	— 5·33	+ 7·09	+ 0·77	— 0·30	— 0·21	+ 0·66
	Goona	+ 0·95	— 0·21	— 0·18	— 0·06	+ 0·46	— 0·14	— 8·33	— 9·29	+ 10·38	+ 0·28	— 0·35	— 0·06	— 6·54
	Morar	+ 1·27	— 0·26	+ 0·41	— 0·13	+ 1·41	— 1·77	— 4·30	— 3·67	— 2·74	— 0·42	— 0·02	— 0·35	— 10·57
	Nowgong	+ 0·93	— 0·26	— 0·13	— 0·11	+ 0·63	— 0·70	— 2·56	— 9·73	— 2·06	— 0·12	— 0·08	— 0·15	— 14·34
	Sutna	+ 0·65	— 0·61	— 0·06	— 0·07	+ 0·12	— 0·64	+ 0·48	— 6·55	+ 6·29	— 0·94	— 0·22	— 0·06	— 1·61
	Nagode	+ 1·25	— 0·38	— 0·22	— 0·22	+ 0·57	+ 0·42	— 0·99	— 6·54	+ 0·86	— 1·15	— 0·14	— 0·21	— 6·75
	Maihar	+ 1·95	— 0·42	— 0·32	— 0·02	+ 0·22	— 4·04	— 1·09	— 5·90	— 0·46	— 1·08	— 0·76	— 0·04	— 12·16
	Rewah	+ 0·55	— 1·03	— 0·02	— 0·29	— 0·45	— 7·42	— 4·96	— 8·42	+ 0·86	— 1·47	— 0·28	— 0·03	— 22·96
	Chandia	?	?	?	?	?	?	?	— 7·76	+ 2·18	— 0·51	— 0·60	0	?
	Ramnagar	?	?	?	?	?	?	?	— 5·29	+ 3·78	— 1·89	— 0·35	0	?
	Sihawal	?	?	?	?	?	?	?	— 9·59	+ 0·22	— 1·15	— 0·55	0	?
N.-W. PROVINCES	Chakrata	+ 3·75	— 2·21	— 1·20	— 0·90	+ 0·72	+ 1·17	— 1·75	— 1·05	— 0·15	— 0·47	+ 0·53	— 0·78	— 2·34
	Mussooree	+ 0·15	— 2·44	— 0·55	— 0·94	— 1·16	— 0·95	— 3·45	— 15·19	+ 1·67	— 0·96	+ 2·91	— 0·76	— 21·67
	Ranikhet	+ 0·91	— 2·29	+ 2·42	— 1·09	+ 0·44	— 3·85	— 7·05	— 2·62	+ 0·97	— 0·54	+ 0·93	— 0·75	— 12·52
	Naini Tal	+ 6·71	— 2·35	+ 3·09	— 1·25	+ 3·51	— 4·04	+ 3·21	— 6·58	— 5·18	— 1·60	+ 0·50	— 1·29	— 5·27
	Almora	+ 1·72	— 1·28	+ 1·07	— 0·93	+ 0·91	— 3·87	— 4·03	— 2·62	— 0·51	— 0·86	+ 0·10	— 0·62	— 10·92
	Dehra Dun	+ 3·85	— 1·93	+ 0·29	— 0·41	— 0·19	+ 5·41	— 7·70	— 9·00	— 2·58	— 0·71	+ 1·39	— 0·41	— 11·99

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883 with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
N.-W. PROVINCES—*contd.*	Saharanpur	+ 2·35	— 1·46	+ 1·00	— 0·16	+ 0·66	+ 0·57	— 7·73	— 8·41	+ 0·63	— 0·44	+ 0·86	— 0·37	— 12·50
	Roorkee	+ 3·37	— 1·54	+ 0·41	— 0·05	— 0·01	+ 4·54	— 2·07	— 5·49	— 0·11	— 0·63	+ 0·45	— 0·32	— 1·45
	Muzaffarnagar	+ 2·25	— 0·92	+ 0·56	— 0·43	+ 1·18	+ 2·68	— 6·52	— 7·60	— 0·51	— 0·38	+ 0·48	— 0·31	— 9·52
	Meerut	+ 1·63	— 0·79	+ 0·34	— 0·43	— 0·35	— 1·42	— 4·80	— 5·68	+ 1·05	— 0·42	+ 0·09	— 0·31	— 11·09
	Bulandshahr	+ 2·00	— 0·88	+ 0·51	— 0·27	+ 1·72	+ 0·93	— 2·82	— 5·75	+ 1·36	— 0·54	— 0·05	— 0·41	— 4·20
	Aligarh	+ 2·09	— 0·50	+ 0·23	+ 0·09	+ 0·65	+ 2·38	— 0·74	— 5·60	— 2·96	— 0·48	— 0·02	— 0·30	— 5·16
	Bijnor	+ 1·49	— 1·16	+ 0·14	— 0·50	— 0·22	+ 1·04	— 4·89	— 4·19	— 1·66	— 0·47	— 0·07	— 0·33	— 10·82
	Moradabad	+ 3·13	— 1·07	+ 0·04	— 0·36	+ 0·36	— 2·42	+ 3·10	— 1·91	— 1·78	— 0·65	— 0·12	— 0·36	— 2·04
	Bareilly	+ 1·83	— 0·81	+ 1·37	— 0·13	+ 0·72	— 4·69	— 5·66	— 4·99	— 3·43	— 1·16	— 0·02	— 0·22	— 17·19
	Budaun	+ 1·53	— 0·57	+ 0·24	— 0·13	+ 0·26	— 2·93	— 6·00	— 5·51	— 1·65	— 0·74	— 0·06	— 0·28	— 15·84
	Shahjahanpur	+ 1·60	— 0·70	+ 0·23	— 0·19	— 0·10	— 1·24	— 4·23	— 1·53	— 4·29	— 1·16	— 0·09	— 0·29	— 11·99
	Muttra	+ 2·55	— 0·33	— 0·08	— 0·20	+ 0·72	+ 0·65	— 1·62	— 6·28	— 2·78	— 0·43	— 0·01	— 0·27	— 8·08
	Agra	+ 1·42	— 0·30	— 0·13	— 0·10	— 0·20	— 1·60	+ 3·02	— 6·21	— 0·70	— 0·33	— 0·03	— 0·24	— 5·40
	Mainpuri	+ 1·54	— 0·30	+ 0·30	— 0·13	+ 0·57	— 1·83	— 1·68	— 6·72	+ 5·04	— 0·67	— 0·05	— 0·37	— 4·30
	Farrukhabad	+ 1·63	— 0·31	+ 0·04	— 0·08	+ 0·13	— 2·04	— 2·61	— 0·66	— 0·80	— 1·03	— 0·05	— 0·30	— 6·08
	Etawah	+ 1·50	— 0·21	+ 0·25	— 0·15	— 0·04	— 1·76	+ 1·39	— 6·29	+ 1·17	— 1·01	— 0·09	— 0·24	— 5·48
	Etah	+ 1·89	— 0·22	— 0·33	— 0·11	+ 0·74	— 0·57	— 4·28	— 5·24	+ 2·20	— 0·70	— 0·02	— 0·25	— 6·89
	Cawnpur	+ 2·37	— 0·36	+ 0·85	— 0·14	— 0·43	— 2·55	— 0·07	— 3·96	— 2·16	— 1·01	— 0·07	— 0·16	— 7·69
	Fatehpur	+ 2·59	+ 0·01	— 0·14	— 0·17	+ 1·00	+ 1·58	+ 14·15	— 6·73	— 0·75	— 1·27	— 0·10	— 0·12	+ 10·05
	Banda	+ 2·41	— 0·32	— 0·28	— 0·12	+ 1·24	+ 2·26	+ 3·37	— 4·82	— 2·39	— 1·02	— 0·23	— 0·12	— 0·02
	Allahabad	+ 1·90	— 0·42	— 0·05	— 0·15	+ 0·01	— 0·59	+ 1·39	— 7·51	— 1·92	— 1·40	— 0·24	— 0·11	— 9·09
	Hamirpur	+ 1·32	— 0·18	— 0·08	— 0·09	— 0·25	— 1·43	+ 3·50	— 6·70	+ 2·30	— 0·77	— 0·14	— 0·22	— 2·74
	Jaunpur	+ 2·32	— 0·31	+ 0·05	— 0·14	— 0·71	+ 0·84	— 0·08	— 7·77	— 0·33	— 3·01	— 0·10	— 0·08	— 9·38
	Azamgarh	+ 2·50	— 0·36	— 0·23	— 0·18	— 0·73	+ 1·08	+ 1·47	— 6·54	— 4·10	— 2·42	— 0·10	— 0·11	— 9·72
	Mirzapur	+ 1·94	— 0·69	— 0·32	— 0·14	+ 0·13	— 3·27	— 2·87	— 5·91	— 2·28	— 0·76	— 0·28	— 0·10	— 14·55
	Dudhi	+ 1·00	— 0·48	+ 0·74	— 0·27	— 0·75	+ 1·26	— 2·09	— 4·82	— 0·54	— 2·99	+ 0·01	— 0·03	— 8·96
	Robertsganj	+ 1·46	— 0·56	+ 0·21	— 0·27	— 0·87	— 3·16	— 7·23	— 6·73	— 1·99	— 2·13	— 0·23	— 0·13	— 21·63
	Benares	+ 1·50	— 0·41	+ 0·24	— 0·17	+ 0·02	+ 0·23	+ 1·85	— 5·24	— 2·96	— 0·74	— 0·15	— 0·06	— 5·89
	Gorakhpur	+ 2·82	— 0·49	— 0·11	+ 0·43	— 1·24	+ 3·25	— 5·34	— 7·04	— 7·23	— 2·85	— 0·18	— 0·09	— 18·07
	Basti	+ 2·39	— 0·50	— 0·13	— 0·24	— 1·28	+ 0·57	— 0·60	— 6·62	— 3·49	— 2·22	— 0·01	— 0·11	— 12·24
	Ghazipur	+ 0·87	— 0·57	— 0·33	— 0·14	— 0·53	+ 0·73	+ 3·17	— 5·05	— 2·23	— 2·01	— 0·32	— 0·07	— 6·48
	Jalaun	+ 1·37	— 0·10	— 0·11	— 0·07	+ 0·55	— 1·83	+ 1·56	— 5·93	+ 1·17	— 0·67	— 0·02	— 0·20	— 4·28
	Jhansi	+ 1·46	— 0·21	— 0·11	— 0·13	+ 0·83	— 0·70	— 6·50	— 8·52	— 2·23	— 0·17	— 0·02	— 0·12	— 16·42
	Lalitpur	+ 0·60	— 0·24	— 0·26	— 0·14	+ 0·62	— 2·15	— 7·11	— 7·66	+ 1·62	— 0·73	— 0·08	— 0·18	— 14·25
	Srinagar	+ 2·21	— 0·16	+ 0·56	— 0·72	— 0·32	— 2·70	— 2·28	— 1·59	— 0·26	— 0·49	— 1·98	— 0·61	— 7·38
	Pithoragarh	?	?	?	?	+ 1·43	— 2·87	— 3·10	— 5·23	+ 0·62	— 0·07	+ 0·12	+ 0·05	?
	Pauri	+ 1·04	— 2·87	+ 1·11	— 0·95	+ 0·57	— 2·06	— 4·31	— 5·20	— 2·81	— 0·57	— 1·18	— 0·56	— 15·43
	Rudarpur	+ 2·71	— 1·28	+ 0·26	— 0·28	+ 0·52	+ 0·81	— 1·00	— 5·22	— 1·64	— 0·86	— 0·06	— 0·38	— 6·42
OUDH	Lucknow	+ 3·80	— 0·29	+ 0·52	— 0·14	— 0·51	— 0·70	+ 8·15	— 6·90	— 2·82	— 1·29	— 0·01	— 0·34	— 0·53
	Unao	+ 2·57	— 0·25	+ 0·03	— 0·13	— 0·39	— 3·72	+ 4·21	— 6·41	+ 0·42	— 1·48	— 0·01	— 0·28	— 5·44
	Nawabganj	+ 4·40	— 0·31	+ 0·38	— 0·26	+ 0·27	+ 2·74	+ 1·04	— 6·41	— 2·21	— 0·93	0	— 0·42	— 1·71

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Sitapur	+ 3·32	— 0·45	+ 0·39	— 0·31	+ 1·33	— 3·14	+ 1·43	— 8·10	— 2·89	— 1·61	+ 0·01	— 0·20	— 10·22
	Hardoi	+ 2·25	— 0·32	— 0·19	— 0·22	— 0·37	— 2·63	+ 4·60	— 4·39	— 0·74	— 1·75	0	— 0·44	— 4·20
	Kheri	+ 3·50	— 0·86	— 0·24	— 0·14	+ 1·49	— 2·43	+ 2·07	— 7·06	— 4·59	— 1·65	0	— 0·32	— 10·23
	Fyzabad	+ 3·17	— 0·41	— 0·21	— 0·26	+ 0·04	— 0·77	— 3·92	— 4·36	— 4·99	— 1·57	— 0·03	— 0·09	— 13·40
OUDH—*contd.*	Bahraich	+ 1·28	— 0·97	— 0·34	— 0·14	— 1·01	+ 0·38	+ 1·49	— 7·68	— 4·74	— 1·63	— 0·04	— 0·32	— 13·72
	Gonda	+ 3·36	— 0·50	+ 0·16	— 0·09	— 0·63	— 0·03	+ 1·77	— 4·70	— 1·79	— 1·43	— 0·05	— 0·16	— 4·09
	Rai Bareli	+ 2·19	— 0·15	— 0·10	— 0·14	— 0·18	— 1·96	— 0·85	— 4·48	+ 2·88	— 1·03	— 0·02	— 0·12	— 3·96
	Sultanpur	+ 2·47	— 0·14	— 0·11	— 0·24	— 0·80	— 1·13	+ 1·12	— 6·50	— 4·16	— 1·62	— 0·04	— 0·11	— 11·26
	Partabgarh	+ 1·45	— 0·31	— 0·01	— 0·07	+ 0·07	— 3·45	— 1·29	— 5·69	— 2·36	— 1·83	— 0·06	— 0·10	— 13·65
NEPAL	Katmandu	+ 4·64	— 1·16	— 0·72	0	— 0·38	— 1·64	+ 0·71	+ 4·35	— 0·58	— 2·19	— 0·20	+ 0·33	+ 3·16
	Burdwan	— 0·19	— 0·12	+ 2·97	+ 1·50	+ 1·85	+ 2·04	+ 9·42	+ 1·68	— 6·24	— 4·22	— 0·58	+ 1·01	+ 9·12
	Bankoora	+ 0·12	— 0·71	+ 0·56	— 0·45	— 0·83	— 2·72	+ 6·18	+ 1·20	— 3·46	— 4·61	— 0·32	+ 1·29	— 3·65
	Soory	— 0·19	— 1·04	+ 1·12	— 0·02	+ 1·68	+ 8·37	+ 6·69	+ 3·90	— 5·78	— 3·72	+ 0·03	+ 0·63	+ 11·67
	Midnapore	+ 2·33	— 0·35	+ 0·43	+ 1·48	— 3·98	— 3·01	— 2·01	+ 5·21	— 4·13	— 4·83	— 0·38	+ 0·75	— 8·49
	Tumlook	— 0·40	+ 0·71	+ 0·48	— 0·36	— 2·94	— 1·38	+ 5·00	+ 1·77	— 4·76	— 3·47	— 0·26	+ 1·73	— 3·88
	Hooghly	— 0·3	— 0·66	— 0·89	+ 1·64	— 2·04	— 1·79	+ 8·70	— 3·34	— 4·49	— 1·37	— 0·35	+ 1·56	— 3·34
	Howrah	— 0·28	+ 0·53	— 1·30	+ 1·40	— 3·52	— 2·09	+ 1·96	— 5·09	— 4·75	— 3·98	— 0·34	+ 2·14	— 15·32
	Saugor Island	— 0·31	+ 0·27	+ 0·35	+ 1·51	— 1·35	+ 1·34	+ 5·10	— 5·77	— 0·71	— 8·92	— 0·75	+ 2·00	— 7·24
	Alipore (Jail)	— 0·52	+ 0·35	— 0·30	+ 1·11	— 4·09	— 0·54	+ 2·94	— 5·92	— 3·77	— 3·84	— 0·37	+ 2·95	— 12·00
	Alipore (Obsy.)	+ 0·03	+ 0·56	+ 0·39	+ 1·12	— 4·66	+ 0·78	+ 2·83	— 5·01	— 2·07	— 2·64	— 0·41	+ 1·64	— 7·42
	Calcutta (Chowringhee, St. Xavier's College).	— 0·40	+ 1·23	— 0·13	+ 0·81	— 3·86	+ 3·07	+ 3·34	— 4·99	— 4·45	— 4·24	— 0·6	+ 2·41	— 7·72
	Buseerhat	— 0·38	+ 1·03	— 1·51	+ 2·01	— 3·35	+ 13·34	+ 10·22	— 1·30	— 3·05	— 4·13	— 0·44	+ 2·49	+ 4·94
	Kishnaghur	— 0·46	— 0·99	— 0·25	— 1·47	— 2·74	— 6·21	— 1·69	— 6·54	— 4·67	— 2·42	— 0·43	+ 0·07	— 27·80
	Jessore	— 0·04	— 0·17	+ 0·16	+ 0·82	— 3·90	— 6·49	+ 2·72	— 3·81	— 3·19	— 4·49	— 0·92	+ 2·14	— 17·08
BENGAL	Khoolna	— 0·60	— 0·42	+ 1·04	+ 0·12	— 3·94	— 0·05	— 2·26	— 5·74	— 1·24	— 4·39	— 0·5	+ 2·94	— 15·05
	Berhampore	— 0·32	— 1·00	+ 0·39	— 1·68	+ 1·73	— 1·47	— 0·55	— 1·68	— 6·73	— 5·24	— 0·31	+ 0·96	— 15·70
	Dinagepore	+ 0·56	— 0·65	— 0·77	+ 0·09	+ 2·65	— 4·67	— 7·77	+ 0·77	— 5·62	— 5·12	— 0·24	+ 0·47	— 20·30
	Maldah	— 0·22	— 0·71	— 0·65	— 0·62	— 0·37	— 0·34	+ 0·05	— 3·72	— 7·25	— 4·24	— 0·24	+ 1·55	— 16·76
	Beauleah	+ 0·06	— 0·99	+ 0·62	— 1·46	— 0·99	— 4·30	— 5·98	— 3·49	— 7·16	— 5·75	— 0·31	+ 1·00	— 26·75
	Rungpore	+ 0·11	— 0·36	— 0·96	+ 4·48	+ 0·80	— 11·17	— 10·74	+ 0·54	— 4·75	— 5·20	— 0·32	+ 0·20	— 27·37
	Bogra	+ 0·11	— 0·97	— 0·58	— 0·64	— 1·84	— 7·98	— 0·56	— 4·07	— 9·26	— 4·74	— 0·90	+ 0·65	— 30·28
	Pubna	+ 0·10	— 1·27	— 1·25	— 1·25	+ 3·96	— 2·39	— 2·30	— 8·56	— 7·83	— 3·16	— 0·35	+ 1·12	— 23·18
	Darjeeling	+ 1·12	— 0·61	— 2·35	— 1·58	+ 0·68	+ 14·27	— 10·60	+ 4·66	— 6·60	— 5·82	— 0·21	— 0·06	— 7·10
	Monrpoo	+ 0·98	— 0·57	— 1·89	— 0·67	+ 2·94	+ 9·88	— 9·03	+ 1·68	— 8·48	— 4·82	— 0·13	— 0·03	— 10·14
	Julpigoree	+ 0·87	— 0·27	— 1·79	+ 0·04	— 2·43	+ 3·84	— 1·46	+ 13·11	+ 6·00	— 4·88	— 0·13	— 0·08	+ 12·82
	Baxa	+ 0·61	— 0·81	— 1·42	+ 0·69	+ 7·38	— 6·09	— 12·81	+ 3·28	— 2·67	— 6·18	— 0·38	+ 1·36	— 10·86
	Cooch Behar	— 0·21	— 0·34	— 1·23	+ 1·27	+ 0·61	— 9·61	— 0·87	+ 13·04	+ 5·28	— 4·99	— 0·05	— 0·10	+ 2·80
	Dacca	— 0·03	— 0·84	— 1·37	— 0·04	— 2·21	— 4·44	+ 6·08	— 4·93	— 6·54	— 3·70	— 0·68	+ 1·36	— 17·36
	Fureedpore	+ 0·29	— 0·95	+ 2·17	+ 0·74	+ 0·72	— 7·46	+ 1·27	— 2·3	— 5·60	— 4·12	— 0·54	+ 1·19	— 14·60

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
BENGAL—*contd.*	Burrisal	— 0·58	+ 0·72	+ 4·15	+ 0·52	+ 1·92	— 4·14	— 3·75	— 3·90	— 3·62	— 0·99	— 0·81	+ 2·97	— 7·51
	Mymensingh	+ 0·11	— 1·05	— 1·62	— 0·79	— 1·67	— 11·32	— 6·13	— 3·51	— 6·47	— 4·67	— 0·84	+ 0·64	— 37·32
	Atia	— 0·17	— 1·15	— 0·86	+ 1·96	+ 2·71	— 5·52	+ 6·14	— 2·37	— 7·71	— 5·12	— 0·29	+ 1·08	— 11·30
	Kishorgunj	— 0·60	— 0·98	— 2·79	+ 4·16	+ 5·13	— 11·40	+ 2·50	+ 5·30	— 11·11	— 1·90	— 0·45	+ 1·22	— 10·92
	Chittagong	— 0·46	— 0·34	+ 1·37	— 0·77	+ 10·10	+ 14·48	+ 2·29	— 4·21	+ 1·76	— 2·15	— 1·38	+ 7·85	+ 28·54
	Cox's Bazar	— 0·47	— 0·31	+ 3·52	— 0·09	+ 0·28	+ 13·33	— 7·44	+ 6·38	+ 2·03	— 3·72	— 1·18	+ 0·55	+ 12·88
	Demagiri	— 0·54	— 0·96	+ 2·29	— 0·43	+ 8·82	— 0·24	— 2·06	+ 20·88	— 4·74	— 7·11	— 0·95	+ 4·07	+ 19·03
	Noakholly	— 0·47	+ 0·55	+ 8·13	+ 2·15	— 2·03	+ 11·54	+ 4·74	+ 1·61	+ 2·98	— 4·21	— 1·48	+ 7·42	+ 30·93
	Tipperah	— 0·45	— 0·38	+ 0·89	+ 0·71	— 1·63	+ 2·26	+ 3·92	— 3·47	— 1·97	— 2·71	— 1·34	+ 4·36	+ 0·19
	Rangamatia Hill.	— 0·43	— 0·66	+ 2·54	+ 1·22	+ 9·73	+ 0·12	— 7·96	+ 1·45	— 2·75	— 4·22	— 1·62	+ 5·72	+ 3·14
	Agartalla	— 0·48	— 1·13	— 3·49	+ 0·64	+ 2·74	+ 0·76	+ 2·20	— 4·25	— 1·92	— 2·15	— 0·97	+ 3·98	— 4·04
	Patna	+ 1·23	— 0·37	+ 0·04	— 0·15	— 1·45	+ 7·59	— 1·54	— 2·34	— 2·78	— 2·42	— 0·22	— 0·13	— 2·54
	Barh	+ 0·66	— 0·47	+ 0·05	— 0·09	— 2·11	+ 8·81	— 0·97	— 1·07	— 3·28	— 2·79	— 0·26	— 0·03	— 1·55
	Gya	+ 0·95	— 0·52	— 0·11	— 0·37	— 0·34	+ 8·11	+ 7·03	— 3·96	— 2·48	— 1·94	— 0·10	— 0·08	+ 6·19
	Arrah	+ 1·01	— 0·54	— 0·24	— 0·60	— 1·27	+ 4·72	— 4·21	— 4·69	— 4·36	— 2·19	— 0·23	— 0·06	— 12·66
	Sasseram	+ 1·00	— 0·66	+ 0·38	— 0·14	— 0·12	+ 2·01	— 3·74	— 8·41	+ 1·05	— 2·60	— 0·25	— 0·08	— 11·56
	Buxar	+ 0·66	— 0·37	+ 0·21	— 0·18	— 0·54	+ 2·75	+ 2·30	— 4·36	— 0·44	— 2·04	— 0·18	— 0·13	— 2·32
	Mozufferpore	+ 0·96	— 0·53	— 0·42	+ 0·21	— 1·31	+ 13·33	— 2·01	+ 1·88	— 3·27	— 2·86	— 0·09	— 0·04	+ 5·85
	Durbhanga	+ 0·44	— 0·44	— 0·28	+ 0·09	— 0·81	+ 10·90	— 5·46	— 0·08	— 6·30	— 2·57	— 0·08	— 0·11	— 5·26
	Chupra	+ 0·73	— 0·51	+ 0·11	— 0·38	— 1·24	+ 5·43	+ 5·99	— 4·37	— 3·44	— 2·36	— 0·22	— 0·03	— 0·27
	Sewan	+ 1·29	— 0·53	— 0·01	— 0·12	— 1·50	+ 0·04	+ 2·14	— 3·93	— 4·04	— 3·92	— 0·12	— 0·06	— 10·76
	Motiharee	+ 1·24	— 0·33	— 0·58	+ 0·11	+ 0·01	— 2·90	+ 0·26	+ 3·09	— 7·11	— 3·72	— 0·09	— 0·10	— 10·12
	Monghyr	+ 0·22	— 0·72	+ 0·44	— 0·21	— 0·51	+ 1·96	— 3·16	— 6·50	— 4·01	— 3·31	— 0·28	— 0·08	— 16·16
	Jamooee	+ 0·53	— 0·82	+ 0·12	— 0·60	— 1·89	+ 0·09	+ 1·97	— 1·63	— 1·46	— 1·37	— 0·09	— 0·04	— 5·19
	Bhagalpur	+ 0·04	— 0·63	+ 0·03	— 0·33	— 1·60	+ 6·26	— 3·20	+ 2·70	— 4·98	— 3·92	— 0·24	+ 0·18	— 5·69
	Muddehpoora	+ 0·25	— 0·64	— 0·11	— 0·08	— 0·95	+ 20·89	+ 0·22	— 4·66	— 5·89	— 4·53	— 0·07	— 0·06	+ 4·37
	Purneah	+ 0·58	— 0·66	— 0·30	— 0·25	— 0·72	— 1·82	— 5·18	— 5·28	— 8·90	— 3·87	— 0·09	— 0·07	— 26·56
	Kissengunge	+ 0·40	— 0·60	— 0·78	+ 1·78	— 2·36	+ 6·36	— 5·91	+ 1·03	— 5·01	— 3·28	— 0·06	— 0·02	— 8·45
	Nya Doomka	— 0·13	— 0·86	+ 0·30	— 1·14	— 1·91	+ 4·12	— 0·05	— 0·61	— 6·56	— 4·60	— 0·09	+ 0·75	— 10 78
	Godda	+ 0·95	— 0·76	+ 0·25	— 0·26	— 1·48	— 1·91	+ 1·16	— 4·12	— 1·47	— 2·70	— 0·11	+ 0·66	— 9·79
	Cuttack	— 0·40	— 0·29	+ 0·33	— 1·36	+ 1·87	+ 12·79	+ 1·55	— 2·80	+ 3·22	— 5·24	— 0·73	+ 0·48	+ 9·42
	Banki	— 0·03	+ 0·13	+ 0·07	— 0·17	— 1·01	+ 6·39	+ 1·23	+ 0·97	+ 5·29	— 2·69	— 0·63	+ 0·97	+ 10·50
	Barreepudda	— 0·27	+ 0·90	+ 0·59	+ 0·93	— 0·96	+ 1·59	— 0·91	+ 0·30	— 3·91	— 4·37	— 0·54	— 0·15	— 6·80
	Dhenkanal	— 0·01	+ 0·67	+ 0·25	+ 0·75	+ 0·59	+ 3·92	— 2·20	— 3·01	+ 1·91	— 3·38	— 0·49	— 0·03	— 1·03
	Angul	0	— 0·26	+ 0·54	+ 0·17	+ 1·67	+ 2·55	— 1·20	+ 0·16	— 2·67	+ 0·69	— 0·72	+ 0·57	+ 1·50
	Bispara	— 0·06	— 0·18	— 0·71	— 0·16	+ 0·48	+ 10·93	— 5·83	— 2·51	— 2·46	— 0·50	— 0·47	+ 0·11	— 1·36
	Kunjabangar	?	?	+ 0·57	— 4·36	— 3·20	+ 5·19	— 0·73	— 4·37	— 4·80	— 3·71	— 1·09	+ 0·17	?
	Talcher	— 0·38	+ 1·17	+ 0·26	+ 0·88	— 0·35	+ 9·04	— 7·78	+ 4·28	— 0·65	— 2·95	+ 0·44	— 0·07	+ 3·89
	Keonjhar	0	+ 0·13	+ 0·23	— 1·38	— 0·77	— 0·47	— 13·37	— 2·67	— 1·01	— 0·75	— 0·90	+ 0·10	— 20·86
	False Point	— 0·29	— 0·20	+ 1·19	— 2·47	— 0·79	+ 8·90	+ 1·13	+ 4·07	— 2·36	— 8·60	— 2·04	+ 2·27	+ 0·81

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
BENGAL—*concld.*	Pooree	— 0·20	— 0·76	+ 0·91	— 1·05	— 2·04	+ 10·32	+ 3·46	— 6·80	+ 3·68	— 3·29	— 0·46	+ 1·43	+ 5·20
	Balasore	— 0·76	+ 2·69	+ 0·27	— 1·51	+ 0·13	+ 7·77	+ 0·88	+ 2·86	— 8·79	— 5·51	— 1·20	+ 1·16	— 3·77
	Jellasore	— 0·89	+ 1·52	+ 1·12	+ 0·92	— 1·42	+ 7·87	+ 0·05	+ 0·31	— 4·76	— 3·90	— 0·45	— 0·05	+ 0·32
	Bhuddruck	— 0·35	— 0·85	+ 1·73	+ 0·36	— 1·98	+ 8·05	— 1·07	— 0·84	— 1·68	— 4·12	— 0·97	+ 0·79	— 0·93
	Hazaribagh	+ 0·63	— 0·66	+ 1·95	— 0·40	+ 0·01	— 1·17	+ 6·69	— 5·95	+ 3·76	— 3·01	+ 0·12	+ 0·23	+ 2·20
	Ranchee	— 0·24	— 1·04	+ 1·76	— 0·22	+ 0·19	+ 5·99	+ 8·31	— 1·74	+ 1·34	— 2·87	+ 1·78	+ 0·32	+ 13·58
	Palamow	+ 1·56	— 0·54	+ 1·39	0	— 0·66	— 0·89	— 2·97	— 3·57	+ 0·02	— 1·96	+ 1·09	— 0·23	— 6·76
	Sirguja	?	?	?	?	?	?	?	?	+ 4·85	0	+ 1·38	0	?
	Chybassa	+ 0·74	— 0·42	+ 2·26	+ 0·05	— 2·46	+ 0·03	+ 1·61	+ 3·68	— 1·87	— 2·52	— 0·14	+ 0·83	+ 1·79
	Purulia	— 0·03	— 0·68	+ 2·66	— 0·28	— 0·81	+ 4·62	+ 5·14	+ 4·07	+ 0·36	— 3·00	+ 0·83	+ 1·05	+ 13·93
	Gobindpur	+ 0·22	— 1·09	+ 0·42	— 0·53	— 0·10	— 0·93	— 1·82	— 4·55	— 1·25	— 4·31	+ 0·02	+ 0·42	— 13·50
ASSAM	Silchar	+ 0·57	— 2·48	+ 2·37	— 6·00	+ 35·81	— 4·15	— 4·30	+ 10·67	+ 3·92	— 2·56	+ 1·13	+ 6·61	+ 41·59
	Sibsagar	— 0·61	— 1·54	+ 1·39	— 6·63	— 1·35	— 6·99	+ 7·54	+ 0·28	+ 0·73	— 2·11	— 1·13	+ 0·75	— 8·45
	Sylhet	— 0·26	— 1·44	— 0·32	— 7·82	+ 14·66	— 7·83	— 6·21	+ 4·02	+ 2·16	— 5·81	— 1·18	+ 2·27	— 7·76
	Goalpara	+ 0·21	— 0·52	— 1·99	— 0·16	+ 8·35	— 14·49	— 8·41	+ 1·63	— 1·17	— 4·17	— 0·23	— 0·16	— 21·11
	Tura	— 0·20	— 0·79	— 1·81	+ 2·92	+ 5·53	— 3·24	— 13·67	— 0·87	— 15·57	— 7·62	— 0·39	+ 0·12	— 35·59
	Gauhati	+ 0·10	— 0·86	— 1·77	— 0·67	+ 7·89	— 3·78	— 5·84	— 2·48	— 3·40	+ 0·26	— 0·66	+ 1·21	— 10·00
	Kulsi	+ 0·32	— 0·52	— 2·20	+ 1·96	+ 2·68	+ 3·12	+ 4·58	— 6·33	— 2·81	— 6·21	— 0·09	+ 0·45	— 5·05
	Tezpur	— 0·64	— 0·90	— 0·83	— 2·90	+ 5·77	— 3·23	— 1·39	+ 2·98	— 0·97	— 2·93	— 0·93	+ 0·77	— 5·20
	Chardner	— 0·42	— 0·75	— 1·88	— 1·52	+ 5·57	— 1·48	+ 7·33	— 1·98	— 9·14	— 4·79	— 0·07	+ 0·44	— 8·69
	Nowgong	— 0·19	— 0·94	— 0·61	+ 0·18	+ 4·13	— 5·85	— 2·22	+ 4·07	— 4·30	— 2·21	— 0·53	+ 0·80	— 7·67
	Dibrugarh	+ 0·24	— 1·35	— 1·16	— 1·49	+ 1·54	— 3·95	+ 2·45	— 1·79	+ 1·46	— 3·69	— 1·16	— 0·37	— 9·27
	Shillong	+ 0·49	— 0·58	— 1·36	+ 0·70	+ 0·14	— 0·70	— 5·90	+ 0·07	— 4·88	— 3·08	— 0·94	+ 1·29	— 14·75
	Cherra Poonjee	+ 0·56	— 2·63	— 4·36	— 15·33	+ 15·86	— 29·21	— 55·04	— 13·56	+ 0·05	— 7·42	— 2·01	+ 2·89	— 110·20
	Kohima	+ 0·40	— 1·00	— 0·62	+ 0·15	+ 3·58	— 3·15	— 1·97	— 1·82	— 1·90	— 2·29	— 0·48	+ 3·31	— 5·79
	Dhubri	— 0·01	— 0·58	— 1·44	+ 0·52	— 0·96	— 14·18	— 11·69	+ 4·98	+ 0·14	— 2·61	— 0·03	— 0·13	— 25·99
CENTRAL PROVINCES.	Nagpur	— 0·22	— 0·42	— 0·29	— 0·45	— 0·56	+ 2·38	+ 2·27	+ 3·35	+ 7·80	+ 3·83	— 0·41	— 0·34	+ 16·94
	Bhandara	— 0·56	— 0·62	— 0·34	— 0·57	— 0·81	+ 11·12	— 5·97	+ 1·47	+ 8·85	+ 2·72	— 0·31	— 0·08	+ 14·90
	Chanda	0	— 0·81	— 0·60	— 0·73	— 2·39	+ 0·28	+ 5·33	+ 3·64	+ 1·92	+ 2·26	+ 0·27	— 0·17	+ 9·00
	Brahmapuri	— 0·37	— 0·15	— 0·21	— 0·38	— 0·85	+ 3·86	+ 4·29	— 1·92	+ 3·25	+ 1·13	— 0·35	— 0·25	+ 8·05
	Wardha	— 0·20	— 0·29	— 0·36	— 0·34	— 0·73	+ 8·12	— 0·26	+ 3·31	— 8·99	+ 5·27	— 0·16	— 0·12	+ 23·23
	Arvi	— 0·38	— 0·16	— 0·54	— 0·17	— 0·64	+ 2·82	+ 1·89	+ 6·81	+ 3·24	+ 1·47	— 0·32	— 0·29	+ 13·73
	Balaghat	+ 0·09	— 0·59	+ 0·77	— 0·54	— 0·55	— 2·08	— 1·12	— 9·55	+ 7·14	+ 0·56	— 0·41	— 0·15	— 6·43
	Sironcha	— 0·04	— 0·42	+ 0·36	— 0·05	— 1·44	+ 3·32	+ 1·45	+ 6·13	+ 4·44	— 1·61	— 0·27	— 0·06	+ 11·81
	Jubbulpore	— 0·01	— 0·46	— 0·29	— 0·24	— 0·15	+ 1·08	— 0·05	— 7·69	+ 4·12	+ 0·01	— 0·34	— 0·16	— 4·18
	Saugor	+ 0·13	— 0·53	— 0·19	— 0·19	+ 0·81	— 0·10	— 8·09	— 5·68	+ 0·08	— 0·69	— 0·39	— 0·28	— 15·12
	Damoh	+ 0·85	— 0·41	— 0·22	— 0·20	+ 0·60	+ 2·78	— 3·69	— 9·40	+ 3·72	+ 0·10	— 0·34	— 0·23	— 6·44
	Seoni	+ 0·47	— 0·92	— 0·45	— 0·60	— 0·67	+ 2·10	+ 3·82	— 3·37	+ 9·82	+ 1·31	— 0·38	— 0·47	+ 10·66
	Mandla	+ 0·27	— 0·55	— 0·33	— 0·54	+ 0·07	+ 3·66	— 6·01	— 6·22	+ 2·70	+ 0·08	— 0·26	— 0·19	— 6·66
	Badnur	— 0·40	— 0·32	— 0·69	— 0·31	— 0·44	+ 0·52	— 4·73	— 1·60	+ 1·53	+ 4·81	— 0·37	— 0·30	— 2·30
	Chhindwara	+ 0·54	— 0·32	— 0·49	— 0·29	+ 0·53	+ 13·78	+ 1·75	— 0·96	+ 3·06	+ 1·17	— 0·32	— 0·22	+ 18·23

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
CENTRAL PROVINCES —*contd.*	Hoshangabad	— 0·14	— 0·15	— 0·18	— 0·04	+ 0·06	+ 4·29	— 2·97	+ 2·57	+ 13·36	+ 2·34	— 0·39	— 0·26	+ 18·49
	Narsinghpur	— 0·03	— 0·32	— 0·25	— 0·27	+ 0·01	+ 1·72	— 1·88	— 5·70	+ 18·11	— 0·09	— 0·24	— 0·21	+ 10·85
	Khandwa	— 0·08	— 0·33	— 0·09	— 0·08	— 0·25	+ 1·94	+ 1·99	+ 1·11	— 1·36	+ 1·46	— 0·10	— 0·22	+ 3·99
	Pachmarhi	— 0·10	— 0·30	— 0·35	— 0·29	— 0·20	+ 0·91	— 8·56	— 7·02	+ 3·84	+ 2·38	— 0·46	— 0·29	— 10·44
	Raipur	— 0·11	— 0·22	+ 1·21	— 0·58	— 0·17	+ 5·84	— 3·07	— 5·25	+ 1·19	+ 0·02	— 0·15	— 0·14	— 1·43
	Dhamtari	— 0·12	— 0·32	+ 1·32	— 0·03	— 1·39	+ 2·65	+ 2·68	— 3·74	+ 5·83	— 0·55	+ 0·28	— 0·10	+ 6·41
	Sambalpur	— 0·51	— 0·41	+ 1·38	— 0·51	— 0·98	+ 8·25	+ 11·52	— 7·73	+ 6·37	— 2·43	+ 1·01	+ 0·82	+ 16·78
	Raigarh	?	?	?	?	?	— 3·25	— 4·43	— 9·03	+ 3·48	+ 0·38	+ 1·87	+ 0·69	?
	Sarangarh	0	— 0·04	— 0·72	— 0·34	+ 0·64	— 1·62	— 2·52	— 6·90	+ 5·53	— 2·46	— 0·30	0	— 8·73
	Bilaspur	+ 0·11	— 0·26	+ 0·33	— 0·82	+ 0·31	— 4·05	+ 0·06	— 8·38	+ 3·74	— 1·07	+ 1·01	— 0·21	— 9·23
	Saragaon	+ 0·29	— 0·12	— 0·37	— 0·51	— 0·32	— 0·69	— 6·35	— 6·50	+ 4·25	— 1·24	— 0·18	— 0·08	— 11·82
BERARS	Makhla	+ 0·08	— 0·36	— 0·20	— 0·02	+ 0·23	+ 1·22	+ 8·03	+ 0·66	+ 5·14	+ 4·38	— 0·51	0	+ 18·65
	Chikalda	— 0·38	— 0·08	— 0·40	— 0·12	+ 0·29	+ 0·67	+ 14·96	— 2·73	+ 5·79	+ 6·66	— 0·39	— 0·42	+ 23·85
	Ellichpur	— 0·42	— 0·10	— 0·43	— 0·21	— 0·31	+ 4·14	+ 6·64	+ 2·04	+ 2·23	+ 6·31	— 0·14	— 0·18	+ 19·57
	Amraoti	— 0·39	— 0·21	— 0·34	— 0·23	— 0·27	+ 2·64	+ 7·20	+ 5·39	+ 4·09	+ 5·28	— 0·21	— 0·24	+ 22·80
	Akola	— 0·53	— 0·16	— 0·40	— 0·11	— 0·12	+ 5·61	+ 14·42	+ 7·60	+ 5·56	+ 6·16	— 0·45	— 0·31	+ 37·27
	Buldana	— 0·69	— 0·14	— 0·28	— 0·28	— 0·32	+ 6·45	+ 4·03	+ 1·96	+ 9·93	+ 7·61	— 0·31	— 0·22	+ 27·74
	Basim	— 0·37	— 0·07	— 0·17	— 0·25	— 0·45	+ 6·51	+ 1·47	— 0·35	+ 5·53	+ 1·80	+ 0·24	— 0·28	+ 13·61
	Yeotmal	— 0·06	— 0·12	— 0·47	— 0·24	— 0·67	+ 4·20	+ 2·94	+ 2·31	+ 6·93	+ 4·82	— 0·34	— 0·15	+ 19·15
	Wun	— 0·31	— 0·16	— 0·67	— 0·13	— 0·04	+ 4·34	— 1·30	0	+ 2·53	+ 5·46	— 0·27	— 0·20	+ 9·25
HYDERABAD	Bolaram	+ 0·26	— 0·24	+ 2·00	+ 0·85	— 0·62	+ 0·77	+ 0·81	+ 5·65	+ 2·17	— 1·05	— 0·23	— 0·40	+ 9·97
	Secunderabad	— 0·09	— 0·24	+ 1·84	— 0·49	— 1·22	+ 2·00	+ 2·67	+ 2·11	+ 0·63	— 1·48	— 0·14	— 0·22	+ 5·37
	Hyderabad	— 0·15	— 0·08	+ 1·46	— 0·55	— 0·80	+ 0·26	— 0·56	+ 0·77	— 3·09	— 0·21	— 0·28	— 0·67	— 3·90
	Lingsugur	0	— 0·01	— 0·01	0	— 0·49	— 2·12	— 1·73	+ 2·66	— 4·72	+ 0·53	— 0·40	— 0·25	— 6·54
	Aurangabad	— 0·10	— 0·03	0	— 0·05	— 0·05	+ 3·32	— 1·81	+ 2·42	+ 1·48	+ 5·65	— 0·60	— 0·22	+ 10·01
	Hingoli	— 0·50	— 0·10	— 0·20	— 0·46	— 0·14	+ 5·73	— 0·93	+ 2·94	+ 8·83	+ 2·87	— 0·28	— 0·24	+ 17·52
	Jalna	0	0	— 0·05	0	— 0·44	+ 3·21	— 1·75	+ 1·90	+ 1·00	+ 4·44	— 1·07	— 0·07	+ 7·17
	Mominabad	0	0	?	?	+ 0·11	+ 1·66	— 1·09	+ 8·08	+ 0·45	— 0·80	— 1·27	0	?
	Ibrahimpatan	— 0·02	— 0·09	+ 2·10	— 0·61	— 1·25	+ 2·39	— 0·34	+ 2·52	+ 0·06	0	— 1·04	— 0·23	+ 3·59
	Medack	— 0·04	— 0·21	+ 2·46	— 0·92	+ 0·04	— 0·18	+ 0·51	+ 16·80	+ 1·97	— 0·84	— 0·35	— 0·08	+ 19·16
	Indur	0	0	— 0·32	— 0·33	— 0·22	+ 2·43	+ 1·33	+ 9·86	+ 7·62	— 0·40	— 0·07	— 0·06	+ 19·84
	Yelgandal	— 0·03	— 0·24	+ 1·35	— 0·65	— 1·31	+ 3·41	+ 2·33	+ 3·21	+ 8·02	— 0·78	— 0·84	— 0·08	+ 14·39
	Khamam	0	— 0·34	+ 1·65	— 0·42	— 0·30	+ 6·64	+ 2·07	+ 2·33	+ 5·70	— 1·37	— 1·24	— 0·26	+ 14·46
	Nalgonda	— 0·09	— 0·01	— 0·42	+ 0·45	— 1·74	+ 3·73	+ 3·12	— 0·44	— 2·35	+ 2·68	— 1·77	— 0·07	+ 3·09
	Nagad Karnul	— 0·03	— 0·04	+ 0·71	— 0·46	+ 0·21	+ 2·91	+ 1·26	— 1·21	+ 0·88	— 0·71	— 0·36	— 0·35	+ 2·81
	Beeder	0	0	+ 0·39	— 0·44	— 0·49	+ 5·11	+ 1·05	+ 20·19	+ 1·99	— 0·32	— 0·53	— 0·04	+ 26·91
	Naldurg	0	0	— 0·26	— 0·25	— 0·91	+ 1·67	— 2·77	+ 12·15	+ 2·23	— 0·32	— 0·69	— 0·16	+ 10·69
	Nanded	— 0·22	0	+ 0·81	— 0·30	— 0·52	+ 5·93	— 1·76	+ 8·54	+ 6·70	— 1·94	— 0·37	— 0·57	+ 16·30
	Gulbarga	— 0·03	— 0·19	+ 0·64	— 0·74	— 1·41	+ 0·34	— 0·85	+ 8.89	— 1·35	— 0·09	+ 0·39	0	+ 5·60
	Shorapur	0	0	— 0·18	— 0·24	— 0·37	abolished.							?
	Raichur	— 0·06	0	+ 1·74	— 0·47	— 0·55	+ 0·87	+ 0·10	+ 0·21	+ 0·19	— 1·11	— 0·10	— 0·02	+ 0·80

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
HYDERABAD —*contd.*	Bheer	— 0·25	— 0·03	— 0·12	— 0·21	+ 0·19	+ 6·37	— 0·26	+ 8·58	+ 6·67	— 0·97	— 1·10	— 0·07	+ 18·80
	Purbhani	— 0·02	0	— 0·14	— 0·20	+ 0·04	+ 5·05	— 4·31	+ 1·33	+ 6·26	— 0·06	— 0·34	— 0·01	+ 7·60
BOMBAY	Dhulia	— 0·17	— 0·07	+ 0·02	— 0·02	— 0·37	+ 0·45	+ 3·80	+ 2·36	+ 3·83	+ 7·08	— 0·55	— 0·15	+ 16·21
	Nasik	+ 0·37	— 0·04	— 0·02	— 0·08	+ 0·01	+ 7·56	+ 6·04	+ 1·50	+ 7·00	+ 10·07	— 0·49	— 0·21	+ 31·71
	Igatpuri	+ 0·85	— 0·12	— 0·06	— 0·09	+ 0·27	+ 2·47	+ 3·97	— 16·05	+ 12·26	+ 7·16	— 0·27	— 0·18	+ 10 21
	Malegaon	— 0·22	— 0·20	— 0·02	— 0·24	— 0·48	— 0·14	+ 5·25	+ 6·36	— 1·05	+ 5·39	— 0·40	— 0·36	+ 13·89
	Ahmednagar	— 0·41	— 0·08	— 0·19	— 0·48	— 0·79	+ 5·63	— 1·29	+ 4·20	+ 3·96	+ 5·20	+ 0·41	— 0·12	+ 16·12
	Poona	— 0·24	— 0·04	— 0·05	— 0·27	+ 0·26	+ 4·23	— 1·36	— 1·20	+ 6·67	+ 4·20	— 0·67	— 0·19	+ 11·24
	Lonavala	+ 0·21	— 0·02	— 0·15	— 0·02	+ 0·68	— 1·56	+ 11·79	— 20·12	+ 19·88	+ 3·31	— 0·19	— 0·06	+ 13·75
	Satara	— 0·23	— 0·08	— 0·08	— 0·09	+ 0·20	+ 2·94	— 1·15	— 2·48	+ 3·00	+ 2·15	— 0·52	— 0·39	+ 3·27
	Mahableshwar	+ 0·17	— 0·05	— 0·39	— 0·71	— 1·07	+ 4·99	+ 24·42	— 31·52	+ 37·53	+ 5·53	— 0·23	— 0·26	+ 38·41
	Sholapur	— 0·03	— 0·12	— 0·14	— 0·63	— 1·04	+ 6·68	— 2·27	+ 10·09	— 1·02	— 1·56	+ 0·77	— 0·16	+ 10·57
	Kolhapur	+ 0·11	— 0·02	— 0·08	+ 1·24	— 1·03	— 1·79	+ 2·41	— 2·41	— 0·84	— 1·35	+ 0·94	— 0·12	— 2·94
	Bavda	+ 0·60	— 0·01	— 0·02	— 0·65	— 2·50	+ 5·65	+ 29·32	— 21·42	— 1·09	+ 0·79	— 8·95	— 0·14	+ 8·58
	Belgaum	— 0·02	— 0·02	— 0·49	— 0·34	+ 0·24	+ 0·44	+ 2·93	— 3·62	+ 3·01	+ 3·45	— 0·14	— 0·10	+ 5·34
	Gokak	— 0·05	0	— 0·19	+ 1·00	— 1·33	+ 0·54	+ 0·65	+ 3·01	— 2·76	+ 0·53	+ 0·75	— 0·68	+ 1·47
	Dharwar	— 0·15	— 0·02	+ 0·11	+ 0·12	— 0·47	— 1·94	+ 1·38	0	— 0·43	— 0·93	— 1·05	— 0·40	— 3·78
	Hubli	— 0·05	0	+ 0·24	+ 0·95	— 0·23	— 1·44	+ 0·76	+ 1·24	— 0·56	— 1·14	— 0·63	— 0·20	— 1·05
	Nandgad	— 0·18	— 0·13	— 0·23	+ 1·85	— 1·28	— 2·37	— 0·44	+ 3·27	— 4·02	+ 0·61	— 0·13	— 0·22	— 3·17
	Mandargi	— 0·41	0	— 0·22	— 0·13	— 1·16	— 1·77	— 1·63	+ 0·94	— 3·17	— 0·35	— 0·48	+ 0·07	— 8·31
	Kalghatgi	— 0·06	0	— 0·28	+ 3·15	— 0·23	— 0·06	+ 1·69	— 2·20	+ 0·79	— 0·14	— 0·12	— 0·33	+ 2·21
	Kaladgi	— 0·10	— 0·15	— 0·03	+ 1·04	— 1·27	+ 2·05	— 0·59	+ 0·98	— 4·81	+ 0·59	+ 0·17	— 0·40	— 2·52
	Bijapur	— 0·04	— 0·03	— 0·09	— 0·53	+ 0·18	+ 1·20	— 1·33	+ 5·58	+ 3·40	— 0·89	+ 3·00	— 0·77	+ 2·88
	Karwar	— 0·17	0	— 0·07	+ 1·87	— 0 47	+ 14·74	+ 10·43	— 3·91	+ 6·26	+ 4·57	+ 2·19	— 0·08	+ 35·36
	Honavar	+ 0·23	0	— 0·16	+ 0·27	— 2·36	+ 2·77	+ 6·17	— 8·40	+ 1·24	+ 4·23	+ 3·00	— 0·04	+ 6·95
	Vengurla	— 0·19	0	— 0·07	— 0·07	+ 1·34	+ 11·61	+ 12·98	— 5·52	+ 3·23	+ 3·61	+ 0·33	— 0·05	+ 27·20
	Ratnagiri	— 0·20	— 0·02	0	— 0·17	— 1·34	+ 0·76	+ 6·70	— 2·66	+ 0·81	+ 3·05	— 0·72	— 0·05	+ 6·16
	Colaba (Observatory.)	0	— 0·02	0	— 0·03	— 0·23	— 7·15	+ 15·36	— 2·42	+ 1·63	+ 8·62	+ 0·38	— 0·04	+ 16·10
	Byculla J. J. Hospital.	+ 0·10	0	— 0·02	0	+ 0·17	+ 0·86	+ 9·87	— 1·78	+ 0·73	+ 8·09	+ 0·61	0	+ 18·63
	Thana	+ 0·33	— 0·08	— 0·01	0	+ 0·19	+ 0·68	+ 12·76	— 0·44	+ 3·93	+ 4·74	— 0·03	— 0·01	+ 22·06
	Matheran	+ 0·08	— 0·01	— 0·02	— 0·01	+ 0·84	— 5·31	+ 6·30	— 30·65	+ 17·72	+ 7·09	— 0·47	— 0·01	— 4·45
	Surat	+ 0·62	— 0·03	0	0	+ 0·05	+ 7·98	+ 5·40	— 7·49	+ 3·17	+ 2·99	— 0·09	— 0·03	+ 12·57
	Broach	+ 0·82	— 0·02	— 0·01	— 0·01	+ 0·72	+ 1·98	+ 5·09	— 6·05	+ 6·77	+ 1·65	— 0·16	— 0·03	+ 10·75
	Kaira	+ 0·36	— 0·24	0	— 0·06	— 0·27	+ 0·57	+ 0·85	— 8·27	+ 4·14	+ 0·09	— 0·15	— 0·07	— 3·05
	Godhra	+ 0·75	— 0·17	— 0·01	— 0·01	+ 3·93	— 1·91	+ 8·58	— 7·07	+ 5·40	— 0·02	— 0·04	— 0·07	+ 9·36
	Ahmedabad	+ 0·12	— 0·09	— 0·02	+ 0·04	+ 1·52	— 0·91	— 0·81	— 7·46	— 0·82	— 0·65	— 0·03	— 0·05	— 9·24
	Bariya	+ 0·47	— 0·35	— 0·01	0	+ 1·38	— 0·87	+ 12·70	— 7·03	+ 7·54	+ 1·45	— 0·08	— 0·14	+ 15·06
	Idar	— 0·01	— 0·20	0	— 0·02	+ 2·69	— 1·07	— 3·44	— 10·29	— 4·19	— 0·22	— 0·11	— 0·04	— 16·90
	Palanpur	+ 0·10	— 0·25	+ 0·67	— 0·01	+ 1·65	+ 1·81	— 1·34	— 11·61	— 1·08	— 0·60	0	— 0·09	— 10·75
	Rajkot	+ 0·08	— 0·08	— 0·02	— 0·01	— 0·35	— 3·65	+ 7·66	— 6·07	+ 0·06	+ 0·52	— 0·24	— 0·07	— 2·17

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
BOMBAY—*contd.*	Bhuj	+ 0·08	— 0·13	+ 1·16	— 0·19	+ 0·25	— 0·76	+ 4·53	— 3·50	+ 0·47	— 0·67	— 0·01	— 0·03	+ 1·20
	Rhahpur	— 0·04	0	+ 0·83	— 0·12	— 0·04	— 0·46	— 6·81	— 2·72	+ 0·85	— 1·30	0	0	— 9·81
	Kurrachee	— 0·27	— 0·26	— 0·03	— 0·18	— 0·05	+ 0·18	+ 1·78	— 1·87	— 0·32	— 0·07	— 0·07	— 0·20	— 1·36
	Sehwan	— 0·34	— 0·22	— 0·23	— 0·23	— 0·11	— 0·01	+ 3·86	— 2·83	— 0·87	0	— 0·09	— 0·17	— 1·24
	Tatta	— 0·04	— 0·13	— 0·12	— 0·56	— 0·03	— 0·23	+ 0·98	— 1·46	+ 1·01	0	— 0·12	— 0·06	— 0·76
	Hyderabad	+ 0·71	— 0·15	+ 0·11	— 0·24	— 0·04	— 0·66	— 0·51	— 3·27	— 0·17	— 0·01	— 0·06	— 0·01	— 3·70
	Umarkot	+ 0·50	— 0·06	— 0·14	— 0·17	— 0·09	— 0·79	— 1·39	— 4·27	+ 1·02	— 0·18	0	— 0·01	— 5·58
	Nagar	— 0·13	— 0·07	— 0·06	— 0·03	— 0·30	— 1·16	+ 3·06	— 6·00	+ 2·26	— 0·40	0	— 0·03	— 2·86
	Shikarpur	— 0·18	— 0·27	— 0·33	— 0·19	— 0·02	— 0·13	+ 0·10	— 1·70	— 0·18	0	— 0·05	— 0·13	— 3·08
	Rohri	— 0·21	— 0·51	— 0·42	— 0·31	— 0·22	+ 0·27	+ 0·47	— 1·23	— 0·31	— 0·02	— 0·08	— 0·21	— 2·78
	Jacobabad	+ 0·40	— 0·23	— 0·29	— 0·09	— 0·11	— 0·09	+ 4·03	— 1·39	— 0·26	— 0·01	— 0·09	— 0·11	+ 1·76
	Deesa	+ 0·02	— 0·20	+ 0·42	— 0·05	+ 0·38	— 0·39	— 0·87	— 8·20	+ 0·49	+ 0·20	— 0·07	— 0·04	— 8·31
MADRAS	Ganjam	+ 0·12	— 0·49	— 0·40	— 0·96	— 1·27	+ 1·99	+ 6·77	— 0·53	— 5·24	+ 5·44	— 1·26	+ 0·64	+ 4·81
	Gopalpore	— 0·34	— 0·01	+ 1·48	— 1·42	— 1·10	+ 5·40	+ 1·83	— 0·81	— 0·34	+ 1·18	+ 0·32	+ 1·03	+ 7·12
	Aska	— 0·23	— 0·42	+ 1·03	+ 0·69	— 1·13	+ 9·66	+ 1·84	+ 5·32	— 4·78	— 1·71	— 1·23	+ 0·42	+ 9·46
	Vizianagram	— 0·19	— 0·47	+ 0·30	+ 0·07	— 0·68	+ 0·90	— 2·33	+ 2·21	— 5·39	— 0·56	— 0·93	— 0·38	— 7·45
	Bimlipatam	— 0·30	— 0·53	+ 0·34	— 0·20	— 1·82	+ 0·18	— 0·04	+ 1·81	— 4·40	+ 1·69	— 0·83	— 0·18	— 4·28
	Royaghadda	0	— 0·02	+ 1·37	— 0·57	— 0·85	+ 3·85	+ 3·22	— 1·65	+ 0·32	— 0·63	— 2·10	+ 0·10	+ 3·04
	Nouranagpur	?	?	+ 0·53	+ 0·07	— 1·37	+ 1·23	— 3·33	— 0·03	— 2·93	— 0·50	— 0·67	— 0·05	?
	Gunipur	?	?	?	?	?	?	?	?	— 1·70	— 2·43	— 1·25	+ 0·42	?
	Kotipad	0	0	+ 0·70	+ 0·77	— 0·75	+ 1·05	— 3·35	+ 1·07	+ 0·40	— 1·27	— 0·28	— 0·03	— 1·69
	Koraput	0	0	— 0·15	+ 0·19	— 1·00	+ 7·00	— 4·00	+ 1·25	+ 0·82	— 0·50	— 1·23	— 0·03	— 2·35
	Malkanagiri	?	?	?	?	— 0·54	+ 7·65	— 4·52	— 2·48	+ 1·22	+ 0·47	— 0·45	0	0
	Narsapatnam	— 0·39	— 0·39	+ 0·13	+ 0·26	— 1·08	— 2·14	— 0·98	+ 1·73	— 2·77	+ 1·02	— 2·53	+ 0·20	— 6·94
	Vizagapatam	+ 0·52	— 0·28	— 0·34	— 0·63	— 2·64	— 2·69	— 2·04	+ 5·78	— 0·97	+ 1·97	+ 1·32	— 1·12	— 1·12
	Coconada	— 0·25	— 0·24	— 0·17	— 0·49	— 1·85	+ 0·15	— 2·33	+ 0·06	— 4·49	+ 4·72	+ 6·38	— 0·16	+ 1·32
	Rajahmundry	— 0·17	— 0·28	— 0·22	— 1·04	— 1·01	+ 2·00	— 1·13	— 3·19	— 2·53	+ 6·10	+ 0·21	— 0·01	— 2·27
	Ellore	— 0·28	— 0·09	— 0·38	— 0·67	— 1·56	+ 2·05	— 0·10	— 0·88	— 4·90	+ 1·50	— 1·61	— 0·37	— 7·29
	Masulipatam	+ 0·33	— 0·08	— 0·34	— 0·04	— 1·48	+ 1·41	— 2·10	— 4·03	+ 3·37	+ 4·77	+ 10·74	— 0·26	+ 5·55
	Guntur	— 0·38	— 0·16	— 0·51	— 0·21	— 1·77	+ 0·01	— 2·28	+ 0·32	— 1·06	+ 0·99	+ 0·77	— 0·25	— 4·53
	Vinukonda	— 0·36	— 0·02	— 0·08	— 0·47	— 0·54	+ 0·28	— 0·02	+ 0·98	— 2·17	+ 4·61	— 0·12	— 0·78	+ 1·31
	Ongole	— 0·28	— 0·03	+ 0·16	+ 1·63	— 1·09	+ 3·15	+ 0·02	+ 3·27	— 3·49	+ 12·92	+ 2·39	— 0·96	+ 17·69
	Nellore	— 0·53	— 0·11	— 0·28	— 0·13	— 1·15	— 0·33	— 1·04	— 1·82	— 2·04	+ 14·56	+ 4·27	— 0·76	+ 2·10
	Udayagiri	— 0·43	— 0·26	— 0·35	+ 0·60	— 1·97	— 0·47	+ 0·54	+ 0·18	+ 0·16	+ 30·36	— 1·57	+ 0·75	+ 7·54
	Tada	— 0·91	— 0·81	— 0·35	— 0·18	— 2·43	+ 3·38	+ 1·75	— 3·58	— 2·50	+ 7·30	— 6·43	+ 5·92	+ 1·16
	Kurnool	— 0·04	— 0·04	+ 0·82	— 0·36	— 1·90	+ 1·36	+ 0·07	+ 2·27	— 1·96	+ 1·72	+ 0·13	— 0·17	+ 1·90
	Cumbum	— 0·12	— 0·06	+ 0·14	— 0·21	— 2·07	+ 0·98	+ 0·64	+ 0·65	— 1·87	+ 6·25	— 0·05	+ 0·32	+ 4·60
	Nandayal	— 0·05	— 0·03	+ 0·02	+ 0·69	— 1·51	+ 3·00	+ 1·58	+ 0·23	— 4·88	+ 2·84	+ 0·38	+ 0·35	+ 2·62
	Bellary	— 0·10	— 0·04	+ 0·78	— 0·55	— 1·30	— 1·64	+ 0·02	+ 1·54	— 3·21	+ 1·16	+ 0·05	— 0·26	— 3·55
	Gooty	— 0·04	— 0·07	+ 0·01	— 0·29	— 1·67	+ 1·45	+ 0·72	— 0·30	— 3·68	+ 0·99	+ 0·43	— 0·08	— 2·53

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
MADRAS—*contd.*	Adoni	0	0	+ 0·19	+ 0·50	— 1·46	— 2·13	— 0·84	+ 1·35	— 3·62	+ 0·11	+ 0·07	— 0·04	— 5·87
	Dharmavaram	— 0·02	— 0·21	+ 0·15	+ 0·97	— 1·97	+ 2·46	— 1·24	+ 4·52	— 4·58	+ 1·46	+ 0·69	+ 0·64	+ 2·87
	Cuddapah	— 0·11	— 0·01	+ 0·25	+ 0·05	— 1·43	+ 1·14	— 2·60	+ 2·14	— 3·09	+ 6·75	— 1·48	+ 2·80	+ 4·41
	Madanapalle	— 0·20	— 0·14	— 0·55	+ 1·15	+ 0·34	— 0·60	+ 0·20	+ 2·39	— 1·00	+ 4·25	— 0·72	+ 4·19	+ 9·31
	Chittoor	— 0·37	— 0·24	— 0·42	+ 0·13	— 1·70	+ 0·43	— 0·19	+ 0·73	+ 0·56	+ 5·75	+ 1·28	+ 1·92	+ 7·88
	Vellore	— 0·72	— 0·37	— 0·14	— 0·52	+ 1·11	— 0·04	— 0·18	— 1·45	+ 0·64	+ 3·21	+ 0·13	+ 3·31	+ 4·88
	Chandragiri	— 0·39	— 0·30	— 0·35	+ 1·04	— 1·83	— 1·33	+ 1·24	— 0·40	+ 0·90	+ 5·11	— 0·36	+ 5·26	+ 8·59
	Arcot	— 0·48	— 0·64	— 0·45	— 0·42	— 0·98	+ 3·79	+ 0·88	+ 0·69	— 3·00	+ 3·31	+ 3·39	+ 3·82	+ 9·91
	Madras	— 0·71	— 0·23	— 0·42	— 0·65	— 2·24	+ 0·29	+ 2·56	— 1·53	— 4·18	+ 11·38	+ 1·52	+ 5·86	+ 11·65
	Palmaner	— 0·24	— 0·21	— 0·35	— 0·54	+ 2·25	+ 0·67	— 0·41	+ 2·44	+ 2·75	+ 9·74	+ 2·07	+ 3·37	+ 21·54
	Saidapet	— 0·85	— 0·49	— 0·42	0	— 0·75	+ 1·66	+ 5·92	— 2·43	— 2·59	+ 6·92	— 4·77	+ 4·87	+ 7·07
	Chingleput	— 0·48	— 0·35	— 0·17	— 0·16	— 1·60	— 0·36	+ 0·93	— 1·05	— 1·75	+ 7·60	— 1·30	+ 1·97	+ 3·28
	Conjeeveram	— 0·59	— 0·46	— 0·16	— 0·39	— 2·02	+ 2·07	— 1·24	— 0·96	— 4·40	+ 6·38	+ 0·25	+ 1·73	+ 0·21
	Tindivanam	— 0·41	— 0·66	— 0·28	— 0·54	— 1·91	+ 1·00	+ 0·54	+ 0·96	— 1·76	+ 3·48	— 1·32	+ 2·64	+ 1·74
	Cuddalore	— 0·82	+ 0·27	— 0·34	— 0·93	— 1·43	+ 0·71	+ 0·22	+ 1·78	— 4·14	+ 7·25	+ 0·14	— 0·22	+ 2·49
	Vriddhachalam	— 0·45	— 0·36	— 0·15	— 0·52	— 0·81	+ 0·31	+ 0·70	+ 1·63	— 2·30	+ 12·28	+ 2·64	— 1·38	+ 11·59
	Udayarpalaiyam	— 0·84	— 0·38	— 0·10	— 0·79	— 3·23	+ 2·59	— 0·63	— 3·25	— 0·65	+ 4·29	+ 0·38	+ 0·37	— 2·24
	Salem	— 0·37	— 0·08	+ 0·24	— 1·43	+ 0·27	+ 1·19	+ 0·65	+ 3·27	— 4·19	+ 5·22	+ 1·71	+ 1·97	+ 8·45
	Atur	— 0·43	— 0·27	+ 1·19	— 0·43	+ 0·92	+ 0·03	+ 3·33	+ 4·36	— 2·39	+ 3·71	+ 3·29	+ 0·43	+ 13·74
	Shevaroy Hills	— 0·42	— 0·19	+ 1·18	— 1·81	+ 0·37	+ 0·30	— 2·70	+ 6·12	— 4·65	+ 3·54	+ 5·62	+ 2·34	+ 9·70
	Kambakonum	— 0·73	— 0·13	— 0·47	— 0·74	— 1·32	+ 1·07	— 2·21	— 2·42	— 2·66	— 0·98	+ 2·29	— 2·84	— 11·14
	Tirupatur	— 0·16	— 0·39	+ 0·05	+ 2·15	— 0·82	— 0·22	— 0·29	— 1·81	— 3·87	+ 2·59	+ 1·44	+ 1·38	— 0·05
	Hosur	— 0·30	— 0·34	— 0·59	+ 1·36	— 2·15	— 1·16	— 0·01	+ 2·28	— 3·51	+ 7·05	— 0·03	+ 2·41	+ 5·01
	Tranquebar	— 1·04	— 0·40	— 0·08	— 1·20	— 1·16	+ 0·55	— 1·62	— 1·90	— 2·61	+ 9·22	— 2·26	— 2·26	— 4·76
	Negapatam	— 0·54	+ 0·06	— 0·13	— 1·08	— 1·27	+ 3·02	— 0·92	+ 3·29	— 2·08	+ 7·13	+ 3·95	— 3·58	+ 7·85
	Tanjore	— 0·73	+ 0·32	— 0·51	— 0·91	+ 0·07	+ 3·73	— 0·88	— 0·57	— 2·15	+ 1·26	+ 2·09	— 0·79	+ 0·93
	Patukota	— 1·30	— 0·15	— 0·32	— 1·29	— 1·14	+ 1·55	— 0·45	— 4·63	— 3·48	+ 8·86	+ 0·16	— 1·04	— 3·23
	Trichinopoly	— 1·09	— 0·56	— 0·74	— 2·02	+ 0·40	+ 1·32	— 1·00	— 0·06	— 0·89	+ 0·08	— 0·01	— 1·98	— 6·55
	Kurur	— 0·29	— 0·13	— 0·35	— 1·91	— 0·61	— 0·26	— 1·35	+ 2·45	— 2·49	+ 1·65	+ 1·24	+ 0·08	— 1·97
	Coimbatore	— 0·27	— 0·14	+ 0·02	— 1·77	— 0·48	— 0·93	— 0·59	+ 1·75	— 0·99	+ 2·87	+ 1·33	+ 1·30	+ 2·10
	Kollegal	— 0·27	— 0·06	+ 0·28	+ 0·66	+ 0·92	— 0·95	— 0·62	+ 2·58	— 4·89	+ 0·80	— 0·14	+ 4·40	+ 2·71
	Dindigul	— 0·66	— 0·28	— 0·25	+ 1·00	— 0·64	— 0·81	— 0·17	+ 0·21	— 2·28	— 1·22	+ 2·50	— 0·89	— 3·49
	Madura	— 0·80	+ 0·55	— 0·55	— 1·59	+ 0·41	— 0·52	+ 0·76	— 0·87	+ 0·06	+ 0·10	+ 5·61	+ 0·57	+ 3·73
	Pasumali	— 0·81	+ 0·56	— 0·71	— 1·12	+ 4·89	— 0·56	+ 1·91	— 1·52	+ 3·90	+ 3·82	+ 6·24	+ 0·86	+ 17·46
	Vattanum	— 0·63	+ 1·61	— 0·51	— 1·39	+ 5·32	— 0·74	— 0·63	— 0·75	— 1·84	+ 7·64	— 3·11	— 2·74	+ 2·23
	Periyakulam	— 0·85	— 0·98	— 1·02	+ 0·87	+ 2·04	— 0·40	— 0·19	+ 2·71	— 0·33	— 0·38	+ 4·21	+ 0·22	+ 5·90
	Tinnevelly	— 1·19	+ 3·06	+ 1·89	— 1·02	+ 2·72	+ 1·24	+ 0·94	— 0·25	— 0·87	+ 1·38	— 3·59	— 0·46	+ 3·85
	Tuticorin	— 1·23	+ 3·75	+ 0·13	— 1·39	+ 5·06	— 0·13	— 0·01	— 0·37	— 0·50	+ 1·90	+ 2·73	+ 0·42	+ 10·36
	Setur	— 0·41	+ 1·55	— 0·97	+ 2·90	+ 7·36	+ 0·49	— 0·92	— 0·30	— 1·67	+ 2·96	+ 5·27	+ 1·69	+ 17·98
	Cochin	+ 0·28	— 0·69	+ 1·30	— 1·22	+ 4·93	+ 1·51	+ 1·70	+ 0·84	— 5·10	+ 1·79	+ 2·67	— 0·12	+ 7·91

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of Table XXV*—continued.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
MADRAS.—*contd.*	Palghat	— 0·07	— 0·12	+ 0·11	— 1·00	+ 3·96	+ 1·26	+ 4·79	+ 5·75	— 2·07	+ 4·39	+ 1·49	+ 1·49	+ 18·99
	Wellington	— 0·59	— 0·37	+ 0·76	— 2·15	— 0·43	— 1·64	— 0·56	+ 0·12	— 1·82	+ 3·79	+ 1·13	+ 1·17	— 0·68
	Manantoddy	— 0·29	— 0·37	+ 1·09	— 0·02	— 2·34	— 1·19	+ 6·37	+ 13·70	— 3·06	+ 1·62	— 0·14	+ 0·95	+ 16·32
	Calicut	— 0·18	— 0·16	+ 0·50	+ 6·25	— 4·50	— 5·27	— 1·20	— 0·70	— 3·89	+ 7·07	+ 0·36	— 1·40	— 3·12
	Tellicherry	— 0·45	— 0·08	+ 0·01	— 1·08	— 4·71	— 6·99	+ 3·22	— 2·03	— 7·75	+ 2·29	+ 8·55	+ 0·32	— 8·70
	Cannanore	— 0·56	— 0·26	+ 0·23	— 0·73	— 0·66	— 12·43	+ 2·31	— 2·88	— 6·51	— 2·07	+ 5·93	+ 0·07	— 17·56
	Mangalore	— 0·18	— 0·09	— 0·11	+ 0·28	— 5·25	— 11·69	+ 9·68	+ 0·04	— 3·07	— 2·27	+ 0·48	— 0·20	— 13·28
	Bangalore	— 0·22	— 0·15	— 0·54	— 0·62	— 3·14	— 2·40	+ 1·25	+ 1·57	— 5·29	+ 6·25	+ 1·06	+ 1·36	— 0·87
	Mysore	— 0·09	— 0·14	+ 1·95	— 0·98	+ 3·96	— 0·71	+ 0·07	+ 3·96	— 3·35	+ 5·58	+ 2·50	+ 3·58	+ 16·33
	Shimoga	— 0·07	— 0·15	+ 0·23	+ 3·53	— 0·49	— 0·17	+ 2·96	+ 4·73	+ 0·50	+ 3·44	+ 2·26	+ 0·54	+ 17·31
MYSORE AND COORG.	Mercara	— 0·33	— 0·05	+ 0·91	+ 2·29	— 1·95	— 4·24	+ 13·40	+ 7·59	— 3·27	+ 3·63	+ 2·62	+ 2·07	+ 22·67
	Kolar	— 0·34	— 0·02	— 0·63	+ 1·32	— 0·15	— 0·28	— 0·52	+ 2·27	— 3·87	+ 6·94	+ 0·21	+ 4·42	+ 9·35
	Tumkur	— 0·17	— 0·26	— 0·15	+ 0·55	— 1·21	— 2·92	+ 0·84	+ 6·99	— 4·17	+ 5·04	+ 0·73	+ 0·39	+ 5·66
	Chitaldroog	— 0·36	— 0·02	+ 0·16	— 0·58	+ 0·22	— 0·50	+ 0·60	+ 3·71	— 2·78	+ 1·10	+ 2·66	+ 0·41	+ 4·62
	Chikmagalur	— 0·42	— 0·16	+ 0·14	+ 0·33	+ 0·11	— 2·05	+ 6·67	+ 4·90	— 1·82	+ 4·87	+ 5·17	+ 1·31	+ 19·05
	Hassan	— 1·39	— 0·17	+ 1·19	+ 1·08	+ 1·32	— 0·33	+ 5·58	+ 6·71	— 1·06	+ 6·58	+ 1·73	+ 1·43	+ 22·67
CEYLON	Jaffna	+ 1·44	+ 3·62	— 0·26	— 0·50	+ 3·29	— 0·49	— 0·46	— 0·56	— 2·67	+ 12·77	+ 5·89	+ 1·08	+ 23·15
	Mannar	+ 3·70	+ 8·47	— 2·14	— 1·72	+ 5·80	— 0·56	— 0·12	— 0·45	— 0·73	+ 11·93	+ 2·18	— 1·20	+ 25·16
	Trincomalee	+ 1·29	+ 5·51	+ 1·03	— 1·09	+ 2·33	+ 4·44	— 2·19	— 2·98	— 0·09	+ 4·49	+ 7·88	— 4·77	+ 15·76
	Batticaloa	+ 1·54	+ 6·38	— 2·71	— 1·41	+ 1·52	+ 0·66	0	— 2·61	— 1·53	+ 4·84	+ 5·31	— 2·25	+ 9·74
	Hambantota	+ 2·43	— 1·25	+ 0·17	— 0·72	+ 1·57	+ 0·48	+ 0·76	— 0·88	— 1·85	+ 2·17	— 1·71	— 3·69	— 2·52
	Galle	+ 1·23	— 0·26	— 1·70	+ 2·66	— 0·70	— 2·50	+ 2·93	+ 0·40	— 1·63	— 2·05	+ 7·97	— 2·01	+ 4·34
	Ratnapura	+ 2·68	+ 2·25	+ 1·79	+ 1·97	+ 8·94	— 3·53	— 1·87	+ 4·64	+ 0·08	+ 3·16	— 1·22	+ 0·22	+ 19·11
	Colombo	— 1·05	— 0·25	— 0·10	— 0·63	+ 5·53	+ 4·19	— 2·47	+ 12·87	— 1·42	+ 1·69	— 3·70	+ 1·21	+ 15·87
	Kandy	— 3·64	+ 0·43	— 0·31	— 1·24	+ 7·86	— 2·65	— 1·65	+ 1·65	— 4·47	— 0·47	— 3·05	— 3·24	— 10·78
	Newera Eliya	— 1·08	+ 2·74	+ 0·30	+ 1·68	+ 4·59	— 7·35	+ 5·29	+ 4·91	— 5·12	— 1·96	— 1·51	— 2·57	— 0·08
	Puttalam	— 1·75	+ 0·99	— 1·42	— 3·08	+ 8·60	— 1·05	— 0·42	+ 0·65	?	+ 2·19	— 0·12	— 5·27	?
BURMA	Anuradhapura	— 1·34	+ 3·99	— 0·30	— 0·41	+ 3·51	+ 2·16	— 0·11	+ 1·87	— 2·72	+ 6·17	+ 4·24	— 0·27	+ 16·79
	Akyab	— 0·16	— 0·20	+ 0·85	+ 0·79	+ 2·81	— 6·92	— 2·70	— 4·84	+ 0·44	— 6·87	— 0·11	+ 6·77	— 10·14
	Kaukpyo	— 0·10	— 0·06	+ 0·58	— 0·89	+ 4·39	+ 1·59	— 8·37	— 3·19	— 0·09	— 7·91	— 0·23	+ 3·26	— 11·02
	Sandaway	— 0·08	— 0·07	— 0·15	— 1·11	— 0·58	— 5·61	+ 9·09	— 8·43	+ 10·86	— 5·62	+ 12·08	+ 0·72	+ 11·10
	Rangoon	— 0·17	— 0·06	+ 0·08	+ 2·32	— 4·20	— 4·21	— 2·25	— 3·43	— 4·16	— 4·66	— 3·47	— 0·07	— 17·34
	Bassein	— 0·14	— 0·04	— 0·08	— 1·33	— 2·27	+ 5·23	+ 1·16	— 7·72	— 1·42	— 2·40	+ 13·38	+ 0·15	+ 4·52
	Diamond Island	— 0·54	— 0·05	— 0·02	— 2·31	— 4·41	+ 1·08	— 1·71	+ 3·22	— 0·17	— 6·45	+ 8·60	— 0·42	— 3·18
	Henzada	— 0·06	— 0·09	0	— 0·43	— 1·45	+ 0·71	+ 5·52	— 1·62	+ 3·28	— 1·15	+ 4·09	+ 0·05	+ 8·85
	Myanaung	— 0·01	0	— 0·02	— 1·01	— 0·08	— 1·01	— 4·36	+ 0·96	+ 3·50	+ 0·31	+ 7·19	+ 0·49	+ 5·87
	Prome	— 0·02	0	— 0·01	— 0·28	— 0·40	+ 2·53	+ 0·47	— 5·63	— 1·17	— 0·54	+ 5·48	+ 0·05	+ 0·48
	Thayetmyo	0	— 0·02	— 0·07	+ 0·90	— 1·37	+ 0·87	— 0·64	— 4·49	— 3·23	+ 4·49	+ 6·65	+ 0·16	+ 3·75
	Toungoo	— 0·02	0	— 0·02	+ 3·22	— 2·61	+ 2·37	+ 3·83	— 0·86	+ 1·51	— 5·22	+ 0·72	— 0·24	+ 2·68
	Moulmein	— 0·01	+ 0·23	— 0·13	— 0·82	— 6·60	+ 0·22	— 2·69	— 12·50	+ 5·04	— 6·33	+ 0·52	— 0·02	— 23·09

TABLE XXVI.—*Comparison of the monthly and total rainfall in 1883, with the averages of 7a XXV*—concluded.

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
BURMA—*contd.*	Tavoy . .	— 0·10	— 0·21	— 0·72	— 2·24	— 2·42	+ 3·82	+ 13·24	+ 0·52	— 14·03	— 0·77	+ 1·30	— 0·15	— 1·58
	Mergui . .	— 0·41	— 0·17	— 2·11	— 1·16	— 2·47	+ 1·06	+ 3·27	+ 1·05	+ 9·34	+ 7·55	+ 2·83	— 0·60	+ 18·18
	Shwegyin .	— 0·02	+ 0·06	— 0·39	+ 2·26	— 0·32	— 4·23	+ 7·48	— 4·84	— 0·50	— 3·66	+ 0·06	— 0·12	— 4·22
BAY ISLAND .	Port Blair .	— 0·40	— 1·21	— 0·45	— 1·84	— 3·71	— 2·24	+ 2·47	+ 2·40	— 2·72	— 5·80	+ 4·32	+ 10·06	+ 0·88
	Nancoury .	— 2·38	+ 0·70	— 1·88	— 3·01	— 2·82	— 2·32	— 0·50	+ 3·65	+ 5·07	— 6·42	+ 14·48	+ 2·52	+ 7·09
STRAITS SETTLEMENTS.	Singapore .	— 4·78	— 3·77	— 0·22	+ 0·81	+ 0·61	— 1·89	— 3·13	— 5·36	+ 2·50	— 1·27	— 4·66	— 3·74	— 24·90

January.—The earlier part of the cold weather of 1882-1883 was nearly rainless. An occasional light shower in the more northerly hills of the Punjab and at stations near the foot of the mountains, was the only precipitation recorded in Northern India during November and December 1882, and up to the 9th January 1883. But from the beginning of this month, the low pressure area around the Gulf of Cambay, which is a normal feature of the winter season, had been more than once developed and extended, to the obliteration of the ridge of high pressure, which equally, as a normal feature of the season, extends from the Punjab across Rajputana and Central India. The normal anticyclonic circulation around this ridge was, therefore, replaced by a cyclonic system of winds around the Gulf of Cambay as a centre. Southerly winds prevailed in the Deccan and Central Provinces, and easterly winds up the Gangetic plain; while they were steady from north or north-east down the Indus Valley, and occasionally in Western Rajputana; in general very light. This anomalous system of winds, repeated, as will presently be seen, through the middle of the month, explains the temperature anomalies of Northern and Central India, described in a preceding section; and they brought up the vapour which in the latter part of the month, more especially, was so copiously condensed on the hills and plains of Northern India.

On the 9th and 10th, the fall was extensive but not very heavy. There was little, if any, rain on the plains to the west of Lahore, but snow fell on the North-West Himalaya, from Hazara eastwards, and rain was very general in the plains districts lying along the hills east of the Ravee, in Delhi and Gurgaon, over the greater part of the North-Western Provinces, and into Behar, in the eastern states of Central India, and south of the Ganges up to the confines of Bengal. It did not extend to the Western Punjab or to any part of Rajputana or the Western states of Central India. Nor was it felt in Berar nor to the south of the Satpuras in the Central Provinces, nor, on the other hand, in Northern Bengal and the Central Himalaya. It coincided, therefore, with a well-defined band on the north-east and north of the region of low pressure and at a considerable distance from its centre.

The four charts on Plate V represent the characteristic phases of the pressure distribution and winds antecedent to, during, and immediately after, this disturbance, which is not quite of the usual type of the cold-weather rains, though not without precedent during

the last few years. The first chart, that of the 4th January, exhibits the state of things when the Cambay depression was encroaching on, and obliterating, the tongue of high pressure across Rajputana. The second and third are those of the 9th and 10th, when the disturbance had culminated in rain, and the fourth exhibits the re-establishment of the original state of things by the wave of high pressure, accompanied with north-west winds, which, as a general rule in such cases, advances from the western mountains after the rainfall.

This final phase was, however, but short-lived. The rain was indeed followed by nearly a fortnight of nearly rainless weather, except on the hills of the Northern Punjab. But, again the depression extended, again southerly winds prevailed throughout Central India, and easterly winds up the Gangetic plain, and on the 20th and following days, a few light sporadic showers fell in Rajputana and Central India. Between the 22nd and 23rd the barometer fell rapidly in the Indus Valley to a minimum in Upper Sind, Rajputana, and the Punjab; and on the 24th and 25th, a great fall of the barometer took place over the latter province, giving rise to a strongly marked cyclonic disturbance in that region. The charts for 10 A.M. of the 24th and 25th on Plate VI illustrate the formation of this disturbance.

The subsequent history of this storm differs from that of most similar cases of cold-weather rainfall. In general, they travel eastwards, and after three or four days break up. But in the present case, while losing its original concentrated character, it continued to occupy the Punjab, during not less than five days, and not till the 29th did the depression disappear. The subsequent phases are illustrated in 3rd to 6th figures on Plate VI.

The precipitation accompanying this storm was wide-spread and very heavy. From the night of the 24th to that of the 27th snow fell almost without intermission on the Punjab Himalaya, at Simla to a thickness of 5 feet, where free from drifts; and at Chamba of 9 or 10 feet. It descended moreover to levels at which it has been rarely known. At Rawalpindi, 8 miles distant from the foot of the hills, on the plateau north of the Salt Range and less than 1,700 feet above the sea, on the night of the 27th, the snow lay to a depth of 4 inches, an occurrence stated to be without precedent in the recollection of any inhabitant.

On the plains, the rainfall extended over the Punjab, Rajputana, Central India, the North-Western Provinces, Oudh and Behar, nearly the whole of Bombay, the Central Provinces, and Bengal; in the last province and Behar, chiefly on the 26th and 27th. The heaviest rain was in Oudh, where, on the 26th, over 4 inches were measured at Nawabganj and Kheri, and over 3 inches at Lucknow and Sitapur. More than 2 inches in the 24 hours were recorded at most stations in the province. In the North-Western Provinces, Mozuffernagar registered 4 inches and Fatehpur over 3. On the plains of the Punjab, the greatest fall in the 24 hours was between 2 and 3 inches, at Gujarat, Sialkot, and Gujranwala on the 25th. In Rajputana, Central India, the Central Provinces, Bombay, and Bengal the fall was much lighter.

Chiefly as the result of this storm, the rainfall of the month exceeded the average at nearly all stations in the Punjab, and especially at Rawalpindi; throughout Rajputana, the greater part of Gujarat and Central India and the Saugor and Narbudda territories, in all parts of the North-Western Provinces and Oudh, Behar, and the northern districts of Bengal. Eastern Bengal the Gangetic delta, Orissa and the southern and eastern districts

of the Central Provinces, on the other hand, had less than the small average of the month; and Hyderabad, the greater part of Berar, the southern districts of the Deccan, Mysore and with a few rare exceptions, the whole of the Madras Presidency, had no rain. Burma was equally rainless, and in Ceylon, while there was an excess of from 1 to 4 inches in the northern and eastern districts, the rest of the island had somewhat less than an average fall. At the Bay Islands there was but little rain.

February.—A long spell of dry weather, with north-westerly winds and a low temperature in Northern India, succeeded the heavy rainfall of the latter end of January, and, with a few insignificant exceptions, the North-Western Provinces, Rajputana, and Central India were rainless throughout the month. In the Punjab, no rain fell before the 18th, on which day a slight fall took place over the most northerly districts, as far east as the Sutlej. But the southern and eastern districts had no rain during the month. On the hills, however, snow fell from the 17th to the 21st, and again on the 28th, but not very heavily. On the 25th, there were a few showers in the south-eastern districts of the North-Western Provinces, and on the same or following days, rain was pretty general in Lower Bengal and Assam. The Central Provinces, Berar, Hyderabad, the whole of the Bombay Presidency, Mysore, and by far the greater part of the Madras Presidency had no rain throughout the month. Only some of the coast stations and the extreme south of the peninsula had some showers; in the first six days, the heaviest being at Tuticorin, where over 4 inches were registered. In Ceylon, except on the south-west coast, the rain was unusually heavy, and especially on the north and east of the island. In Burma the only rain was in Tenasserim, and that but slight.

Except around Calcutta and Balasore in Bengal, in the southern extremity of the peninsula and Ceylon, the rainfall of the month was everywhere below the average, and the greater part of India was absolutely rainless.

March.—This was also, on the whole, a rather dry month, but less so than February and also the deficiency of rain was less general. In the Punjab, the first five days were showery, and on the 11th and 12th rain fell generally over the province. And during the remainder of the month, though but little rain was recorded on the plains, falls of snow on the higher hills, and rain at lower levels, were by no means infrequent. Still, it was only in the south-eastern districts of the province, and at Murree, Rawalpindi, and Jhelum that the fall of the month exceeded the average. Elsewhere the deficiency averaged half an inch, or rather more.

In Rajputana and Central India, light sporadic showers fell almost daily up to the 12th, and, on the whole, the total fall of these provinces differed but little from the normal amount, being slightly above it at some stations, below it at others. In the North-West Provinces and Oudh also, the first 12 days were showery, and more or less rain fell in all parts of these provinces, while the remainder of the month was all but rainless. In the Meerut division and Rohilkhand, the total fall more or less exceeded the average, and elsewhere was but little below it.

In the central and western districts of Bengal the first 12 days were generally rainy, and at one or two stations there was also a shower on one of the last few days of the month. In Eastern Bengal, there was a long dry interval from the 6th to the 26th, and in Assam and Cachar, except in Upper Assam, from the 6th to the 20th only, after which local showers were frequent. In the Chittagong division, and everywhere to the west of

the delta and in Orissa, the rainfall of the month rather exceeded the average, and it was only to the north of the Ganges and in Assam that the fall was deficient.

In the eastern districts of the Central Provinces, as in Orissa, there was more than an average fall, but elsewhere the amounts were generally short of the average, and at the more westerly and northerly stations there was no rain. The rainy period was from the 4th to the 12th, and at the most southerly stations one or two days later. In Berar there was no rain of importance. In Hyderabad there fell from 1 to 3 inches in the eastern part of the state, but in the western half there was little or no rain except in the south. The rainy period was from the 3rd to the 15th.

In Bombay the only rain, and that but slight, was in Dharwar and the adjoining districts, and in Cutch, Sind, and at Palanpore. In the north, the showers occurred between the 5th and 7th; in the south between the 14th and 17th.

In Madras, there was rather more rain than usual in the Northern Circars, the Ceded Districts, around the Salem hills, in Tinnevelly, and on the west coast; but over the greater part of the Carnatic there was no rain. In the north of the Presidency, it fell at intervals up to the 16th, in the south and west up to the 19th or 20th, and more frequently. In Mysore and Coorg, there was, on the whole, an average fall, with local variations; and it continued to the 19th, after which there was no further rain. In Ceylon also, there was, on the whole, about the usual amount of rain. But in Burma very little, and none at Port Blair.

The first half of the month was, therefore, more or less showery in Northern India, in the south the first twenty days; but the latter part of the month was all but rainless, except in Assam and Eastern Bengal.

April.—This was, in general, a very dry month. In the Punjab, indeed, there were four rainy intervals, *viz.* the first four days, between the 14th and 16th, between the 22nd and 25th, and on the 29th; but the total fall of the month was almost everywhere somewhat deficient. Rajputana and Central India were particularly rainless, and the North-Western Provinces also, except on and near the Himalaya. In this latter region showers occurred between the 23rd and 26th.

In Bengal, except in Behar, there were partial showers on the 2nd and 3rd, and these were followed by from 9 to 11 days of dry rainless weather. Local storms then began to recur and the latter part of the month was very rainy throughout the province; in Behar, from the 24th to the 27th, only. On the whole, the total of the month was nearly that of an average season. In Assam, there was a large deficiency in Sylhet and Cachar, and on the southern face of the Khasi hills, but not in the Assam Valley. There was but one rainless interval, and that but short, *viz.* from the 7th to the 11th.

In the Central Provinces proper and Berar; there was no rain, except slight showers at Sironcha and Sambalpur. But in Bastar, showers were frequent during the last half of the month. In Hyderabad, occasional slight sporadic showers fell chiefly during the last half of the month, but they were very local, and nearly half the stations recorded no rain, while elsewhere, the fall was generally deficient.

In Bombay, there was rather more than an average fall in and around Dharwar, but the greater part of the Presidency had no rain whatever. In Madras, the distribution of the rain varied much as in the preceding month, but the fall was somewhat greater on and around the hills of the Eastern Ghats, and especially at Calicut. But over the greater

part of the Presidency it was more or less below the average. In Mysore and Coorg, however, the average was generally exceeded, especially at Mercara and Shimoga. In this province and on the west coast, rain fell at intervals throughout the month, and daily after the 19th.

In Ceylon, the rainfall was rather deficient except in the south-west province and on the hills, but not greatly so. In Burma a little rain was recorded at all stations, and a certain excess at the more northerly stations and Rangoon, but elsewhere it was below the average of the month. There was a deficiency also at the Andamans and Nicobars.

May.—Throughout North-Western, Western, and Central India, and Hyderabad as far south as Bijapur and the Kistna river, that is, over the whole region in which the north-westerly land winds are a normal feature of the spring season, the first three weeks of this month were rainless and the atmosphere remarkably dry. But, after the 21st, a change set in, the dry winds gave way to those from the south and south-east, bringing up vapour, which was discharged copiously and generally as rain, over a large part of India, and as snow on the North-Western Himalaya; and in the last week of the month the precipitation was heavy and extensive. In the Gangetic delta, Orissa, and Chutia Nagpur occasional thunder storms gave a sporadic rainfall throughout the month, but in Northern and Central Bengal, and in Assam and Cachar, all the earlier part of the month was characterized by frequent and often heavy rain, and in Cachar, the country was devastated by disastrous floods, accompanied by an extensive destruction of property and not inconsiderable loss of life.

The barometric features which respectively characterized these two periods, the one of great dryness in North-Western and Western India, and great precipitation in Cachar, the other of general rain in the former and comparatively fine weather in the latter tract, are of much interest, and are respectively illustrated in Plate VII. The upper charts, those of the 12th and 20th May, illustrate the former; the lower, those of the 22nd and 28th May, exhibit characteristic phases of the latter. During the former or dry period, the seat of lowest pressure was along the foot of the North-West Himalaya, but it was nearly as low in Chutia Nagpur and Behar. In the region of the Indus Valley and the Indian desert, the pressure was unusually high relatively to other parts of India and, as is seen in the charts, the isobars ran obliquely across Northern India from north-west to south-east. During the greater part of the latter or rainy period, a barometric minimum was established in the lower Indus Valley, and the pressure in the Punjab was relatively high; but the humid winds, circulating cyclonically on the east and north of the depression, discharged their vapour abundantly over Northern India.

In the Punjab, rain fell daily in some part or parts of the province, from the 22nd to the 29th, and on the 28th and 29th snow fell abundantly on the outer Snowy Range, down to levels of 10,000 or 11,000 feet. On the hills, notwithstanding the extraordinary dryness of the first three weeks, the total fall of the month exceeded the average, and especially at Simla and Abbottabad. It was also excessive in some parts of the plains, as at Mooltan, Montgomery, Jhelum, Lahore, and Sirsa.

In Rajputana and Central India, the rainy period was the same as in the Punjab, and an abnormal excess was all but universal, amounting to from 3 to 5 inches in the south-west corner of the Malwa plateau, and to upwards of 2 inches at Neemuch and Agar. In the North-Western Provinces and Oudh, it was less, and about half the

stations had somewhat less than an average fall. At Cawnpore and in the southern portion of Mirzapore district, there was no rain.

In Eastern and Northern Bengal, the rainfall was very considerable in the first three weeks; that is, during the dry period of North-Western India, but not afterwards; and the central and western districts and Orissa were virtually excluded from both the rainy areas. In Behar especially, there was scarcely any rain, and in the Gangetic delta and Orissa, the total fall of the month was far short of the average.

In Assam and Cachar, as has already been stated, and especially in the latter, the rainfall of the first three weeks was excessive. Silchar had 36 inches above the average fall of 16 inches, and Sylhet nearly 15 inches above the average of nearly 22 inches; and the river Barak, which drains the district of Cachar, rose 41½ feet above its normal level, submerging the greater part of the station of Silchar and all the lower levels. The flood was attended with much loss of life, and for a time cut off many of the tea-gardens from their food supplies, threatening the cooly labourers with starvation. By the exertions of the local officers this extreme disaster was happily averted.

In the Central Provinces, as in the North-West, dry, almost rainless, weather prevailed up to the 23rd, and, even during the last week, the fall was comparatively light and sporadic. At most stations, therefore, the total was below the small average of the month. In Berar it was even less, and indeed there was no rain at any station before the 26th, and at most, not before the 31st. In Hyderabad also, the rain was light and partial. At only two stations in the list did it amount to 1 inch, and at several there was no rain. Such showers as fell were nearly all in the last week, chiefly on the last two days of the month.

In Bombay, there was no rain in Sind, but rather more than the average in Gujarat and the most northern districts of the Concan, but in the southern part of the Concan and the South Mahratta country, the fall was below the small average of the month. In the southern districts rain fell daily at Belgaum, and at intervals elsewhere, during the first fortnight; and again on the last three days. But in other parts of the Presidency the rain was restricted to the latter part of the month.

In Madras, all the first portion of the month was rainless or nearly so in the northern districts, and showery towards its close. Over all the central portion of the Presidency, in the Ceded Districts and the Carnatic, as far south as the Cavery, there were only occasional slight local showers throughout; most frequent on and around the Salem hills, and in the south, although there were but one or two falls, that between the 8th and 10th was very copious; and whereas, over the greater part of the Presidency, the rainfall of the month was more or less deficient, in Madura and Tinnevelly, and also in Cochin, it exceeded the average by some inches. In Mysore any deficiency was but slight and not universal.

In Ceylon, there was a more or less considerable excess at nearly all stations, amounting to over 8 inches at Ratnapura and Pattalam, and nearly as much at Kandy. In Burma rain fell more or less throughout the month, but the showers were light, and, except at Akyab, the total amount was more or less below the average at all stations. This was also the case at Port Blair and Nancowry.

June.—June was a dry month in the Upper Provinces and Rajputana. In Bengal the rains set in on the 13th, but they advanced only as far as Behar, with a moderate fall up

to Allahabad. Further westward there were occasional thunder storms, but no heavy rain fell before the 25th, nor in Punjab, before the 29th, and even then it was not continuous. During the earlier part of the month and up to the 19th, occasional thunder storms occurred however in all parts of the Punjab, excepting the more westerly districts, and on the hills (except indeed at Murree) there were thunder storms with hail, at intervals of three or four days, throughout the month, but save at Gujarat, Delhi, and Gurgaon, the total rainfall was more or less considerably below the average.

In Eastern Rajputana also dust storms, with light showers, occurred sporadically after the 6th, but here also the total fall was below the average at the majority of the recording stations. In Central India, rain was more frequent, and at Agar, Rutlam, and Bhopal, the average of the month was exceeded by 2 or 3 inches; but there was a large deficiency in the northern part of Rewah.

In the North-Western Provinces and Oudh, the rainfall was deficient in Kumaon, Rohilkhand, and the Gangetic Doab, and most parts of Oudh. But there was an excess in the northern part of the Meerut division, at some stations to the south of the Ganges, and in the most eastern districts, where rain was general and in some cases heavy between the 13th and 15th. Over Behar the excess was general and considerable, and especially so in Tirhoot, Patna, and Gya, where the rain was very heavy between the 16th and 18th. At Mozufferpore, 12½ inches in the 24 hours was registered on the 17th, and at Durbhanga 8⅔ inches on the 18th. In Bhagalpur, Sikkim, and Chittagong, the average was much exceeded, and also in Orissa, but in the Dacca division, on the plains north of the Ganges, and on the greater part of the delta, there was a more or less considerable deficiency.

The rains set in, as usual, with the formation of a local barometric depression, which, in the present case, first appeared over a portion of the Gangetic delta on the forenoon of the 14th. On the morning of the 15th it had travelled to the north-west, and lay over Hazaribagh. On the 16th it had progressed somewhat further in the same direction to the south of Benares; after which, on the 17th and 18th, its path recurved to the north-east till it reached Purneah, where it broke up. The very heavy precipitation in Tirhoot and Bhagulpore, and in Southern Behar, took place on these three days. The charts on Plate VIII shew the position of the storm on the 14th, 15th, 16th, and 17th at 10 A.M.

In Assam and Cachar, as in Eastern Bengal, the rainfall was deficient; at Goalpara to the extent of more than one-third of the normal amount, and at Dhubri of more than one-half. Elsewhere, however, it was not so great. But at Cherra Punji there was a deficiency of nearly 30 inches on the average of 114 inches.

In the Central Provinces, on the other hand, the average was exceeded at most stations, and especially at Chindwara and Bhandara. Here heavy and general rain set in at the same time as in Bengal, but all the earlier portion of the month had been showery, though the falls were light. In Berar also, an excess was universal, greater in the south and on the plain of the Poorna river than on the hills to the north. In Hyderabad also, with very few exceptions, the rainfall of the month was more or less above the local average.

In Bombay, there was but little rain in the southern districts of the Deccan throughout the month, and in Gujarat scarcely any before the 24th, and except on that day, the falls were light. On the South Concan and on the Ghats, rain fell daily, and on the coast it was

heavy on the 5th, 12th, and 24th and subsequent days, but it was not until the latter date that the monsoon set in strongly. In the Deccan, all through the middle of the month, any rain was light and sporadic, and the falls were separated by long rainless intervals up to the 24th, and in the South Mahratta country up to the end of the month. In Gujarat, Sind, and Cutch, the fall of the month was generally below the average, though not greatly so. At Colaba, the deficiency was greater, and there was also a deficiency in Dharwar, but elsewhere, as a general rule, the fall was in excess of the average, though not greatly so.

In Madras, except on the west coast, in some of the districts bordering on Mysore, and in the extreme south, there was also, as a rule, rather more than the average; but in Malabar and South Canara there was a decided deficiency, and a slight general deficiency in Mysore.

In Ceylon, the fall was below the average in the south-west and on the hills, but elsewhere there was about an average or rather more.

On the Arakan coast, the fall was rather short, but in Pegu and Tenasserim, at most stations, there was quite an average fall. At the Bay Islands the deficiency was but small.

July.—The first part of this month was rainy throughout Northern India, but on the North-West Himalaya and in the Punjab, there was little or no continuous rain; and after the 19th, a break set in over a large portion of North-Western India, and subsequently extended to the North-Western Provinces, the Central Provinces, and the Concan and Deccan, so that in the latter part of the month the rainfall was widely deficient.

On the North-West Himalaya, storms occurred daily with heavy rain and frequently with hail up to the 19th, after which rain almost ceased. On the plains of the Punjab, the rain was never general, but there were some heavy falls of 2 or 3 inches in the 24 hours, at intervals, over portions of the province; but these also ceased on the 18th or 19th, and consequently the total fall of the month was more or less short of the average at nearly all stations, except those in the west of the province. The deficiency was greatest at Dharmsala, and on the plains at Hoshiarpur and Jullunder, also at Delhi and Kurnal, Gujarat and Gurdaspur.

In Rajputana, rain fell frequently up to the 18th, but after that date, except for a single day at Ulwar, Deoli, and Kotah, there was no rain of importance, and after the 22nd none, except a few light showers in the south of the province. Some stations in the north-west, and Mount Abu alone had an average fall or rather more. In the eastern states, it was very deficient. The deficiency was still greater in the Central India states, although, up to the 24th, rain was more frequent than in Rajputana, and in the most eastern state (Rewah), there was a moderate fall between the 28th and 30th, not however elsewhere.

In the North-Western Provinces and Oudh, there was general and more heavy rain on the 6th, and again between the 16th and 25th. But during the remainder of the month, there were merely local and for the most part light showers. Nevertheless, in Oudh, the rainfall was in general rather above the average, and greatly so at Fatehpur. A few other stations, *viz.* Agra, Moradabad, Etawah, Banda, Allahabad, Benares, Ghazipur, and Jalaun, also registered rather more than an average fall. But Bareilly, Budaun, and the most southerly stations of the province had a large deficiency.

In Bengal, the Presidency and Burdwan divisions had an excessive fall, and some, but not all of the eastern districts, and some parts of Behar, but throughout the province the rain was very irregularly distributed, and in some of the northern districts there was a considerable deficiency. In Behar and the Bhagulpore division, there was but little rain during the first half of the month, but it was more frequent in Chutia Nagpur and Orissa. Nevertheless there were frequent fine intervals in nearly all parts of the province. In Assam and Cachar, except in the upper districts of the Assam valley, the rain was generally below the average, and greatly so on the Khasi and Garo Hills.

In the Central Provinces, the local variations were great, and although at Sambalpur and some few other stations the fall more or less exceeded the average of the month, on the mean of the whole province it was rather deficient than otherwise. There was no general interruption of the rains, but during the latter part of the month the fall was partial and light. In the Berars, however, there was a greater or less excess at nearly all stations and especially at Chikalda and Akola, where the fall was 14 or 15 inches above the average of the month. But this was due to the very heavy rain on the first two days of the month, followed by another heavy fall on the 9th, and again, but more locally, on the 14th. During the latter part of the month, the falls were very light.

A slight excess of rain was also very general, nearly throughout Hyderabad, but the falls were frequently interrupted and the total amounts small as compared with Berar. After the 21st there was no general or heavy rain.

The rainfall was heavier than usual over the greater part of the Bombay Presidency, especially in the Concan and on the Ghats. But, even here, there was no rain of importance on the last five or six days of the month. In Gujarat, there was scarcely any ; and in Sind and Cutch no rain after the 18th, so that, in the north of the Presidency, the rains were interrupted at the same time as in the Punjab.

The rainfall of Northern and Central India in the first half of July was determined by a series of small cyclones (small as regards intensity, though not as to the area affected), cyclones of the usual monsoon type, which were formed in the north of the Bay of Bengal and travelled westwards across India. The first of these was formed over the head of the Bay on the 26th and 27th June. It was felt on the coast of Orissa on the 28th, but the centre, at which the barometer stood below 29·2, did not cross the coast until the forenoon of the 29th. On that of the 30th, it was approaching Sambalpur. On that of the 1st July, it lay between Raipur, Seoni, and Nagpur, and on that of the 2nd having crossed the Satpuras, between Hoshangabad and Indore, bringing a torrent of rain on the hills north of Berar, flooding the rivers and breaching the railways. On the following day, its movement was more rapid, and on the forenoon of the 3rd, the centre lay over Katiwar and Cutch, after which its further progress is no longer traceable in the charts.

Before this storm has completed its course, another was forming in the north of the Bay. It appeared on the coast of Bengal on the 4th and 5th, but apparently did not progress further. On the 6th, another small vortex appeared on the Orissa coast, and, moving westward on the same course as the first storm, lay near Seoni on the 9th. The barometric depression of this storm was comparatively slight, and after the 9th, it became merged in the general trough of depression which extended from Orissa to the North-Western Provinces and the Punjab. Between the 11th and 12th a fourth vortex was formed

over the Bay, and the centre passed False Point on the forenoon of the 13th, and on the 14th lay between Ganjam and Sambalpur. After this, it also disappeared in the general depression of Northern India. For some days after its disappearance, general rain fell over Northern India, and although slight local depressions appeared over Bengal and Berar, there were no further travelling storms. Then the trough of minimum pressure moved northwards to the Gangetic plain and the neighbourhood of the Central Himalaya. Westerly winds began to set in over North-Western India, and all but slight sporadic rain gradually ceased.

In Madras, rain fell daily on the highlands above the Eastern Ghats of the Northern Circars, and on the plain, as far south as Cuddalore, occasional showers occurred, at intervals, more or less throughout the month; but more frequently in the earlier than in the latter part. In the southern part of the Presidency, rain was but slight, but on the west coast, there was scarcely a day without rain up to the 29th. In general, the rainfall of the month exceeded the average; and especially so in the northern districts and zemindaries. On the west coast, however, it was short of the average, and especially so at Cannanore and Mangalore.

In Mysore and Coorg, except in the first week and on the last three days, rain was very frequent, but not very heavy, and, on the whole, the fall was slightly but generally below the average.

In Ceylon also, at many stations, the fall was somewhat deficient. In Burma, except at Akyab, Sandaway, Rangoon, and Shwegyin, there was, in general, rather more, but there was a small deficiency at Port Blair and Nancowry.

August.—This month was characterized by a prolonged and extensive drought, the continuation of that which set in in the latter part of July. Not indeed that it was absolutely rainless over any considerable area. Even in the Punjab, where it was most prolonged, there were a few showers, and a couple of days of heavy rain at stations near the hills in the north of the province, and on the hills of Kangra and Sirmoor some very heavy showers fell during the first week. But all such rain was more or less local, and everywhere in the Punjab, Rajputana, Central India, the North-Western Provinces and Oudh, the rainfall was largely deficient.

In Rajputana, save at a few stations on the borders of Gujarat, there was no rain before the 18th or 19th, and no heavy or general rain before the 29th or 30th of the month. In Central India, there were a few light showers on the first five days, chiefly in Rewah, but otherwise this province also was rainless up to the 18th. In the North-Western Provinces, except in the Meerut division and the Gangetic Doab, the break was less absolute, and on the hills, and in the eastern and south-eastern districts, there were some heavy showers on the first six days. But the only general rain was on the 20th and 21st, and even up to the end of the month any further rain was light and sporadic.

Bengal was less affected by the drought. The districts to the west of the Hooghly, and some parts of Chutia Nagpur, had more than an average fall, and so also had Sikkim, the Bhootan Duars, and Cooch Behar, but with these and some slighter local exceptions, the rainfall of the month was below the average, and especially so in Behar. Assam had, on the whole, about an average fall, with local variations in both directions; in Cachar a considerable excess.

In the Central Provinces, the deficiency in some parts was scarcely less than in Central India, &c. But around Nagpur and in the Godavery valley the average was exceeded by a few inches. In this province the break in the rains, although not amounting to an absolute cessation of rain, was very strongly marked, and lasted till the 18th. And in Berar, where it was more developed, except some slight showers, on the 1st, there was virtually no rain before the 19th. After this date, rain was frequent and heavy, and as the final result, the fall of the month at nearly all stations was up to, or beyond, the average, and especially so on the plain of the Poorna river. So also throughout the state of Hyderabad, where, up to the 9th, there was no rain of importance. On this and the following day, there was heavy but partial rain, and again on the 15th and 16th. After the 19th the rain was more general, and by the end of the month, nearly every station had received more or less in excess of the normal average, and especially Berar, Mehduck and Nuldroog.

In the Bombay Presidency, there was a great deficiency in Gujarat, the Concan, and some parts of the Western Deccan, and Sind and Cutch were rainless. But Khandesh and the adjoining districts and Sholapur and the southernmost districts had an average fall or more, especially Sholapur.

During all the earlier part of the month, as during the latter part of July, the region of lowest pressure lay apparently in the Upper Punjab, and along the foot of the Himalaya it was lower than to the south. There was a local secondary minimum in Chutia Nagpur and Sambalpur, but this was cut off from the depression of the Punjab by a region of higher pressure in Central India and Oudh, and the North-Western Provinces. This lasted till the 19th, when the pressure fell over Central India relatively to the Gangetic plain and the normal trough of low pressure to the south of the Ganges was once more re-established. In the last ten days, one or two small cyclonic vortices crossed the coast of the Northern Circars and travelled to the north-west towards the Central Provinces; but the barometric depression in these was very slight, and after a day or two they disappeared in the general trough of low pressure.

In Madras, the August rainfall was, on the whole, quite equal to the normal average, or indeed rather above it; but with local variations; and in Mysore, there was an universal excess of from 1 to 7 inches. In general, the falls, though frequently interrupted, were well distributed throughout the month. In Ceylon, there was a considerable excess at Colombo and a slight excess at other stations on the west coast and on the hills, but on the east coast a slight deficiency. In Burma, there was a slight general deficiency, but at the Andamans and Nicobars rather more than the local averages. It is noteworthy that, at these islands, from the 6th to the 15th, the rainfall was almost entirely suspended, and that this coincided with the period of greatest drought in Rajputana and Central India, &c.

September.—In the Punjab, after the prolonged break in July and August, the rains set in again at the end of the latter month, as already described, and in the first week of September there was heavy general rain in the province, more especially on the 5th and 6th. This was the last expiring effort of the monsoon. After the 8th, only light local showers fell, and by the 15th the rains had come to an end on the plains of the Punjab. On the hills, there were showers again between the 26th and 29th; but Rawalpindi, alone of the lower stations, shared this fall. So heavy, however, was the rainfall of the early

part of the month, that the September average was universally exceeded, and especially so at Ludhiana, Lahore, and Ferozepore.

In Rajputana, rain fell daily also during the first eight days, after which it ceased at the most western stations; but in the eastern states it continued till about the 18th, and in the southern states showers fell at intervals up to the end of the month. Here also the rainfall generally exceeded the average, but there were a few local exceptions, the chief of which was Banswara.

In Central India, there was daily rain in the western states up to the 15th, and after that, occasional showers at intervals. In Rewah, the rainfall of the earlier part of the month was more interrupted, but was prolonged till the 20th, after which it ceased. In general the total fall exceeded the average, and most so at Goona and Bhopal.

In the North-Western Provinces, the rain of the early part of the month was much less general and more interrupted. There were a few heavy falls, but they were quite local. Over the greater part of the province, the rain ceased after the 15th, but in the eastern and southernmost districts, it continued at intervals up to the 20th, but not beyond. Consequently, the rainfall of the month was generally below the average, a rule to which there were but few exceptions.

The change in the distribution of pressure that marked the close of the rains in the upper provinces was essentially of the same kind as that which, in July, ushered in the prolonged drought. During the latter part of August and the early part of September, a trough of low pressure extended from the Punjab in a south-east direction to Orissa with a higher pressure on the north in the Ganges valley. There were not in September any travelling cyclones, but local minima were formed on several occasions within this trough. About the 15th, a relative rise of pressure in Central India and Eastern Rajputana separated the low pressure region of Chutia Nagpur and Sambalpur from the Punjab minimum, and, with this rise, rain ceased throughout the greater part of North-Western India: westerly and north-westerly winds setting in on the plains.

In Bengal, rain fell almost daily in Orissa, the Burdwan, and Presidency divisions, in the first half of the month, but during the remainder, in this portion of the province, and in the northern districts and Behar throughout the month, it was light and much interrupted. Nearly everywhere, the total fall of the month was deficient, and to a much greater extent than in August. The deficiency amounted, on an average, to about half the usual fall. In Chutia Nagpur and Sirguja, as also in Cuttack, there was however a certain excess.

In Assam, it was only in the easternmost and southern districts that the fall was not below the average. At Tura it was more than 15 inches less.

In the Central Provinces, rain fell steadily, and sometimes heavily, during the first half of the month, and during the latter part was less interrupted than in the provinces previously noticed. Everywhere the fall exceeded the average more or less considerably, and greatly so in the Nerbudda valley; there being an excess of more than 18 inches at Nursingpur and of more than 13 inches at Hoshangabad. Berar shared the heavy rainfall of the Central Provinces, and also had a considerable excess, to the extent of about double the normal amount. In Hyderabad also, the fall was generally more or less above the average, but except at one or two stations the excess was smaller. There was a very general break from the 10th to the 16th, but otherwise the falls were repeated almost daily at many stations up to the end of the month.

In Bombay, except in Sind and Cutch, rain was very general up to the 14th or 15th, and after a nearly rainless interval of 6 or 8 days, again in the latter part of the month; the chief exceptions in addition to the above, being the most southerly stations on the Madras frontier, some of which were almost rainless. In the central and southern districts of the Deccan, the total fall was somewhat short of the average; but in Khandesh, Poona, Satara, and in the Concan, it was more or less excessive, and, in general, also in Gujarat.

In Madras, with merely local and unimportant exceptions, and also in Mysore, the rainfall was more or less largely deficient. On the west coast indeed, rain was frequent, but by no means heavy during the first half of the month; but over the greater part of the Presidency, a few insignificant local showers were the only rain recorded, excepting in the Carnatic on the 15th, and on the last three days of the month. In Ceylon the total fall was below the average; but less considerably.

In Burma, there was about an average fall, on the whole; though with many local irregularities, and rain fell pretty steadily, without any general interruption of importance. At Port Blair, the fall was slightly below, at Nancowry somewhat above the average.

October.—In the Punjab, the North-Western Provinces, and Bengal, October was a very dry month. In the Punjab, beyond a few drops at Sirsa on the 4th, and at Hissar and Rohtak on the 20th, there was no rain on the plains; and on the hills only moderate showers on the latter date. There were, however, some falls of snow in Cashmere, as far north and east as Leh, and in Chamba, four times during the month, snow fell down to levels of 10,000 feet, and even lower.

In Rajputana, there was no rain at most of the northern stations nor in the extreme west; but in the other parts, there were slight showers at one place or another almost daily up to the 13th, after which there was nothing of importance. And there were similar local showers in the western states of Central India, repeated between the 18th and 20th, while in the Eastern States, only the latter fall was received. At Jodhpur, Erinpura, and a few other stations in Rajputana, and in Central India as far east as Bhopal and Goona, the total rainfall exceeded the average of the month, but it was deficient in the eastern states.

In the North-Western Provinces and Oudh, all the western half of the former province and the whole of Oudh was rainless, and, although there was a little rain in the eastern districts between the 19th and 21st, it nowhere amounted to an average fall.

In Bengal, the rainfall was very deficient, the rains having virtually come to an end in September, an unusually early date. And, although there was a general fall in the central and eastern districts and Orissa between the 11th and 13th, and in Behar and the western divisions on the 20th and 21st, and a few local showers on some other dates, the total amount was really insignificant, and there was a very considerable loss of agricultural produce in consequence. In Assam the fall was almost equally deficient.

In the Central Provinces, the rain from the 19th to the 21st was very general and locally heavy, and there had been light local showers on several days in the earlier part of the month. Hence, over a great part of the province, the total fall was quite up to, or in excess of, the average, and only in the more easterly districts, was the deficiency at all considerable. In Berar, where the rainfall of the 19th and 20th was still heavier, a large excess was universal.

There was a similar excess in the north-west of the Hyderabad State, but in the remainder the rainfall of the month was rather below the average. In Bombay, the rainfall was unusually heavy in Khandesh and the northern districts of the Deccan, as far south as Mahableshwar and Satara, and in the Concan and at Belgaum. In these parts of the Presidency, the rain was almost uninterrupted up to the 23rd. But in other parts there was either only an average or less, and Sind was rainless.

The very heavy rainfall of Berar, Khandesh, and the surrounding region, on the 20th and 21st, was due to a depression which appeared over the North Deccan, and was probably formed there on the first of these dates, and on the following day moved towards Nagpur.

In Madras, from Vizagapatam southwards, the rainfall was very heavy. As early as the 2nd nearly 5 inches fell at Madras, and during the greater part of the month, there appears to have been a barometric depression over the bay, not far from the Coromandel coast. Consequently, rain was frequent throughout, and there was a remarkably heavy and general fall in the Carnatic on the 15th and 16th. It was in the northern and central districts of the Carnatic, at Ongole, Nellore, Madras, and in South Arcot that the abnormal fall was greatest, amounting to from 9 to 15 inches in excess of the average. But it extended also to the plateau above the Eastern Ghats, where Cuddapah and some other stations had an excess of between 6 and 7 inches, and Hosur on the borders of Mysore one of 7 inches. In Mysore it was as general, and, on the whole, as considerable as in the Carnatic; and it prevailed on the west coast also, except at Mangalore and Cannanore.

In Ceylon, rainfall was equally abnormal in the north of the island. At Jaffna and Manaar it exceeded the average by 12 inches and more. But it was less in the south, and on the hills at Kandy and Newera Eliya, it was scarcely up to the average of the month.

In Burma, on the other hand, except at Thyetmyo in the extreme north and at Mergui in the extreme south, the fall was generally deficient; on the Arakan coast by from 5 to 8 inches, and at Tounghoo and Moulmein by 5 or 6 inches. At Mergui, however, the fall was $7\frac{1}{2}$ inches over the average. In Burma, the rains continued pretty steadily up to the 10th, after which there were only local and intermittent showers. At Port Blair and Nancowry, there was a deficiency of about 6 inches, or nearly half the average.

November.—Over a large part of Northern India there was but little rain in this month. But between the 10th and 15th, a very heavy fall of snow took place on the North-West Himalaya, which exercised an important influence on the winds and temperature of the plains up to at least the end of the year, and this was accompanied by rain on the plains of the Punjab, and in one or two of the adjoining districts of the North-Western Provinces. Simultaneously therewith, a small cyclone was formed in the neighbourhood of the Andamans, and subsequently progressed on a northerly course to the Arakan coast, where it passed near the port of Akyab; but there is no present reason to regard this simultaneity as other than fortuitous, except in so far as both may have been brought about by a general fall of pressure over the whole Indian region.

The disturbance which gave rise to the heavy precipitation on the North-Western Himalaya had its origin in North-Western India, and was of the usual character of those disturbances which bring about the cold-weather rainfall. During the first days of the month a tongue of high pressure extended from the Indus valley across Rajputana and

Central India with a slightly lower pressure along the foot of the North-Western Himalaya. On the 5th, a considerable fall of the barometer over the western plains reduced this tract of maximum pressure to an isolated area on the plateau of Eastern Rajputana and Central India; and a further fall on the following days in the same region pushed it further south towards the Deccan and Hyderabad. On the 10th it lay over the central region of the peninsula, and a ridge extended thence to Behar and the lower half of the Gangetic plain, separating the two independent areas of low pressure, the minimum of the one embracing the whole of the western desert, that of the other, a region between the Andamans and Nicobars, and extending thence towards the coast of Tenasserim. This disposition is shewn in the first chart of Plate IX. It deserves noticing with reference to the views which have been put forward as to the determining causes of cyclones, that, for several days previously, the barometer had been falling more or less over the whole of India, and it was not, therefore, an increase of pressure over the land (the peninsula) that determined the relative depressions in North-Western India and the Andaman regions respectively, but these latter originated in virtue of local action, in the local intensification of an universal fall of pressure.

The heavy snowfall of Cashmere, Chamba, and Kulu began on the 10th. At Simla, there had been rain and snow two days earlier. In Cashmere, snow fell and lay at Srinagar (5,276 ft.), and in Kulu it fell down to 4,000 ft. In Bissahir the total fall between the 10th and 13th yielded 13 inches of snow water according to Mr. Minnikin's register at Kilba; but it is difficult to resist the impression that this return which was sent in by a native subordinate, a comparatively uneducated man, is not quite trustworthy. At Simla, one register gives about 5 inches, another about 7 inches, of snow water for the four or five days. On the plains, from 3 to upwards of 4 inches of rain was registered at Rawalpindi, Jhelum, Gujarat, and Gujranwala, and over 1 inch at Sialkot and Amritsar. To the south and east it was less, and the fall extended beyond the Jumna ot Meerut and Moradabad, where it was very slight. On the south it just reached to Bickanree.

The snow and rainfall of the 10th raised the pressure greatly along the foot of the Himalaya, and indeed all over the Punjab, and in a minor degree all Western India, and on the forenoon of the 11th the area of low pressure was restricted to the southern and rainless portion of the western desert, as is shewn in the second chart on Plate IX. The rise continued on the 12th, being greatest in the Indus Valley, where the temperature had fallen more than 15° with the cool northerly winds; but the position of the minimum changed but little, as may be seen on the third chart of Plate IX. And now the current of north-east winds from the cooled region of the rainfall advanced eastward across the western desert, accompanied by the usual barometric rise, and displacing the region of minimum eastwards, until it merely formed a band of slight relative depression between the advancing wave and the persistent region of maximum in the Deccan and Hyderabad. This is shewn on the 4th chart of Plate IX.

The Andaman and Akyab cyclone, not one of great severity, began and progressed simultaneously with the storm in the north-west, but it lasted till the 14th, on the forenoon of which day it passed across the coast line a little to the south of Akyab, and then broke up among the hills of the Arakan Roma. Its progress on the first four days is represented on Plate IX. The data are partly inserted from ship observations obtained by Mr. Eliot.

Owing to the heavy rainfall of the 10th to 15th November in the Punjab, the rainfall of the month somewhat exceeded the average at most stations, and especially at the hill stations, and at Gujarat, Jhelum, Gujranwala, and Rawalpindi on the plains. But in Rajputana, save at Bickaneer, there was scarcely any rain, and none whatever in Central India. In the North-Western Provinces, the rain was restricted to the hill districts and to the Meerut and Rohilkhand divisions; and here, as in the Punjab, the average was exceeded. In Bengal, with the exception of Chutia Nagpur, there was an universal deficiency, and no rain whatever except in the westernmost districts, Orissa, and, as already mentioned, in Chutia Nagpur. This fell on the first three days of the month, and had therefore no connection with the rainfall of North-Western India. In Assam, there was a heavy shower on the 15th at Silchar, and a few drops were registered on one or two other days at some stations, but most parts of the province were rainless, and, except at Silchar, the fall was nowhere up to the average of the month.

In the Central Provinces, there was a little rain on the first three days in the eastern and southernmost districts, but none elsewhere. And in Berar, a little fell on the same days chiefly in the southern half of the province. On the Gawilghar hills, and most parts of the Poorna valley, there was no rain.

In Hyderabad, light sporadic showers fell up to the 6th, but not afterwards. Everywhere the total amount was below the average.

In Bombay, from Bombay and Nassik southwards, in the Concan and Deccan, the first six days were also showery, the heaviest rain being at Bijapur. At this station, and at Karwar and Honawar, the total fall was 2 or 3 inches above the average, but in general it was below it, and all the northern parts of the Presidency was rainless.

In Madras, the rain ceased in the northernmost districts on the 1st or 2nd, and progressively later to the south, so that from the mouth of the Kistna and beyond, it lasted to the 6th or 8th, in South Arcot, Trichinopoly, and Coimbatore, to the 9th or 10th, and in Tinnevelly to the 15th. There was also a fall more or less all over the Carnatic between the 17th and 20th. It is noteworthy, as an additional illustration of the conditions of cyclone formation prominently formulated by Mr. Eliot, that the rainless interval that separated this from the rainfall of the early part of the month, in all but the southernmost districts, coincided with the formation and progress to extinction of the Andaman and Akyab cyclone. In most parts of the Carnatic and as far north as Vizagapatam, and also on the west coast, the total rainfall exceeded the average of the month, but there were some local exceptions to the rule. In Mysore, an excess was universal, and also in the north and east of Ceylon, and at Galle, but not in all parts of the island.

In Burma, the beginning of the month was fine, but there was a rainy period extending from the 7th to the 15th, corresponding to the generation and duration of the cyclone. The heaviest rainfall measured in this storm was at Bassein, where it amounted to nearly 12 inches on the 12th and 13th. On the same days from 3 to 5 inches were recorded at many other stations in Pegu. In Arakan, the heaviest rain was at Sandaway, where upwards of 6 inches was measured on the 13th. In general, owing to this storm, the total fall exceeded the November average more or less considerably; but not at Akyab, to the south and east of which the storm passed, and which therefore did not experience the passage of its rainiest quarters.

Both at Port Blair and Nancowry, and especially the latter, the rainfall of the month was excessive. At the latter the 18th, 19th, and 30th, were the only days without rain, and from the 8th to the 11th, that is, during the formation of the cyclone to the north, it averaged nearly 2 inches a day.

December.—Over a great part of Northern India, this month was a dry or even drier than November. In the Punjab, no rain fell before the 28th, and what fell between this and the 30th on the plains was restricted to the central and some parts of the eastern districts, and both there and on the hills the fall was light. While therefore many parts of the province were rainless, in none, except, perhaps, at Jullunder, did the total amount equal an average fall. In Rajputana, Central India, the North-Western Provinces and Oudh, there was no drop of rain during the month.

In Bengal, there was an unusual and most inopportune fall, lasting for two days, *viz.*, the 4th and 5th, in Calcutta and the districts around, which coincided with, and marred, the opening ceremonial of the Calcutta International Exhibition and the festivities of the following day. In the more eastern districts and in Cachar, it lasted two days longer. In its essential characteristics, this storm appears to have been a cyclone, but one of very feeble depression, and in which the winds never attained to any considerable strength. It was generated over the Bay and passed apparently on a north-easterly course across the Sunderbans towards Cachar. If it is to be counted as a true cyclone, it occurred nearly a month later than any hitherto recorded so far north in the Bay of Bengal. As the result, the rainfall of all parts of Bengal affected by the storm, that is to say, of all except the most northern districts and the western divisions of the province, was more or less considerably in excess of the average. Especially was this the case in Eastern Bengal, where the excess amounted to from 4 to 7½ inches. It was equally great in Cachar.

In the Central Provinces, except at Sambalpur and Raigarh, which lay within the region of precipitation of the above storm, there was no rain; and none whatever in Berar, Hyderabad, nor with the most trivial exceptions in any part of the Bombay Presidency.

In Madras, the Northern Circars and the adjacent highlands caught a slight precipitation from the Bengal storms; and, far to the south, Tranquebar and Negapatam had it on the preceding days. With these exceptions, there was no rain in the Presidency before the 10th, when a rainy period set in all through the Carnatic, and continued in the central districts till the 15th or 16th; and from the Cavery southwards, with fine intervals to the 25th or 26th. From the 13th to the 26th, similar rain prevailed in Malabar and Travancore. In the districts around Madras, the rainfall of the month exceeded the normal average by some inches, and, as a rule, throughout the Carnatic, was rather above than below it, but the excess was less general than in November. In Mysore and Coorg, as in the previous month, an excess was universal. In this province it rained daily from the 12th to the 16th.

In Ceylon, on the other hand, the fall of the month was deficient, except at Jaffna and two other stations.

In Burma, showers fell during the first eight days, chiefly on the Arakan coast, being evidently a local effect of the disturbances, which chiefly affected Lower Bengal. In the east of Pegu and throughout Tenasserim there was no rain. At Port Blair there was a large excess and a small one at Nancowry; at both of which stations the month was more or less rainy throughout.

The characteristic features of the rainfall of 1883, as regards Northern India, were a heavy fall of rain over a great part of North-Western India, and an excessive fall of snow on the North-West Himalaya in the latter part of January, followed by a dry February, except on the hills, a somewhat showery March, and a second spell of dry weather lasting from the middle of March to the end of the third week in May, and of exceptional dryness in the first of that month. While this great dryness prevailed with westerly winds in North India proper, heavy rain fell in Cachar, producing disastrous floods, and when it ceased, a copious fall took place over the hitherto rainless provinces of the North-West, with much snow on the outermost snowy range of the North-West Himalaya. In June, the rains set in in Bengal about the usual date, and penetrated rapidly to Behar, but North-Western India remained very dry and nearly rainless, up to nearly the close of the month. Sporadic but locally heavy rain followed in the first three weeks of July, and then set in a drought which, first appearing in the Punjab, gradually extended to the east and south, until it prevailed to the confines of Bengal, to the Satpuras, and even beyond into Khandesh, Berar, the Concan, and Hyderabad. This lasted for a month or six weeks, and was followed by a heavy burst of rain in the first half of September, which brought the rainy season of North-Western India to a close. Bengal was but little, if at all affected by this drought, but the rains ceased at the end of September, an unusually early date, and the loss of agricultural produce was consequently very great in some parts of this province. The latter months of the year were generally dry, but falls of snow took place on the North-West Himalaya in September and October, and a very heavy fall, accompanied with rain in the Punjab, shortly before the middle of November; a very unusual occurrence. From this time to the end of the year no further rain fell; except in Lower Bengal, Orissa, and Cachar, owing to the passage of a cyclonic storm early in December.

In the peninsula, the first five months of the year were, in general, either rainless or brought less than an average fall; the chief exceptions being the first three weeks of March, and locally in April and May. On the west coast, the monsoon rains did not set in steadily at Bombay until nearly the end of June, although preceded by one or two stormy bursts; and further south, and in the interior of the peninsula, the rainfall was comparatively light, but, in the Carnatic, the season was more rainy than usual. July was very rainy, more or less throughout the peninsula; and in August, to the south of the region affected by the drought of North-Western India, the rain was more copious than usual. September was rather dry, except in the Concan and Northern Deccan, but in October, the dryness of the Bengal Province was fully compensated by the heavier rainfall of the greater part of the peninsula. In November, the limits of the rainfall area gradually retreated southwards, and in the peninsula there was a dry interval, during which a cyclone was formed in the east of the Bay and passed northwards to Akyab, coinciding also with the unseasonable Punjab rain of this month. But nevertheless, as a rule, in the southern and eastern parts of the peninsula, and especially in Mysore, the rainfall was more than usually copious in this month. December also, except the first portion of the month, was very rainy in Southern India, and exceptionally so on the Mysore plateau.

As the final result of the year, the rainfall was deficient in nearly all parts of Northern India, and especially in the North-Western Provinces and Lower Bengal; but it was only in the latter province that the drought was such as to cause serious losses. In the

peninsula, on the other hand, the fall was above the average, in all provinces, and in such measure as almost exactly to compensate the deficiency of Northern India. This is shewn in detail in the following table, which differs only from that given in previous reports, in that the provinces of the Eastern Peninsula are given in a separate summation of the totals, and in a correction of the assigned areas of the Punjab, the North-Western Provinces and Oudh, the Central India states and Sind and Cutch, all of which were under-stated in previous tables :—

TABLE XXVII.—*Geographical Summary of rainfall anomalies in 1883.*

	Rainfall Provinces.	Area: Square Miles.	Number of Stations.	Average rainfall.	Mean, 1883.	Mean Excess or Defect.	Total Excess: square miles × one inch.	Total Defect; square miles × one inch.
I	Punjab Plains	120,000	29	21·38	17·18	—4·20	...	504,000
II	North-Western Provinces and Oudh	83,500	41	37·12	29·02	—8·10	...	676,350
III	Rajputana	67,000	19	27·93	22·83	—5·10	...	341,700
IV	Central India States	91,000	21	41·32	36·82	—4·50	...	409,500
V	Behar	30,000	13	43·38	38·08	—5·30	...	159,000
VI	Western Bengal	38·000	10	49·64	47·24	—2·40	...	91,200
VII	Lower Bengal	54,000	29	66·71	53·61	—13·10	...	707,400
VIII	Assam and Cachar	61,000	17	95·22	89·72	—5·50	...	335,500
IX	Orissa and Northern Circars	27,000	16	47·82	48·32	+0·50	13,500	...
X	Central Provinces, South	61,000	19	49·92	55·62	+5·70	347,700	...
XI	Berar and Khandesh	43,000	11	34·67	56·17	+21·50	924,500	...
XII	Gujarat	54,000	10	35·62	35·42	—0·20	...	10,800
XIII	Sind and Cutch	68,000	10	8·80	6·90	—1·90	...	129,200
XIV	North Deccan	48,000	14	29·46	31·46	+2·00	96,000	...
XV	Conkan and Ghats	16,000	12	143·81	164·21	+20·40	326,400	...
XVI	Malabar and Ghats	18,000	8	115·00	117·90	+2·90	52,200	...
XVII	Hyderabad	74,000	19	31·76	41·66	+9·90	732,600	...
XVIII	Mysore and Bellary	58,000	16	28·85	35·25	+6·40	371,200	...
XIX	Carnatic	72,000	40	34·25	39·45	+5·20	374,400	...
		1,083,500	...	...	...	...	3,238,500	3,364,650
XX	Arakan	11,000	6	154·95	160·75	+5·80	63,800	...
XXI	Pegu	32,500	7	73·06	74·36	+1·30	42,250	...
XXII	Tenasserim	10,500	4	172·02	169·22	—2·80	...	29,400
		1,137,500	...	...	...	...	3,344,550	3,394,050

The following is the classification of the stations adopted for the rainfall provinces in the above table :—

I.—PUNJAB PLAINS.—All the stations enumerated in the Punjab Province in Table XXV, excepting *Abbottabad*, *Murree*, *Dharmsala*, and *Simla*.

II.—NORTH-WESTERN PROVINCES and OUDH.—All the stations enumerated under these provinces in Table XXV, excepting *Dehra*, *Chakrata*, *Mussooree*, *Ranikhet*, *Naini Tal*, *Almora*, *Dudhi*, *Jhansi*, *Lalitpur*, *Srinagar*, *Pauri*, *Pithoragarh*, and *Rudarpur*.

III.—RAJPUTANA.—All the stations in the table under this heading, excepting *Partabgarh*, *Bickaneer*, and *Pachbudra*.

IV.—CENTRAL INDIA STATES, &c.—All the stations enumerated under Central India in Table XXV except *Chandia*, *Ramnagar*, *Sihawal*, and *Maihar*, and, in addition to these, *Jhansi* and *Lalitpur* in the North-Western Provinces and *Saugor*, *Damoh*, *Jubbulpore*, *Hoshangabad*, *Nursinghpur*, and *Khandwa* in the Central Provinces.

V.—Behar.—All the stations from *Patna* to *Jamooee* inclusive, in the Bengal list.

VI.—Western Bengal.—*Bhagalpur, Nyadoomka, Godda,* and from *Hazaribagh* to *Gobindpore* inclusive, (except *Sirguja,*) in the Bengal list; also *Dudhi* in the North-Western Provinces.

VII.—Lower Bengal.—All the stations from *Burdwan* to *Pubna* inclusive (excepting *Alipore Observatory* and *Jail*; also from *Dacca* to *Kishoregunj* and from *Maddehpoora* to *Kishenganj,* inclusive, in the Bengal list.

VIII.—Assam and Cachar.—All the stations enumerated under Assam, (except *Cherra Poonjee,*) together with the Bengal stations, *Noakhelly, Comillah,* and *Agartollah.*

IX.—Orissa and Northern Circars.—From *Cuttack* to *Bhuddruck,* inclusive, with the exception of *Banki, Barcepudda, Dhenkanal, Angul, Bispara, Kunjabangarh, Talchir,* and *Keonjhar,* in the Bengal list; and those from *Ganjam* to *Masulipatam* inclusive, (excepting *Gopalpore, Royaghadda, Kotipad, Korapat, Nourangapur, Gunipur,* and *Malkangiri,* in the Madras lists.

X.—Central Provinces, South.—The stations in the Central Provinces, excepting *Raigarh, Sarangarh,* and those specified above as included with the Central India stations.

XI.—Berar and Khandesh.—All the Berar stations (excepting *Makhla*) and *Dhulia, Malegaon,* and *Nasik,* in the Bombay list.

XII.—Gujarat.—The stations in the Bombay list, from *Surat* to *Rajkot* inclusive, and *Deesa.*

XIII.—Sind and Cutch.—All in the Bombay list from *Bhuj* to *Jacobabad* inclusive (excepting *Rahpur*).

XIV.—North Deccan.—All in the Bombay list from *Ahmednagar* to *Bijapur* inclusive, with the exception of the Ghat stations *Lonavla, Mahableshwar,* and *Bavda.*

XV.—Conkan and Ghats.—*Igatpuri* and the omitted stations enumerated in the preceding section, together with those from *Karwar* to *Matheran,* inclusive, in the Bombay list.

XVI.—Malabar and Ghats.—From *Cochin* to *Mangalore* inclusive, (except *Wellington*), in the Madras list; and *Mercara* in Coorg.

XVII.—Hyderabad.—All the stations enumerated under Hyderabad, except *Jalna, Mominabad, Shorapur,* and *Bolarum.*

XVIII.—Mysore and Bellary.—All the stations in *Mysore* and *Coorg,* excepting *Mercara,* and those in the Madras list from *Kurnool* to *Madanapalle* inclusive.

XIX.—Carnatic.—All the stations in the *Madras* list from *Guntoor* to *Cumbum,* and from *Chittoor* to *Tuticorin* inclusive, excepting *Kurnool, Saidapet, Hosur,* and those specified in XVIII.

XX.—Arakan.—*Chittagong, Cox's Bazar,* and *Rangamati,* in the Bengal list; and *Akyab, Kaukpyu,* and *Sandaway* in the Burma list.

XXI.—Pegu.—Those in the Burma list from *Rangoon* to *Toungoo* inclusive (except *Diamond Island*).

XXII.—Tenasserim.—The last four stations in the Burma list.

Taking the difference of the sums of the two final columns and dividing by the sum of the areas, we obtain—0·04 inch as the mean anomaly (deficiency) of the whole area, or, excluding Arakan, Pegu and Tenasserim—0·12 inch.

The anomalies of the latter area for the last 20 years, as compared with the averages now adopted, have lately been recomputed with the following result. Before 1870 the data are somewhat incomplete, as Western Bengal is not represented before 1868 and Hyderabad before 1870. The average rainfall of the whole area is found to be 41·09 inches.

Table XXVIII.—*Annual anomaly of the rainfall of India (exclusive of the Burmese peninsula) from 1864 to 1883, inclusive.*

Year.	Mean Anomaly.	Year.	Mean Anomaly.
	Inches.		Inches.
1864	—5·52	1874	+4·64
1865	—0·77	1875	+2·38
1866	—2·09	1876	—4·49
1867	+2·77	1877	—4·28
1868	—6·63	1878	+6·34
1869	+0·40	1879	+1·69
1870	+1·49	1880	—1·56
1871	+0·93	1881	+0·10
1872	+2·31	1882	+2·64
1873	—4·46	1883	—0·12

Like the shorter series of annual anomalies given in the report of last year the above table gives no support to the idea of a variation of the total rainfall of India coinciding with the sun-spot cycle.

SUMMARY.

The year 1883 was characterized in the Indian area, on the whole, by a low temperature, a mean pressure also slightly below the average, a smaller proportion of water vapour, rendering the atmosphere both relatively and absolutely drier than on the average of past years; but, on the other hand, a slight excess of cloud, and a rainfall more than usually copious in most parts of the peninsula, and less than the normal amount in the greater part of Northern India, the excess of the one region almost exactly compensating the deficiency of the other.

The year opened with rainless, but warm and cloudy weather in Northern India and a frequent prevalence of southerly winds in Central India and the North-West, which resulted in light rain on the 9th and 10th of January, and between the 24th and 28th in a much heavier fall, accompanied with thick snow on the North-Western Himalaya down to a level much below 2,000 feet. This fall brought down the temperature to such a degree that the whole of February was unusually cool, and in a large part of Northern India, lower temperatures were recorded than any that had occurred earlier in the season. A few light falls of snow took place on the Himalaya during February, but on the plains there was little or no rain, and the greater part of Northern and Western India was swept by steady, west and north-west winds, dry and cool, which are indeed the characteristic winds of the cold weather. In the peninsula, save in the Concan, the depression of temperature was not felt, and south-easterly winds prevailed with a somewhat higher temperature, and damper atmosphere than usual in parts of Orissa, the Central Provinces, and the Deccan.

Showery weather set in again throughout Northern India in the beginning of March, and lasted for about 12 days, and, although there was little rain subsequently on the plains in the latter part of the month, some further falls of snow and rain took place on the Himalaya, which, like the previous falls, were chiefly restricted to the outer ranges. In consequence of this rain, the weather remained remarkably cool through the greater part of March; but after the rain had ceased on the plains, dry winds set in, which lasted throughout April and up to the 20th of May. With the continuance of these, the temperature rose, and the latter part of April and the first half of May was characterized by excessive heat and dryness, with steady westerly winds, all over Northern India, up to the confines of Lower Bengal. In Northern and Central Bengal, and still more in Assam and Cachar, the early part of May was, on the other hand, a period of frequent and heavy rain; and in Cachar there ensued a heavy flood in the Barak, which caused much destruction of property and loss of life.

The northern part of the peninsula, and especially the Concan, to some extent shared the dryness of Northern India. In the Deccan and further south, the weather was much of the usual character, occasional thunder storms and showers keeping down the temperature.

In the latter part of May, the weather changed. Heavy rain fell over the whole of North-Western India and North-West Himalaya, but it did not extend to Behar, and this province remained almost rainless. At the same time comparatively dry weather set in in Assam and Cachar.

In the Punjab and indeed throughout the North-West, the heavy precipitation at the end of May was followed by a long spell of dry weather, lasting nearly or quite to the end of June. In the dry western plain and in the Punjab, the temperature rose again, and at some stations exceeded the highest readings recorded in May. Further eastward, the heat was mitigated by occasional dust and thunder storms. In Bengal, the weather was cloudy throughout, and the rains set in on the 13th and extended inland as far as Behar, where the beginning of the monsoon was accompanied with a very heavy fall of rain. There was little rain in the North-Western Provinces and Oudh before the 25th, and in the Punjab before the 27th. On the Bombay side, the monsoon did not set in steadily before the 24th, but there were one or two heavy falls in the earlier part of the month, and in Berar and Nagpur the month was very rainy. But in the Deccan and all down the western half of the peninsula the rainfall was light, and the weather dry.

At the end of June rain became general, except in the Punjab, and lasted through the first half of July. In the Punjab, there were some heavy local falls up to the 19th, but after this date, a drought set in with westerly winds, which rapidly extended to the Gangetic plain, Rajputana, Central India, Bombay, and even to the Deccan and Hyderabad. The drought continued more or less through August, the weather becoming warmer the longer it lasted, until it reached a climax in the second week of August. It retreated as it had advanced, the rain setting in again first in the Central Provinces, the Deccan, and Hyderabad, and advancing, until, on the last days of August, Rajputana and the Punjab once more were visited by heavy rain. Bengal was but little affected by drought at this time, except to some extent in Behar. In the south of the peninsula, in Mysore, and also in Ceylon, there was more than the usual amount of rain. It is noteworthy, although it may have been a coincidence only, that for 9 days, during which the drought was at its height in North-Western India, there was an almost entire suspension of rainfall also at the Andamans and Nicobars.

The occurrence of this drought is of interest, as it followed on a heavy cold weather and spring snowfall on the North-Western Himalaya; heavy and unusually late, and indeed, on the strength of this fact, a retardation of the rains had been predicted in a forecast issued in the beginning of June by the Meteorological Office.

On the cessation of the drought, the rain continued heavy and general during the early part of September, but it came to an end earlier than usual, and the temperature rose as the air became drier, so that the latter part of the month was very warm in the Punjab and North-Western Provinces. In Bengal the rainfall was light throughout, and much interrupted, more especially in Behar and Northern Bengal; and even in Assam the fall was deficient. But while dryness prevailed from an unusually early date more or less throughout Northern India, the rainfall was heavy to the south of the tropic, in the Central Provinces and Berar, the Western Deccan, and Concan, and for the most part continuous.

October continued dry on the plains of Northern India and unusually so in Bengal, where the early cessation of the rains caused an extensive loss of the crops. But there was a heavy fall of rain in the Central Provinces, Berar, the Deccan, and a part of Hyderabad, and in the Carnatic; rain set in at the beginning of October, and was repeated frequently and heavily during the month. Indeed, the rainfall was very copious over the whole of the south of the peninsula. In Cashmere there were some falls of snow, and

also in Chamba, down to levels of 10,000 feet. Except in Tenasserim and the south-east of the Bay the atmospheric pressure was everywhere above the average, for the first time since May 1882. This was not due to the coolness and density of the lower atmosphere, for, although the temperature was somewhat below the average in the regions of heavy rainfall, it was not the case generally, since Chutia Nagpur and Orissa, as well as the Eastern Peninsula, had a certain excess of temperature.

The excessive pressure was not lasting. In November, between the 5th and 10th it again fell below the average, and two storms were formed independently, the one in North-Western India, the other to the east of the Andamans, or rather more south. The former brought a heavy fall of snow to the North-West Himalaya, and rain on the plains of the Punjab and the western districts of the North-West Provinces, which immediately brought down the temperature and ushered in a spell of cool weather and north-westerly winds which lasted up to the end of the year. The latter was developed into a travelling cyclone, which moved on a course somewhat west of north, crossing between the Andamans and Cape Negrais, and then, turning north, passed over Akyab and broke up among the Arakan hills.

Except a small barometric depression formed apparently in the north of the Bay in the beginning of December, which passed into Eastern Bengal and Cachar, and brought unusual and very unseasonable rain on the 4th and 5th, there was no further disturbance in Northern India, and no rain on the plains up to the last days of the year. In the Carnatic, occasional bursts of rain, separated by intervals of fine weather, were frequently repeated in both months. In December, in Northern India, the weather was cold and dry and the pressure remarkably high, more so indeed than in October; and this appears to have been the case not only over India, but also around the coasts of the North Indian Ocean, and possibly, therefore, over that sea itself.

EXPLANATION OF THE PLATES.

PLATE I.—FRONTISPIECE.—A chart of India, shewing the positions of the meteorological observatories and rain-gauge stations in 1883.

PLATES II to IV.—Charts shewing the mean distribution of temperature and pressure, and the resultant wind direction, in each month of 1883.

TEMPERATURE.—The data for the isotherms are given in Table VI of the Appendix. The isotherms (in red) represent increments of 5° Fahrenheit; the figures, indicating their respective values, are placed on the side of the higher temperature; and the seats of the highest and lowest mean temperatures are indicated (in red) by the words 'high' and 'low' respectively.

PRESSURE.—The data for the isobars are given in Table VIII of the Appendix. The isobars (in blue) are given for each twentieth of an inch, and their values are marked by the figures on the side of the higher pressure. The seats of maximum and minimum pressure are indicated (in blue) by the words 'high' and 'low' or their initials.

WIND DIRECTIONS.—These are the resultants computed by Lambert's formula from the observations, an equal value being assigned to each. Their values are given in Table IX of the Appendix. The arrows shew the direction of the resultant, the point of the arrow indicating the station; and by their respective lengths, the percentage of the observations expressing the numerical value of the resultant in each case; five-eighths of an inch being equal to 100 per cent.

PLATES V to IX.—Weather charts, shewing the pressure, wind, and rainfall at 10 A.M. certain days. The arrows shew simply the direction of the wind, without distinction of velocity. The rainfall is shewn by varying depths of shading.

PLATES V AND VI.—Illustrate the changes preceding, accompanying, and terminating two rainy periods in the cold weather.

PLATE VII.—The two upper charts illustrate the distribution of pressure and winds during the drought of Northern India in the earlier part of May; the lower charts those of the rainy period in the latter part of that month.

PLATE VIII.—Illustrates the setting-in of the rains in Bengal.

PLATE IX.—Illustrates the simultaneous formation of November storms in North-Western India and the Andaman Sea.

JANUARY 1883.



FEBRUARY 1883.



MARCH 1883.



APRIL 1883.



Lithographed at the Survey of India Offices, Calcutta, February 1883

MAY 1883.



JUNE 1883.



JULY 1883.



AUGUST 1883.



Lithographed at the Survey of India Offices, Calcutta. February 1885

SEPTEMBER 1883.



OCTOBER 1883.



NOVEMBER 1883.



DECEMBER 1883.


LOW
HIGH
55°
60°
30·10
60°
30·10
30·10
30·10
70°
65°
30·00
30·00
30·00

BARIC, WIND AND RAINFALL CHARTS.

JAN. 4TH 10 A.M.



JAN. 9TH 10 A.M.



JAN. 10TH 10 A.M.



JAN. 11TH 10 A.M.

Lithographed at the Survey of India Offices, Calcutta, April 1885

BARIC, WIND AND RAINFALL CHARTS.

JAN. 24TH 10 A.M.

JAN. 25TH 10 A.M.

JAN. 26TH 10 A.M.

JAN. 27TH 10 A.M.

JAN. 28TH 10 A.M.

JAN. 29TH 10 A.M.

Lithographed at the Survey of India Office, Calcutta, A.D. 1883

BARIC, WIND AND RAINFALL CHARTS.

MAY 12TH 10 A.M.



MAY 20TH 10 A.M.



MAY 22ND 10 A.M.



MAY 28TH 10 A.M.



Lithographed at the Survey of India Offices, Calcutta, April 1885.

BARIC, WIND AND RAINFALL CHARTS.

JUNE 14TH 10 A.M.



JUNE 15TH 10 A.M.



JUNE 16TH 10 A.M.



JUNE 17TH 10 A.M.



Lithographed at the Survey of India Office, Calcutta, April 1883.

BARIC, WIND AND RAINFALL CHARTS.

NOV. 10TH 10 A.M.



NOV. 11TH 10 A.M.



NOV. 12TH 10 A.M.



NOV. 13TH 10 A.M.

Lithographed at the Survey of India Offices, Calcutta, April 1883

APPENDIX

Abstract of Meteorological Registers for the year 1883.

TABLE I.—EQUILIBRIUM TEMPERATURES OF SOLAR RADIATION IN 1883. (111 STATIONS).

1. ZANZIBAR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	153·6†	1st	164·1	25th	142·0	67·7†	78·8	58·7
February	154·1‡	19th	161·9	11th	133·1	68·1‡	75·1	47·9
March	156·4§	18th	167·5	7th	120·2	69·3§	80·7	35·8
April	158·0‡	21st	168·2	10th	148·5	72·6‡	80·6	67·0
May	148·1§	17th	159·6	1st	112·9	65·1§	75·6	33·1
June	155·6	17th	164·6	15th	152·6	71·8	81·0	67·0
July	150·3	28th	159·1	29th	124·0	68·5	76·8	46·6
August	153·1	16th	162·6	30th	135·7	70·3	80·5	52·9
September	152·4	5th	157·8	20th	138·3	69·2	73·7	57·0
October	151·6	7th	156·7	12th	137·9	68·1	72·8	57·6
November	150·1	12th	159·2	1st	137·7	65·7	77·4	54·2
December	152·1	28th	156·7	1st	138·3	66·3	71·3	54·6
Year	153·0	...	168·2	...	112·9	68·6	81·0	33·1
Means of extremes	...	...	161·5	...	135·1	...	77·0	52·7

* On a stand 4 feet high. † Mean of 28 days. ‡ Mean of 21 days. § Mean of 30 days.

2. ADEN (*corrected*).‖

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	135·4	19th	139·7	23rd	125·7	53·2	58·4	44·4
February	136·6	16th	144·0	5th	131·2	54·4	60·9	50·9
March	139·2	17th	150·2	12th	132·7	53·4	66·1	49·4
April	139·0	17th	146·2	14th	132·7	48·8	55·3	44·6
May	139·6¶	15th	147·7	18th	134·2	46·6¶	50·3	41·7
June	139·8	28th	150·2	16th	135·7	45·4	50·9	42·4
July	134·2	7th & 28th	140·2	11th	121·2	44·4	51·9	34·4
August	139·7	20th	144·2	1st	134·7	47·5	51·7	42·4
September	142·0	3rd	152·2	23rd	132·2	48·3	57·9	37·9
October	141·7	18th	146·7	31st	134·2	49·2	52·4	45·9
November	134·3**	1st, 2nd & 11th.	140·2	28th	124·2	48·0**	51·4	41·9
December	130·5	15th	137·7	26th	121·2	48·2	56·4	39·7
Year	137·7	...	152·2	...	121·2	49·0	66·1	34·4
Means of extremes	...	...	144·9	...	130·0	...	55·3	43·0

‖ On a stand 5 feet high. ¶ Mean of 30 days. ** Mean of 26 days.

3. BUSHIRE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	132·2†	18th, 19th & 21st.	142·9	8th	121·9	67·4†	76·2	57·2
February	136·5	18th	142·9	23rd	128·9	71·2	79·2	66·2
March	146·7	27th & 30th	159·9	6th	133·9	74·9	86·3	65·3
April	154·5	16th	165·9	19th	140·9	70·6	82·3	58·3
May	155·7	11th	169·9	1st	148·9	63·8	73·3	53·4
June	155·4	6th	158·9	15th	150·9	63·7	69·3	59·4
July	158·5	26th	165·9	2nd & 3rd	151·9	63·7	75·3	55·4
August	160·2	4th & 15th	164·9	27th	154·9	62·4	66·4	57·4
September	156·9	4th	161·4	30th	150·9	62·7	65·4	58·4
October	151·2†	21st	155·9	30th	144·9	62·9†	66·2	58·3
November	141·3	2nd	156·9	20th	129·9	63·2‡	70·3	56·3
December	134·4	1st	140·9	27th	125·9	65·3	73·2	55·3
Year	148·6	...	169·9	...	121·9	66·0	86·3	53·4
Means of extremes	...	...	157·2	...	140·3	...	73·6	58·4

* On a stand 3 feet 9½ inches high. † Mean of 30 days. ‡ Mean of 29 days.

4. QUETTA (*corrected*).§

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	109·2	31st	134·1	20th	82·7	61·4	101·5	35·7
February	114·6	15th	128·9	2nd	66·2	63·0	78·3	33·6
March	125·1	29th	148·9	10th	94·4	63·8	80·3	47·4
April	136·8	20th	149·3	16th	124·5	62·7	72·8	53·9
May	139·1‖	16th	146·3	2nd	125·4	56·4‖	64·4	50·8
June	148·4	9th	162·7	11th	140·7	54·6	65·3	50·5
July	148·7	7th	164·6	22nd	141·9	57·4	65·2	48·3
August	147·2	8th	155·6	24th	137·2	54·7	66·1	51·0
September	140·9¶	2nd	145·7	15th	135·1	54·0¶	57·9	52·5
October	129·2	13th	142·0	19th	119·1	55·7	64·7	53·0
November	116·3	5th	126·5	29th	105·6	56·2	69·7	51·6
December	108·0	24th	118·1	12th	59·2	52·7	63·1	15·1
Year	130·3	...	164·6	...	59·2	57·7	101·5	15·1
Means of extremes	...	...	143·6	...	111·0	...	70·8	45·3

§ On a stand 4 feet high. ‖ Mean of 30 days. ¶ Mean of 22 days.

5. LEH (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	90·8	27th	111·6	26th	55·6	56·7	79·0	25·6
February	94·7	13th	120·5	28th	60·1	61·8	87·9	30·2
March	114·2	31st	130·2	23rd	81·1	70·0	84·9	42·1
April	127·3	22nd	142·1	13th	111·8	66·4	76·4	56·3
May	128·1	31st	138·6	28th	98·6	64·9	75·8	34·1
June	137·6	30th	154·6	13th	117·1	62·4	69·7	53·8
July	142·4	1st	151·1	17th	123·6	57·7	70·6	42·5
August	140·1	1st	149·5	8th	126·7	58·6	69·9	44·9
September	131·6	10th	149·1	5th	108·6	52·5	73·0	21·5
October	117·7	3rd	126·6	26th	107·8	58·9	70·3	48·9
November	106·2†	1st	119·4	17th	94·1	57·8†	67·7	41·5
December	98·4	31st	112·1	21st	86·1	62·0	79·2	47·1
Year	119·1	...	154·6	...	55·6	60·8	87·9	21·5
Means of extremes	...	...	133·8	...	97·6	...	75·4	40·7

* On a stand 4 feet 6 inches high.
† Mean of 24 days.

6. MOOLTAN (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	124·7	8th	134·9	24th	85·9	55·2	67·0	28·7
February	132·1	28th	143·9	3rd	124·9	60·0	65·5	54·0
March	144·5	29th	156·9	5th	135·4	60·8	70·0	55·4
April	156·7	20th & 21st	165·9	4th	145·9	58·5	63·0	54·6
May	158·3	20th	165·9	26th	133·9	56·5	63·0	45·0
June	162·4	6th	169·3	30th	155·9	55·0	60·0	51·0
July	157·2	3rd	164·9	1st	126·9	60·9	65·5	38·0
August	154·9	28th	161·9	6th	149·9	54·6	59·0	51·0
September	153·8	12th	159·7	4th & 19th	149·9	55·5	65·0	50·4
October	149·5§	7th	153·9	25th	140·9	54·7§	59·0	52·0
November	Imperfect.							
December	123·7	10th, 12th & 16th.	127·9	7th	114·9	51·8	55·0	47·0
Year	?	...	169·3	...	85·9	?	70·0	28·7
Means of extremes	...	...	?	...	?	...	?	?

‡ On a stand 3 feet 7 inches high.
§ Mean of 25 days.

7. DERAH ISMAIL KHAN (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	125·0	15th	141·7	8th	109·7	56·3	69·1	42·1
February	130·5	22nd & 24th	140·7	27th	110·7	58·3	69·0	38·0
March	142·3	18th	157·7	24th	129·7	60·5	75·0	53·0
April	155·8	24th	170·7	4th	142·7	60·2	77·8	54·2
May	156·9	20th	168·7	22nd	132·7	54·8	63·2	32·2
June	162·1	25th & 26th	169·7	6th	152·7	50·9	54·2	47·2
July	156·2	3rd & 27th	163·7	1st	133·7	52·9	63·2	44·1
August	156·7	26th & 27th	163·7	23rd	145·7	51·5	60·1	43·2
September	153·9	23rd	160·7	29th	143·7	52·5	59·1	45·2
October	147·8	5th	152·7	31st	131·7	51·6	56·1	43·1
November	Untrustworthy.							
December	Ditto.							
Year			170·7				77·8	
Means of extremes								

* On a stand 4 feet 2 inches high.

8. PESHAWAR (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	Not recorded.							
February	124·0	16th & 17th	138·1	28th	82·2	58·8	68·9	22·4
March	133·9	30th	152·6	2nd	75·6	59·2	69·4	15·8
April	149·0	20th	157·6	3rd	133·1	59·6	66·5	54·6
May	155·3	17th	164·0	1st	124·6	55·4	64·0	38·5
June	164·9	14th	175·1	28th	148·6	55·7	67·6	39·6
July	157·5	6th & 30th	167·6	10th	125·6	55·8	63·6	38·5
August	158·1	1st & 5th	165·6	31st	147·6	56·0	62·1	52·9
September	150·4	9th	158·8	29th	135·8	52·8	61·3	45·3
October	141·8	7th	151·6	25th	133·6	53·6	59·5	48·7
November	127·8	2nd	139·6	11th	80·6	53·9	58·2	20·8
December	115·7	1st & 6th	126·7	12th	71·9	49·4	59·0	14·1
Year	?	...	175·1	...	80·6	?	69·4	14·1
Means of extremes			?	...	?	...	?	?

† On a stand 2 feet 10 inches high.

9. MURREE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.			Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	106·5†	31st	145·9	21st	60·7	59·4†	110·1	22·6	112·4§	15th	126·4	19th & 21st	82·4	49·4§	70·8	25·6
February	123·5‡	12th	136·4	15th	91·0	76·6‡	96·0	46·5	121·6‖	8th & 26th	133·4	18th	77·4	57·7‖	68·3	20·3
March	124·3§	30th	145·7	12th	66·4	68·1§	92·2	27·8	134·9¶	31st	155·4	22nd	91·9	60·1¶	71·4	23·8
April	137·0‖	18th	151·7	24th	95·5	67·9	81·1	33·9	150·1	23rd & 28th	164·4	1st	99·4	60·7	71·9	21·4
May	142·7¶	11th	153·2	1st	103·2	66·8¶	79·4	34·8	154·9	20th	166·9	27th	92·4	58·3	72·4	21·0
June	148·6	12th	159·1	4th	138·6	65·4	75·7	59·6	163·9	14th & 24th	169·4	28th	151·4	58·1	66·4	49·2
July	143·9¶	6th	162·1	2nd	115·8	66·9¶	79·0	41·4	157·9**	6th	170·9	14th	140·4	59·2**	67·6	49·4
August	142·2	29th	157·4	9th	107·7	66 8	79·7	37·8	156·5	5th	165·9	31st	143·4	59·8	66·7	53·4
September	138·4¶	11th	151·9	7th	100·1	64·7¶	77·7	35·3	152·0	11th	157·4	29th	132·4	58·8	66·4	52·4
October	131·3¶	15th	143·6	24th	120·7	64·1¶	73·0	60·7	144·0	4th	150·9	21st	136·4	56·3	60·6	53·4
November	122·0§	5th	132·9	16th	112·4	64·0§	74·4	59·2	127·8§	7th	139·4	20th	118·4	55·1§	63·3	51·9
December	109·8**	4th	121·9	28th	53·4	58·5**	68·0	10·2	119·1§	1st 13th & 14th	126·4	30th	105·0	52·7§	60·8	44·6
Year	130·9	...	162·1	...	53·4	65·8	110·1	10·2	141·3	...	170·9	...	77·4	57·2	72·4	20·3
Means of extremes	...	...	146·8	...	97·1	...	82·2	39·1	...	...	152·2	...	114·3	...	67·2	38·9

* On a stand 3 feet 8 inches high.

† Mean of 22 days.
‡ „ „ 25 „
§ „ „ 28 „
‖ Mean of 27 days.
¶ „ „ 29 „
** „ „ 30 „

†† On a stand 4 feet 7 inches high.

10. RAWALPINDI (*corrected*).††

11. SIALKOT (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.			Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	Not recorded.								119·0	7th	131·2	24th	64·7	51·4	63·5	11·0
February	Imperfect.								127·0	27th	140·2	17th	94·7	56·9	67·0	24·5
March	125·3	31st	146·6	2nd	74·0	46·3	55·1	13·4	142·6	29th	156·7	12th	123·7	60·1	71·0	55·2
April	146·7	28th	160·0	4th	134·0	49 9	56·2	45·8	157·2	28th & 29th	166·7	2nd & 3rd	146·7	59·4	66·3	52·7
May	156·6	25th	173·4	29th	141·0	50·3	71·9	40·5	158·4	1st & 18th	168·7	27th	97·7	55·1	66·8	22·5
June	156·5	3rd	163·0	5th	145·0	45·9	54·5	34·7	162·7	12th	172·7	15th	141·7	53·7	62·4	43·2
July	149·3	6th	163·1	3rd	102·2	46·1	59·6	2·5	159·6	16th	171·7	12th	130·7	57·1	74·1	42·1
August	145·1	4th	160·1	31st	102·0	45·5	57·3	17·2	161·7	11th	169·0	14th, 17th & 30th	155·7	57·4	68·2	52·4
September	140·3	19th	155·0	7th	111·1	45·5	64·3	27·2	148·2	2nd	164·7	6th	84·7	54·7	66·2	8 5
October	131·1	2nd	140·3	19th	118·4	37·6	44·5	20·6	146·9	3rd & 4th	152·7	31st	136·7	54·9	61·1	49·9
November	110·0	9th	123·3	11th	89·3	30·2	37·4	6·6	131·5	7th	142·7	12th	119·7	53·8	6 0	44 0
December	94·9	6th	100·2	28th	81·8	26·3	30·3	18·6	121·8	2nd	130·2	28th	92·7	51·4	58·2	28·0
Year	?	...	173·4	...	81·8	?	71·9	2·5	144·7	...	172·7	...	64·7	55·5	74·1	8·5
Means of extremes	...	...	?	...	?	...	?	?	..	...	155·6	...	115·8	..	65·4	36·2

* On a stand 3 feet 10 inches high.

† On a stand 3 feet 8 inches high.

13. LUDHIANA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	118·5	1st	129·2	24th	80·2	50·3	66·5	21·5
February	129·8	27th	143·2	6th	119·2	60·4	66·5	50·5
March	145·9	30th	163·2	11th	121·2	63·0	70·5	55·0
April	158·6	20th	167·2	1st	143·2	58·7	66·4	50·4
May	161·4	18th & 20th	169·2	27th	129·2	55·1	60·0	41·5
June	162·5	22nd	175·2	30th	102·2	55·2	65·9	19·5
July	154·7	30th	170·2	17th	105·2	54·7	63·4	22·0
August	160·4	2nd	172·2	11th	148·7	57·8	68·9	50·9
September	146·4	2nd	160·7	3rd	87·2	52·0	65·1	5·7
October	146·6	5th	151·8	20th	131·2	54·4	63·7	47·5
November	131·1	1st & 6th	141·2	12th	116·2	52·4	58·5	41·5
December	120·1	1st	131·2	30th	113·2	49·7	58·0	44·0
Year	144·7	...	175·2	...	80·2	55·3	70·5	5·7
Means of extremes	...	...	156·2	...	116·4		64·5	37·5

* On a stand 3 feet 6 inches high.

14. SIMLA (*corrected*).†

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
108·5	13th	131·7	26th	38·7	60·4	93·5	5·4
124·0	7th	144·9	18th	96·0	72·4	90·3	47·9
125·5	31st	148·7	12th	55·7	66·9	87·0	6·6
141·0	24th	152·7	4th	114·7	68·9	78·6	59·5
143·4‡	10th	155·7	26th	116·0	64·9‡	73·0	47·5
140·8	27th	154·2	30th	91·2	62·3	74·9	23·1
132·7	3rd	151·7	17th	84·0	60·0	77·4	13·9
130·0	18th	150·7	1st	82·7	57·5	75·6	10·4
136·5	11th	148·7	3rd	84·2	62·3	78·4	16·7
133·2	5th	141·7	20th	119·7	66·1	74·3	60·5
118·7	1st	131·4	10th	61·9	61·6	73·2	7·4
116·3	13th	122·2	2nd	110·2	62·4	67·2	55·0
129·2	...	155·7	...	38·7	63·8	93·5	5·4
...	...	144·5	...	87·9	...	78·6	29·5

† On a stand 3 feet 5 inches high.
‡ Mean of 29 days.

15. DELHI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	125·0	23rd	140·0	25th	90·2	53·4	67·5	29·5
February	131·4	27th	146·2	2nd	118·2	56·7	63·5	50·7
March	145·1	31st	160·2	13th	126·2	57·8	65·9	46·9
April	159·8	18th	166·2	1st	144·2	56·4	62·1	50·6
May	163·7	11th, 18th & 20th	171·2	22nd	145·2	56·7	71·5	50·8
June	159·8†	3rd	170·7	30th	89·2	52·3†	63·5	7·5
July	153·3	6th & 30th	166·2	9th	100·2	56·0	63·6	13·1
August	162·3	19th	167·2	31st	157·2	59·5	67·4	53·6
September	154·1	1st	164·2	6th	143·2	57·9	70·7	51·1
October	149·3	6th	158·2	20th	138·7	54·7	63·6	51·1
November	137·0	6th	142·2	17th	127·2	51·9	58·8	47·1
December	124·7	21st	129·2	30th	120·2	50·3	53·5	48·5
Year	147·1	...	171·2	...	89·2	55·3	71·5	7·5
Means of extremes	...	...	156·8	...	125·0	...	64·3	41·7

* On a stand 3 feet 11 inches high.
† Mean of 27 days.

16. SIRSA (*corrected*).‡

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
133·5	5th	145·7	24th	86·3	62·9	70·1	30·0
140·9	28th	154·1	1st	129·9	67·3	74·7	61·7
153·0	22nd	167·6	11th	136·9	67·5	74·8	62·4
166·6	22nd	178·8	4th	151·8	63·9§	68·7	57·1
169·3	21st	177·6	26th	155·3	63·1	67·7	60·3
168·3	12th	175·7	30th	138·3	59·2	66·9	40·0
163·5	8th	175·6	17th	131·9	62·7	71·3	49·3
168·0	25th & 28th	175·3	22nd	161·3	64·0	72·5	58·9
159·8	1st	173·0	6th	153·3	62·9	69·9	58·1
158·4	5th	166·6	31st	150·9	63·5	73·9	59·7
143·5	6th	152·2	23rd	134·9	62·7	68·4	58·8
134·0	28th	140·6	30th	126·0	60·0	65·1	53·7
154·9	...	178·8	...	86·3	63·3	74·8	30·0
...	...	165·2	...	138·1	...	70·3	54·2

‡ On a stand 3 feet 9 inches high.
§ Mean of 29 days.

17. CHAKRATA (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Difference, sun and shade. Maximum.	Difference, sun and shade. Minimum.
January	110·3‡	31st	148·7	26th	66·7	61·9‡	109·3	22·3
February	121·4	1st	151·7	18th	107·1	71·3	114·9	55·7
March	120·5†	18th	135·7	11th	74·7	59·9†	75·0	29·3
April	Doubtful.							
May	Ditto.							
June	Imperfect.							
July	Not recorded.							
August	Ditto.							
September	Ditto.							
October	128·6‡	13th	135·9	31st	123·6	62·9‡	71·2	59·1
November	119·8§	1st & 30th	125·6	11th	102·1	62·3§	75·4	45·8
December	116·0†	1st	125·1	29th	77·1	63·9†	73·4	30·5
Year	?	...	136·9	...	67·7	?	114·9	22·3
Means of extremes	...	...	?	...	?	...	?	?

18. DEHRA.‖

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Difference, sun and shade. Maximum.	Difference, sun and shade. Minimum.
January	118·0	24th	139·0	27th	59·2	53·5	85·6	4·4
February	128·0	15th	142·7	24th	109·9	60·1	67·5	44·7
March	134·3	24th	147·8	1st	93·1	58·5	71·2	26·1
April	149·7	15th	157·2	2nd	124·2	59·0	66·5	41·5
May	151·0	18th	161·5	24th	95·2	55·6	65·9	15·6
June	150·8	26th	158·3	30th	132·6	57·7	67·7	47·6
July	141·2†	11th	156·7	1st	89·0	55·0†	70·1	6·0
August	146·4	24th	157·8	2nd	115·7	60·8	71·0	33·5
September	145·4	1st	159·3	3rd	92·0	61·3	74·4	11·4
October	141·3	7th	147·3	30th	136·0	59·4	64·1	56·5
November	122·9	1st	134·7	13th	69·9	52·2	62·3	6·5
December	118·6	2nd	129·0	31st	103·7	53·2	64·6	42·8
Year	137·3	...	161·5	...	59·2	57·2	85·6	4·4
Means of extremes	...	...	149·3	...	101·7	...	69·2	28·1

* On a stand 2 feet 10½ inches high.
† Mean of 30 days.
‡ Mean of 23 days.
§ „ „ 29 „
‖ The readings of the sun thermometer refer to the preceding day.

19. ROORKEE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Difference, sun and shade. Maximum.	Difference, sun and shade. Minimum.
January	127·5	22nd	143·5	26th	84·0	57·3	66·6	28·5
February	132·2	24th	147·5	23rd	121·5	60·2	70·1	52·1
March	142·8	18th	155·5	4th	117·5	60·0	69·1	54·1
April	155·4	14th	164·0	1st	136·0	56·3	62·6	48·3
May	158·3	19th	167·5	23rd	106·5	54·7	66·8	22·3
June	153·9†	3rd	161·5	30th	111·5	52·6‡	67·8	31·3
July	147·0	12th	164·0	17th	94·5	54·1	68·3	16·6
August	151·4	4th	160·5	21st	133·0	56·8	65·6	46·3
September	149·3	12th	158·0	2nd	94·0	57·4	68·3	13·3
October	148·1	6th	157·0	30th	142·5	57·1	64·3	54·7
November	133·9	9th	143·0	12th	121·5	56·2	61·0	51·1
December	127·6	1st	142·5	30th	113·5	55·8	67·6	48·1
Year	144·0	...	167·5	...	84·0	56·5	70·1	13·3
Means of extremes	...	...	155·4	...	114·7	...	66·5	38·9

20. RANIKHET (*corrected*).§

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Difference, sun and shade. Maximum.	Difference, sun and shade. Minimum.
January	110·9‡	7th	125·5	28th	58·3	58·0‖	70·9	28·5
February	123·2	17th	136·7	18th	110·8	67·1	80·5	56·0
March	131·7	31st	139·8	4th	118·3	68·7	82·2	62·2
April	140·0	13th	145·3	3rd	132·8	63·9	76·2	58·8
May	137·7	21st	150·1	26th	77·3	60·2	72·8	14·8
June	140·8	24th	149·3	30th	98·3	62·4	70·5	31·8
July	132·6	11th	150·3	19th	85·3	58·1	73·0	18·5
August	135·3	26th	152·8	4th	102·3	61·3	80·4	33·9
September	140·7	12th	155·5	14th	121·3	67·6	81·0	50·7
October	134·7	2nd	147·3	20th	115·3	65·2	74·7	49·6
November	122·1	12th	133·3	11th	63·3	62·4	76·3	21·5
December	115·6‖	8th	127·8	30th	76·3	60·1‖	71·0	29·0
Year	130·4	...	155·5	...	58·3	62·9	82·2	14·8
Means of extremes	...	...	142·8	...	96·6	...	75·8	37·9

* On a stand 3 feet 6 inches high.
† Mean of 29 days.
‡ „ „ 28 „
§ On a stand 3 feet 9 inches high.
‖ Mean of 30 days.

21. MEERUT (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	120·8	6th	150·5	25th	72·2	49·8	77·7	12·8
February	128·4	27th	136·0	18th	116·5	55·0	64·0	44·2
March	141·8	31st	155·5	12th	124·2	56·1	60·5	50·3
April	155·3	11th	162·5	1st	133·5	53·7	57·9	40·9
May	157·7†	20th	169·5	23rd	119·2	54·9†	62·1	35·2
June	153·0	3rd	166·5	30th	91·5	50·1	57·9	13·6
July	Untrustworthy.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	132·9	9th	136·9	10th	123·7	53·1	59·3	41·2
December	123·1	1st	127·5	16th	116·2	50·6	53·2	44·9
Year	?	...	169·5	...	72·2	48·9	77·7	12·8
Means of extremes	...	...	?	...	?	...	?	?

* On a stand 3 feet 10 inches high.
† Mean of 28 days.

22. BAREILLY (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	123·1	10th	127·8	7th	117·8	53·3§	66·1	45·6
February	129·9	20th & 21st	138·8	1st	119·3	57·0	65·6	51·1
March	140·3	31st	151·8	15th	130·8	55·3	70·9	46·9
April	151·8	14th & 30th	157·8	5th & 6th	144·8	50·3	56·1	46·1
May	159·2	3rd	169·8	27th	140·8	54·8	67·6	45·6
June	156·4	16th	161·8	25th	144·8	53·6	67·1	48·1
July	148·5	1st	159·8	20th	127·8	55·2	68·6	42·1
August	146·2	22nd	156·8	21st	118·8	50·6	67·1	37·1
September	146·9	8th	156·8	13th	132·6	53·4	64·1	44·4
October	140·2	13th & 19th	147·8	18th	133·1	47·7	56·1	41·9
November	126·3	3rd	134·3	22nd	109·3	45·0	49·6	35·1
December	118·9	2nd	147·6	18th	112·8	46·2	73·4	41·4
Year	140·6	...	169·8	...	109·3	51·9	73·4	35·1
Means of extremes	...	...	150·9	...	127·7	...	64·4	43·8

‡ On a stand 3 feet 6 inches high.
§ Mean of 30 days.

23. AGRA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	129·4	2nd	138·8	25th	109·6	56·5	63·2	39·0
February	134·1	16th, 24th & 27th	143·6	28th	103·1	58·9	67·5	26·0
March	150·5	31st	167·6	3rd	129·6	61·5	69·5	51·0
April	163·7	21st	174·6	2nd	147·6	59·1	63·1	54·1
May	165·4	19th	174·8	28th	144·1	58·3	64·7	52·3
June	159·7	3rd	169·3	27th	121·3	54·2	64·1	25·7
July	144·2	5th	164·3	21st	93·1	51·1	63·1	12·5
August	158·0	23rd	165·3	21st	133·1	59·2	64·8	45·0
September	155·1	27th	163·3	14th	123·1	59·1	69·6	35·0
October	153·0	6th	169·3	20th	142·3	57·9	69·8	52·3
November	138·9	7th	153·1	17th	131·8	55·4	62·5	51·7
December	128·9	14th & 21st	137·1	25th, 27th & 31st	124·3	54·0	60·5	50·0
Year	148·4	...	174·8	...	93·1	57·1	69·8	12·5
Means of extremes	...	...	160·1	...	125·3	...	65·2	41·2

24. LUCKNOW (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	132·3	21st	146·9	26th	75·9	58·3	70·2	16·1
February	137·6	28th	147·9	1st	126·4	62·4	69·5	57·7
March	146·7	29th	162·9	7th	124·9	59·8	70·2	50·9
April	161·4	21st	166·4	3rd	154·9	58·2	64·9	49·9
May	164·6	19th	173·4	27th	131·9	58·8	82·7	41·7
June	161·1	15th	172·9	29th	143·4	59·3	76·9	49·4
July	145·4	11th & 13th	162·9	6th	100·4	53·6	67·7	10·7
August	156·9	18th	169·9	3rd	137·9	62·6	72·9	48·7
September	154·1	12th	165·9	17th	138·9	61·5	72·2	52·9
October	149·4	18th	158·9	19th	111·9	57·5	66·9	30·7
November	139·8†	11th & 12th	146·9	23rd	131·9	57·9†	63·9	52·7
December	132·4	1st	137·9	19th & 24th	128·9	58·1	64·7	54·7
Year	148·5	...	173·4	...	75·9	59·0	82·7	10·7
Means of extremes	...	...	159·4	...	125·6	...	70·2	43·0

* On a stand 3 feet high.
† Mean of 29 days.

25. GORAKHPUR (*corrected*).*

MONTH.	Mean.	MAXIMUM. Day.	MAXIMUM. °	MINIMUM. Day.	MINIMUM. °	DIFFERENCE, SUN AND SHADE. Mean.	Maximum.	Minimum.
January	128·4	11th & 17th	135·5	26th	70·5	54·6	66·0	1·0
February	135·2	19th	146·5	25th	118·5	59·6	66·0	40·1
March	147·6	24th	157·5	11th	99·5	58·4	67·1	17·1
April	153·3	7th	162·5	22nd & 28th	149·5	52·8	63·1	47·6
May	156·0	19th & 27th	164·5	4th, 10th & 13th.	152·5	53·0	63·1	46·1
June	149·7	3rd	170·5	14th	90·5	53·5	72·1	1·1
July	149·3	4th	160·5	26th	105·5	57·0	65·1	18·1
August	149·6	25th	162·0	4th	109·5	57·3	67·6	18·1
September	150·9	4th	159·5	17th	103·5	58·8	67·6	21·6
October	148·4	14th	156·0	19th	103·5	56·6	63·6	13·6
November	137·0	13th	154·5	24th	130·5	54·8	68·6	52·1
December	128·1	4th	133·5	22nd & 24th	122·0	53·4	56·6	50·6
Year	144·5	...	170·5	...	70·5	55·8	72·1	1·0
Means of extremes	...	...	155·3	...	113·0	...	65·5	27·3

* On a stand 3 feet 6 inches high.

26. JHANSI (*corrected*).†

MONTH.	Mean.	MAXIMUM. Day.	MAXIMUM. °	MINIMUM. Day.	MINIMUM. °	DIFFERENCE, SUN AND SHADE. Mean.	Maximum.	Minimum.
January	132·6	1st	140·0	21st	121·0	58·6	65·9	53·6
February	135·0	28th	138·5	2nd	131·0	58·5	67·6	54·1
March	145·4	31st	164·8	14th	131·8	55·4	64·0	44·5
April	165·7	25th	174·5	6th	155·8	60·6	66·5	55·7
May	168·9	20th & 21st	181·0	29th	152·5	61·9	67·5	56·0
June	Untrustworthy.							—
July	Ditto.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	137·3	13th	143·0	23rd & 25th	132·0	54·5	62·1	48·1
December	131·2	16th	139·0	5th	123·0	55·9	63·1	48·1
Year	?	...	181·0	...	121·0	54·4	67·6	?
Means of extremes	...	...	?	...	?	...	?	?

† On a stand 3 feet 1½ inches high.

27. ALLAHABAD (*corrected*).*

MONTH.	Mean.	MAXIMUM. Day.	MAXIMUM. °	MINIMUM. Day.	MINIMUM. °	DIFFERENCE, SUN AND SHADE. Mean	Maximum.	Minimum.
January	126·8	21st	140·4	9th	71·2	54·7	65·9	6·8
February	134·5	17th	146·7	2nd	125·0	58·1	64·8	54·0
March	148·2	23rd	160·6	14th	138·8	57·9	65·8	53·6
April	159·9	21st	165·5	5th	153·8	55·2	62·9	51·4
May	162·8	12th	169·4	23rd	150·2	54·5	65·3	47·9
June	159·5	3rd	172·7	12th	139·4	57·5	68·9	48·2
July	146·0	4th	165·2	6th	100·2	54·5	64·7	19·6
August	152·8¶	24th	162·2	3rd	123·2	59·0¶	68·0	36·9
September	149·4	21st	162·6	5th	127·2	58·3	71·6	42·2
October	144·5	18th	159·2	19th	109·2	54·5	66·4	28·7
November	137·2	1st	145·8	24th	130·8	55·6	60·6	53·4
December	128·9	1st	134·2	31st	121·0	55·2	57·4	49·6
Year	145·9	...	172·7	...	71·2	56·3	71·6	6·8
Means of extremes	...	...	157·0	...	124·2	...	65·2	41·0

* On a stand 3 feet 6 inches high.

28. BENARES (*corrected*).†

MONTH.	Mean.	MAXIMUM. Day.	MAXIMUM. °	MINIMUM. Day.	MINIMUM. °	DIFFERENCE, SUN AND SHADE. Mean.	Maximum.	Minimum.
January	131·1‡	23rd	139·6	22nd	101·3	56·7‡	65·6	34·6
February	136·8§	17th	147·0	25th	127·3	59·5‡	67·8	54·6
March	151·2¶	23rd	163·4	3rd & 12th	141·8	60·7¶	67·7	56·8
April	159·2	20th	167·1	28th	154·4	57·7	64·7	52·4
May	162·2	19th	170·8	27th	146·1	55·5	62·2	48·9
June	154·1	8th	167·3	16th	112·6	54·1	66·7	26·5
July	144·0	4th	167·6	18th	99·8	51·5	66·9	13·9
August	152·8¶	22nd	165·6	3rd	127·6	59·0¶	70·4	38·3
September	148·5	1st	161·0	13th	105·1	55·8	66·4	17·0
October	143·7	7th	160·2	20th	85·3	52·1	64·0	8·7
November	135·8	1st	146·9	26th	128·9	53·9	62·5	50·4
December	127·3	1st	132·5	25th	121·2	53·2	57·4	49·0
Year	145·7	...	170·8	...	85·3	55·8	70·4	8·7
Means of extremes	...	...	157·4	...	121·0	...	65·2	37·6

¶ Mean of 30 days.

† On a stand 3 feet 5½ inches high.
‡ Mean of 29 days.
§ „ of 27 „
‖ „ of 20 „

29. GHAZIPUR (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Maximum.	Minimum.
January	127·4	15th	131·5	22nd	102·1	53·1	59·6	32·0
February	132·8‡	17th	145·9	25th	96·0	55·3‡	65·1	25·6
March	147·7	23rd	161·5	12th	139·1	56·6	65·4	52·5
April	156·5	15th	164·4	28th	147·4	53·1	59·1	50·4
May	156·3	8th & 19th	162·6	27th	147·8	51·1	60·3	47·1
June	150·7	3rd	166·6	16th	100·8	52·6	63·9	18·2
July	145·2	4th	163·3	18th	106·6	52·4	63·8	23·7
August	145·4	19th	156·3	20th	117·1	52·3	63·0	31·6
September	148·5	8th	161·6	19th	110·1	55·4	68·3	23·7
October	142·1	6th	158·7	20th	101·1	49·8	61·2	20·8
November	133·0	2nd	146·1	27th	126·4	51·3	59·6	48·3
December	124·1	1st	129·1	25th	118·7	50·1	55·1	45·0
Year	142·5	...	166·6	...	96·0	52·8	68·3	18·2
Means of extremes	...	...	154·0	...	117·8	...	62·0	34·9

30. KATMANDU (*corrected*).†

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Maximum.	Minimum.
January	126·1	19th	141·8	26th	106·8	61·8	75·5	53·5
February	131·2‡	21st	139·8	20th	107·1	63·3‡	69·5	44·3
March	140·7§	18th & 29th	149·8	7th	111·8	63·1§	71·6	48·6
April	142·7	29th	156·8	21st	123·8	58·3‖	73·6	45·8
May	146·3	1st	158·8	28th	124·8	59·7	72·6	53·1
June	145·6	2nd & 18th	156·8	20th	102·8	59·0	68·6	26·4
July	148·8	15th	157·0	30th	129·8	61·0§	73·1	40·1
August	141·3‖	2nd	156·8	11th	89·8	55·8‖	67·7	20·9
September	144·9	21st	150·3	20th	134·6	58·6	64·8	49·8
October	139·6	8th	150·8	19th	125·8	54·1	61·8	40·8
November	129·5	25th	133·8	30th	120·8	49·4	59·6	45·6
December	122·3	4th	131·8	15th & 20th	111·8	47·6	58·5	36·6
Year	158·3	...	158·8	...	89·8	57·6	75·5	20·9
Means of extremes	...	...	148·7	...	115·8	...	68·1	42·1

* On a stand 4½ feet high. ‡ Mean of 27 days. † On a stand 4 feet high. § Mean of 3 days. ‖ „ „ 29 „

31. SIBSAGAR (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Maximum.	Minimum.
January	125·5	13th	138·7	7th	80·5	56·1	70·6	19·4
February	124·4	26th	143·6	9th	93·6	52·3	71·5	27·1
March	133·5	10th	148·0	1st	89·0	56·2	72·5	26·5
April	137·2	30th	153·6	1st	93·6	53·7	66·5	21·8
May	143·0	29th	163·6	9th	113·2	57·6	70·9	36·4
June	149·4	12th	161·7	9th	124·0	58·5	68·1	34·4
July	151·9	23rd	163·6	15th	128·0	59·3	72·3	41·1
August	149·8	1st	163·6	9th	118·0	59·7	74·1	33·4
September	150·8	8th	163·8	27th	93·0	62·0	73·0	15·4
October	148·8	4th	162·7	12th	114·8	63·1	74·0	33·1
November	137·7	3rd	149·3	29th	127·4	59·7	6,*/	52·6
December	124·1	17th	143·6	6th	75·2	54·7	75·2	11·6
Year	139·7	...	163·8	...	75·2	57·7	75·2	11·6
Means of extremes	...	...	154·7	...	104·2	...	71·4	29·4

32. DHUBRI (*corrected*).†

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, sun and shade. Mean.	Maximum.	Minimum.
January	117·8‡	3rd	123·7	10th	82·8	45·4‡	53·1	17·1
February	124·9	20th	133·2	1st	105·1	47·8	54·3	38·6
March	136·3	29th	143·0	3rd	125·2	48·6	58·4	45·4
April	134·9	7th	147·7	27th	83·4	45·7	56·1	12·5
May	132·4	1st	146·3	15th	95·5	48·5	60·5	20·8
June	141·1	20th	153·7	26th	104·9	54·2	66·0	24·7
July	144·6	12th	154·9	16th	100·8	55·5	66·6	17·0
August	137·2	3rd	153·1	6th	87·9	50·7	64·4	10·1
September	141·4	9th	154·5	24th	92·2	54·6	65·2	14·9
October	137·0	15th	145·7	31st	129·5	52·1	60·2	46·5
November	128·5	2nd	139·3	30th	118·7	48·7	58·7	42·7
December	116·9	10th	128·9	5th	101·9	45·7	52·1	35·0
Year	132·8	...	154·9	...	82·8	49·8	66·6	10·1
Means of extremes	...	...	143·7	...	102·3	...	59·6	27·1

* On a stand 4 feet high.

† On a stand 3 feet 4 inches high up to May, afterwards 4 feet high.
‡ Mean of 30 days.

33. SILCHAR (*corrected*).*

MONTH.	Mean.	MAXIMUM.		MINIMUM.		DIFFERENCE, SUN AND SHADE.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	128·3	21st	135·3	28th	110·1	51·1	62·9	40·7
February	130·3	20th	140·7	1st	85·1	50·4	58·0	22·4
March	137·4	23rd	148·1	1st	127·9	52·4	60·7	43·6
April	139·4	25th	147·1	23rd	95·9	51·4	64·8	22·2
May	130·5	28th	156·0	13th	96·6	47·9	65·1	23·0
June	140·8	8th	153·9	29th	95·7	52·0	64·9	16·1
July	144·7	19th	154·3	15th	118·0	53·4	65·3	32·2
August	141·0	15th	154·1	20th	97·9	52·7	66·2	16·5
September	141·2	3rd	151·0	27th	93·3	52·8	61·0	15·9
October	137·5	13th	153·1	11th	91·0	49·5	67·7	15·7
November	132·2	1st	142·3	3rd	124·9	48·8	55·0	39·1
December	122·7	3rd	134·5	5th	75·1	47·6	54·2	9·4
Year	135·5	...	156·0	...	75·1	50·8	67·7	9·4
Means of extremes	...	...	147·5	...	101·0	...	62·2	24·7

* On a stand 4 feet high.

34. DARJEELING (ST. PAUL'S SCHOOL) (*corrected*).†

MONTH.	Mean.	MAXIMUM.		MINIMUM.		DIFFERENCE, SUN AND SHADE.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	105·6‡	30th	116·7	4th	80·6	61·9‡	78·9	36·6
February	112·5§	4th	132·5	6th	96·5	65·9§	95·0	55·4
March	124·8‖	25th	132·7	31st	97·2	67·3‖	76·2	40·4
April	125·8‡	17th	137·6	1st	106·7	63·4‡	74·7	47·6
May	Not recorded.							
June	Ditto.							
July	125·7	27th	140·4	30th	101·8	58·0	71·2	35·1
August	120·7	19th	142·6	11th	94·6	54·7	75·0	31·1
September	121·4‡	6th	137·6	15th	87·1	56·5‡	71·4	23·3
October	125·1‖	6th	134·8	20th	97·8	64·5‖	74·0	44·0
November	118·6‖	4th	129·6	19th	107·2	64·2‖	72·9	57·6
December	Not recorded.							
Year	?	...	142·6	...	80·6	?	95·0	23·3
Means of extremes	...	...	?	...	?	...	?	?

† On a stand 4 feet 7½ inches high.
‡ Mean of 29 days.
§ Mean of 26 days
‖ „ „ 25 „

35. PURNEAH (*corrected*).*

MONTH.	Mean.	MAXIMUM.		MINIMUM.		DIFFERENCE, SUN AND SHADE.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	124·6	7th	131·1	27th	95·3	49·5	58·1	26·6
February	132·9	27th	140·3	25th	120·1	Imperfect.		
March	145·0	29th	154·3	3rd	129·3	55·1	61·6	47·1
April	150·6	17th	161·3	21st	125·5	53·6	61·1	32·3
May	148·3†	29th	160·3	10th	133·3	54·1†	62·1	47·9
June	146·7	10th	161·3	19th	121·7	54·0	66·1	39·1
July	145·6	25th	158·3	16th	112·8	54·4	69·1	26·1
August	137·1‡	18th	153·3	5th	91·9	47·7‡	62·1	8·4
September	146·5	29th	154·3	14th	131·3	56·3	64·9	39·1
October	143·0	4th	153·3	21st	121·8	55·1	62·1	41·1
November	132·0	1st	139·3	2nd	124·3	50·4	55·6	40·6
December	123·7	3rd	131·1	4th	118·3	48·1	51·1	38·9
Year	139·7	...	161·3	...	91·9	?	69·1	8·4
Means of extremes	...	...	149·9	...	118·8	...	?	?

* On a stand 3 feet 10 inches high up to January, afterwards 4 feet high.

36. DURBHUNGA (*corrected*).§

MONTH.	Mean.	MAXIMUM.		MINIMUM.		DIFFERENCE, SUN AND SHADE.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	118·2	11th	128·4	26th	84·4	46·7	55·8	18·3
February	126·4	20th	136·4	2nd	117·7	52·0	59·8	48·3
March	137·3†	24th	145·4	1st	130·0	50·9†	56·2	43·8
April	145·6	30th	154·7	25th & 26th	140·0	50·9	61·8	45·2
May	147·7	29th	158·2	21st	139·2	53·1	63·1	45·3
June	139·2	11th	157·2	17th	93·4	47·4	62·5	13·8
July	Not recorded.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	Ditto.							
December	Ditto.							
Year	?	...	?	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

† Mean of 30 days.
‡ „ „ 29 „
§ On a stand 4 feet high.

37. PATNA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	116·6	16th	122·2	26th	76·0	43·6	53·8	13·8
February	122·7	20th	138·4	2nd	113·2	46·5	54·0	43·1
March	136·5	24th	145·8	15th	121·4	46·5	53·0	40·5
April	146·6	16th	155·4	28th	135·8	44·9	49·4	41·1
May	147·6	27th & 30th	156·0	3rd	132·0	44·5	53·3	29·9
June	140·3	2nd	157·0	17th	101·8	44·7	52·4	20·5
July	134·4	11th	148·2	26th	101·4	42·5	54·2	15·4
August	135·2	23rd	149·4	3rd	111·2	44·3	57·2	17·8
September	139·8	12th	147·4	19th	98·4	48·2	54·0	13·0
October	135·3	14th	146·4	20th	84·6	45·6	56·4	11·5
November	127·5	2nd	138·2	24th	120·4	45·9	52·0	41·3
December	118·5	17th	125·0	22nd	113·4	45·1	50·9	41·7
Year	133·4	...	157·0	...	76·0	45·2	57·2	11·5
Means of extremes	...	...	144·1	...	109·1	...	53·4	27·5

* On a stand 3 feet 9 inches high.

38. HAZARIBAGH (*corrected*).†

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
116·6	25th	127·6	26th	103·1	45·7	53·2	33·8
122·9	11th	136·1	2nd	111·6	47·6	52·9	44·7
131·5	31st	139·6	11th	95·9	46·3	53·9	28·4
144·2	16th	154·1	6th	136·1	45·3	52·3	40·9
147·8	12th	156·1	22nd	139·1	45·3	50·8	41·1
136·5	3rd	151·9	30th	108·6	46·1	53·4	29·7
129·0	1st	143·9	31st	90·6	45·6	58·0	13·7
131·3	22nd	145·6	5th	93·1	47·0	59·1	16·5
137·7	23rd	147·1	26th	125·6	52·6	60·4	42·2
130·8	14th	145·1	31st	86·6	46·1	57·8	17·2
117·7	4th	127·6	2nd	80·6	42·6	48·4	15·1
110·7	3rd	115·9	5th	75·6	41·3	44·9	12·0
129·7	...	156·1	...	75·6	46·0	60·4	12·0
...	...	140·9	...	103·9	...	53·8	27·9

† On a stand 3½ feet high.

39. BERHAMPORE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	134·3	9th	141·2	27th	120·2	58·6	65·8	47·6
February	141·0	20th	149·7	1st	127·2	60·5	71·1	56·6
March	145·1	30th	154·6	16th	106·1	53·9	62·7	20·0
April	162·9	16th & 17th	170·2	24th	154·2	62·4	72·6	57·5
May	159·2	26th	165·2	21st	145·2	61·7	69·1	55·5
June	157·2	1st	168·2	29th	125·2	65·8	74·5	44·6
July	155·0	30th	164·2	17th	126·2	65·7	73·6	41·6
August	152·5	17th	174·2	6th	114·2	64·2	72·6	31·6
September	156·4	25th	163·7	8th	134·2	66·0	74·1	47·6
October	151·1	11th & 14th	159·2	31st	114·2	61·4	70·6	34·6
November	141·7	8th & 9th	148·2	2nd	123·2	59·1	63·6	43·1
December	130·7	8th	142·2	4th	92·7	56·1	65·6	23·1
Year	148·9	...	174·2	...	92·7	61·3	74·5	20·0
Means of extremes	...	...	158·4	...	123·6	...	69·7	42·0

40. BURDWAN (*corrected*).*

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
136·5	25th	147·2	10th	123·2	59·2	66·7	49·7
139·7	28th	152·2	1st	92·2	58·5	66·7	28·6
149·3	25th	157·0	11th	127·2	58·1	69·8	47·7
155·7	17th	168·7	28th	137·2	55·3	68·0	42·8
154·7	1st	166·2	4th	145·7	56·7	70·6	51·0
154·1	8th	164·1	29th	123·7	61·0	68·5	40·9
148·4	3rd	159·6	17th	118·8	58·6	68·4	31·2
151·2	23rd	162·5	1st	132·5	61·9	70·9	46·9
154·8	21st	163·6	26th	142·0	64·1	71·3	52·4
151·1	3rd	159·2	31st	134·2	60·6	66·6	46·8
141·0	3rd	152·8	2nd	103·9	58·3	68·3	27·0
130·3	3rd	145·5	5th	91·2	55·5	63·5	16·5
147·2	...	168·7	...	91·2	59·0	71·3	16·5
...	...	158·2	...	122·6	...	68·3	40·1

* On a stand 4 feet high.

41. JESSORE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	130·8	27th	141·8	22nd	106·9	52·3	61·2	28·0
February	136·0	20th	142·7	2nd & 3rd	129·0	53·3	58·5	45·2
March	144·2	25th	153·2	11th	125·9	51·4	57·6	41·4
April	147·3	8th	154·1	27th	136·3	49·7	56·2	43·2
May	148·7	30th	155·9	21st	132·2	53·4	59·1	46·3
June	142·6	1st	161·3	22nd	110·9	50·7	64·1	21·7
July	144·0	5th	154·4	17th	105·5	54·3	65·6	19·5
August	144·0	28th	156·9	6th	106·6	54·7	68·8	22·6
September	147·0	23rd	158·1	28th	125·9	57·0	64·9	39·6
October	145·1	4th	154·2	21st	136·3	54·6	61·7	46·7
November	134·8	4th	146·4	2nd	109·2	50·9	58·2	28·2
December	124·2	1st	139·4	4th	100·1	47·9	58·7	19·2
Year	140·7	...	161·3	...	100·1	52·5	68·8	19·2
Means of extremes	...	...	151·5	...	118·7	...	61·2	33·5

* On a stand 3 feet and 4½ inches high.

42. DACCA (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	135·7	23rd	141·1	29th	132·6	60·2	66·3	54·9
February	139·5	26th	150·6	1st	111·1	57·5	64·8	43·4
March	148·5	23rd	154·1	4th	140·1	58·4	64·3	52·8
April	154·7	25th	163·9	3rd	146·6	60·0	77·3	51·4
May	153·0	8th	162·9	21st	133·8	62·5	72·0	45·8
June	144·4	4th	166·9	9th	101·1	56·7	74·4	20·4
July	149·9	11th	162·9	17th	101·2	61·5	71·0	21·5
August	149·0	13th	161·9	14th	110·5	61·5	74·6	27·0
September	150·7	23rd	160·1	25th	101·9	62·5	69·3	21·2
October	153·3	19th	164·5	11th	126·0	65·1	74·9	43·7
November	143·1	1st	156·9	2nd	123·9	60·4	71·0	44·0
December	129·3	3rd	142·1	6th	94·1	53·8	62·1	24·8
Year	146·1	...	166·9	...	94·1	60·0	77·3	20·4
Means of extremes	...	...	157·3	...	118·6	...	70·2	37·6

† On a stand 3 feet and 2½ inches high.

43. CHITTAGONG (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	139·5	24th	149·4	17th	134·9	62·8	71·1	59·8
February	140·6	2nd, 12th & 13th	148·9	27th	108·2	60·1	70·0	35·9
March	146·2	20th	155·9	2nd	88·9	62·4	73·0	8·8
April	146·8	17th	155·9	29th	109·9	59·6	67·8	32·8
May	147·7	6th	162·9	2nd	126·9	61·0	76·8	43·8
June	141·1	22nd	161·9	29th	84·9	55·8	78·8	6·8
July	142·8	23rd	155·9	29th	107·9	57·8	70·8	26·8
August	144·6	22nd	160·9	9th	99·9	60·3	73·3	20·7
September	148·7	26th	158·7	28th	107·8	63·3	75·4	29·2
October	146·2	1st	157·7	12th	97·9	60·1	70·6	19·3
November	143·9	30th	158·9	21st	134·9	62·1	78·0	52·3
December	129·2	2nd	146·4	5th	78·9	54·7	65·8	6·3
Year	143·1	...	162·9	...	78·9	60·0	78·8	6·3
Means of extremes	...	..	156·1	...	106·8	...	72·6	28·5

* On a stand 3 feet and 10 inches high.

44. CALCUTTA (ALIPORE) (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	131·2	27th	144·8	10th	113·8	55·0	64·3	40·4
February	133·3	11th	145·0	1st	77·5	54·0	65·4	13·8
March	147·1	25th	153·1	2nd	138·0	58·2	64·7	52·5
April	150·8	9th	154·8	2nd	144·7	57·0	63·4	53·3
May	154·9	27th	163·0	21st	146·3	60·9	68·0	54·2
June	146·4	8th	161·9	29th	102·5	55·6	68·6	19·9
July	146·1	5th	158·4	17th	114·9	58·0	69·9	29·3
August	147·4	29th	156·5	1st	108·5	60·1	70·0	23·6
September	149·1	18th	159·3	28th	120·5	61·2	72·1	36·5
October	145·8	11th	156·4	13th	127·5	58·1	66·7	41·7
November	135·3	4th	150·3	2nd	121·3	54·1	64·0	41·6
December	124·0	29th	136·5	5th	85·8	50·8	61·9	16·9
Year	142·6	...	163·0	...	77·5	56·9	72·1	13·8
Means of extremes	...	...	153·3	...	116·8	...	66·6	35·3

† On a stand 4 feet high.

45. SAUGOR ISLAND (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	137·6	26th	142·5	4th	133·4	59·8	66·8	55·5
February	138·3	21st	144·7	1st	108·7	57·3	65·3	30·0
March	146·3	26th	156·5	10th	125·3	59·0	65·7	40·7
April	151·4	29th	156·7	5th	145·9	59·6	65·5	54·5
May	150·2	26th	159·8	23rd	145·7	58·0	65·6	52·7
June	144·7	1st	161·7	14th	99·8	54·1	70·6	18·0
July	136·6	28th	154·9	17th	103·7	49·2	67·7	15·5
August	139·4	10th	178·2	8th	91·5	52·0	90·0	4·3
September	147·6	23rd	158·1	28th	112·5	59·6	66·9	27·3
October	147·0	3rd	157·2	11th	139·5	59·2	68·5	49·1
November	141·3	4th	148·2	28th	130·7	59·9	63·5	52·5
December	127·0	23rd	143·9	5th	80·7	53·4	72·7	10·3
Year	142·3	...	178·2	...	80·7	56·8	90·0	4·3
Means of extremes	...	...	155·2	...	118·1	...	69·1	34·2

* On forked sticks 6 inches above ground.

46. CUTTACK (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	140·6	7th	147·1	10th	136·0	56·7	62·8	51·9
February	144·2	21st	152·4	1st	102·1	55·4	66·8	20·8
March	154·2	27th	161·6	10th	128·6	58·1	66·5	43·1
April	157·6	27th	163·6	6th	151·1	56·1	61·6	52·2
May	160·6	11th	169·6	28th	151·6	57·5	63·0	47·0
June	144·3	21st	162·6	15th	103·6	51·4	67·5	14·2
July	141·3	10th	159·1	18th	106·6	53·2	66·5	15·4
August	147·6	13th	161·8	26th	124·2	57·9	68·6	36·4
September	147·6	23rd	162·6	7th	98·4	58·3	70·0	18·3
October	148·4	12th	156·6	13th	133·0	58·0	67·6	48·2
November	141·3	23rd	147·2	28th	132·6	56·5	65·4	50·8
December	130·7	3rd	146·6	5th	88·0	50·3	66·4	7·5
Year	146·5	...	169·6	...	88·0	55·8	70·0	7·5
Means of extremes	...	...	157·6	...	121·3	...	66·1	33·8

47. FALSE POINT (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	136·5†	11th	141·5	6th	130·2	61·6†	66·3	54·7
February	137·3	17th	147·1	1st	111·9	60·5	70·1	36·9
March	145·1	26th	152·4	29th	138·9	61·8	70·0	54·6
April	150·4	27th	163·5	1st	144·1	62·5	75·4	57·6
May	152·6	29th	165·8	22nd	138·0	63·2	72·6	48·6
June	148·6‡	26th	162·6	27th	114·1	59·4‡	71·9	26·3
July	143·4	16th	163·1	19th	93·1	56·3	75·0	7·0
August	151·5	11th	176·1	29th	105·1	64·1	84·9	18·3
September	138·4§	4th	165·9	24th	116·1	56·9§	78·6	27·6
October	147·8	4th	157·1	27th	138·8	59·4	68·9	53·8
November	136·5	2nd	143·9	30th	129·1	54·6	60·8	48·1
December	125·7†	7th	134·1	4th	102·1	51·2†	56·9	28·6
Year	142·8	...	176·1	...	93·1	59·3	84·9	7·0
Means of extremes	...	...	156·1	...	121·8	...	71·0	38·5

48. SAMBALPUR (NEW OBSERVATORY) (*corrected*).‖

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	Observatory opened on 16th October 1883.							
February								
March								
April								
May								
June								
July								
August								
September								
October	Imperfect.							
November	Ditto.							
December	Ditto.							
Year	128·0	5th	136·4	1st	88·4	47·3	55·1	11·5
Means of extremes	124·6†	1st	128·7	5th	118·6	49·5†	52·8	44·7

* On a stand 3 feet and 1½ inches high.

‡ Mean of 29 days.
§ „ „ 28 „

† Mean of 30 days.

‖ On a stand 4 feet high.

49. RAIPUR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	129·1	8th & 25th	134·3	23rd	115·3	48·5	51·6	41·7
February	139·0	26th	152·3	1st	126·3	51·2	58·5	48·0
March	Imperfect.							
April	159·0†	29th	166·4	6th	153·4	52·6†	56·2	49·3
May	169·6	21st	176·3	29th	153·4	59·6	62·7	54·4
June	152·7	4th	169·3	30th	101·0	57·2	67·5	21·5
July	138·1	13th	154·8	28th	105·1	50·6	62·7	25·6
August	149·5	14th, 15th & 17th.	158·4	2nd	124·4	58·9	62·7	43·4
September	143·7	20th	154·4	8th	123·4	57·1	65·1	43·2
October	141·1	1st	154·4	31st	115·4	54·0	61·1	34·4
November	133·0	5th	145·4	1st	109·6	51·8	60·8	30·4
December	125·3	14th	130·4	20th	120·4	49·6	53·8	46·8
Year	?	...	176·3	...	101·0	?	67·5	21·5
Means of extremes	...	...	?	...	?	...	?	?

† Mean of 26 days.

50. NAGPUR (*corrected*).*

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
143·0	19th	146·5	26th	136·1	60·1	69·8	56·6
149·8	24th	155·3	2nd	140·3	59·6	65·1	55·9
159·6	29th	165·5	15th	149·1	61·3	68·8	56·9
169·4	20th	176·7	6th	164·3	61·9	67·0	56·6
171·5	20th	178·3	31st	148·4	59·9	65·4	51·5
156·4	9th	174·3	15th	108·0	60·3	72·1	26·1
140·1	24th	156·9	1st	98·5	53·0	70·9	20·9
154·5	18th	165·8	2nd	134·9	62·9	71·3	48·2
149·8	17th	160·3	3rd	93·0	63·4	71·4	17·0
150·1	6th	161·1	20th	101·4	62·3	70·8	25·4
143·7	4th	153·3	1st	126·1	60·7	67·6	46·2
136·2	5th & 14th	141·4	18th	131·6	58·4	64·4	55·4
152·0	...	178·3	...	93·0	60·3	72·1	17·0
...	...	161·3	...	127·6	...	68·7	43·1

* On a stand 4 feet high.

51. SEONI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	139·7	20th	147·9	27th	131·0	61·2	69·3	56·0
February	144·4	23rd	150·7	2nd	131·7	59·9	65·4	55·4
March	154·1	25th	162·6	15th	144·7	60·8	67·2	56·4
April	163·4	20th	172·1	14th	150·7	61·0	66·8	52·3
May	165·3	16th	172·7	29th	154·2	59·8	68·5	55·5
June	151·3	2nd	166·7	16th	135·8	59·1	67·3	47·6
July	136·9	2nd	153·7	23rd	101·7	53·5	73·7	21·4
August	147·4	13th	160·9	1st	125·0	59·8	69·8	41·9
September	144·8	29th	158·7	3rd	114·8	61·0	75·4	34·3
October	143·9	4th	156·7	20th	99·5	59·3	71·0	18·4
November	142·8	17th	150·8	2nd & 26th	138·0	63·2	71·2	58·9
December	136·0	15th	148·1	14th	130·0	61·6	73·0	53·7
Year	147·5	...	172·7	...	99·5	60·0	75·4	18·4
Means of extremes	...	...	158·5	...	129·8	...	69·9	46·0

* On a stand 1 foot 10 inches high.

52. JUBBULPORE (*corrected*).†

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
137·3	23rd	143·3	27th	130·3	59·5	68·5	55·5
Imperfect.							
149·1	24th	160·7	11th	131·5	56·8	64·5	52·0
162·3	21st & 29th	172·0	6th	153·0	58·6	66·0	55·1
168·1	19th	174·1	28th	152·4	61·7	68·7	57·5
156·7‡	3rd	173·2	24th	118·0	59·0‡	68·0	21·8
151·7§	20th	166·8	27th	126·5	65·4§	77·8	39·1
159·2	25th	167·2	3rd	125·0	69·8	78·2	42·8
156·0	30th	169·5	16th	143·0	69·8	79·4	60·6
156·6	1st	170·0	20th	108·4	70·3	79·4	37·0
149·3	3rd	159·8	28th	144·6	68·4	77·0	64·2
141·6	24th	147·8	6th	136·2	67·7	73·4	61·3
?	...	174·1	...	108·4	?	79·4	21·8
...	...	?	...	?	...	?	?

† On a stand 3 feet high. ‡ Mean of 29 days. § Mean of 27 days.

53. SAUGOR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	136·4	20th	146·2	26th	86·2	60·1	67·3	24·2
February	143·9	17th	156·7	2nd	128·2	63·7	70·4	55·9
March	153·2	3rd	161·2	12th	142·7	62·6	70·9	57·6
April	163·8	13th	176·2	3rd, 5th & 6th.	157·2	61·3	69·8	53·8
May	162·5	19th & 21st	171·2	27th	153·2	57·7	66·9	51·8
June	154·5	3rd	166·2	30th	115·2	56·7	74·4	32·9
July	137·0	3rd	159·2	25th	92·2	52·2	70·4	17·4
August	149·4	19th	164·2	21st	115·7	61·7	72·9	34·6
September	148·0	24th	162·2	12th, 13th, 16th & 18th.	126·2	62·3	74·1	41·4
October	145·1	2nd	164·2	19th	88·2	59·5	76·1	15·4
November	141·6	4th	152·7	24th	137·2	60·9	71·9	56·9
December	138·0	9th & 16th	141·2	2nd & 31st	134·2	64·7	69·0	57·4
Year	147·8	...	176·2	...	86·2	60·3	76·1	15·4
Means of extremes	...	...	160·1	...	123·0	...	71·2	41·6

* On a stand 8 feet 8 inches high.

54. PACHMARHI (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	131·2	23rd	140·7	26th	108·5	59·4	65·9	36·9
February	135·9	23rd	142·4	2nd	123·1	59·5	64·3	55·1
March	142·7	24th	155·2	15th	123·6	59·0	68·8	50·1
April	153·4	12th	163·9	5th	145·4	59·0	69·0	54·2
May	153·8	21st	158·6	27th	143·5	57·9	66·9	53·1
June	147·5	11th	158·3	30th	106·6	61·1	73·8	33·1
July	126·1	12th	148·2	1st	82·0	50·7	68·4	10·5
August	138·8	8th	153·4	21st	109·8	60·6	73·3	36·1
September	132·8	29th	149·6	9th	88·6	57·0	72·3	17·9
October	135·7	2nd	154·1	20th	92·0	59·7	76·2	25·5
November	134·3	3rd	145·1	21st	128·5	63·D	73·0	55·7
December	128·6	13th	135·6	4th	124·3	61·9	66·5	58·8
Year	138·4	...	163·9	...	82·0	59·1	76·2	10·5
Means of extremes	...	...	150·4	...	114·7	...	69·9	40·6

† On a stand 3 feet high.

55. HOSHANGABAD (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	136·2	9th	142·0	26th	87·0	55·2	60·1	21·6
February	143·2	17th	151·6	2nd	132·6	57·8	61·8	54·5
March	152·5	30th & 31st	161·6	14th	140·0	57·6	60·1	53·9
April	161·4	20th	170·4	4th	154·2	54·9	61·6	49·6
May	160·4	20th	170·2	28th	147·4	52·6	57·2	50·2
June	151·3	3rd	166·8	30th	135·6	53·7	60·9	48·9
July	139·1	14th	155·6	23rd	102·6	52·9	64·0	23·4
August	146·1	13th	155·0	21st	111·0	57·4	66·5	28·5
September	137·4	23rd	151·2	9th	98·6	51·9	63·5	19·8
October	142·6	10th	157·2	19th	97·6	56·1	70·5	25·7
November	135·8	3rd	142·2	22nd	131·4	54·0	58·1	50·3
December	128·3	1st	131·4	22nd	120·4	52·9	54·8	48·1
Year	144·5	...	170·4	...	87·0	54·8	70·5	19·8
Means of extremes	...	...	154·6	...	121·5	...	61·6	39·5

56. KHANDWA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	143·1	21st	150·6	26th	123·6	59·5	66·1	53·0
February	148·6	17th	158·9	1st	136·6	60·2	68·0	55·9
March	155·8	27th	163·6	12th	148·1	60·4	67·2	57·2
April	165·5	20th	173·3	4th	156·7	59·5	64·3	55·6
May	163·3	19th & 31st	167·6	24th	158·8	56·9	65·1	54·0
June	154·5	1st	167·0	27th	115·6	59·3	71·3	32·6
July	143·5	12th	161·1	2nd	110·1	56·9	71·4	31·8
August	146·1	15th	160·4	30th	102·2	58·4	67·2	27·1
September	140·9	27th	157·9	3rd	103·4	56·8	68·1	23·4
October	146·2	10th	157·4	19th	113·9	59·6	69·2	46·1
November	142·1	14th	146·6	21st & 22nd	139·0	58·6	62·7	56·9
December	135·2	1st	138·4	31st	129·3	57·3	59·4	54·0
Year	148·7	...	173·3	...	102·2	58·6	71·4	23·4
Means of extremes	...	...	158·6	...	128·1	...	66·7	45·6

* On a stand 4 feet high.

57. CHANDA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	133·1	11th	138·8	28th	126·9	47·6	57·8	43·7
February	140·2	26th	146·8	2nd	129·8	46·6	53·3	44·1
March	149·3	28th	157·4	12th	138·8	49·4	64·1	45·2
April	158·5	17th	169·3	8th	152·9	49·6	61·6	44·6
May	162·0	16th	168·8	1st & 27th	159·1	49·8	58·0	46·0
June	146·0	3rd	162·9	14th	120·1	50·5	60·5	34·0
July	137·3	19th	153·7	1st	84·4	49·2	61·3	9·0
August	141·2	16th	152·4	20th	117·4	50·5	63·7	35·1
September	137·3	16th	150·6	2nd	101·2	50·5	61·9	22·4
October	136·7	16th	146·9	20th	105·9	48·5	57·9	28·2
November	127·2	2nd	138·3	25th & 29th	122·9	45·0	55·9	41·7
December	120·9	13th	125·6	18th, 19th & 26th	118·8	42·5	44·4	40·1
Year	140·8	...	169·3	...	84·4	48·3	64·1	9·0
Means of extremes	...	...	151·0	...	123·2	...	58·4	36·2

* On a stand 4 feet high.

58. SIRONCHA (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	142·4	30th	148·4	26th	137·2	56·9	68·1	52·6
February	147·9	26th	152·2	5th	142·6	54·0	63·2	49·7
March	153·8	16th, 20th & 31st	160·2	12th	146·8	55·1	65·4	49·5
April	157·7	28th	165·2	2nd	132·2	51·1	55·5	36·2
May	161·4	23rd	167·8	30th	155·4	50·2	54·6	46·9
June	143·3	8th	166·2	30th	103·2	50·3	68·0	21·6
July	134·2	21st	150·2	8th	97·2	47·3	62·0	20·7
August	142·0	13th	160·2	23rd	101·2	53·5	66·1	23·7
September	141·2	13th	155·6	3rd	100·4	55·4	67·5	22·9
October	148·0	4th	156·4	31st	124·5	58·4	64·7	39·9
November	143·4	4th	150·4	30th	136·4	59·3	64·2	55·3
December	135·4	13th	143·4	14th	103·2	55·7	62·7	27·3
Year	145·9	...	167·8	...	97·2	53·9	68·1	20·7
Means of extremes	...	...	156·4	...	123·4	...	63·5	37·2

† On a stand 3 feet high.

59. CHIKALDA (*corrected*).*

Month.	Mean.	Maximum.		Minimum		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	139·6	10th	149·9	26th	114·3	66·8	75·2	44·7
February	145·3	19th	153·6	1st	138·3	66·2	72·8	62·3
March	151·1	23rd	165·9	15th	136·6	66·4	76·2	61·1
April	158·2	15th	164·7	4th	150·9	64·7	71·9	60·1
May	155·7	19th	164·9	27th	149·9	61·3	69·7	58·2
June	146·7	3rd	162·4	27th	97·4	63·8	73·4	26·3
July	133·5	30th	150·0	1st	87·4	59·4	75·1	15·9
August	137·2	19th	160·6	25th	99·0	62·1	82·6	25·1
September	133·2	28th	159·9	9th	93·8	59·5	79·7	23·8
October	141·3	8th	153·0	19th	77·4	65·8	79·9	6·7
November	142·3	2nd	153·6	30th	135·8	69·2	78·9	63·9
December	135·2	14th	140·8	22nd	128·9	66·3	72·4	62·2
Year	143·2	...	165·9	...	77·4	64·3	82·6	6·7
Means of extremes	...	...	156·6	...	117·5	...	75·7	42·5

60. BULDANA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	129·1	7th	139·7	26th	108·1	48·1	56·8	29·2
February	138·4	23rd	146·0	1st	125·0	51·4	55·9	46·9
March	146·6	17th	156·7	15th	134·7	54·5	62·3	50·6
April	157·6	15th	166·7	4th	148·5	56·8	66·6	51·3
May	157·6	30th	165·7	25th	152·7	56·1	67·1	51·9
June	146·7	16th	159·7	28th	124·2	57·7	70·5	42·8
July	135·9	13th	152·9	9th	96·8	54·0	69·0	22·0
August	135·4	8th	154·2	22nd	88·6	53·0	67·1	17·3
September	131·9	11th	144·7	9th	89·7	52·7	66·6	17·7
October	133·7	10th	144·9	1st	101·7	52·4	60·9	25·1
November	126·6	2nd	136·1	3rd	111·7	47·4	56·6	34·5
December	119·6	12th	123·3	19th	117·4	44·6	48·6	42·7
Year	138·3	...	166·7	...	88·6	52·4	70·5	17·3
Means of extremes	...	...	149·2	...	116·6	...	62·3	36·0

* On a stand 4 feet high.

61. AKOLA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	145·3	19th	154·6	26th	123·6	60·1	69·6	41·0
February	151·3	17th & 18th	158·8	1st	141·9	59·2	63·9	52·9
March	156·6	31st	162·2	12th	149·6	58·5	63·9	55·4
April	165·1	15th	174·2	4th	157·6	58·2	66·8	54·1
May	163·3	20th	176·5	31st	151·7	55·3	62·8	50·2
June	152·0	1st	166·5	28th	127·2	57·9	65·4	38·3
July	140·0	21st	155·8	1st	94·7	53·1	66·0	9·9
August	142·7	11th	158·9	25th	106·0	54·1	65·4	26·0
September	145·4	28th	157·0	8th	103·5	60·9	72·3	26·2
October	147·9	9th	156·6	20th	135·3	61·1	70·6	56·6
November	144·5	4th	156·8	30th	140·5	60·6	71·1	58·0
December	138·9	13th	142·3	23rd	136·7	60·0	63·2	57·9
Year	149·4	...	176·5	...	94·7	58·3	72·3	9·9
Means of extremes	...	...	160·0	...	130·7	...	66·8	43·9

62. AMRAOTI (*corrected*).*

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
141·3	23rd	154·1	27th	130·1	56·7	68·0	52·6
145·7	21st	153·4	2nd	137·2	54·2	59·6	49·2
153·2	30th	159·6	15th	143·0	54·8	58·0	52·2
161·1	21st	168·4	4th	154·8	54·2	60·0	49·5
160·6	7th	166·1	31st	144·8	51·6	58·7	46·1
149·7	3rd	165·0	30th	122·4	54·6	68·3	32·5
135·7	22nd	152·1	26th	96·0	49·1	68·0	12·3
144·2	18th	161·6	30th	110·1	54·6	68·0	29·4
139·1	29th	157·1	3rd	102·1	54·4	68·7	22·1
144·3	2nd	156·1	14th	123·4	57·7	68·0	41·4
140·1	16th	149·0	22nd	135·1	56·9	65·3	52·8
134·6	13th	140·1	18th	131·5	55·8	58·9	52·4
145·8	..	168·4	...	96·0	54·6	68·7	12·3
...	...	156·9	...	127·5	..	64·1	41·0

* On a stand 4 feet high.

63. NEEMUCH (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	140·8	19th	150·7	26th	130·9	63·9	71·5	58·2
February	143·6	17th & 18th	149·9	27th	133·7	64·8	72·4	54·6
March	150·6	30th	158·7	9th	138·7	61·7	69·8	52·8
April	161·8	25th	169·7	4th	153·8	59·8	68·4	55·3
May	159·7	19th	169·9	27th	141·8	57·1	66·1	51·9
June	156·3	9th	165·7	27th	111·7	58·7	69·4	28·2
July	146·9	8th	159·5	24th	121·8	61·0	71·2	40·0
August	153·1	27th	168·5	31st	99·6	63·8	77·6	18·7
September	146·3	28th	162·9	12th	97·7	61·4	73·7	19·8
October	153·0	12th	162·6	20th	141·6	65·2	73·7	57·8
November	145·8	7th & 11th	153·7	24th	139·7	62·7	68·4	57·8
December	138·9	29th	142·3	31st	132·9	64·0	67·6	61·0
Year	149·7	...	169·9	...	97·7	62·0	77·6	18·7
Means of extremes	...	...	159·5	...	128·7	...	70·8	46·3

64. NOWGONG (*corrected*).†

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
132·0	7th	140·5	26th	76·8	56·5	67·9	6·9
137·7	18th	145·5	1st	125·8	59·0	64·9	55·7
152·3	25th	166·5	8th	142·3	59·5	66·1	54·4
165·6	22nd	178·3	5th	157·3	58·8	66·3	54·8
166·6	19th	177·8	27th	153·0	57·2	64·0	52·3
159·8‡	10th	171·8	29th	133·2	54·6‡	63·1	40·3
143·1§	30th	174·5	23rd	94·0	52·9§	87·9	13·6
149·9	19th	159·5	29th	115·8	56·5	69·1	29·2
148·8	1st	160·8	18th	124·3	56·3	69·2	38·2
148·3	2nd	159·8	19th	101·0	56·7	66·4	25·9
140·5	7th	155·8	16th	131·5	57·3	73·4	52·4
128·6	1st & 2nd	133·5	31st	121·8	53·4	56·9	48·7
147·8	...	178·3	...	76·8	56·6	87·9	6·9
..	...	160·4	...	123·1	...	67·9	39·4

* On a stand 4 feet high.

† On a stand 3 feet 4½ inches high.

‡ Mean of 29 days.

§ Mean of 30 days.

65. SUTNA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	132·6	2nd	140·0	9th	87·5	60·1	72·0	26·1
February	139·2	18th	148·7	3rd & 5th	131·7	62·8	73·1	56·1
March	147·7	31st	154·7	11th	139·5	59·1	66·9	53·3
April	159·7	20th	167·4	2nd & 6th	152·7	57·8	62·5	54·3
May	162·0	17th	169·5	23rd	151·7	56·8	61·9	52·4
June	158·0	3rd	168·5	27th	142·7	60·5	73·7	52·8
July	145·8	2nd & 10th	159·5	29th	112·7	59·5	73·1	34·4
August	150·5	28th	169·5	4th	119·7	61·9	81·2	38·1
September	148·3†	5th, 11th & 20th.	155·7	6th	128·7	62·1†	75·7	46·9
October	144·5	9th	154·7	20th	107·5	59·3	70·1	42·6
November	138·9	2nd	145·7	28th	133·0	59·8	66·9	55·2
December	130·5	8th	137·7	31st	119·7	58·5	65·9	50·4
Year	146·5	...	169·5	...	87·5	59·9	81·2	26·1
Means of extremes	...	...	155·5	...	127·3	...	70·3	46·9

* On a stand 4 feet high. † Mean of 29 days.

66. INDORE (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	138·4	16th	143·7	27th	128·3	59·2	68·8	53·9
February	142·5	17th	149·5	2nd	131·8	59·8	71·8	55·1
March	148·8	2nd	155·5	12th	140·7	58·5	65·8	51·9
April	159·1	20th	170·5	4th	150·7	57·4	65·2	53·5
May	159·2	19th	165·4	27th	145·7	56·9	60·8	52·8
June	151·7	3rd	165·8	11th	130·8	58·2	65·8	42·7
July	140·7	4th	154·9	7th, 9th & 24th.	121·9	57·0	67·8	39·8
August	143·7	18th	152·0	21st	124·5	57·7	64·7	42·3
September	139·9	27th	153·4	10th & 11th	121·9	56·6	63·8	33·3
October	142·8	4th	151·9	19th	120·9	58·7	66·6	43·8
November	137·6	8th	144·5	2nd	133·7	57·2	60·2	53·1
December	132·0	26th	136·8	22nd	126·5	57·3	62·8	53·8
Year	144·7	...	170·5	...	120·9	57·9	71·8	33·3
Means of extremes	...	...	153·7	...	131·5	...	65·3	48·0

‡ On a stand 3·8 feet high.

67. BICKANEER (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	144·5	5th	155·8	24th	111·8	73·9	83·3	44·3
February	152·5	17th	164·7	1st	140·8	78·1	85·8	70·8
March	163·4	29th	181·3	11th	148·3	77·6	88·8	69·8
April	176·5	16th	183·3	4th	164·8	74·7	82·7	69·2
May	175·8	20th	187·3	27th	156·3	71·9	83·8	64·7
June	175·2	26th	182·8	5th	167·3	68·5	79·7	62·7
July	159·6	15th	183·3	1st	156·8	72·9	86·7	61·8
August	170·9	27th, 28th & 31st.	180·3	6th	163·3	?	?	?
September	172·7	7th & 9th	181·3	15th	165·3	?	?	?
October	169·1	2nd	178·3	26th	158·8	Imperfect.		
November	153·9	8th	163·8	13th	141·3	73·5	82·2	68·6
December	147·7	28th	154·3	30th	137·3	74·6	78·7	70·3
Year	164·3	...	187·3	...	111·8	?	88·8	44·3
Means of extremes	...	...	174·7	...	151·0	...	?	?

* On a stand 4 feet high.

68. JEYPORE (*corrected.*)†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	129·1	10th	140·2	25th	102·0	55·8	71·1	41·9
February	133·4	24th	146·0	17th	113·7	57·9	64·8	38·4
March	149·7	28th	163·4	12th	139·1	61·9	69·0	56·9
April	161·7	14th	173·2	3rd	154·2	58·8	69·3	55·7
May	161·9	21st	172·4	29th	146·9	57·9	66·1	52·7
June	159·5	14th	169·5	30th	133·3	57·8	69·7	41·7
July	147·8	12th	160·0	24th	114·3	57·2	67·9	29·8
August	159·2	28th	172·3	30th	149·5	61·9	70·9	55·3
September	156·2	26th	167·8	4th	134·0	62·9	70·5	50·9
October	151·9	1st	164·5	20th	141·0	58·5	68·5	54·6
November	138·6	10th	146·0	17th	131·8	55·7	62·2	50·8
December	128·7	12th	134·0	30th	120·8	53·6	56·2	50·1
Year	148·1	...	173·2	...	102·0	58·3	71·1	29·8
Means of extremes	...	...	159·1	...	131·7	...	67·2	48·2

† On a stand 4 feet high from March, previously 5 feet.

69. SAMBHAR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	128·1	19th & 20th	134·3	30th	119·3	56·0	71·4	48·9
February	133·2	24th	144·8	1st	122·3	58·9	67·9	45·4
March	148·4	17th	160·3	12th	136·3	61·9	70·8	57·4
April	160·1	23rd	165·3	4th	150·3	58·4	62·3	53·6
May	161·1	12th	173·5	24th	150·5	58·4	67·8	51·6
June	158·0	14th	165·3	30th	144·3	56·1	64·5	48·1
July	148·2†	13th	160·8	16th	116·3	57·7†	71·4	33·9
August	151·5	27th	160·3	11th	147·1	55·2	62·7	47·6
September	145·9	1st	156·3	6th	123·3	54·2	66·9	40·9
October	146·1	11th	161·6	20th	136·5	54·7	65·1	48·7
November	133·6	10th	141·3	16th	126·3	52·7	61·2	48·9
December	124·8	21st	127·8	17th	117·3	51·2	56·0	46·0
Year	144·9	...	173·5	...	116·3	56·3	71·4	33·9
Means of extremes	...	...	154·3	...	132·5	...	65·7	47·6

* On a stand 3½ feet high. † Mean of 30 days.

70. AJMERE (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	125·8	8th & 21st	135·8	29th	114·8	52·8	68·5	44·7
February	128·0	28th	139·8	1st & 2nd	116·8	52·7	59·7	46·7
March	138·4	31st	150·8	12th	128·8	53·2	60·7	42·8
April	149·0	23rd	156·8	2nd	140·8	50·0	56·8	44·8
May	148·9	11th	156·8	27th	135·8	48·3	59·7	44·8
June	147·3	15th	167·8	27th	134·8	49·0	75·7	34·8
July	138·7	29th	147·8	7th	96·8	50·8	58·7	17·7
August	144·7	27th	153·8	5th, 10th & 11th	136·8	50·6	58·7	44·7
September	143·4	24th & 30th	150·8	20th	129·8	54·4	61·7	48·7
October	142·3	11th	149·8	20th	130·8	52·1	56·8	46·7
November	133·1	7th	164·8	15th	122·8	52·0	78·7	42·2
December	122·5	1st & 2nd	129·8	30th	112·8	48·3	54·6	44·6
Year	138·5	...	167·8	...	96·8	51·2	78·7	17·7
Means of extremes	...	...	150·4	...	125·1	...	62·5	41·9

‡ On a stand 3 feet 11 inches high.

71. MOUNT ABU (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	132·7	20th	146·1	25th	80·5	65·7	76·8	22·2
February	138·1	27th	146·5	1st	129·6	68·6	72·1	64·0
March	144·3	29th	152·1	12th	135·2	68·1	78·9	62·6
April	150·6	13th	160·0	3rd & 28th	144·0	62·1	70·9	57·7
May	147·6	7th	154·5	29th	137·1	59·8	66·3	54·9
June	141·9	21st	151·6	30th	130·2	58·3	67·4	52·3
July	127·5	14th	150·3	10th	91·6	53·5	70·2	18·2
August	135·4	28th	153·3	6th	116·4	58·8	71·9	44·3
September	130·2	25th	151·0	11th	81·8	56·2	70·8	14·0
October	141·2	5th	150·1	1st	132·0	63·7	70·0	57·6
November	135·0	23rd	142·9	10th & 11th	130·1	63·6	68·9	60·5
December	132·5	27th	139·4	4th	126·0	64·7	68·6	60·0
Year	138·1	...	160·0	...	80·5	61·9	78·9	14·0
Means of extremes	...	...	149·8	...	119·5	...	71·1	47·4

72. PACHBADRA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	142·2	21st & 24th	151·2	29th	131·2	62·6	67·6	56·6
February	146·8	16th	156·2	1st	137·2	65·2	71·6	58·6
March	158·0	29th & 30th	171·2	4th	146·2	66·7	73·6	59·6
April	169·2	10th	180·2	1st—4th	163·2	63·4	70·7	59·7
May	167·9	20th	179·2	24th & 28th	156·2	61·0	68·7	56·7
June	179·2	19th	185·2	28th	167·2	73·4	78·7	59·7
July	167·9†	28th	186·6	27th	157·2	73·3†	87·8	60·4
August	163·7	27th	177·6	26th	148·2	62·9	73·4	43·7
September	165·3‡	29th	180·2	12th	143·6	69·7‡	82·4	56·6
October	164·0	1st	176·4	6th	151·4	66·5	80·6	52·5
November	150·9	4th & 8th	161·2	29th	144·5	64·0	72·2	56·6
December	143·8	30th	158·2	23rd	137·5	64·5	85·6	57·8
Year	159·9	...	186·6	...	131·2	66·1	87·7	43·7
Means of extremes	...	...	172·0	...	148·6	...	76·1	56·5

* On a stand 4 feet high. † Mean of 30 days. ‡ Mean of 29 days.

73. JACOBABAD (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.			Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	137·7	8th	150·6	12th	120·6	65·7	84·6	48·7	135·5	18th	142·7	24th	106·3	60·0	66·0	33·0
February . .	142·5	25th	151·8	23rd	117·6	66·5	73·4	43·9	141·1	26th	155·5	19th	110·7	62·0	67·8	40·2
March . .	154·1	28th	167·5	10th	129·5	66·9	73·3	54·2	154·2	29th	165·5	10th	141·8	64·1	70·6	56·7
April . . .	166·8	28th	179·4	4th	158·4	63·5	69·7	59·2	163·4	9th	171·9	4th & 30th	156·3	59·9	65·5	55·5
May . . .	170·8	20th	182·2	27th	159·2	63·9	70·0	55·1	163·8	13th	173·3	24th	152·3	56·0	60·9	51·5
June . . .	170·8	2nd	179·4	30th	164·4	57·0‡	68·1	54·2	159·5	1st	171·3	30th	142·7	55·6	59·1	44·3
July . . .	165·1	8th	180·8	10th	149·0	60·9	70·0	46·7	153·1	2nd	164·3	4th	120·5	56·5	64·1	31·3
August . .	163·6	25th	170·8	14th	158·6	58·8	69·5	56·9	153·8	26th	162·3	31st	132·5	57·5	64·7	41·9
September . .	163·2†	11th	168·8	30th	157·4	60·2†	64·0	56·4	153·4	4th	157·7	3rd	136·9	57·6	61·3	46·3
October . .	156·5	5th	164·4	25th	129·2	59·6	64·4	41·3	155·9	18th	162·7	26th	146·3	58·3	60·7	55·1
November . .	142·9	8th	154·9	30th	134·3	58·9	62·0	55·2	143·0	6th	155·1	12th	131·3	58·4	62·9	55·4
December . .	130·6	5th	136·8	7th	98·9	55·5	62·6	33·8	134·7	14th	139·5	31st	129·3	57·1	60·6	54·8
Year . . .	155·4	...	182·2	...	98·9	61·5	84·6	33·8	151·0	...	173·3	...	106·3	58·6	70·6	31·3
Means of extremes	...	...	165·6	...	139·8	...	69·3	50·5	...	...	160·2	...	133·9	...	63·7	47·2

* On a stand 4 feet high. † Mean of 28 days. ‡ Mean of 24 days.

74. HYDERABAD (*corrected*).§

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.			Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	135·5	18th	142·7	24th	106·3	60·0	66·0	33·0	138·5	8th	151·4	24th	105·6	61·0	71·5	33·2
February . .	141·1	26th	155·5	19th	110·7	62·0	67·8	40·2	144·0	25th	155·5	24th	134·6	65·9	75·4	56·9
March . .	154·2	29th	165·5	10th	141·8	64·1	70·6	56·7	153·1	27th	165·7	10th	144·4	68·5	78·4	62·7
April . . .	163·4	9th	171·9	4th & 30th	156·3	59·9	65·5	55·5	157·6	8th	167·6	2nd	151·9	68·2	76·9	63·1
May . . .	163·8	13th	173·3	24th	152·3	56·0	60·9	51·5	158·7	12th	172·2	2nd	145·4	66·0	69·9	57·5
June . . .	159·5	1st	171·3	30th	142·7	55·6	59·1	44·3	161·6	7th	169·0	10th	157·8	67·8	75·8	62·1
July . . .	153·1	2nd	164·3	4th	120·5	56·5	64·1	31·3	157·1	14th	170·8	4th	123·6	68·6	79·8	36·7
August . .	153·8	26th	162·3	31st	132·5	57·5	64·7	41·9	155·9	3rd	163·2	24th	140·3	70·0	77·2	56·4
September . .	153·4	4th	157·7	3rd	136·9	57·6	61·3	46·3	155·9	2nd	164·1	13th	125·6	69·1	77·2	42·4
October . .	155·9	18th	162·7	26th	146·3	58·3	60·7	55·1	158·0	14th	167·5	1st	147·5	65·4	72·3	55·5
November . .	143·0	6th	155·1	12th	131·3	58·4	62·9	55·4	152·5	1st	159·6	13th	144·3	67·2	74·8	63·2
December . .	134·7	14th	139·5	31st	129·3	57·1	60·6	54·8	145·5	26th	150·6	8th	132·6	66·3	70·6	54·9
Year . . .	151·0	...	173·3	...	106·3	58·6	70·6	31·3	153·2	...	172·2	...	105·6	67·0	79·8	33·2
Means of extremes	...	...	160·2	...	133·9	...	63·7	47·2	...	...	163·1	...	137·8	...	75·0	53·7

§ On a stand 3·9 feet high.

75. KURRACHEE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.			Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	138·5	8th	151·4	24th	105·6	61·0	71·5	33·2	144·8	8th	153·5	26th	139·0	64·9	72·1	60·5
February . .	144·0	25th	155·5	24th	134·6	65·9	75·4	56·9	149·8	16th	163·3	1st	141·0	67·3	74·1	61·4
March . .	153·1	27th	165·7	10th	144·4	68·5	78·4	62·7	153·7	28th	163·7	5th	120·6	64·0	76·0	38·2
April . . .	157·6	8th	167·6	2nd	151·9	68·2	76·9	63·1	163·9	12th	171·3	3rd	155·0	61·5	68·7	58·5
May . . .	158·7	12th	172·2	2nd	145·4	66·0	69·9	57·5	163·2	30th	169·0	2nd	156·0	62·4	69·6	59·6
June . . .	161·6	7th	169·0	10th	157·8	67·8	75·8	62·1	165·0	12th	178·9	29th	146·7	66·4	77·5	60·1
July . . .	157·1	14th	170·8	4th	123·6	68·6	79·8	36·7	151·1	14th	167·0	4th	105·0	63·3	75·0	23·8
August . .	155·9	3rd	163·2	24th	140·3	70·0	77·2	56·4	157·1	18th	165·5	31st	138·3	66·4	74·7	49·9
September . .	155·9	2nd	164·1	13th	125·6	69·1	77·2	42·4	155·6	21st	165·3	13th	128·0	66·5	74·0	44·9
October . .	158·0	14th	167·5	1st	147·5	65·4	72·3	55·5	158·3	17th	165·0	20th	152·0	62·5	70·5	59·0
November . .	152·5	1st	159·6	13th	144·3	67·2	74·8	63·2	148·3	7th	156·5	23rd	141·0	61·5	66·7	57·4
December . .	145·5	26th	150·6	8th	132·6	66·3	70·6	54·9	141·1	28th	147·0	31st	130·0	60·7	64·1	56·5
Year . . .	153·2	...	172·2	...	105·6	67·0	79·8	33·2	154·3	...	178·9	...	105·0	64·0	77·5	23·8
Means of extremes	...	...	163·1	...	137·8	...	75·0	53·7	...	...	163·8	...	137·7	...	71·9	52·5

* On a stand 4 feet high.

76. BHUJ (*corrected*).*

77. RAJKOT (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	145·4	16th	154·8	26th	133·0	61·0	71·1	53·1
February	147·1	24th	155·1	1st	139·3	60·5	65·1	54·2
March	152·9	16th	162·8	13th	142·0	59·4	67·1	54·8
April	159·5	13th	169·5	4th	152·4	55·2	64·2	51·6
May	156·9	31st	165·3	27th	149·1	52·0	56·8	48·3
June	154·5	1st	164·0	29th	118·8	54·0	61·5	31·6
July	143·4	5th	161·8	3rd	93·4	53·3	71·2	13·0
August	148·6	24th	160·4	30th	125·5	55·2	65·5	33·0
September	147·2	27th	160·3	6th	121·8	59·3	69·7	40·0
October	151·4	4th	158·4	18th	127·8	58·5	64·6	35·9
November	147·9	8th	153·4	22nd	143·0	59·9	66·0	55·9
December	143·5	28th	147·8	31st	136·3	61·0	64·8	57·6
Year	149·9	...	169·5	...	93·4	57·4	71·2	13·0
Means of extremes	...	...	159·5	...	131·9	...	65·6	44·1

78. DEESA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	138·8	16th	149·9	25th	123·5	55·9	63·3	49·1
February	141·8	24th	153·1	1st	130·5	57·1	64·1	49·9
March	149·4	30th	158·2	6th	132·9	57·1	64·9	52·2
April	157·5	13th	171·5	3rd	150·7	52·0	64·3	49·0
May	154·8	20th	163·0	27th	147·7	49·4	55·2	42·6
June	154·9	23rd	164·4	29th	147·4	52·3	60·9	46·5
July	145·4	14th	159·8	10th	95·0	55·1	64·5	5·9
August	147·9	18th	158·1	30th	119·1	53·2	60·8	24·6
September	141·6	19th	157·1	11th	105·9	51·3	64·0	22·9
October	146·1	12th	157·5	18th	133·9	51·3	60·3	41·2
November	138·2	2nd	144·3	16th & 29th	130·6	50·1	58·0	44·2
December	133·1	28th	139·0	31st	125·0	49·9	53·6	47·0
Year	145·8	...	171·5	...	95·0	52·9	64·9	5·9
Means of extremes	...	...	156·3	...	128·5	...	61·2	39·6

* On a stand 4 feet high.

79. SURAT (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	141·4	11th	149·7	27th	130·5	54·3	59·4	49·8
February	145·4	24th	153·9	1st	135·3	56·0	62·4	50·3
March	149·5	29th	157·5	14th & 18th	141·3	55·3	60·6	50·2
April	155·2	8th	170·5	13th	144·5	54·4	65·3	48·9
May	153·9	29th	162·3	16th	147·5	55·6	65·9	47·0
June	145·7	12th	158·3	29th	105·5	53·5	65·2	25·7
July	142·8†	19th	151·7	12th	120·3	56·5†	65·8	36·0
August	144·4	18th	153·7	30th	114·5	55·5	65·8	34·6
September	143·8	30th	151·3	7th	103·5	58·8	66·0	24·2
October	144·4	15th	153·7	20th	134·9	55·5	63·0	50·3
November	140·1	8th	143·9	30th	136·7	53·0	57·5	51·2
December	135·6	11th & 23rd	138·5	31st	131·9	52·3	56·2	49·8
Year	145·2	...	170·5	...	103·5	55·1	66·0	24·2
Means of extremes	...	...	153·8	...	128·9	...	62·8	43·2

80. MALEGAON (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	144·3	22nd	151·5	27th	135·7	60·1	66·5	54·8
February	148·9	27th	155·1	1st	138·4	58·9	66·5	56·8
March	154·1	27th	160·1	14th	148·1	58·2	64·5	54·5
April	161·4	19th	168·3	5th	153·7	55·7	64·1	53·4
May	158·7	6th	168·4	31st	147·7	54·1	60·3	47·9
June	147·3	2nd	157·9	28th	109·1	54·2	62·5	26·9
July	138·0	19th	151·4	2nd	85·7	52·6	62·9	3·8
August	141·6	14th	162·1	22nd	98·7	54·2	69·2	19·6
September	141·4	25th	155·5	10th	99·4	58·5	71·3	22·3
October	144·9	15th	153·5	19th	117·4	60·2	70·7	40·3
November	143·7	5th	152·1	21st	138·7	60·7	66·9	56·9
December	132·1	3rd	140·1	20th	125·0	50·8	61·6	42·5
Year	146·4	...	168·4	...	85·7	56·7	71·3	3·8
Means of extremes	...	...	156·3	...	124·8	...	65·6	40·0

* On a stand 4·3 feet high. † Mean of 29 days. ‡ On a stand 4 feet high

81. BOMBAY (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	137·3	4th	142·1	27th	133·5	53·8	56·9	49·7
February	137·5	5th	144·9	1st	134·5	55·0	62·6	52·3
March	139·4	26th	145·0	28th	135·9	54·9	57·5	51·8
April	142·0	17th & 26th	145·8	3rd	137·5	53·5	57·3	50·0
May	144·3	23rd & 30th	148·9	3rd	141·1	54·0†	57·9	50·2
June	135·6	19th	150·7	13th	94·5	48·6	61·8	10·6
July	128·0	28th	141·5	2nd	92·6	43·8	56·2	10·9
August	128·1	19th	144·5	23rd	94·9	44·0	58·9	15·6
September	133·2	29th	148·5	23rd	106·3	50·2	63·9	25·7
October	138·1	16th	149·9	19th	89·9	52·1	65·0	12·9
November	138·6	6th	147·1	29th	133·4	53·0	58·4	49·8
December	133·5	2nd	137·8	23rd	118·7	51·0	54·7	39·5
Year	136·3	...	150·7	...	89·9	51·2	65·0	10·6
Means of extremes	...	...	145·6	...	117·7	...	59·3	34·9

† Mean of 30 days.

82. POONA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	138·0	21st	146·3	27th	132·5	53·4	63·3	49·8
February	145·8	10th	153·3	1st	138·3	53·9	62·8	51·0
March	Imperfect.							
April	160·3	14th	168·9	3rd & 4th	152·9	58·0	65·5	52·8
May	154·9	5th	169·7	26th	145·4	54·2	67·1	50·0
June	142·1	11th	158·8	26th	127·9	55·6	69·0	46·1
July	133·6	11th	144·9	2nd	102·9	52·6	62·4	26·7
August	133·2	17th	154·7	22nd	94·9	50·7	66·9	22·8
September	133·7	27th	151·4	28th	81·9	53·6	69·5	9·0
October	139·1	7th	149·9	19th	87·8	54·9	62·9	13·9
November	137·0	6th	144·2	18th	118·5	54·4	59·4	36·7
December	135·1	16th	140·9	23rd	131·8	54·9	57·7	51·2
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

* On a stand 4 feet high.

83. SHOLAPUR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	147·8	30th	153·8	9th	143·5	61·8	66·3	58·6
February	155·2	24th	161·7	1st	147·7	60·9	65·3	56·7
March	162·7	27th	167·8	14th	149·5	63·7	69·4	58·1
April	167·2	15th	171·3	3rd	161·4	62·6	66·5	58·3
May	164·1†	11th	172·1	28th	157·1	59·4†	64·4	54·2
June	150·4	1st	163·1	30th	135·3	59·2	70·4	49·1
July	151·6	22nd	159·1	8th	112·8	61·7	68·8	32·6
August	142·5	9th	165·7	23rd	97·7	54·5	69·5	22·9
September	150·5	17th	164·1	3rd	108·2	64·6	74·4	29·4
October	155·6	24th	161·5	3rd	137·2	68·4	75·5	53·8
November	149·4	6th	160·3	3rd	136·2	65·2	75·0	56·7
December	148·2	15th	162·9	28th	133·3	66·3	77·2	55·8
Year	153·8	...	172·1	...	97·7	62·4	77·2	22·9
Means of extremes	...	...	163·6	...	135·0	...	70·2	48·9

† Mean of 24 days.

84. RATNAGIRI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	144·3	7th	152·5	26th	130·6	56·3	60·4	47·3
February	143·4	5th	152·6	6th	132·9	57·3	62·4	46·1
March	143·3	26th	147·3	11th	135·5	57·1	60·2	50·3
April	144·9	29th	147·7	10th & 12th	141·9	55·4	59·9	51·5
May	147·4	3rd	154·9	28th	144·1	55·9	63·9	51·7
June	133·9	15th	149·5	18th	101·9	49·4	62·3	19·5
July	128·4	6th	150·3	10th	90·1	45·2	63·7	11·3
August	134·5	8th	150·9	26th	96·1	50·5	65·0	17·7
September	136·1	14th	146·7	3rd	99·6	53·2	63·0	17·8
October	142·4	24th	155·5	20th	87·9	54·8	68·7	9·0
November	146·2	2nd	154·9	12th	138·1	57·0	65·7	53·2
December	143·6	27th & 29th	146·9	7th	137·9	55·7	60·5	50·7
Year	140·7	...	155·5	...	87·9	54·0	68·7	9·0
Means of extremes	...	...	150·8	...	119·7	...	63·0	35·5

* On a stand 4 feet high.

85. BELGAUM (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	143·3	10th	151·5	12th	139·5	62·3	70·3	58·0
February	149·6	9th	158·2	3rd	143·3	61·0	70·7	58·0
March	155·1	17th	163·6	14th	137·4	61·9	74·0	51·9
April	154·2	27th	163·8	20th	147·2	58·6	68·1	53·9
May	150·5	7th	162·1	22nd	143·8	57·5	64·6	50·9
June	137·4	1st	150·4	5th	109·7	59·5	70·4	38·2
July	133·6	11th	148·6	8th	102·4	58·9	73·9	31·9
August	138·3	18th	153·6	25th	98·6	60·3	72·4	29·5
September	141·7	18th	153·4	3rd	116·2	65·2	74·6	44·0
October	145·6	2nd, 3rd, 6th & 7th.	152·6	17th	126·4	64·9	72·7	52·5
November	140·6	6th	148·3	2nd	132·4	61·1	67·0	55·3
December	139·9	10th	148·5	24th	130·0	61·7	69·8	56·3
Year	144·2	...	163·8	...	98·6	61·1	74·6	29·5
Means of extremes	...	...	154·6	...	127·2	...	70·7	48·4

86. KARWAR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	150·0	4th	152·7	28th	143·2	62·6	68·0	58·4
February	150·1	3rd	156·2	10th, 15th & 16th	146·2	62·6	66·5	59·7
March	151·6	29th	156·2	14th	125·2	64·4	69·5	40·0
April	152·3	29th	166·2	26th	146·2	62·8	76·4	57·9
May	153·0	11th	158·2	12th	147·7	62·7	66·9	58·4
June	135·2	19th	151·2	27th	97·3	50·7	66·5	13·6
July	129·0	30th & 31st	150·2	10th & 15th	97·2	45·4	66·8	12·0
August	142·0	18th	159·2	29th	102·2	58·9	75·5	24·1
September	141·4	18th	149·2	5th	98·2	58·9	66·0	16·8
October	146·3	5th, 13th & 24th	152·2	6th	119·7	61·8	69·0	38·3
November	147·1	5th	151·7	3rd	134·7	61·4	65·5	49·3
December	143·5	10th & 28th	148·2	14th	110·2	58·5	62·5	30·1
Year	145·1	...	166·2	...	97·2	59·2	76·4	12·0
Means of extremes	...	...	154·3	...	122·3	...	68·3	38·2

* On a stand 4 feet high.

87. VIZAGAPATAM.*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	106·3	13th	112·0	23rd	101·5	27·7	32·5	23·0
February	107·0	21st	113·5	2nd	102·2	24·1	28·7	17·2
March	109·0	14th	114·5	30th	103·3	23·1	29·7	16·7
April	108·9	28th	121·0	12th	103·8	20·9	31·3	16·5
May	113·2	1st	119·2	5th	107·5	22·5	30·2	17·7
June	109·5†	2nd	126·0	25th	91·7	18·8‖	33·8	3·2
July	111·6‡	22nd	127·0	26th	93·5	23·3‡	36·5	9·3
August	114·3§	19th	130·1	20th	93·0	25·2§	42·4	6·4
September	110·0‡	15th	125·0	28th	93·2	22·3‡	35·5	6·8
October	109·7‖	1st	118·0	14th	97·0	23·4‖	32·2	10·8
November	102·4¶	4th	111·4	27th	90·0	22·5¶	29·5	10·0
December	98·8‖	20th	106·5	2nd	85·0	23·5‖	31·9	7·4
Year	108·4	...	130·1	...	85·0	23·1	42·4	3·2
Means of extremes	...	...	118·7	...	96·8	...	32·9	12·1

88. MASULIPATAM.

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	140·7	30th	151·6	14th	136·1	59·1	69·8	55·1
February	144·0	1st	149·7	6th, 7th & 10th.	139·7	58·2	66·7	53·8
March	150·5	16th	157·4	2nd	144·5	58·8	64·4	54·4
April	151·3	28th	163·6	8th	144·7	56·5	64·3	51·3
May	157·0	25th	169·5	18th & 19th	149·5	56·3	61·4	50·8
June	143·8	9th	164·1	29th	94·6	48·6	66·0	12·2
July	141·9	25th	157·4	21st	124·4	49·9	64·4	29·3
August	147·2	31st	163·5	24th	105·7	54·0	69·4	24·9
September	149·0	16th	162·2	7th	111·6	55·7	65·0	22·6
October	141·2	12th	155·7	14th	89·7	52·5	63·7	0·7
November	141·5	3rd	148·2	1st	94·8	58·1	64·3	17·2
December	137·1	7th	148·8	4th	94·8	56·8	65·7	24·0
Year	145·4	...	169·5	...	89·7	55·4	69·8	0·7
Means of extremes	...	...	157·6	...	118·3	...	65·4	33·0

* The instrument is not in vacuo.
† Mean of 24 days.
‡ Mean of 25 days.
§ „ of 23 „
‖ Mean of 28 days.
¶ „ of 29 „

89. SECUNDERABAD.

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	144·8	24th	154·6	26th	137·3	62·5	69·2	54·1
February	152·2	2nd	157·6	4th	145·3	60·8	70·9	55·8
March	155·0	28th	161·6	16th	139·0	60·0	65·6	55·0
April	161·7	25th	171·6	11th	156·2	59·0	67·7	53·3
May	166·3	11th	175·0	20th & 25th	160·4	59·8	66·7	52·5
June	144·9	3rd	165·8	20th	110·7	54·4	67·1	29·7
July	132·1	5th	152·4	8th	80·3	46·7	62·7	9·2
August	138·4	13th	160·8	25th	84·6	52·6	67·1	13·0
September	138·8	18th	158·2	2nd	87·7	54·9	73·4	14·9
October	144·7	7th	159·9	14th	113·6	60·1	71·2	36·0
November	144·7	4th	154·7	2nd	130·2	63·3	69·6	50·5
December	143·3	14th	153·4	30th	138·8	63·2	67·3	60·0
Year	147·2	...	175·0	...	80·3	58·1	73·4	9·2
Means of extremes	...	...	160·5	...	123·7	...	68·2	40·3

90. BELLARY (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	143·2	29th	153·8	7th	134·6	57·2	65·5	50·7
February	147·9	28th	154·3	3rd	139·1	54·0	57·3	51·1
March	154·0	28th	160·1	16th	144·7	54·1	64·0	49·2
April	155·7	7th	163·0	9th	144·8	51·0	57·5	43·0
May	154·8	31st	160·1	30th	147·0	49·5	58·2	43·6
June	145·4	3rd	158·0	20th	122·1	49·7	59·3	32·0
July	136·9	4th	153·3	8th	91·9	44·8	55·8	12·3
August	138·2	9th	154·0	25th	92·3	47·0	56·7	16·1
September	140·2	24th	150·4	2nd	109·6	48·4	58·4	25·4
October	Imperfect.							
November	Ditto.							
December	139·1	16th	149·4	14th	110·0	55·6	65·1	29·4
Year	?	...	163·0	...	91·9	?	65·5	12·3
Means of extremes	...	...	?	...	?	...	?	?

91. MANGALORE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	148·7	7th	153·8	15th	141·4	60·6	65·8	55·1
February	149·7	3rd	156·0	9th	147·2	61·2	65·9	59·6
March	149·9	10th	163·6	14th	113·2	61·1	75·3	25·7
April	150·8	19th	164·4	28th	145·2	60·5	74·3	54·9
May	149·3	6th	158·1	10th	123·5	59·3	68·9	35·2
June	140·4	16th	157·9	4th	99·4	55·4	72·3	16·9
July	133·3	16th	152·4	11th	89·4	51·5	70·9	9·1
August	139·3	5th	153·2	28th	102·8	56·6	68·9	23·5
September	148·6	5th	160·5	2nd	141·2	64·6	76·8	58·1
October	147·7	5th	155·9	22nd	106·4	63·5	73·2	23·8
November	147·0	8th	157·5	2nd	125·7	60·4	71·3	45·0
December	146·2	9th	151·2	13th	132·4	59·9	66·2	48·4
Year	145·9	...	164·4	...	89·4	59·6	76·8	9·1
Means of extremes	...	...	157·0	...	122·3	...	70·8	37·9

92. MERCARA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	145·1	31st	158·5	10th	136·5	69·5	78·6	60·9
February	148·9	2nd	156·5	5th	122·5	68·2	77·7	48·7
March	152·9	9th	157·5	14th	143·5	70·0	75·2	63·2
April	152·1	7th	159·5	23rd	147·7	68·3	73·1	61·5
May	149·8	9th & 31st	157·5	14th	142·7	69·0	78·9	60·6
June	131·9	1st	152·5	30th	107·7	59·5	72·5	39·6
July	117·6	4th	146·2	9th	90·5	49·0	72·1	25·2
August	132·8	10th & 12th	156·5	25th	102·5	60·8	78·4	38·3
September	137·5	17th	152·5	6th	101·2	65·6	76·8	35·8
October	141·9	10th & 19th	150·0	17th	114·2	67·5	75·6	46·0
November	140·2	12th & 13th	149·7	2nd	129·5	67·0	75·3	59·1
December	136·2	9th	146·5	13th	90·1	65·0	74·7	27·4
Year	140·6	...	159·5	...	90·1	65·0	78·9	25·2
Means of extremes	...	...	153·6	...	119·1	...	75·7	47·2

* On a stand about 4 feet high.

93. BANGALORE (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	135·7	29th	147·6	5th	128·3	57·9	67·7	51·4
February	139·3	2nd	148·8	11th	133·3	56·1	65·9	53·1
March	146·9	15th	156·4	16th	127·7	57·2	67·6	44·3
April	147·9	21st	157·3	28th	127·9	55·2	67·3	46·3
May	143·7	13th	151·8	26th	134·4	51·7	58·4	46·5
June	137·7	22nd	149·7	26th	109·6	52·1	64·1	27·8
July	129·7	5th	147·8	21st	109·1	48·7	58·9	31·7
August	135·3	9th	151·3	28th	120·4	53·2	64·6	43·6
September	135·9	16th	144·0	6th	121·2	53·9	60·6	45·8
October	132·0	2nd	148·0	16th	90·1	52·5	61·7	19·5
November	127·7	8th	141·6	20th	103·4	51·4	64·1	29·8
December	124·3	9th	134·1	11th & 13th	92·6	50·1	57·8	22·9
Year	136·3	...	157·3	...	90·1	53·3	67·7	19·5
Means of extremes	...	...	148·2	...	116·5	...	63·2	38·6

94. MADRAS.

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	142·4	27th	149·9	9th	131·0	57·7	63·2	48·7
February	144·9	4th	151·8	3rd	133·9	57·9	64·2	49·5
March	146·4	16th	152·4	31st	143·0	56·7	62·2	52·8
April	147·4	24th	157·7	8th	139·9	54·0	64·1	49·2
May	147·9	17th	151·3	18th	140·9	49·2	56·3	41·7
June	142·3	2nd	154·1	24th	113·0	44·1	55·4	24·3
July	137·6	25th	146·9	20th	108·6	44·1	52·4	22·8
August	145·7	17th	152·6	20th	121·5	51·3	58·2	31·9
September	147·3	23rd	160·7	17th	118·0	51·4	63·0	29·7
October	129·1	1st	148·1	29th	90·8	43·4	57·8	13·6
November	137·0	12th	149·4	28th	103·3	53·7	65·4	27·9
December	128·0	16th & 26th	140·9	12th	77·6	47·8	61·0	3·3
Year	141·3	...	160·7	...	77·6	50·9	65·4	3·3
Means of extremes	...	...	151·3	...	118·5	...	60·3	33·0

95. SALEM (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	141·2	6th	148·3	16th	132·7	53·6	63·0	47·1
February	143·3	4th	147·7	3rd & 5th	137·7	50·8	56·1	46·6
March	145·1	16th	152·8	20th	140·8	47·1	58·6	43·7
April	147·6	24th	159·9	30th	141·9	46·9	59·7	41·5
May	141·5	13th	151·8	29th	128·6	42·1	49·9	33·7
June	136·8	2nd	149·6	29th	121·0	41·6	53·7	31·2
July	130·3	16th	139·6	20th	119·6	38·6	46·0	27·0
August	134·3	5th	139·5	18th & 20th	129·6	44·1	50·2	39·9
September	136·0	28th	141·4	3rd & 11th	129·5	43·6	48·6	38·6
October	126·5	21st	136·6	16th	85·6	39·7	48·2	8·2
November	129·3	19th	137·5	10th	116·3	45·1	52·3	35·9
December	123·7	14th	137·5	11th	99·5	40·9	50·5	16·0
Year	136·3	...	159·9	...	85·6	44·5	63·0	8·2
Means of extremes	...	...	145·2	...	123·6	...	53·1	34·1

96. WELLINGTON (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	127·7	27th	143·2	11th	98·9	62·6	73·2	41·2
February	132·6	26th	138·4	5th	117·8	62·9	70·5	55·6
March	Registers not received from the Madras Meteorological Office.							
April								
May								
June								
July	120·2	30th	144·3	9th	87·0	49·2	69·8	20·7
August	126·6	24th	141·4	22nd	99·5	55·5	72·6	34·2
September	130·3	15th	142·6	28th	98·0	58·0	71·9	32·0
October	121·0	18th & 22nd	131·5	16th	81·1	53·4	64·1	18·8
November	124·9	30th	136·1	2nd	92·8	58·0	68·1	29·7
December	117·8*	12th	130·3	11th	85·1	54·3*	64·0	23·3
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

* Mean of 28 days.

97. COIMBATORE (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	141·7	28th	151·5	8th	132·6	55·5	64·9	47·4
February . .	143·9	3rd	152·9	5th	124·7	52·8	65·5	43·4
March . . .	148·9	13th	157·3	17th	142·2	52·8	64·2	45·7
April . . .	149·1	10th	170·1	22nd	133·6	50·7	68·1	35·2
May . . .	147·1	17th	157·0	9th	134·7	53·2	64·0	43·3
June . . .	145·3	9th	158·0	24th	115·8	55·2	71·0	35·3
July . . .	138·4	11th	149·8	20th	105·9	51·6	61·7	24·4
August . . .	141·5	22nd	152·7	28th	121·4	54·7	64·4	39·1
September . .	143·3	30th	159·9	6th	125·0	54·6	62·2	40·5
October . .	134·7	4th	150·8	5th	93·2	49·7	64·0	17·5
November . .	133·8	25th	142·7	4th	102·5	51·3	60·8	24·6
December . .	131·4	15th	142·8	19th	114·5	49·4	57·0	36·7
Year . . .	141·6	...	170·1	...	93·2	52·6	71·0	17·5
Means of extremes	...	...	153·0	...	120·5	...	64·0	36·1

98. TRICHINOPOLY (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	144·7	31st	151·9	5th	132·2	57·7	63·3	50·1
February . .	144·4	11th	155·8	3rd	128·9	53·5	68·7	44·3
March . . .	151·3	23rd	158·3	14th	144·2	53·6	61·3	47·0
April . . .	155·0	28th	163·2	10th	149·4	52·6	60·1	45·3
May . . .	147·5	6th	161·7	8th	99·9	45·9	59·4	10·0
June . . .	146·1	3rd	155·0	30th	136·0	47·7	56·4	39·8
July . . .	144·1	10th	155·3	13th	123·0	47·2	58·4	32·8
August . . .	143·8	31st	153·7	23rd	114·2	48·4	55·4	25·5
September . .	144·9	6th	153·5	3rd	124·7	48·3	59·4	30·5
October . .	134·9	13th	144·9	28th	97·1	47·1	64·0	18·6
November . .	135·3	30th	142·8	28th	125·5	50·4	57·4	40·2
December . .	128·7	5th	139·8	25th	85·1	45·4	53·1	11·6
Year . . .	143·4	...	163·2	...	85·1	49·8	68·7	10·0
Means of extremes	...	...	153·0	...	121·7	...	59·7	33·0

99. NEGAPATAM.

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	144·9	1st	155·8	13th	120·4	63·4	74·3	42·3
February . .	145·8	12th	156·0	3rd & 4th.	132·2	62·2	73·5	49·7
March . . .	148·7	14th	160·2	7th	144·6	60·4	73·2	55·6
April . . .	150·0	28th & 29th	161·1	7th	144·4	57·1	63·6	52·4
May . . .	148·1	6th	162·4	8th	88·5	51·2	68·5	1·2
June . . .	148·9	8th	156·8	24th	128·8	52·1	57·8	41·6
July . . .	146·2	25th	155·6	20th	131·4	50·5	56·9	37·6
August . . .	149·8	29th	160·4	18th	130·2	55·9	65·7	38·9
September . .	149·6	6th	163·3	11th	143·4	56·0	69·2	50·9
October . .	139·2	31st	154·7	16th	77·7	54·0	70·4	3·6
November . .	139·6	2nd, 13th & 24th.	151·3	8th	85·3	57·6	70·1	6·3
December . .	134·3	5th & 8th	148·0	2nd	90·4	54·4	67·1	16·4
Year . . .	145·5	...	163·3	...	77·7	56·2	74·3	1·2
Means of extremes	...	...	157·1	...	118·1	...	67·5	33·0

100. MADURA.

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	136·3	25th	142·7	16th	122·5	47·5	52·3	34·9
February . .	134·9	8th & 10th	140·2	4th	112·6	44·1	49·8	27·5
March . . .	142·9	5th & 30th	146·8	14th	133·2	46·0	49·2	40·9
April . . .	141·8	14th	148·4	23rd	118·6	40·2	45·5	25·2
May . . .	140·4	4th & 19th	149·9	9th	98·9	40·3	47·2	10·3
June . . .	140·7	18th	149·1	28th	124·6	41·6	49·4	30·1
July . . .	140·6	25th	148·3	6th	129·4	43·7	54·5	34·1
August . . .	143·2	30th	148·8	24th	129·2	46·8	53·6	35·3
September . .	142·0	5th	146·9	23rd	137·2	43·8	48·3	38·5
October . .	130·1	9th	141·2	16	86·8	40·3	47·4	11·2
November . .	129·7	30th	134·6	5th	124·4	44·1	50·7	8·5
December . .	127·0	17th	136·9	21st	97·3	42·5	53·2	12·7
Year . . .	137·5	...	149·9	...	86·8	43·4	54·5	10·3
Means of extremes	...	...	144·5	...	117·9	...	50·1	28·3

101. COCHIN (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	139·1	23rd	148·6	31st	97·0	50·4	57·4	15·2
February	137·6	11th	144·5	5th	103·2	48·6	56·2	19·0
March	139·4	10th	143·6	19th	135·7	49·5	53·1	47·2
April	136·3	28th	143·8	4th	129·8	46·1	53·9	42·0
May	128·6	31st	137·7	9th	86·6	40·0	49·6	2·9
June	122·1	3rd	134·8	24th	92·9	36·7	46·2	14·1
July	120·3	3rd	137·3	22nd	87·7	37·4	51·4	10·8
August	126·9	31st	135·0	29th	94·2	43·4	51·7	17·4
September	131·0	20th	137·5	6th	101·8	46·2	53·1	21·2
October	129·7	4th	137·9	16th	86·4	44·9	55·6	10·2
November	128·8	11th	136·7	2nd	91·9	43·1	51·1	13·2
December	129·2	15th	133·8	14th	122·2	43·8	48·1	37·7
Year	130·8	...	148·6	...	86·4	44·2	57·4	2·9
Means of extremes	...	...	139·3	...	102·5	...	52·3	20·9

102. KURNOOL (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
		Observatory established in February 1883.						
February	161·2*	12th	175·2	10th	151·6	65·3*	84·0	57·4
March	161·5	3rd	170·3	16th	134·3	60·3	73·4	35·4
April	164·2	7th & 20th	173·6	9th	157·3	58·4	67·7	52·4
May	167·8	18th	183·6	28th	158·6	60·3	72·4	53·4
June	161·4	12th	172·3	20th	143·6	66·4	76·3	57·5
July	158·0	25th	174·6	8th	144·3	67·5	81·9	55·8
August	158·1	19th	190·2	20th.	127·1	70·0	98·5	49·6
September		Imperfect.						
October		Not recorded.						
November		Ditto.						
December	166·9	25th	183·1	9th	139·7	85·9	104·4	59·0
Year	?	...	?	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

* Mean of 20 days.

103. AKYAB (*corrected*) *

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	128·9	31st	134·5	5th & 17th	125·2	48·2	50·7	46·0
February	132·6	14th	138·7	27th	119·7	49·1	51·7	42·5
March	139·5	31st	146·7	6th	135·2	51·7	57·0	48·5
April	142·2	26th	147·9	9th & 27th	136·9	51·3	58·7	47·5
May	139·1	27th	152·0	15th	115·7	50·4	62·0	31·4
June	129·9†	24th	146·7	28th	95·7	44·9†	63·5	15·5
July	129·1	1st	143·7	31st	97·2	44·9	56·5	16·0
August	125·1	3rd & 6th	140·7	13th	90·7	41·5	54·3	12·7
September	129·0	13th	141·2	3rd	92·7	44·0	55·5	13·8
October	134·0	6th	143·9	7th	117·5	45·2	52·7	33·3
November	122·3‡	1st	137·2	13th	83·2	38·5‡	47·7	8·9
December	117·9	4th	127·0	3rd	100·3	38·8	43·7	20·9
Year	130·8	...	152·0	...	83·2	45·7	63·5	8·9
Means of extremes	...	...	141·7	...	109·2	...	54·5	28·1

104. THAYETMYO (*corrected*).§

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	131·1‖	29th	137·8	16th	125·8	46·2	52·8	42·2
February	138·8	5th, 20th & 28th	145·6	1st	131·6	46·3	56·8	42·3
March	148·5	25th	155·8	2nd	141·1	49·2	53·3	45·9
April	151·9	28th	159·6	7th	134·1	50·1	57·9	39·9
May	155·3‖	25th	163·6	10th	133·6	56·8‖	65·8	49·9
June	154·3	9th	160·1	24th	141·6	63·3	68·8	50·4
July	150·7	8th	161·1	27th	141·6	62·8	72·5	54·8
August	149·9	13th	156·6	23rd	128·6	60·7	69·3	42·0
September	150·1	4th & 8th	156·1	1st	143·6	60·2	70·3	52·7
October	142·3	4th	149·3	9th & 30th	135·6	51·4	58·4	44·0
November	131·3†	10th	148·6	29th	98·6	46·1†	63·8	17·8
December	126·0	9th	142·6	1st	98·6	46·1	57·8	24·9
Year	144·2	...	163·6	...	98·6	53·3	72·5	17·8
Means of extremes	...	...	153·1	...	129·5	...	62·3	42·2

* On a stand 3 feet 8 inches high. ‡ Mean of 26 days. † Mean of 29 days. § On a stand 4 feet high. ‖ Mean of 30 days.

105. TOUNGOO (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	144·7	30th & 31st	149·1	6th & 8th	141·1	59·1	62·5	56·3
February	152·5	20th	161·1	4th & 6th	145·1	60·0†	64·4	55·4
March	151·8	13th	157·1	16th	143·1	54·6	62·4	47·4
April	149·3	29th	154·1	8th	128·1	52·1	55·4	34·4
May	150·9	9th	158·1	22nd	134·1	56·3	61·4	43·4
June	142·2	19th	153·1	18th	121·1	54·3	65·3	34·3
July	141·2	2nd	152·1	26th	112·1	55·5	65·3	30·3
August	142·4	20th	153·1	4th	114·1	56·0	64·4	30·3
September	147·3	19th	158·1	7th	130·1	59·8	68·4	46·3
October	148·9	3rd	159·1	7th	125·1	58·2	68·4	40·3
November	136·4	6th	149·1	12th	90·1	51·1	61·3	10·3
December	137·5	11th	146·1	1st & 2nd	120·1	55·0	62·3	35·3
Year	145·4	...	161·1	...	90·1	56·0	68·4	10·3
Means of extremes	...	...	154·2	...	125·4	...	63·5	38·7

* On a stand 4 feet high.

† Mean of 27 days.

106. BASSEIN (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	142·7	21st & 28th	148·3	6th	132·3	57·7	62·2	49·2
February	146·4†	27th	153·3	5th—8th	142·3	55·2†	59·6	49·6
March	148·3	11th	155·3	18th	139·3	53·8	62·2	48·1
April	147·9	5th	154·3	7th	133·3	52·4	60·1	45·7
May	145·6	7th & 16th	159·3	11th	102·8	53·3	66·6	24·7
June	136·4	16th	151·3	4th	109·8	50·7	63·7	28·7
July	135·8	11th	151·3	24th	103·8	50·9	65·2	20·7
August	137·9	19th	155·3	23rd	95·3	52·8	68·4	15·4
September	136·2	21st & 28th	151·3	8th	91·3	Imperfect.		
October	145·0	18th	149·8	6th	123·8	Shade maximum not recorded.		
November	133·3	18th	147·8	30th	82·3	Ditto.		
December	136·6	9th	143·8	1st	112·3	55·9§	60·7	48·7
Year	141·0	...	159·3	...	82·3	?	?	?
Means of extremes	...	...	151·8	...	114·1	...	?	?

‡ On a stand 3 feet 10 inches high.

§ Mean of 23 days.

107. RANGOON (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	147·3	13th	155·4	6th	137·0	59·6	65·8	52·4
February	152·2	11th	158·3	12th	148·0	58·8	67·2	54·3
March	154·0	22nd	163·8	31st	148·3	57·6	67·3	52·1
April	150·8	30th	161·4	7th	86·4	56·3	65·2	9·7
May	151·6	7th	164·9	24th	101·3	59·6	67·0	20·1
June	142·1	26th	161·1	2nd	98·4	56·4	74·6	14·9
July	141·2	30th	157·4	19th	101·9	55·9	69·0	21·0
August	142·8	9th	157·2	12th	98·7	56·8	69·8	20·3
September	138·8	19th	160·9	6th	97·2	54·2	72·2	18·5
October	147·1	20th & 21st	156·1	8th	106·2	58·2	66·1	20·6
November	138·2	16th	151·1	9th	90·6	53·1	64·8	13·9
December	143·7	2nd	151·5	16th	124·4	58·7	64·7	43·8
Year	145·8	...	164·9	...	86·4	57·1	74·6	9·7
Means of extremes	...	...	158·3	...	111·5	...	67·8	28·5

* On a stand 3½ feet high.

108. MOULMEIN (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum	Minimum.
January	144·5	3rd	150·8	6th	133·7	57·0‡	63·7	48·4
February	148·0	24th & 26th	152·2	23rd	144·0	55·9	59·2	50·1
March	150·8	25th	155·2	15th	147·9	57·1	64·2	51·5
April	150·3	2nd	158·3	7th	117·2	57·1	65·9	33·8
May	151·7	16th	161·4	27th	131·4	61·4	68·4	44·9
June	133·8	1st	163·2	25th	99·2	50·2	73·3	17·3
July	137·6	7th	160·4	19th	98·4	55·6	78·2	19·3
August	143·7	3rd	161·8	29th	116·4	59·2	74·7	36·4
September	139·3	30th	154·2	7th	96·4	55·9	67·1	16·2
October	148·3	17th	167·4	23rd	117·6	59·1	77·2	28·8
November	145·5	8th	155·2	12th	128·2	54·4	65·5	40·8
December	143·6	15th	151·9	5th	137·2	57·2	68·5	50·6
Year	144·8	...	167·4	...	96·4	56·7	78·2	16·2
Means of extremes	...	...	157·7	...	122·3	...	68·8	36·5

† On a stand 4 feet high.

‡ Mean of 30 days.

109. MERGUI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	152·1	29th	157·4	7th	137·6	62·6	65·2	50·9
February	156·7	15th	160·8	18th	151·6	64·4	68·0	59·9
March	153·3	3rd	157·6	25th & 29th	148·3	61·0	64·0	56·2
April	149·9	30th	158·8	6th	124·3	58·6	65·2	39·6
May	148·0	13th	162·3	21st	97·3	57·8	69·7	11·1
June	131·6	15th	161·3	3rd & 27th	96·3	47·1	74·2	12·1
July	138·5	15th	152·3	6th	95·3	45·2	65·6	18·1
August	139·1	3rd & 9th	152·3	21st	111·3	54·6	66·1	30·1
September	135·1	18th	158·8	9th	104·3	51·6	74·1	24·1
October	142·3	1st & 12th	152·3	6th	109·3	55·5	64·6	31·0
November	140·8	18th	151·3	10th	100·3	53·8	63·1	17·2
December	141·8	2nd & 28th	147·3	29th	129·3	56·0	60·1	44·1
Year	143·3	...	162·3	...	95·3	55·7	74·2	11·1
Means of extremes	...	...	156·0	...	117·1	...	66·7	32·9

110 PORT BLAIR (*corrected*).*

Mean.	Maximum.		Minimum.		Difference, sun and shade.		
	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
135·2	18th	142·1	24th	124·6	49·2	55·1	39·6
138·4	27th	144·1	8th	133·6	50·5	55·1	46·8
143·5	17th & 19th	148·6	23rd	140·1	53·1	59·6	48·8
146·7	26th & 30th	153·6	6th	132·1	53·9	59·5	44·1
136·4	16th	151·6	26th	97·1	46·1	60·6	10·0
132·8	17th	151·6	5th	94·6	46·5	61·6	9·0
127·8	8th	153·4	11th	93·6	42·9	67·2	10·6
129·9	12th	149·1	27th	102·6	44·1	62·1	19·8
132·2	20th	149·6	3rd	99·6	47·6	65·2	19·7
137·1	9th	147·6	5th	99·6	50·0	63·6	17·2
129·7	22nd	142·2	9th	96·6	44·3	55·4	15·4
128·7	12th	142·6	9th	95·6	44·8	57·1	12·6
134·9	...	153·6	...	93·6	47·8	67·2	9·0
...	...	148·0	...	109·1	...	60·2	24·5

* On a stand 4 feet high.

111. NANCOWRY (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, sun and shade.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	146·3	21st	153·4	29th	118·9	58·7	66·6	31·8
February	148·6	15th	155·7	12th	142·9	61·1‡	68·7	55·6
March	149·3	29th	169·9	17th	97·9	60·6	80·3	8·6
April	151·4†	26th	165·1	3rd	126·9	61·1	74·5	38·1
May	142·8	8th	161·4	27th	96·9	52·1	70·6	6·7
June	134·3	9th & 20th	152·7	1st	87·4	45·8	63·9	0·6
July	137·2	8th & 30th	151·9	9th	108·9	49·2	64·1	20·7
August	142·7	11th	171·9	3rd	93·9	53·9	81·1	6·7
September	140·1	2nd	155·9	20th	113·9	51·3	68·1	25·7
October	147·9	16th	175·9	5th	132·9	60·1	88·9	44·9
November	142·8	20th	154·9	9th	131·9	54·5	66·1	43·7
December	140·3	13th, 14th, 17th & 27th	147·9	29th	111·9	51·5	59·1	23·1
Year	143·6	...	175·9	...	87·4	55·0	88·9	0·6
Means of extremes	...	...	159·7	...	113·7	...	71·0	25·5

* On a stand 4 feet high. † Mean of 29 days. ‡ Mean of 27 days.

TABLE II.—DURATION OF BRIGHT SUNSHINE IN 1883. (2 STATIONS).

Month.	Calcutta (Alipore).			Allahabad.		
	Total hours of bright sunshine.	Total hours of sun above horizon.	Percentage ratio of actual to possible sunshine.	Total hours of bright sunshine.	Total hours of sun above horizon.	Percentage ratio of actual to possible sunshine.
January	300	337	89	259	329	79
February	263	318	83	273	312	87
March	290	371	78	306	368	83
April	287*	379	76	309†	353	87
May	296	408	73	329	410	80
June	136	403	34	227	407	56
July	137	413	33	151	416	36
August	124	398	31	202	400	50
September	169	367	46	221	366	60
October	287	359	80	273	354	77
November	262	331	79	282*	313	90
December	239	333	72	272	324	84
Year	232	368	64	259	363	73

* 1 day wanting.

† 2 days wanting.

TABLE III.—TEMPERATURES OF NOCTURNAL RADIATION IN 1883. (107 STATIONS).

1. ZANZIBAR (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	73·0†	10th	75·4	7th	70·1	5·2†	8·8	3·1
February	72·8‡	14th	75·6	23rd	67·7	5·7§	10·6	2·2
March	73·8‖	17th	76·5	30th	70·0	5·6‖	10·1	3·2
April	72·4¶	12th	75·0	10th	68·2	5·4¶	7·5	1·5
May	71·5	8th	74·6	29th	67·6	4·2	8·5	0·6
June	68·5	3rd	72·0	11th	65·2	6·4	11·4	4·2
July	67·1	9th	70·4	24th	63·8	6·4	12·0	2·8
August	63·0	27th	65·8	17th	59·8	10·2	12·3	7·2
September	62·8**	8th	66·1	19th	60·5	11·0**	13·6	8·4
October	63·7	13th	69·1	17th & 18th	60·6	10·9	13·7	5·8
November	66·7	18th	72·0	14th	62·5	9·5	17·1	5·4
December	70·7	21st	74·1	14th	67·3	6·3	9·6	1·2
Year	68·8	...	76·5	...	59·8	7·2	17·1	0·6
Means of extremes	...	...	72·2	...	65·3	...	11·3	3·8

* On a woollen pad on ground.
† Mean of 27 days.
‡ „ „ 19 „
§ Mean of 18 days.
‖ „ „ 21 „
¶ „ „ 29 „
** „ „ 29 „

2. ADEN (*corrected*).††

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	69·2	14th	73·0	29th	64·0	3·5	8·5	0·9
February	69·9	23rd & 25th	72·0	10th	63·8	3·1	6·9	1·9
March	73·1	22nd	75·6	2nd	68·0	2·3	6·4	0·7
April	74·8	28th	80·1	17th	68·5	2·5	5·4	0
May	78·7‡‡	16th	83·1	1st & 18th	76·1	2·7‡‡	6·0	0·7
June	78·6	3rd	83·3	27th & 28th	75·1	4·5‖	9·1	0·4
July	75·0‖	7th	81·1	14th & 20th	71·0	1·7	4·9	−0·8
August	77·6	16th	80·3	13th & 31st	74·1	2·9	6·7	1·0
September	76·8	17th	81·2	23rd	72·0	4·6	9·6	1·7
October	72·4§	4th	80·1	17th	64·0	5·0§	11·3	0·3
November	69·3	8th	74·1	2nd	62·2	3·7	9·2	1·0
December	67·8	28th & 30th	72·0	8th	59·6	3·5	9·3	0·9
Year	73·6	...	83·3	...	59·6	3·3	11·3	−0·8
Means of extremes	...	...	78·0	...	68·2	...	7·8	0·7

†† On a woollen pad 6 inches above ground. ‡‡ Mean of 28 days.

3. QUETTA (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Not recorded.							
February	Ditto.							
March	Ditto.							
April	Ditto.							
May	Ditto.							
June	Ditto.							
July	Ditto.							
August	46·6	8th	58·3	24th	39·5	13·6	18·0	7·2
September	35·0†	1st	58·4	24th	22·9	16·4†	20·3	9·5
October	23·0	2nd	42·5	20th	7·1	15·6	25·9	5·4
November	16·4	8th	27·9	30th	3·0	13·8	19·6	5·6
December	15·8	12th	33·9	30th	2·0	13·4	18·9	7·0
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

* On a woollen pad.
† Mean of 23 days.

4. LEH (*corrected*).‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	0·7	26th	11·5	29th	−15·3	10·8	14·0	5·7
February	0·9	18th	15·8	1st	−15·5	9·8	15·6	5·0
March	9·8	31st	22·8	9th	− 1·5	10·5	13·9	5·2
April	22·0	29th	35·3	7th	7·5	11·1	14·8	5·1
May	26·1	5th	32·8	20th	19·8	10·8	16·8	4·9
June	34·2	30th	42·2	1st, 7th & 9th	28·5	10·9	14·3	7·1
July	43·2	16th	51·7	20th	33·8	10·3	21·2	5·9
August	40·5	31st	49·2	17th	30·7	9·5	15·5	3·8
September	36·0	1st	51·4	24th & 25th	27·3	8·4§	20·1	0
October	18·8	3rd	29·4	31st	6·5	10·0‖	17·7	3·4
November	9·1	9th	23·3	29th & 30th	1·3	10·4¶	18·2	3·5
December	− 1·2‖	28th	11·5	18th & 19th	−11·7	12·0‖	21·4	6·2
Year	20·0	...	51·7	...	−15·5	10·4	21·4	0
Means of extremes	...	...	31·4	...	9·3	...	17·0	4·7

‡ On a woollen pad 3 inches above ground.
§ Mean of 29 days.
‖ Mean of 30 days.
¶ „ „ 22 „

5. MOOLTAN (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	39·8†	25th	48·1	28th	28·9	6·7†	9·2	2·0
February	35·5	28th	48·9	6th	26·9	7·8	10·4	4·6
March	48·2	22nd	57·2	6th	40·0	7·6	13·6	3·3
April	57·1	27th	63·2	5th & 15th	51·2	10·3	16·0	4·6
May	63·1	20th & 25th	67·2	28th	59·4	10·1	14·0	6·0
June	74·0	4th	80·3	1st	67·0	9·8	16·0	4·1
July	73·0	10th	79·1	11th, 21st, 28th & 30th	70·2	7·8	16·0	1·9
August	71·7	15th	76·1	21st	65·2	8·9	13·0	5·0
September	68·2	4th	76·3	24th	56·4	9·8	14·2	5·6
October	52·0	3	63·2	31st	42·1	10·8	14·8	5·4
November	40·2	11th	51·5	30th	31·1	8·5	12·0	4·9
December	32·8	28th	38·0	19th & 20th	29·9	8·5	12·2	5·9
Year	54·6	...	80·3	...	26·9	8·9	16·0	1·9
Means of extremes	...	...	62·4	...	47·4	...	13·5	4·4

* On a woollen pad 3 inches above ground.
† Mean of 30 days.

6. DERA ISMAIL KHAN (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	Not recorded.							
February	31·0§	28th	49·8	6th	20·6	10·0§	13·2	4·9
March	44·3	31st	58·7	6th	34·6	8·7	14·0	1·0
April	58·5	24th	70·7	2nd	46·8	8·4	16·2	3·1
May	Imperfect.							
June	Ditto.							
July	77·4‖	8th & 9th	84·7	11th & 18th	69·7	4·6‖	10·2	1·2
August	77·0	6th, 30th & 31st	81·7	17th	69·7	4·3	8·2	1·2
September	69·0	2nd & 3rd	78·7	24th	57·7	6·3	14·2	3·2
October	53·2	1st & 2nd	62·7	31st	41·7	8·2	14·1	4·1
November	38·1	10th	53·7	30th	27·7	7·7	11·0	2·2
December	31·2	2nd & 28th	41·7	17th	24·9	8·2	11·1	5·1
Year	?	...	?	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

‡ On a woollen pad 3 inches above ground. § Mean of 27 days.
‖ Mean of 29 days.

7. PESHAWAR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	32·8	1st	48·2	31st	20·4	7·3	11.3	0·9
February	31·1	28th	49·4	1st	17·4	8·2	11·8	3·3
March	40·8	31st	57·3	6th & 10th	32·4	8·1	12·7	2·5
April	53·9	20th	67·2	5th	39·8	7·7	11·4	2·1
May	61·5	21st	85·0	14th	50·3	9·6	17·9	1·6
June	69·4	28th	87·5	6th	60·4	8·1	12·6	0·1
July	73·6	9th	87·0	26th	65·2	4·7	9·5	0·1
August	73·4	2nd	85·0	13th	63·2	4·6	7·8	0·1
September	65·0	3rd	75·6	24th	53·3	6·4	11·4	0·9
October	48·2	3rd	57·5	31st	35·6	9·2	11·7	4·3
November	34·1	12th	48·0	20th	25·4	9·6	12·3	1·3
December	28·6	29th	45·0	24th & 25th	21·4	8·9	12·8	2·7
Year	51·0	...	87·5	...	17·4	7·7	17·9	0·1
Means of extremes	...	...	66·1	...	40·4	...	11·9	1·7

* On a woollen pad 3 inches above ground.

8. MURREE (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	23·9	19th	33·0	6th	16·4	9·3	22·1	0
February	Untrustworthy.							
March	31·2‡	17th	40·0	13th	19·7	10·7§	23·4	0
April	42·8	28th	53·7	6th	28·0	9·7	19·1	0·9
May	48·2§	21st	57·9	14th	37·4	11·4‖	24·3	0·1
June	54·1§	28th	63·9	18th	44·9	12·2§	18·8	3·1
July	Not recorded.							
August	Ditto.							
September	49·3¶	12th	54·7	20th & 23rd	45·7	11·7¶	17·0	5·1
October	Not recorded.							
November	Ditto.							
December	Imperfect.							
Year	?	...	?	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

† On a woollen pad 3 inches above ground. ‡ Mean of 29 days
§ Mean of 28 days. ‖ Mean of 30 days. ¶ ,, ,, 20 ,,

9. RAWALPINDI (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Not recorded.							
February	Ditto.							
March	40·6	22nd	54·7	8th & 9th	33·0	7·2	10·0	1·8
April	51·6†	23rd	67·7	6th	39·3	8·8†	12·9	4·4
May	Not recorded.							
June	Imperfect.							
July	72·8‡	7th	84·6	1st & 22nd	64·6	4·6‡	9·6	0·1
August	75·7§	1st	80·6	17th	64·6	3·9§	6·2	0·6
September	62·4‖	1st	72·6	23rd & 24th	52·7	6·3‖	9·9	2·6
October	48·4	5th	62·1	31st	34·8	7·8	11·9	1·0
November	34·4‡	11th	49·7	30th	24·5	8·1	11·1	1·8
December	27·1‡	30th	42·9	18th & 25th	21·4	8·6‡	12·0	1·8
Year	?	...	?	..	?	?	?	?
Means of extremes	..	...	?	...	?	...	?	?

† Mean of 23 days. § Mean of 28 days. ‖ ,, ,, 27 ,,

10. SIALKOT (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Not recorded.							
February	Imperfect.							
March	46·4	22nd	57·8	9th	37·9	6·2	9·1	1·4
April	61·4	29th	75·3	6th	43·8	5·9	8·5	1·3
May	67·4¶	19th	73·0	29th	59·8	7·5¶	13·9	0·7
June	76·0‡	28th	85·8	4th	69·0	7·2‡	14·9	1·0
July	Untrustworthy.							
August	Ditto.							
September	70·2**	16th	75·7	30th	62·2	3·1**	6·5	0·7
October	58·0	5th	65·6	29th	46·6	3·5	7·3	1·0
November	43·7	12th	52·5	29th	38·5	6·0	15·1	0·9
December	35·8	3rd	42·2	25th	28·0	4·9	13·4	0·7
Year	?	...	85·8	...	?	?	14·9	?
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 3 inches above ground. ‡ Mean of 29 days. ¶ Mean of 25 days. ** Mean of 24 days.

11. LAHORE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	36·1	25th	50·5	19th & 31st	26·9	7·8	12·0	0·5
February	32·0	28th	50·4	6th	19·9	10·6	15·1	6·7
March	46·7	22nd	60·9	9th	34·4	8·5	17·7	2·7
April	61·3	29th	74·9	2nd	49·9	8·0	12·1	3·2
May	63·7	22nd	73·9	13th	54·9	10·0	17·5	2·2
June	76·9	29th	89·9	6th	64·9	6·0	10·0	1·9
July	78·4	7th	83·9	18th	72·9	3·6	6·9	1·0
August	77·6	1st, 4th, 5th, and 27th.	81·9	17th	68·9	4·0	7·0	0·7
September	68·6	2nd & 3rd	75·9	30th	58·9	5·1	8·2	0·2
October	53·1	1st & 2nd	66·9	29th	41·4	8·5	10·6	2·6
November	39·7	10th	54·9	21st	30·9	8·6	12·2	4·0
December	33·4	29th	50·9	23rd & 25th	25·9	8·2	12·0	2·1
Year	55·6	...	89·9	...	19·9	7·4	17·7	0·2
Means of extremes	...	...	67·9	...	45·8	...	11·8	2·3

12. LUDHIANA (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	30·1	25th	38·0	31st	24·0	13·2	19·1	6·1
February	31·8	28th	42·1	1st	23·5	11·6	14·1	8·1
March	45·4	25th	54·6	10th	35·0	11·2	18·2	7·0
April	58·3	30th	69·8	7th	49·1	8·9	16·2	3·2
May	66·2	15th & 25th	69·8	28th	60·0	7·2	13·9	2·0
June	Imperfect.							
July	75·6‡	7th	80·3	1st	69·8	3·3†	7·5	0
August	78·4	4th	85·0	15th	72·3	2·6	10·4	0·7
September	70·2	13th	77·7	25th	61·9	3·9	7·1	0·2
October	54·7	20th	65·4	30th	42·6	7·2	9·2	3·0
November	41·5	12th	54·1	22nd	33·0	8·7	11·8	4·6
December	36·9	30th	50·1	24th	27·0	8·1	11·8	2·2
Year	?	...	85·0	...	23·5	?	18·2	0
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 3 inches above ground. † Mean of 24 days.

13. DELHI (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January				Not recorded.				
February	37·5†	25th	50·0	7th & 8th	26·7	12·8†	19·9	6·5
March	49·6	27th	57·7	9th	39·7	11·1	17·5	2·7
April	62·6	29th	72·6	4th	51·1	11·8	15·5	4·6
May	70·4	21st	79·5	29th	59·5	9·5	16·1	3·6
June	77·3	23rd	83·1	6th	64·7	6·7	14·4	0
July	77·0	31st	83·2	1	71·4	4·5	7·1	1·5
August	77·8	4th	84·2	23rd	72·0	5·2	9·1	2·0
September	72·3	10th	77·2	28th	65·4	6·2	10·1	1·8
October	57·8	2nd	70·6	31s	41·7	9·9	14·5	3·5
November	41·4	12th	56·5	26th	32·5	12·5	18·7	5·2
December	34·2	30th	49·7	3rd & 21st	28·7	12·6	18·5	5·7
Year	?	...	84·2	...	26·7	?	19·9	0
Means of extremes	...	...	?	...	?	...	?	?

† Mean of 22 days.

14. SIRSA (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	31·8	25th	44·6	4th	20·5	10·8	15·6	6·2
February	29·6	28th	42·4	6th	19·8	14·0	17·8	9·1
March	44·7	22nd	52·8	6th	30·1	10·6	15·8	5·3
April	61·2‡	23rd	80·4	3rd	49·3	8·9‡	16·9	1·0
May	65·2	25th	70·5	23rd	58·7	8·3	15 8	1·1
June	77·7	30th	85·3	1st	70·4	5·8	11·0	1·5
July	78·0	9th	85·0	1st	69·9	3·1	5·6	1·2
August	78·7	3rd	82·2	22nd	75·8	3·4	6·0	1·3
September	70·0	1st	78·9	23rd	54·3	8·3	15·9	2·5
October	48·6	2nd	60·0	31st	37·0	13·4	17·5	10·0
November	34·1	12th	47·3	21st	25·2	13·4	19·3	8·0
December	24·8	29th	38·1	18th	18·3	15·2	18·5	10·2
Year	53·7	...	85·3	...	18·3	9·6	19·3	1·0
Means of extremes	...	...	64·0	...	44·1	...	14·6	4·8

* On a woollen pad 3 inches above ground.

‡ Mean of 28 days.

15. CHAKRATA (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	23·8	1st	30·6	29th	18·6	9·9	19·8	0·7
February	23·2	19th	32·7	1st, 3rd, 6th, 13th & 14th	17·6	11·8	18·4	4·2
March	31·2	22nd & 31st	41·1	9th	20·6	10·3	18·4	1·2
April	37·6	29th	53·4	5th	26·6	12·4	20·9	1·6
May	49·4	3rd	60·0	25th	40·0	8·2	15·3	0·8
June	53·3	27th	61·3	4th	39·6	6·4	14·4	0·3
July	57·1	9th	61·3	1st & 23rd	53·4	3·0	7·6	0·7
August	54·7	3rd	60·5	15th	47·9	4·3	9·7	0·4
September	51·8	13th	59·3	30th	38·6	6·1	15·4	0·3
October	38·1	4th	47·4	31st	28·1	11·5	16·3	7·1
November	30·3	24th	37·9	21st & 30th	24·6	10·2	17·3	0·7
December	25·0	29th	34·2	17th	17·6	11·3	18·3	0
Year	39·6	...	61·3	...	17·6	8·8	20·9	0
Means of extremes	...	...	48·3	...	31·1	...	16·0	1·5

16. DEHRA.

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	37·3	25th	45·3	29th	28·7	6·5	9·2	1·6
February	37·5	19th	50·9	1st	28·8	6·6	8·4	4·5
March	45·2	22nd	55·8	9th	33·8	7·4	10·9	3·9
April	56·4	23rd	67·8	3rd	43·3	8·7	14·1	5·5
May	61·9	15th	66·3	29th	55·5	8·5	11·5	3·0
June	69·8	20th	76·7	6th	60·6	4·6	8·8	—1·8
July	71·8	8th	75·1	1st	65·9	2·9	5·0	0·4
August	69·8	3rd	75·8	16th	64·8	3·8	7·6	0·9
September	66·6	13th	72·1	29th	58·7	4·6	7·9	1·7
October	50·9	2nd	58·6	28th	44·8	8·4	11·0	5·1
November	43·3	1st	51·6	21st	36·7	7·2	10·5	3·3
December	35·6	30th	45·8	19th	31·5	7·8	9·7	4·4
Year	53·8	...	76·7	...	28·7	6·4	14·1	—1·8
Means of extremes	...	...	61·8	...	46·1	...	9·6	2·7

* On a woollen pad 3 inches above ground.

17. ROORKEE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	35·7	26th	50·8	18th	25·8	8·4	10·9	1·1
February	36·3	18th	52·8	1st	27·8	7·7	11·4	4·7
March	46·4	4th	53·8	9th & 13th	39·7	8·4	12·6	2·6
April	58·2	29th	75·7	7th	42·7	9·1	13·3	3·5
May	65·8	23rd	75·7	24th	60·8	7·4	12·4	0·6
June	76·3	12th, 20th & 23rd	8·32	6th	65·3	2·8	7·0	−3·5
July	77·4†	6th	80·7	1st	73·7	1·4†	3·8	0·4
August	76·0‡	4th	81·7	15th, 16th & 22nd	71·7	2·1‡	5·8	−1·1
September	71·3	1st, 2nd, 4th, 9th, 10th, 16th & 18th	75·7	30th	59·8	2·5	5·1	0·4
October	52·4	2nd & 3rd	61·8	28th & 30th	43·7	6·3	9·3	3·5
November	42·8	11th	53·8	27th & 28th	34·8	7·5	9·6	4·7
December	33·0	30th	48·3	25th	27·3	7·7‡	9·4	4·9
Year	56·0	...	83·2	...	25·8	5·9	13·3	−3·5
Means of extremes	...	...	66·2	...	47·8	...	9·2	1·8

* On a woollen pad 1 inch above ground. † Mean of 28 days. ‡ Mean of 30 days.

18. RANIKHET (*corrected*).§

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	26·1	1st & 2nd	34·0	29th	16·8	11·5	19·3	1·5
February	25·8	18th	39·0	2nd	14·0	14·6	20·0	7·0
March	34·0	31st	44·0	9th	24·0	12·1	18·0	4·5
April	44·5	30th	54·0	5th	35·8	13·9	18·5	6·0
May	50·0	2nd	58·3	23rd	37·0	11·3	21·7	1·3
June	56·7	29th	63·1	1st & 6th	50·0	6·5	12·3	0·4
July	59·7	31st	63·6	7th	55·5	3·4	7·8	0·1
August	57·0‡	4th	63·5	16th	51·0	5·2‡	11·5	0
September	52·6	3rd	58·6	30th	41·0	7·9	15·5	2·5
October	37·6	1st	47·0	28th & 29th	31·0	16·0	19·0	9·0
November	28·9	11th	40·0	29th	19·0	15·6	26·5	0
December	23·5	1st	29·0	17th	17·0	16·5	22·0	6·0
Year	41·4	...	63·6	...	14·0	11·2	26·5	0
Means of extremes	...	...	49·5	...	32·7	..	17·7	3·2

§ On a woollen pad 3 inches above ground.

19. MEERUT (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	38·8	26th	52·8	31st	32·5	5·1	7·9	0·4
February	37·4	18th	50·5	2nd	28·5	5·6	7·4	3·6
March	49·4	23rd	56·2	9th	40·9	6·1	9·3	1·8
April	59·4	29th	70·4	3rd	49·3	9·0	12·2	6·5
May	62·3	17th	70·9	29th	51·8	12·2†	14·3	7·9
June	68·2	18th & 29th	73·4	6th	57·4	12·5	17·6	7·6
July	67·6	8th	72·4	1st & 9th	63·2	12·5	16·7	9·9
August	68·0	4th	72·4	22nd	62·7	12·6	15·8	9·0
September	62·2	2nd & 4th	68·3	25th	54·3	12·5	16·4	5·4
October	55·4	2nd	66·7	30th	44·0	5·9	7·4	4·3
November	43·1	11th	54·5	23rd	35·6	5·7	11·4	1·8
December	35·8	30th	50·1	24th	30·2	4·7	6·2	3·1
Year	54·0	...	73·4	...	28·5	8·7	17·6	0·4
Means of extremes	...	...	63·2	...	45·9	...	11·9	5·1

* On a woollen pad 3 inches above ground.
† Mean of 28 days.

20. BAREILLY (*corrected*).‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	37·0	10th	49·1	1st	32·5	9·9	22·7	2·1
February	40·6§	20th	50·6	7th	29·0	9·7§	13·7	4·2
March	48·3‖	1st	54·1	9th	41·5	9·3‖	14·6	3·1
April	57·0	29th	70·2	6th & 8th	47·1	12·3	15·5	7·4
May	63·5	26th	72·2	8th	56·1	11·3	18·5	0·4
June	75·1	12th	81·1	1st	64·2	5·5	11·4	1·4
July	75·1	11th	78·2	1st & 2nd	72·2	3·8	7·9	0·4
August	74·4	4th	79·2	15th	71·7	4·6	8·9	0
September	71·7	1st to 3rd	76·2	30th	61·1	4·8	9·5	1·9
October	52·8	3rd	61·1	22nd	45·1	10·4	13·6	7·6
November	41·1	11th & 14th	52·1	16th, 17th 21st & 28th	35·0	10·3	13·1	5·6
December	33·5	30th	41·5	25th	28·5	8·7	12·1	0·5
Year	55·8	...	81·1	...	28·5	8·4	22·7	0
Means of extremes	...	...	63·8	...	48·7	...	13·5	2·9

‡ On a woollen pad 1 inch above ground.
§ Mean of 26 days.
‖ „ „ 30 „

21. AGRA. (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	37·4	26th	54·6	31st	27·6	11·7	17·5	2·8
February	35·9	18th	53·6	2nd & 7th	24·6	12·7	17·2	6·5
March	49·2	24th & 25th	55·6	9th	39·3	11·8	17·0	7·0
April	62·5	29th	77·3	3rd	47·0	11·5	15·6	5·5
May	70·7	21st	83·5	29th	62·0	10·0	14·6	1·6
June	*77·4	21st	84·5	1st, 2nd & 6th	70·5	6·6	12·6	1·1
July	76·3	6th	82·5	1st & 27th	71·5	3·3	6·1	1·4
August	77·1	25th & 28th	81·5	23rd	72·5	4·7	7·3	2·6
September	71·9	10th	77·5	24th	62·5	5·9	14·6	2·1
October	61·0†	1st	73·5	23rd	54·5	9·31	12·8	3·2
November	41·4	12th	57·6	25th	29·9	12·3	18·2	4·9
December	32·1	30th	41·8	19th	26·9	13·0	15·2	9·3
Year	57·7	...	84·5	...	24·6	9·4	18·2	1·1
Means of extremes	...	...	68·6	...	49·1	...	14·1	4·0

* On a woollen pad 2 inches above ground.
† Mean of 24 days.

22. LUCKNOW (*corrected*). ‡

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	37·9	26th	55·0	19th	29·0	8·7	16·2	2·6
February	39·5	20th	55·0	2nd	28·0	8·8	14·2	3·7
March	52·2	26th	65·0	6th	44·0	7·6	12·1	1·6
April	62·8	14th	73·0	4th	49·0	10·0	14·4	4·1
May	69·6	26th	79·1	28th	63·5	8·1	18·9	0·9
June	76·6	10th	84·1	27th	67·0	4·7	12·8	0·3
July	77·8	5th	83·1	8th	70·0	2·2	10·3	0·2
August	76·3	4th, 18th, 24th & 28th.	79·1	12th	67·0	3·8	12·8	0·7
September	73·2	3rd	80·1	30th	62·0	3·5	7·9	0·2
October	54·3	3rd	67·0	30th	43·0	8·2	11·1	2·4
November	40·5	15th	50·0	28th	33·0	9·5	12·2	4·6
December	32·8	6th & 31st	43·0	24th to 26th	27·0	9·6	13·2	5·2
Year	57·8	...	84·1	...	27·0	7·1	18·9	0·2
Means of extremes	...	...	67·8	...	48·5	...	13·0	2·2

‡ On a woollen pad 3 inches above ground.

23. GORAKHPUR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	Not recorded.							
February								
March								
April								
May								
June								
July	77·3	25th	79·9	17th & 18th	75·0	2·5	5·9	0·4
August	77·4	1st	79·9	13th & 25th	74·0	2·5	3·9	0·9
September	74·9	2nd	77·9	30th	68·1	3·5	7·2	1·8
October	59·9	2nd	72·0	25th	50·2	8·5	17·6	4·7
November	45·2	1st & 11th	52·6	22nd	36·6	9·5	13·2	7·7
December	36·3	6th	44·1	19th & 23rd	32·1	9·8	11·8	7·4
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

* On a woollen pad 3½ inches above ground.

24. JHANSI (*corrected*). †

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	49·0	26th	57·5	31st	41·0	1·9	4·6	0·4
February	48·4	25th	57·5	1st	39·5	3·2	5·0	1·4
March	59·4	25th	64·9	13th	51·6	4·1	7·9	0·9
April	67·2	29th	76·3	17th	61·4	8·6	12·5	5·1
May	74·9	13th	81·4	27th	68·3	7·9	13·1	1·6
June	77·8	18th	81·9	27th to 29th	74·8	4·8	10·6	1·1
July	75·3‡	11th	78·3	3rd & 4th	71·8	2·1‡	4·3	0·9
August	75·8	23rd	78·9	12th & 13th	72·8	2·6	5·6	1·0
September	74·6	8th	78·3	25th	66·8	1·6	5·1	0·1
October	65·6	1st	74·7	31st	57·5	2·6	6·3	0·9
November	51·4	13th	58·0	24th & 26th	45·1	4·1	6·0	1·4
December	43·0	2nd	49·1	25th	37·0	4·5	9·4	1·3
Year	63·5	...	81·9	...	37·0	4·0	13·1	0·1
Means of extremes	...	...	69·7	...	57·3	...	7·5	1·3

† On a woollen pad 3 inches above ground.
‡ Mean of 30 days.

25. ALLAHABAD (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	39·9	26th	58·8	6th	31·5	9·6	12·7	2·1
February	36·3†	25th	49·6	6th	24·9	11·5†	15·3	6·0
March	49·5	23rd	58·3	16th	38·4	11·1	16·5	4·9
April	61·5	30th	72·6	6th	49·6	10·6	14·3	5·3
May	69·7	22nd	77·4	4th	63·2	9·1	16·5	4·7
June	77·0‡	12th	84·6	1st & 2nd	70·6	4·8‡	8·1	1·0
July	77·1	5th	82·4	7th	72·6	2·5	6·8	0·1
August	75·9	29th	78·0	12th	72·1	4·0	7·9	1·7
September	73·6	13th & 19th	77·8	30th	63·0	3·3	9·0	0·2
October	58·7	7th	68·6	30th	47·2	7·5	10·5	0·4
November	42·1	2nd	57·0	21st	32·5	10·3	17·1	6·9
December	33·3	5th	43·8	25th	28·3	11·0	14·0	8·3
Year	57·9	...	84·6	...	24·9	7·9	17·1	0·1
Means of extremes	...	...	67·4	...	49·5	...	12·4	3·2

* On a woollen pad 2·5 inches above ground from February, previously 3·5 inches. ‡ Mean of 29 days.
† Mean of 25 days.

26. BENARES (*corrected*).§

Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
38·4‖	11th	51·3	19th	31·2	10·4‖	13·3	4·8
38·9‖	25th	49·2	7th	29·2	10·4‖	13·8	7·4
52·7¶	26th	62·6	2nd	43·7	9·6¶	13·8	6·5
63·0**	26th	75·9	6th	53·7	9·8**	16·7	4·0
72·2‡	15th	78·0	31st	63·8	7·6‡	12·9	2·3
76·0‖	11th	83·9	1st	67·6	5·1‡	11·0	1·6
77·4††	3rd	79·6	7th	75·1	2·8††	6·2	0·3
76·6††	19th	79·4	25th	74·4	3·8††	6·3	1·3
73·5‡	12th	77·7	30th	62·4	4·7‡	8·8	1·9
58·1††	15th	70·4	27th & 30th	49·5	9·2††	13·3	2·0
42·7	2nd	63·4	23rd	31·6	11·5	16·1	5·9
32·2	6th	42·7	20th	26·1	12·4	14·9	8·6
58·5	...	83·9	...	26·1	8·1	16·7	0·3
...	...	67·8	...	50·7	...	12·3	3·8

§ On a woollen pad 5 inches above ground.
‖ Mean of 26 days.
¶ „ „ 24 „
** Mean of 27 days.
†† „ „ 30 „

27. GHAZIPUR (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	40·8	26th	54·2	20th	31·8	6·8†	10·4	3·4
February	39·4	19th	49·3	2nd	29·8	6·7	9·6	3·8
March	49·9	26th	60·5	16th	43·4	8·1	13·1	3·2
April	60·4‡	26th	71·6	9th	50·7	10·0‡	16·2	3·2
May	73·4†	20th	80·5	8th	66·0	4·0†	10·3	0·2
June	76·8§	11th	85·6	1st	69·1	1·9§	6·4	0·2
July	77·6†	12th	80·0	20th	73·4	1·5¶	3·6	0
August	77·6	18th	80·5	25th	75·0	1·5	3·5	0·2
September	75·8	2nd	79·0	24th	72·5	3·1§	10·6	0
October	60·9	1st	74·3	30th	51·5	3·6	8·6	0·3
November	44·6	1st	58·4	28th to 30th	35·6	7·6	14·0	0·2
December	34·4	5th & 6th	42·5	20th	28·7	9·0	11·8	5·9
Year	59·3	...	85·6	...	28·7	5·3	16·2	0
Means of extremes	...	...	68·0	...	52·3	...	9·8	1·7

* On a black blanket 1½ inches above ground.
† Mean of 30 days.
‡ „ „ 26 „

28. SIBSAGAR (*corrected*).**

Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
43·7	28th	52·5	21st	38·5	5·8	7·4	2·7
45·8	20th	51·3	4th	36·5	6·1	9·3	3·9
52·6	23rd	59·3	10th	46·4	6·0	7·7	4·5
59·5	14th	66·6	7th	54·0	6·6	9·0	3·8
65·2	25th	71·2	8th	60·3	6·6	10·3	5·2
70·1	18th	72·7	2nd	66·4	6·8	8·3	4·5
72·8	12th	76·5	3rd	68·5	5·4	8·4	1·9
73·2	24th	75·8	12th & 19th	70·9	4·7	6·4	3·4
72·8	2nd	75·0	27th & 30th	69·5	3·5	5·8	1·4
65·2	6th	72·7	30th	55·4	4·7	7·0	2·8
52·6	3rd	60·8	30th	45·9	6·7	9·1	4·8
45·0	8th	57·8	27th	35·4	5·0	7·7	2·6
59·9	...	76·5	...	35·4	5·7	10·3	1·4
...	...	66·0	...	54·0	...	8·0	3·5

§ Mean of 29 days.
‖ „ „ 27 „
¶ „ „ 23 „
** On a woollen pad 3 inches above ground.

29. DHUBRI (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	49·6	27th	57·3	30th	40·2	4·5	9·0	1·7
February	47·0	20th	54·9	3rd	40·2	6·7	9·7	3·6
March	Imperfect.							
April	Ditto.							
May	69·7	29th	74·9	11th	63·0	2·5	4·5	0·7
June	75·8	2nd	78·6	30th	74·2	2·1	4·5	0·7
July	76·9	23rd	78·5	1st	74·0	2·8	5·0	0·8
August	75·8	5th	78·2	11th	72·3	2·7	5·1	0·9
September	74·4	8th	77·0	30th	69·9	3·0	4·8	1·2
October	66·9	5th	72·1	28th	57·8	5·8	9·2	2·4
November	55·4	3rd	63·5	30th	49·1	7·4	9·5	5·2
December	47·6	5th	59·7	22nd	38·8	7·2	9·6	2·6
Year	?	...	78·6	...	38·8	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 1 inch above ground.

30. DARJEELING (ST. PAUL'S SCHOOL) (*corrected*).†

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	17·7‡	7th	24·5	31st	12·3	16·1§	21·1	11·2
February	20·7‖	21st	26·5	1st	14·5	13·0¶	18·3	5·4
March	Not recorded.							
April	Ditto.							
May	Ditto.							
June	Ditto.							
July	Ditto.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	Ditto.							
December	23·3¶	13th	30·7	18th	10·7	11·8¶	18·4	4·7
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

† On a woollen pad.
‡ Mean of 30 days.
§ „ „ 26 „
‖ Mean of 22 days.
¶ „ „ 29 „

31. PURNEAH (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	42·2	10th	56·3	17th to 20th & 30th.	35·3	6·9†	11·2	0·8
February	43·4	19th	57·3	3rd	35·3	5·9‡	16·2	2·6
March	52·5	5th, 10th & 31st	58·3	17th	44·3	5·8	9·6	2·2
April	62·8	13th & 14th	72·5	5th	51·3	5·9	11·6	1·5
May	71·6	17th & 24th	76·6	12th	60·3	2·5	5·1	0
June	75·1	17th, 18th, 23rd & 24th.	77·6	1st & 2nd	69·5	2·6	7·6	0·1
July	77·7	31st	80·3	6th, 8th & 15th.	75·5	1·5	4·7	0
August	76·2§	24th	79·4	7, 11, 13, 16, 17 & 25th.	74·5	1·6§	3·8	0
September	74·8	14th	77·6	29th & 30th	69·5	2·8	6·5	0·2
October	62·0	14th & 15th	69·5	25th	53·3	7·5	11·6	3·4
November	45·9	1st & 3rd	53·3	21st	36·3	8·9	13·0	7·2
December	Imperfect.							
Year	?	...	80·3	...	?	?	16·2	0
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad inches above ground.
† Mean of 30 days.
‡ Mean of 19 days.
§ „ „ 29 „

32. DURBHUNGA (*corrected*).‖

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	43·6	10th	54·3	19th & 30th	36·0	9·9	17·4	2·8
February	41·4	19th & 25th	53·6	3rd	31·9	11·2	16·7	3·0
March	50·3	4th	55·6	16th	44·9	11·4	17·3	7·3
April	60·4	30th	69·9	7th	49·3	10·1	15·2	4·1
May	71·3	3rd	76·4	21st	62·7	5·1	10·1	2·4
June	74·8	14th	78·8	1st	65·2	4·2	10·9	0
July	78·0	30th	80·1	19th	74·6	2·6	4·7	0·2
August	78·3¶	23rd	80·6	13th	76·6	1·9¶	3·5	0
September	75·5	1st	79·1	24th & 27th	69·7	3·6	5·5	2·0
October	65·1	1st	75·1	25th	55·3	7·3	11·6	2·7
November	56·2**	2nd	59·7	5th	49·8	5·2**	10·6	0
December	Not recorded.							
Year	?	...	80·6	...	31·9	?	17·4	0
Means of extremes	...	...	?	...	?	...	?	?

‡ On a woollen pad 4 inches above ground.
¶ Mean of 28 days.
** „ „ 20 „

33. PATNA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	44·5	10th	58·2	20th	36·3	7·1	11·9	0·5
February	43·6	21st	53·3	7th	34·5	7·5	12·4	2·2
March	53·5	26th	60·0	16th	47·6	8·7	13·6	5·2
April	63·6†	20th	73·3	8th	53·3	8·5†	13·0	1·7
May				Imperfect.				
June	76·8	9th	81·5	1st	70·1	3·2	12·1	0·9
July	77·7	12th	80·9	5th	72·3	2·5	5·7	1·3
August	77·8	11th	80·1	17th	72·5	2·1	2·9	1·5
September	77·1	2nd & 7th	79·3	27th	73·3	2·4	3·9	1·5
October	67·3	3rd	75·1	26th	58·1	3·9	5·2	2·0
November	52·9	2nd	66·9	23rd	44·1	4·5	6·5	2·6
December	44·2	5th	58·7	24th	39·2	4·0	6·5	2·0
Year	?	...	81·5	..	34·5	?	13·6	0·5
Means of extremes	...	...	?	...	?	?	...	?

* On a woollen pad 2½ inches above ground. † Mean of 26 days.

34. HAZARIBAGH (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	42·2	10th	54·3	20th	32·8	8·9	15·3	1·5
February	44·1	20th	55·8	8th	29·7	7·7	15·3	3·5
March	55·7	24th & 25th	63·6	1st	47·4	6·8	15·1	1·0
April	66·2	14th	72·8	9th	57·8	7·1	13·7	3·1
May	71·9	18th & 19th	76·3	23rd	64·8	5·1	9·3	2·0
June	72·5	4th	75·8	28th	69·6	2·7	8·1	0·
July	71·9	30th	73·6	2nd	68·6	1·6	5·8	0
August	71·1	4th	74·3	22nd	66·6	2·5	6·5	0·3
September	70·0	5th & 17th	72·8	30th	64·3	2·9	6·¾	0·6
October	57·6	14th	67·3	25th	46·7	9·0	13·8	3·0
November	44·4	2nd	62·6	23rd	32·9	11·4	17·6	1·0
December	35·2	5th	56·6	21st	28·4	12·9	16·9	4·7
Year	58·6	...	76·3	...	28·4	6·6	17·6	0
Means of extremes	...	...	67·2	...	50·8	...	12·0	1·5

‡ On a woollen pad 1 inch above ground.

35. BERHAMPORE (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	38·6	27th	53·0	30th	30·4	14·6	18·7	6·7
February	38·3	20th	50·4	4th	26·8	15·6	19·5	10·7
March	52·1	29th	65·8	15th to 17th	42·8	12·1	16·9	3·7
April	65·4	15th, 16th & 20th	74·3	9th	50·8	8·4	16·5	0·4
May	74·2	14th	83·0	20th	67·3	3·4	5·8	0·5
June	75·6	16th & 17th	78·8	9th	71·8	2·5	5·5	1·0
July	77·2	27th	79·3	18th	74·3	1·6	3·5	0·5
August	76·7	5th	78·8	12th	74·3	1·8	3·7	0·5
September	75·3	16th	78·0	30th	69·8	2·9	5·0	1·5
October	65·5	4th, 5th & 13th	72·8	29th	55·8	7·4	11·4	3·0
November	49·7	2nd	66·3	21st & 22nd	37·8	10·3	15·2	3·4
December	39·5	5th	60·3	24th	31·8	11·9	15·9	1·4
Year	60·7	...	83·0	...	26·8	7·7	19·5	0·4
Means of extremes	...	...	70·1	...	52·8	...	71·5	2·8

* On a woollen pad 4 inches above ground.

36. BURDWAN (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	45·0	10th	54·4	20th	37·1	8·5	11·7	0·2
February	46·5	12th	61·0	6th	33·5	8·9	12·1	3·0
March	58·9‡	29th	70·5	17th	49·8	8·1‡	12·0	1·4
April	68·0	21st	75·4	9th	55·3	6·3	12·5	2·2
May	74·4	15th	79·4	23rd	67·5	4·2	8·0	0·8
June	73·7	4th & 16th	75·4	19th	70·3	5·1	7·5	2·9
July	72·2‡	30th	79·3	25th	67·0	4·5‡	13·9	1·5
August	75·3	4th & 8th	77·9	15th	67·2	3·1	9·7	0
September	75·3§	17th	78·9	30th	70·9	3·8§	6·4	1·5
October	66·2	3rd	72·9	26th	56·6	7·0	10·4	3·2
November	50·6	2nd & 3rd	66·5	22nd	38·1	10·5	15·2	2·9
December	43·7	4th	63·5	24th	34·8	9·6	13·2	0·9
Year	62·5	...	79·4	...	33·5	6·6	15·2	0
Means of extremes	...	...	71·3	...	54·0	...	11·1	1·7

† On a woollen pad 2½ inches above ground.
‡ Mean of 30 days.
§ Mean of 29 days.

37. JESSORE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January . .	42·3	24th	51·3	30th	37·4	9·3	12·0	2·4
February . .	44·1†	21st	58·6	4th	33·1	9·9†	15·5	6·7
March . . .	58·2‡	25th	68·4	17th	46·8	9·0‡	13·9	4·8
April . . .	Imperfect.							
May . . .	74·2§	13th	80·3	10th	66·9	3·2§	6·4	1·3
June . . .	75·9	2nd	78·2	3rd & 4th	72·3	2·8	5·2	1·2
July . . .	76·5	17th & 30th	79·2	12th	73·5	2·4	4·8	1·0
August . . .	76·3	5th	80·2	16th & 27th	73·2	2·6	6·7	0·6
September . .	75·0	2nd	78·2	30th	70·0	3·4	6·1	1·4
October . .	66·2	6th	73·0	26th & 30th	58·1	7·2	9·4	4·3
November . .	52·8†	2nd	69·2	22nd	38·2	7·5†	10·9	1·3
December . .	43·4	5th	62·7	24th	35·8	9·2	14·0	1·1
Year . . .	?	...	80·3	...	33·1	?	15·5	0·6
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 2 inches above ground.
† Mean of 26 days.
‡ Mean of 21 days.
§ Mean of 27 days.

38. DACCA (*corrected*).‖

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January . .	42·5	24th	50·2	31st	34·3	11·1	19·1	3·5
February . .	41·9	13th	56·7	4th	32·8	11·8	19·9	1·0
March . . .	60·2	25th	72·3	15th	46·2	7·8	14·8	2·4
April . . .	68·7¶	15th	76·8	7th	61·2	4·7¶	10·9	1·7
May . . .	72·9	13th	79·1	22nd	67·3	3·0	5·1	0·5
June . . .	76·4	18th	78·9	4th	72·7	2·0	4·8	0·5
July . . .	76·8§	9th	78·1	2nd	75·4	2·4§	4·4	0·5
August . . .	76·5	5th	78·4	29th	74·4	2·4	5·1	0·7
September . .	75·6	14th	78·1	28th	72·3	3·1	5·5	0·6
October . .	67·6	5th & 11th	73·8	23rd	56·2	6·8	11·1	0·9
November . .	53·4	4th	70·3	30th	43·3	10·1	16·1	2·6
December . .	45·9	7th	64·7	22nd & 26th	37·3	9·8	14·7	0·1
Year . . .	63·2	...	79·1	...	32·8	6·3	19·9	0·1
Means of extremes	...	...	71·5	...	56·1	...	11·0	1·3

‖ On a woollen pad 4 inches above ground.
¶ Mean of 29 days.

39. CHITTAGONG (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January . .	48·3	28th	60·2	31st	39·5	5·6	9·8	1·1
February . .	48·1	27th	59·2	7th	36·5	7·7	12·7	2·0
March . . .	63·6	26th	71·5	15th	52·2	3·9	9·3	0·1
April . . .	67·6	18th	72·5	6th	62·2	4·8	10·9	0·6
May . . .	72·8	13th	78·3	22nd	65·3	2·4	5·0	0·6
June . . .	74·4	2nd	77·3	20th	72·5	1·5	4·6	0
July . . .	74·1	13th	76·3	25th	71·0	1·9	4·2	0
August . . .	74·3†	21st	77·3	12th, 29th & 31st	72·5	1·3†	3·1	0
September . .	73·8	22nd	75·9	5th	70·5	1·8	5·0	0
October . .	69·8	8th	76·3	24th, 25th & 31st	64·3	4·2	11·9	0·1
November . .	59·3	13th	68·4	21st	47·3	6·3	11·3	0·9
December . .	52·9	4th	68·4	25th	39·5	5·5	12·5	0
Year . . .	64·9	...	78·3	...	36·5	3·9	12·7	0
Means of extremes	...	...	71·8	...	57·8	...	8·4	0·5

* On a woollen pad 3 inches above ground.
† Mean of 30 days.

40. CALCUTTA (ALIPORE) (*corrected*).‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January . .	42·7	28th	52·9	20th	35·2	10·2	13·8	3·6
February . .	47·4	13th	61·2	7th	32·3	9·9§	14·8	0·6
March . . .	60·6	24th & 31st	67·3	17th	48·3	8·7	12·5	2·9
April . . .	69·0	17th	75·2	23rd	62·3	6·0	11·1	1·9
May . . .	75·2	14th	80·4	1st & 20th	68·2	3·8	6·8	0·9
June . . .	75·0‖	17th	78·6	5th	71·4	2·8‖	7·1	0·7
July . . .	76·0	25th	77·8	19th	73·6	2·5	4·4	1·2
August . . .	75·3	4th	77·9	14th	70·8	3·0	4·4	1·0
September . .	74·8	14th	76·7	30th	70·3	3·6	5·4	1·3
October . .	66·8	6th	73·2	26th	55·6	7·1	10·1	4·6
November . .	50·6	2nd	68·8	22nd	38·0	10·4	13·5	3·1
December . .	43·9	5th	63·1	23rd	36·6	10·0	13·3	1·1
Year . . .	63·1	...	80·4	...	32·3	6·5	14·8	0·6
Means of extremes	...	...	71·1	...	55·2	...	9·8	1·9

‡ On a woollen pad 1 inch above ground.
§ Mean of 26 days.
‖ Mean of 29 day.

41. Saugor Island (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January				Not recorded.				
February	45·0†	12th	63·0	7th & 8th	38·9	9·6‡	13·7	0
March	64·8	25th	72·2	17th	55·8	9·0	15·6	4·8
April	72·3	25th	77·2	22nd	66·5	6·2	11·0	1·9
May	76·8	18th	80·8	4th	70·1	4·8	9·2	2·0
June	77·6†	9th	82·2	10th	69·8	4·1†	13·9	0·2
July	75·7§	17th	80·0	31st	66·2	4·0§	14·8	0·8
August								
September								
October								
November				Untrustworthy.				
December								
Year								
Means of extremes								

* On a woollen pad 2½ inches above ground.
† Mean of 24 days. ‡ Mean of 23 days.
§ „ 30 „

42. Cuttack (*corrected*).‖

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	49·4	5th, 24th & 27th.	55·0	22nd	42·9	10·9	13·0	8·6
February	53·9	25th	63·1	4th & 6th	42·0	10·6	19·5	4·0
March	63·5	28th	70·8	18th	54·8	8·8	14·1	5·6
April	71·3	29th	77·1	22nd	65·0	6·9	10·2	2·7
May	75·0	17th	83·1	20th	69·0	4·6	7·8	0·7
June	75·2	7th & 22nd	77·1	11th	72·1	3·2	6·9	1·1
July	75·2	31st	77·5	1st, 27th & 30th.	73·1	2·9	4·8	1·3
August	74·6	23rd & 24th	76·9	5th	71·1	3·3	8·2	1·6
September	73·3	15th	76·4	29th	69·0	4·8	8·4	1·0
October	66·8	1st & 22nd	70·5	27th	56·5	7·5	9·1	4·6
November	54·2	3rd	69·5	23rd	43·0	8·2	11·6	2·6
December	43·8	5th & 6th	50·0	26th	38·0	10·5	18·0	7·8
Year	64·7	...	83·1	...	38·0	6·9	19·5	0·7
Means of extremes	...	...	70·6	...	58·0	...	11·0	3·5

‖ On a woollen pad 2 inches above ground.

43. False Point (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	55·0†	7th	61·1	21st & 22nd	49·5	4·9†	11·2	2·2
February	60·7‡	28th	68·8	6th	49·5	3·6‡	9·4	0
March	70·3§	23rd	76·2	17th	64·7	3·2§	8·3	0·4
April	74·7‖	29th	78·3	22nd	69·9	2·5‖	7·5	0·2
May	76·1¶	17th & 21st	80·0	2nd	69·5	2·4¶	6·6	0·5
June	76·6	6th, 8th, 10th 22nd & 25th.	79·0	13th	73·0	1·4	3·6	0
July	76·6**	17th	80·0	6th	73·9	1·5††	2·9	0
August	75·6‖	5th	78·0	16th	73·0	1·6‖	4·1	0
September	76·4	13th & 18th	78·0	17th	74·6	1·5	4·1	0
October	69·9	2nd	76·0	27th	57·9	3·8	7·0	0·5
November	57·1	3rd	71·0	24th	47·9	4·3	7·3	0·6
December	45·9	5th	61·1	26th	35·5	7·4	13·6	4·1
Year	67·9	...	80·0	...	35·5	3·2	13·6	0
Means of extremes	...	...	74·0	...	61·6	...	7·1	0·7

* On a woollen pad 2½ inches above ground.
† Mean of 30 days.
‡ Mean of 27 days.
§ „ 26 „
‖ Mean of 28 days.
¶ „ 29 „
** „ 25 „
†† „ 24 „

44. Sambalpur (*corrected*).‡‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	49·8	26th	60·1	16th	42·1	6·5	8·7	4·7
February	53·8	13th	62·9	6th & 7th	44·2	7·1	10·7	3·4
March	59·7	2nd	66·5	18th	51·4	8·1	14·2	5·0
April	63·3	30th	72·8	1st	57·0	14·1	17·4	9·6
May	72·6	17th	78·1	7th	66·0	12·0	18·1	6·4
June	71·2	25th	75·0	30th	66·3	10·0	18·2	5·4
July	70·7	12th *	74·8	28th	66·1	6·3	8·8	4·0
August	71·4	24th	74·2	2nd	67·0	6·4	8·1	4·9
September	71·1	20th	75·2	26th & 28th	68·0	6·2	8·7	4·0
October	65·9	4th	71·0	26th	55·5	6·3	9·0	3·5
November	52·0	4th	67·8	24th	41·8	7·2	12·4	4·8
December	42·3	5th	57·9	25th	37·2	7·7	10·3	4·8
Year	62·0	...	78·1	...	37·2	8·2	18·2	3·4
Means of extremes	...	...	69·7	...	55·2	...	12·1	5·0

‡‡ On a woollen pad 5 inches above ground.

45. SAMBALPUR (NEW OBSERVATORY) (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Observatory opened on 16th October 1883.							
February								
March								
April								
May								
June								
July								
August								
September								
October	Imperfect.							
November	51·1	4th	67·9	24th	39·3	7·7	11·0	4·1
December	41·4	5th	56·9	25th	35·9	8·1	12·3	4·1
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

* On a woollen pad 1½ inches above ground.

46. RAIPUR (*corrected*).†

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Not recorded.							
February	Ditto.							
March	62·1‡	25th	72·9	17th	52·2	6·9‡	12·0	1·4
April	71·8	28th & 30th	82·3	9th	61·1	6·4	12·1	2·6
May	81·7	15th	86·8	31st	70·1	3·3	11·6	1·2
June	72·7	9th	82·3	14th	69·1	3·2	7·6	1·6
July	70·4	21st	73·3	7th	67·3	3·8	7·6	1·0
August	72·9	15th	75·8	4th	70·1	2·5	6·1	1·4
September	70·9	30th	73·8	25th	69·3	2·1	3·2	1·1
October	66·0	3rd	72·8	26th	52·6	2·7	8·2	1·0
November	49·7	3rd	66·1	23rd	38·2	7·3	11·5	1·4
December	38·1	5th	56·4	20th & 26th	33·2	8·8	11·9	3·3
Year	?	...	86·8	...	?	?	12·1	1·0
Means of extremes	...	...	?	...	?	...	?	?

† On a woollen pad resting on the ground.
‡ Mean of 23 days.

47. NAGPUR (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	43·3	26th	60·6	29th	33·9	13·1	19·9	3·6
February	45·5	18th	53·3	3rd	34·7	13·7	18·0	9·7
March	54·1	25th	62·6	13th	41·1	13·2	18·6	6·6
April	63·9	14th	74·9	7th	52·0	12·6	18·1	6·1
May	71·9	19th	82·2	9th	64·9	11·2	16·8	3·5
June	73·5	2nd	80·7	5th	67·9	3·4	9·1	1·3
July	71·6	15th	74·7	3rd	65·9	3·3	6·6	1·2
August	70·1	19th & 29th	74·4	12th & 17th	66·5	5·8	10·8	1·1
September	70·1	2nd	72·8	19th	66·8	3·5	7·4	0·8
October	60·0	1st	69·9	29th	44·5	8·5	14·8	1·9
November	43·0	1st	66·9	27th	31·1	14·4	20·6	3·3
December	31·3	13th	39·6	18th	24·3	17·6	20·5	12·0
Year	58·2	...	82·2	...	24·3	10·0	20·6	0·8
Means of extremes	...	...	67·7	...	49·5	...	15·1	4·3

* On a woollen pad 3 inches above ground.

48. SEONI (*corrected*).†

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	43·1	26th	56·8	28th	31·4	9·6	12·9	2·9
February	44·9	11th	54·8	3rd & 4th	37·2	10·2	15·5	5·0
March	49·7	24th	57·8	17th	38·3	13·5	18·8	6·7
April	61·3	14th	74·2	7th	49·7	11·9	16·1	7·0
May	68·3	26th	74·6	6th	59·1	9·5	15·3	1·2
June	71·5	10th	75·9	24th	67·9	3·2	6·9	0·7
July	69·4	16th	72·6	3rd	63·8	2·6	4·6	0·6
August	67·7	28th	71·9	15th	62·3	4·5	9·9	1·6
September	67·6	3rd	72·0	28th	62·3	3·6	7·5	0·5
October	56·7‡	1st	66·8	29th	43·4	8·0‡	12·4	1·2
November	42·4	1st	65·3	25th	32·4	10·4	18·4	1·4
December	31·0	5th	40·7	21st	24·9	14·0	17·8	9·3
Year	56·1	...	75·9	...	24·9	8·4	18·8	0·5
Means of extremes	...	...	65·3	...	47·7	...	13·0	3·2

† On a woollen pad 6 inches above ground.
‡ Mean of 30 days.

f

49 JUBBULPORE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	41·9	9th	54·5	29th	32·2	10·4	20·7	4·6
February	41·7	18th	53·5	15th	32·7	11·2	15·4	6·6
March	49·8	24th	55·5	17th	41·2	13·6†	27·1	7·8
April	60·3†	14th	73·0	3rd	48·5	13·7†	20·8	9·3
May	70·1	13th & 15th	77·4	6th	59·8	14·7‡	28·9	3·8
June	74·1	11th	80·7	2nd	69·6	5·0§	14·5	0·4
July	72·8	9th	77·0	3rd	68·1	1·4§	5·3	0
August	72·2	5th & 28th	74·5	7th	69·4	2·7	6·4	0·6
September	71·1	1st	74·1	29th	64·8	2·1	6·6	0·1
October	59·9	7th & 8th	68·6	30th	45·9	4·5	9·9	1·0
November	41·3	1st	55·8	27th	28·5	8·8	13·6	4·6
December	29·1	30th	34·7	20th	24·8	10·3	12·5	7·5
Year	57·0	...	80·7	...	24·8	8·2	28·9	0
Means of extremes	...	...	64·9	...	48·8	...	15·1	3·9

* On a woollen pad 2 inches above ground.
† Mean of 29 days.
‡ Mean of 28 days.
§ ,, ,, 30 ,,

50. SAUGOR (*corrected*).‖

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	44·8	9th	55·3	28th	31·4	8·8	12·6	3·5
February	43·0	18th	55·8	2nd & 5th	31·9	10·1	14·5	5·7
March	53·9	3rd	61·7	16th	42·4	9·1	14·4	3·4
April	61·4	14th	71·2	6th	53·8	13·5	16·9	8·9
May	69·6	21st	81·1	5th	52·3	9·0	26·3	1·0
June	74·2†	4th	81·1	6th	68·2	2·7†	8·4	0
July	71·6	15th	75·6	3rd	67·2	1·9	5·9	0
August	70·2	27th	75·1	11th & 17th	65·2	2·9	6·5	0
September	69·3	2nd	74·7	28th & 29th	62·2	2·5	7·6	0
October	57·6	2nd	68·7	30th	44·3	8·0	17·4	1·5
November	44·3	14th	51·3	25th	35·4	11·9	17·4	7·5
December	36·2	1st	44·3*	26th	32·4	11·9	17·0	8·6
Year	58·0	...	81·1	...	31·4	7·7	26·3	0
Means of extremes	...	...	66·3	...	48·9	...	13·7	3·3

‖ On a woollen pad 3 inches above ground.

51. PACHMARHI (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	35·5	26th	54·1	29th	22·0	13·0	16·2	3·8
February	36·6	18th	52·1	3rd	26·8	13·8	18·2	11·0
March	45·6	5th	58·6	17th	33·8	14·4	20·5	7·4
April	54·7	26th	68·3	4th	43·1	15·6	21·7	8·1
May	Imperfect.							
June	Ditto.							
July	66·3†	15th	69·9	3rd	58·9	1·2‡	5·6	−0·5
August	Untrustworthy.							
September	64·2	1st	67·7	28th	55·8	2·1	7·9	−0·6
October	52·8	1st	64·8	29th	38·9	6·6	14·0	0
November	35·9	1st	52·0	25th	24·8	10·8	13·9	7·2
December	26·0	13th	32·8	18th	20·2	13·0	15·9	9·2
Year	?	...	?	...	20·2	?	21·7	−0·6
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 3 inches above ground.
† Mean of 22 days.

52. HOSHANGABAD (*corrected*).‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	48·1	22nd	55·9	29th	34·1	6·5	10·3	1·4
February	47·8	25th	56·1	3rd	37·8	7·2	11·6	4·0
March	54·1	25th	60·6	16th	43·4	10·4	14·5	6·9
April	64·0	14th & 28th	71·1	4th	54·9	10·5	18·1	7·5
May	72·1	21st	79·1	2nd	59·6	8·2	17·6	4·5
June	74·2	3rd	78·1	6th	69·5	3·6	8·1	1·1
July	72·6	1st	75·5	3rd	69·1	2·5	4·1	0·5
August	70·7	29th	74·3	16th	66·0	3·6	7·6	1·1
September	71·2	3rd	73·7	21st	68·6	2·3	4·7	0·4
October	60·9	8th	71·5	30th	46·9	6·4	12·4	1·5
November	42·6	1st	53·3	25th	32·9	11·9	14·5	8·8
December	33·3	30th	37·8	18th	30·1	11·7	14·1	9·0
Year	59·3	...	79·1	...	30·1	7·1	18·1	0·4
Means of extremes	...	...	65·6	...	51·1	...	11·5	3·9

‡ On a woollen pad resting on the ground.

53. KHANDWA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.			Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	49·1	20th	62·0	29th	33·8	4·6	6·9	1·1	46·7	26th	65·2	29th	38·0	8·6	12·2	4·6
February	49·0	11th	56·9	1st	37·8	5·7	9·5	3·5	49·9	10th	57·3	2nd & 3rd	41·2	10·4	14·2	8·1
March	57·7	18th	64·1	12th	46·2	7·0	12·0	2·0	58·5	11th	68·1	17th	48·7	9·8	14·5	2·0
April	69·1	28th	80·2	6th	57·5	6·4	9·3	3·9	65·6	22nd	75·8	5th	54·5	11·7	15·6	8·4
May	76·5	19th	83·6	11th	69·0	4·4	10·0	1·7	74·0	31st	83·9	7th	62·8	10·2	13·3	2·5
June	74·8	2nd	82·6	11th	69·9	2·2	4·6	1·2	75·4	6th	80·0	7th	71·7	3·1	7·5	1·0
July	71·8	12th	74·8	4th	68·2	2·8	4·9	1·3	73·1	15th	75·7	3rd	69·2	3·0	6·1	0·8
August	70·4	19th	74·0	5th	66·7	3·3	7·0	1·2	72·6	1st	76·3	5th & 17th	68·7	3·3	7·4	0·6
September	70·4	2nd	72·4	13th	67·9	2·1	3·2	1·2	71·4	1st	74·6	11th	67·2	2·6	5·9	0·6
October	62·2	9th	70·9	31st	49·3	4·0	6·7	0·8	64·5	1st	70·5	26th	52·1	3·7	7·6	1·1
November	45·7	1st	58·4	27th	33·9	6·9	10·3	3·9	48·8	3rd	69·3	27th	36·9	7·1	9·4	1·9
December	33·4	13th	39·8	19th	28·5	8·9	10·4	5·8	37·3	14th	54·0	27th	31·8	7·7‡	9·1	6·1
Year	60·8	...	83·6	...	28·5	4·9	12·0	0·8	61·5	...	83·9	...	31·8	6·8	15·6	0·6
Means of extremes	...	...	68·3	...	52·4	...	7·9	2·2	...	...	70·9	...	53·6	...	10·2	3·1

* On a woollen pad 4½ inches above ground.

54. CHANDA (*corrected*).†

† On a woollen pad 3 inches above ground.
‡ Mean of 29 days.

55. SIRONCHA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.			Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	50·9	26th	63·5	29th	44·2	9·5	12·6	4·8	43·3	26th	52·2	29th	27·6	13·3	23·1	3·9
February	55·1	11th	60·7	5th	47·0	10·7	13·5	4·1	47·5	18th	56·5	2nd	29·6	13·0	19·7	2·2
March	65·4	16th	70·9	17th & 27th	59·7	9·2	14·0	4·2	55·8	22nd & 25th	65·2	16th	41·8	9·5	22·9	2·1
April	70·4	28th	80·7	7th	58·9	10·1	15·7	3·6	Untrustworthy.							
May	80·0	22nd	90·7	28th	71·2	6·8	10·6	2·2	Ditto.							
June	75·9	11th	82·7	2nd	70·2	3·0	6·8	1·4	Ditto.							
July	73·5	4th & 6th	75·7	8th	70·7	3·0	5·7	1·2	Ditto.							
August	73·4	1st, 15th, 18th & 19th.	75·7	17th	70·1	3·5	6·7	1·2	Ditto.							
September	72·1	1st, 2nd, 15th to 17th.	73·7	14th	69·6	3·6	6·1	1·2	Ditto.							
October	67·7	1st & 5th	71·1	27th	55·2	5·6	9·4	1·7	Ditto.							
November	51·3	1st	70·9	30th	40·0	10·1	14·2	2·8	Ditto.							
December	41·8	14th	57·9	19th	34·0	11·2	14·1	5·5	Ditto.							
Year	64·8	...	90·7	...	34·0	7·2	15·7	1·2	...	...	...	...	...	...	...	...
Means of extremes	...	...	72·9	...	57·6	...	10·8	2·8	...	...	...	...	...	...	...	...

* On a woollen pad 6 inches above ground.

56. CHIKALDA (*corrected*).†

† On a woollen pad 3 inches above ground.

57. BULDANA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.			Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	47·7	20th	62·1	29th	31·2	10·8	23·1	0·8	46·1	20th & 25th	54·4	28th	29·5	9·2	16·7	4·6
February . .	46·8	22nd	60·4	2nd	31·9	15·6	20·5	1·8	47·8	11th	55·0	2nd	35·1	9·5	14·1	4·6
March . .	56·7	28th	65·1	13th	44·4	12·3	21·9	3·8	56·9	20th	66·5	13th	42·4	9·2	14·3	3·7
April . . .	64·9	13th	75·0	8th	52·4	12·4	24·2	4·9	65·2	13th	81·1	10th	52·9	10·1	19·5	4·1
May . . .	71·0	19th	77·0	22nd	63·1	6·1	10·2	2·8	75·9	20th	82·1	5th	63·4	5·5	12·7	0·6
June . . .	69·0	2nd	74·5	11th	65·1	2·4	7·3	0·5	72·6	2nd	77·4	30th	69·4	2·3	6·3	—0·9
July . . .	67·5	15th	71·6	4th & 31st	63·1	2·2	4·4	0	70·7	7th & 15th	74·5	3rd	65·9	2·5	4·6	0
August . .	66·1	19th	71·0	6th	62·1	2·7	6·5	—1·5	69·9	27th & 28th	74·0	5th	64·5	3·5	6·7	0
September . .	66·7	21st & 27th	69·0	15th	63·4	1·3	3·2	0	69·7	2nd & 7th	72·5	12th	65·0	2·1	4·8	—0·7
October . .	59·9	18th	68·0	30th	45·1	7·2	20·2	—0·7	61·4	9th	69·9	29th	46·8	6·2	12·7	0
November . .	44·9	4th	63·3	23rd	34·5	14·8	21·5	4·5	45·1	1st	65·2	28th	34·1	9·9	12·7	4·1
December . .	36·3	14th & 30th	43·4	18th	32·0	17·2	22·0	9·9	32·2	14th	40·5	18th	25·3	11·9	14·7	9·8
Year . . .	58·1	...	77·0	...	31·2	8·8	24·2	—1·5	59·5	...	82·1	...	25·3	6·8	19·5	—0·9
Means of extremes	...	...	66·7	...	49·0	...	15·4	2·2	...	...	67·8	...	49·5	...	11·7	2·5

* On a woollen pad 2·5 inches above ground.

58. AKOLA (*corrected*).†

† On a woollen pad 2·2 inches above ground.

59. AMRAOTI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.			Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	46·0	25th	55·0	28th	30·5	11·7	27·4	7·7	39·1	25th	48·0	28th	23·3	10·6	15·6	6·6
February . .	50·6†	25th	58·0	2nd	41·4	11·0†	18·8	5·6	36·7	18th	50·3	1st	24·1	12·4	15·7	8·1
March . . .	55·2	4th	64·4	13th	47·2	12·3	18·5	5·6	48·0	31st	56·4	12th	27·2	12·5	21·9	7·5
April . . .	61·1‡	7th	67·7	5th & 18th	55·5	15·7‡	23·0	6·6	56·6	28th	64·4	3rd & 7th	51·1	15·5	21·7	11·9
May . . .	66·1§	30th	77·2	6th	55·5	12·9§	21·4	3·6	61·2	20th	68·1	4th	54·7	13·7	18·7	3·4
June . . .	71·6	18th	75·7	3rd	68·7	2·8	6·0	0·8	68·3	19th	71·2	1st	60·4	8·5	16·4	5·5
July . . .	70·1	15th	73·5	3rd & 4th	66·3	2·5	9·7	—0·7	66·4	6th	69·2	3rd	62·7	6·7	8·3	4·0
August . .	66·9	27th	71·1	14th	62·8	5·8	11·8	2·2	64·4	27th	68·4	13th	59·8	7·9	11·2	5·3
September . .	65·9	2nd & 18th	68·3	13th	62·4	5·1	8·6	3·1	63·9	2nd	68·3	29th	57·4	7·4	12·2	4·3
October . .	60·5§	19th	67·3	29th	45·7	7·1§	13·1	1·0	51·6	2nd	61·8	25th	42·6	12·0	17·6	4·9
November . .	48·6‡	4th	62·5	29th	38·1	9·3‡	15·7	1·4	36·6	8th	48·3	23rd	26·3	15·2	20·6	7·5
December . .	40·5	31st	46·2	17th	34·2	10·4	15·9	4·4	27·2	2nd & 30th	33·3	18th	22·3	18·2	20·9	15·6
Year . . .	58·6	...	77·2	...	30·5	8·9	23·0	—0·7	51·7	...	71·2	...	22·3	11·7	21·9	3·4
Means of extremes	...	...	65·6	...	50·7	...	15·8	3·4	...	...	59·0	...	42·7	...	16·7	7·0

* On a woollen pad 1·7 inches above ground.
† Mean of 27 days.
‡ „ „ 29 „
§ Mean of 30 days.

60. NEEMUCH (*corrected*).‖

‖ On a woollen pad 2·5 inches above ground.

61. NOWGONG (*corrected*).*

MONTH.	MAXIMUM.			MINIMUM.		DIFFERENCE, SHADE AND RADIATION.			MAXIMUM.		MINIMUM.		DIFFERENCE, SHADE AND RADIATION.		
	Mean.	Day.	°	Day.	°	Mean	Maximum.	Minimum.	Mean.	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	36·6	26th	54·0	28th	27·3	12·5	16·8	5·9				Imperfect.				
February	34·1	25th	54·5	6th	22·8	13·9	17·5	6·2	42·8	25th	56·2	7th	32·0	5·5	8·7	1·9
March				Not recorded.					54·4	23rd	60·3	16th	44·1	5·4	8·2	1·5
April	56·2†	30th	72·7	6th	45·6	14·8†	16·7	10·1	65·0	30th	76·3	6th	54·2	6·2	9·9	1·7
May	65·9	13th	76·6	10th	60·0	13·6	26·3	1·9	73·5	22nd	80·7	9th	65·5	4·4	7·7	0·3
June	75·1	11th	81·1	2nd & 3rd	67·4	7·6	19·2	1·6	78·0	12th	85·5	26th	70·9	3·0	10·3	0·5
July	74·3‡	15th	77·1	3rd	68·6	3·7‡	7·6	0·1	75·0	4th, 5th & 19th	78·2	12th	70·4	1·3§	3·2	0·2
August	73·0	25th	75·9	17th	69·4	5·3	9·1	1·1	74·8	18th	77·3	12th	71·9	2·0	3·4	0
September	71·2	2nd & 12th	75·9	26th	63·2	4·8	8·6	1·0	72·9	10th	76·5	29th	65·5	1·9	5·2	0
October	56·9§	19th	69·6	28th	40·4	9·2§	17·3	0·5	60·6	1st	71·9	30th	49·2	4·4	6·5	0·4
November	39·7	2nd	51·5	22nd	28·0	11·3	14·4	5·2	44·4‖	2nd	55·7	22nd	34·2	6·0‖	8·0	1·1
December	28·7	30th	34·8	19th	24·0	12·9	14·4	11·4	35·2	31st	45·1	20th	30·5	6·8	8·7	3·9
Year	?	...	81·1	...	22·8	?	26·3	0·1	?	...	85·5		?	?	10·3	0
Means of extremes	...	...	?	...	?	...	?	?	?	...	?	...	?	...	?	?

* On a woollen pad 1½ inches above ground.
† Mean of 27 days.
‡ Mean of 29 days.
§ „ „ 30 „
‖ On a woollen pad 3 inches above ground.

62. SUTNA (*corrected*).‖

63. INDORE (*corrected*).*

MONTH.	MAXIMUM.			MINIMUM.		DIFFERENCE, SHADE AND RADIATION.			MAXIMUM.		MINIMUM.		DIFFERENCE, SHADE AND RADIATION.		
	Mean.	Day.	°	Day.	°	Mean.	Maximum.	Minimum.	Mean.	Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	38·0	19th	46·9	28th	23·8	13·4	17·9	10·0	38·5	24th	46·3	31st	24·3	12·3	19·7	6·7
February	35·7	18th	46·4	1st	22·8	14·4	19·2	8·3	37·8	17th & 18th	54·1	6th	24·3	14·5	22·7	5·3
March	43·9	4th	56·3	12th	33·2	15·8	24·2	8·7	52·9	27th & 31st	64·1	14th	41·8	10·6	19·6	4·3
April	53·9	29th	69·2	3rd	38·3	16·5	27·6	4·0	68·7	29th	83·1	2nd	58·1	9·1	15·6	2·0
May				Imperfect.					76·5	11th	86·1	24th	65·1	5·9	14·6	—0·8
June				Not recorded.					83·4	26th & 27th	88·9	1st	76·1	4·3	9·7	0·7
July				Ditto.					78·7	9th	82·9	20th	74·8	3·6	7·8	—1·7
August				Ditto.					77·6	29th	83·9	14th	73·8	5·0	9·3	—1·2
September				Ditto.					73·6	1st	79·9	28th	64·9	6·6	14·3	2·9
October				Ditto.					60·5	2nd	71·8	30th	48·7	12·5	18·6	4·9
November				Ditto.					48·0	9th	62·0	22nd	32·9	11·2	19·1	0·9
December				Ditto.					35·3	29th	45·2	10th	27·9	14·9	20·1	7·8
Year	...	...	...	...	...	...	...	...	61·0	...	88·9	...	24·3	9·2	22·7	—1·7
Means of extremes	...	...	...	...	...	...	...	...	...	...	70·7	...	51·1	...	15·9	2·7

* On a woollen pad 2·5 inches above ground.

64. BICKANEER (*corrected*).†

† On a woollen pad 4 inches above ground.

65. JEYPORE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	38·6	20th	54·3	29th	28·3	11·3	15·1	3·1
February	37·0	18th	52·2	6th	25·0	12·4	15·8	6·7
March	50·5	2nd	61·6	15th	39·6	9·7	16·7	2·6
April	62·0	10th	75·5	3rd	52·8	10·0	13·7	0·3
May	67·9	22nd	81·1	5th	60·2	6·9	12·1	0·8
June	73·7	14th	82·8	1st	67·0	4·9	8·3	1·1
July	72·8	2nd	78·0	28th	67·3	2·8	6·0	0
August	71·5	29th	78·8	12th & 16th	66·0	4·5	6·9	1·8
September	70·8	8th	74·6	23rd	64·7	3 6	7·6	0·9
October	54·3	2nd	66·0	31st	42·4	9·0	13·2	4·9
November	40·0	13th	54·7	21st	33·3	10·6	13·2	6·8
December	33·2	1st	48·1	18th	26·2	11·2	15·5	7·2
Year	56·0	...	82·8	...	25·0	8·1	16·7	0
Means of extremes	...	...	67·3	...	47·7	...	12·0	3·0

* On a woollen pad 1 inch above ground.

66. SAMBHAR (*corrected*).†

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	37·5	20th	47·5	31st	25·9	8·7	13·5	1·0
February	35·5	18th & 28th	49·0	6th	21·9	10·5	15·9	5·5
March	49·6	19th	61·8	13th	38·9	7·7	11·8	2·4
April	64·4	29th	80·5	3rd	51·0	6·7	11·3	1·9
May	75·0‡	21st	85·9	29th	63·8	4·5‡	8·5	1·1
June	78·4	4th & 12th	84·9	1st	70·7	3·7	9·2	0·3
July	74·4	2nd	78·8	18th	70·7	3·2‡	12·7	1·2
August	74·4	29th	80·8	12th	69·7	3·8	7·6	1·1
September	70·8	2nd	75·7	23rd	61·7	5·0	11·8	0·6
October	55·1	3rd	65·8	30th	41·4	9·2	12·9	3·6
November	38·8	12th	56·9	18th	29·9	11·6	15·1	6·2
December	31·0	30th	37·1	18th	25·1	11·1	13·8	7·3
Year	57·1	...	85·9	...	21·9	7·1	15·9	0·3
Means of extremes	...	...	67·1	...	47·6	...	12·0	2·7

† On a woollen pad 2 inches above ground.
‡ Mean of 30 days.

67. AJMERE (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	35·6	25th	42·3	28th & 31st	25·0	10·9	20·3	7·1
February	34·9	25th	49·1	1st	24·0	10·7	16 3	5·6
March	47·0	31st	59·2	12th, 15th to 17th	40·2	10·5	17·0	6·1
April	61·0	27th	78·2	9th	51·1	10·4	15·0	3·0
May	74·0	15th & 21st	83·2	5th	60·2	4·9	11·0	0
June	Imperfect.							
July	Not recorded.							
August	72·4†	24th	76·7	15th	57·7	6·0†	10·5	1·5
September	70·2	7th	74·7	25th	61·7	4·7	11·5	0·5
October	54·5	1st	65·7	30th	39·7	8·4	14·5	3·5
November	38·0	13th	51·7	18th	29·7	9·8	12·6	7·6
December	30·5	2nd & 30th	36·7	18th	24·7	9 9	12·6	7·6
Year	?	...	?	...	24·0	?	17·0	0
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 2¼ inches above ground.

68. MOUNT ABU (*corrected*).‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Untrustworthy.							
February	Ditto							
March	38·4†	19th	49·5	16th	28·4	22·2†	33·2	6·2
April	50·8	24th	60·0	6th	35·5	19·9	31·6	7·3
May	58·8	15th	65·6	9th	50·4	10·4	17·7	3·3
June	63·9	27th	68·5	8th	57·9	5·0	15·0	0·2
July	62·4	2nd	67·6	14th	54·1	4·4	17·1	0·8
August	58·5	28th	64·0	31st	52·0	5·8	13·8	1·8
September	57·1	7th	64·9	5th	50·1	8·2	15·9	0·6
October	46·8	4th	57·1	30th	31·7	16·5	25·8	7·8
November	30·7	14th	37·7	15th	19·8	23·9	28·9	18·2
December	26·6	3rd	31·8	18th	20·6	23·1	26·5	18·1
Year	?	...	68·5	...	?	?	33·2	0·2
Means of extremes	...	...	?	...	?	...	?	?

† Mean of 20 days.

‡ On a woollen pad 4 inches above ground.

69. PACHPADRA *corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Untrustworthy.							
February	38·4	25th	50·5	1st	27·3	7·3	17·4	1·5
March	50·9	3rd	62·4	12th	40·4	7·0	14·3	3·3
April	64·5	23rd, 28th & 30th.	71·4	6th	55·5	7·3	13·2	3·2
May	73·1†	17th, 18th, 20th & 21st.	78·3	2nd	66·4	3·0†	8·2	0·3
June	78·9‡	14th	83·6	29th	74·6	2·9‡	10·3	0
July	Not recorded.							
August	Ditto.							
September	Imperfect.							
October	59·8	6th	71·0	30th	46·0	5·7	8·9	1·6
November	42·8	10th & 11th	54·8	18th	34·8	6·0	9·7	0
December	35·1	27th	40·0	16th	30·9	6·1	9·2	3·0
Year	?	...	83·6	...	...	...	...	...
Means of extremes	...	...	?	...	...	...	...	...

* On a woollen pad 3 inches above ground.
† Mean of 22 days.
‡ „ „ 28 „

70. JACOBABAD (*corrected*).§

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	Untrustworthy.							
February	32·2	28th	47·3	1st	20·2	13·0	17·1	9·1
March	48·0	24th	58·4	5th	28·8	10·1	18·5	5·1
April	62·1	26th	69·0	16th	53·4	9·9	15·4	6·4
May	68·6	23rd	82·2	4th	59·4	9·2	14·4	1·7
June	78·0	27th	86·7	12th	72·0	5·9	11·4	2·4
July	78·1	8th	87·5	16th & 17th	72·0	3·5	7·6	0
August	75·5	9th	79·0	29th	70·4	3·4	7·5	1·5
September	71·7‡	3rd	82·6	23rd	59·9	5·2‡	10·3	1·3
October	52·0	1st	65·1	21st	37·0	8·8	13·4	4·7
November	38·8	7th	49·1	14th	31·0	8·6	10·5	6·8
December	33·4	3rd	44·4	5th	29·7	8·5	12·2	5·6
Year	?	...	86·7	...	20·2	?	18·5	0
Means of extremes	...	...	?	...	?	...	?	?

§ On a woollen pad 2·5 inches above ground.

71. HYDERABAD (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	43·6	24th	55·5	28th	32·9	7·1	11·1	0·9
February	42·0	26th	55·5	1st & 13th	30·3	11·0	16·9	6·6
March	53·7†	3rd & 30th	65·4	14th	41·7	9·6†	17·8	4·4
April	65·0‡	23rd	69·6	9th	58·3	7·5‡	14·3	3·3
May	Not recorded.							
June	Ditto.							
July	Ditto.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	Ditto.							
December	Ditto.							
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

* On a woollen pad 3 inches above ground.
† Mean of 30 days.
‡ „ „ 25 „

72. KURRACHEE (*corrected*).§

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	46·1	24th	58·3	27th	28·5	9·0	21·2	2·7
February	45·0	27th	61·2	6th	34·7	11·8	16·6	4·8
March	53·7	3rd	64·6	5th	39·5	11·1	18·5	6·3
April	63·4	26th	72·1	5th & 6th	57·3	9·9	15·1	3·6
May	71·6	27th	80·2	12th	61·1	6·7	12·6	1·1
June	78·1	28th	81·4	29th	76·1	4·2	6·5	1·8
July	76·5	3rd	79·9	15th	73·5	3·2	7·2	0·8
August	73·9	26th & 28th	74·9	9th, 13th, 18th & 19th.	73·2	3·3	5·0	1·8
September				Imperfect.				
October				Ditto.				
November	48·0	8th	62·6	29th	41·2	10·7	14·1	7·5
December	42·1	3rd	49·8	17th	34·7	10·9	17·6	7·3
Year	?	...	81·4	...	28·5	?	21·2	0·8
Means of extremes	...	...	?	...	?	...	?	?

§ On a woollen support 2·5 inches above ground.

73. BHUJ (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	41·5	25th	56·7	28th	30·6	14·6	20·0	3·6
February	41·2	28th	57·2	7th	31·2	15·0	20·3	8·4
March	53·0	4th	63·1	11th & 16th	43·7	12·4	17·6	7·2
April	62·1	23rd	73·9	2nd	53·7	10·9	16·6	4·2
May	71·2†	27th	78·8	6th	58·1	5·0†	13·2	−0·3
June	77·0	26th	82·3	29th	74·5	4·1	5·9	−1·1
July	75·0	28th	76·5	11th	71·2	Imperfect.		
August	71·5	2nd	76·2	26th	67·4	5·1	7·6	2·2
September	68·5	2nd	74·3	29th	62·4	5·8	9·8	1·7
October	60·6	18th	66·7	30th	50·6	11·6	16·5	4·9
November	43·7	10th	62·6	15th	34·4	15·5	19·5	5·3
December	36·2	29th	43·7	17th	30·4	16·2	18·7	10·2
Year	58·5	...	82·3	...	30·4	?	20·3	−1·1
Means of extremes	...	...	67·7	...	50·7	...	?	?

† Mean of 30 days.

74. RAJKOT (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	41·8	25th	60·0	27th	29·6	10·5	13·7	1·3
February	40·9	28th	65·2	1st	28·8	10·5	14·9	3·3
March	52·6	5th	62·2	15th & 16th	44·2	8·5	12·8	4·4
April	61·4	27th	68·5	16th	54·0	8·3	12·6	3·1
May	69·8	26th & 27th	78·8	7th	57·2	4·7	14·6	1·3
June	75·5	1st & 2nd	78·8	18th	71·8	2·7	8·1	1·1
July	74·1	28th	77·1	3rd	67·4	1·3	3·1	0·4
August	71·8	1st	76·4	18th	67·4	2·4	3·9	1·0
September	69·9	5th	73·5	20th	64·9	2·3	5·7	0·7
October	61·9	4th	70·4	31st	45·2	6·1	9·5	2·6
November	43·6	4th	57·5	26th	35·4	11·1	14·2	5·3
December	35·1	29th	42·3	17th & 31st	29·1	12·5	16·0	8·7
Year	58·2	...	78·8	...	28·8	6·7	16·0	0·4
Means of extremes	...	...	67·6		49·6	...	10·8	2·8

* On a woollen pad 2·5 inches above ground.

75. DEESA (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	43·5	25th	56·1	27th	27·6	9·4	13·5	2·9
February	43·6	28th	56·2	1st	32·6	10·0	14·2	6·8
March	53·5	3rd	66·0	12th	42·4	10·0	17·8	6·5
April	63·1†	11th	70·9	4th	57·1	10·0†	16·4	3·6
May	Not recorded.							
June	Ditto.							
July	Imperfect.							
August	70·8	27th	76·5	17th	66·5	5·2	7·6	0·9
September	72·0	1st, 2nd, 4th & 6th.	75·4	28th	67·0	3·2	7·2	0
October	61·6	4th	74·4	30th & 31st	44·9	6·9	13·3	2·4
November	45·3	14th	58·9	28th	38·4	9·6	12·7	5·7
December	41·0	4th	48·2	17th	33·2	7·8	13·2	3·7
Year	?	...	?	...	27·6	?	17·8	0
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad on the ground. † Mean of 24 days.

76. SURAT (*corrected*).‡

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Maximum.	Minimum.
January	48·1	25th	56·3	29th	39·9	9·9	12·6	6·8
February	45·8	28th	53·3	1st	37·5	11·6	15·8	8·7
March	54·7	29th	65·3	12th	45·4	9·4	17·2	6·2
April	63·9	24th	70·3	8th	56·3	8·5	13·7	3·5
May	66·8§	19th	70·3	7th	60·3	10·0§	11·9	5·7
June	Not recorded.							
July	Ditto.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	Ditto.							
December	Ditto.							
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

‡ On a woollen pad 3 inches above ground. § Mean of 25 days.

77. MALEGAON (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	45·4	20th	61·9	28th	27·2	8·0	15·0	0·8
February . .	45·9	25th	50·9	1st	33·2	8·2	10·5	4·6
March . . .	52·5	29th	60·6	12th	37·3	8·5	12·0	4·0
April . . .	61·9	29th	70·4	4th	46·7	9·5	15·5	4·2
May . . .	68·4	27th & 29th	73·7	13th	62·8	6·5	11·5	0·7
June . . .	69·5	14th	73·8	9th & 24th	65·8	3·8	6·8	1·7
July . . .	69·9	15th	72·0	10th	66·5	2·3	5·2	0
August . .	65·1	28th	69·9	13th	59·9	4·5	8·2	0·9
September . .	66·6	25th	69·8	16th	60·6	3·3	8·1	0·2
October . .	63·3	13th	70·4	31st	47·3	4·0	11·2	0
November . .	48·0	3rd	65·5	23rd	37·3	7·2	13·2	3·3
December . .	Imperfect.							
Year . . .	?	...	73·8	...	?	?	15·5	0
Means of extremes	...	...		...	?	...	?	?

* On a woollen pad 3 inches above ground.

78. BOMBAY (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	57·9	26th	63·2	29th	53·4	11·0	13·6	3·2
February . .	58·8	27th	63·4	2nd	51·3	9·0	12·5	3·4
March . . .	63·6	26th	70·0	12th	59·9	8·2	11·8	4·6
April . . .	70·9	21st & 30th	75·2	3rd	64·2	6·7	9·5	4·2
May . . .	75·2	26th	80·0	3rd	71·0	4·9	7·6	3·0
June . . .	76·1	15th	79·2	7th	71·1	2·0	4·6	0·1
July . . .	75·1	2nd	77·6	10th	72·0	1·7	3·6	0·3
August . .	74·0	3rd & 19th	75·6	30th	70·5	3·0	6·2	0·5
September . .	72·9	9th	75·6	21st	68·9	2·4	7·1	0·2
October . .	70·2	6th & 18th	74·0	30th	60·4	5·5	12·4	0·7
November . .	61·7	5th	71·3	29th	53·6	10·1	14·3	5·0
December . .	52·0	15th	57·9	23rd	46·2	14·4	20·9	8·8
Year . . .	67·4	...	80·0	...	46·2	6·6	20·9	0·1
Means of extremes	...	...	71·9	...	61·9	...	10·3	2·8

† On a woollen pad 2 inches above ground.

79. POONA (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	41·4	26th	52·4	28th	32·3	12·6	15·5	8·6
February . .	43·5	24th	48·9	1st	26·6	13·6	17·0	11·0
March . . .	49·2	19th	55·6	12th	37·3	12·9	16·7	8·4
April . . .	58·1	13th	70·3	5th	47·0	11·3	15·2	6·1
May . . .	62·6	30th	72·3	6th	49·3	9·3	21·8	2·5
June . . .	68·4	14th	71·3	17th	64·8	3·3	6·6	0·4
July . . .	66·9†	15th & 16th	69 8	4th	61·4	3·4†	8·2	0·6
August . .	Imperfect.							
September . .	63·8	2nd & 27th	67·8	17th	56·3	4·0	8·5	1·5
October . .	61·1	18th	69·0	29th	45·6	5·7	11·4	1·7
November . .	47·1	3rd	66·0	29th	34·8	9·9	13·4	3·9
December . .	36·0	15th & 16th	45·1	18th	31·0	11·5	14·1	7·0
Year . . .	?	...	72·3	...	26 6	?	21·8	0·4
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 2·5 inches above ground. † Mean of 23 days.

80. SHOLAPUR (*corrected*).‡

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	Not recorded.							
February . .	Ditto.							
March . . .	Ditto.							
April . . .	Ditto.							
May . . .	Ditto.							
June . . .	Ditto.							
July . . .	Ditto.							
August . .	Ditto.							
September . .	Ditto.							
October . .	Ditto.							
November . .	43·6	7th	57·0	29th	33·6	23·9	34·9	10·7
December . .	38·8	15th	53·3	27th	28·7	16·8	36·9	6·1
Year . . .	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	..

‡ On a woollen pad 2 inches above ground.

81. RATNAGIRI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	56·0	26th	65·2	28th	49·3	10·1	14·6	3·2
February	57·5	25th	61·9	1st	47·4	9·9	14·8	7·7
March	63·3	3rd	68·5	12th	56·1	7·9	12·3	3·5
April	70·3	12th	76·3	5th	60·3	6·8	10·6	3·1
May	74·5	29th	80·1	3rd	69·9	5·5	9·3	2·2
June	74·1	16th	77·7	7th	70·5	1·9	5·1	0·6
July	73·4	5th	76·3	1st	70·5	2·0	3·8	0·3
August	71·9	1st	74·7	25th	68·8	3·1	6·8	0·4
September	70·7	8th	74·5	22nd	66·3	2·8	6·4	0·9
October	69·0	12th	72·9	29th	56·5	4·3	10·1	0·6
November	60·0	6th	71·5	28th	49·1	8·5	12·7	3·5
December	53·6	15th	64·9	4th	48·6	10·2	15·1	6·3
Year	66·2	...	80·1	...	47·4	6·1	15·1	0·3
Means of extremes	...	...	72·0	...	59·4	...	10·1	2·7

* On a woollen pad 3 inches above ground.

82. BELGAUM (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	45·6	20th	51·3	1st	39·5	11·2	16·2	7·4
February	48·0	9th	55·2	20th	39·8	12·2	19·4	4·7
March	53·5	18th	57·5	12th	47·6	9·7	14·1	4·8
April	58·7	29th	64·1	5th	51·4	8·4	14·6	5·0
May	64·2	12th	70·1	22nd	58·7	4·9	7·8	0
June	66·3	3rd	69·6	7th	63·6	1·5	3·9	0·3
July	65·7	21st	67·0	31st	62·6	·0·7	4·0	—1·3
August	64·1	10th	68·0	11th	61·1	1·8	4·2	0
September	61·9	28th	66·6	23rd	55·8	2·6	5·5	0·2
October	61·4	18th	66·8	29th	52·0	3·5	8·3	0·3
November	50·1	2nd & 3rd	65·6	29th	35·1	8·7	17·3	0·7
December	42·3	15th	59·6	7th	33·8	12·3	17·3	5·2
Year	56·8	...	70·1	...	33 8	6·5	19·4	—1·3
Means of extremes	...	...	63·5	...	50·1	...	11·1	2·3

† On a woollen pad of country blanket on the ground.

83. KARWAR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	62·1	31st	65·8	5th	58·4	3·4	6·3	1·1
February	63·6	14th & 26th	67·2	20th & 25th	59·4	3·1	11·3	0·6
March	67·3	27th	73·3	24th	60·4	4·3	12·4	1·6
April	72·2	29th	78·0	4th & 6th	65·3	4·6	9·6	1·7
May	75·4	16th	80·0	30th	69·1	3·5	8·1	1·7
June	70·1	3rd	74·1	10th	67·2	3·7	8·0	0
July	69·8	2nd, 4th & 5th.	73·1	12th, 15th & 17th.	67·2	4·1	6·0	1·9
August	69·4	19th	71·6	22nd, 24th, 25th & 30th.	67·2	4·4	5·7	2·5
September	67·5	9th	71·1	24th	64·4	4·7	5·6	3·7
October	66 9	5th	70·1	29th	59·4	5·1	6·5	4·3
November	61·1	2nd	69·1	30th	52·4	5·8	11·2	3·6
December	58·7	14th & 15th	67·2	6th	51·4	4·8	9·0	2·6
Year	67·0	...	80·0	...	51·4	4·3	12·4	0
Means of extremes	...	...	71·7	...	61·8	...	8·3	2·1

* On a woollen pad 3·5 inches above ground.

84. VIZAGAPATAM.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	58·3	28th	68·9	4th	51·5	12·8	17·1	7·4
February	62·9	28th	67·7	19th	58·9	12·0	15·3	9·6
March	70·0	4th & 8th	77·4	12th	65·1	10·4	14·5	3·6
April	75·3	26th	80·2	30th	70·6	8·2	14·6	3·3
May	80·1	15th	85·9	2nd	72·4	6·2	12·4	0·6
June	79·1	6th	83·9	28th	74·7	6·1	10·8	2·9
July	76·4	20th	82·4	27th	69·4	6·7	12·4	0·6
August	76·3	9th	82·9	10th	72·3	7·7	11·9	2·6
September	75·4	25th	78·6	13th	71·7	7·3	11·3	4·1
October	73·2	5th & 6th	75·9	27th	69·5	8·2	11·0	6·1
November	61·2	5th	73·9	23rd	51·4	11·9	16·6	4·9
December	56·5	4th	68·7	27th	48·1	13·2	21 9	5·1
Year	70·4	...	85·9	...	48·1	9·2	21·9	0·6
Means of extremes	...	...	77 2	...	64·6	...	14·2	4·2

85. MASULIPATAM (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	62·6	29th	70·1	15th	59·2	3·9	7·6	1·4
February . .	62·1	3rd	66·8	13th	55·8	4·9	8·0	2·7
March . .	69·1	5th	76·0	25th	62·0	4·8	6·2	2·0
April . .	73·6	28th	79·2	12th	68·6	3·7	8·5	1·4
May . .	80·4	25th	86·2	8th	73·8	2·2	4·9	0
June . .	78·5	11th & 14th	84·0	23rd	71·8	1·0	5·0	2·0
July . .	74·8	17th	79·0	7th	71·9	2·2	3·5	1·1
August . .	76·4	7th	79·1	24th	71·9	1·6	3·4	0
September . .	75·1	16th	79·1	24th & 29th	72·9	2·2	4·5	0·6
October . .	73·3	4th & 5th	75·9	23rd	69·9	2·6	4·1	0·2
November . .	65·2	1st	73·7	24th	58·9	4·1	6·7	0
December . .	60·5	13th	67·7	22nd	53·2	3·4	5·7	1·0
Year . . .	71·0	..	86·2	...	53·2	3·1	8·5	2·0
Means of extremes	...	...	76·4	...	65·8	...	5·7	0·7

86. SECUNDERABAD.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	54·7	26th & 31st	62·2	4th	49·1	5·1	7·8	1·7
February . .	59·4	28th	64·4	19th	53·8	5·3	8·9	2·3
March . .	65·9	19th	70·2	17th	60·0	3·7	6·9	0·1
April . .	71·5	26th	76·6	4th	64·4	4·6	7·6	0·6
May . .	78·6	24th	83·8	30th	69·6	2·6	5·2	0·8
June . .	72·5	2nd	77·9	8th	68·9	1·1	2·2	0·1
July . .	69·3	5th	71·1	3rd	66·6	2·1	4·1	1·0
August . .	69·3	9th	73·2	24th	66·2	2·4	5·4	0·5
September . .	68·5	16th	71·4	13th	64·8	1·7	4·6	0
October . .	65·8	10th	70·0	28th	54·2	3·6	7·9	1·1
November . .	52·2	1st	69·0	29th	40·7	6·6	10·2	0·3
December . .	44·9	11th	57·0	27th	36·7	9·2	14·6	5·1
Year . . .	64·4	..	83·8	...	36·7	4·0	14·6	0
Means of extremes	...	...	70·6	...	57·9	...	7·1	1·1

87. BELLARY.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	56·2	23rd	65·4	5th	49·1	4·5	6·4	1·9
February . .	58·5	27th	65·3	12th	52·9	5·3	13·1	2·3
March . .	68·8	28th	74·9	25th	62·9	4·1	9·6	1·2
April . .	75·2	16th	81·3	11th	68·0	2·7	4·8	0·1
May . .	76·4	2nd	80·6	3rd	63·8	2·3	9·8	0
June . .	74·5	2nd & 3rd	77·0	6th	71·6	2·0	5·0	0·2
July . .	72·7	4th	74·5	3rd	69·9	1·8	3·7	0
August . .	72·2	9th	77·9	18th & 19th	69·4	1·7	4·9	0
September . .	70·6	7th	73·9	24th	65·9	2·2	6·3	0
October . .	69·3	10th	73·9	24th	65·1	1·9	5·5	—2·7
November . .	58·7	1st	71·5	28th	48·3	4·0	7·6	—1·9
December . .	51·6*	14th	65·7	7th & 29th	45·5	6·4*	10·5	—1·3
Year . . .	67·1	...	81·3	...	45·5	3·2	13·1	—2·7
Means of extremes	...	...	73·5	...	61·0	...	7·3	0·2

88. MANGALORE (*corrected*).†

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	61·5	31st	66·7	5th	52·8	7·8	12·7	3·5
February . .	65·7	17th	69·6	11th	59·4	6·8	17·4	4·7
March . .	71·9	30th	75·7	12th	66·3	3·8	7·4	1·3
April . .	76·1	16th	80·5	26th	69·6	1·6	4·8	0
May . .	74·8	20th	79·1	1st	70·1	4·1	7·4	1·3
June . .	72·0	13th	74·6	2nd	69·6	2·8	5·4	0·9
July . .	71·2	5th	74·9	10th & 14th	68·5	2·7	5·0	0
August . .	73·0	10th	76·1	27th	70·1	1·6	3·7	0
September . .	70·4	9th	73·6	28th	67·5	3·6	6·6	0·4
October . .	69·7	20th	71·6	27th	67·7	4·1	7·0	1·1
November . .	66·6	7th	74·6	27th	60·7	4·9	9·6	1·7
December . .	62·9	17th	69·2	29th	57·4	5·5	9·5	1·7
Year . . .	69·7	...	80·5	...	52·8	4·1	17·4	0
Means of extremes	...	...	73·9	...	65·0	...	8·0	1·4

* Mean of 29 days.

† On a woollen pad.

89. MERCARA (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	46·6	1st	55·4	27th	39·5	8·9	12·7	2·4
February . .	45·4	5th	54·5	11th	37·0	11·4	14·8	5·1
March . . .	53·0	5th	60·1	1st	46·9	8·4	12·2	2·9
April . . .	56·9	25th	64·0	6th	47·9	6·9	12·7	1·8
May . . .	60·1*	13th	67·1	30th	54·4	5·1*	8·2	0·7
June . . .	61·8	3rd	63·7	1st	56·6	1·9	8·2	0·1
July . . .	62·0	2nd & 7th	64·0	22nd & 31st	59·4	0·7	3·4	0·1
August . .	61·4	28th & 29th	64·0	1st	56·9	1·7	6·3	0·1
September . .	57·7	6th	62·7	25th	43·9	3·6	11·9	0·2
October . .	57·6	12th	63·5	25th	49·1	4·6	11·0	0·1
November . .	50·6	9th	62·5	30th	38·2	8·2	15·9	0·3
December . .	46·8	15th	58·4	1st	34·5	8·7	15·8	0
Year . . .	55·0	...	67·1	...	34·5	5·8	15·9	0
Means of extremes	...	...	61·7	...	47·0	...	11·1	1·2

* Mean of 30 days.

90. BANGALORE.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	51·6	31st	59·0	13th	46·8	2·3	4·3	1·6
February . .	56·1	3rd	61·6	11th	51·5	2·1	3·5	1·2
March . . .	63·1	14th	65·9	26th	58·8	2·4	3·2	1·5
April . . .	65·3	4th	66·8	28th	62·2	3·7	5·3	1·7
May . . .	65·0	19th	67·6	20th	60·7	2·9	4·4	1·8
June . . .	63·7	2nd	65·4	12th	60·7	2·1	3·4	0·8
July . . .	61·7	4th	64·4	10th & 29th	58·8	2·7	4·2	1·5
August . .	60·8	6th	62·9	11th	57·3	3·6	5·7	1·9
September . .	59·7	28th	64·2	22nd	57·4	2·9	4·7	1·5
October . .	59·7	22nd	62·2	17th	57·5	2·8	4·9	1·1
November . .	55·4	8th	61·8	26th	49·6	2·1	3·0	1·2
December . .	50·7	16th	57·9	29th	45·9	2·8	5·3	1·9
Year . . .	59·4	...	67·6	...	45·9	2·7	5·7	0·8
Means of extremes	...	...	63·3	...	55·6	...	4·3	1·5

91. MADRAS.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	64·6	20th	71·8	8th	58·7	3·5	5·5	1·0
February . .	62·6	3rd	72·5	12th	57·5	4·7	6·6	2·5
March . . .	69·4	14th	75·4	1st	64·1	4·0	9·1	1·2
April . . .	74·5	30th	82·0	10th	68·2	2·4	4·3	0·7
May . . .	80·3	17th, 25th & 26th.	82·6	8th	77·0	1·4	2·5	0·7
June . . .	78·4	7th	83·0	4th	73·5	1·8	6·8	0·3
July . . .	75·7	1st	78·7	18th	71·9	1·8	3·5	0·5
August . .	76·1	11th	78·5	22nd	73·1	1·7	5·6	0·2
September . .	76·1	6th	80·7	30th	71·7	1·8	4·3	0·5
October . .	72·7	2nd	77·0	23rd & 26th	70·5	1·8	5·3	0·1
November . .	68·7	5th	74·6	13th & 14th	61·4	2·2	4·8	0·7
December . .	65·8	16th	72·6	6th	56·5	2·7	6·9	0·3
Year . . .	72·1	...	83·0	...	56·5	2·5	9·1	0·1
Means of extremes	...	...	77·5	...	67·0	...	5·4	0·7

92. SALEM.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	59·3	28th & 30th	62·8	6th & 8th	54·7	4·9	7·4	2·2
February . .	58·3	5th	67·8	16th	52·7	5·5	8·3	2·5
March . . .	66·8	31st	71·8	26th	58·8	4·1	6·9	1·8
April . . .	73·1	25th	76·4	2nd	68·3	2·9	6·2	0·7
May . . .	72·3	17th	76·8	20th	66·0	2·7	6·4	1·6
June . . .	71·0	3rd	74·9	5th & 26th	68·7	1·9	2·6	0·6
July . . .	69·5	6th	71·6	26th	67·9	2·2	3·0	1·6
August . .	69·1	5th	71·5	15th	67·1	2·2	3·0	1·7
September . .	68·3	28th	71·7	4th	64·5	2·4	4·3	1·0
October . .	67·3	2nd & 10th	69·8	24th	63·2	2·3	3·8	1·8
November . .	63·4	1st	68·1	23rd	58·1	2·8	4·5	1·8
December . .	59·3	16th	68·1	29th	50·6	3·9	10·2	2·0
Year . . .	66·5	...	76·8	...	50·6	3·2	10·2	0·6
Means of extremes	...	...	70·9	...	61·7	...	5·6	1·6

93. WELLINGTON.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	37·9	30th	50·2	5th	27·6	9·3	13·8	0·3
February . .	34·6	4th	49·7	12th	21·6	11·8	17·0	4·0
March . . .	44·6	13th	54·1	11th	37·3	9·1	13·8	1·0
April . . .	50·4§	19th	57·4	13th	44·5	6·8§	10·4	1·8
May . . .	53·7	17th	63·2	2nd	48·2	5·3	8·8	0
June . . .	54·3	9th	58·0	17th	46·8	4·5	9·1	1·7
July . . .	55·3*	7th	59·0	6th	48·9	3·5*	6·9	0·7
August . .	53·8	18th	58·2	12th	46·0	4·5	9·8	1·6
September . .	49·3	9th	57·3	26th	44·8	5·3	11·6	1·4
October . .	52·4	6th	57·4	24th & 25th	46·5	2·7	6·0	0
November . .	42·6	6th	56·4	26th	28·1	7·3	13·8	0·8
December . .	43·5†	13th	54·9	29th	28·9	5·1†	11·5	0
Year . . .	47·7	...	63·2	...	21·6	6·3	17·0	0
Means of extremes	...	...	56·3	...	39·1	...	11·0	1·0

94. COIMBATORE.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	59·6	31st	68·5	13th	52·3	5·3	9·8	1·5
February . .	57·0	5th	67·6	12th	50·5	7·6	12·6	2·5
March . . .	65·8	29th	69·5	22nd	60·0	4·6	8·7	0
April . . .	70·7	18th	75·9	2nd	64·5	3·2	6·0	0·3
May . . .	71·5*	5th & 26th	74·6	11th	65·6	2·0*	4·3	0
June . . .	70·5‡	12th	72·7	18th	67·8	1·5‡	4·1	0·2
July . . .	69·6§	8th	73·1	18th	66·5	1·1§	2·2	0
August . .	67·8	1st & 15th	71·7	27th	64·0	1·7	3·0	0·4
September . .	66·9	19th & 30th	69·2	25th	62·2	2·6	4·2	0·7
October . .	67·2	5th	70·6	8th	61·6	3·0	4·7	1·6
November . .	63·4	19th	69·6	30th	53·6	4·0	7·1	1·7
December . .	59·2	16th	69·9	29th	45·6	5·3	9·1	1·5
Year . . .	65·8	...	75·9	...	45·6	3·5	12·6	0
Means of extremes	...	...	71·1	...	59·5	...	6·3	0·9

* Mean of 30 days. ‡ Mean of 27 days.
† „ „ 28 „ § „ „ 29 „

95. TRICHINOPOLY (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	65·2	23rd	68·8	6th	60·0	3·6	5·8	1·3
February . .	63·9	5th	71·4	21st	60·0	2·9	4·7	0·5
March . .	69·9	14th	76·9	10th	65·8	3·2	6·2	0·9
April . . .	74·2	29th	80·3	12th	68·6	3·3	7·3	1·1
May . . .	77·7	25th	82·3	1st	72·0	1·6	4·4	0
June . . .	77·0	14th	79·3	23rd	72·9	1·4	2·6	0·5
July . . .	76·4	7th	79·9	13th	73·5	1·6	4·1	0
August . .	74·8	1st	77·2	13th	70·9	1·8	5·4	0·8
September . .	74·3	14th	76·6	29th & 30th	72·4	1·2	2·5	0·1
October . .	72·3	10th	75·2	29th	69·5	1·0	2·3	0
November . .	68·3	7th	73·7	25 h	62·3	2·1	4·4	0·2
December . .	65·9	14th & 15th	71·6	29th	55·6	2·2	4·1	0·5
Year . . .	71·7	...	82·3	...	55·6	2·2	7·3	0
Means of extremes	...	...	76·1	...	67·0	...	4·5	0·5

96. NEGAPATAM (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January . .	68·7	1st	72·6	6th	65·6	2·8	6·8	0·1
February . .	66·9	4th	74·2	21st	62·2	4·3	9·5	1·0
March . .	70·1	29th	76·6	26th	64·5	4·5	7·2	2·0
April . . .	74·5	30th	79·2	3rd	69·1	4·3	6·0	2·9
May . . .	77·3	18th & 23rd	80·9	10th	70·6	2·8	5·4	0·9
June . . .	74·3	4th	78·3	21st	71·3	3·6	6·7	0·3
July . . .	73·1	20th	77·4	25th	70·0	4·3	7·0	0·8
August . .	73·6	9th	75·3	26th	68·6	3·5	6·0	0·7
September . .	72·1	22nd & 24th	74·6	6th	63·5	4·2	14·3	0·1
October . .	72·1	19th	75·1	2nd	65·8	2·5	12·3	0
November . .	69·8	1st|& 7th	73·2	14th	64·5	2·2	6·9	−1·0
December . .	67·9*	17th	73·0	29th	61·6	2·0*	6·8	0
Year . . .	71·7	...	80·9	...	61·6	3·4	14·3	−1·0
Means of extremes	...	...	75·9	...	66·4	...	7·9	0·7

* Mean of 30 days.

97. MADURA.

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	64·7	31st	67·8	8th	61·5	4·1	6·3	3·1
February	64·7	2nd	67·5	17th	60·5	4·0	7·7	0·9
March	68·9	7th	72·2	1st	62·4	4·3	6·2	2·5
April	70·3	10th & 14th	71·4	2nd	68·0	5·4	7·3	3·0
May	71·5	4th	73·4	10th	69·4	5·5	8·4	3·2
June	73·4	11th	75·5	8th	70·6	3·8	7·7	1·6
July	72·3	9th & 19th	73·2	31st	69·9	2·8	6·0	0·7
August	73·3	2nd & 5th	74·8	13th	70·6	1·9	3·2	−1·3
September	71·3	2nd	74·4	16th	67·5	2·9	5·8	1·2
October	70·0	2nd	71·6	25th	67·8	2·4	4·1	1·4
November	67·3	7th, 8th & 15th.	70·5	30th	60·5	3·2	5·8	2·0
December	63·4	16th	67·6	25th	57·4	4·7	7·6	2·1
Year	69·3	...	75·5	...	57·4	3·8	8·4	−1·3
Means of extremes	...	...	71·7	...	65·5	...	6·3	1·7

98. COCHIN (*corrected*).

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	67·7	26th	73·1	5th	61·9	4·3	6·4	0
February	69·2	4th	74·4	12th	62·5	3·5	5·9	1·0
March	74·2	30th	76·6	14th	71·5	2·8	4·4	0·2
April	76·0	15th	81·5	18th	69·8	2·0	4·1	0·6
May	Not recorded.							
June	Ditto.							
July	Ditto.							
August	Ditto.							
September	Ditto.							
October	Ditto.							
November	Ditto.							
December	Ditto.							
Year	...	...	...	...	...	...	...	...
Means of extremes	...	...	...	...	...	...	...	...

99. AKYAB (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	52·4	7th	58·0	31st	44·0	7·2	9·0	5·9
February	50·3	24th	60·0	5th & 17th	41·0	8·3	14·1	5·4
March	63·1	27th	71·4	17th	55·0	6·0	8·1	1·2
April	69·0†	26th	73·1	24th	64·9	5·4†	8·3	0·8
May	73·4	8th	78·9	10th, 11th & 22nd.	66·8	4·0	10·5	0·3
June	75·8‡	16th & 17th	78·9	30th	73·3	2·0‡	4·1	0·5
July	75·7	1st & 12th	77·3	11th	72·0	1·9	8·1	0·5
August	75·1	3rd & 6th	77·3	14th	72·1	1·9	4·5	0
September	74·7	11th	76·8	28th	70·8	3·1	7·3	1·3
October	72·4	5th & 7th	76·3	22nd	69·1	4·5	8·3	1·7
November	64·0§	15th	72·6	19th	53·1	6·3§	13·5	2·7
December	59·0	7th	72·2	24th & 25th	48·6	6·0	9·0	1·9
Year	67·1	...	78·9	...	41·0	4·7	14·1	0
Means of extremes	...	...	72·7	...	60·9	...	8·7	1·9

100. THAYETMYO (*corrected*).‖

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.		Mean.	Maximum.	Minimum.
January	50·3	26th	58·5	24th	46·1	Imperfect.		
February	50·2	28th	58·7	9th	39·6	Ditto.		
March	62·2	25th	70·6	17th	56·5	3·7	11·7	1·2
April	73·2¶	15th	78·5	1st	65·7	3·1¶	8·7	0·4
May	75·0¶	11th	79·0	10th	69·0	2·5¶	4·6	0
June	75·2¶	24th	76·9	16th	74·1	0·9¶	2·6	0
July	74·9	13th	76·5	30th	71·6	1·5	5·1	0
August	75·0	21st	76·4	31st	73·0	1·8	4·0	0·7
September	73·8	2nd, 24th & 27th.	75·6	22nd	71·0	1·9	4·3	0·3
October	71·1	7th	74·6	24th, 25th & 31st.	68·1	3·1	5·3	1·3
November	63·8	15th	72·6	21st	51·7	4·5	8·5	0·7
December	55·6	9th	68·6	21st	44·6	5·2	8·4	1·1
Year	66·7	...	79·0	...	39·6	...	...	...
Means of extremes	...	...	72·2	...	60·9	...	...	...

* On a woollen pad 2½ inches above ground.
† Mean of 29 days.
‡ ,, ,, 28 ,,
§ ,, ,, 27 ,,

‖ On a woollen pad 4 inches above ground.
¶ Mean of 24 days.

101. TOUNGOO (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	50·1	31st	52·7	7th to 10th, 25th, 26th & 28th.	48·6	5·8	8·5	2·4
February	51·8	25th	58·7	6th	42·5	6·7	12·5	4·3
March	58·0	3rd, 5th, 7th, &c.	58·7	1st	55·7	6·6	9·5	3·5
April	56·0	25th to 28th & 30th.	58·7	10th to 13th	52·7	?	?	?
May	59·2	11th, 13th to 21st.	59·7	3rd	57·7	?	?	?
June	66·7	22nd	71·6	1st	59·7	6·7	10·5	2·6
July	70·3	30th & 31st	72·6	1st	67·6	4·2	8·6	2·6
August	71·8	7th, 21st & 22nd.	73·6	12th, 13th, 16th, 25th, 26th, 28th & 29th.	70·6	2·7	3·6	2·6
September	71·7	21st	73·6	1st to 3rd, 9th, 12th, 14th, 24th & 27th.	70·6	2·9	3·6	2·6
October	71·8	12th	74·6	15th	69·6	2·9	4·6	2·6
November	67·3	7th	71·6	23rd	59·7	3·2	5·5	2·5
December	58·1	3rd	66·6	21st & 26th	50·7	4·9	7·5	3·4
Year	62·7	...	74·6	...	42·5	...	...	...
Means of extremes	...	...	66·1	...	58·8	...	...	...

102. BASSEIN (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	Not recorded.							
February	55·8†	20th	65·3	7th	47·8	7·9†	15·3	3·3
March	63·1	8th	67·3	18th	56·3	7·0	10·9	4·9
April	69·2	30th	72·3	2nd	62·8	5·3	7·9	2·4
May	73·3	21st	75·8	1st & 11th	70·3	3·9	6·9	1·9
June	Imperfect.							
July	Not recorded.							
August	73·8	12th	76·3	14th, 19th, 28th, 29th & 31st.	72·3	2·5	3·5	1·4
September	72·6	17th	74·3	7th & 26th	70·8	Imperfect.		
October	71·8	4th	74·8	15th	68·8	Not recorded.		
November	65·8	29th	69·8	23rd	58·8	Ditto.		
December	61·8	16th	68·8	26th	50·8	5·5‡	7·7	2·6
Year	?	...	?	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad. † Mean of 25 days. ‡ „ „ 23 „

103. RANGOON (*corrected*).*

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	Not recorded.							
February	56·7†	28th	64·6	6th	43·3	8·2‡	13·5	0·2
March	63·3	11th	69·6	18th	55·7	7·9	11·7	4·8
April	69·0	6th	75·7	2nd	63·7	6·3	9·1	1·3
May	73·6	23rd & 31st	76·7	11th	69·0	3·9	6·2	0·6
June	74·4‡	2nd	77·0	5th	72·3	1·8‡	4·0	0
July	73·9	17th	75·6	19th	72·2	1·9	4·4	0·4
August	74·9§	8th	77·6	29th	72·1	1·8§	3·2	0·1
September	72·5	17th	75·6	1st	70·7	2·8	5·4	...
October	71·6	4th	75·9	18th	68·8	4·6	6·5	0·9
November	68·3	14th	77·3	21st	62·0	5·1	12·1	0·6
December	61·2	4th	67·1	26th	54·5	6·7	10·4	4·3
Year	?	...	77·6	...	?	?	13·5	0
Means of extremes	...	...	?	...	?	...	?	?

104. MOULMEIN (*corrected*).‖

Month.	Mean.	Maximum. Day.	Maximum. °	Minimum. Day.	Minimum. °	Difference, shade and radiation. Mean.	Difference, shade and radiation. Maximum.	Difference, shade and radiation. Minimum.
January	53·5	31st	59·3	7th	43·1	9·2	13·0	6·0
February	59·9	28th	66·3	7th	52·4	7·8	9·9	6·1
March	64·0	10th	68·4	20th	59·5	8·1	13·4	5·6
April	67·4¶	17th & 30th	70·5	9th	64·5	7·9¶	10·0	5·7
May	67·7	8th & 13th	70·5	24th	62·3	7·1	11·5	4·4
June	66·7	1st	70·4	11th & 14th	63·3	7·5	11·6	5·1
July	66·0	30th	69·5	14th	59·8	7·7	13·4	4·7
August	72·7	7th	75·2	3rd	68·3	1·4	6·5	...
September	73·0	28th	75·1	13th	70·9	0·5	2·1	...
October	72·1†	3rd	75·4	13th	68·3	2·4†	4·5	...
November	Not recorded.							
December	Ditto.							
Year	?	...	?	...	?	?	13·4	...
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 3 inches above ground.
† Mean of 26 days.
‡ „ „ 29 „
§ „ „ 30 „
‖ On a woollen pad.
¶ Mean of 28 days.

105. MERGUI (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	65·6	31st	72·3	7th	50·5	3·2	10·3	0·6
February	72·0	4th	73·4	15th & 21st	70·4	0·7	1·4	0·5
March	70·5	1st	72·9	26th, 27th & 29th	65·3	2·1	8·9	0·6
April	69·1	30th	73·2	24th & 27th	66·3	4·0	7·7	1·7
May	72·2	9th	74·2	22nd	69·3	1·9	4·7	0·8
June	71·5	1st	73·2	28th	69·3	1·3	2·3	0·7
July	71·0	28th	72·4	14th	68·8	1·3	2·3	0·7
August	71·1	7th	72·7	25th	69·3	1·4	2·6	0·4
September	70·5	30th	71·6	13th	68·6	1·5	2·2	0·5
October	70·2	4th	72·2	30th	66·3	1·6	2·6	0·5
November	Imperfect.							
December	Not recorded.							
Year	?	...	74·2	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

106. PORT BLAIR (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	69·2	21st	72·4	24th & 31st	64·3	6·0	8·6	0·7
February	65·6	3rd	72·4	17th	59·5	7·7	10·1	5·6
March	66·2	1st	70·4	15th & 19th	63·3	8·2	10·1	6·6
April	70·0	6th	74·0	1st, 4th & 5th	66·3	7·5	9·6	4·7
May	71·8	5th	77·4	26th	67·8	6·4	9·2	1·5
June	71·8	7th	74·7	3rd & 25th	68·3	6·1	9·3	3·5
July	70·9	8th & 26th	73·4	17th	68·0	5·9	9·4	3·7
August	70·7	26th	73·9	17th, 22nd, 24th & 30th	68·3	6·1	9·3	4·0
September	70·8	7th	73·9	24th	67·3	5·0	7·1	1·7
October	71·0	15th	74·4	11th, 21st & 31st	69·4	6·1	7·9	3·0
November	Imperfect.							
December	Not recorded.							
Year	?	...	77·4	...	?	?	?	?
Means of extremes	...	...	?	...	?	...	?	?

* On a woollen pad 2 inches above ground.

107. NANCOWRY (*corrected*).*

Month.	Mean.	Maximum.		Minimum.		Difference, shade and radiation.		
		Day.	°	Day.	°	Mean.	Maximum.	Minimum.
January	72·2	29th	74·2	1st	68·2	5·2	7·1	3·6
February	70·7	3rd & 27th	74·2	17th	63·2	6·2	10·1	4·1
March	73·6	15th	76·0	9th	71·0	4·1	5·6	2·0
April	75·3†	23rd	77·2	12th	73·0	3·9†	5·3	2·6
May	75·8	13th	77·2	6th	73·4	3·8	5·9	2·0
June	75·2	7th & 9th	78·2	23rd	71·7	3·3	5·1	1·6
July	75·7	23rd & 26th	80·2	3rd	69·2	Dry minimum untrustworthy.		
August	76·4	1st, 6th, 7th, 14th & 25th	78·2	3rd & 27th	74·2	Ditto.		
September	75·2	5th	78·2	24th	72·2	Ditto.		
October	74·8	7th, 9th & 13th	76·2	1st & 31st	73·2	Ditto.		
November	73·9	2nd, 3rd, 13th & 27th	75·2	8th, 9th & 17th	72·2	Ditto.		
December	73·7	15th & 16th	75·2	5th, 28th & 29th	72·2	.....		
Year	74·4	...	80·2	...	63·2	?	?	?
Means of extremes	...	...	76·7	...	71·1	...	?	?

* On a woollen pad 2 inches above ground. † Mean of 29 days.

TABLE IV.—TEMPERATURES OF THE GROUND IN 1883 (4 STATIONS).

1. CALCUTTA (ALIPORE).

Month.	Surface.			1 foot deep (old).			1 foot deep (new).			3 feet deep.			Mean.			
	5½ hours.	13½ hours.	21½ hours.	5½ hours.	13½ hours.	21½ hours.	5½ hours.	13½ hours.	21½ hours.	5½ hours.	13½ hours.	21½ hours.	Surface.	1 foot old.	1 foot new.	3 feet.
January	58·3	74·0	62·2	67·0	67·5	67·6	...	...	...	71·9	72·5	72·2	64·8	67·4	...	72·2
February	62·5	78·9	66·5	69·6	69·8	70·3	...	...	...	72·7	72·9	72·8	69·3	69·9	...	72·8
March	72·1	97·1	76·5	76·9	77·0	77·9	77·6	77·1	78·8	77·2	77·3	77·4	81·9	77·3	77·8	77·3
April	79·0	109·9	82·9	85·0	85·4	86·5	86·1	85·5	87·4	83·7	83·9	83·9	90·6	85·6	86·3	83·8
May	82·9	110·9	86·1	88·7	89·0	90·4	89·4	89·1	91·4	87·0	87·1	87·1	93·3	89·4	90·0	87·1
June	82·2	97·0	83·8	87·3	87·5	88·2	87·7	87·4	88·7	87·8	87·7	87·7	87·7	87·7	87·9	87·7
July	81·5	95·0	83·4	86·0	85·9	86·4	86·1	85·6	86·6	86·2	86·3	86·3	86·6	86·1	86·1	86·3
August	81·8	94·7	84·0	85·9	85·8	86·2	86·0	85·6	86·5	86·3	86·3	86·3	86·8	86·0	86·0	86·3
September	81·4	96·6	83·3	86·2	86·2	86·7	86·3	85·9	86·8	86·6	86·5	86·6	87·1	86·4	86·3	86·6
October	76·1	96·0	78·9	83·8	83·9	84·2	84·0	83·6	84·4	85·7	85·8	85·8	83·7	84·0	84·0	85·8
November	62·3	83·3	65·6	74·7	75·0	75·3	75·4	75·0	75·9	79·9	80·7	80·5	70·4	75·0	75·4	80·4
December	55·4	72·0	58·9	66·1	66·4	66·8	66·9	66·3	67·2	73·1	73·6	73·4	62·1	66·4	66·8	73·4
Year	73·0	92·1	76·0	79·8	80·0	80·5	?	?	?	81·5	81·7	81·7	80·4	80·2	?	81·6

2. ALLAHABAD.

Month.	Surface.				1 foot deep.				3 feet deep.				Mean.		
	4 hours.	10 hours.	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.	½ inch.	1 foot.	3 feet.
January	56·2	63·8	70·3	60·1	64·8	64·1	64·6	65·6	69·9	69·8	69·9	69·9	62·2	64·8	69·9
February	55·5	64·6	72·0	60·3	64·3	63·5	64·2	65·4	68·1	68·0	68·2	68·2	62·7	64·4	68·1
March	65·9	79·8	86·2	72·3	74·7	73·7	74·7	76·3	73·9	73·9	74·1	74·1	75·6	74·8	74·0
April	77·0	101·8	102·9	84·3	86·1	85·3	86·3	87·7	81·9	81·9	82·1	82·1	91·5	86·4	82·0
May	83·2	106·9	106·5	89·8	92·8	91·8	92·6	93·8	88·0	88·0	88·1	88·0	96·6	92·8	88·0
June	85·5	98·8	98·4	89·1	91·7	90·9	91·8	92·4	89·4	89·2	89·4	89·4	93·0	91·7	79·4
July	83·3	88·3	90·5	85·5	87·4	86·8	87·0	87·6	87·4	87·3	87·4	87·3	86·9	87·2	87·4
August	83·6	90·3	93·6	86·3	88·1	87·7	88·0	88·7	87·3	87·3	87·4	87·4	88·4	88·1	87·4
September	81·5	90·1	91·3	87·2	86·9	86·4	86·8	87·4	87·4	87·0	87·1	87·1	87·5	86·9	87·1
October	72·7	87·5	90·2	76·7	82·0	81·3	82·1	82·7	84·2	84·2	84·3	84·2	81·8	82·0	84·2
November	60·7	75·4	82·0	65·8	73·0	72·5	73·2	73·8	78·0	77·9	78·2	78·0	71·0	73·1	78·0
December	52·2	64·2	74·5	57·6	64·6	64·1	64·7	65·7	70·6	70·6	71·0	70·9	62·1	64·8	70·8
Year	71·4	84·3	88·2	76·3	79·7	79·0	79·7	80·6	80·5	80·4	80·6	80·6	79·9	79·8	80·5

3. JEYPORE.

Month.	Surface.				4 inches deep.				1 feet deep.				3 feet deep.			
	4 hours.	10 hours.	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.	4 hours	10 hours.	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.
January . .	44·6	75·6	73·0	48·8	55·6	60·4	71·8	60·9	62·1	61·1	63·4	64·0	67·8	67·8	67·9	67·8
February .	43·9	78·5	93·6	50 3	57·5	59·8	76·3	64·6	61·9	59·9	64·3	65·8	64·9	65·1	65·2	65·1
March . .	56·0	99·4	108·9	62·2	70·0	75·2	90·6	77·3	74·1	72·5	76·7	77·9	72·6	72·8	72·9	73·0
April . .	67·0	120·2	127·2	75·6	81·9	89·8	105·7	91·3	85·9	84·5	87·8	89·1	81·6	81·8	81·9	81·9
May . .	72·8	116·4	126·1	81·8	86·4	92·0	107·5	95·0	90·2	89·0	92·4	93·1	87·3	87·4	87·5	87·4
June . .	77·4	115·4	115·8	83·5	86·9	91·5	102·2	93·4	90·9	89·5	94·4	93·4	89·3	89·3	89·5	89·4
July . .	76·4	101·1	102·5	80·2	82·7	84·7	92·7	86·8	85·1	84·1	87·3	87·5	86·0	86·1	86·1	86·0
August . .	75·5	116·0	118·1	82·9	87·3	91·3	103·0	92·2	91·4	90·3	93·4	94·0	89·7	89·9	89·9	89·9
September .	73·8	110·0	107·2	77·6	82·4	85·4	95·9	86·8	85·5	84·3	88·4	88·2	86·7	86·8	86·8	86·7
October . .	59·7	106·1	110·9	66·9	76·9	81·4	98·3	84·7	82·6	81·1	84·5	85·3	85·2	85·2	85·3	85·2
November .	44·5	87·9	86·5	52·2	63·5	68·3	83·1	70·8	70·5	69·4	71·9	72·8	77·2	77·2	77 3	77·2
December .	37·4	76·2	71·0	42·9	54·0	58·9	70·7	60·1	60·8	60·0	62·1	62·8	69·1	69·2	69·3	69·2
Year . .	60·8	100·2	103·4	67·1	73·8	78·2	91·5	80·3	78·4	77·1	80·6	81·2	79·8	79·9	80·0	79·9

3. JEYPORE—(*continued*).

Month.	10 feet deep.				20 feet deep.			
	4 hours.	10 hours	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.
January . .	76·4	76·4	76·4	76·4	80·7	80·7	80·7	80·7
February .	73·7	73·7	73·7	73·7	79·7	79·7	79·7	79·6
March . .	73·0	73·0	73·0	72·9	78·7	78·7	78·7	78 7
April . .	75·2	75·2	75·3	75·3	78·0	78·0	78·0	78·0
May . .	79·0	79·1	79·1	79·1	78·2	78·3	78 3	78·3
June . .	81·9	82·0	82·0	82·0	79·1	79·1	79·1	79·1
July . .	83·6	83·7	83·7	83·6	80·2	80·2	80·3	80·3
August . .	84·2	84·2	84·2	84·2	81·3	81·3	81·3	81·3
September .	85·1	85·1	85·1	85·1	82·1	82·1	82·1	82·1
October .	84·9	84·8	84·8	84·8	82·8	82·8	82·8	82·8
November .	83·1	83·1	83·1	83 1	83·1	83·1	83·1	83·1
December .	79·5	79·4	79·4	79·4	82·2	82·2	82·1	82·1
Year . .	80·0	80·0	80·0	80·0	80·5	80·5	80·5	80·5

4. DEHRA.

Month.	Mean.										
	Surface.	4 inches.	1 foot.	3 feet.	10 feet.	20 feet.	1'1 foot.	3'2 feet.	6'4 feet.	12'8 feet.	25'6 feet.
January . .	60·5	62·2	62 6	67·8	76·4	80·7	58·0	62·3	67·6	72·5	75·9
February .	66·6	64·5	63·0	65·1	73·7	79·7	58·5	60·7	65·1	70·4	75·0
March . .	81·6	78·3	75·3	72·8	73·0	78 7	65·9	64·8	66·5	69·8	74·3
April . .	97·5	92·2	86·8	81·8	75·2	78·0	79·5	74·1	71·0	70·9	73·9
May . .	99·3	95·2	91·2	87·4	79·1	78·3	86·7	81·6	76·7	73·0	74·0
June . .	98·0	93·5	92·0	89·4	82·0	79·1	87·9	83·4	79·3	75·2	74·0
July . .	90·0	86·7	86·0	86·0	83·6	80·2	84·6	83·0	80·7	76·8	74·3
August . .	98 1	93·4	92·3	89 9	84·2	81·3	84·9	83·4	81·4	78·2	74·9
September .	92·2	87·6	86·6	86·8	85·1	82·1	82·2	81·7	81·1	79·0	75·7
October .	85·9	85·3	83·4	85·2	84·8	82·8	76·7	78·2	79·5	78 9	76·2
November .	67·8	71·4	71·1	77·2	83·1	83·1	65·4	69·7	74·5	76·9	76·3
December .	56·9	60·9	61·4	69·2	79·4	82·2	57·8	62·5	68·7	73·5	76·1
Year . .	82·9	80·9	79·3	79·9	80·0	80·5	74·0	73·8	74·3	74·6	75·1

TABLE IV.—TEMPERATURES OF THE GROUND IN 1883 (4 STATIONS).

1. CALCUTTA (ALIPORE).

Month.	Surface.			1 foot deep (old).			1 foot deep (new).			3 feet deep.			Mean.			
	5½ hours.	13½ hours.	21½ hours.	5½ hours.	13½ hours.	21½ hours.	5½ hours.	13½ hours.	21½ hours.	5½ hours.	13½ hours.	21½ hours.	Surface.	1 foot old.	1 foot new.	3 feet.
January	58·3	74·0	62·2	67·0	67·5	67·6	...	...	...	71·9	72·5	72·2	64·8	67·4	...	72·2
February	62·5	78·9	66·5	69·6	69·8	70·3	...	...	...	72·7	72·9	72·8	69·3	69·9	...	72·8
March	72·1	97·1	76·5	76·9	77·0	77·9	77·6	77·1	78·8	77·2	77·3	77·4	81·9	77·3	77·8	77·3
April	79·0	109·9	82·9	85·0	85·4	86·5	86·1	85·5	87·4	83·7	83·9	83·9	90·6	85·6	86·3	83·8
May	82·9	110·9	86·1	88·7	89·0	90·4	89·4	89·1	91·4	87·0	87·1	87·1	93·3	89·4	90·0	87·1
June	82·2	97·0	83·8	87·3	87·5	88·2	87·7	87·4	88·7	87·8	87·7	87·7	87·7	87·7	87·9	87·7
July	81·5	95·0	83·4	86·0	85·9	86·4	86·1	85·6	86·6	86·2	86·3	86·3	86·6	86·1	86·1	86·3
August	81·8	94·7	84·0	85·9	85·8	86·2	86·0	85·6	86·5	86·3	86·3	86·3	86·8	86·0	86·0	86·3
September	81·4	96·6	83·3	86·2	86·2	86·7	86·3	85·9	86·8	86·6	86·5	86·6	87·1	86·4	86·3	86·6
October	76·1	96·0	78·9	83·8	83·9	84·2	84·0	83·6	84·4	85·7	85·8	85·8	83·7	84·0	84·0	85·8
November	62·3	83·3	65·6	74·7	75·0	75·3	75·4	75·0	75·9	79·9	80·7	80·5	70·4	75·0	75·4	80·4
December	55·4	72·0	58·9	66·1	66·4	66·8	66·9	66·3	67·2	73·1	73·6	73·4	62·1	66·4	66·8	73·4
Year	73·0	92·1	76·0	79·8	80·0	80·5	?	?	?	81·5	81·7	81·7	80·4	80·1	?	81·6

2. ALLAHABAD.

Month.	Surface.				1 foot deep.				3 feet deep.				Mean.		
	4 hours.	10 hours.	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.	4 hours.	10 hours.	16 hours.	22 hours.	½ inch.	1 foot.	3 feet.
January	56·2	63·8	70·3	60·1	64·8	64·1	64·6	65·6	69·9	69·8	69·9	69·9	62·2	64·8	69·9
February	55·5	64·6	72·0	60·3	64·3	63·5	64·2	65·4	68·1	68·0	68·2	68·2	62·7	64·4	68·1
March	65·9	79·8	86·2	72·3	74·7	73·7	74·7	76·3	73·9	73·9	74·1	74·1	75·6	74·8	74·0
April	77·0	101·8	102·9	84·3	86·4	85·3	86·3	87·7	81·9	81·9	82·1	82·1	91·5	86·4	82·0
May	83·2	106·9	106·5	89·8	92·8	91·8	92·6	93·8	88·0	88·0	88·1	88·0	96·6	92·8	88·0
June	85·5	98·8	98·4	89·1	91·7	90·9	91·8	92·4	89·4	89·2	89·4	89·4	93·0	91·7	79·4
July	83·3	88·3	90·5	85·5	87·4	86·8	87·0	87·6	87·4	87·3	87·4	87·3	86·9	87·2	87·4
August	83·6	90·3	93·6	86·3	88·1	87·7	88·0	88·7	87·3	87·3	87·4	87·4	88·4	88·1	87·4
September	81·5	90·1	91·3	87·2	86·9	86·4	86·8	87·4	87·4	87·0	87·1	87·1	87·5	86·9	87·1
October	72·7	87·5	90·2	76·7	82·0	81·3	82·1	82·7	84·2	84·2	84·3	84·2	81·8	82·0	84·2
November	60·7	75·4	82·0	65·8	73·0	72·5	73·2	73·8	78·0	77·9	78·2	78·0	71·0	73·1	78·0
December	52·2	64·2	74·5	57·6	64·6	64·1	64·7	65·7	70·6	70·6	71·0	70·9	62·1	64·8	70·8
Year	71·4	84·3	88·2	76·3	79·7	79·0	79·7	80·6	80·5	80·4	80·6	80·6	79·9	79·8	80·5

5. QUETTA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	37·6	40·5	44·8	47·8	17·5	30·3	4th	60·9	43·3	31st	17·6
February	39·8	42·5	50·3	51·6	22·4	29·2*	28th	68·8	53·7	1st	15·1
March	48·4	54·4	57·9	61·3	22·5	38·8	29th	73·6	47·4	5th	26·2
April	59·9	68·2	70·9	74·1	25·3	48·8†	19th	82·8	43·8	2nd & 4th	39·0
May	67·2	76·3	80·7‡	82·7‡	29·1	53·6‡	31st	90·7	45·4	13th	45·3
June	76·1	86·3	90·6	93·8	32·3	61·5	27th	102·3	51·5	13th	50·8
July	76·3	83·3	87·2	91·3	25·9	65·4‡	7th	99·4	43·3	22nd	56·1
August	75·0	84·4	89·7	92·5	32·3	60·2	4th	96·3	42·4	24th	53·9
September	68·4	78·2§	85·3‖	86·9	35·4	51·5§	2nd	92·2	51·8	24th	40·4
October	54·8	64·7	70·9	73·5	34·9	38·6	2nd	82·8	58·9	20th	23·9
November	43·9	51·0	57·6	60·1	29·9	30·2	5th	73·3	54·9	30th	18·4
December	40·9	44·7	52·6	55·4	26·2	29·2	26th	64·9	48·6	31st	16·3
Year	57·4	64·5	69·9	72·6	27·8	44·8	...	102·3	87·2	...	15·1

* Mean of 27 days. † „ „ 29 „ ‡ „ „ 30 „ § Mean of 23 days. ‖ „ „ 22 „

6. LEH (*corrcted*).

Month.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	19·4	...	20·8	27·3	...	34·0	22·5	11·5	16th	39·8	41·3	29th	—1·5
February	19·5	...	21·6	28·2	...	32·8	22·0	10·8	10th	40·8	44·1	1st	—3·3
March	29·2	...	33·5	38·0	...	44·3	24·0	20·3	18th	56·6	47·6	9th	9·0
April	39·0	43·6	...	49·6	54·1	...	60·9	27·8	33·1	28th & 29th	71·8	50·2	7th	21·6
May	45·3	46·2	..	53·6	55·3	...	63·2	26·2	37·0	3rd	71·7	39·9	4th	31·8
June	50·8	56·9	...	62·4	68·6	...	75·2	30·1	45·1	30th	92·2	52·9	7th	39·3
July	56·1	65·5	..	70·3	77·8	...	84·7	31·5	53·2	9th	91·7	43·2	27th	48·5
August	53·9	62·6	...	66·4	75·2	...	81·5	31·5	50·0	1st	90·3	47·4	17th	42·9
September	40·4	56·3	44·7	60·9	67·7	51·7	79·1	34·4	44·7†	4th	87·2	51·7	15th	35·5
October	23·9	38·9	29·9	42·3	47·6	35·8	58·9	30·1	28·8‡	1st	76·1	54·6	30th & 31st	21·5
November	18·4	27·1	18·5¶	29·7¶	36·0**	24·3††	46·6††	27·6	19·0‡	2nd 11th	58·1	45·6	15th & 22nd	12·5
December	16·3	19·7	11·1	22·0	28·6†	17·2	36·3	25·7	10·6	3rd	48·8	45·3	18th	3·5
Year	15·1	40·4	...	44·4	50·4	...	58·1	27·8	30·3	...	92·2	95·5	...	—3·3

‡ Mean of 26 days. ** „ „ 24 „ †† Mean of 25 days.

7. MOOLTAN (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	55·5	58·9	67·8	69·5	26·3	43·2	15th	75·7	40·7	31st	35·0
February	57·0	61·2	70·6	72·0	28·7	43·3	26th	80·9	45·9	2nd	35·0
March	68·8	72·3	81·8	83·7	27·9	55·8	30th & 31st	95·9	49·5	6th	46·4
April	82·1	87·5	96·6	98·2	30·7	67·5	20th	105·9	45·8	15th	60·1
May	86·7	93·7	100·0	101·8	28·5	73·3	26th	111·9	43·7	27th	68·2
June	94·8	98·9	105·8	107·4	23·6	83·8	11th	110·9	34·7	2nd	76·2
July	89·3	91·7	97·8	99·6	18·8	80·8	8th & 5th	105·9	30·2	2nd	75·7
August	89·7	91·1	98·7	100·3	19·7	80·6	28th to 30th	108·9	33·7	29th	75·2
September	87·3	90·0	96·6	98·3	20·3	78·0	3rd	102·9	32·3	24th	70·6
October	77·4	82·6	92·0*	93·6	30·8	62·8	3rd	98·9	47·4	28th	51·5
November	63·7	68·5	78·7†	80·1	31·4	48·7	7th	89·9	49·9	30th	40·0
December	55·8	59·4	70·2	71·9	30·6	41·3	12th	75·9	38·9	19th	37·0
Year	75·7	79·6	88·1	89·7	26·4	63·3	...	111·9	76·9	..	35·0

* Mean of 30 days. † Mean of 29 days.

8. DERA ISMAIL KHAN (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	54·0	59·2	66·2	68·7	26·9	41·8	3rd & 4th	77·7	43·7	31st	34·0
February	55·1	61·9	69·6	72·2	31·7	40·5	25th & 26th	77·7	49·7	1st	28·0
March	66·0	71·6	78·9	81·8	28·7	53·1	26th	94·6	51·7	6th	42·9
April	79·6	86·5	92·2	95·6	28·7	66·9	20th	105·5	49·8	2nd	55·7
May	87·1	93·9	99·8	102·1	27·8	74·3	20th	113·5	48·7	13th	64·8
June	96·0	100·5	109·2	111·2	28·4	82·8	26th & 27th	117·5	40·6	1st	76·9
July	90·6	93·5	99·8	103·4	22·1	81·3	30th	110·5	39·7	1st	70·8
August	92·1	93·8	102·8	105·1	23·8	81·3	26th	112·5	39·7	17th	72·8
September	87·1	89·7	98·8	101·4	26·1	75·3	13th, 24th & 24th	105·5	39·7	24th	65·8
October	76·0	81·7	90·5	93·0	31·5	61·5	3rd, 4th & 7th	98·5	47·7	31st	50·8
November	61·3	66·6	76·7	79·8	34·0	45·8	3rd	91·6	54·7	30th	36·9
December	54·6	57·2	69·6	72·2	32·7	39·5	9th	76·7	42·7	22nd	34·0
Year	75·0	79·7	87·8	90·5	28·5	62·0	...	117·5	89·5	...	28·0

9. PESHAWAR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	49·9	52·3	59·6	62·9	22·8	40·1	3rd	72·2	41·5	31st	30·7
February	51·2	56·5	63·0	65·2	25·9	39·3	27th	72·7	43·5	1st	29·2
March	60·6	66·3	72·2	74·7	25·8	48·9	30th	88·6	47·9	8th	40·7
April	73·4	81·7	85·0	89·5	27·8	61·7	20th	101·0	51·7	5th	49·3
May	84·3	91·9	97·3	99·9	28·7	71·2	19th	110·0	47·2	13th	62·8
June	91·9	99·9	106·3	109·2	31·7	77·5	24th	116·5	44·8	6th	71·7
July	88·6	92·3	98·9	101·7	23·4	78·3	6th	111·5	41·3	15th	70·2
August	88·5	92·5	98·9	102·0	24·0	78·0	5th	111·0	40·8	13th	70·2
September	83·3	88·9	95·0	97·6	26·1	71·5	14th & 18th	101·5	39·2	24th & 30th	62·3
October	71·1	79·2	84·7	88·1	30·7	57·4	3rd	94·5	47·2	30th & 31st	47·3
November	57·2	63·9	70·7	73·9	30·2	43·7	3rd, 5th & 6th	84·6	49·4	29th	35·2
December	50·4	53·6	63·3	66·3	28·8	37·5	9th	71·7	39·5	18th	32·2
Year	70·9	76·6	82·9	85·9	27·2	58·8	...	116·5	87·3	...	29·2

10. MURREE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	36·3	40·3	39·4	43·9	10·7	33·2	3rd & 5th	58·0	36·9	31st	21·1
February	36·7	41·8	40·9	46·1	13·7	32·4	9th	54·0	33·7	19th	20·3
March	45·6	50·6	50·1	55·0	14·0	41·0	30th	68·9	43·2	5th	25·7
April	58·3	63·1	64·1	68·3	15·8	52·5	21st	79·4	40·7	3rd	38·7
May	64·5	70·0	69·9	74·4	15·3	59·1	20th	84·9	41·1	27th	43·8
June	73·3	78·0	79·6	83·2	16·3	66·9	24th	90·9	32·9	17th	58·0
July	69·5	72·1	75·2	77·0	13·3	63·7	31st	85·0	27·6	19th	57·4
August	67·1	73·6	72·0	75·4	13·2	62·2	4th	83·1	27·3	12th	55·8
September	64·9	68·9	70·0	73·5	13·8	59·7	24th	77·8	32·2	29th	45·6
October	56·8	62·9	61·6*	67·1	15·2	51·9	3rd	73·1	33·5	25th	39·6
November	45·6	52·6	48·5	56·7	14·0	42·7	7th	67·8	36·7	12th	31·1
December	41·2	46·8	44·2*	50·8	12·7	38·1	25th	58·8	28·9	30th	29·9
Year	55·0	60·1	59·6	64·3	14·0	50·3	...	90·9	70·6	...	20·3

* Mean of 30 days.

11. RAWALPINDI (*corrected*).

Month.	Mean	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	48·9	50·3	58·2	61·6	22·0	39·6	15th	70·0	38·1	4th	31·9
February	49·4	55·0	59·8	63·7	24·7	39·0	17th	71·6	40·7	6th	30·9
March	59·0	65·0	70·2*	74·1	26·3	47·8	30th	86·0	46·6	6th	39·4
April	73·5	81·0*	85·4†	89·3	27·7	61·6*	21st & 27th	99·8	50·8	6th	49·0
May	80·9	88·9	94·1	96·6	29·0	67·6	20th	107·5	48·4	14th	59·1
June	90·4	97·4	102·6	105·8	27·7	78·1	25th	114·0	44·3	1st & 4th	69·7
July	86·2	89·9	95·2	98·4	21·2	77·2	6th & 31st	108·0	39·3	16th	68·7
August	84·5	89·0	93·1	96·7	20·8	75·9	4th	105·5	36·3	16th & 17th	69·2
September	79·6	84·9	90·3	93·3	24·4	68·9	17th, 22nd & 24th	98·0	38·4	30th	59·6
October	69·8	75·5	83·3*	87·7	31·5	56·2	4th	92·6	48·6	28th, 30th, & 31st	44·0
November	50	62·2*	67·2	72·3	29·6	42·7	5th & 7th	85·0	50·6	30th	34·4
December	48·4	52·7*	61·0*	65·9*	30·2	35·7*	11th	69·9	39·4	18th	30·5
Year	68·8	74·6	80·0	83·8	26·3	57·5	...	114·0	83·5	..	30·5

12. SIALKOT (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	53·9	53·7	63·8	66·6	22·7	43·9	3rd & 15th	72·7	37·7	31st	35·0
February	54·7	55·9	66·9	68·4	26·0	42·4	26th	75·3	39·7	5th & 6th	35·6
March	65·0	68·8	77·2	79·0	26·3	52·7	31st	94·6	50·5	1st	44·1
April	80·8	86·9	94·2	96·8	29·4	67·4	28th	108·7	56·4	6th	52·3
May	87·0	93·8	100·7	106·3	33·1	73·2	21st	113·8	49·6	29th	64·2
June	94·8	96·8	106·5	110·5	27·5	83·0	12th, 24th & 25th	114·9	39·8	1st & 6th	75·1
July	88·5	89·3	97·7	103·2	23·9	79·3	11th	114·9	46·4	4th	68·5
August	87·3	88·0	96·5	99·5	21·5	78·0	2nd	107·8	37·4	13th	70·4
September	83·0	84·9	92·5	94·8	21·3	73·5	24th	99·7	32·4	30th	67·3
October	75·5	79·9	90·2	93·5	32·0	61·5	3rd	98·7	47·1	29th	51·6
November	62·2	62·4	74·7	79·8	30·1	49·7	7th & 10th	86·6	45·5	21st & 22nd	41·1
December	53·7	52·7	66·7	68·7	22·0	40·7	1st	73·1	39·0	18th	34·1
Year	73·9	76·1	85·6	88·9	26·8	62·1	...	114·9	80·8	...	34·1

* Mean of 29 days. † Mean of 28 days.

13. LAHORE (*corrected*).

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	55·0	47·3	56·9	64·9	50·9	67·6	23·6	44·0	3rd & 13th.	74·7	37·2	30th & 31st.	37·5
February	56·2	45·9	59·6	67·9	51·4	70·0	27·4	42·6	26th & 27th.	77·7	42·7	1st & 6th	35·0
March	68·7	58·0	72·5	80·0	64·2	82·5	27·3	55·2	31st	96·1	51·0	9th	45·1
April	83·8	72·8	88·5	95·5	78·5	97·8	28·4	69·4	28th	108·3	50·4	2nd & 3rd	57·9
May	89·4	76·7	95·3	101·3	84·2	103·3	29·6	73·7	20th	112·5	47·9	28th	64·6
June	96·0	85·8	98·7	107·2	92·2	109·1	26·2	82·9	23rd	115·0	42·0	6th	73·0
July	91·7	83·4	94·2	99·1	90·0	102·5	20·5	82·0	31st	114·5	38·6	17th & 19th.	75·9
August	91·9	83·7	95·3	100·3	88·3	104·3	22·7	81·6	25th	109·0	34·5	7th	74·5
September	83·5	76·0	87·0	91·2	79·9	93·5	19·8	73·7	23rd	98·7	31·6	30th	67·1
October	76·2	64·7	82·4	88·4	69·4	91·9	30·2	61·7	3rd	97·1	46·1	29th & 31st.	51·0
November	62·3	51·4	67·5	73·8	56·3	77·7	29·4	48·3	7th	87·6	45·9	22nd	41·7
December	54·4	44·4	58·6	66·4	48·3	70·4	28·8	41·6	11th & 12th.	73·7	37·7	22nd, 24th & 25th.	36·0
Year	75·8	65·8	79·7	86·3	71·1	89·2	26·2	63·1	...	115·0	80·0	...	35·0

14. LUDHIANA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	53·7	58·2	63·9	68·2	24·8	43·4	1st	77·7	39·2	18th	38·5
February	54·8	59·8	66·2	69·4	26·0	43·4	27th	76·7	40·2	1st	36·5
March	67·8	72·6	79·0	82·9	26·3	56·6	31st	95·8	47·7	1st	48·1
April	81·6	90·0	95·9	99·9	32·7	67·2	22nd	109·3	51·1	4th	58·2
May	88·1	96·4	102·7*	106·3	32·9	73·4	19th	114·3	46·0	28th	68·3
June	90·5	96·3	103·2†	107·3	29·5	77·8	11th	114·8	44·5	6th	70·3
July	86·8	89·9	94·8	99·9	21·1	78·8	10th	112·8	38·5	18th	74·3
August	89·9	93·8	98·5	102·6	21·4	81·2‡	3rd, 10th & 24th.	105·8	29·0	1st & 7th.	76·3
September	82·5	87·0	90·9	94·3	20·2	74·1	23rd	100·0	31·5	24th	68·5
October	75·0	82·7	88·0	92·1	30·2	61·9	4th	98·6	46·8	30th	51·8
November	61·9	67·8	73·6	78·7	28·5	50·2	6th	88·2	45·2	22nd	43·0
December	54·1	59·0	66·3	70·3	28·5	41·8	14th	73·7	37·9	24th	35·8
Year	73·9	79·5	85·3	89·3	26·8	62·5	...	114·8	79·0	...	35·8

* Mean of 30 days. † Mean of 29 days. ‡ Mean of 24 days.

15. KAILANG (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	The observatory opened in July.										
February											
March											
April											
May											
June											
July	62·9	69·3*	73·0*	77·6*	24·8	52·8*	5th & 7th	83·5	38·4	27th	45·1
August	60·8	67·4	71·2	73·2	22·8	50·4	3rd	82·5	40·9	15th	41·6
September	55·8	63·1	66·1	70·7	25·3	45·4†	25th	78·7	44·6	30th	34·1
October	39·6	48·2	49·5	56·7	27·0	29·7	3rd	68·7	45·7	22nd	23·0
November	27·4	32·1	35·2	40·7	21·2	19·5	7th	57·3	48·3	17th	9·0
December	18·8	22·9	25·8*	31·5*	19·7	11·8	26th	37·2	35·2	18th	2·0
Year	...	...	...	...	...	...	...	...	...	...	...

16. SIMLA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	38·2	42·0	42·1	48·1	13·8	34·3	4th	61·7	40·7	31st	21·0
February	40·7	45·3	46·2	51·6	16·4	35·2	6th	59·8	40·1	1st	19·7
March	48·1	51·2	53·6	58·6	16·0	42·6	31st	71·3	40·1	12th	31·2
April	60·7	65·0	67·7	72·1	18·4	53·7	20th	80·1	38·6	2nd	41·5
May	65·2	70·0‡	72·0†	78·5†	20·2	58·3†	19th	87·4	42·8	29th	44·6
June	66·7	71·2	71·8	78·5	16·9	61·6	11th	83·8	33·4	6th	50·4
July	64·5	66·1	67·9	72·8	11·8	61·0	27th	76·5	18·6	3rd & 10th	57·9
August	63·3	65·2	66·9	72·5	12·8	59·7	18th	77·1	20·5	7th	56·6
September	61·8	64·6	65·6	70·9	13·0	57·9	15th, 16th & 20th.	74·1	20·0	30th	54·1
October	55·9	60·2	61·5	67·1	16·8	50·3	8th	72·5	32·2	21st	40·3
November	46·7	50·3	51·0	57·1	14·8	42·3	22nd	66·6	32·2	12th	34·4
December	42·1	45·8	46·5	53·9	16·2	37·7	29th	61·9	30·3	17th	31·6
Year	54·5	58·1	59·4	65·1	15·6	49·6	...	87·4	67·7	...	19·7

* Mean of 30 days. † Mean of 29 days. ‡ Mean of 28 days.

17 DELHI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	59·4	60·0	69·6	71·6	22·4	49·2*	1st	82·7	41·4	31st	41·3
February	60·8	63·5	72·8	74·7	25·9	48·8	16th	83·7	42·6	2nd	41·1
March	72·6	76·3	84·4	87·2	25·5	60·7	31st	102·0	53·2	13th	48·8
April	87·5	92·8	100·6	103·4	29·1	74·3	21st & 28th	110·6	46·4	3rd	64·2
May	92·0	96·8	104·0	106·9	27·0	79·9	19th	116·6	48·4	28th & 29th	68·2
June	93·7	96·1	103·3	106·6	22·5	84·1	3rd	116·6	44·6	6th	72·0
July	88·3	89·0	95·1	97·4	15·9	81·5	30th	106·0	30·0	1st	76·0
August	91·5	94·6	99·8	102·9	19·8	83·1	17th & 24th	108·6	31·4	22nd	77·2
September	86·0	88·8	93·5	96·1	17·6	78·5	24th	101·6	27·4	30th	74·2
October	79·7	84·9	91·7	94·6	26·9	67·7	4th & 9th	99·6	43·9	31st	55·7
November	66·4	69·8	78·8	81·8	27·9	53·9	6th	90·5	44·3	26th	46·2
December	59·2	60·4	71·6	74·4	27·7	46·7	12th & 13th	76·7	35·4	20th	41·3
Year	78·1	81·1	88·8	91·5	24·1	67·4	...	116·6	75·5	...	41·1

* Mean of 30 days.

18. SIRSA (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
55·8	60·7	68·9	70·6	28·0	42·6	1st	80·1	45·1	4th	35·0
57·6	63·6	71·6	73·6	30·0	43·6	16th	83·1	50·2	2nd	32·9
68·9	76·9	82·5	85·5	30·2	55·3	31st	99·3	55·3	6th	44·0
84·7	95·0	99·6†	102·4†	32·7	69·7	22nd	111·2	53·9	3rd	57·3
88·8	97·8	104·0	106·2	32·7	73·5	20th	116·2	50·9	22nd	65·3
94·1	100·3	104·7	109·0	25·5	83·5	3rd	115·5	40·5	1st	75·0
89·2	93·0	97·2	100·8	19·6	81·2	13th	106·2	34·1	10th	72·1
92·2	96·2	102·2	104·0	21·9	82·1	28th	110·0	31·7	22nd	78·3
84·4	90·2	93·8	96·9	22·0	74·9	1st	103·2	34·8	23rd	68·4
77·5	85·9	92·9	94·8	32·8	62·0	9th	100·6	49·3	29th	51·3
62·9	70·5	78·2	80·8	33·3	47·5	6th	91·3	51·7	30th	39·6
55·9	61·9	71·7	74·0	34·0	40·0	13th	77·1	43·2	18th	33·9
76·0	82·7	88·9	91·5	28·6	63·0	...	116·2	83·3	...	32·9

† Mean of 29 days.

19. CHAKRATA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	39·5	42·9	40·9	47·9	14·2	33·7	1st	60·0	38·2	29th	21·8
February	42·5	46·1	45·5	50·1	15·1	35·0	23rd	56·5	34·7	1st	21·8
March	49·4	54·2	53·8	60·1	18·6	41·5	24th	71·0	41·2	12th	29·8
April	62·1	66·6	67·8	73·3	20·3	53·0	11th	80·2	40·5	3rd	39·7
May	66·4	70·5	71·6	77·2	19·6	57·6	19th	85·0	39·7	28th	45·3
June	65·7	68·2	68·9	74·3	14·7	59·6	3rd	79·5	29·7	6th	49·8
July	64·2	66·1	66·2	70·8	10·7	60·1	27th	75·7	17·7	1st, 3rd, 7th & 8th	58·0
August	64·1	65·6	65·8	70·1	11·1	59·0	18th	73·7	17·2	22nd	56·5
September	63·2	65·7	64·8	69·8	12·0	57·8	3rd	73·0	23·0	28th	50·0
October	57·8	62·9	61·8	66·7	17·1	49·6	4th	71·5	27·8	31st	43·7
November	47·2	51·6	50·1	57·0	16·5	40·5	22nd	64·5	31·5	13th	33·0
December	43·5	48·1	45·5	51·7	15·3	36·4	13th	60·0	31·2	17th	28·8
Year	55·5	59·0	58·6	64·1	15·4	48·7	...	85·0	63·2	...	21·8

20. MUSSOOREE (ST. FIDELIS) (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
42·0	47·8*	46·3‡	51·8‡	14·1	37·7*	1st	61·4	38·7	26th	22·7
45·3	51·8‡	50·8‡	55·0‡	15·2	39·8‡	17th	62·4	35·7	1st	26·7
52·7	58·4*	58·5§	63·2§	16·4	46·8*	31st	74·4	41·7	13th	32·7
66·2	72·6†	73·1¶	76·8¶	17·6	59·2‖	19th	83·4	34·5	2nd	48·9
69·8	76·8**	76·9	82·0	19·4	62·6**	17th & 19th	89·4	38·4	28th & 29th	51·0
69·1	72·7§	75·1	78·9	15·8	63·1§	3rd	85·4	30·4	4th to 6th, 8th & 9th.	55·0
66·3	69·0*	69·4††	73·0*	9·8	63·2§	7th & 20th	79·4	19·3	1st	60·1
66·2	69·2**	69·5	72·1**	9·3	62·8**	9th, 16th, 17th & 25th.	76·4	17·3	20th	59·1
64·7	69·3††	68·0†	71·3†	9·9	61·4††	24th	75·4	21·4	28th	54·0
59·9	68·0††	65·0§	69·9§	15·1	54·8††	5th & 13th	74·4	25·4	31st	49·0
49·8	56·4†	54·3‡‡	58·7‡‡	13·4	45·3†	5th & 22nd	64·4	24·5	11th, 12th & 30th	39·9
Imperfect.										
?	?	?	?	?	?	...	?	?	...	?

* Mean of 29 days. § Mean of 28 days. ** Mean of 30 days.
† ,, ,, 26 ,, ‖ ,, ,, 22 ,, †† ,, ,, 27 ,,
‡ ,, ,, 25 ,, ¶ ,, ,, 20 ,, ‡‡ ,, ,, 21 ,,

21. DEHRA (G. T. S. OFFICE).*

Month.	Mean.	9-30 hours.	15-30 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	53·7	53·2	64·1	64·5	20·7	43·8	2nd	71·3	35·9	29th	35·4
February	55·4	54·9	68·7	67·8	23·7	44·1	18th	76·7	42·0	1st	34·7
March	63·8	65·7	75·2	75·7	23·1	52·6	31st	86·0	42·5	9th	43·5
April	78·8	81·4	90·7	90·7	25·6	65·1	22nd	97·8	45·5	3rd	52·3
May	83·4	87·4	94·7	95·5	25·1	70·4	20th	104·0	42·5	29th	61·5
June	83·1	85·1	90·3	93·1	18·7	74·4	4th	100·4	34·3	8th	66·1
July	79·8	80·8	84·3	85·9	11·2	77·7	3rd	89·3	19·2	1st	70·1
August	79·2	80·5	84·2	85·6	12·0	73·6	11th	90·0	20·1	19th	69·9
September	76·9	78·3	82·2	84·1	12·9	71·2	25th	87·0	21·0	29th	66·0
October	69·3	71·2	80·0	81·9	22·6	59·3	7th	86·0	32·4	30th	53·6
November	59·3	60·3	69·4	70·7	20·2	50·5	1st & 2nd	77·0	33·0	21st	44·0
December	53·3	53·5	64·2	65·4	22·0	43·4	12th	69·0	30·7	19th	38·3
Year	69·7	71·0	79·0	80·1	19·8	60·3	...	104·0	69·3	...	34·7

22. DEHRA (FOREST SCHOOL) (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
51·4	56·7	62·4	65·6	25·3	40·3	1st & 2nd	73·6	41·8	29th	31·8
53·4	58·5	66·6	69·0	28·8	40·2	17th	77·5	45·5	1st	32·0
61·8	68·6	74·5	79·9	30·8	49·1	...	...	...	...	...
74·7	83·5	90·1	92·6	33·3	59·3	...	...	...	...	...
79·5	90·0	93·1	97·1	31·2	65·9	...	...	...	...	...
81·3	85·3	89·8	94·4	21·7	72·7	...	...	...	...	...
78·6	80·7	83·3	86·9	13·1	73·8	...	...	...	...	...
78·4	81·7	84·1	88·3	15·6	72·7	...	...	...	...	...
76·2	81·0	82·5	86·4	16·5	69·9	...	...	...	...	...
68·4	76·3	82·2	84·8	30·3	54·5	...	...	...	...	...
57·7	63·8	69·0	73·8	27·4	46·4	...	...	...	...	...
51·1	57·9	64·3	68·2	30·3	37·9	...	...	...	...	...
67·7	73·7	78·5	82·3	25·4	56·9	...	...	...	...	...

* The maximum readings refer to the preceding day in this and previous reports.

23. PAORI (*correcte*

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	44·7	47·8	48·7	53·7	15·3	38·4	1st & 2nd	61·2	32·2	28th & 29th	29·0
February	48·9	51·5	53·9	57·7	17·3	40·4	16th	62·2	32·2	1st	30·0
March	55·5	58·2	61·5	65·2	17·8	47·4	31st	76·1	39·9	12th	36·2
April	68·6	71·3	75·9	78·6	20·5	58·1	21st	84·7	40·6	3rd	44·1
May	72·2	75·2	79·1	82·5	20·1	62·4	19th	91·3	37·8	25th	53·5
June	74·2	76·5	79·6	83·0	16·0	67·0	19th	87·4	28·7	6th	58·7
July	71·7	73·1	74·5*	77·5*	10·0	67·5	10th	81·5	17·2	1st	64·3
August	71·1	72·5*	74·4	77·4*	11·4	66·0*	11th	81·8	19·2	7th	62·6
September	69·4	71·4	72·9	75·3	11·3	64·0	23rd	77·5	20·1	28th	57·4
October	61·2	66·0†	67·1*	71·0*	17·8	53·2†	13th	77·0	30·4	30th	46·6
November	51·7	54·6	56·3	60·7	16·4	44·3	5th	67·4	27·7	30th	39·7
December	The Observatory abolished.										
Year	...	...	...	...	...	...	...	...	...	...	...

24. ROORKEE (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
56·7	58·8	67·1	70·2	26·1	44·1	2nd	79·4	44·5	18th	34·9
57·1	59·6	69·4	72·0	27·9	44·1	17th	82·2	45·2	1st & 2nd	37·0
68·1	72·0	79·8	82·9	28·1	54·8	31st	97·2	52·0	13th	45·2
84·2	89·5	96·7	99·1	31·8	67·3	21st	107·2	51·7	6th & 7th	55·5
88·1	93·3	100·5	103·6	30·4	73·2	18th & 19th	112·5	46·2	28th & 29th	66·3
89·3	91·1	98·4	101·1†	22·0	79·1	3rd	110·5	42·7	6th	67·8
84·7	86·0	90·0	92·9	14·4	78·5	12th	99·2	25·0	14th	74·2
85·3	86·7	92·3	94·6	16·7	77·9	10th & 11th	101·7	29·0	22nd	72·7
81·9	84·8	88·4	91·8	18·1	73·7	28th	95·7	30·8	30th	64·9
74·1	80·7	86·9	90·9	32·2	58·7	6th	96·0	44·6	30th	51·4
62·7	67·9	73·1	77·7	27·3	50·4	1st	86·2	43·0	27th & 28th	43·2
55·2	59·1†	67·6	71·8	31·2	40·6*	31st	76·2	41·3	25th	34·9
74·0	77·5	84·2	87·4	25·5	61·9	...	112·5	77·6	...	34·9

* Mean of 30 days.
† " " 29 "

25. RANIKHET (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	daily Mean range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	43·5	46·4	47·4	51·7	14·1	37·6	2nd	63·2	36·5	28th	26·7
February	48·2	50·4	52·8	56·1	15·7	40·4	17th	62·5	35·2	1st	27·3
March	53·7	56·8	58·8	63·0	16·9	46·1	30th	74·1	40·6	13th	33·5
April	67·4	70·8	72·5	76·1	17·7	58·4	12th	81·3	34·8	2nd	46·5
May	68·9	72·4	73·1	77·5	16·3	61·2	17th	84·2	35·2	28th & 29th	49·0
June	70·1	72·4	75·2	78·4	15·2	63·2	11th & 19th	81·3	29·0	6th	52·3
July	67·8	69·2	71·2	74·6	11·5	63·1	11th	80·0	21·5	20th	58·5
August	67·5	69·1	71·0	73·9	11·7	62·2	17th	78·7	20·2	25th	58·5
September	66·2	68·2	69·9	73·0	12·5	60·5	17th	75·7	19·2	30th	56·5
October	60·7	65·2	65·8	69·4	15·9	53·5	3rd	75·3	28·3	21st	47·0
November	51·6	54·8	55·6	59·7	15·2	44·5	22nd	64·7	25·2	10th & 12th	39·5
December	46·4	49·5	50·2	55·5	15·5	40·0	13th	63·5	30·5	31st	33·0
Year	59·3	62·1	63·6	67·4	14·9	52·6	...	84·2	57·5	...	26·7

26. PITHORAGARH (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	daily Mean range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	46·9	49·8	52·9	57·7	18·5	39·2	1st	70·8	42·9	28th	27·9
February	52·3	54·6*	59·3	61·6	19·9	41·7*	16th	67·9	35·6	2nd	32·3
March	57·3	60·1	64·6	67·5	19·8	47·7	31st	77·8	39·3	12th	38·5
April	69·2	72·7	76·0	80·3	22·0	58·3	21st	85·4	36·8	3rd	48·6
May	70·7	74·2	76·6	81·6	20·4	61·2	19th	89·7	38·1	29th	51·6
June	71·6	73·3	77·4	81·4	16·8	64·6	9th	84·4	30·2	4th	54·2
July	71·5	72·8	75·4	79·4	13·0	66·4	10th	84·3	20·7	1st	63·6
August	71·2	72·5	75·3	78·8	13·3	65·5	18th	83·7	20·6	6th	63·1
September	70·2	72·0	75·1	78·9	15·4	63·5	23rd	81·8	25·0	28th	56·8
October	63·8	67·3	72·7	74·4	19·9	54·5†	5th	79·9	31·5	30th	48·4
November	55·1	58·2‡	61·9‡	65·7‡	20·5	45·2‡	5th	70·2	28·8	30th	41·4
December	49·3	52·8	56·0	61·7	21·9	39·8	12th	68·9	35·8	17th	33·1
Year	62·4	65·0	68·6	72·4	18·5	54·0	...	89·7	61·8	...	27·9

* Mean of 27 days.
† " " 30 "
‡ " " 29 "

27. MEERUT (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	daily Mean range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	56·7	58·1	67·1	70·9	27·0	43·9	2nd	79·4	42·7	31st	36·7
February	58·0	60·7	70·2	73·4	30·3	43·1	16th	81·7	48·0	2nd	33·7
March	70·3	74·2	82·1	85·7	30·2	55·5	31st	99·6	53·7	13th	45·9
April	85·0	91·5	97·3	101·6	33·2	68·4	21st	106·6	50·5	3rd	56·1
May	88·8	94·6*	99·5†	102·6‡	28·4	74·2†	20th	111·6	46·6	29th	65·0
June	91·5	93·7	99·9	102·9	22·1	80·8	3rd	110·6	39·2	6th	71·4
July	86·7	87·3	91·0	94·0	13·9	80·1	30th	98·7	24·3	20th	74·4
August	88·4	89·9	94·0	97·2	16·7	80·5	18th	103·6	28·7	22nd	74·9
September	83·7	86·8	90·6	93·6	18·8	74·8	1st	97·8	28·9	25th	68·9
October	75·5	80·5	88·3	91·2	29·9	61·3	5th	96·1	45·1	30th	51·0
November	62·8	66·3	75·1	79·7	30·9	48·8	7th & 9th	85·5	44·3	30th	41·2
December	55·6	57·9	68·3	72·5	32·0	40·5	1st	75·4	39·5	24th	35·9
Year	75·3	78·5	85·3	88·8	26·1	62·7	...	111·6	77·9	...	33·7

28. BAREILLY (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	daily Mean range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute.	Lowest Minimum. Day.	°
January	58·9	61·0	68·7	69·8§	22·9	46·9	2nd	75·2	34·1	19th & 31st	41·1
February	59·9	62·8	71·6	72·9	26·7	46·2	19th	80·2	41·6	7th	38·6
March	70·9	75·3	82·4	85·0	27·7	57·3	31st	97·2	46·5	13th	50·7
April	85·4	91·2	98·8	101·5	32·2	69·3	21st	109·2	48·5	4th, 6th & 8th	60·7
May	88·4	93·8	101·1	104·4	29·6	74·8	19th	113·2	45·5	28th	67·7
June	90·8	93·4	100·6	102·8	22·2	80·6	19th	108·7	36·6	6th	72·1
July	84·7	85·9	90·3	93·2	14·3	78·9	4th	101·2	25·6	20th	75·6
August	86·0	87·9	93·0	95·6	16·5	79·1	12th	102·3	26·4	29th	75·9
September	84·0	86·9	90·0	93·5	17·0	76·5	25th	98·2	27·6	29th & 30th	70·6
October	76·8	83·4	89·3	92·5	29·3	63·2	1st	98·2	42·0	26th	56·2
November	64·8	69·6	78·0	81·3	29·9	51·4	3rd, 6th & 7th	87·2	44·1	28th	43·1
December	56·0	59·0	70·4	72·7	30·5	42·1	1st	79·2	42·2	23rd	37·0
Year	75·6	79·2	86·2	88·8	24·9	63·9	...	113·2	76·2	...	37·0

* Mean of 29 days.
† " " 28 "
‡ " " 27 "

§ Mean of 30 days.

29. AGRA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	62·2	63·5	71·8	72·8	23·5	49·3	1st & 2nd	80·6	39·7	31st	40·9
February	62·8	64·3	74·6	75·2	26·5	48·7	27th	82·9	43·3	3rd	39·6
March	76·1	78·0	87·4	89·0	27·9	61·1	30th & 31st	101·0	49·2	13th	51·8
April	90·9	93·4	103·4	104·6	30·5	74·1	21st	111·8	49·4	5th	62·4
May	94·9	96·7	105·7	107·1	26·3	80·8	20th	116·5	46·4	29th	70·1
June	94·6	96·7	103·7	105·4	21·3	84·1	3rd	114·5	37·4	30th	77·1
July	86·5	86·8	91·0	93·1	13·4	79·7	5th	101·2	25·6	21st	75·6
August	91·2	91·6	96·6	98·8	17·0	81·8	18th	106·0	27·9	6th	78·1
September	87·6	89·4	93·4	96·0	18·1	77·9	25th	102·5	28·4	25th, 29th & 30th	74·1
October	82·3	85·7	93·6	95·0	26·6	68·4	5th	100·8	43·3		57·5
November	69·5	72·5	82·1	83·4	29·5	53·9	6th	91·5	45·2	30th	46·3
December	60·9	63·4	74·0	74·8	29·6	45·2	1st	78·6	37·8	22nd	40·8
Year	80·0	81·8	89·8	91·3	24·2	67·1	...	116·5	76·9	19th	39·6

30. LUCKNOW (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	61·9	64·8	71·8	74·1	27·5	46·6	3rd	80·7	41·4	19th	39·3
February	62·7	65·5	74·3	75·2	26·8	48·4	17th & 19th	81·7	42·9	2nd	38·8
March	74·7	79·0	86·2	86·9	27·0	59·9	31st	101·0	48·6	6th	52·4
April	89·0	94·3	101·7	103·2	30·5	72·7	20th	109·0	46·5	3rd	62·5
May	92·7	95·8	104·6	105·8	28·1	77·7	19th	115·0	47·1	23rd	67·9
June	91·8	93·9	99·6	101·9	20·6	81·3	2nd	110·0	37·2	30th	72·8
July	85·5	87·1	89·5	91·8	11·8	80·0	13th	100·0	24·2	7th	75·6
August	86·9	89·0	91·8	94·2	14·2	80·0	17th	101·0	23·2	17th	77·8
September	85·2	88·2	90·9	92·8	16·2	76·6	25th & 26th	97·0	27·1	29th & 30th	69·9
October	77·8	85·0	89·5	91·9	29·4	62·5	5th	98·5	45·4	31st	53·1
November	66·6	74·7	78·0	81·8	31·8	50·0	7th	89·2	45·9	23rd & 25th	43·3
December	58·5	65·0	71·2	74·4	32·1	42·3	2nd to 4th	78·2	41·7	22nd	36·5
Year	77·8	81·9	87·4	89·5	24·7	64·8	...	115·0	78·5	...	36·5

31. GORAKHPUR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	59·9	63·9	69·8	73·8	24·7	49·1	16th	77·4	34·9	19th	42·5
February	61·2	63·7	72·2	75·6	25·6	50·0	21st	82·4	40·4	2nd	42·0
March	74·5	77·7	85·6	89·2	28·2	61·0	24th	99·4	43·6	2nd & 17th	55·8
April	85·3	89·2	97·3	100·6	29·3	71·3	15th	106·4	42·6	8th	63·8
May	89·1	90·1	100·2	102·9	25·1	77·8	19th & 20th	108·4	34·6	12th & 14th	73·8
June	86·1	87·8	91·6	96·2	17·2	79·0	2nd	109·4	37·6	6th & 7th	71·8
July	84·6	86·3	88·9	92·3	12·5	79·8	13th & 14th	99·9	23·1	17th	76·8
August	85·4	86·6	89·3	92·3	12·4	79·9	23rd	96·9	21·1	13th	75·8
September	85·0	86·6	89·2	92·1	13·7	78·4	7th	95·9	21·1	30th	74·8
October	80·1	84·5	88·9	91·8	23·4	68·4	3rd, 5th, 6th, 9th & 10th	95·9	36·6	25th & 30th	59·3
November	67·7	74·7	78·7	82·2	27·5	54·7	1st, 7th & 9th	86·4	39·0	22nd	47·4
December	60·1	65·5	70·7	74·8	28·8	46·0	4th	79·9	38·9	23rd & 25th	41·0
Year	76·6	79·7	85·2	88·7	22·4	66·3	...	109·4	68·4	...	41·0

32. JHANSI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	63·5	67·2	71·7	74·0	23·1	50·9	1st	83·4	40·0	31st	43·4
February	64·5	68·2	74·3	76·5	24·9	51·6	28th	83·9	42·5	3rd	41·4
March	77·2	81·4	87·6	90·0	26·6	63·4	31st	101·5	48·6	13th	52·9
April	91·5	98·2	102·4	105·0	29·2	75·8	25th & 29th	110·5	42·6	3rd	67·9
May	95·5	100·4	103·9	107·0	24·2	82·8	21st	115·0	45·1	27th	69·9
June	94·0	97·8	98·9	104·6	22·0	82·6	5th	114·0	38·1	27th & 28th	75·9
July	83·4	85·7	87·4	90·2	12·9	77·3	4th, 5th & 13th	96·5	22·1	4th	74·4
August	86·3	89·5	91·0	94·3	15·9	78·4	18th	102·5	27·6	3rd	74·9
September	83·9	88·0	89·1	92·2	16·0	76·2	24th & 28th	99·0	27·1	25th	71·9
October	81·3	87·9	89·3	91·8	23·6	68·2	5th	99·0	40·6	31st	58·4
November	71·6	78·3	80·2	82·8	27·3	55·5	8th	90·4	41·5	26th	48·9
December	62·4	67·9	72·6	75·3	27·7	47·6	1st	79·9	36·5	19th	43·4
Year	79·6	84·2	87·4	90·3	22·8	67·5	...	115·0	73·6	...	41·4

33. ALLAHABAD (*corrected*).

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	60·2	51·8	63·0	69·7	56·3	72·1	22·7	49·4	3rd	79·0	35·4	6th	43·6
February	61·8	51·2	64·8	74·3	56·8	76·4	28·5	47·9	20th	84·6	46·0	7th	38·6
March	75·6	63·2	80·6	88·5	70·1	90·3	29·6	60·7	31st	103·3	49·6	16th	53·7
April	89·0	74·7	95·0	102·7	83·4	104·7	32·7	72·0	20th	111·2	47·3	6th	63·9
May	93·4	81·7	98·4	105·8	87·8	108·3	29·4	78·9	19th	116·4	45·5	24th	70·9
June	90·8	83·2	94·2	98·0	87·7	102·0	20·2	81·8	3rd	111·4	34·8	27th	76·6
July	84·7	81·0	86·2	88·9	82·8*	91·5	11·9	79·6	4th	101·2	26·9	6th	74·3
August	85·8	80·8*	88·2	90·8	83·3	93·9	14·0	79·9	17th	100·2	22·5	21st	77·7
September	83·0	78·1	85·9	87·8	80·2	91·1	14·2	76·9	29th	96·3	25·0	29th	71·3
October	77·2	68·1	82·2	86·9	71·6	90·0	23·8	66·2	5th & 11th	96·4	40·2	30th	56·2
November	66·3	55·2	71·4	78·3	60·4	81·4	29·0	52·4	7th	86·7	42·9	23rd	43·8
December	58·2	47·0	61·8	71·2	52·7	73·7	29·5	44·2	1st	78·6	39·0	25th	39·6
Year	77·2	68·0	81·0	86·9	72·8	89·6	23·8	65·8	...	116·4	77·8	...	38·6

* Mean of 30 days.

34. BENARES (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	61·6	63·6	72·0	74·2	24·4	49·8	3rd	79·7	36·9	20th	42·8
February	63·2	66·6	75·8	76·8†	27·1	49·7	20th	86·2	46·8	7th	39·4
March	76·0	80·6	89·1	90·1	28·6	61·5	28th	102·1	47·6	2nd	54·5
April	88·2	93·9	102·6	103·4	30·8	72·6	20th	109·5	44·8	1st	64·7
May	92·6	95·8	105·6	106·7	26·9	79·8	19th	114·6	40·6	28th & 31st	74·0
June	88·4	91·0	94·5	100·0	19·1	80·9	3rd	109·8	36·1	12th	73·7
July	84·7	86·1	89·1	92·5	12·3	80·2	12th	103·0	26·1	6th & 7th	76·9
August	86·1	87·6	90·4	93·6	13·3	80·3	17th	99·4	21·4	4th	78·0
September	84·2	86·3	89·9	92·7	14·5	78·2	29th	98·9	27·7	30th	71·2
October	78·4	83·7	88·9	91·6	24·5	67·1	5th	98·8	39·9	30th	58·9
November	67·5	73·1	79·5	81·8	27·6	54·2	8th	87·5	42·6	23rd	44·9
December	58·5	63·3	72·1	74·1	29·6	44·5	1st	78·5	38·7	20th	39·8
Year	77·5	81·0	87·5	89·8	23·2	66·6	...	114·6	75·2	...	39·4

† Mean of 21 days.

35. GHAZIPUR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	59·4	62·9	71·0	74·2	26·4	47·8*	3rd	79·0	39·0	20th	40·0
February	60·4	65·4	74·6	77·6	31·5	46·1	20th	86·5	49·7	2nd	36·8
March	73·3	81·2	88·4	91·1	33·0	58·1	28th	101·1	50·6	2nd	50·5
April	86·1	94·0	101·3	103·4	32·5	70·9	20th	109·1	47·3	1st	61·8
May	90·4	94·9	103·3	105·2	27·8	77·4*	19th	112·5	40·4	28th	72·1
June	85·7	91·1	92·9	98·1	19·6	78·5†	3rd	107·8	37·1	21st	70·7
July	84·0	86·9	89·1	92·4	13·5	78·9‡	12th	102·8	26·5	20th	76·3
August	84·6	87·8	89·9	93·1	13·9	79·2	17th	100·4	24·5	25th	75·9
September	84·1	87·4	89·2	93·1	14·1	79·0§	28th	98·7	23·9	12th	74·8
October	76·8	83·0	89·0	92·3	27·7	64·6	1st	98·9	43·9	23rd	55·6
November	65·3	71·5	78·3	81·7	29·4	52·3	2nd	86·5	42·5	22nd	44·0
December	57·0	60·5	70·4	74·0	30·5	43·5	1st	79·1	42·8	20th	36·3
Year	75·6	80·6	86·5	89·7	25·0	64·7	...	112·5	76·2	...	36·3

36. KATMANDU (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	47·4	52·1	58·1	64·3	27·7	36·6	5th	69·7	39·2	30th	30·5
February	49·8	51·5	63·8	67·9	32·1	35·8	12th	75·1	46·1	2nd	29·0
March	57·9	62·5	72·5	77·2	33·9	43·3	30th	86·2	49·7	9th	36·5
April	63·5	72·0	77·7	84·4‡	35·2	49·2	13th	91·2	50·1	4th	41·1
May	68·1	76·6	78·9	86·6	29·3	57·3	22nd & 31st	92·2	41·8	8th	50·4
June	72·0	78·0	79·7	86·5	22·3	64·2	2nd	93·4	37·7	2nd	55·7
July	72·9	76·5	79·1	87·8*	21·2	66·6	12th & 14th	91·2	26·1	14th	65·1
August	71·9	77·0	76·9	85·3	18·4	66·9	25th	95·7	33·4	15th	62·3
September	71·1	78·2	76·9	86·3	21·1	65·2	2nd	90·5	34·2	29th	56·3
October	63·6	71·7	74·5	85·4	32·7	52·7	13th	91·7	48·6	31st	43·1
November	53·3	61·2	66·3	80·2	40·0	40·2	15th	86·2	51·7	30th	34·5
December	45·7	47·8	59·0	74·6	42·2	32·4	3rd	80·7	51·7	8th	29·0
Year	61·4	67·3	72·0	80·5	29·7	50·9	...	95·7	66·7	...	29·0

* Mean of 30 days.
† ,, ,, 28 ,,
‡ ,, ,, 24 ,,
§ ,, ,, 29 ,,

37. SIBSAGAR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	58·9	58·0	67·4	69·4	19·9	49·5	16th & 26th	72·6	27·5	21st & 27th	45·1
February	61·7	61·2	70·2	72·1	20·2	51·9	21st & 23rd	79·6	38·1	4th	41·5
March	67·8	68·3	75·3	77·3	18·7	58·6	17th	82·9	31·2	4th	51·7
April	74·4	74·9	81·5	83·5	17·4	66·1	30th	90·7	29·4	9th	61·3
May	78·3	78·8	83·0	85·4	13·6	71·8	28th	95·7	29·6	8th	66·1
June	83·5	83·4	87·7	90·9	14·0	76·9	30th	96·2	24·8	4th	71·4
July	84·9	84·0	90·6	92·6	14·4	78·2	12th	102·1	27·6	3rd & 8th	74·5
August	83·2	82·8	88·3	90·1	12·2	77·9	24th	95·5	19·5	29th	76·0
September	82·2	82·7	86·4	88·8	12·5	76·3	7th	95·3	23·9	27th	71·4
October	77·2	78·2	83·5	85·7	15·8	69·9	5th	91·1	30·8	30th	60·3
November	68·4	69·9	76·0	78·0	18·6	59·4	2nd & 4th	82·6	31·2	30th	51·4
December	59·7	59·4	67·2	69·4	19·4	50·0	9th	76·2	36·1	27th	40·1
Year	73·4	73·5	79·8	81·9	16·4	65·5	...	102·1	62·0	...	40·1

38. DHUBRI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	62·3	61·8	70·4	72·1	18·0	54·1	21st	75·7	26·5	30th	49·2
February	64·6	64·8	75·3	77·1	23·3	53·8	20th	85·9	37·4	3rd	48·5
March	75·0	75·4	86·2	87·7	23·9	63·8	24th	96·5	39·8	2nd	56·7
April	79·3	79·7	87·4	89·3	18·2	71·1	4th	98·4	31·4	25th	67·0
May	77·0	77·2	81·7	83·9	11·7	72·2	24th	93·7	28·5	8th	65·2
June	81·0	81·8	84·0	86·9	9·0	77·9	1st	93·7	18·1	3rd	75·6
July	83·0	84·1	86·2	89·1	9·4	79·7	12th	94·4	17·4	14th	77·0
August	81·2	82·3	83·9	86·5	8·0	78·5	21st	90·1	16·3	11th	73·8
September	80·6	81·7	83·7	86·8	9·3	77·5	7th	91·8	17·8	24th	74·0
October	77·8	79·0	82·8*	84·9	12·2	72·7	17th	89·3	23·6	29th	65·7
November	70·3	71·3	77·7	79·8	17·0	62·8	4th	84·3	27·8	29th	56·5
December	62·5	63·0	70·2	72·2	17·4	54·8	2nd	77·4	29·1	22nd & 24th	48·3
Year	74·6	75·2	80·8	83·0	14·8	68·2	...	98·4	50·1	...	48·3

* Mean of 30 days.

39. TURA (GARO HILLS) (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	The observatory opened in June.										
February											
March											
April											
May											
June	77·9	80·4*	81·2	84·0	9·4	74·6*	2nd	88·2	15·4	3rd, 6th & 30th	72·8
July	78·3	80·8	81·9	84·8†	10·1	74·7	11th	89·6	16·5	13th & 17th	73·1
August	77·1	80·0	79·9	82·5‡	8·3	74·2	21st	86·3	14·0	13th	72·3
September	76·9	79·9	80·4	83·3	10·0	73·3	7th	85·4	17·5	30th	67·9
October	74·3	79·5	79·4	83·0	13·8	69·2	8th & 9th	86·6	21·9	30th	64·7
November	69·1	73·2	75·5	79·0	16·4	62·6	18th.	85·9	29·6	30th	56·3
December	62·2	66·1	68·7	69·6	14·0	55·6	2nd	79·7	29·4	24th	50·3
Year	...	...	...	...	...	...	...	...	...	...	...

40. SILCHAR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	63·7	66·2	74·7	77·2	25·5	51·7	21st & 27th	81·6	37·2	31st	44·4
February	65·6	68·7	77·6	79·9	27·6	52·3	21st & 22nd	88·6	43·2	6th	45·4
March	73·9	75·4	83·9	85·0	21·4	63·6	23rd	91·1	34·5	15th	56·6
April	77·8	79·9	86·6	87·9	19·9	68·0	7th	93·5	32·9	5th	60·6
May	76·2	77·7	80·2	82·7	11·8	70·9	26th	94·4	30·1	12th	64·3
June	81·6	83·5	85·2	88·8	12·5	76·3	8th	96·5	22·3	22nd	74·2
July	83·8	85·7	88·8	91·3	14·2	77·1	11th	97·9	22·8	8th	75·1
August	81·7	82·5	86·6	88·3	12·1	76·2	17th	94·3	21·5	13th	72·8
September	81·7	82·6	86·5	88·4	12·1	76·3	6th	95·3	24·0	28th	71·3
October	79·3	81·3	86·3	88·0	16·9	71·1	9th	93·6	31·0	29th	62·6
November	72·7	75·8	81·2	83·4	20·4	63·0	5th	89·4	36·0	22nd	53·4
December	64·5	66·3	73·6	75·1	20·4	54·7	2nd	84·2	38·8	25th	45·4
Year	75·2	77·1	82·6	84·7	17·9	66·8	...	97·9	53·5	...	44·4

* Mean of 29 days. † Mean of 24 days. ‡ Mean of 28 days.

41. DARJEELING (ST. PAUL'S SCHOOL) (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	37·9	39·5	40·2	43·1	8·8	34·3*	5th to 7th	48·5	16·7	24th	31·8
February .	39·3	41·4	42·9†	46·4	12·6	33·8‡	20th	57·6	37·7	1st	19·9
March .	?	50·5§	51·3*	56·1§	Dry minimum not recorded.		25th	62·6	?	?	?
April .	?	57·5	58·5†	62·4¶			11th	66·9	?	?	?
May .	?	58·8§	60·4**	64·2			23rd	71·6	?	?	?
June .	?	61·5	63·0‖	65·7			1st	70 6	?	?	?
July .	61·8	64·1	64·4§	67·8	10·7	57·1	13th	71·4	17·0	15th	54·4
August .	60·8	62·4	62·9	66·0	8·8	57·2	1st	69·7	14·2	11th & 13th	55 5
September	59·4	61·3	61·6†	65·0	9·3	55·7	2nd	69·5	18·8	30th	50·7
October .	54·1	57·0†	56·8††	60·6¶	11·7	48·9‡	4th	64·6	22·2	30th	42·4
November	46·2	50·2¶	49·3¶	53·6¶	13·7	39·9¶	14th	58·5	27·3	29th	31·2
December	41·2	44·8	44·8	48·3	13·3	35·0	7th	55·0	28·3	19th	26·7
Year .	?	54·1	54·7	58·3	?	?	...	71·6	?	...	?

42. MONGPOO (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	52·8	57 9	10·2	47·7	15th, 20th & 21st	60·5	19·0	28th	41°5
February .	54·5	59·9	10·9	49·0	13th	68·0	27·5	2nd	40·5
March .	62·1	68·3	12·4	55·9	25th & 29th	73·5	26·0	2nd	47·5
April .	68·3	74·0	11·4	62·6	11th	79·5	22·5	3rd & 4th	57·0
May .	69·2	73·9	9·4	64·5	24th	80·0	20·0	6th & 20th	60·0
June .	72·2	76·1	7·9	68·2	1st & 8th	80·0	17·0	24th	63·0
July .	73·5	77·8	8·6	69·2	13th	83·5	16·5	14th	67·0
August .	72·2	76·5	8·6	67·9	19th	82·0	17·0	11th	65·0
September	71 3	75·5	8·4	67·1	1st, 2nd & 6th.	79·5	15·5	27th to 30th	64·0
October .	66·9	72·2	10·6	61·6	10th	76·5	21·0	30th	55·5
November	59·9	66·0	12·2	53·8	4th & 14th	70·0	20·0	28th to 30th	50·0
December	53·0	59·2	12·4	46·8	3rd, 7th & 8th.	63·0	22·5	18th	40·5
Year .	64·7	69·8	10·3	59·5	...	83·5	43·0	...	40·5

* Mean of 26 days. § Mean of 30 days. ** Mean of 25 days.
† " " 27 " ‖ " " 28 " †† " " 23 "
‡ " " 24 " ¶ " " 29 "

43. PURNEAH (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	62·0	64·2*	72·7	75·2	26·0	49·2*	20th	77·7	34·9	19th & 20th	42·8
February .	?	66·1†	Imperfect.			50·0‡	?	?	?	6th	43·3
March .	74·8	79·2	87·7	89·9	31·6	58·3	29th	99·7	47·7	16th	52·0
April .	83·1	85·6	95·0	97·1	28·4	68·7	17th	106·2	47·2	5th	59·0
May .	83·6	85·7	91·1	94·1	20·1	74·0	31st	103·7	38·8	12th	64·9
June .	84·3	86·2	89·6	92·7	15·0	77·7	1st	105·4	32·0	26th	73·4
July .	84·9	86·9	88·0	91·2	12·0	75·2	12th	98·2	21·8	19th	76·4
August .	83·4	84·8‡	86·7‡	89·4‡	11·6	77 8‡	9th	93·2	18·4	7th	74 8
September	83·4	85·0	86·7	90·2	12·6	77·6	6th	92·8	20·4	28th	72·4
October .	78 8	83·1	85·5	87·9	18·4	69·5	4th	92·5	31·1	25th & 30th	61·4
November	68 7	73·8	78·9	81·6	26·8	54·8	3rd	86·2	41·4	21st	44·8
December	59·6	63·8	72·0	75·6	30·9	44·7	3rd	81·8	44·1	21st	37·7
Year .	?	78·7	?	?	?	65·1	...	106·2	68·5	...	37·7

44. DURBHUNGA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	62·4	63·6	70·5	71·5	17·9	53·6	7th	75·2	28·9	29th	46·3
February .	63·5	65·1	73·4	74·4	21·8	52·6	21st	82·9	39·2	3rd	43·7
March .	74·7	77·3	85·6	86·4*	24·7	61·7	24th	97·2	40·3	8th	56·9
April .	83·6	86·2	94·0	94·7	24·2	70·5	15th	102·6	39·4	8th	63·2
May .	85 1	86·3	92·7	94·5	18·1	76·4	31st	102 9	36·0	21st	66·9
June .	85·0	85·8	90·1	91·4	12·3	79·1	1st & 2nd	103·4	31·1	6th	72·3
July .	84·9	86·0	87 6	90·1	9·5	80·6	12th	96 4	18·1	5th & 6th	78·3
August .	83·8	84·4	86·6	88·6	8·8	79·8	8th & 9th	92·4	17·6	12th	74·8
September	83·9	84·9	87·2	88·9	9·9	79 0	7th	91·4	17·6	24th & 27th	73·8
October .	79·8	81·6	86 1	88·7	15·0	72·4	5th	92·2	27·0	25th	65·2
November	69·5	71·7	78·9	80·0	20·8	59·2	3rd	84·2	31 8	21st	52·4
December	63·4	71·6	72·8	21·8,	51·0	3rd	78·9	33·1	19th	45·8	
Year .	76·5	78·0	83·7	85·1	17·1	68·0	...	103 4	59·7	...	43·7

* Mean of 30 days. † Mean of 19 days. ‡ Mean of 29 days.

45. PATNA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	62·1	64·0	71·2	73·0	21·4	51·6	8th	77·1	30·7	29th	46·4
February .	64·0	67·0	74·8	76·2	25·1	51·1	19th	84·8	41·9	7th	42·9
March . .	76·7	80·5	88·2	90·0	27·8	62·2	24th	101·1	44·8	16th	56·3
April . .	87·3	90·5	99·4	101·6	29·6	72·0	15th	108·6	43·1	9th	65·5
May . .	90·1	91·5	100·9	103·1	25·1	78·0	7th	110·0	37·6	11th	72·4
June . .	86·2	87·9	90·9	95·6	15·7	79·9	1st & 2nd	109·4	36·2	6th	73·2
July . .	84·4	85·3	87·0	91·9	11·7	80·2	12th	99·9	25·7	5th	74·2
August . .	84·2	85·3	86·7	90·9	11·0	79·9	4th	95·9	21·3	17th	74·6
September .	84·7	85·9	88·1	91·6	12·1	79·5	27th	96·1	20·1	13th	76·0
October .	80·4	83·6	86·9	89·7	18·5	71·2	9th	95·9	33·0	25th	62·9
November .	69·6	73·7	79·1	81·6	24·2	57·4	4th	86·6	38·4	22nd	48·2
December .	60·8	63·8	71·3	73·4	25·2	48·2	3rd	77·9	34·4	24th	43·5
Year . .	77·5	79·9	85·4	88·2	20·6	67·6	...	110·0	67·1	...	42·9

46. GYA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	64·0	67·3	72·7	75·2	22·5	52·7	4th & 8th	79·3	33·1	20th & 21st	46·2
February .	66·6	70·2	76·6	79·1	25·1	54·0	19th	89·3	46·0	7th	43·3
March . .	79·4	83·9	89·1	92·2	25·5	66·7	31st	102·5	47·7	1st	54·8
April . .	91·8	97·2	102·2	104·6	27·1	77·5	20th	109·7	39·4	1st	70·3
May . .	95·4	98·7	105·4	107·9	26·7	81·2	19th	115·8	44·5	23rd	71·3
June . .	87·8	90·1	92·8	98·0	17·4	80·6	2nd	109·4	35·6	6th	73·8
July . .	84·1	85·8	88·0	91·1	12·2	78·9	12th	99·2	28·7	5th	70·5
August . .	85·7	88·2	89·1	91·9	12·0	79·9	23rd	95·8	18·9	1st	76·9
September .	85·3	88·1	89·0	93·0	14·5	78·5	29th	96·6	23·1	19th	73·5
October .	81·5	86·8	87·8	91·9	22·0	69·9	29th	96·6	35·4	27th	61·2
November .	70·9	77·4	78·8	81·8	23·7	58·1	5th	88·2	41·0	30th	47·2
December .	62·1	68·1	72·2	75·0	27·4	47·6	3rd	78·6	36·5	25th	42·1
Year . .	79·6	83·5	87·0	90·1	21·3	68·8	...	115·8	73·7	...	42·1

47. HAZARIBAGH (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	60·4	64·3	68·5	70·9	19·8	51·1	8th	75·4	31·1	29th	44·3
February .	62·4	67·5	72·7	75·3	23·6	51·7	19th	86·2	44·3	3rd	41·9
March . .	73·2	77·7*	83·0	85·2	22·6	62·6	31st	95·3	40·7	15th	54·6
April . .	86·0	91·4	96·5	98·9	25·5	73·4	12th & 20th	104·0	36·3	4th	67·7
May . .	89·2	94·7	98·1	102·5	25·5	77·0	12th	108·3	37·8	29th	70·5
June . .	81·4	84·9	85·6	90·4	15·2	75·2	9th	100·5	28·8	6th & 30th	71·7
July . .	77·6	79·1	80·3	83·5	9·9	73·6	13th	89·3	18·1	1st & 4th	71·2
August . .	78·4	80·2	80·8	84·3	10·7	73·6	15th	89·0	18·1	6th	70·9
September .	78·1	80·6	81·4	85·1	12·2	72·9	23rd	89·3	18·8	29th	70·5
October .	75·3	79·5	82·3	84·7	18·1	66·6	4th & 9th	89·3	30·0	25th	59·3
November .	65·1	69·2	73·2	75·1	19·3	55·8	8th	79·4	30·6	22nd	48·8
December .	58·0	62·5	66·8	69·4	21·4	48·0	3rd	72·9	30·0	21st	42·9
Year . .	73·8	77·6	80·8	83·8	18·7	65·1	...	108·3	66·4	...	41·9

48. BERHAMPORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	63·8	66 5	74·3	75·8	22·6	53·2	26th	79·6	32·5	30th	47·1
February .	66·5	70·2	79·4	80·5	26·7	53·8	20th	90·6	45·2	7th	45·4
March . .	76·6	81·8	89·6	91·2	27·1	64·1	24th & 25th	101·2	43·0	15th	58·2
April . .	84·7	89·2	98·3	100·4	26·5	73·9	11th	107·2	40·0	8th, 9th & 28th.	67·2
May . .	84·3	87·8	94·0	97·5	19·9	77·6	7th	105·2	36·0	21st	69·2
June . .	82·6	85·8	87·8	91·4	13·3	78·1	2nd	102·2	27·9	9th & 19th	74·3
July . .	82·4	84·2	86·4	89·3	10·5	78·8	11th	93·7	18·9	18th	74·8
August . .	81·6	84·2	84·6	88·3	9·8	78·5	17th, 21st, 23rd & 24th.	91·1	15·6	2nd	75·5
September .	82·9	85·3	88·0	90·4	12·2	78·2	16th & 23rd	92·7	18·4	28th	74·3
October .	80·2	84·2	87·5	89·7	16·8	72·9	5th & 7th	93·7	27·0	25th	66·7
November .	70·9	75·4	80·7	82·6	22·6	60·0	12th	87·6	35·9	22nd	51·7
December .	62·3	65·2	73·0	74·6	23·2	51·4	3rd	81·6	36·5	24th	45·1
Year . .	76·6	80·0	85·3	87·6	19·3	68·4	...	107·2	62·1	...	45·1

* Mean of 30 days.

49. BURDWAN (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·7	68·5	75·0	77·3	23·8	53·5	26th	80·9	33·6	30th	47·3
February	67·4	71·4	79·2	81·2	25·8	55·4	20th	92·6	47·9	4th & 6th	44·7
March	77·3	80·7	89·1	91·2	24·1	67·1	24th	102·7	43·8	17th	58·9
April	84·2	88·0	97·2	100·3	26·0	74·3	12th	107·7	41·3	9th	66·4
May	85·3	88·7	94·8	97·9	19·3	78·6	19th, 25th & 26th	103·7	33·3	4th	70·4
June	83·5	86·5	89·3	93·1	14·3	78·8	2nd	102·6	29·2	10th & 19th	73·4
July	82·6	84·1	86·6	89·8	10·7	79·1	11th	94·5	19·1	18th	75·4
August	81·7	83·8	85·5	89·3	10·9	78·4	11th	92·4	17·0	2nd	75·4
September	82·9	85·0	87·0	90·7	11·6	79·1	24th	93·6	17·6	28th	76·0
October	80·2	84·5	87·2	90·5	17·3	73·2	6th	95·1	29·6	27th	65·5
November	71·1	75·7	79·8	82·7	21·6	61·1	4th	87·8	36·5	23rd	51·3
December	63·0	65·9	72·6	74·8	21·5	53·3	3rd	82·0	36·5	24th	45·4
Year	77·0	80·2	85·3	88·2	18·9	69·3	...	107·7	63·0	...	44·7

50. JESSORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	63·9	69·1	74·5	78·6	27·1	51·5	27th to 29th	82·6	37·1	31st	45·5
February	67·2	72·1	79·1	82·7	28·2	54·5	20th	93·5	50·4	4th	43·1
March	77·5	81·0	89·0	92·8	25·0	67·8	25th	101·8	45·0	17th	56·8
April	81·8	86·7	93·1	97·6	25·1	72·5	9th	103·4	44·1	29th	59·3
May	83·7	88·4	91·5	95·4	18·3	77·1	25th	100·1	30·6	21st	69·5
June	82·6	86·8	86·1	91·8	13·1	78·7	2nd & 8th	100·2	26·1	27th	74·1
July	82·4	84·6	86·0	89·7	10·8	78·9	11th	94·6	18·6	18th	76·0
August	82·2	85·2	84·9	89·3	10·4	78·9	22nd	93·2	17·4	1st	75·8
September	82·1	85·1	85·2	90·0	11·6	78·4	23rd	93·2	18·4	30th	74·8
October	80·4	85·2	86·8	90·4	17·1	73·3	6th	94·7	28·4	26th	66·3
November	71·0	78·0	80·0	83·9	25·0	58·9	13th	90·1	42·5	22nd	47·6
December	63·3	68·1	72·0	76·3	23·7	52·6	3rd	85·1	38·9	24th	46·2
Year	76·5	80·9	84·0	88·2	19·6	68·6	...	103·4	60·3	...	43·1

51. DACCA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	65·8	69·4	75·1	77·4	23·8	53·6	26th	81·4	34·9	31st	46·5
February	69·0	73·2	80·2	82·0	28·3	53·7	21st	91·4	46·9	1st	44·8
March	79·1	82·0	88·6	90·1	22·1	68·0	24th	97·6	38·7	15th	59·9
April	83·4	86·6*	90·7	94·6	21·2	73·4*	9th	101·7	35·4	28th	66·3
May	83·6	86·2	88·9	90·4	14·6	75·8	20th, 25th & 26th	99·0	24·3	21st	68·7
June	83·1	85·3	84·8	87·7	9·3	78·4	1st & 2nd	94·0	18·8	11th	75·2
July	83·9	85·4	86·6	88·4	9·5	78·9	11th	93·8	18·8	17th	75·0
August	83·7	84·7	85·9	87·4	8·5	78·9	22nd	90·0	13·4	14th	76·6
September	83·8	85·5	86·0	88·2	9·5	78·7	6th	91·0	15·6	29th	75·4
October	82·6	85·5	86·3	88·2	13·9	74·3	7th	91·7	24·4	23rd	67·3
November	74·0	78·7	79·9	82·7	19·2	63·5	12th	87·8	32·2	30th	55·6
December	66·4	69·9	73·0	75·5	19·8	55·7	2nd	83·5	33·1	20th	50·4
Year	78·2	81·0	83·8	86·1	16·6	69·4	...	101·7	56·9	...	44·8

52. CHITTAGONG (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	65·5	67·8	73·4	76·7	22·8	53·9	26th	81·9	34·7	31st	47·2
February	68·6	71·2	77·4	80·5	24·7	55·8	21st	88·1	40·3	5th	47·8
March	75·7	78·3	81·4	83·7	16·2	67·5	9th, 11th & 31st	86·1	26·0	17th & 18th	60·1
April	80·0	82·8	84·5	87·3	14·9	72·4	8th	91·2	24·2	24th, 25th & 27th	67·0
May	81·4	83·8	84·8	86·7	11·5	75·2	25th	90·7	23·7	10th	67·0
June	80·0	81·7	81·9	85·3	9·4	75·9	3rd	89·3	16·3	21st	73·0
July	80·3	82·1	82·3	85·0	9·0	76·0	13th	90·1	16·2	18th	73·9
August	79·9	81·5	82·2	84·3	8·7	75·6	22nd	88·0	15·0	14th	73·0
September	80·4	82·5	82·9	85·4	9·8	75·6	6th	89·9	16·9	28th	73·0
October	79·9	81·7	84·3	86·1	12·1	74·0	7th	89·3	21·3	30th	68·0
November	76·5	79·1	81·8	16·2	65·6	2nd, 3rd & 5th	86·1	33·9	23rd	52·2	
December	67·1	71·7	74·5	16·1	58·4	2nd	83·1	32·9	25th	50·2	
Year	76·0	78·2	80·3	83·1	14·3	68·8	...	91·2	44·0	...	47·2

* Mean of 29 days.

53. DEMAGIRI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	61·5	61·6	71·9	73·4	22·3	51·1	26th	77·4	31·3	31st	46·1
February	61·4	65 1	73·9	75·8	27·0	48·8	22nd	86·6	40·5	1st to 3rd, 5th to 8th, 10th, & 12th to 16th	46·1
March	71·6	76·4	80·8	83·0	20 6	62·4	25th	90·2	31·7	2nd	58·5
April	78·4	80·6	87·6	89·4	20·2	69·2	15th	93·8	28·6	8th & 9th	65·2
May	78·4	81·3	85·2	87·9	16·3	71·6	26th	97·8	31·6	11th & 17th	66·2
June	79·5	81·2	83·8	86·0	10·8	75·2	13th	95·8	22·6	10th & 21st	73·2
July	77·9	81·4	80·4	85·5	10·1	75·4	10th	93·8	19·6	3rd & 8th	74·2
August	80·0	81·2	84·5	86·4	10·9	75·5	3rd	90·8*	16·1	9th	74·7
September	78·0	80·1	82·8	84·9	11·8	73·1	6h & 14th	94·8	21·4	28th	73·4
October	79·6	81·7	85·8	87·3	13·9	73·4	4th	91·8	20·8	26th, 29th, & 30th	71·0
November	73·5	75·9	79·9	81·7	14·6	67·1	5th & 16th	86·8	26·5	22nd	60·3
December	64·6	68·5	72·0	73·4	16·3	57·1	2nd	81·9	30·6	25th & 27th	51·3
Year	73·7	76·3	80·7	82·9	16·2	66·7	...	97·8	51·7	...	46·1

54. CALCUTTA (CHOWRINGHEE) (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
66·6	69·8	75·7	77·5	20·8	56·7	24th	81·1	29·3	30th	51·8
69·4	72·1	79·4	81·9	21·8	60·1	20th	91·9	41·6	7th	50·3
78·8	81·6	89·0	91·0	20·8	70·2	25th	99·8	36·4	17th	63·4
83·7	87·7	93·1	95·3	19·6	75·7	9th	100·8	31·1	28th	69·7
85·6	89·8	92·1	95·6	15·7	79·9	25th	102·0	31·2	4th	70·8
83·4	87·0	87·6	91·3*	12·1	79·2	1st & 7th	99·0	23·2	5th & 18th	75·8
82·4	84·8	85·4	88·7	9·7	79·0	11th	92·3	16·6	18th	75·7
81·8	84·6	84·4	88·8	10 1	78·7	11th	91·3	16·3	1st	75·0
82·5	85·2	85·4	89·1	10·1	79·0	23rd	92·5	16·7	30th	75·8
80·9	84·6	87·0	89·5	14·7	74·8	5th & 7th	93·3	26·4	26th	66·9
71·7	76·5	79·3	82·7	20·3	62·4	4th	87·8	34·1	22nd	53·7
64·2	67·1	72·4	75·1	19·6	55·5	3rd	79·4	29·3	24th	50·1
77·6	80·9	84·2	87·2	16·3	70·9	...	102·0	51·9	...	50·1

* Mean of 29 days.

55. CALCUTTA (ALIPORE) (*corrected*).

Month.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	63·9	54·9	68·3	74·9	60·0	76·2	23·2	53·0	27th	80·5	32·1	20th & 21st	48·4
February	67·5	59·4	70·7	77·8	63·7	79·4	22·3	57·1*	20th	89·5	43·3	8th	46·2
March	77·9	69·8	80·5	87·4	75·0	88·9	19·6	69·3	25th	97·4	37·1	17th	60·3
April	83·8	76·1	87·0	91·5	79·6	93·8	18·8	75·0	9th	99·5	30·0	28th	69·5
May	86·1	80·1	88·7	91·0	82·6	94·1	15·2	78·9	24th	100·2	30·6	4th	69·6
June	83·9	79·8	86·2	86·8	81·1	90·8	13·1	77·7	1st	98·7	25·5	5th	73·2
July	82·8	79·4	84·1	84·7	80·7	88·0	9·5	78·5	11th	92·5	17·6	18th	74·9
August	82·4	79·1	84·0	83·6	80·5	87·3	9·0	78·3	9th	89·7	15·5	14th	74·2
September	82·7	79·1	84·2	84·6	80·5	87·8	9·4	78·4	24th	90·7	15·5	30th	75·2
October	80·1	74·3	83·4	85·9	77·2	87·8	13·9	73·9	6th	92·4	27·2	26th	65·2
November	69·8	61·9	74·8	79·4	65·4	81·2	20·2	61·0	13th	87·1	36·0	22nd	51·1
December	62·4	54·9	65·7	71·9	58·3	73·2	19·3	53·9	3rd	78·8	32·1	24th	46·7
Year	76·9	70·7	79·8	83·3	73·7	85 7	16·1	69·6	...	100·2	54·0	...	46·2

56. SAUGOR ISLAND (*corrected*).

Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range	Lowest Minimum. Day.	°
66·7	59·8	70·4	73·8	62·8	77·8	20·0	57·8	27th	81·4	30·7	20th	50·7
69·6	63·5	72·2	76·1†	66·4	81·0	20·3	60·7‡	25th	85·6	35·9	3rd	49·7
79·1	75·2	81·4	83·4	76·5	87·3	13·5	73·8	26th	96·7	29·8	10th & 12th	66·9
83·7	80·1	86·7	87·3	80·7	91·8	13·3	78·5	6th	96·0	24·5	23rd & 28th	71·5
85·8	82·8	88·3	88·9	83·0	92·2	10·6	81·6	30th	95·9	21·9	4th	74·0
84·7	82·3	86·9	87·1	82·6	90·6	9·2	81·4‡	9th	95·6	21·5	10th & 13th	74·1
82·9	80·5	84·3	85·0	81·9	87·4	7·9	79·5	11th	92·4	19·4	1st	73·0
82·5	80·6	83·1	84·8	81·3	87·4	7·9	79·5	22nd	90·4	14·4	16th	76·0
82·6	80·3	83·9	84·9	81·3	88·0	8·7	79·3	23rd	91·2	14·7	30th	76·5
80·9	77·2	83·7	84·9	77·9	87·8	11·8	76·0	9th & 10th	91·0	21·3	26th	69·7
72·5	67·6	75·2	79·0	68·3	81·4	16·1	65·3	5th	85·4	31·1	23rd	54·3
64·6	59·5	67·0	71·0	60·8	73·6	16·1	57·5	2nd	78·0	28·1	23rd	49·9
78·0	74·1	80·3	82·2	75·3	85·5	13·0	72·6	...	96·7	47·0	...	49·7

* Mean of 26 days. † Mean of 29 days. ‡ Mean of 27 days.

57. CUTTACK (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	72·1	74·4	82·1	83·9	23·0	60·3	24th	87·3	31·6	22nd	55·7
February .	75·8	77·6	86·8	88·8	24·4	64·4	21st	98·6	43·2	4th & 6th	55·4
March .	83·1	85·0	93·6	96·1	23·8	72·3	25th	105·4	39·3	18th	66·1
April .	88·2	90·9	97·0	101·5	23·3	78·2	10th	105·3	31·0	2nd	74·3
May .	89·5	93·8	96·4	103·0	23·3	79·7	11th	109·4	37·2	22nd	72·2
June .	84·1	86·4	88·3	92·9	14·5	78·4	7th	104·3	29·0	4th & 11th	75·3
July .	82·8	84·4	86·4	88·1	10·0	78·1	2nd & 11th	93·4	18·1	20th & 27th	75·3
August .	83·2	85·6	86·1	89·7	11·8	77·9	13th	93·2	18·9	16th	74·3
September	83·3	85·4	86·4	89·3	11·2	78·1	23rd	94·6	19·0	27th & 30th	75·6
October .	82·3	85·7	87·5	90·4	16·0	74·4	19th	96·4	31·0	28th	65·4
November	73·9	77·6	82·4	84·8	22·4	62·4	5th	88·4	34·0	22nd	54·4
December	66·0	69·5	75·8*	80·5	26·2	54·3	15th	82·5	33·4	22nd & 27th	49·1
Year .	80·4	83·0	87·4	90·8	19·2	71·5	...	109·4	60·3	...	49·1

58. FALSE POINT (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	66·9	70·4	73·8*	75·0	15·0	60·0	27th	77·8	23·6	22nd	54·2
February .	69·7	73·3	75·5†	76·8	12·9	63·9	21st & 25th	80·6	26·8	4th	53·8
March .	77·9	80·6	82·4	83·3	10·0	73·3	26th	90·0	22·9	9th	67·1
April .	81·1	85·7	85·2	87·9	11·0	76·9	7th	91·8	19·5	30th	72·3
May .	82·8	87·0	87·3	89·4	11·2	78·2	29th	92·8	22·1	2nd	70·7
June .	82·0	85·0	85·8	88·9	10·8	78·1	6th	102·0	27·3	12th	74·7
July .	80·7	83·7	83·7	87·0	9·3	77·7*	30th	92·4	18·5	5th	73·9
August .	80·7	84·3	84·2	87·4	10·3	77·1	3rd	91·5	18·5	16th	73·0
September	81·4	84·0	84·8	87·3	9·4	77·9	23rd	91·2	16·3	27th	74·9
October .	79·8	85·5	85·9	88·4	14·7	73·7	8th	93·5	28·6	27th	64·9
November	70·4	77·3	79·3	82·0	20·5	61·5	13th	85·6	33·7	22nd	51·9
December	62·6	69·0	71·8	74·5	21·2	53·3	31st	78·2	32·2	27th	46·0
Year .	76·3	80·5	81·6	84·0	13·0	71·0	...	102·0	56·0	...	46·0

* Mean of 30 days. † Mean of 27 days.

59. SAMBALPUR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	68·7	74·8	81·0	81·9	25·6	56·3	25th	85·7	35·8	16th	49·9
February .	74·1	80·8	87·3	88·1	27·2	60·9	21st	96·3	45·0	7th	51·3
March .	80·8	86·8	93·8	96·0	28·2	67·8	25th	103·5	44·3	17th	59·2
April .	91·0	97·4	104·5	106·4	29·0	77·4	20th	110·4	43·0	1st	67·4
May .	96·5	101·3	108·4	111·1	26·5	84·6	21st	116·1	38·3	24th	77·8
June .	87·7	90·3	94·0	96·7	15·4	81·3	4th	109·7	34·1	27th	75·6
July .	80·4	82·7	83·7	86·8	9·8	77·0	16th	91·7	17·9	28th	73·8
August .	82·3	84·6	86·7	88·9	11·1	77·8	17th	93·7	18·9	2nd, 14th & 15th	74·8
September	81·9	83·0	86·4	88·2	10·9	77·3	30th	91·7	16·9	28th	74·8
October .	79·7	84·1	87·2	88·5	16·3	72·2	6th	93·1	29·9	26th & 27th	63·2
November.	69·1	76·4	79·0	80·5	21·3	59·2	5th	85·4	35·8	22nd	49·6
December.	61·8	69·0	73·5	75·1	25·1	50·0	1st	78·0	33·3	27th	44·7
Year .	79·5	84·3	88·8	90·7	20·5	70·2	...	116·1	71·4	...	44·7

60. SAMBALPUR (New observatory) (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January .	Observatory opened on 16th October 1883.										
February .											
March .											
April .											
May .											
June .											
July .											
August .											
September											
October .							Imperfect.				
November.	69·3	77·4	79·7	80·7	21·9	58·8	5th	85·8	36·8	22nd	49·0
December.	61·7	70·2	73·8	74·8	25·3	49 5	1st	79·8	36·1	27th	43·7
Year .	...	...	...	...	...	...	...	...	...	...	...

61. RAIPUR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	67·7	72·8	78·9	80·6	24·2	56·4	25th	85·1	35·7	30th	49·4
February	72·7	77·9	85·4	87·8	27·0	59·9	19th	94·4	44·9	3rd	49·5
March	80·6	85·6	92·4	95·1	26·4	68·7	25th	104·6	43·7	17th	60·9
April	90·9	96·2	103·6	106·1	27·9	78·2	29th	110·2	40·5	6th	69·7
May	96·6	100·7	108·3	111·0	25·1	84·9	22nd	114·2	39·3	29th	74·9
June	83·1	86·9	90·1	95·5	19·5	76·0	4th	108·1	36·6	27th	71·5
July	79·1	81·8	83·9	87·6	13·4	74·2	13th	92·1	22·2	24th	69·9
August	81·8	84·8	88·2	90·6	15·2	75·4	17th	98·0	25·3	19th	72·7
September	78·6	81·6	84·2	86·6	13·6	73·0	30th	92·1	20·6	18th	71·5
October	76·8	82·0	84·8	87·1	18·4	68·7	1st	93·3	32·6	25th, 27th & 29th	60·7
November	68·2	73·8	79·4	81·2	24·2	57·0	9th	85·7	38·8	22nd	46·9
December	60·5	66·2	74·0	75·6	28·7	46·9	8th	79·2	37·8	2nd	41·4
Year	78·1	77·5	87·8	90·3	22·0	68·3	...	114·2	72·8	...	41·4

62. NAGPUR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	68·7	72·4	81·0	82·8	26·4	56·4	5th	86·1	38·9	29th	47·2
February	73·9	77·7	88·5	90·1	30·9	59·2	25th	96·8	46·7	3rd	50·1
March	81·8	87·5	96·3	98·3	31·0	67·3	25th	104·7	46·5	13th	58·2
April	90·5	98·9	104·4	107·5	31·0	76·5	29th & 30th	111·7	42·3	4th	69·4
May	95·6	102·0	108·1	111·6	28·5	83·1	20th	117·7	42·2	29th	75·5
June	83·1	87·6	89·2	96·1	19·1	77·0	4th	108·7	37·4	15th	71·3
July	79·7	82·1	84·5	87·1	12·2	74·9	4th	94·3	23·2	2nd	71·1
August	82·1	84·9	88·2	91·6	15·7	75·9	15th	99·0	26·0	31st	73·0
September	78·2	81·8	82·7	86·5	12·9	73·6	28th	91·0	19·1	26th	71·9
October	76·7	82·0	84·8	87·8	19·3	68·5	6th	94·7	35·4	29th	59·3
November	69·2	75·8	80·9	83·0	25·6	57·4	8th	87·5	37·3	25th	50·2
December	62·4	68·5	75·9	77·8	28·9	48·9	13th	82·2	39·1	18th	43·1
Year	78·5	83·4	88·7	91·4	23·5	68·2	...	117·7	74·6	...	43·1

63. SEONI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·4	70·4	76·1	78·4	25·7	52·7	3rd	83·1	39·4	28th	43·7
February	68·9	74·5	82·6	84·5	29·4	55·1	20th	90·3	46·6	2nd	43·7
March	77·3	83·9	91·3	93·3	30·1	63·2	31st	100·7	46·7	17th	54·0
April	86·3	95·6	99·5	102·4	29·3	73·1	30th	106·9	43·5	4th	63·4
May	90·3	97·9	102·7	105·5	27·7	77·8	20th	110·6	42·6	29th	68·0
June	80·0	86·0	85·3	92·2	17·6	74·6	4th	105·9	36·1	16th	69·8
July	76·5	78·9	80·9	83·4	11·4	72·0	4th	88·4	20·1	3rd & 23rd	68·3
August	78·1	82·6	83·9	87·5	15·3	72·2	14th	94·1	24·1	16th	70·0
September	75·6	79·6	80·0	83·8	12·6	71·2	28th	89·4	20·7	12th	68·7
October	72·9	80·4	81·1	84·7	20·0	64·7	5th	91·4	36·8	29th	54·6
November	65·2	74·1	77·6	79·6	26·8	52·8	8th	85·1	49·3	28th	44·8
December	58·7	66·5	72·3	74·5	29·5	45·0	13th	80·4	40·6	21st	39·8
Year	74·5	80·9	84·4	87·5	23·0	64·5	...	110·6	70·8	...	39·8

64. JUBBULPORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·0	67·1	75·7	77·8	25·5	52·3	3rd	83·6	41·6	28th & 29th	42·0
February	66·8	69·9	80·7	82·1	29·2	52·9	17th	90·9	47·0	3rd	43·9
March	77·0	81·4	90·6	92·3	28·9	63·4*	31st	101·5	50·4	16th	51·1
April	87·5	95·1	101·1	103·7	29·8	73·9	30th	107·9	46·0	1st & 3rd	61·9
May	94·5	96·7	104·2	106·3	21·5	84·8†	20th	112·5	38·0	7th	74·5
June	85·7	88·2	92·4	97·2	18·3	78·9*	4th	109·0	37·1	27th	71·9
July	78·7	79·7	83·2	85·3	11·1	74·2‡	12th	92·2	21·6	24th	70·6
August	80·6	82·8	86·2	89·4	14·5	74·9	17th	95·4	23·6	19th	71·8
September	78·2	80·2	83·1	86·2	13·0	73·2	27th	91·8	20·9	11th	70·9
October	73·8	79·3	83·0	86·3	21·8	64·5	6th	93·3	39·6	29th	53·7
November	64·6	70·0	79·1	80·9	30·8	50·1	9th	86·6	47·1	25th	39·5
December	55·8	61·3	72·2	73·9	34·5	39·4	30th	78·3	43·1	20th	35·2
Year	75·6	79·3	86·0	88·5	23·2	65·2	...	112·5	77·3	...	35·2

* Mean of 29 days. † Mean of 28 days. ‡ Mean of 30 days.

65. SAUGOR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·3	68·9	74·9	76·3	22·7	53·6	1st	83·5	39·5	27th & 28th	44·0
February	66·1	71·1	79·1	80·2	27·1	53·1	17th	89·8	49·7	2nd	40·1
March	76·1	82·6	89·1	90·6	27·6	63·0	31st	100·4	46·6	13th	53·8
April	87·8	96·3	100·7	102·5	27·7	74·8	20th	107·9	40·4	3rd	67·5
May	90·5	96·4	102·4	104·8	26·2	78·6	20th	110·9	43·7	28th	67·2
June	84·4	88·7	92·2	97·8	21·3	76·5*	3rd	106·9	37·7	19th	69·2
July	78·3	79·4	83·0	84·8	11·3	73·5	12th	90·8	21·2	2nd	69·6
August	79·1	82·4	85·1	87·7	14·6	73·1	19th	95·4	24·8	11th	70·6
September	77·5	81·1	83·1	85·7	13·8	71·9	25th & 28th	91·4	22·9	29th	68·5
October	74·4	81·0	83·2	85·6	20·0	65·6	5th & 12th	90·8	34·0	29th	56·8
November	67·4	75·8	78·6	80·7	24·5	56·2	7th to 9th	85·3	37·4	25th	47·9
December	60·1	67·6	72·0	73·3	25·2	48·1	1st	78·3	36·2	13th	42·1
Year	75·5	80·9	85·3	87·5	21·8	65·7	...	110·9	70·8	...	40·1

* Mean of 28 days.

66. PACHMARHI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	58·4	66·1	68·3	71·7	23·3	48·4	1st	75·8	40·4	28th	35·4
February	62·3	70·1	74·1	76·4	26·0	50·4	17th	82·7	41·3	3rd	41·4
March	71·0	76·7	82·0	83·7	23·7	60·0	28th	92·4	42·3	17th	50·1
April	81·2	87·3	91·9	94·4	24·0	70·4	19th	99·4	39·7	4th	59·7
May	84·8	87·5	94·1	95·9	20·4	75·5	20th	101·4	40·3	2nd	61·1
June	77·1	79·7	83·0	86·4	15·3	71·1	3rd	97·7	31·0	6th & 24th	66·7
July	70·3	70·8	73·4	75·4	8·2	67·2	14th	80·4	16·2	26th	64·2
August	71·6	73·2	75·9	78·2	11·0	67·2	18th	84·3	19·6	20th	64·7
September	69·8	72·2	73·3	75·8	9·5	66·3	28th	81·6	19·1	28th	62·5
October	66·2	73·4	72·9	76·0	16·6	59·4	5th	81·6	31·5	30th	50·1
November	57·7	68·0	68·6	71·2	24·5	46·7	9th	74·8	36·9	25th	37·9
December	51·2	62·0	63·4	66·7	27·7	39·0	13th & 29th	72·3	38·7	18th	33·6
Year	68·5	73·9	76·7	79·3	19·2	60·1	...	101·4	67·8	...	33·6

67. HOSHANGABAD (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	67·0	68·1	79·3	81·0	26·4	54·6	2nd	85·9	45·8	28th	40·1
February	69·5	72·2	84·0	85·4	30·4	55·0	17th	93·7	48·1	3rd	45·6
March	78·9	83·8	93·3	94·9	30·4	64·5	31st	103·0	45·9	12th	57·1
April	89·4	96·6	104·2	106·5	32·0	74·5	20th	111·2	45·4	3rd	65·8
May	93·1	96·3	105·8	107·9	27·6	80·3	20th	115·6	43·4	28th	72·2
June	86·3	88·0	94·7	97·6	19·8	77·8	3rd	111·4	39·7	24th	71·7
July	79·0	80·5	83·0	86·2	11·2	75·0	14th	91·6	18·9	3rd	72·7
August	79·8	82·0	85·3	88·7	14·4	74·3	19th	94·5	21·5	13th	73·0
September	78·3	78·9	83·0	85·5	12·0	73·5	28th	91·9	21·7	11th	70·2
October	75·4	79·1	83·4	86·5	19·2	67·3	4th	92·5	35·0	30th	57·5
November	67·3	72·0	80·1	81·9	27·5	54·4	7th	86·1	40·3	24th	45·8
December	59·2	62·8	73·4	75·3	30·3	45·0	1st	79·0	37·9	18th & 20th	41·1
Year	76·9	80·0	87·5	89·8	23·4	66·4	...	115·6	75·5	...	40·1

68. KHANDWA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	67·9	75·1	82·1	83·6	29·9	53·7	1st	89·3	49·7	29th	39·6
February	70·8	76·9	87·0	88·3	33·7	54·6	17th	95·5	51·5	1st	44·0
March	79·3	85·4	93·9	95·4	30·7	64·7	31st	103·0	49·3	12th	53·7
April	89·5	97·2	103·4	106·0	30·5	75·5	20th	110·4	45·1	6th	65·3
May	92·6	95·6	104·2	106·3	25·4	80·9	20th	112·0	38·0	27th	74·0
June	84·4	87·4	91·8	95·3	18·3	77·0	3rd	108·8	37·7	11th	71·1
July	79·1	80·4	83·6	86·5	11·9	74·6	4th & 13th	91·2	20·2	3rd	71·0
August	79·8	80·4	85·8	87·8	14·1	73·7	18th	95·2	24·1	26th	71·1
September	77·8	78·3	82·9	84·2	11·6	72·6	27th	90·9	20·6	13th	70·3
October	75·1	80·0	83·9	86·5	20·3	66·2	12th	92·5	37·3	30th	55·2
November	67·4	76·4	82·2	83·5	30·9	52·6	8th & 9th	86·9	42·7	27th	44·2
December	59·3	67·5	76·3	77·8	35·5	42·3	29th	83·9	46·5	18th	37·4
Year	76·9	81·7	88·1	90·1	24·4	65·7	...	112·0	74·6	...	37·4

69. CHANDA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. o	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. o
January .	69·0	74·7	82·6	85·5	30·2	55·3	31st	89·0	42·8	29th	46·2
February .	76·0	80·1	91·6	93·6	33·3	60·3	25th	100·5	50·4	2nd	50·1
March .	82·6	89·3	96·9	100·0	31·7	68·3	31st	107·3	46·3	17th	61·0
April .	91·8	98·2	106·1	108·9	31·5	77·4	29th	113·1	44·2	5th & 6th	68·9
May .	97·0	101·8	109·7	112·2	28·0	84·2	21st	116·3	40·2	7th	76·1
June .	85·0	87·0	91·5	95·5	17·0	78·5	3rd	109·8	37·0	7th	72·8
July .	80·8	82·9	85·4	88·1	12·0	76·1	29th	93·9	20·9	3rd	73·0
August .	81·6	84·7	87·2	90·7	14·8	75·9	18th	97·7	24·8	23rd	72·9
September .	78·6	81·2	83·1	86·8	12·8	74·0	28th	91·3	19·5	11th	71·8
October .	77·4	82·1	85·6	88·3	19·1	69·2	6th	94·1	36·0	26th	58·1
November .	67·6	73·6	79·4	82·3	26·5	55·8	9th	86·4	40·8	28th	45·6
December .	60·5	65·9	76·1	78·4	33·5	44·9*	13th	82·2	43·6	19th	38·6
Year . .	79·0	83·5	89·6	92·5	24·2	68·3	...	116·3	77·7	...	38·6

* Mean of 29 days.

70. SIRONCHA (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. o	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. o
71·8	74·2	83·2	85·5	25·2	60·3	25th	89·7	34·6	29th	55·1
78·7	79·9	91·7	93·8	28·1	65·7	26th	101·1	43·0	5th	58·1
84·8	84·9	95·0	98·7	24·1	74·6	31st	105·9	35·9	17th	70·0
92·4	90·8	104·2	106·5	26·0	80·5	30th	112·9	39·4	6th	73·5
97·4	97·4	108·1	111·3	24·6	86·7	21st	115·9	36·5	28th	79·4
84·1	84·3	89·2	93·0	14·1	78·9	1st	107·2	34·3	2nd	72·9
80·2	81·4	83·8	86·9	10·4	76·5	4th	92·7	20·3	8th	72·4
81·0	82·2	85·0	88·5	11·6	76·9	14th	94·8	21·9	23rd	72·9
79·0	80·2	82·3	85·8	10·1	75·7	27th	90·8	17·9	3rd	72·9
79·6	82·1	85·9	89·6	16·3	73·3	8th	93·3	28·7	27th	64·6
71·4	72·8	81·4	84·1	22·7	61·4	4th	88·7	35·4	24th	53·3
65·3	65·4	77·6	79·7	26·7	53·0	13th	83·1	36·5	28th	46·6
80·5	81·3	89·0	92·0	20·0	72·0	...	115·9	69·3	...	46·6

71. CHIKALDA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. o	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. o
January .	63·4	66·2	70·2	72·9	16·3	56·6	1st & 2nd	77·4	34·2	28th	43·2
February .	68·8	72·2	77·1	79·1	18·7	60·4	23rd	83·9	37·8	1st	46·1
March .	74·2	77·1	83·0	84·7	19·4	65·3	31st	91·6	37·2	12th	54·4
April .	83·0	86·5	91·3	93·5	18·9	74·6	20th	97·2	30·6	5th	66·6
May .	82·7	84·9	92·5	94·4	21·6	72·8	20th	100·4	36·5	27th	63·9
June .	73·5	75·1	79·1	82·5	14·7	67·8	3rd & 4th	95·2	31·0	24th	64·2
July .	68·7	68·9	72·1	74·1	8·8	65·3	13th	79·4	16·4	2nd	63·0
August .	69·3	70·3	73·6	75·1	10·1	65·0	18th	80·7	17·4	20th	63·3
September .	66·5	69·3	68·8	72·7	8·0	64·7	28th	80·2	18·2	10th	62·0
October .	67·3	72·4	71·6	75·5	12·5	63·0	5th	79·4	21·6	24th	57·8
November .	63·5	68·8	69·8	73·1	16·0	57·1	5th & 13th	75·4	23·7	22nd	51·7
December .	58·8	64·1	65·7	68·9	17·1	51·8	12th	72·2	24·6	19th	47·6
Year . .	70·0	73·0	76·2	78·9	15·2	63·7	...	100·4	57·2	...	43·2

72. BULDANA (*corrected*).

Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. o	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. o
68·4	73·5	78·4	80·9	22·5	58·4	1st	88·0	37·9	28th	50·1
74·0	77·9	85·5	87·0	24·6	62·4	17th and 24th	92·4	42·3	2nd	50·1
79·4	81·7	89·9	92·1	23·2	68·9	27th and 31st	99·1	37·9	12th	61·2
88·0	92·3	98·6	100·8	23·5	77·3	12th and 21st	104·4	34·7	4th	69·7
88·3	90·6	99·6	101·5	24·5	77·0	19th	109·1	37·6	31st	71·5
78·8	80·7	86·1	89·0	17·6	71·4	3rd	100·4	32·7	24th	67·7
74·6	76·3	79·5	82·0	12·4	69·6	4th	86·8	20·5	2nd	66·3
74·5	75·5	80·2	82·4	13·6	68·8	18th	89·2	23·2	23rd	66·0
72·3	73·7	76·5	79·2	11·2	68·0	27th	83·9	18·1	12th	65·8
72·7	77·8	78·2	81·3	14·1	67·2	11th	86·4	25·0	24th	61·4
68·4	75·4	77·1	79·2	19·6	59·6	9th	83·0	28·9	28th	54·1
63·2	69·6	72·8	75·0	21·5	53·5	29th	79·7	30·1	20th	49·6
75·2	78·8	83·5	85·9	19·0	66·8	...	109·1	59·5	...	49·6

73. AKOLA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	69·4	75·0	83·5	85·2	29·0	55·3	1st & 24th	89·0	48·8	28th	40·2	70·0	75·1	82·3	84·6	26·9	57·7	24th	88·5	44·5	28th	44·0
February	74·2	80·2	91·1	92·1	34·8	57·3	17th	97·2	52·0	2nd	45·2	75·5	80·6	89·5	91·5	30·1	61·4	17th	96·1	46·2	1st	49·9
March	81·6	88·1	97·0	98·1	31·0	66·2	31st	104·3	49·9	13th	54·4	81·8	88·3	96·0	98·4	30·9	67·5	31st	105·2	46·8	13th	58·4
April	90·4	98·6	105·5	106·9	31·6	75·3	21st	110·7	44·8	8th	65·0	90·2	96·0	103·9	106·8	30·4	76·4	30th	110·5	44·0	5th	66·5
May	94·1	97·5	106·7	108·0	26·6	81·4	20th	113·7	38·3	5th	75·4	92·6	98·5	106·2	109·0	30·0	79·0	20th	114·3	40·9	14th	73·4
June	83·4	85·4	91·8	94·1	19·2	74·9	2nd	105·3	33·0	24th	72·3	81·7	85·4	89·0	95·2	20·8	74·4	4th	106·7	35·5	8th	71·2
July	79·1	80·8	85·0	86·0	13·7	73·2	13th	91·4	21·7	3rd	69·7	77·6	80·2	82·6	86·6	14·0	72·6	13th	92·0	26·2	2nd	65·8
August	80·2	82·3	86·0	88·6	15·2	73·4	18th	96·9	26·2	6th & 20th	70·7	79·9	82·3	87·1	89·7	17·4	72·6	15th	98·1	28·3	23rd	69·8
September	77·2	79·3	82·4	84·5	12·6	71·9	27th	90·9	22·1	12th	68·8	75·7	79·6	80·3	84·6	13·5	71·1	27th	90·7	22·9	13th	67·8
October	75·6	80·8	83·6	86·8	19·2	67·6	11th	92·8	35·6	30th	57·2	74·9	81·1	82·4	86·6	19·2	67·4	12th	95·5	36·7	29th	58·8
November	68·7	76·4	82·3	83·9	28·8	55·1	5th	87·6	42·1	28th	45·5	69·3	76·2	80·8	83·2	25·5	57·7	8th	87·1	36·2	26th	50·9
December	60·9	68·0	77·6	78·9	34·8	44·1	13th	83·6	44·2	18th	39·4	63·9	70·2	76·9	78·8	27·9	50·9	13th	83·7	35·8	6th & 30th	47·9
Year	77·9	82·7	89·5	91·2	24·9	66·3	...	113·7	74·3	...	39·4	77·8	83·0	88·1	91·3	23·9	67·4	...	114·3	70·3	...	44·0

74. AMRAOTI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	69·4	75·0	83·5	85·2	29·0	55·3	1st & 24th	89·0	48·8	28th	40·2	70·0	75·1	82·3	84·6	26·9	57·7	24th	88·5	44·5	28th	44·0
February	74·2	80·2	91·1	92·1	34·8	57·3	17th	97·2	52·0	2nd	45·2	75·5	80·6	89·5	91·5	30·1	61·4	17th	96·1	46·2	1st	49·9
March	81·6	88·1	97·0	98·1	31·0	66·2	31st	104·3	49·9	13th	54·4	81·8	88·3	96·0	98·4	30·9	67·5	31st	105·2	46·8	13th	58·4
April	90·4	98·6	105·5	106·9	31·6	75·3	21st	110·7	44·8	8th	65·0	90·2	96·0	103·9	106·8	30·4	76·4	30th	110·5	44·0	5th	66·5
May	94·1	97·5	106·7	108·0	26·6	81·4	20th	113·7	38·3	5th	75·4	92·6	98·5	106·2	109·0	30·0	79·0	20th	114·3	40·9	14th	73·4
June	83·4	85·4	91·8	94·1	19·2	74·9	2nd	105·3	33·0	24th	72·3	81·7	85·4	89·0	95·2	20·8	74·4	4th	106·7	35·5	8th	71·2
July	79·1	80·8	85·0	86·0	13·7	73·2	13th	91·4	21·7	3rd	69·7	77·6	80·2	82·6	86·6	14·0	72·6	13th	92·0	26·2	2nd	65·8
August	80·2	82·3	86·0	88·6	15·2	73·4	18th	96·9	26·2	6th & 20th	70·7	79·9	82·3	87·1	89·7	17·4	72·6	15th	98·1	28·3	23rd	69·8
September	77·2	79·3	82·4	84·5	12·6	71·9	27th	90·9	22·1	12th	68·8	75·7	79·6	80·3	84·6	13·5	71·1	27th	90·7	22·9	13th	67·8
October	75·6	80·8	83·6	86·8	19·2	67·6	11th	92·8	35·6	30th	57·2	74·9	81·1	82·4	86·6	19·2	67·4	12th	95·5	36·7	29th	58·8
November	68·7	76·4	82·3	83·9	28·8	55·1	5th	87·6	42·1	28th	45·5	69·3	76·2	80·8	83·2	25·5	57·7	8th	87·1	36·2	26th	50·9
December	60·9	68·0	77·6	78·9	34·8	44·1	13th	83·6	44·2	18th	39·4	63·9	70·2	76·9	78·8	27·9	50·9	13th	83·7	35·8	6th & 30th	47·9
Year	77·9	82·7	89·5	91·2	24·9	66·3	...	113·7	74·3	...	39·4	77·8	83·0	88·1	91·3	23·9	67·4	...	114·3	70·3	...	44·0

75. MAKHLA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·5	66·4	71·7	75·3	18·0	57·3	2nd	78·9	36·6	28th	42·3	62·6	64·7	75·5	76·9	27·2	49·7	5th	83·9	46·1	28th	37·8
February	68·8	72·0	77·7	83·1	23·2	59·9	24th	87·6	43·9	1st	43·7	63·1	68·4	77·1	78·8	29·7	49·1	17th	87·9	49·3	1st	38·6
March	75·5	77·4	85·3	89·7	24·0	65·7	30th	96·6	41·0	12th	55·6	73·7	81·4	86·8	88·9	28·4	60·5	26th	98·9	49·8	12th	49·1
April	84·9	88·7	94·6	98·5	23·3	75·2	10th	103·0	38·4	4th	64·6	86·2	95·2	100·3	101·9	29·8	72·1	11th & 21st	106·8	41·7	5th	65·1
May	85·2	88·4	96·0	99·4	25·1	74·3	20th	105·0	37·6	27th	67·4	87·5	93·2	100·0	102·6	27·7	74·9	19th	112·7	48·7	27th	64·0
June	75·3	78·0	80·4	86·2	16·1	70·1	3rd	99·6	33·0	24th	66·6	85·6	88·4	94·5	97·6	20·9	76·7	9th	106·8	36·8	27th	70·0
July	70·8	71·6	73·8	76·7	9·0	67·7	13th	82·1	16·8	3rd	65·3	78·1	80·7	83·1	85·9	12·8	73·1	9th	89·3	19·7	3rd	69·6
August	71·0	72·0	75·3	78·1	11·4	66·7	15th	84·9	20·6	5th	64·3	79·5	83·2	86·6	89·4	17·1	72·3	26th	96·9	27·3	13th	69·6
September	68·7	70·1*	70·5*	73·4*	6·6	66·8*	26th	81·2	18·4	30th	62·8	76·6	80·3	81·8	84·9	13·6	71·3	25th	91·8	23·2	30th	68·6
October	68·4	72·8	73·3	77·5	14·0	63·5	3rd	82·7	25·9	25th	56·8	74·2	82·0	84·7	87·8	24·2	63·6	5th.	91·9	37·8	30th	54·1
November	63·5	66·6	70·1	74·3	17·4	56·9	4th	77·3	25·8	22nd	51·5	66·0	75·3	80·2	83·0	31·2	51·8	11th	91·9	45·0	23rd	46·9
December	63·1	61·6	67·2	69·6	10·6	59·0	13th	74·5	27·7	19th	46·8	59·6	66·5	72·6	74·9	29·5	45·4	29th	80·9	39·0	18th	41·9
Year	71·6	73·8	78·0	81·8	16·6	65·3	...	105·0	62·7	...	42·3	74·3	79·9	85·3	87·7	24·3	63·4	...	112·7	74·9	...	37·8

76. NEEMUCH (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·5	66·4	71·7	75·3	18·0	57·3	2nd	78·9	36·6	28th	42·3	62·6	64·7	75·5	76·9	27·2	49·7	5th	83·9	46·1	28th	37·8
February	68·8	72·0	77·7	83·1	23·2	59·9	24th	87·6	43·9	1st	43·7	63·1	68·4	77·1	78·8	29·7	49·1	17th	87·9	49·3	1st	38·6
March	75·5	77·4	85·3	89·7	24·0	65·7	30th	96·6	41·0	12th	55·6	73·7	81·4	86·8	88·9	28·4	60·5	26th	98·9	49·8	12th	49·1
April	84·9	88·7	94·6	98·5	23·3	75·2	10th	103·0	38·4	4th	64·6	86·2	95·2	100·3	101·9	29·8	72·1	11th & 21st	106·8	41·7	5th	65·1
May	85·2	88·4	96·0	99·4	25·1	74·3	20th	105·0	37·6	27th	67·4	87·5	93·2	100·0	102·6	27·7	74·9	19th	112·7	48·7	27th	64·0
June	75·3	78·0	80·4	86·2	16·1	70·1	3rd	99·6	33·0	24th	66·6	85·6	88·4	94·5	97·6	20·9	76·7	9th	106·8	36·8	27th	70·0
July	70·8	71·6	73·8	76·7	9·0	67·7	13th	82·1	16·8	3rd	65·3	78·1	80·7	83·1	85·9	12·8	73·1	9th	89·3	19·7	3rd	69·6
August	71·0	72·0	75·3	78·1	11·4	66·7	15th	84·9	20·6	5th	64·3	79·5	83·2	86·6	89·4	17·1	72·3	26th	96·9	27·3	13th	69·6
September	68·7	70·1*	70·5*	73·4*	6·6	66·8*	26th	81·2	18·4	30th	62·8	76·6	80·3	81·8	84·9	13·6	71·3	25th	91·8	23·2	30th	68·6
October	68·4	72·8	73·3	77·5	14·0	63·5	3rd	82·7	25·9	25th	56·8	74·2	82·0	84·7	87·8	24·2	63·6	5th.	91·9	37·8	30th	54·1
November	63·5	66·6	70·1	74·3	17·4	56·9	4th	77·3	25·8	22nd	51·5	66·0	75·3	80·2	83·0	31·2	51·8	11th	91·9	45·0	23rd	46·9
December	63·1	61·6	67·2	69·6	10·6	59·0	13th	74·5	27·7	19th	46·8	59·6	66·5	72·6	74·9	29·5	45·4	29th	80·9	39·0	18th	41·9
Year	71·6	73·8	78·0	81·8	16·6	65·3	...	105·0	62·7	...	42·3	74·3	79·9	85·3	87·7	24·3	63·4	...	112·7	74·9	...	37·8

* Mean of 25 days.

77. NOWGONG *(corrected)*.

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	60·8	65·5	72·4	75·5	26·3	49·2	2nd & 3rd	82·6	41·2	28th	41·4
February	62·2	68·3	76·3	78·7	30·7	48·0	18th	86·1	48·0	2nd	38·1
March	75·0	82·3	90·2	92·8	33·1	59·7	31st	104·0	52·2	16th	51·8
April	87·5	97·7	103·8	106·7	35·6	71·1	22nd, 24th & 30th	112·0	51·3	6th	60·7
May	92·3	100·7	105·0	109·5	29·9	79·6	19th & 20th	116·5	44·4	27th	72·1
June	91·2	95·1	99·8	105·4	22·8	82·6	11th	114·0	37·8	20th & 28th	76·2
July	82·2	84·3	86·6	90·1	12·3	77·8	5th	97·7	23·3	7th	74·4
August	83·8	87·3	89·3	93·4	15·1	78·3	19th	100·0	24·3	6th	75·7
September	82·1	85·6	88·1*	92·6	16·5	76·1	27th	97·5	26·4	26th	71·1
October	76·2	82·6	86·5	91·6	25·8	65·8	5th	97·7	40·3	29th	57·4
November	65·3	71·5	79·7	83·2	32·3	50·9	8th	91·1	48·7	22nd	42·4
December	56·8	61·7	72·0	75·1	33·5	41·6	30th	82·1	44·5	19th	37·6
Year	76·3	81·9	87·5	91·2	26·2	65·1	...	116·5	78·9	...	37·6

78. SUTNA *(corrected)*.

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	60·2	65·3	71·8	72·5	23·9	48·6	2nd	81·6	41·4	28th	40·2
February	62·2	67·4	76·0	76·4	28·1	48·3	19th	84·3	46·0	7th	38·3
March	74·1	81·1	88·3	88·6	28·8	59·8	31st	100·6	48·3	16th	52·3
April	86·4	95·9	101·6	101·9	30·8	71·1	21st & 22nd	106·6	44·4	5th	62·2
May	91·3	99·8	104·6	105·2	27·3	77·9	21st	111·8	41·2	25th	70·6
June	89·0	93·9	96·9	97·5	16·5	81·0	3rd & 10th	108·3	32·7	29th	75·6
July	81·1	83·0	85·9	86·3	10·1	76·2†	5th	94·3	23·4	12th	70·9
August	82·5	85·2	88·1	88·5	11·7	76·8	17th	96·3	22·4	21st	73·9
September	80·3	83·7	85·8	86·1	11·3	74·8	29th	92·6	22·5	29th	70·1
October	75·0	82·1	84·9	85·2	20·2	65·0	5th	92·3	38·1	30th	54·2
November	64·6	73·9	78·7	79·1	28·7	50·4*	7th	85·8	43·6	22nd	42·2
December	56·9	64·2	71·8	72·0	30·1	41·9	30th	77·8	40·7	27th	37·1
Year	75·3	81·3	86·2	86·6	22·3	64·3	...	111·8	74·7	...	37·1

* Mean of 29 days. † Mean of 30 days.

79. INDORE *(corrected)*.

Month.	Mean.	10 hours.	16 hours.	Mean of maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	64·2	72·2	76·9	79·2	27·8	51·4	3rd	84·9	45·9	28th	39·0
February	65·4	74·0	80·7	82·7	32·6	50·1	17th	89·9	51·2	2nd	38·7
March	73·8	82·0	88·0	90·2	30·6	59·6	27th, 28th & 30th	97·2	45·0	12th	52·2
April	84·7	94·9	98·8	101·7	31·2	70·5	20th	106·5	44·5	6th	62·0
May	87·4	93·2	99·8	102·3	27·3	75·0	19th	109·0	43·8	27th	65·2
June	81·7	85·5	89·3	93·5	19·4	74·1	3rd	106·8	36·9	24th	69·9
July	76·3	77·7	81·0	83·7	12·1	71·6	13th	89·7	21·8	3rd	67·9
August	76·6	79·8	83·0	86·0	15·8	70·2	18th	91·6	23·7	13th	67·9
September	74·7	77·4	79·5	83·3	13·5	69·8	29th	93·1	27·7	30th	65·4
October	71·6	79·7	80·1	84·1	21·0	63·1	4th	90·3	39·3	31st	51·0
November	64·3	76·1	78·0	80·4	29·8	50·6	8th	85·1	41·9	23rd	43·2
December	57·4	69·4	72·0	74·8	32·0	42·8	29th	81·1	42·4	17th	38·7
Year	73·2	80·2	83·9	86·8	24·4	62·4	...	109·0	70·3	...	38·7

80. BICKANEER *(corrected)*.

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	60·0	61·3	69·1	70·6	19·8	50·8	15th & 19th	77·5	34·4	31st	43·1
February	62·9	66·7	73·4	74·4	22·0	52·4	28th	85·0	42·1	6th	42·9
March	74·2	77·3	84·7	85·9	22·3	63·6	30th	99·1	46·1	6th	53·0
April	89·5	93·1	101·1	101·8	24·0	77·8	22nd	108·1	42·3	3rd	65·8
May	92·8	94·7	103·1	103·9	21·5	82·4	20th	115·1	47·3	27th	67·8
June	97·0	97·6	106·2	106·7	19·0	87·7	3rd	111·1	28·4	1st & 28th	82·7
July	89·2	90·0	96·1	96·8	14·6	82·2	9th	102·6	24·9	17th	77·7
August	91·6	91·3	100·6	Not recorded.		82·6	?	?	?	6th	79·7
September	87·0	88·6	93·8	Ditto		80·2	?	?	?	30th	75·7
October	83·0	86·4	93·1	Imperfect.		72·9	?	?	?	31st	61·9
November	69·3	70·4	79·4	80·5	21·3	59·2	7th	92·2	40·2	22nd	52·0
December	61·1	61·4	72·0	73·1	22·9	50·2	27th	77·1	30·1	31st	47·0
Year	79·8	81·6	89·4	?	?	70·2	...	115·1	72·2	...	42·9

81. JEYPORE (*corrected*).

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	60·8	52·7	64·8	70·8	54·9	73·3	23·3	50·0	1st	81·7	43·3	27th	38·4	57·8	61·5	70·6	72·1	25·9	46·2	22nd	78·4	39·7	27th & 31st.	38·7
February	62·0	52·1	66·2	73·6	50·1	75·4	26·0	49·4	16th	83·2	44·0	2nd	39·2	60·2	64·1	73·7	74·4	28·4	46·0	10th	82·4	46·6	1st	35·8
March	73·6	62·7	78·7	85·1	67·7	87·8	27·6	60·2	30th	90·4	48·5	13th & 15th.	50·6	72·2	77·5	85·3	86·4	29·1	57·3	30th	98·4	49·9	15th	48·5
April	87·7	75·3	94·4	100·5	80·7	102·9	30·8	72·1	23rd	108·2	44·3	4th	63·0	87·5	93·4	99·8	101·7	30·6	71·1	22nd	109·6	50·3	3rd	59·3
May	89·2	77·4	94·3	100·0	84·3	103·0	29·1	74·8	20th	113·3	47·3	29th	69·0	91·0	94·1	101·6	102·7	23·3	79·4	20th	111·7	44·0	26th	67·7
June	88·9	80·2	93·5	97·2	84·7	101·8	23·3	78·5	3rd & 4th	109·2	35·9	7th	73·3	90·6	93·5	99·0	101·8	19·6	82·2	10th	112·7	36·7	28th	76·0
July	82·5	77·1	84·2	88·3	80·2	90·6	15·1	75·5	29th	96·6	24·9	27th	71·7	83·0	84·5	88·8	90·5	12·9	77·6*	2nd	97·1	24·2	3rd	72·9
August	85·8	77·6	88·0	93·7	83·0	67·3	21·3	76·0	26th	104·3	32·3	8th	72·0	85·9	87·6	94·6	96·3	18·1	78·2	26th	104·6	30·5	5th	74·1
September	82·6	76·2	85·0	89·8	78·3	93·3	18·0	74·4	26th	100·1	29·9	23rd	70·2	82·2	85·1	89·7	91·6	15·8	75·8	24th	97·1	25·0	23rd & 26th.	72·1
October	78·3	69·4	85·0	89·9	71·7	93·2	29·8	63·4	4th	98·0	44·8	30th	53·2	76·8	84·5	89·9	91·4	27·2	64·2	4th	97·1	42·8	30th & 31st.	54·3
November	66·7	53·7	74·5	79·5	59·2	82·9	32·3	50·6	6th to 8th	90·1	45·5	23rd	44·6	63·9	71·0	79·7	80·9	30·6	50·3	6th to 9th	87·5	44·4	23rd	43·1
December	59·4	47·5	66·4	72·4	51·4	75·2	30·8	44·4	21st	78·4	39·4	18th	39·0	56·1	62·6	72·0	73·6	31·5	42·1	10th	79·3	42·0	18th	37·3
Year	76·5	66·7	81·4	86·8	71·0	89·8	25·7	64·1	...	113·3	74·9	...	38·4	75·6	79·9	87·1	88·6	24·4	64·2	...	112·7	76·9	...	35·8

* Mean of 30 days.

82. SAMBHAR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	58·4	62·6	70·9	73·0	26·5	46·5	1st	79·1	45·0	31st	34·1
February	60·2	65·2	73·5	75·3	29·7	45·6	28th	84·1	50·0	1st	34·1
March	71·5	76·6	83·7	85·3	27·8	57·5	30th	95·0	47·7	15th	47·3
April	86·1	90·6	97·9	99·1	27·6	71·5	19th	105·0	41·8	5th	63·2
May	88·8	90·0	99·5	100·6	21·7	78·9	20th	109·0	45·8	26th	63·2
June	87·8	89·0	96·3	98·2	17·3	80·9	3rd & 9th to 12th.	102·0	29·8	1st	72·2
July	80·8	82·1	86·1	87·8	11·9	75·9	2nd	93·0	19·8	3rd, 8th & 27th.	73·2
August	83·7	84·0	92·2	94·1	16·7	77·4	28th	104·0	29·5	10th & 11th	74·2
September	80·2	82·2	86·8	89·0	14·1	74·9	26th	95·0	25·8	25th	68·2
October	75·3	83·1	87·9	90·2	27·3	62·9	4th, 10th & 17th	94·0	43·7	30th & 31st	50·3
November	63·4	74·0	78·2	81·0	33·1	47·9	2nd	89·1	48·9	18th	40·2
December	56·1	64·8	72·4	74·2	33·9	40·3	1st	82·1	45·0	18th	34·1
Year	74·4	78·7	85·5	87·3	24·0	63·4	...	109·0	74·9	...	34·1

83. AJMERE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	57·4	60·9	63·4	67·1	15·8	51·3	5th	74·0	35·0	26th	39·0
February	59·0	62·5	65·7	69·5	17·2	52·3	27th	76·2	37·9	1st	38·3
March	66·2	69·4	73·2	76·2	17·1	59·1	29th	86·9	36·9	7th	50·0
April	78·2	81·7	85·7	88·5	17·8	70·7	18th	94·0	33·1	4th	60·9
May	77·6	80·7	85·8	87·8	18·5	69·3	20th	96·0	34·9	24th	61·1
June	75·4	76·0	81·9	83·6	14·7	68·9	1st	89·8	24·0	20th	65·8
July	69·1	69·7	71·4	73·9	7·1	66·8	14th	80·1	36·7	26th	63·4
August	69·5	70·5	74·7	76·6	12·3	64·3	28th	88·4	27·6	10th	60·8
September	67·9	70·6	70·4	73·9	8·6	65·3	26th	80·5	17·3	11th	63·2
October	68·4	74·5	73·4	77·5	14·2	63·3	11th & 17th	81·0	23·7	31st	57·3
November	60·4	67·1	66·2	71·4	16·8	54·6	6th	78·0	30·7	15th	47·3
December	56·0	62·4	62·2	67·8	18·1	49·7	27th	75·9	30·9	17th	45·0
Year	67·1	70·5	72·8	76·2	14·9	61·3	...	96·0	57·7	...	38·3

84. MOUNT ABU (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	58·4	62·6	70·9	73·0	26·5	46·5	1st	79·1	45·0	31st	34·1
February	60·2	65·2	73·5	75·3	29·7	45·6	28th	84·1	50·0	1st	34·1
March	71·5	76·6	83·7	85·3	27·8	57·5	30th	95·0	47·7	15th	47·3
April	86·1	90·6	97·9	99·1	27·6	71·5	19th	105·0	41·8	5th	63·2
May	88·8	90·0	99·5	100·6	21·7	78·9	20th	109·0	45·8	26th	63·2
June	87·8	89·0	96·3	98·2	17·3	80·9	3rd & 9th to 12th.	102·0	29·8	1st	72·2
July	80·8	82·1	86·1	87·8	11·9	75·9	2nd	93·0	19·8	3rd, 8th & 27th.	73·2
August	83·7	84·0	92·2	94·1	16·7	77·4	28th	104·0	29·5	10th & 11th	74·2
September	80·2	82·2	86·8	89·0	14·1	74·9	26th	95·0	25·8	25th	68·2
October	75·3	83·1	87·9	90·2	27·3	62·9	4th, 10th & 17th	94·0	43·7	30th & 31st	50·3
November	63·4	74·0	78·2	81·0	33·1	47·9	2nd	89·1	48·9	18th	40·2
December	56·1	64·8	72·4	74·2	33·9	40·3	1st	82·1	45·0	18th	34·1
Year	74·4	78·7	85·5	87·3	24·0	63·4	...	109·0	74·9	...	34·1

85. PACHPADRA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	59·4	66·1	77·3	79·6	38·2	41·4	5th, 15th, 18th & 21st.	84·6	48·6	29th	36·0
February	62·8	66·6	79·9	81·2	35·5	45·7	28th	92·5	55·5	6th	37·0
March	73·9	82·5	89·8	91·4	33·5	57·9	28th to 30th	102·5	53·6	12th	48·9
April	87·9	96·3	104·1	105·8	34·1	71·7	18th & 19th	110·5	45·8	3rd, 4th & 6th.	64·7
May	90·6	92·3	105·3	106·9	31·1	75·8	20th	119·5	52·8	27th	66·7
June	93·0	94·2	104·1	105·7	23·9	81·8	1st	113·5	35·9	6th	77·6
July	86·0	88·3	93·2	94·7	16·0	78·7	2nd	103·5	27·5	31st	76·0
August	87·5	87·5	98·0	100·8	23·8	77·0	27th	111·5	37·7	16th	73·8
September	83·3	86·0	91·3	95·5	20·2	75·3	23rd	102·5	30·8	30th	71·7
October	80·0	88·2	94·6	97·5	32·1	65·4	5th	102·8	48·7	31st	54·1
November	66·3	74·4	83·8	86·9	38·1	48·8	7th	95·9	54·0	25th & 26th	41·9
December	59·0	64·2	76·7	79·3	38·1	41·2	27th	84·9	47·9	17th & 18th	37·0
Year	77·5	82·2	91·5	93·8	30·4	63·4	...	119·5	83·5	...	36·0

86. JACOBABAD (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	57·7	61·6	71·8	72·0	28·4	43·6	15th	78·3	44·4	27th	33·9
February	60·1	64·7	74·9	76·0	30·8	45·2	26th	84·7	51·5	1st	33·2
March	72·7	76·6	87·2	87·2	29·1	58·1	27th	98·3	51·0	5th	47·3
April	87·6	93·8	103·1	103·4	31·3	72·1	22nd	111·6	48·5	3rd	63·1
May	93·6	101·2	109·3	106·9	29·1	77·8	20th	114·8	42·5	4th	71·3
June	98·0	101·8	112·1	112·7*	28·8	83·9	10th	118·2	37·1	8th	81·1
July	91·3	94·0	100 9	104·3	22·7	81·6	6th	111·1	38·2	16th	72·9
August	90·9	91·5	103·0	104·8	26·0	78·8	28th	110·5	34·6	28th	75·9
September	88·6	92·2†	100·3†	102·9†	26·1	76·8†	12th	106·8	36·7	24th	70·1
October	76·4	85·1	92·0	96·8	36·0	60·8	4th	103·7	56·3	21st	47·4
November	63·3	72·0	79·2	84·0	36·6	47·4	8th	98·2	58·1	14th	40·1
December	57·1	61·6	72·3	75·2	33·3	41·9	15th	79·0	41·5	17th	37·5
Year	78·1	83·0	92·2	93·9	29·9	64·0	...	118·2	85·0	...	33·2

* Mean of 24 days. † Mean of 28 days.

87. HYDERABAD (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	62·4	67·2	74·0	75·5	24·8	50·7	18th	81·7	40·2	28th	41·5
February	65·1	69·1*	77·1*	79·1	26·1	53·0	26th	90·4	45·5	1st	44·9
March	75·9	79·5	88·5	90·1	26·8	63·3	29th	101·8	48·6	11th	53·2
April	87·5	93·0	101·8	103·5	30·3	73·2	23rd	110·0	42·7	3rd	67·3
May	91·5	95·6	104·9	107·8	29·7	78·1	12th	114·2	41·9	1st	72·3
June	91·2	95·4	100·6	104·0	22·3	81·7	1st	116·2	37·4	14th	78·8
July	86·3	89·3	93·1	96·6	17·1	79·5	2nd	104·4	29·8	16th	74·6
August	85·2	88·3	93·2	96·3	19·2	77·1	26th	106·8	33·0	28th	73·8
September	84·4	87·8	93·1	95·8	20·1	75·7	23rd	100·2	27·9	27th	72·3
October	82·7	87·7	95·7	97·5	27·9	69·6	5th	104·8	49·4	31st	55·4
November	69·2	74·8	82·5	84·6	28·7	55·9	6th	95·4	48·2	15th	47·2
December	62·4	66·9	75·8	77·6	28·7	48·9	26th	82·5	40·4	17th	42·1
Year	78·7	82·9	90·0	92·4	25·1	67·2	...	116·2	74·7	...	41·5

88. KURRACHEE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	65·8	69·7	75·2	77·2	22·0	55·2	16th	83·0	35·8	29th	49·2
February	67·8	70·9	75·9	78·2	21·4	56·8	14th	82·9	34·1	2nd	48·8
March	74·6	77·6	80·4	84·5	19·7	64·8	27th	99·7	43·2	11th	56·5
April	81·0	85·1	85·8	89·3	16·0	73·3	18th	96·2	27·5	3rd	68·7
May	85·2	89·0	89·1	92·7	14·4	78·3	12th	109·4	37·8	12th	71·6
June	87·6	90·9	91·1	93·8	11·5	82·3	1st	99·1	19·6	29th	79·5
July	83·4	85·3	85·9	88·6	8·9	79·7	3rd	96·0	20·1	5th	75·9
August	80·9	83·0	83·7	85·9	8·7	77·2	26th	89·5	13·9	13th	75·6
September	81·3	83·9	83·9	86·8	9·9	76·9	22nd	89·9	16·0	20th	73·9
October	80·2	86·9	87·5	92·5	22·4	70·1	17th	101·8	40·3	30th	61·5
November	70·3	77·1	81·0	85·3	26·6	58·7	9th	94·3	42·2	15th	52·1
December	65·9	69·8	76·5	79·2	26·2	53·0	15th	82·0	34·3	17th	47·7
Year	77·0	80·8	83·0	86·2	17·3	68·9	...	109·4	61·7	...	47·7

* Mean of 27 days.

89. BHUJ (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Ab. Interan.	Lowest Minimum. Day.	°	Mean.	10 hours.	16 hours.
January	67·1	72·0	78·1	79·9	23·0	56·0	5th	85·9	36·9	27th	49·0	67·6	71·3	82·8
February	68·4	73·4	80·6	82·5	26·3	56·2	28th	92·3	43·2	7th	49·1	68·3	72·2	85·1
March	76·3	81·0	87·1	89·7	24·3	65·4	29th	100·0	41·5	11th	58·5	76·3	81·7	91·6
April	85·8	93·1	98·6	102·4	29·4	73·0	18th	108·4	40·5	2nd & 3rd	67·9	85·8	92·6	101·8
May	85·8	93·7	95·5	100·8	24·8	76·0	11th	108·1	39·8	12th	68·3	88·0	93·4	101·4
June	87·9	92·6	94·6	98·6	17·5	81·1	1st	107·8	30·0	28th	77·8	87·0	90·6	95·6
July	?	84·1	85·2	87·9	Imperfect.		1st & 2nd	95·0	?	?	?	80·9	83·4	86·3
August	81·9	86·0	87·1	90·6	14·0	76·6	26th	97·5	23·2	14th & 26th	74·3	82·3	85·3	90·5
September	79·7	84·4	85·0	89·1	14·8	74·3	22nd	93·5	21·7	30th	71·8	78·3	82·1	84·4
October	82·0	89·0	93·1	95·8	23·7	72·1	17th	100·5	34·7	30th	65·8	78·9	86·3	89·7
November	71·4	80·0	83·6	86·7	27·5	59·2	8th	93·6	40·6	15th	53·0	70·3	80·7	85·9
December	65·2	72·8	77·8	80·4	27·0	52·5	28th	85·3	37·3	18th	48·0	64·2	72·5	80·7
Year	?	83·5	87·2	90·4	?	?	...	108·4	60·4	...	48·0	77·3	82·7	89·7

90. RAJKOT (*corrected*).

Month.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	84·4	32·1	52·3	5th	91·8	50·6	28th	41·2
February	86·0	55·2	51·4	28th	94·5	50·8	1st	43·7
March	93·6	32·6	61·0	31st	102·3	47·7	12th	54·6
April	104·3	34·6	69·7	18th	110·3	47·7	4th	62·6
May	104·9	30·3	74·6	11th	110·3	45·8	2nd	64·5
June	100·5	22·2	78·3	1st	109·3	36·1	30th	73·2
July	90·1	14·7	75·4	1st	97·3	26·8	3rd	70·5
August	93·4	19·3	74·1	28th	98·8	27·6	9th & 14th	71·2
September	87·9	15·7	72·2	27th	92·3	23·5	20th	68·8
October	92·0	24·9	68·0	17th	97·3	42·7	31st	54·6
November	88·0	33·3	54·7	8th	92·9	45·4	26th	47·5
December	82·6	34·9	47·7	28th	86·2	43·8	22nd	42·4
Year	92·4	27·5	65·0	...	110·3	69·1	...	41·2

91. DEESA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	68·0	73·3	80·5	82·9	29·9	53·0	5th	89·7	50·9	27th	38·8
February	70·2	74·8	83·1	84·7	31·1	53·6	28th	93·1	49·3	1st	43·8
March	79·0	82·9	90·2	92·3	28·8	63·5	29th	102·7	47·6	12th	55·1
April	91·1	94·6	103·6	105·4	32·3	73·1	18th	110·3	43·5	4th	66·8
May	91·0	91·3	103·6	105·4	30·0	75·4	20th	114·3	44·5	6th	69·8
June	90·8	91·3	100·0	102·6	21·0	81·6	1st	106·0	33·3	29th	76·3
July	82·2	83·5	87·0	90·2	13·0	77·3	1st	97·1	22·1	4th	75·0
August	84·4	84·8	92·9	94·8	18·8	76·0	28th	102·6	29·4	17th	73·2
September	81·5	83·4	87·7	90·3	15·2	75·1	23rd	98·2	25·3	30th	72·9
October	80·2	87·5	90·6	94·8	26·3	68·5	11th	98·9	42·8	30th	56·1
November	71·3	79·8	85·3	88·1	33·2	54·9	7th	94·7	45·5	25th & 28th	49·2
December	66·2	72·9	80·3	83·2	34·3	48·9	27th	86·8	43·7	17th	43·1
Year	79·7	83·3	90·4	92·9	26·2	66·7	...	114·3	75·5	...	38·8

92. SURAT (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	70·2	73·4	82·4	87·1	29·1	58·0	3rd & 4th	93·7	44·9	28th	48·8
February	71·6	74·4	85·9	89·4	32·1	57·3	24th	98·3	48·5	1st	49·8
March	77·4	80·8	90·6	94·3	30·1	64·1	26th	103·4	45·9	12th	57·5
April	84·1	88·5	95·8	100·9	28·5	72·4	8th	111·3	45·8	3rd	65·5
May	86·1	90·2	94·7	98·3	20·9	77·4	31st	106·7	35·7	5th	71·0
June	83·2	85·9	88·3	92·2	14·1	78·1	1st	99·1	28·1	5th	71·0
July	80·9	82·7*	84·4*	86·3*	8·9	77·4*	1st	89·1	14·7	10th	74·4
August	81·5	83·9	85·8	88·9	11·8	77·1	19th	93·7	19·7	30th	74·0
September	78·5	81·2	82·2	85·0	10·3	74·7	27th	88·3	16·5	20th	71·8
October	78·7	83·0	86·4	88·9	18·0	70·9	12th	94·0	32·0	31st	62·0
November	72·7	78·4	84·5	87·1	26·3	60·8	8th	90·8	37·3	26th	53·5
December	67·5	71·5	81·1	83·2	29·4	53·8	28th	86·5	40·7	17th	45·8
Year	77·7	81·2	86·8	90·1	21·6	68·5	...	111·3	65·5	...	45·8

* Mean of 29 days.

93. MALEGAON (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	68·1	73·3	82·7	84·2	30·8	53·4	2nd	88·6	52·0	28th	36·6
February	71·3	78·1	88·6	89·9	35·9	54·0	24th	94·6	53·0	1st	41·6
March	77·4	85·1	93·7	95·9	34·9	61·0	27th	103·1	54·2	12th	48·9
April	86·2	95·9	100·9	103·7	32·3	71·4	19th	108·1	48·5	4th	59·6
May	88·3	93·7	101·7	104·6	29·7	74·9	20th	110·8	40·3	22nd	70·5
June	81·3	84·4	89·3	93·1	19·8	73·3	2nd	98·8	29·7	9th & 24th	69·1
July	77·5	80·7	82·9	85·4	13·3	72·1	4th	90·9	21·2	3rd	69·7
August	76·8	80·5	83·9	87·4	17·8	69·6	15th	93·9	26·4	15th	67·5
September	75·7	78·0	81·4	82·8	12·9	69·9	18th	86·9	20·1	15th	66·8
October	75·0	79·3	82·8	84·7	17·5	67·2	12th	90·9	36·3	31st	54·6
November	67·9	74·8	80·6	83·0	27·8	55·2	8th	85·6	39·0	23rd, 25th & 28th	46·6
December	60·6	68·8	76·7	81·3	36·9	44·4	29th to 31st	83·9	45·6	18th	38·3
Year	75·5	81·1	87·1	89·7	25·8	63·9	...	110·8	74·2	...	36·6

94. BOMBAY (*corrected*).

Month.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily Range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	75·5	69·8	77·0	81·9	73·6	83·5	14·5	69·0	4th	87·6	25·6	29th	62·0
February	75·0	68·9	77·6	80·8	73·0	82·5	14·7	67·8	24th	85·7	24·7	2nd	61·0
March	78·1	72·5	81·2	82·7	76·0	84·5	12·6	71·9	31st	90·5	23·9	12th	66·6
April	82·5	78·1	85·6	86·4	80·5	88·5	10·9	77·6	17th	92·5	19·7	5th	72·8
May	84·5	80·7	87·4	88·1	82·4	90·3*	10·3	80·0	31st	92·3	14·7	2nd & 4th	77·6
June	92·0	80·1	84·3	84·2	80·8	87·0	8·9	78·1	1st	92·3	18·6	7th	73·7
July	80·5	79·0	82·0	82·0	79·2	84·2	7·4	76·8	6th	86·8	13·4	10th	73·4
August	80·2	78·1	81·5	82·4	78·8	84·1	7·1	77·0	17th	88·1	9·1	30th	72·0
September	78·5	76·4	80·6	80·5	77·5	83·0	7·8	75·2	19th	84·9	11·4	23rd	73·5
October	80·1	76·4	81·9	84·1	78·5	86·0	10·4	75·6	12th	90·4	17·6	30th	72·8
November	77·8	72·8	79·9	83·1	75·2	85·6	13·8	71·8	5th	89·3	23·2	26th & 30th	66·1
December	73·3	67·7	74·5	79·9	70·0	82·6	16·1	66·5	11th	85·6	22·6	17th	63·0
Year	79·0	75·0	81·1	83·0	77·1	85·2	11·2	73·9	...	92·5	31·5	...	61·0

* Mean of 30 days.

95. POONA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	72·2	74·2	82·4	84·5	30·5	54·0	30th	87·9	43·2	28th	44·7
February	78·1	79·9	89·6	91·9	34·7	57·2	24th	96·7	53·1	1st	43·6
March	81·2	83·7	92·4	95·9	33·8	62·1	31st	102·2	49·1	12th	53·1
April	86·9	92·4	98·1	102·3	32·9	69·4	22nd	106·0	45·3	5th	60·7
May	85·7	91·2	95·8	100·7	28·8	71·9	7th	107·5	40·4	2nd	67·1
June	76·7	80·5	79·9	86·4	14·7	71·7	2nd	92·8	24·4	5th	68·4
July	74·6	77·0	77·1	80·9	10·6	70·3	5th	86·6	18·3	10th	68·3
August	75·1	77·1	78·2	82·1	13·4	68·7	12th	90·3	23·9	18th	66·4
September	73·0	75·5	75·8	80·1	12·3	67·8	16th	85·5	21·6	13th	63·9
October	75·7	78·1	80·0	84·1	17·3	66·8	5th	88·6	32·2	29th	56·4
November	73·0	75·7	80·5	82·6	25·7	56·9	5th	85·0	38·8	29th	46·2
December	67·2	71·1	78·4	80·2	32·7	47·5	16th	87·5	44·6	7th & 18th	42·9
Year	76·6	79·7	84·0	87·0	23·9	63·7	...	107·5	64·6	...	42·9

96. SHOLAPUR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	70·3	76·4	83·8	86·1	29·3	56·8	30th	91·0	41·9	28th	49·1
February	77·3	83·0	92·3	94·3	32·1	62·2	23rd, 24th, & 26th	98·0	48·4	1st	49·6
March	82·0	88·9	96·4	99·0	31·5	67·5	31st	104·7	42·6	1st & 12th	62·1
April	87·6	93·2	101·6	104·6	31·1	73·5	22nd	106·2	37·7	6th	68·5
May	88·5	91·3*	102·3*	104·7*	30·0	74·7*	10th	109·0	36·7	12th	72·3
June	77·7	80·7	85·6	91·2	21·5	69·7	1st	100·2	34·8	5th	65·4
July	78·4	80·3	85·5	89·9	18·7	71·2	4th & 29th	94·5	26·1	1st	68·4
August	77·9	78·9	84·6	88·0	16·8	71·2	9th	96·2	29·2	10th	67·0
September	76·5	77·6	81·6	85·9	14·5	71·4	17th	91·8	23·2	24th	68·6
October	77·6	81·3	84·3	87·2	16·4	70·8	21st	91·4	25·8	28th	65·6
November	74·4	78·3	80·9	84·2	16·3	67·9	12th	87·2	26·0	27th	61·2
December	67·6	73·8	79·5	81·8	26·1	55·7	14th	86·9	40·7	27th	46·2
Year	78·0	82·0	88·2	91·4	23·7	67·7	...	109·0	62·8	...	46·2

* Mean of 24 days.

97. RATNAGIRI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	74·6	83·4	83·0	88·0	21·9	66·1	1st & 4th	94·0	34·4	28th	59·6
February	75·5	83·4	83·5	86·2	18·8	67·4	3rd	90·8	30·8	1st	60·0
March	77·4	83·0	83·5	86·2	14·9	71·3	25th	89·6	22·4	7th	67·2
April	81·9	87·1	86·6	89·5	12·4	77·1	16th	92·4	22·5	5th	69·9
May	84·3	88·8	88·5	91·5	11·5	80·0	31st	99·0	22·1	9th	76·9
June	79·1	82·0	82·1	84·5	8·5	76·0	1st	89·0	16·2	7th	72·8
July	78·3	80·5	81·1	83·3	7·9	75·4	4th	86·9	14·9	8th	72·0
August	78·5	81·5	81·9	84·0	9·0	75·0	15th	87·6	17·0	25th	70·6
September	77·0	80·6	80·4	83·0	9·5	73·5	17th	84·9	13·3	22nd	71·6
October	78·3	84·9	83·2	87·6	14·2	73·4	13th	94·4	27·8	29th	66·6
November	75·9	85·3	83·4	89·1	20·7	68·4	5th & 7th	93·0	32·8	30th	60·2
December	72·8	82·5	81·7	87·9	24·1	63·8	12th	91·0	32·4	6th	58·6
Year	77·8	83·6	83·2	86·7	14·5	72·3	...	99·0	40·4	...	58·6

98. BELGAUM (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	69·9	72·8	79·1	81·0	24·2	56·8	30th	86·8	33·3	7th	53·5
February	76·4	80·1	86·6	88·6	28·4	60·2	27th & 28th	93·4	41·5	1st	51·9
March	78·9	84·0	88·6	93·1	29·9	63·2	31st	98·7	39·8	6th	58·9
April	80·4	86·6	88·0	95·6	28·5	67·1	7th	99·9	38·6	7th	61·3
May	80·2	84·9	86·4	93·1	24·1	69·0	9th	102·6	37·0	22nd	65·6
June	72·1	74·5	73·0	77·9	10·1	67·8	1st	85·2	20·1	7th	65·1
July	70·2	72·1	71·5	74·7	8·3	66·4	4th	79·3	14·6	8th	64·7
August	71·3	73·9	74·5	78·0	12·1	65·9	14th	85·3	21·4	13th	63·9
September	69·9	72·7	72·9	76·5	12·0	64·5	27th	81·4	20·9	23rd	60·5
October	72·7	75·7	76·8	80·7	15·8	64·9	3rd	85·1	24·8	29th	60·3
November	70·5	73·5	77·8	79·5	20·7	58·8	6th	82·1	30·7	29th	51·4
December	67·7	70·8	76·5	78·1	23·5	54·6	16th	83·3	34·3	29th	49·0
Year	73·4	76·8	79·3	83·1	19·8	63·3	...	102·6	53·6	...	49·0

99. KARWAR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	75·2	76·3	84·9	87·3	21·8	65·5	2nd	90·3	29·3	9th	61·0
February	75·8	77·9	84·9	87·4	20·7	66·7	5th	92·8	29·8	2nd & 20th	63·0
March	78·2	81·7	84·7	87·1	15·4	71·7	26th, 27th & 29th.	89·3	23·4	12th & 13th	65·9
April	81·6	85·6	86·3	89·5	12·7	76·8	18th	91·3	21·5	5th	69·8
May	83·4	86·3	87·8	90·1	11·2	78·9	24th	92·8	20·1	30th	72·7
June	77·5	80·4	81·2	84·4	10·6	73·8	28th	87·3	16·5	6th, 8th & 10th.	70·8
July	76·7	79·7	79·5	83·6	9·7	73·9	6th	87·9	18·1	12th	69·8
August	77·2	79·9	80·5	83·1	9·2	73·9	10th	86·2	15·5	26th	70·7
September	76·2	78·8	80·2	82·5	10·3	72·2	22nd	85·7	15·9	24th	69·8
October	76·5	80·1	80·9	84·4	12·4	72·0	30th	88·3	22·4	29th	65·9
November	74·5	78·4	82·1	85·7	18·8	66·9	19th	89·3	30·2	30th	59·1
December	72·7	75·6	81·9	85·1	21·7	63·4	12th	88·3	31·9	6th	56·4
Year	77·1	80·1	82·9	85·9	14·5	71·3	..	92·8	36·4	...	56·4

100. GOPALPORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	68·2	73·3	73·1	75·8	12·5	63·3	26th & 31st	77·6	17·6	2nd, 3rd, 17th 18th, 21st & 22nd.	60·0
February	74·5	77·1	78·9	79·2	9·2	70·0	22nd & 28th	82·6	20·7	7th	61·9
March	79·7	81·7	82·3	82·8	5·8	77·0	19th to 27th	84·6	10·8	9th & 10th	73·8
April	81·3	83·0	83·0	83·1	3·6	79·5	7th to 10th	84·6	7·8	1st	76·8
May	82·6	84·1	84·1	84·1	3·1	81·0	27th, 29th & 31st	87·6	8·8	1st, 13th & 14th.	78·8
June	82·5	83·7	83·8	Untrustworthy.		81·1	?	?	?	30th	76·8
July	80·7	81·9	81·9	82·6*	3·2	79·4*	15th	85·6	9·8	27th & 28th	75·8
August	82·5	83·3	84·1	84·3*	3·4	80·9	1st, to 5th, 7th to 9th, 11th, 17th, 19th & 21st.	85·6	8·8	16th	76·8
September	82·4	83·2	83·9	84·8	4·0	80·8	19th	88·6	9·8	3rd, 7th & 8th.	78·8
October	81·2	82·6	84·2	85·2	7·1	78·1	6th, 8th to 11th.	88·6	15·8	27th	72·8
November	72·4	74·5	77·8	78·6	11·6	67·0	4th	83·6	26·6	22nd to 25th	57·0
December	64·1	66·8	71·9	72·0	15·7	56·3	1st & 2nd	76·6	25·6	27th & 29th	51·0
Year	77·7	79·6	80·8	...	...	74·5	...	?	?	...	51·0

* Mean of 29 days.

101. VIZAGAPATAM (*uncorrected*).

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	75·3	72·5	75·8	78·0	74·7	78·6	7·5	71·1	27th	80·3	12·3	3rd	68·0
February	79·3	76·5	80·1	82·2	78·2	82·9	8·0	74·9	21st	91·0	20·2	19th	70·8
March	83·6	81·4	84·9	85·1	82·8	85·8	5·4	80·4	20th and 23rd	89·5	11·7	12th	77·8
April	86·1	84·0	87·8	87·3	85·3	88·0	4·5	83·5	27th	89·8	8·3	2nd	81·5
May	88·7	86·6	90·4	89·9	87·8	90·7	4·4	86·3	24th	94·6	10·8	4th	83·8
June	87·4	85·5	88·3	89·1	86·8	89·6	4·4	85·2	11th	95·5	14·5	28th	81·0
July	85·5	83·4	86·1	87·4	85·2	87·8	4·7	83·1	17th	92·3	11·9	27th	80·4
August	85·9	84·5	86·5	87·1	85·3	87·6	3·6	84·0	2nd	91·5	12·5	26th	79·0
September	84·8	83·2	85·0	86·5	84·5	87·0	4·2	82·8	16th	90·2	13·7	3rd	76·5
October	83·6	82·1	84·3	85·1	83·0	85·7	4·3	81·4	12th	89·0	10·6	31st	78·4
November	76·7	74·2	77·5	79·2	76·0	80·0	6·9	73·1	7th	83·2	16·2	24th	67·0
December	72·8	71·0	72·9	74·7	72·6	75·4	5·6	69·8	5th	78·6	16·6	27th	62·0
Year	82·5	80·4	83·3	84·3	81·9	84·9	5·3	79·6	...	95·5	33·5	...	62·0

102. MASULIPATAM (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	74·0	78·3	78·7	73·4	81·6	15·1	66·5	28th	87·2	24·5	17th	62·7
February	75·8	81·5	82·1	73·4	85·7	18·7	67·0	26th	93·7	31·9	13th	61·8
March	80·8	86·0	85·4	78·6	91·7	17·8	73·9	20th	96·2	28·5	25th	67·7
April	84·0	89·6	88·3	81·4	94·8	17·5	77·3	29th	103·4	30·6	10th	72·8
May	89·0	94·5	93·9	85·6	100·7	18·1	82·6	13th	112·6	34·8	20th	77·8
June	85·5	88·3	91·2	83·6	95·1	15·6	79·5	3rd, 17th & 18th	103·6	31·8	23rd	71·8
July	82·8	86·0	83·5	80·3	91·9	14·9	77·0	4th	99·3	25·5	27th	73·8
August	83·9	87·2	88·8	81·8	93·2	15·2	78·0	4th, 5th & 6th	100·9	27·4	24th and 25th	73·5
September	84·0	87·1	89·9	81·6	93·3	16·0	77·3	15th	99·0	24·3	29th	74·7
October	80·6	83·9	83·6	79·5	88·6	12·7	75·9	13th	96·8	24·8	16th	72·0
November	75·4	78·6	80·1	74·1	83·3	14·1	69·2	6th	88·1	23·7	28th	64·4
December	71·4	75·2	77·1	70·8	80·3	16·5	63·8	7th	83·1	25·0	27th	58·1
Year	80·6	84·7	85·6	78·7	90·0	16·0	74·0	...	112·6	54·5	...	58·1

103. SECUNDERABAD (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	69·5	71·9	79·7	67·9	82·3	22·5	59·8	31st	87·9	32·0	1st	55·9
February	76·8	79·8	88·5	75·3	91·4	26·7	64·7	26th	99·6	38·4	20th	61·2
March	80·5	83·2	91·4	78·6	94·9	25·3	69·6	29th	103·5	40·2	14th	63·3
April	87·7	91·4	98·7	85·5	102·7	26·5	76·2	14th	107·1	35·1	4th	72·0
May	91·9	94·8	102·1	90·6	106·5	25·3	81·2	16th	110·4	37·4	30th	73·0
June	79·9	82·1	86·0	78·4	90·5	16·9	73·6	1st & 3rd	102·4	33·3	8th	69·1
July	76·8	78·5	82·5	75·2	85·4	14·0	71·4	5th	94·7	25·8	8th	68·9
August	77·1	79·3	82·1	75·7	85·8	14·1	71·7	13th	96·6	28·9	24th and 25th	67·7
September	75·3	77·2	80·2	73·6	83·8	13·6	70·2	17th	90·2	22·4	29th	67·8
October	75·4	79·2	80·1	73·3	84·6	15·2	69·4	12th	89·6	27·5	28th	62·1
November	69·2	74·5	78·1	66·1	81·4	22·7	58·7	4th	85·1	35·6	28th	49·5
December	65·6	70·1	77·1	63·1	80·1	26·0	54·1	14th	86·1	39·2	27th	46·9
Year	77·1	80·2	85·5	75·3	89·1	20·7	68·4	...	110·4	63·5	...	46·9

104. KURNOOL (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	...	...	...	...	...	...	...	...	...	...	...
February	79·2	84·9*	94·0*	96·0*	32·5	63·5*	28th	100·9	43·1	19th and 20th	57·8
March	83·5	89·0	97·5	101·1	26·7	74·4	27th	106·2	40·9	17th	65·3
April	90·1	94·8	102·5	106·0	27·0	79·0	29th and 30th	109·9	38·8	28th	71·1
May	90·8	94·4	102·3	107·5	25·0	82·5	19th	111·9	37·9	30th	74·0
June	82·3	86·0	89·5	95·0	19·1	75·9	2nd	105·2	33·5	24th	71·7
July	79·6	83·5	85·9	90·5	17·1	73·4	4th	102·2	32·3	7th	69·9
August	79·7	82·4	85·9	88·1	14·5	73·6	6th	96·9	27·0	18th and 28th	69·9
September	79·2	81·2	86·0	87·2	14·6	72·6	16th	92·8	23·1	23rd	69·7
October	78·1	81·5	82·9	84·0	12·0	72·0	7th	89·6	21·3	28th	68·3
November	73·3	78·0	82·5	82·9	20·0	62·9	19th	85·9	31·6	29th	54·3
December	68·8	74·0	81·0	81·0	24·6	56·4	17th	84·5	34·8	27th	49·7
Year	...	...	...	...	...	...	...	...	...	...	...

* Mean of 20 days.

105. BELLARY (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	71·9	75·9	83·2	69·1	85·9	25·2	60·7	31st	92·8	37·7	5th	55·1
February	77·5	82·3	91·2	74·0	93·9	30·2	63·7	28th	101·7	44·0	12th	57·7
March	84·3	87·8	95·8	82·1	99·9	26·9	73·0	27th	106·1	39·0	25th	67·1
April	89·4	93·3	100·9	86·4	104·6	26·8	77·8	7th	108·0	36·0	11th	72·0
May	90·0	92·1	101·7	88·6	105·3	26·6	78·7	17th	108·8	35·2	3rd	73·6
June	83·3	86·6	90·5	80·1	95·7	19·1	76·6	1st	100·3	26·2	24th	74·1
July	80·7	83·8	87·5	77·6	92·1	17·6	74·5	3rd & 4th	99·3	29·1	29th	70·2
August	80·2	82·1	86·6	78·6	91·2	17·3	73·9	6th & 9th	99·7	29·4	18th	70·3
September	80·9	82·8	89·1	78·7	91·7	18·9	72·8	16th	95·9	27·0	24th	68·9
October	77·7	80·8	83·5	76·1	87·9	16·7	71·2	1st	96·0	28·6	22nd	67·4
November	72·8	78·0	82·1	69·1	85·2	22·5	62·7	7th	87·4	32·6	28th	54·8
December	69·2	73·9	80·7	65·9	83·5	25·2	58·3	16th	90·2	38·2	7th	52·0
Year	79·8	83·3	89·4	77·2	93·1	22·8	70·3	...	108·8	56·8	...	52·0

106. MANGALORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	76·7	81·7	84·0	88·1	18·8	69·3	2nd & 6th	91·3	26·4	20th	64·9
February	78·7	83·7	84·9	88·5	16·0	72·5	3rd	94·6	24·6	21st	70·0
March	80·7	84·1	85·6	88·7	13·0	75·7	27th & 28th	90·3	18·0	10th	72·3
April	82·5	86·1	87·2	90·3	12·6	77·7	23rd	91·7	20·1	26th & 30th	71·6
May	82·9	86·0	86·9	90·0	11·1	78·9	25th	92·2	19·2	3rd	73·0
June	78·3	80·8	81·7	85·0	10·2	74·8	1st	88·5	16·2	2nd	72·3
July	76·5	78·5	79·1	81·8	7·9	73·9	3rd	86·7	16·3	12th	70·4
August	77·2	79·1	79·7	82·7	8·1	74·6	12th	86·2	14·3	23rd & 25th	71·9
September	77·8	81·0	81·6	84·0	10·0	74·0	24th	85·5	14·6	25th	70·9
October	77·5	81·0	81·2	84·2	10·4	73·8	29th	88·0	16·9	7th & 8th	71·1
November	77·4	82·0	83·3	86·6	15·1	71·5	7th	91·0	25·8	30th	65·2
December	75·4	80·4	82·3	86·3	17·9	68·4	27th	89·4	26·3	29th	63·1
Year	78·5	82·0	83·1	86·4	12·6	73·8	...	94·6	31·5	...	63·1

107. MERCARA (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	63·9	66·3	72·2	75·6	20·1	55·5	31st	79·9	28·6	27th	51·3
February	67·5	71·4	78·1	80·7	23·9	56·8	25th	86·3	37·0	11th	49·3
March	69·6	76·2	77·7	82·9	21·5	61·4	26th	88·1	30·3	1st	57·8
April	70·7	77·3	77·6	83·8	20·0	63·8	7th	90·1	30·5	6th	59·6
May	70·5	74·4	75·8	80·8	15·6	65·2	3rd & 5th	85·1	23·6	30th	61·5
June	65·5	68·2	67·2	72·4	8·7	63·7	1st	80·0	18·5	24th	61·5
July	64·0	65·3	65·3	68·6	5·9	62·7	4th	74·9	15·1	22nd	59·8
August	65·5	67·6	67·8	72·0	8·9	63·1	14th	80·4	19·3	25th	61·1
September	64·5	67·4	67·6	71·9	10·6	61·3	17th	76·2	20·4	25th	55·8
October	65·9	69·7	69·5	74·4	12·2	62·2	26th	77·3	18·7	19th	58·6
November	64·2	66·9	69·6	73·2	14·4	58·8	14th	76·3	23·2	26th	53·1
December	61·8	64·6	68·0	71·2	15·7	55·5	3rd	76·3	26·0	1st & 6th	50·3
Year	66·1	69·6	71·4	75·6	14·8	60·8	...	90·1	40·8	...	49·3

108. BANGALORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	66·3	69·4	76·3	67·0	77·8	23·9	53·9	28th	82·9	34·0	12th	48·9
February	71·1	73·7	82·1	71·5	83·1	24·8	58·3	28th	90·5	36·7	11th	53·8
March	77·2	80·3	87·8	76·0	89·7	24·2	65·5	31st	93·6	31·9	26th	61·7
April	80·3	83·2	90·6	79·1	92·7	23·7	69·0	15th	95·6	30·8	28th	64·8
May	79·3	82·4	89·1	78·8	92·0	24·1	67·9	19th	96·5	31·6	20th & 30th	64·9
June	74·7	78·1	82·1	73·7	85·6	19·8	65·8	2nd	91·6	28·1	12th	63·5
July	71·2	74·2	77·0	70·1	80·9	16·6	64·3	5th	89·7	27·5	29th	62·2
August	72·5	74·7	79·5	71·8	82·1	17·7	64·4	10th	90·5	28·3	25th	62·2
September	72·4	74·3	80·1	72·5	82·0	19·4	62·6	16th, 24th & 30th	84·6	25·4	25th	59·2
October	70·7	74·1	76·7	70·3	79·6	17·0	62·6	2nd	86·3	26·3	17th	59·7
November	67·4	70·5	74·7	67·6	76·3	18·8	57·5	9th	79·6	27·9	25th & 26th	51·7
December	64·4	67·7	72·7	65·4	74·2	20·6	53·6	4th	78·6	30·4	29th	48·2
Year	72·3	75·2	80·7	72·0	83·0	20·9	62·1	...	96·5	48·3	...	48·2

109. MADRAS (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	75·6	80·6	80·3	74·3	84·7	16·6	68·1	29th	87·5	23·3	8th	64·2
February	76·4	82·4	83·0	73·8	87·0	19·7	67·3	16th	90·3	27·5	12th	62·8
March	80·7	86·0	84·9	79·3	89·7	16·3	73·4	19th	95·1	25·7	25th	69·4
April	83·7	89·5	87·2	81·9	93·4	16·5	76·9	6th	101·2	28·9	10th & 12th	72·3
May	87·5	94·4	89·7	84·7	98·7	17·0	81·7	24th	107·7	29·1	10th	78·6
June	86·6	90·8	92·2	83·8	98·2	18·0	80·2	17th	105·1	29·6	4th	75·5
July	83·2	86·7	88·7	80·6	93·5	16·0	77·5	1st & 17th	97·6	23·6	2nd, 7th & 28th	74·0
August	83·9	88·3	88·6	81·3	94·4	16·7	77·7	28th	98·9	24·4	22nd	74·5
September	84·7	89·2	89·6	82·1	95·9	18·0	77·9	19th	102·3	30·1	30th	72·2
October	78·6	81·7	81·7	77·0	85·8	11·3	74·5	1st	95·6	24·0	17th	71·6
November	76·3	79·8	80·2	74·5	83·2	12·3	70·9	7th	87·2	22·6	13th	64·6
December	73·6	76·9	77·3	72·3	80·2	11·7	68·5	4th	87·5	26·1	28th	61·4
Year	80·9	85·5	85·3	78·8	90·4	15·8	74·6	...	107·7	46·3	...	61·4

110. SALEM (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	75·2	78·7	85·1	74·1	87·6	23·3	64·3	28th	92·0	30·9	4th, 6th & 7th	61·1
February	77·5	80·5	89·5	77·4	92·5	28·7	63·8	28th	97·0	17·9	11th	59·1
March	83·0	84·5	95·8	82·0	98·0	27·1	70·9	26th	102·4	38·0	25th	64·4
April	86·1	88·4	96·8	84·4	100·7	24·7	76·0	15th	104·6	32·5	30th	72·1
May	84·6	87·4	95·3	81·7	99·4	24·5	74·9	16th	104·9	36·6	20th	68·3
June	81·4	83·7	90·4	79·3	95·2	22·3	72·9	17th	98·3	27·4	5th, 9th 25th & 29th	70·9
July	79·6	81·2	87·8	78·7	91·7	20·1	71·6	4th	96·5	26·7	26th	69·8
August	78·7	81·0	85·7	77·3	90·2	19·0	71·2	2nd & 4th	95·4	26·4	15th	69·0
September	80·5	81·8	90·7	78·9	92·4	21·7	70·7	15th	96·4	27·6	4th	68·8
October	76·8	78·9	83·1	76·0	86·7	17·0	69·7	1st	93·7	27·8	24th	65·9
November	74·0	76·9	80·8	72·9	84·2	18·0	66·2	29th	86·6	25·6	23rd	61·0
December	71·8	74·9	79·4	71·3	82·8	19·6	63·2	4th	87·7	31·8	29th & 30th	55·9
Year	79·1	81·5	88·4	77·8	91·8	22·2	69·6	...	104·9	49·0	...	55·9

111. WELLINGTON (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	55·1	59·2	61·1	54·1	65·1	17·9	47·2	27th	70·0	28·6	5th	41·4
February	57·6	64·6	66·2	53·9	69·7	23·3	46·4	26th	76·7	38·1	12th	38·6
March	62·5	68·1	69·0	60·1	72·9	19·2	53·7	28th	77·2	28·5	11th	48·7
April	65·7	71·6*	71·4*	63·6*	75·7*	18·6	57·1*	5th	79·4	25·1	2nd	54·3
May	66·8	73·5	71·1	64·3	77·3	18·3	59·0	18th	80·6	26·0	11th	54·6
June	63·6	67·9	66·8	61·5	72·0	13·2	58·8	16th	76·7	20·8	17th	55·9
July	63·2	66·8	66·4	61·4	71·0	12·4	58·6	31st	77·0	21·7	18th	55·3
August	63·1	67·1	66·3	61·0	71·1	12·9	58·2	10th	74·9	20·3	3rd	54·6
September	62·0	67·6	66·7	59·1	72·3	17·7	54·6	10th	77·1	26·5	23rd	50·6
October	60·1	64·2	63·4	58·1	67·6	12·5	55·1	1st	70·3	19·1	25th	51·2
November	57·3	63·0	61·9	55·0	66·9	17·1	49·8	3rd	72·4	31·5	30th	40·9
December	54·9	59·6†	60·1†	52·7†	64·4†	15·9	48·5†	23rd	69·5	32·7	29th	36·8
Year	61·0	66·1	65·9	58·7	70·5	16·6	53·9	...	80·6	43·8	...	36·8

112. COIMBATORE (*corrected*).

Month.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	74·1	75·5	83·3	74·0	86·2	21·4	64·8	27th	91·4	31·0	13th & 17th	60·4
February	76·8	79·6	88·3	75·8	91·1	26·4	64·7	28th	97·9	39·1	11th	58·8
March	81·3	83·0	93·3	79·3	96·1	25·6	70·5	28th	99·7	32·4	25th	67·3
April	83·3	86·6	93·3	80·5	98·4	24·5	73·9	7th & 10th	102·0	31·7	4th	70·3
May	81·4	85·2	89·1	78·6	93·9	20·4	73·5	1st	99·9	32·0	22nd	67·9
June	78·4	81·7	84·6	76·5	90·1	18·5	71·6	3rd	96·4	28·9	9th	67·5
July	76·6	79·9	81·8	74·8	86·7	16·2	70·5	6th	91·5	25·4	16th	66·1
August	77·0	80·1	83·2	75·6	86·8	17·3	69·5	14th	92·5	26·8	27th	65·7
September	77·7	81·0	85·0	75·2	88·7	19·2	69·5	20th	91·9	26·7	26th	65·2
October	76·1	78·5	82·0	74·3	85·0	14·8	70·2	4th	90·0	23·7	8th	66·3
November	74·1	76·5	80·7	72·6	82·5	15·1	67·4	3rd	86·7	26·4	26th	60·3
December	74·6	79·9	70·9	82·0	17·5	64·5	2nd	80·4	32·2	29th	54·2	
Year	77·4	80·2	85·4	75·7	89·0	19·7	69·2	...	102·0	47·8	...	54·2

* Mean of 29 days. † Mean of 28 days.

113. TRICHINOPOLY (*corrected*).

MONTH.	Mean	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	HIGHEST MAXIMUM. Day.	°	Absolute range	LOWEST MINIMUM. Day.	°
January	76·4	79·8	84·4	73·5	86·9	18·2	68·7	29th	90·9	26·9	26th	64·0
February	77·9	81·6	88·9	75·3	90·9	24·1	66·8	26th	96·3	33·3	17th	63·0
March	84·1	87·5	95·4	81·3	97·7	24·5	73·2	27th	101·5	31·5	10th	70·0
April	88·7	92·1	99·7	86·3	102·4	24·9	77·5	28th	105·8	33·1	2nd	72·7
May	88·4	91·1	98·0	85·1	101·6	22·3	79·3	16th	107·3	32·8	10th & 11th	74·5
June	86·4	90·3	95·6	82·1	98·4	20·0	78·4	18th	102·6	28·2	23rd	74·4
July	84·9	88·5	92·5	81·4	96·9	18·9	78·0	29th	100·4	24·6	31st	75·8
August	84·2	87·1	91·9	81·5	95·4	18·8	76·6	6th	99·8	27·7	13th	72·1
September	84·5	88·1	93·9	80·6	96·6	21·1	75·5	4th	99·9	27·4	29th	72·5
October	79·1	81·7	84·4	77·3	87·8	14·5	73·4	10th	94·7	23·9	29th & 30th	70·8
November	76·5	79·0	81·3	74·7	84·9	14·5	70·4	2nd	89·0	22·3	25th	66·7
December	74·4	77·9	80·1	72·7	83·3	15·2	68·1	4th	89·9	31·6	29th	58·3
Year	82·1	85·5	90·6	79·3	93·6	19·8	73·8	...	107·3	49·0	...	58·3

114. NEGAPATAM (*corrected*).

MONTH.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	HIGHEST MAXIMUM. Day.	°	Absolute range.	LOWEST MINIMUM. Day.	°
January	76·5	79·1	79·4	76·5	81·4	10·0	71·4	30th	83·6	16·8	6th	66·8
February	77·4	80·6	81·1	77·1	83·6	12·4	71·2	28th	86·2	19·4	12th	66·8
March	81·4	85·5	85·5	80·2	88·3	13·6	74·7	29th	90·5	20·9	26th	69·6
April	84·8	89·0	88·6	83·4	92·9	14·1	78·8	28th	99·4	26·2	10th	73·2
May	86·2	90·9	90·3	84·5	97·0	16·9	80·1	21st	106·4	30·4	10th	76·0
June	86·7	89·0	90·0	82·6	96·8	18·9	77·9	12th	102·3	30·7	21st	71·6
July	84·0	87·4	89·7	82·4	95·7	18·3	77·4	29th	99·2	24·2	17th	75·0
August	83·5	86·2	88·4	82·8	93·9	16·8	77·1	1st	99·4	25·8	13th	73·6
September	82·9	86·0	87·2	82·2	93·6	17·3	76·3	21st	96·6	24·0	16th	72·6
October	79·2	81·1	82·5	79·0	85·2	10·7	74·5	1st	92·2	21·1	17th	71·1
November	76·8	78·8	79·6	77·3	82·0	10·0	72·0	1st	87·0	19·4	25th	67·6
December	74·6	76·5	77·6	75·4	79·8	10·0	69·8	5th	87·9	24·5	29th	63·4
Year	81·0	84·2	85·0	80·3	89·2	14·1	75·1	...	106·4	43·0	...	63·4

115. MADURA (*corrected*).

MONTH.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	HIGHEST MAXIMUM. Day.	°	Absolute range	LOWEST MINIMUM. Day.	°
January	77·8	81·6	85·6	76·5	88·8	19·9	68·9	31st	92·8	26·4	11th	66·4
February	78·5	81·6	87·6	77·1	90·8	22·1	68·7	24th	94·3	29·9	17th	64·4
March	83·5	86·5	94·5	80·8	96·9	23·8	73·1	31st	99·8	32·7	1st	67·1
April	86·0	92·5	95·7	81·3	101·6	25·9	75·7	11th	104·0	33·0	2nd	71·0
May	86·3	90·6	96·3	82·1	100·1	23·1	77·0	20th	104·8	31·8	11th	73·0
June	85·7	91·4	93·5	81·6	99·1	21·9	77·2	18th	103·2	29·0	27th	74·2
July	83·4	90·6	89·8	78·8	96·9	21·8	75·1	30th	103·4	30·3	29th	73·1
August	83·6	89·5	91·8	78·3	96·4	21·2	75·2	2nd	101·3	28·8	1st	72·5
September	84·0	89·8	93·7	78·3	98·1	23·9	74·2	1st	101·3	30·3	16th	71·0
October	79·5	84·1	85·2	77·0	89·8	17·4	72·4	1st	98·6	28·7	15th & 25th	69·9
November	77·0	80·6	81·0	76·4	85·5	15·0	70·5	1st & 6th	87·7	21·8	30th	65·9
December	75·5	79·2	81·0	75·1	84·4	16·3	68·1	6th	91·4	29·5	29th	61·9
Year	81·7	86·5	89·6	78·6	94·0	21·0	73·0	...	104·8	42·9	...	61·9

116. COCHIN (*corrected*).

MONTH.	Mean.	10 hours.	16 hours.	22 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	HIGHEST MAXIMUM. Day.	°	Absolute range.	LOWEST MINIMUM. Day.	°
January	79·3	83·1	85·5	77·4	88·7	16·7	72·0	12th	91·6	23·3	5th	68·3
February	79·7	83·1	85·7	77·9	89·0	16·3	72·7	25th	91·8	23·7	12th	68·1
March	82·4	84·7	87·2	81·3	89·8	12·8	77·0	9th	91·7	20·0	14th	71·7
April	83·3	86·0	87·9	81·5	90·3	12·2	78·1	17th	93·7	22·2	18th	71·5
May	82·2	84·3	86·0	81·3	88·6	11·0	77·6	20th	61·6	18·0	10th & 11th	73·6
June	78·9	81·0	82·0	78·2	85·5	10·9	74·6	5th	89·8	17·5	13th	72·3
July	77·2	79·0	79·7	76·6	82·8	8·9	73·9	1st	86·7	15·4	16th	71·3
August	78·1	79·9	80·3	77·5	83·4	8·5	74·9	15th	87·1	13·9	19th	73·2
September	79·5	81·4	82·9	78·6	84·8	9·7	75·1	23rd	86·7	14·3	26th	72·4
October	78·3	81·4	82·0	76·4	84·7	10·7	74·0	28th	86·9	16·0	17th	70·9
November	78·3	81·5	82·4	76·3	85·7	12·2	73·5	18th	88·9	18·2	27th	70·7
December	77·1	80·5	82·3	75·5	85·3	14·2	71·1	13th	87·5	23·0	29th	64·5
Year	79·5	82·2	83·7	78·2	86·6	12·0	74·6	...	93·7	29·2	...	64·5

117. COLOMBO (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	79·7	87·0	14·6	72·4	29th	90·6	20·8	30th	69·8
February	80·1	86·7	13·3	73·4	18th	89·7	21·9	10th	67·8
March	81·7	88·8	14·2	74·6	12th	90·6	18·8	14th	71·8
April	82·8	89·1	12·7	76·4	4th	92·0	19·2	7th	72·8
May	82·7	87·5	9·6	77·9	21st	90·3	17·5	9th & 10th	72·8
June	81·1	85·4	8·7	76·7	2nd	87·8	15·0	9th	72·8
July	81·2	84·8	7·2	77·6	2nd	87·0	14·2	16th	72·8
August	79·2	82·0	5·7	76·3	2nd & 4th	86·9	14·5	30th	72·4
September	81·9	85·9	8·0	77·9	14th	87·7	12·9	20th	74·8
October	80·5	85·5	10·1	75·4	3rd	87·7	15·9	15th	71·8
November	78·7	84·1	10·8	73·3	16th	86·7	15·4	21st	71·3
December	78·1	84·6	13·0	71·6	5th	86·2	18·1	29th	68·1
Year	80·6	86·0	10·7	75·3	...	92·0	24·2	...	67·8

118. JAFFNA (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	77·2	81·5	8·7	72·8	28th	85·3	15·0	28th	70·3
February	77·5	83·6	12·2	71·4	24th	87·2	21·2	10th	66·0
March	82·1	87·4	10·6	76·8	25th	91·7	19·3	8th	72·4
April	85·6	89·1	7·0	82·1	24th	90·7	11·0	26th	79·7
May	84·5	87·1	5·2	81·9	2nd & 3rd	89·0	14·0	9th	75·0
June	83·9	86·2	4·7	81·5	19th	89·3	10·3	21st	79·0
July	82·3	84·7	4·8	79·9	30th	86·6	7·9	16th	78·7
August	83·5	86·0	5·1	80·9	6th	90·0	12·7	8th	77·3
September	83·0	85·6	5·2	80·4	27th	87·0	7·8	27th	79·2
October	79·8	83·0	6·5	76·5	11th	87·3	14·3	28th	73·0
November	77·7	81·0	6·7	74·3	15th	84·0	13·0	29th	71·0
December	76·1	79·3	6·5	72·8	7th	82·5	14·5	28th	68·0
Year	81·1	84·5	6·9	77·6	...	91·7	25·7	...	66·0

119. TRINCOMALEE (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	78·5	83·1	9·2	73·9	19th	85·6	14·5	6th	71·1
February	79·3	84·8	11·1	73·7	27th	88·8	19·5	11th	69·3
March	81·9	89·1	14·5	74·6	30th	92·2	21·1	9th	71·1
April	85·0	93·7	17·4	76·3	15th & 16th.	97·7	24·0	26th	73·7
May	84·4	92·7	16·6	76·1	2nd	96·8	26·0	9th	70·8
June	83·4	91·3	15·8	75·5	18th	96·0	25·4	21st	70·6
July	83·7	92·2	17·0	75·2	27th	96·8	24·6	20th	72·2
August	83·6	92·0	16·8	75·2	2nd	97·2	24·7	11th	72·5
September	84·3	93·6	18·7	74·9	15th	95·6	22·3	9th	73·3
October	81·5	88·7	14·5	74·2	1st	96·4	25·2	1st	71·2
November	78·2	83·5	10·6	72·9	2nd	89·3	18·4	29th	70·9
December	77·6	82·5	9·9	72·6	5th	87·5	17·3	3rd	70·2
Year	81·8	88·9	14·3	74·6	...	97·7	28·4	...	69·3

120. BATTICALOA (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	78·0	82·5	9·1	73·4	23rd & 28th.	84·2	14·0	8th	70·2
February	77·1	83·5	12·9	70·6	23rd	86·6	18·8	10th & 11th.	67·2
March	80·7	87·9	14·5	73·4	30th	90·3	20·1	22nd	70·2
April	83·1	91·4	16·7	74·7	21st	95·0	21·8	2nd, 12th & 19th	73·2
May	84·7	92·5	15·7	76·8	25th	96·2	25·4	7th	70·8
June	84·8	93·5	17·4	76·1	13th, 14th & 16th.	97·0	24·4	21st	72·6
July	85·0	94·4	18·8	75·6	26th	98·2	26·5	6th	71·7
August	85·1	93·9	17·6	76·3	20th	98·0	26·3	14th	71·7
September	83·7	93·0	18·6	74·4	7th	98·0	25·3	8th	72·7
October	80·7	88·3	15·3	73·0	8th	96·4	28·0	23rd	68·4
November	77·3	83·3	12·1	71·2	1st & 2nd	87·8	19·6	18th & 26th.	68·2
December	76·6	82·8	12·5	70·3	12th	86·0	20·8	29th	65·2
Year	81·4	88·9	15·1	73·8	...	98·2	33·0	...	65·2

121. HAMBANTOTA (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	78·9	84·9	12·1	72·8	2nd, 4th, 11th, 12th, 22th, 23rd, & 27th.	86·0	16·9	4th	69·1
February	78·2	85·1	13·9	71·2	19th & 27th	88·0	18·9	18th, 20th & 26th.	69·1
March	80·4	87·5	14·3	73·2	13th	90·0	18·9	9th & 11th	71·1
April	81·6	87·9	12·6	75·3	3rd to 5th, 11th, 14th, 18th & 23rd.	89·0	15·9	1st & 2nd	73·1
May	81·1	85·0	7·9	77·1	1st, 5th & 7th.	87·0	12·9	30th	74·1
June	81·0	86·1	10·3	75·8	24th	92·0	19·9	13th	72·1
July	80·5	85·8	10·7	75·1	26th	94·0	23·9	15th	70·1
August	81·2	86·7	11·1	75·6	4th	93·0	18·9	6th, 8th, 9th, 12th & 16th.	74·1
September	81·3	87·1	11·7	75·4	1st & 5th	90·0	15·9	13th, 19th, 20th, 21st, 27th & 28th.	74·1
October	80·3	86·7	12·8	73·9	3rd & 17th	90·0	18·9	24th	71·1
November	78·7	84·4	11·5	72·9	3rd, 5th & 6th.	87·0	15·9	18th, 24th & 26th.	71·1
December	78·5	85·1	13·2	71·9	6th & 25th	87·0	17·9	5th & 6th.	69·1
Year	80·1	86·0	11·8	74·2	...	94·0	24·9	...	69·1

122. GALLE (*corrected*).

Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
77·6	81·4	7·7	73·7	2nd	85·3	13·1	27th	72·2
78·3	82·5	8·5	74·0	26th	86·0	13·1	1st, 3rd, 20th & 22nd.	72·9
80·8	85·3	9·0	76·3	30th	87·8	13·7	9th	74·1
81·9	85·4	7·0	78·4	31st March	88·1	12·7	18th	75·4
81·6	84·1	5·0	79·1	23rd & 25th.	86·2	12·3	5th	73·9
80·7	83·3	5·3	78·0	6th	85·2	11·5	13th	73·7
80·2	82·5	4·7	77·8	2nd & 26th.	84·2	11·3	15th	72·9
80·4	82·6	4·4	78·2	4th & 6th	84·7	8·7	12th	76·0
80·7	83·2	5·1	78·1	8th	84·7	9·2	21st	75·5
79·3	82·3	6·1	76·2	2nd & 6th	84·0	11·0	27th	73·0
77·9	81·1	6·5	74·6	29th	83·9	11·0	24th	72·9
77·4	81·4	8·1	73·3	14th & 16th.	83·2	12·3	28th to 30th.	70·9
79·7	82·9	6·5	76·5	...	88·1	17·2	...	70·9

123. KANDY (*corrected*).

Month.	Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	73·7	79·1	10·8	68·3	22nd	83·0	17·6	23rd, 30th & 31st.	65·4
February	74·1	80·5	12·9	67·6	27th	85·0	19·6	27th	65·4
March	78·6	85·8	14·4	71·4	7th	88·4	21·2	22nd	67·2
April	78·8	86·0	14·5	71·5	7th	89·5	20·1	20th	69·4
May	79·6	85·4	11·6	73·8	19th & 25th	89·2	19·7	9th & 10th	69·5
June	76·6	81·1	9·0	72·1	2nd & 3rd	87·4	17·4	9th, 10th & 25th.	70·0
July	76·1	80·5	8·8	71·7	3rd	85·5	18·3	15th	67·2
August	76·1	80·7	9·2	71·5	6th	86·6	18·4	22nd	68·2
September	76·3	81·4	10·2	71·2	8th	85·0	16·6	13th	68·4
October	75·1	79·7	9·3	70·4	18th, 19th & 30th.	82·4	13·9	15th	68·5
November	74·0	78·3	8·7	69·6	8th	82·4	15·4	17th	67·0
December	73·4	78·4	10·1	68·3	11th	83·0	21·0	6th	62·0
Year	76·0	81·4	10·8	70·6	...	89·5	27·5	...	62·0

124. NEWERA ELIYA (*corrected*).

Mean.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
56·8	65·6	17·7	47·9	December 1882, 31st	70·0	30·0	4th	40·0
56·4	67·9	23·1	44·8	21st	73·0	41·0	20th	32·0
57·5	69·5	24·1	45·4	2nd	73·0	37·0	21st	36·0
59·7	70·9	22·4	48·5	8th	74·5	34·5	1st	40·0
61·5	70·2	17·4	52·8	17th	76·0	29·0	15th	47·0
58·3	64·6	12·7	51·9	1st	73·0	22·0	2nd, 25th, 29th & 30th	51·0
58·8	64·8	12·0	52·8	4th	70·0	21·0	30th	49·0
58·3	64·4	12·2	52·2	6th	70·0	21·0	5th	49·0
58·5	65·5	14·1	51·4	13th, 15th, 17th, 26th & 28th.	68·0	23·0	13th	45·0
58·1	65·7	15·2	50·5	18th & 19th	69·0	23·0	1st	46·0
58·5	65·9	14·9	51·0	2nd	68·0	22·0	20th	46·0
56·7	65·9	18·4	47·5	11th	69·0	29·0	29th	40·0
58·3	66·7	17·0	49·7	...	76·0	44·0	...	32·0

125. AKYAB (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	69·8	71·3	78·0	80·9	21·3	59·6	31st	85·2	32·3	31st	52·9
February	71·5	74·2	79·6	83·5	24·8	58·7	21st	88·8	38·8	5th	50·0
March	78·7	81·2	83·7	87·8	18·7	69·1	10th	93·7	32·3	17th	61·4
April	83·1	85·5	87·2	91·0	16·4	74·6	5th	93·2	24·6	27th	68·6
May	83·2	84·1	86·3	88·7	11·4	77·3	24th	91·7	23·6	10th	68·1
June	81·2	81·8	82·2*	84·9*	7·3	77·6	1st	89·3	15·2	28th	74·1
July	80·6	80·6	81·5	84·2	6·6	77·6	12th	89·7	14·8	17th	74·9
August	80·1	80·5	80·9†	83·7	6·6	77·1	20th	86·8	13·1	14th	73·7
September	81·3	82·0	82·8	85·1	7·3	77·8	30th	88·2	12·4	8th	75·8
October	82·4	83·6	86·1	88·8	11·9	76·9	6th	91·2	17·2	22nd	74·0
November	76·8	78·2‡	80·9§	83·8‖	13·5	70·3‡	5th	90·4	27·5	21st	62·9
December	71·4	72·1	76·1	79·0	14·0	65·0	4th	85·1	29·0	24th & 25th	56·1
Year	78·3	79·6	82·1	85·1	13·3	71·8	...	93·7	43·7	...	50·0

* Mean of 29 days. ‡ Mean of 27 days. ‖ Mean of 26 days.
† „ „ 30 „ § „ „ 25 „

126. THAYETMYO (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	?	72·6	84·5	85·0	Imperfect.		29th	91·8	?	?	?
February	?	77·0	91·9	92·5	Imperfect.		22nd	98·9	?	?	?
March	81·9	87·1	97·9	99·3	33·4	65·9	27th	104·7	44·4	17th	60·3
April	87·0	91·5	97·9	101·8	25·7	76·1	14th & 19th	104·7	35·9	1st	68·8
May	84·2	88·8	91·8	98·6	22·0	76·6	3rd, 5th & 7th.	103·2	34·2	10th	69·0
June	80·1	83·5	84·1	91·0	15·0	76·0	2nd	96·1	21·4	9th	74·7
July	80·4	82·7	84·3	88·0	11·6	76·4	9th	91·2	16·3	1st	74·9
August	80·6	84·1	84·3	89·2	12·4	76·8	19th & 21st	92·3	17·4	31st	74·9
September	81·0	84·0	86·3	90·0	14·3	75·7	30th	93·2	19·8	20th	73·4
October	81·1	84·4	88·0	90·9	16·7	74·2	6th	92·9	20·8	24th & 25th	72·1
November	75·0	77·8	81·8	84·8	16·6	68·2	4th	92·0	33·2	21st	58·8
December	69·8	72·3	78·8	79·9	19·1	60·8	8th	86·0	34·7	21st & 26th	51·3
Year	?	82·2	87·6	90·9	?	?	...	104·7	?	...	...

127. TOUNGOO (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	69·2	73·3	82·5	85·6	29·7	55·9	31st	91·2	40·1	9th	51·1
February	73·6	78·4	88·6	92·9*	34·3	58·6	20th	96·7	49·6	6th	47·1
March	79·5	85·5	94·3	97·3	32·7	64·6	28th & 31st	100·7	38·5	13th, 22nd & 25th.	62·2
April	?	87·2	92·7	97·3	Untrustworthy.		3rd & 4th	101·7	?	?	?
May	?	86·0	90·7	94·6	Untrustworthy.		4th, 8th & 9th.	98·7	?	?	?
June	77·8	82·1	82·1	87·9	14·5	73·4	1st	93·7	28·5	2nd	65·2
July	77·6	80·9	80·6	85·7	11·1	74·6	10th	90·7	17·5	5th & 18th	73·2
August	77·7	80·5	80·8	86·3	11·8	74·5	6th & 21st	89·7	16·5	11th, 12th, 16th, 25th, 28th & 29th.	73·2
September	78·4	82·2	82·1	87·5	12·9	74·6	21st	90·7	17·5	2nd & 3rd	73·2
October	80·7	86·7	86·7	90·7	16·1	74·6	15th, 17th & 19th.	92·7	19·5	5th, 14th, 23rd, 26th, 28th & 31st.	73·2
November	76·1	80·6	81·6	85·3	14·8	70·5	4th & 6th	90·7	25·5	23rd & 24th.	65·2
December	71·1	76·4	79·2	82·5	19·5	63·0	8th	88·7	33·6	21st	55·1
Year	?	81·7	85·2	89·5	?	?	...	101·7	54·6	...	47·1

128. BASSEIN (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	Highest Maximum. °	Absolute range.	Lowest Minimum. Day.	Lowest Minimum. °
January	70·9	76·8	82·2	85·0	25·5	59·5	31st	89·1	36·5	8th & 9th	52·6
February	75·4	81·2	87·4	91·0	27·7	63·3	20th to 23rd	96·2	41·1	7th	55·1
March	80·2	85·6	90·2	94·5	24·4	70·1	10th & 13th	98·7	35·1	18th	63·6
April	82·7	88·0	90·8	95·5	21·0	74·6	28th & 30th	99·2	29·0	2nd	70·2
May	83·0	86·8	88·6	92·3	14·9	77·3	5th	98·7	25·5	11th	73·2
June	78·3	81·5	80·7	85·7	9·8	75·9	1st	92·2	18·0	29th	74·2
July	78·0	81·2	80·6	84·9	9·5	75·4	17th & 30th	88·1	14·9	5th	73·2
August	78·7	81·5	81·0	85·0	8·7	76·3	1st & 4th	89·4	15·7	28th	73·7
September	?	8·2	80·5	Imperfect.			?	?	?	?	?
October	84·4	Not recorded.					?	?	?	?	?
November	79·3	80·6	Ditto.				?	?	?	?	?
December	76·3	79·6	81·1†	15·3	65·8†		9th	84·6	26·1	26th	58·5
Year	?	82·0	83·9	?	?	?	...	99·2	46·6	...	52·6

* Mean of 27 days. † Mean of 23 days.

129. DIAMOND ISLAND (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	74·5	77·2	79·0	82·5	12·6	69·9	22nd	87·2	21·3	8th	65·9
February	76·1	79·7	80·6	83·7	12·1	71·6	27th	88·3	20·3	7th & 9th	68·0
March	78·5	82·1	82·1	85·0	10·2	74·8	2nd	87·7	14·1	10th	73·6
April	81·2	86·4*	84·8	87·8	10·2	77·6*	30th	91·0	16·0	8th	75·0
May	82·3	85·9	85·9	90·1	11·5	78·6	10th	92·9	19·9	14th & 15th	73·0
June	78·6	81·8	81·3	84·4	8·6	75·8	1st	89·7	26·7	27th & 28th	73·0
July	78·0	82·0	80·6	84·1	8·7	75·4	1st	86·7	15·7	19th	71·0
August	78·3	82·0†	80·6†	84·5†	8·6	75·9†	5th & 6th	87·9	15·5	29th	72·4
September	77·9	81·1	80·9	84·1	9·2	74·9	21st & 27th	87·2	14·8	7th	72·4
October	80·4	83·9	83·7	86·7	9·6	77·1	15th	89·3	15·9	30th	73·4
November	77·5	80·2	80·9	84·2	10·2	74·0	4th	89·9	19·7	30th	70·2
December	76·0	77·8	80·9	83·0	12·0	71·0	8th	87·8	21·7	26th	66·1
Year	78·3	81·5	81·8	85·0	10·3	74·7	...	92·9	27·0	...	65·9

* Mean of 29 days. † Mean of 30 days.

130. RANGOON (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	74·4	77·8	84·5	87·7	23·4	64·3	28th & 29th	92·5	35·6	9th	56·9
February	77·4	79·8	89·8	93·4	28·5	64·9	19th	98·2	42·5	7th	55·7
March	81·4	83·2	91·4	96·4	25·1	71·3	14th & 28th	99·2	32·1	18th	67·1
April	83·1	85·4	90·9	94·6	19·3	75·3	28th	99·5	26·7	2nd & 3rd	72·8
May	81·8	86·0	86·0	92·0	14·5	77·5	4th	99·3	25·5	11th	73·8
June	79·0	81·5	81·7	85·7	9·5	76·2	1st	92·8	19·4	29th	73·4
July	77·2	81·2	78·6	85·3	9·5	75·8	8th	88·7	14·6	19th	73·5
August	78·1	81·9	79·5	85·9	9·3	76·6	3rd	90·7	17·5	12th	73·2
September	78·2	80·2	81·0	84·6	9·3	75·3	21st	89·5	15·6	8th	72·9
October	81·0	84·8	85·8	88·9	12·8	76·1	21st	92·8	20·6	19th & 25th	72·2
November	77·9	80·5	82·4	85·1	11·7	73·4	4th	91·5	23·7	21st	67·8
December	75·0	78·2	82·0	85·0	17·1	67·9	2nd	87·5	28·0	26th	59·5
Year	78·7	81·7	84·5	88·7	15·8	72·9	...	99·5	43·8	...	55·7

131. MOULMEIN (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	74·0	76·9	85·3	87·7*	25·0	62·7	31st	92·6	37·8	7th	54·8
February	78·5	80·3	89·3	92·1	24·5	67·6	2nd & 20th	94·9	36·3	7th	58·6
March	81·0	85·3	89·8	93·7	21·6	72·1	30th	97·9	30·1	19th	67·8
April	82·7	86·0	90·2	93·1	17·9	75·2	30th	97·6	25·1	6th	72·5
May	81·2	84·8	87·5	90·3	15·5	74·8	1st	94·0	22·0	2nd	72·0
June	77·3	79·4	80·4	83·5	9·3	74·2	1st	89·9	18·3	20th	71·6
July	76·7	78·7	79·7	82·0	8·3	73·7	16th	85·7	13·3	24th	72·4
August	77·6	80·0	81·0	84·5	10·4	74·1	3rd	87·1	16·0	12th	71·1
September	77·3	79·3	81·1	83·4	9·9	73·5	30th	88·0	16·3	4th	71·7
October	80·6	83·9	86·9	89·2	15·0	74·2	22nd	92·0	21·3	31st	70·7
November	77·5	82·7	83·6	91·0	19·6	71·4	10th	99·4	33·2	23rd	66·2
December	75·5	79·5	84·5	86·5	20·1	66·4	2nd	90·2	28·8	17th	61·4
Year	78·3	81·4	84·9	88·1	16·4	71·7	...	99·4	44·6	...	54·8

* Mean of 30 days.

132. MERGUI (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	76·4	79·9	84·0	89·5	20·7	68·8	31st	93·0	35·0	8th	58·0
February	80·6	86·2	88·4	92·3	19·6	72·7	15th	93·9	22·7	21st	71·2
March	80·4	86·9	88·2	92·3	19·7	72·6	7th	94·2	24·2	29th	70·0
April	80·3	86·4	87·4	91·3	18·2	73·1	25th	94·4	23·4	1st, 2nd, 3th, 9th, 17th, 18th & 24th	71·0
May	79·7	84·4	85·2	90·1	16·0	74·1	5th	95·1	24·1	22nd	71·0
June	76·3	79·9	79·7	84·5	11·7	72·8	1st	90·1	19·9	28th	70·2
July	75·8	79·2	79·2	83·3	11·0	72·3	29th	87·2	17·2	14th	70·0
August	76·1	80·8	79·7	84·5	12·0	72·5	9th	89·1	18·5	18th	70·6
September	75·8	78·9	79·5	83·5	11·5	72·0	7th	86·7	16·7	13th	70·0
October	77·0	82·4	82·2	86·8	15·0	71·8	12th	90·1	21·2	30th	68·9
November	77·2	81·0	82·9	85·8	18·6	67·2	6th	88·7	28·8	16th	59·9
December	75·1	81·0	82·9	85·8	15·9	71·7	...	95·1	37·1	...	58·0
Year	77·5	82·4	83·3	87·6	15·9	71·7	...	95·1	37·1	...	58·0

133. PORT BLAIR (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	79·3	81·7	83·3	86·0	10·8	75·2	26th	88·5	18·4	8th	70·1
February	79·7	81·9	86·0	87·9	14·6	73·3	24th	90·2	21·7	17th & 18th	68·5
March	81·6	84·6	88·6	90·4	15·9	74·5	24th & 25th	92·1	19·7	3rd & 15th	72·4
April	83·7	87·1	89·9	92·8	15·3	77·5	28th	96·1	21·2	1st & 4th	74·9
May	82·2	85·3	86·2	90·3	12·1	78·2	1st & 4th	94·1	21·2	26th	72·9
June	80·8	82·9	83·7	86·3	8·4	77·9	1st & 16th	90·2	16·3	25th	73·9
July	79·4	81·5	82·0	84·8	8·0	76·8	30th	88·8	15·9	2nd	72·9
August	79·8	82·2	82·7	85·8	9·0	76·8	8th	89·3	16·4	29th & 30th	72·9
September	78·5	80·8	81·1	84·6	8·8	75·8	14th	88·0	15·9	5th	72·1
October	80·5	83·4	83·8	87·2	10·1	77·1	25th	89·8	14·9	6th	74·9
November	79·6	82·0	82·7	85·4	8·9	76·5	6th	85·5	15·6	11th, 27th & 28th.	73·9
December	78·0	79·7	80·9	83·9	8·9	75·0	2nd	86·2	14·3	16th & 27th	71·9
Year	80·3	82·8	84·2	87·1	10·9	76·2	..	96·1	27·6	...	68·5

134. NANCOWRY (*corrected*).

Month.	Mean.	10 hours.	16 hours.	Mean of Maxima.	Mean daily range.	Mean of Minima.	Highest Maximum. Day.	°	Absolute range.	Lowest Minimum. Day.	°
January	79·7	82·6	82·0	87·6	10·3	77·3	1st	90·8	15·7	31st	75·1
February	80·4	83·9	83·9	87·5*	10·6	76·9	22nd	89·0	16·8	16th	72·2
March	81·1	85·8	84·4	88·8	11·1	77·7	13th & 14th	89·8	13·7	8th	76·1
April	82·5	87·4	85·9	90·3	11·2	79·1	7th	93·5	16·4	9th	77·1
May	82·7	85·8	85·8	90·8	12·3	79·5	7th	93·3	17·5	14th	75·8
June	81·1	84·4	83·7	88·5	10·0	78·5	16th	90·6	15·5	23rd	75·1
July	?	84·0	84·0	88·0	*Dry min. tm. untrustworthy.*		27th to 29th	90·2	?	?	?
August	?	83·8	82·5	88·8	Ditto		13th to 15th	91·4	?	?	?
September	?	82·1	82·2	88·8	Ditto.		11th, 12th, 14th & 25th.	90·0	?	?	?
October	?	84·1	82·8†	87·8	Ditto.		11th & 30th	88·4	?	?	?
November	?	82·0	80·4	88·3	Ditto.		20th, 22nd, 23rd, 28th & 30th.	88·8	?	?	?
December	?	81·4	80·9	88·8	Ditto.		14th & 15th	90·8	?	?	?
Year	?	?	?	?	?		...	93·5	?	...	?

* Mean of 27 days. † Mean of 30 days.

TABLE VI.—SEA-LEVEL EQUIVALENTS OF MONTHLY MEAN AIR-TEMPERATURES IN 1883 (111 STATIONS).

STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
Zanzibar	81·5	81·7	83·0	81·1	78·5	79·1	76·9	77·4	77·6	78·7	79·9	81·2	79·7
Aden	75·7	75·7	78·9	81·8	84·5	87·3	81·7	84·5	85·8	82·1	77·1	74·6	80·8
Seychelles	?	?	?	?	?	76·4	76·3	76·3	76·9	77·0	75·6	75·0	?
Bushire	57·9	58·1	62·5	72·7	83·1	85·8	88·7	90·6	85·5	79·7	70·4	61·1	74·7
Mooltan	56·4	57·9	69·7	83·0	87·6	95·7	90·2	90·6	88·2	78·3	64·6	56·7	76·6
Dera Ismail Khan	55·3	56·4	67·3	80·9	88·4	97·3	91·9	93·4	88·4	77·3	62·6	55·9	76·3
Peshawar	52·4	53·7	63·1	75·9	86·8	94·4	91·1	91·0	85·8	73·6	59·7	52·9	73·4
Rawalpindi	52·6	53·1	62·7	77·2	84·6	94·1	89·9	88·2	83·3	73·5	58·7	52·1	72·5
Sialkot	55·7	56·5	66·8	82·6	88·8	96·6	90·3	89·1	84·8	77·7	64·0	55·5	75·7
Lahore	56·6	57·8	70·3	85·4	91·0	97·6	93·3	93·5	85·1	77·8	63·9	56·0	77·4
Ludhiana	55·5	56·6	69·6	83·4	89·9	92·3	88·6	91·7	84·3	76·8	63·7	55·9	75·7
Delhi	61·0	62·4	74·2	89·1	93·6	95·3	89·9	93·1	87·6	81·3	68·0	60·8	79·7
Sirsa	57·3	59·1	70·4	86·2	90·3	95·6	90·7	93·7	85·9	79·0	64·4	57·4	77·5
Dehra	58·7	60·4	68·8	83·8	88·4	88·1	84·8	84·2	81·9	74·3	64·3	58·3	74·7
Roorkee	58·7	59·1	70·1	86·2	90·1	91·3	86·7	87·3	83·9	76·1	64·7	57·2	76·0
Meerut	58·3	59·6	71·9	86·6	90·4	93·1	88·3	90·0	85·3	77·1	64·4	57·2	76·9
Bareilly	60·2	61·2	72·2	86·7	89·7	92·1	86·0	87·3	85·3	78·1	66·1	57·3	76·9
Agra	63·4	64·0	77·3	92·1	96·1	95·8	87·7	92·4	88·8	83·5	70·7	62·1	81·2
Lucknow	62·7	63·5	75·5	89·8	93·5	92·6	86·3	87·7	86·0	78·6	67·4	59·3	78·6
Gorakhpur	60·5	61·8	75·1	85·9	89·7	86·7	85·2	86·0	85·6	80·7	68·3	60·7	77·2
Jhansi	65·4	66·4	79·1	93·4	97·4	95·9	85·3	88·2	85·8	83·2	73·5	64·3	81·5
Allahabad	60·9	62·5	76·3	89·7	94·1	91·5	85·4	86·5	83·7	77·9	67·0	58·9	77·9
Benares	62·2	63·8	76·6	88·8	93·2	89·0	85·3	86·7	84·8	79·0	68·1	59·1	78·1
Ghazipur	59·9	60·9	73·8	86·6	90·9	86·2	84·5	85·1	84·6	77·3	65·8	57·5	76·1
Sibsagar	59·6	62·4	68·5	75·1	79·0	84·2	85·6	83·9	82·9	77·9	69·1	60·4	74·1
Dhubri	62·6	64·9	75·3	79·6	77·3	81·3	83·3	81·5	80·9	78·1	70·6	62·8	74·9
Silchar	63·9	65·8	74·1	78·0	76·4	81·8	84·0	81·9	81·9	79·5	72·9	64·7	75·4
Purneah	62·3	?	75·1	83·4	83·9	84·6	85·2	83·7	83·7	79·1	69·0	59·9	?
Durbhanga	62·8	63·9	75·1	84·0	85·5	85·4	85·3	84·2	84·3	80·2	69·9	62·2	76·9
Patna	62·5	64·4	77·1	87·7	90·5	86·6	84·8	84·6	85·1	80·8	70·0	61·2	77·9
Gya	64·8	67·4	80·2	92·6	96·2	88·6	84·9	86·5	86·1	82·3	71·7	62·9	80·4
Hazaribagh	64·9	66·9	77·7	90·5	93·7	85·9	82·1	82·9	82·6	79·8	69·6	62·5	78·3
Berhampore	63·9	66·6	76·7	84·8	84·4	82·7	82·5	81·7	83·0	80·3	71·0	62·4	76·7
Burdwan	64·9	67·6	77·5	84·4	85·5	83·7	82·8	81·9	83·1	80·4	71·3	63·2	77·2
Jessore	64·0	67·3	77·6	81·9	83·8	82·7	82·5	82·3	82·2	80·5	71·1	63·4	76·6
Dacca	65·9	69·1	79·2	83·5	83·7	83·2	84·0	83·8	83·9	82·7	74·1	66·5	78·3
Chittagong	65·7	68·8	75·9	80·2	81·6	80·2	80·5	80·1	80·6	80·1	74·1	66·6	76·2
Calcutta (ALIPORE)	63·9	67·5	77·9	83·8	86·1	83·9	82·8	82·4	82·7	80·1	69·8	62·4	76·9

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September	October.	November.	December.	Year.
Calcutta (Chowringhee)	66·6	69·4	78·8	83·7	85·6	83·4	82·4	81·8	82·5	80·9	71·7	64·2	77·6
Saugor Island	66·8	69·7	79·2	83·8	85·9	84·8	83·0	82·6	82·7	81·0	72·6	64·7	78·1
Cuttack	72·3	76·0	83·3	88·4	89·7	84·3	83·0	83·4	83·5	82·5	74·1	66·2	80·6
False Point	66·9	69·7	77·9	81·1	82·8	82·0	80·7	80·7	81·4	79·8	70·4	62·6	76·3
Sambalpur	69·7	75·1	81·8	92·0	97·5	88·7	81·4	83·3	82·9	80·7	70·1	62·8	80·5
Raipur	69·8	74·8	82·7	93·0	98·7	85·2	81·2	83·9	80·7	78·9	70·3	62·6	80·2
Nagpur	71·0	76·2	84·1	92·8	97·9	85·4	82·0	84·4	80·5	79·0	71·5	64·7	80·8
Seoni	68·9	73·4	81·8	90·8	94·8	84·5	81·0	82·6	80·1	77·4	69·7	63·2	79·0
Jubbulpore	67·0	69·8	80·0	90·5	97·5	88·7	81·7	83·6	81·2	76·8	67·6	58·8	78·6
Saugor	68·2	70·0	80·0	91·7	94·4	88·3	82·2	83·0	81·4	78·3	71·3	64·0	79·4
Hoshangabad	69·3	71·8	81·2	91·7	95·4	88·6	81·3	82·1	80·6	77·7	69·6	61·5	79·2
Khandwa	70·2	73·1	81·6	91·8	94·9	86·7	81·4	82·1	80·1	77·4	69·7	61·6	79·2
Chanda	70·4	77·4	84·0	93·2	98·4	86·4	82·2	83·0	80·0	78·8	69·0	61·9	80·4
Sironcha	72·7	79·6	85·7	93·3	98·3	85·0	81·1	81·9	79·9	80·5	72·3	66·2	81·4
Buldana	73·1	78·7	84·1	92·7	93·0	83·5	79·3	79·2	77·0	77·4	73·1	67·9	79·9
Akola	71·5	76·3	83·7	92·5	96·2	85·5	81·2	82·3	79·3	77·7	70·8	63·0	80·0
Amraoti	72·7	78·2	84·5	92·9	95·3	84·4	80·3	82·6	78·4	77·6	72·0	66·6	80·5
Neemuch	66·2	65·7	77·3	89·8	91·1	89·2	81·7	83·1	80·2	77·8	69·6	62·6	77·9
Nowgong	62·5	63·9	76·7	89·2	94·0	92·9	83·9	85·5	83·8	77·9	67·0	58·5	78·0
Sutna	62·5	64·5	76·4	88·7	93·6	91·3	83·4	84·8	82·6	77·3	66·9	59·2	77·6
Indore	68·2	69·4	77·8	88·7	91·4	85·7	80·3	80·6	78·7	75·6	68·3	61·4	77·2
Bickaneer	61·7	64·6	75·9	91·2	94·5	98·7	90·9	93·3	88·7	84·7	71·0	62·8	81·5
Jeypore	64·0	65·2	76·8	90·9	92·4	92·1	85·7	89·0	85·8	81·5	69·9	62·6	79·7
Sambhar	60·6	63·0	75·0	90·3	93·8	93·4	85·8	88·7	85·0	79·6	66·7	58·9	78·4
Ajmere	62·0	63·8	75·1	89·7	92·4	91·4	84·4	87·3	83·8	78·9	67·0	59·7	78·0
Pachbudra	60·3	63·7	74·8	88·8	91·5	93·9	86·9	88·4	84·2	80·9	67·2	59·9	78·4
Jacobabad	58·1	60·5	73·1	88·0	94·0	98·4	91·7	91·3	89·0	76·8	63·7	57·5	78·5
Hyderabad	62·7	65·4	76·2	87·8	91·8	91·5	86·6	85·5	84·7	83·0	69·5	62·7	79·0
Kurrachee	65·9	67·9	74·7	81·1	85·3	87·7	83·5	81·0	81·4	80·3	70·4	66·0	77·1
Bhuj	68·0	69·3	77·2	86·7	86·7	88·8	?	82·8	80·6	83·5	72·3	66·1	?
Rajkot	68·6	69·3	77·3	86·8	89·0	88·0	81·9	83·3	79·3	79·9	71·3	65·2	78·3
Deesa	69·0	71·2	80·0	92·1	92·0	91·8	83·2	85·4	82·5	81·2	72·3	67·2	80·7
Surat	70·3	71·7	77·5	84·2	86·2	83·3	81·0	81·6	78·6	78·8	72·8	67·6	77·8
Malegaon	71·3	74·5	80·6	89·4	91·5	84·5	80·7	80·0	78·9	78·2	71·1	63·8	78·7
Bombay	75·6	75·1	78·2	82·6	84·6	82·1	80·6	80·3	78·6	80·2	77·9	73·4	79·1
Poona	76·3	82·2	85·3	91·0	89·8	80·8	78·7	79·2	77·1	79·8	77·1	71·3	80·7
Sholapore	73·8	80·8	85·5	91·1	92·0	81·2	81·9	81·4	80·0	81·1	77·9	71·1	81·5
Ratnagiri	74·8	75·7	77·6	82·1	84·5	79·3	78·5	78·7	77·2	78·5	76·1	73·0	78·0
Belgaum	75·6	82·1	84·6	86·1	85·9	77·8	75·9	77·0	75·6	78·4	76·2	73·4	79·1
Karwar	75·3	75·9	78·3	81·7	83·5	77·6	76·8	77·3	76·3	76·6	74·6	72·8	77·2

Stations.	January.	February.	March.	April.	May.	June.	July.	August	September.	October.	November.	December.	Year.
Gopalpore	68·3	74·6	79·8	81·4	82·7	82·6	80·8	82·6	82·5	81·3	72·5	64·2	77·8
Vizagapatam	75·4	79·4	83·7	86·2	88·8	87·5	85·6	86·0	84·9	83·7	76·8	72·9	82·6
Masulipatam	74·0	75·8	80·8	84·0	89·0	85·5	82·8	83·9	84·0	80·6	75·4	71·4	80·6
Secunderabad	73·5	80·8	84·5	91·7	95·9	83·9	80·8	81·1	79·3	79·4	73·2	69·6	81·1
Kurnool	?	81·2	87·5	92·1	92·8	84·3	81·6	81·7	81·2	80·1	75·3	70·8	?
Bellary	75·1	80·7	87·5	92·6	93·2	86·5	83·9	83·4	84·1	80·9	76·0	72·4	83·0
Mangalore	76·8	78·8	80·8	82·6	83·0	78·4	76·6	77·3	77·9	77·6	77·5	75·5	78·6
Mercara	72·1	75·7	77·8	78·9	78·7	73·7	72·2	73·7	72·7	74·1	72·4	70·0	74·3
Bangalore	72·9	77·7	83·8	86·9	85·9	81·3	77·8	79·1	79·0	77·3	74·0	71·0	78·9
Madras	75·6	76·4	80·7	83·7	87·5	86·6	83·2	83·9	84·7	78·6	76·3	73·6	80·9
Salem	77·3	79·6	85·1	88·2	86·7	83·5	81·7	80·8	82·6	78·9	76·1	73·9	81·2
Coimbatore	77·1	79·8	84·3	86·3	84·4	81·4	79·6	80·0	80·7	79·1	77·1	75·1	80·4
Trichinopoly	77·0	78·5	84·7	89·3	89·0	87·0	85·5	84·8	85·1	79·7	77·1	75·0	82·7
Negapatam	76·5	77·4	81·4	84·8	86·2	84·7	84·0	83·5	82·9	79·2	76·8	74·6	81·0
Madura	78·8	79·5	84·5	87·0	87·3	86·7	84·4	84·6	85·0	80·5	78·0	76·5	82·7
Cochin	79·3	79·7	82·4	83·3	82·2	78·9	77·2	78·1	79·5	78·3	78·3	77·1	79·5
Colombo	79·8	80·2	81·8	82·9	82·8	81·2	81·3	79·3	82·0	80·6	78·8	78·2	80·7
Jaffna	77·2	77·5	82·1	85·6	84·5	83·9	82·3	83·5	83·0	79·8	77·7	76·1	81·1
Trincomalee	78·9	79·7	82·3	85·4	84·8	83·8	84·1	84·0	84·7	81·9	78·6	78·0	82·2
Batticaloa	78·1	77·2	80·8	83·2	84·8	84·9	85·1	85·2	83·8	80·8	77·4	76·7	81·5
Hambantota	79·0	78·3	80·5	81·7	81·2	81·1	80·6	81·3	81·4	80·4	78·8	78·6	80·2
Galle	77·7	78·4	80·9	82·0	81·7	80·8	80·3	80·5	80·8	79·4	78·0	77·5	79·8
Kandy	77·5	77·9	82·4	82·6	83·4	80·4	79·9	79·9	80·1	68·9	77·8	77·2	79·8
Akyab	69·8	71·5	78·7	83·1	83·2	81·2	80·6	80·1	81·3	82·4	76·8	71·4	78·3
Thyetmio	?	?	82·2	87·3	84·5	80·4	80·7	80·9	81·3	81·4	75·3	70·1	?
Tounghoo	69·6	74·0	79·9	?	?	78·2	78·0	78·1	78·8	81·1	76·5	71·5	?
Bassein	71·0	75·5	80·3	82·8	83·1	78·4	78·1	78·8	?	?	?	72·8	?
Diamond Island	74·6	76·2	78·6	81·3	82·4	78·7	78·1	78·4	78·0	80·5	77·6	76·1	78·4
Rangoon	74·5	77·5	81·5	83·2	81·9	79·1	77·3	78·2	78·3	81·1	78·0	75·1	78·8
Moulmein	74·2	78·7	81·2	82·9	81·4	77·5	76·9	77·8	77·5	80·8	77·7	75·7	78·5
Mergui	76·6	80·8	80·6	80·5	79·9	76·5	76·0	76·3	76·0	77·2	77·0	75·3	77·7
Port Blair	79·4	79·8	81·7	83·8	82·3	80·9	79·5	79·9	78·6	80·6	79·7	78·1	80·4
Nancowry	79·9	80·6	81·3	82·7	82·9	81·3	?	?	?	?	?	?	?

TABLE VII.—MONTHLY MEANS AND EXTREMES OF PRESSURE IN 1883 (125 STATIONS).

1. ZANZIBAR.

2. ADEN.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		29 +		29 +			29 +	29 +	29 +		29+		29 +		
January	·849	·914*	·783†	·131	·996	1st	·703	21st	·293	·931	·984	·878	·106	1.083	5th	·778	21st	·305
February	·870	·925‡	·815§	·110	·979	8th	·729	7th	·250	·915	·968	·862	·106	1·050	8th	·762	17th	·288
March	·864	·931‖	·796‖	·135	·996	18th	·715	6th	·281	·867	·930	·803	·127	1·050	9th	·735	19th	·315
April	·897	·952§	·841§	·111	1·028	30th	·784	13th	·244	·781	·841	·721	·120	·924	1st	·620	26th	·304
May	·974	1·025	·922	·103	1·141	12th	·843	6th	·298	·722	·780	·665	·115	·861	20th & 21st	·547	31st	·314
June	1·062	1·114	1·010	·104	1·192	25th	·954	3rd	·238	·602	·661	·543	·118	·740	3rd	·458	30th	·282
July	1·093	1·139	1·046	·093	1·167	17th	·982	2nd	·185	·571	·641	·501	·140	·745	17th	·431	31st	·314
August	1·067	1·124	1·010	·114	1·185	14th & 17th	·940	9th	·245	·594	·661	·526	·135	·728	17th	·435	1st	·293
September	1·068	1·127	1·009	·118	1·186	19th	·968	6th	·218	·691	·749	·633	·116	·825	20th	·517	6th & 7th	·308
October	1·004	1·064	·944	·120	1·165	4th	·872	21st & 22nd	·293	·835	·885	.784	·101	·992	30th	·684	21st	·308
November	·921	·982	·860	·122	1·052	8th	·746	16th	·306	·885	·935	·835	·100	1·009	18th	·758	6th	·251
December	·929	·990	·867	·123	1·050	10th	·754	20th	·296	1·005	1·050	·960	·090	1·097	13th	·836	25th	·261
Year	·967	1·024	·909	·115	1·192	...	·703	...	·489	·783	·840	·726	·115	1·097	...	·431	...	·666

* Mean of 27 days.
† " " 28 "
‡ Mean of 22 days.
§ " " 21 "
‖ Mean of 30 days.

3. SEYCHELLES.

4. BUSHIRE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		30 +		29 +			29 +	29 +	29 +		29 +		29 +		
January										1·065	1·099‡‡	1·031‡‡	·068	1·231	13th	·841	21st	·390
February										1·060	1·089	1·031	·058	1·277	7th	·933	14th & 26th.	·344
March	Observatory opened in June 1883.									·980	1·007	·952	·055	1·122	4th	·669	15th	·453
April										·838	·869	·807	·062	·959	1st	·579	24th	·380
May										·703	·729	·676	·053	·863	5th	·509	26th	·354
June	·934	·967*	·901†	·066	·034	25th	·856	21st	·178	·527	·550	·504	·046	·773	1st	·395	29th	·378
July	·971	1·001‡	·941‖	·060	·043	11th	·891	2nd	·152	·455	·482	·427	·055	·543	13th	·352	11th	·191
August	·966	·999*	·933§	·066	·064	18th	·896	6th	·168	·532	·562	·502	·060	·636	15th	·370	5th	·266
September	·976	1·015**	·937‡	·078	·079	19th	·869	6th	·210	·680	·707	·653	·054	·839	19th	·497	6th	·342
October	·966	1·007††	·924††	·083	·061	5th	·867	19th	·194	·924	·954‡‡	·894‡‡	·060	1·100	16th	·739	8th	·361
November	·904	·943††	·865††	·078	·026	8th	·806	5th	·220	1·017	1·044	·990††	·054	1·179	19th	·829	10th	·350
December	·951	·989**	·912¶	·077	·067	7th	·877	20th	·190	1·135	1·171	1·099	·072	1·288	14th	·850	24th	·438
Year	...	...	...	...	...	...	...	...	...	·826	·855	·797	·058	1 288	...	·352	...	·936

* Mean of 22 days.
† " " 20 "
‡ " " 25 "
§ Mean of 24 days.
‖ " " 21 "
¶ " " 26 "
** Mean of 28 days.
†† " " 29 "
‡‡ Mean of 30 days.

5. QUETTA.

Month.	Mean. 10 hours.	Mean. 16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	24 +	24 +	24 +		24 +		24 +	
January	·647	·686	·607	·079	·871	4th	·327	25th	·544
February	·647	·688	·606	·082	·796	21st	·488	28th	·308
March	·603	·641	·564	·077	·788	25th	·449	3rd	·339
April	·597	·636	·557	·079	·716	8th	·451	27th	·265
May	·526	·555	·497*	·058	·642	16th	·315	27th	·327
June	·430	·465	·395	·070	·677	1st	·266	27th	·411
July	·399	·433	·364	·069	·492	1st	·279	6th	·213
August	·453	·489	·417	·072	·554	14th	·326	5th	·228
September	·527	·571†	·483‡	·088	·690	30th	·376	5th	·314
October	·716	·736	·675	·081	·867	28th	·556	7th	·311
November	·714	·752	·675	·077	·859	18th	·528	10th	·331
December	·764	·804	·723	·081	·892	31st	·598	1st	·294
Year	·585	·623	·547	·076	·892	...	·266	...	·626

* Mean of 30 days.
† ,, 23 ,,
‡ ,, 22 ,,

6. LEH.

Month.	Mean. 6 hours.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	19 +	19 +	19 +	19 +		19 +		19 +		
January	·567	...	·601	526	...	·073	·992	4th, 10h.	·204	26th, 16h.	·788
February	·536	...	·568	·496	...	·072	·756	6th, ,,	·318	18th, ,,	·438
March	·616	...	·651	·576	...	·075	·813	15th, ,,	·387	5th, ,,	·426
April	·684	...	·719	·630	...	·089	839	21st, ,,	·460	4th, ,,	·379
May	·647	...	·669	609	...	·060	·831	31st, ,,	·429	27th, ,,	·402
June	·643	...	·673	·598	...	·075	·871	1st, ,,	·494	5th, ,,	·377
July	·580	...	·622	·516	...	·106	·736	3rd, ,,	·374	25th, ,,	·362
August	·603	...	·642	539	...	·103	·738	27th, ,,	·416	1st, ,,	·322
September	·663	·696	·711	·604	·652	·107	·885	18th, ,,	·498	2nd, ,,	·387
October	·736	·759	·782	·685	·731	·097	·881	16th, 6h.	·580	18th, ,,	·301
November	·663	·675	·707§	·626§	·655§	·081	·862	21st, 10h.	·435	10th, ,,	·427
December	·713	·719	·769	·673	·711	·096	·928	25th, ,,	·445	16th, ,,	·483
Year	·638	...	·676	·590	...	·086	·992	...	·204	...	·788

§ Mean of 29 days.

7. MOOLTAN.

Month.	Mean. 10 hours.	Mean. 16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	28 +	29 +		28 +		
January	·621	·676	1·566	·110	·852	4th & 10th	1·171	25th	·681
February	·602	·657	1·547	·110	·789	14th	1·360	17th	·429
March	·471	·529	1·413	·116	·712	13th	1·149	18th	·563
April	·333	·385	1·280	·105	·535	9th	1·088	27th	·447
May	·161	·207	1·114	·093	·439	30th	·946	21st	·493
June	·005	·052	·958	·094	·332	1st	·846	27th	·486
July	·046	·088	1·003	·085	·238	1st	·893	26th	·345
August	·093	·139	1·046	·093	·276	14th	·927	1st	·349
September	·227	·280	1·173	·107	·464	30th	1·005	6th	·459
October	·477	·529	1·424*	·105	·690	28th	1·258	7th	·432
November	·562	·607	1·517†	·090	·730	20th & 21st	1·294	10th	·436
December	·717	·767	1·667	·100	·885	31st	1·527	2nd	·358
Year	·360	·410	1·309	·101	·885	...	·846	...	1·039

* Mean of 30 days.
† ,, 29 ,,

8. DERA SMAIL KHAN.

Month.	Mean. 10 hours.	Mean. 16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +	29 +		28 +		
January	1·478	1·522	1·433	·089	·709	10th	1·008	25th	·701
February	1·440	1·493	1·386	·107	·633	19th	1·167	17th	·466
March	1·346	1·397	1·294	·103	·550	13th	1·123	18th	·427
April	1·195	1·250	1·139	·111	·384	9th	·947	27th	·437
May	1·035	1·082	·987	·095	·269	29th	·839	11th	·430
June	·881	·945‡	·816‖	·129	·150	1st	·680	27th	·470
July	·890	·932	·847	·085	·109	1st	·690	31st	·419
August	·939	·985	·892	·093	·121	13th	·697	5th	·424
September	1·088	1·139	1·036	·103	·319	30th	·879	6th	·440
October	1·338	1·384	1·292	·092	·534	27th	1·145	7th	·389
November	1·408	1·453	1·363	·090	·565	30th	1·177	10th	·388
December	1·553	1·597	1·508	·089	·725	31st	1·380	15th	·345
Year	1·216	1·265	1·166	·099	·725	...	·680	...	1·045

‡ Mean of 24 days.
‖ ,, 25 ,,

9. PESHAWAR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +		
January .	·926	·972	·880	·092	1·148	10th	·495	25th	·653
February .	·902	·957	·847	·110	1·108	19th	·610	17th	·498
March . .	·804	·856	·752	·104	1·005	25th	·594	27th	·411
April . .	·683	·739	·626	·113	·874	9th	·410	27th	·464
May . .	·487	·359	·434	·105	·774	30th	·291	26th	·483
June . .	·338	·391	·284	·107	·620	1st	·140	27th	·480
July . .	·354	·408	·300	·108	·601	15th	·119	31st	·482
August .	·412	·471	·352	·119	·613	7th	·109	5th	·504
September .	·552	·610	·493	·117	·806	30th	·314	6th	·492
October .	·804	·858	·749	·109	·999	27th	·571	7th	·428
November .	·862	·910	·814	·096	1·036	30th	·631	10th	·405
December .	1·005	1·055	·954	·101	1·179	31st	·791	15th	·388
Year . .	·677	·731	·624	·107	1·179	...	·109	...	1·070

10. MURREE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	23 +	23 +	23 +		23 +		23 +		
January .	·831	·853	808	·045	1·015	4th	·430	25th	·585
February .	·835	·852	·817	·035	·934	14th	·568	18th	·366
March . .	·839	·855	·822	·033	·967	25th	·663	18th	·304
April . .	·857	·874	·840	·034	·972	9th	·756	27th	·216
May . .	·760	·780	·740	·040	·911	30th	·564	12th	·347
June . .	·720	·737	·703	·034	·890	1st	·643	14th	·247
July . .	·701	·718	·683	·035	·812	4th & 15th	·583	18th	·229
August .	·746	·763	·729*	·034	·839	19th	·605	5th	·234
September .	·823	·843	·803	·040	·947	30th	·677	5th & 6th	·270
October .	·942	·958	·925†	·033	1·077	15th	·835	7th	·242
November .	·880	·894	·866	·028	1·010	4th	·754	10th	·256
December .	·941	·960	·921*	·039	1·026	31st	·803	15th	·223
Year . .	·823	·841	·805	·036	1·077	...	·438	...	·639

* Mean of 30 days. † Mean of 29 days.

11. RAWALPINDI.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27 +	27 +	27 +		28 +		27 +		
January .	1·338	1·375	1·301	·074	·567	10th	·874	25th	·693
February .	1·313	1·350	1·275	·075	·452	19th	1·037	18th	·415
March . .	1·234	1·272	1·196*	·076	·409	13th	1·017	18th	·392
April . .	1·131	1·168*	1·093†	·075	·288	9th	·912	27th	·376
May . .	·967	1·005	·929	·076	·241	30th	·752	12th	·489
June . .	·839	·884	·793	·091	·117	1st	·689	27th	·428
July . .	·853	·898	·807	·091	·066	1st	·649	31st	·417
August .	·918	·960	·876	·084	·081	7th	·683	5th	·398
September .	1·040	1·081	·998	·083	·260	29th	·860	6th	·400
October .	1·257	1·297	1·216*	·081	·433	27th	1·077	7th	·356
November .	1·295	1·331*	1·259	·072	·434	20th	1·122	10th	·312
December .	1·427	1·467*	1·386*	·081	·585	31st	1·240	15th	·345
Year . .	1·134	1·174	1·094	·080	·585	...	·649	...	·936

12. SIALKOT.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +		
January .	1·167	1·208	1·126	·082	1·393	10th	·726	25th	·667
February .	1·140	1·176	1·103	·073	1·289	21st	·971	18th	·318
March . .	1·042	1·076	1·008	·068	1·226	13th	·881	18th	·345
April . .	·913	·949	·876	·073	1·065	9th	·732	27th	·333
May . .	·754	·789‡	·718*	·071	1·109	31st	·514	20th	·595
June . .	·633	·675*	·590*	·085	·770	2nd	·510	27th	·260
July . .	·653	·692	·614	·078	·844	15th	·472	25th	·372
August .	·721	·758	·683	·075	·873	14th	·539	1st	·334
September .	·842	·881	·803	·078	1·040	30th	·708	6th	·332
October .	1·055	1·094	1·015	·079	1·217	28th	·884	7th	·333
November .	1·108	1·144	1·072	·072	1·239	20th	·921	9th	·318
December .	1·248	1·288	1·208	·080	1·400	31st	1·090	15th	·310
Year . .	·940	·978	·901	·076	1·400	...	·472	...	·928

† Mean of 28 days. * Mean of 29 days. ‡ Mean of 30 days.

13. LAHORE.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Range	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	28 +	28 +	28 +	28 +	28 +		28 +		28 +		
January	1·277	1·257	1·330	1·243	1·279	·087	1·516	10th, 10h.	·824	25th, 16h.	·692
February	1·258	1·238	1·309	1·223	1·263	·086	1·424	2nd, „	1·021	18th „	·403
March	1·143	1·128	1·191	1·108	1·146	·083	1·338	14th, „	·937	18th, „	·401
April	1·003	·988	1·055	·967	1·003	·088	1·175	9th, „	·793	27th, „	·382
May	·838	·828	·887	·799	·836	·088	1·156	30th, „	·592	12th, 4h.	·564
June	·713	·710	·772	·670	·701	·102	1·029	1st, „	·562	27th, 16h.	·467
July	·734	·735	·786	694	·722	·092	·968	1st, „	·563	25th, „	·405
August	·792	·784	·845	·751	·788	·094	·977	14th, „	·600	5th, „	·377
September	·934	·919	·987	·901	·927	·086	1·152	30th, „	·770	6th, 4h.	·382
October	1·155	1·140	1·209	1·119	1·151	·090	1·349	27th, „	·975	5th, 16h.	·374
November	1·214	1·195	1·263	1·181	1·217	·082	1·378	20th, „	1·000	9th, „	·378
December	1·366	1·345	1·416	1·334	1·368	·082	1·526	31st, „	1·205	15th, „	·321
Year	1·036	1·022	1·088	·999	1·033	·088	1·526	...	·562	...	·964

14. LUDHIANA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +		
January	1·203	1·249	1·157	·092	1·410	5th	·821	25th	·589
February	1·175	1·219	1·131	·088	1·332	21st	·922	18th	·410
March	1·063	1·104	1·021	·083	1·252	13th	·909	31st	·343
April	·927	·973	·881	·092	1·085	4th	·748	27th	·337
May	·770	·813	·727	·086	1·049	30th	·557	12th	·492
June	·670	·716	·624	·092	·943	1st	·545	26th	·398
July	·685	·728	·642	·086	·910	15th	·512	25th	·398
August	·736	·782	·690	·092	·894	14th	·564	5th	·330
September	·863	·908	·818	·090	1·055	30th	·680	6th	·375
October	1·079	1·125	1·032	·093	1·260	27th	·886	6th	·374
November	1·138	1·182	1·093	·089	1·274	18th	·931	9th	·343
December	1·280	1·323	1·236	·087	1·404	21st	1·124	15th	·280
Year	966	1·010	·921	·089	1·410	...	·512	...	·898

15. KAILANG.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	20 +	20 +	20 +		20 +		20 +		
January	Observatory established in July 1883.								
February									
March									
April									
May									
June									
July	·629	·669*	·588*	·081	·962	10th	·427	31st	·535
August	·615	·651	·579	·072	·726	14th & 18th	·469	4th	·257
September	·694	·724	·663	·061	·781	21st	·577	1st	·204
October	·792	·823	·760	·063	·911	21st	·663	7th	·248
November	·772	·805	·739	·066	·923	5th	·604	28th	·319
December	·839	·865	·812†	·053	·967	12th	·585	15th	·382
Year	...	...	..	...	...	...	...	...	...

16. SIMLA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	23 +	23 +	23 +		23 +		23 +		
January	·290	·312	·268	·044	·463	4th	·000	26th, 10h.	·463
February	·257	·280	·233	·047	·363	17th	·172	24th	·191
March	·263	·288	·237	·051	·372	25th	·147	2nd	·225
April	·276	·308	·243	·065	·414	9th	·133	26th & 27th	·281
May	·210	·234‡	·186‡	·048	·353	30th	·102	12th	·251
June	·160	·188	·131	·057	·340	1st	·069	5th & 27th	·271
July	·144	·169	·119	·050	·278	1st	·024	25th	·254
August	·190	·214	·166	·048	·289	14th	·071	5th	·218
September	·259	·289	·228	·061	·395	21st	·082	5th	·313
October	·371	·399	·343	·056	·504	15th	·247	7th	·257
November	·305	·335	·274	·061	·430	4th	·181	27th	·249
December	·340	·381	·299	·082	·441	20th, 25th & 26th.	·148	19th	·293
Year	·255	·283	·227	·056	·504	...	·000	...	504

* Mean of 24 days.
† „ „ 30 „
‡ Mean of 29 days.

17. DELHI.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +		
January	1·304	1·355	1·253	·102	1·534	4th	·994	25th	·540
February	1·267	1·321	1·213	·108	1·426	21st	1·117	25th	·309
March	1·155	1·209	1·100	·109	1·378	13th	·953	27th	·425
April	·995	1·054	·935	·119	1·172	9th	·777	30th	·395
May	·858	·911	·805	·106	1·114	30th	·658	20th	·456
June	·764	·822	·706	·116	1·035	1st	·627	10th	·408
July	·782	·831	·733	·098	·972	4th	·632	25th	·340
August	Untrustworthy.								
September	Ditto.								
October	Ditto.								
November	Ditto.								
December	Ditto.								
Year	Ditto.								

18. SIRSA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		29 +		28 +		
January	1·362	1·410	1·314	·096	·590	4th	·943	25th	·647
February	1·351	1·399	1·303	·096	·520	21st	1·118	18th	·402
March	1·215	1·264	1·166	·098	·431	13th	1·022	27th	·409
April	1·069	1·123	1·014*	·109	·255	4th	·865	27th	·390
May	·917	·967	·867	·100	·177	30th	·707	21st	·470
June	·816	·863	·769	·094	·092	1st	·673	27th	·419
July	·831	·878	·784	·094	·018	4th	·694	25th	·324
August	·884	·935	·833	·102	·066	14th	·733	5th	·333
September	1·010	1·056	·964	·092	·235	30th	·774	6th	·461
October	1·248	1·295	1·200	·095	·431	28th	1·052	5th	·379
November	1·300	1·341	1·259	·082	·447	20th	1·068	9th	·379
December	1·450	1·492	1·408	·084	·568	21st & 26th	1·297	15th	·271
Year	1·121	1·169	1·073	·095	·590	...	·673	...	·917

* Mean of 29 days.

19. CHAKRATA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	23 +	23 +	23 +		23 +		22 +		
January	·226	·262	·211	·051	·424	4th	·923	27th	·501
February	·203	·241	·190	·051	·314	17th	1·095	1st	·219
March	·209	·242	·199	·043	·324	24th	1·104	4th	·220
April	·224	·259	·210	·049	·346	9th	1·129	26th	·217
May	·155	·188	·141	·047	·282	31st	1·048	28th	·234
June	·111	·132	·093	·039	·271	1st	1·006	6th	·265
July	·088	·114	·072	·042	·224	1st	·973	25th	·251
August	·131	·155	·111	·044	·217	19th	1·022	5th	·195
September	·195	·226	·171	·055	·330	30th	1·060	5th	·270
October	·322	·357	·301	·056	·442	15th	1·214	7th	·228
November	·266	·297	·251	·046	·384	4th	1·181	28th	·203
December	·303	·337	·284	·053	·399	26th	1·175	17th	·224
Year	·203	·234	·186	·048	·442	...	·923	...	·519

20. MUSSOOREE (ST. FIDELIS).

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	24 +	24 +	24 +		24 +		23 +		
January	·315	·348*	·282†	·066	·563	10th	1·071	26th	·492
February	·282	·302‡	·261§	·041	·401	11th	1·185	1st	·216
March	·276	·297*	·255‖	·042	·399	8th	1·165	4th	·234
April	·272	·308¶	·235**	·073	·372	9th	1·157	26th	·215
May	·206	·230	·181	·049	·352	30th	1·098	12th	·254
June	·152	·182‖	·121	·061	·324	1st	1·022	16th	·802
July	·122	·142*	·101‖	·041	·267	1st	·962	18th	·305
August	·181	·204††	·157	·047	·283	19th	1·072	5th	·211
September	·248	·278‡‡	·218†	·060	·380	30th	1·104	5th	·276
October	·374	·402‖	·346*	·056	·485	15th	1·282	5th	·203
November	·320	·347†	·293§§	·054	·436	4th	1·207	27th	·229
December	Imperfect.								
Year	?	?	?	?	·563	...	·962	...	·601

* Mean of 29 days.
† " " 26 "
‡ " " 24 "
§ " " 23 "
‖ Mean of 28 days.
¶ " " 22 "
** " " 20 "
†† Mean of 30 days.
‡‡ " " 27 "
§§ " " 21 "

21. DEHRA.

Month.	Mean.	04 hours.	16½ hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27 +	27 +	27 +		27 +		27 +			24 +	24 +	24 +		24 +		24 +		
January	·741	·793	·711	·082	·940	5th	·481	25th	·459	·976	1·033	·952	·081	1·226	4th	·720	26th	·506
February	·693	·739	·659	·080	·826	14th	·552	25th	·274	·934	·99	·904	·093	1·072	19th	·812	25th	·260
March	·626	·671	·597	·074	·779	13th	·450	26th	·329	·928	·979	·898	·081	1·102	6th	·793	26th	·309
April	·525	·584	·488	·096	·667	9th	·365	27th	·302	·889	·952	·861	·091	1·038	9th	·752	26th	·286
May	·413	·461	·380	·081	·637	30th	·261	20th	·376	·801	·858	·782	·076	·995	30th	·676	20th	·319
June	·351	·400	·315	·085	·580	1st	·219	5th	·361	·738	·795	·716	·079	·946	1st	·649	14th	·297
July	·351	·392	·324	·068	·538	15th	·219	25th	·319	·737	·777	·713*	·064	·906	15th	·600	25th	·306
August	·401	·442	·370	·072	·526	19th	·283	4th	·243	·776	·829†	·759	·070	·912	13th	·674	5th	·238
September	·490	·538	·455	·083	·658	30th	·317	5th	·341	·855	·915	·833	·082	1·014	30th	·696	5th	·318
October	·693	·747	·656	·091	·860	27th	·526	6th	·334	1·009	1·078‡	·986‡	·092	1·177	27th	·886	6th	·291
November	·713	·762	·678	·084	·832	4th	·600	10th	232	·982	1·039	·954	·085	1·130	4th	·870	27th	·260
December	·815	·867	·781	·086	·941	31st	·677	15th	·264	Observatory abolished.								
Year	·568	·616	·535	·082	·941	...	·219	...	·722	...	...	...	...	...	...	...	...	...

* Mean of 30 days. ‡ Mean of 28 days.
† „ „ 29 „

22. PAORI.

23. ROORKEE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.	Mean.	10 hours.	16 hours.	Range.	Highest reading	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +			23 +	23 +	23 +		24 +		23 +		
January	1·108	1·176	1·069	·107	1·331	5th	·831	25th	·500	1·089	1·133	1·071	·062	·262	4th	·859	31st	·403
February	1·060	1·106	1·026	·080	1·224	21st	·882	25th	·342	1·062	1·098	1·045	·053	·171	19th	·955	1st	·216
March	·955	1·003*	·925*	·078	1·156	13th	·745	26th	·411	1·057	1·090	1·037	·053	·150	24th	·960	2nd	·190
April	·801	·871	·756	·115	·960	9th	·627	27th	·333	1·040	1·081	1·023	·058	·162	9th	·939	26th	·223
May	·684	·743	·644	·099	·948	30th	·498	12th	·450	·975	1·013	·962	·051	·116	30th	·878	20th	·238
June	·600	·666	·551	·115	·853	1st	·454	18th	·399	·916	·955	·901	·054	·092	1st	·837	6th	·255
July	·615	·670	·578	·092	·814	15th	·447	26th	·367	·908	·941	·889	·052	·078	1st	·782	26th	·296
August	·674	·733	·628	·105	·833	22nd	·536	4th	·297	·944	·988	·930	·058	·058	22nd	·855	5th	·203
September	·774	·837	·729	·108	·970	30th	·588	5th	·382	1·014	1·057	·998	·059	·128	29th	·905	5th	·223
October	·994	1·061	·949	·112	1·195	27th	·798	6th	·397	1·134	1·185	1·116	·069	·266	27th	1·026	7th	·240
November	1·050	1·105	1·010	·095	1·186	4th	·914	10th	·272	1·104	1·145	1·085	·060	·296	1st	·961	27th	·335
December	1·179	1·241	1·139	·102	1·342	21st	1·031	15th	·311	1·152	1·194	1·136	·058	·264	30th	1·051	15th	·213
Year	·875	·934	·834	·101	1·342	...	·447	...	·895	1·033	1·073	1·016	·057	·296	...	·782	...	·514

* Mean of 30 days.

24. RANIKHET.

25. PITHORAGARH.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	24 +	24 +	24 +		24 +		24 +		
January	·749	·809	·725	·084	·934	4th	·544	31st	·390
February	·708	·762	·682	·080	·860	19th	·594	25th	·266
March	·692	·743	·663	·080	·820	8th	·564	26th	·256
April	·656	·715	·630	·085	·801	9th	·534	30th	·267
May	·592	·646	·574	·072	·795	22nd	·470	11th	·325
June	·530	·581*	·511†	·070	·717	1st	·439	16th	·278
July	·527	·565	·504	·061	·672	15th	·401	26th	·271
August	·557	·607	·541	·066	·672	20th & 21st	·469	5th	·203
September	·633	·686	·613	·073	·780	30th	·520	5th	·260
October	·764	·830	·742	·088	·933	27th	·650	5th	·283
November	·749	·804‡	·723†	·081	·876	4th	·654	27th	·222
December	·808	·862	·787	·075	·944	30th	·696	15th	·248
Year	·664	·718	·641	·076	·944	...	·401	...	·543

* Mean of 28 days.
† „ „ 29 „

26. MEERUT.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +		
January	1·274	1·331	1·230	·101	1·487	4th	·999	25th	·488
February	1·232	1·288	1·187	·101	1·392	21st	1·087	25th	·305
March	1·108	1·163	1·072	·091	1·327	13th	·941	27th	·386
April	·961	1·027	·910	·117	1·133	9th	·755	30th	·378
May	·814	·871	·777	·094	1·031	31st	·628	20th	·403
June	·728	·790	·687	·103	·987	1st	·595	14th	·392
July	·744	·798	·700	·098	·929	4th	·592	18th	·337
August	·799	·858	·754	·104	·958	13th	·655	5th	·303
September	·897	·960	·855	·105	1·122	30th	·699	5th	·423
October	1·140	1·200	1·094	·106	1·319	28th	·951	5th & 6th	·368
November	1·206	1·264	1·162	·102	1·331	18th	1·091	11th	·240
December	1·337	1·396	1·292	·104	1·482	21st	1·187	13th	·295
Year	1·020	1·079	·977	·102	1·487	...	·592	...	·895

27. BAREILLY.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	28 +	29 +		29 +		28 +		
January	1·465	1·522	1·423	·099	·655	5th	1·219	26th	·436
February	1·392	1·447	1·346	·101	·540	21st	1·235	25th	·305
March	1·280	1·334	1·231	·103	·488	13th	1·093	26th	·395
April	1·122	1·187	1·068	·119	·291	9th	·926	30th	·365
May	1·000	1·056	·950	·106	·259	30th	·818	12th	·441
June	·925	·983	·858	·125	·166	1st	·751	18th	·415
July	·936	·980	·884	·096	·107	1st	·783	26th	·324
August	·993	1·042	·938	·104	·132	13th	·859	1st	·273
September	1·095	1·146	1·040	·106	·290	30th	·932	6th	·358
October	1·325	1·378	1·280	·098	·505	27th	1·133	7th	·372
November	1·382	1·440	1·335	·105	·517	18th	1·235	11th	·282
December	1·518	1·573	1·473	·100	·673	21st	1·328	7th	·345
Year	1·203	1·257	1·152	·105	·673	...	·751	...	·922

28. AGRA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28 +	29 +	28 +		29 +		28 +		
January	1·475	·541	1·427	·114	·715	4th	1·186	26th	·529
February	1·448	·511	1·397	·114	·610	14th	1·292	25th	·318
March	1·324	·388	1·268	·120	·537	13th	1·170	27th	·367
April	1·170	·239	1·112	·127	·353	8th	·947	30th	·406
May	1·036	·095	·982	·113	·282	30th	·832	20th	·450
June	·946	·004	·880	·124	·211	1st	·754	13th	·457
July	·968	·017	·911	·106	·159	4th	·835	18th	·324
August	1·024	·075	·967	·108	·196	13th	·872	23rd	·324
September	1·123	·174	1·068	·106	·344	30th	·898	6th	·446
October	1·352	·411	1·301	·110	·537	27th	1·153	7th	·384
November	1·407	·466	1·360	·106	·577	18th	1·228	10th	·349
December	1·555	·614	1·505	·109	·695	19th & 21st	1·383	16th	·312
Year	1·236	·295	1·182	·113	·715	...	·754	...	·961

29. LUCKNOW.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		29 +		28 +		
January	·667	·734	·617	·117	·893	4th	1·441	25th	·452
February	·622	·679	·574	·105	·764	2nd	1·505	28th	·259
March	·501	·556	·451	·105	·693	7th	1·322	26th	·371
April	·337	·403	·282	·121	·501	8th & 9th	1·142	30th	·359
May	·208	·270	·153	·117	·451	30th	1·039	20th	·412
June	·146	·196	·089	·107	·391	1st	·969	18th	·422
July	·147	·189	·096	·093	·340	3rd	·977	19th	·363
August	·213	·256	·163	·093	·354	13th	1·067	23rd	·287
September	·305	·355	·250	·105	·502	30th	1·111	6th	·391
October	·535	·592	·485	·107	·734	27th	1·329	6th	·405
November	·595	·656	·547	·109	·735	18th	1·458	8th	·277
December	·734	·795	·686	·109	·914	31st	1·580	5th	·334
Year	·418	·473	·366	·107	·914	...	·969	...	·945

30. GORAKHPUR.

Mean.	10 hours.	16 hours.	Range	Highest reading.	Date,	Lowest reading.	Date.	Absolute range.
29 +	29 +	29 +		29 +		29+		
·783	·853	·732	·121	·991	5th	·594	23rd	·397
·715	·776	·666	·110	·870	2nd	·593	27th	·277
·594	·652	·542	·110	·790	7th	·413	26th	·377
·445	·511	·390	·121	·614	9th	·255	26th	·359
·328	·396	·268	·128	·535	30th	·167	12th	·368
·276	·328	·217	·111	·473	1st	·124	5th	·349
·259	·304	·205	·099	·429	3rd	·081	25th	·348
·325	·373	·271	·102	·491	13th	·206	1st	·285
·417	·471	·359	·112	·616	30th	·233	6th	·383
·642	·701	·591	·110	·824	27th	·424	6th	·400
·692	·754	·644	·110	·823	4th	·560	14th	·263
·836	·893	·789	·104	·986	20th & 29th	·662	5th	·324
·526	·584	·473	·112	·991	...	·081	...	·910

31. JHANSI.

Month.	Mean.	10 hours	16 hours.	Range.	Highest reading.	Date,	Lowest reading.	Date.	Absolute range.
	28 +	28 +	28 +		28 +		28 +		
January	1·147	1·204	1·106	·098	1·374	4th	·863	25th	·511
February	1·129	1·186	1·082	·104	1·264	21st	·997	18th	·267
March	1·022	1·078	·972	·106	1·220	14th	·889	27th	·331
April	·885	·942	·837	·105	1·058	8th	·684	30th	·374
May	·766	·820	·718	·102	·974	30th	·596	20th	·378
June	·676	·720	·625	·095	·906	1st	·537	10th	·369
July	·684	·728	·646	·082	·893	4th	·570	19th	·323
August	·750	·793	·701	·092	·928	13th	·605	24th	·323
September	·822	·865	·775	·090	1·040	30th	·612	6th	·428
October	1·042	1·088	1·002	·086	1·195	28th	·857	6th	·338
November	1·088	1·134	1·052	·082	1·230	18th	·925	9th	·305
December	1·223	1·273	1·183	·090	1·372	23rd	1·060	16th	·312
Year	·936	·986	·892	·094	1·374	...	·537	...	·837

32. ALLAHABAD.

Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Range	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
29 +	29 +	29 +	29 +	29 +		29 +		29 +		
·731	·704	·801	·682	·738	·119	·947	4th, 10h.	·477	26th, 16h. 25th, 4h.	·470
·683	·654	·756	·632	·688	·124	·855	2nd, ,,	·562	28th, 16h.	·293
·553	·526	·627	·502	·557	125	·763	13th, ,,	·406	28th, ,,	·357
·400	·384	·474	·336	·405	·138	·591	8th, ,,	·192	30th, ,,	·399
·267	·247	·330	·216	·276	·114	·513	30th, ,,	·101	19th, ,,	·412
·199	·199	·250	·135	·212	·115	·441	1st, ,,	·028	18th, ,,	·413
·202	·189	·245	·148	·224*	·097	·404	3rd, ,,	·050	24th, ,,	·354
·273	·257*	·323	·219	·291	·104	·446	13th, ,,	·109	23rd, ,,	·337
·359	·343	·412	·300	·381	·112	·576	30th, ,,	·171	6th, ,,	·405
·599	·580	·658	·551	·606	·107	·785	27th, ,,	·390	6th, ,,	·395
·654	·632	·720	·605	·660	·115	·864	18th, ,,	·515	10th, ,,	·289
·797	·769	·866	·750	·802	·116	·969	21st, ,,	·643	4th & 5th, ,,	·326
·476	·457	·539	·423	·487	·116	·969	...	·028	...	·941

* Mean of 30 days.

33. BENARES.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		29 +		29 +		
January	·779	·849	·728	·121	·986	4th	·539	26th	·447
February	·727	·793	·672	·121	·895	2nd	·602	27th	·293
March	·601	·666	·544	·122	·814	7th	·438	26th	·376
April	·435	·508	·376	·132	·621	8th	·244	30th	·377
May	·303	·367	·247*	·120	·542	30th	·123	12th	·719
June	·244	·293	·188	·105	·494	1st	·095	18th	·399
July	·238	·283	·184	·099	·435	3rd	·667	20th	·368
August	·310	·360	·254	·106	·501	13th	·151	23rd	·350
September	·393	·448	·334	·114	·612	30th	·199	8th	·413
October	·635	·694	·583	·111	·820	27th	·420	6th	·400
November	·692	·756	·641	·115	·843	18th	·516	14th	·327
December	·840	·903	·789	·114	1·005	21st	·670	4th	·335
Year	·516	·577	·462	·115	1·005	...	·067	...	·938

* Mean of 30 days.

34. GHAZIPUR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		29 +		29 +		
January	·832	·892	·771	·121	1·032	4th	·628	26th	·404
February	·765	·822	·707	·115	·921	2nd	·635	27th	·286
March	·634	·696	·572	·124	·851	7th	·455	19th	·396
April	·468	·537	·399	·138	·637	8th	·270	26th	·367
May	·332	·392	·272	·120	·552	30th	·197	12th	·355
June	·281	·330	·231	·099	·509	1st	·135	18th	·374
July	·277	·323	·231	·092	·449	3rd	·109	25th	·340
August	·341	·391	·290	·101	·525	13th	·197	23rd	·328
September	·426	·479	·373	·106	·607	30th	·249	8th	·358
October	·656	·711	·600	·111	·834	26th	·420	1st	·414
November	·708	·759	·656	103	·841	4th	·551	8th	·290
December	·874	·917	831	·086	1·053	21st	·701	4th	·352
Year	·550	·604	·494	·110	1·053	...	·109	...	·944

35. KATMANDU.*

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	25 +	25 +	25 +		25 +		25 +		
January	·782	·831	·732	·099	·902	26th	·636	24th	·266
February	·609	·668	·550	·118	·783	19th	·448	5th	·335
March	·609	·664	·553	·111	·788	11th	·437	26th	·351
April	·501	·549	·453	·096	·644	8th	·399	27th	·245
May	·417	·454	·379	·075	·584	4th	·299	20th	·285
June	·331	·364	·298	·066	·454	1st	·202	7th	·252
July	·330	·367	·292	·075	·490	3rd	·188	25th	·302
August	·411	·455†	·366	·089	·556	20th	·264	1st	·292
September	Imperfect.								
October	Not recorded.								
November	Ditto.								
December	Ditto.								
Year	...	...	...	...	...	...	...	...	...

36. SIBSAGAR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		29 +		29 +		
January	·745	·809	·666	·143	·963	5th	·499	30th	·464
February	·658	·725	·578	·147	·784	2nd	·477	22nd	·307
March	·568	·631	·490	·141	·716	1st	·362	20th	·354
April	·481	·550	·404	·146	·677	21st	·274	30th	·403
May	·382	·444	·317	·127	·566	15th	·184	25th	·382
June	·289	·345	·225	·120	·494	1st	·138	6th	·356
July	·254	·320	·180	·140	·458	15th	·025	25th	·433
August	·320	·383	·251	·132	·478	30th	·127	1st	·351
September	·412	·477	·340	·137	·633	30th	·173	6th	·460
October	·595	·663	·518	·145	·787	27th	·293	6th	·494
November	·632	·697	·548	·149	·765	18th	·416	14th	·349
December	·778	·837†	·709	·128	·960	19th	·600	1st	·360
Year	·510	·573	·436	·138	·963	...	·025	...	·938

* The readings from 1st January to 9th March have been corrected to the present elevation of 4,387·8 feet. The register is of doubtful accuracy.

† Mean of 30 days.

37. DHUBRI.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·946	1·015	·877	·138	1·154	5th	·737	30th	·417
February .	·860	·936	·784	·152	·995	2nd & 10th.	·702	22nd	·293
March . .	·738	·819	·657	·162	·913	11th	·521	20th	·392
April . .	·649	·729	·569	·160	·843	22nd	·471	26th	·372
May . .	·562	·627	·496	·131	·731	30th	·397	26th	·334
June . .	·479	·535	·422	·113	·667	1st	·306	6th	·361
July . .	·449	·505	·392	·113	·648	15th	·254	25th	·394
August . .	·519	·579	·459	·120	·695	13th	·328	1st	·367
September .	·611	·677	·545	·132	·838	30th	·410	6th	·428
October .	·799	·862	·735*	·127	·982	27th	·567	6th	·415
November .	·828	·896	·760	·136	·974	18th	·639	14th	·335
December .	·981	1·048	·913	·135	1·158	19th	·778	1st	·380
Year . .	·702	·769	·634	·135	1·158	...	·254	...	·904

38. SILCHAR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·947	1·015	·879	·136	1·163	5th	·747	31st	·416
February .	·880	·955	·807	·148	1·011	19th	·754	24th	·257
March . .	·785	·866	·714	·152	·953	7th	·596	20th	·357
April . .	·704	·777	·631	·146	·851	23rd	·513	30th	·338
May . .	·606	·664	·545	·119	·786	9th	·427	27th	·359
June . .	·521	·571	·459	·112	·741	1st	·327	6th	·414
July . .	·479	·532	·402	·130	·691	15th	·251	26th	·440
August . .	·552	·611	·477	·134	·713	20th	·354	24th	·359
September .	·642	·705	·566	·139	·832	30th	·387	6th	·445
October .	·799	·857	·731	·126	·957	27th	·585	5th	·372
November .	·809	·870	·749	·121	·967	18th	·605	14th	·362
December .	·953	1·014	·891	·123	1·117	19th	·744	7th	·373
Year . .	·723	·786	·654	·132	1·163	...	·251	...	·912

* Mean of 30 days.

39. DARJEELING (ST. PAUL'S SCHOOL).

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	22+	22+	22+		22+		22+		
January .	·974	1·014	·933	·081	1·138	5th	·742	31st	·396
February .	·928	·963	·892*	·071	1·051	19th	·794	5th	·257
March . .	·930	·968†	·892*	·076	1·045	7th	·770	2nd	·275
April . .	·938	·976‡	·900§	·076	1·047	22nd	·792	2nd	·255
May . .	·895	·932†	·858‖	·074	1·033	30th	·752	12th	·281
June . .	·865	·896	·833‡	·063	1·001	1st	·754	6th	·247
July . .	·860	·891	·828†	·063	·989	14th	·699	25th	·290
August . .	·889	·928	·850	·078	1·005	20th	·717	5th	·288
September .	·965	·998	·931*	·067	1·062	30th	·855	6th	·207
October . .	1·048	1·081*	1·015¶	·066	1·169	15th	·895	8th	·274
November .	1·002	1·041**	·962**	·079	1·114	4th	·871	10th	·273
December .	1·040	1·081	·998	·083	1·172	30th	·911	17th	·261
Year . .	·945	·981	·908	·073	1·172	...	·699	...	·473

40. PURNEAH.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·917	·990†	·859	·131	1·135	5th	·713	31st	·422
February .	·831	·909	·772	·137	·977	2nd	·702	24th	·275
March . .	·709	·784	·641	·143	·909	7th	·509	20th & 29th.	·400
April . .	·592	·665	·521	·144	·770	22nd	·449	26th	·321
May . .	·494	·555	·424	·131	·662	15th	·344	24th	·318
June . .	·412	·458	·350	·108	·611	21st	·202	19th	·409
July . .	·407	·450	·350	·100	·583	15th	·218	25th	·365
August . .	·478	·530**	·414**	·116	·638	13th	·293	1st	·345
September .	·571	·625	·505	·120	·789	30th	·380	6th	·409
October . .	·774	·836	·716	·120	·956	27th	·536	6th	·420
November .	·814	·879	·758	·121	·957	18th	·649	14th	·308
December .	963	1·035	·906	·129	1·149	21st	·792	1st	·357
Year . .	·664	·726	·601	·125	1·149	...	·202	...	·947

* Mean of 27 days. † Mean of 30 days. ‡ Mean of 28 days. § Mean of 26 days. ‖ Mean of 25 days. ¶ Mean of 23 days. ** Mean of 29 days.

TABLE VII.—MONTHLY MEANS AND EXTREMES OF PRESSURE IN 1883.

41. DURBHUNGA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·905	·975	·844	·131	1·142	5th	·710	30th	·432
February .	·817	·884	·762	·122	·985	2nd	·696	24th	·289
March . .	·689	·756	·629*	·127	·896	7th	·483	29th	·413
April . .	·563	·634	·494	·140	·733	8th	·415	26th	·318
May . .	·455	·518	·390	·128	·630	30th	·317	12th	·313
June . .	·376	·430	·319	·111	·591	21st	·225	15th	·366
July . .	·365	·414	·307	·107	·543	15th	·168	25th	·375
August .	·438	·495	·380	·115	·602	13th	·268	1st	·334
September .	·527	·584	·467	·117	·737	30th	·336	7th	·401
October .	·744	·808	·687	·121	·937	27th	·508	6th	·429
November .	·790	·859	·732	·127	·934	18th	·619	14th	·315
December .	·939	1·003	·886	·117	1·113	19th	·769	1st	·344
Year . .	·634	·697	·575	·122	1·142	...	·168	...	·974

* Mean of 30 days.

42. PATNA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·883	·952	·823	·129	1·090	4th	·690	31st	·400
February .	·807	·880	·747	·133	·981	2nd	·673	24th	·308
March . .	·675	·741	·616	·125	·884	7th	·487	29th	·397
April . .	·534	·601	·469	·132	·713	8th	·370	30th	·343
May . .	·408	·473	·341	·132	·589	30th	·243	19th	·346
June . .	·350	·399	·299	·100	·566	1st	·177	15th	·389
July . .	·345	·391	·290	·101	·506	3rd	·165	25th	·341
August .	·415	·468	·361	·107	·579	13th	·262	1st	·317
September .	·501	·554	·445	·109	·699	30th	·320	6th	·379
October .	·723	·783	·669	·114	·921	27th	·506	6th	·415
November .	·776	·848	·717	·131	·942	18th	·625	14th	·317
December .	·930	1·003	·871	·132	1·116	21st	·744	5th	·372
Year . .	·612	·674	·554	·120	1·116	...	·165	...	·951

43. HAZARIBAGH.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	27+	27+		27+		27+		
January .	·987	1·042	·942	·100	1·184	4th	·804	31st	·380
February .	·936	·990	·888	·102	1·050	14th	·841	27th	·209
March . .	·863	·916	·816	·100	1·001	8th	·734	29th	·267
April . .	·752	·808	·695	·113	·916	8th	·575	26th	·341
May . .	·633	·679	·579	·100	·815	30th	493	12th	·322
June . .	·563	·600	·514	·086	·805	1st	·397	15th	·408
July . .	·558	·591	·508	·083	·732	3rd	·400	25th	·332
August .	·619	·662	·570	·092	·795	13th	·458	1st	·337
September .	·693	·740	·641	·099	·899	30th	·502	7th	·397
October .	·911	·955	·863	·092	1·056	27th	·721	6th	·335
November .	·922	·974	·878	·096	1·052	18th	·805	14th	·247
December .	1·027	1·084	·987	·097	1·174	21st	·898	4th	·276
Year . .	·789	·837	·740	·097	1·184	...	·397	...	·787

44. BERHAMPORE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·984	1·058	·932	·126	1·199	5th	·803	31st	·396
February .	·908	·989	·849	·140	1·052	2nd	·794	12th	·258
March . .	·785	·863	·727	·136	·980	12th	·586	29th	·394
April . .	·659	·738	·583	·155	·846	22nd	·505	12th	·341
May . .	553	·615	·482	·133	·735	30th	·366	13th	·369
June . .	·486	·534	·424	·110	·710	1st	·312	14th	·398
July . .	·472	·520	·412	·108	·659	15th	·276	26th	·383
August .	·551	·599	·488	·111	·721	13th	·343	1st	·378
September .	·633	·692	·569	·123	·858	30th	·419	7th	·439
October .	·834	·899	·778	·121	1·002	27th	·605	6th	·397
November .	·870	·937	·816	·121	1·026	19th	·701	14th	·325
December .	1·017	1·086	·967	·119	1·196	19th & 21st	·840	6th	·356
Year . .	·729	·794	·669	·125	1·199	...	·276	...	·923

45. BURDWAN.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·951	1·028	·898	·130	1·162	5th	·769	31st	·393
February	·879	·964	·818	·146	1·021	2nd & 14th	·750	25th	·271
March	·764	·844	·704	·140	·969	8th	·556	29th	·413
April	·628	·705	·554	·151	·825	9th	·416	27th	·409
May	·520	·583	·449	·134	·700	30th	·348	9th	·352
June	·446	·495	·383	·112	·687	1st	·245	29th	·442
July	·439	·483	·383	·100	·616	15th	·242	26th	·374
August	·518	·566	·456	·110	·703	13th	·309	1st	·394
September	·597	·651	·538	·113	·821	30th	·384	7th	·437
October	·801	·863	·749	·114	·968	28th	·585	6th	·383
November	·842	·910	·788	·122	1·009	18th	·659	14th	·350
December	·986	1·061	·931	·130	1·163	19th	·811	1st	·352
Year	·698	·763	·638	·125	1·163	...	·242	...	·921

46. JESSORE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·921	1·092	·971	·121	1·228	4th	·847	30th	·381
February	·945	1·024	·888	·136	1·081	14th	·827	25th	·254
March	·832	·907	·774	·133	1·021	8th	·658	29th	·363
April	·719	·790	·649	·141	·881	22nd	·578	12th	·303
May	·608	·666	·542	·124	·787	30th	·395	13th	·392
June	·529	·577	·466	·111	·759	1st	·345	28th	·414
July	·508	·560	·442	·118	·709	15th	·314	26th	·395
August	·593	·645	·527	·118	·783	13th	·409	1st	·374
September	·674	·732	·612	·120	·880	30th	·481	6th	·399
October	·865	·930	·809	·121	1·036	27th	·601	7th	·435
November	·901	·965	·851	·114	1·057	18th	·771	12th	·286
December	1·040	1·104	·993*	·111	1·210	19th	·865	5th	·345
Year	·770	·833	·710	·122	1·228	...	·314	...	·914

* Mean of 30 days.

47. DACCA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	+	29+		29+		29+		
January	1·020	1·083	·964	·119	1·213	5th	·826	27th	·387
February	·945	1·016	·883	·133	1·072	2nd	·833	27th	·299
March	·838	·909	·773	·136	1·022	12th	·673	29th	·349
April	·739	·805*	·678	·127	·910	22nd	·603	30th	·307
May	·631	·680	·580	·100	·777	31st	·499	11th	·278
June	·556	·593	·508	·085	·771	21st	·393	6th	·378
July	·532	·573	·473	·100	·723	15th	·325	26th	·398
August	·610	·652	·552	·100	·759	13th	·437	1st	·322
September	·698	·746	·639	·107	·884	30th	·502	6th	·382
October	·865	·918	·811	·107	1·028	27th	·633	6th	·395
November	·888	·946	·831	·115	1·041	18th	·690	14th	·351
December	1·038	1·093	·986	·107	1·196	19th	·827	6th	·369
Year	·780	·835	·723	·111	1·213	...	·325	...	·888

48. CHITTAGONG.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·961	1·017	·906	·111	1·170	4th	·791	31st	·379
February	·898	·961	·844	·117	1·015	11th	·789	23rd	·226
March	·828	·889	779	·110	·971	7th	·703	20th	268
April	·741	·802	·691	·111	·885	25th	·604	30th	·281
May	·642	·691	·592	·099	·795	31st	·475	25th	·320
June	·529	·565	·483	·082	·744	1st	·349	27th	·395
July	·529	·564	·479	·085	·744	16th	·323	26th	·421
August	·601	·643	·545	·098	·751	13th	·427	23rd	·324
September	·680	·729	622	·107	·844	30th	·467	6th	·377
October	·818	·873	·761	·112	·962	28th	·608	6th	·354
November	·828	·881	·776	·105	·975	18th	·615	14th	·360
December	·971	1·021	·922	·099	1·106	19th & 29th	·723	5th	·383
Year	·752	·803	·700	·103	1·170	...	·323	...	·847

* Mean of 29 days.

49. CALCUTTA (ALIPORE).

Month.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	29+	29+	29+	29+	29+	...	29+	...	29+	...	...
January .	1·026	1·046	1·110	·981	1·045	·129	1·254	4th & 5th, 10h.	·846	27th, 16h.	·408
February	·958	·964	1·040	·904	·975	·136	1·095	6th & 10th, 10h.	·844	25th, „	·251
March .	·849	·857	·924	·790	·864	·134	1·051	8th, „	·680	29th, „	·371
April .	·721	·740	·792	·660	·744	·132	·871	9th, „	·545	27th, „	·326
May .	·608	·618	·666	·548	·632	·118	·786	31st, „	·438	12th, „	·348
June .	·519	·532	·566	·469	·552	·097	·773	1st, „	·214	29th, „	·559
July .	·509	·523	·557	·462	·547	·095	·697	15th, „	·325	26th, „	·372
August .	·588	·597	·641	·544	·629	·097	·790	13th, „	·427	1st, „	·363
September	·668	·671	·723	·618	·707	·105	·880	30th, „	·447	7th, „	·433
October .	·873	·893	·930	·826	·893	·110	1·043	27th & 28th, 10h.	·661	6th, „	·382
November	·910	·930	·982	·861	·935	·121	1·083	18th, „	·736	14th, „	·347
December	1·051	1·062	1·128	1·007	1·076	·121	1·230	19th, „	·874	6th, „	·356
Year .	·773	·786	·839	·723	·800	·116	1·254	...	·214	...	1·040

50. SAUGOR ISLAND.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	29+	29+	29 †	29+	29+	...	29+	...	29+	...	...
January .	·784	·762	·836	·732	·805	·104	1·235	4th, 10h.	·817	27th, 16h.	·418
February	·952	·921	1·017	·904	·967	·113	1·071	10th, „	·815	25th, „	·256
March .	·861	·829	·926	·807	·881	·119	1·050	12th, „	·696	29th, „	·354
April .	·744	·718	·808	·684	·767	·124	·928	22nd, 22h.	·576	27th, „	·352
May .	·628	·605	·679	·572	·655	·107	·810	31st, 22h.	·455	12th & 13th, 16h.	·355
June .	·533	·522	·568	·482	·561	·086	784	1st, 10h.	·112	29th, „	·672
July .	·531	·516	·563	·490	·555	·073	·724	16th, „	·359	26th, „	·365
August .	·605	·582	·648	·554	·635	·094	·775	13th, „	·439	23rd „	·336
September	·677	·662	·719	·619	·708	·100	·870	30th, „	·436	7th, „	·434
October .	·879	·861	·931	·826	·897	·105	1·028	28th, „	·663	6th, „	·365
November	·919	·899	·975	·867	·934	·108	1·077	18th, „	·737	14th, „	·340
December	1·054	1·029	1·110	1·005	1·073	·105	1·212	21st, „	·840	5th, 4h.	·372
Year .	·784	·762	·836	·732	·805	·104	1·235	...	·112	...	1·123

51. CUTTACK.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	...	29+	...	29+	...	...
January .	·959	1·026	·894	·132	1·166	4th	·733	31st	·433
February	·889	·960	·816	·144	1·016	10th	·703	25th	·313
March .	·796	·861	·722	·139	·998	12th	·628	29th	·370
April .	·672	·739	·593	·146	·835	8th	·466	27th	·369
May .	·558	·608	·488	·120	·731	31st	·390	13th	·341
June .	·478	·521	·417	·104	·729	1st	·285	29th	·444
July .	·474	·511	·419	·092	·651	16th	·300	7th	·351
August .	·545	·588	·487	·101	·728	13th	·243	23rd	·385
September	·608	·657	·548	·109	·818	30th	345	7th	·463
October .	·820	·874	·766	·108	·968	27th	·619	6th	·349
November	·862	·920	·804	·116	1·024	18th	·696	14th	·328
December	1·004	1·063	·947*	·116	1·165	21st	·737	4th	·428
Year .	·722	·777	·658	·119	1·166	...	·285	...	·881

52. FALSE POINT.†

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	+	29+	...	29+	...	...
January .	·795	·845	·741	·104	1·243	4th	·843	31st	·400
February	1·036	1·093	·983	·110	1·243	4th	·843	31st	·400
March .	·966	1·023	·910	·113	1·086	10th	·821	25th	·265
April .	·874	·936	·814	·122	1·058	12th	·722	29th	·336
May .	·757	·822	694	·128	·931	3rd	·582	4th	·349
June .	·635	·687	·578	·109	·802	31st	·475	13th	·327
July .	·544	·585	·493	·092	·782	1st	·296	28th	·486
August .	·535	·571	·488	·083	·719	16th	·363	7th	·356
September	·616	·656	·563	·093	·795	13th	·421	23rd	·374
October .	·680	·726	·627	·099	·883	30th	·416	6th	·467
November	·889	·936	·843	·093	1·025	27th	·685	6th	·340
December	·932	·984	·880	·104	1·091	18th	·786	14th	·305
Year .	1·072	1·124	1·019	·105	1·225	21st	·831	5th	·394
	795	·845	·741	·104	1·243	...	·296	...	·947

* Mean of 30 days.

† The readings of the month of March have been corrected to the elevation of 20·6 feet.

53. SAMBALPUR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	28+		29+		28+		
January	·529	·586	1·472	·114	·705	4th	1·292	31st	·413
February	·459	·518	1·399	·119	·574	14th	1·293	25th	·281
March	·383	·455	1·310	·145	·606	7th	1·213	29th	·393
April	·244	·324	1·164	·160	·429	8th	1·021	30th	·408
May	·106	·180	1·031	·149	·348	31st	·936	21st	·412
June	·049	·113	·984	·129	·314	1st	·769	30th	·545
July	·066	·112	1·020	·092	·274	4th	·935	7th	·339
August	·131	·186	1·076	·110	·329	13th	·919	25th	·410
September	·196	·253	1·139	·114	·428	30th	·967	7th	·461
October	·394	·443	1·343	·100	·547	28th	1·217	6th	·330
November	·445	·492	1·398	·094	·597	22nd	1·314	14th	·283
December	·575	·622	1·527	·095	·715	28th	1·411	5th	·304
Year	·298	·357	1·239	·118	·715	...	·769	...	·946

54. RAIPUR.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
28+	28+	28+		28+		28+		
·823	·891	·752	·139	·960	5th	·821	31st	·139
·823	·891	·752	·139	·962	14th	·823	26th	·139
·734	·793	·673	·120	·873	15th	·753	29th	·120
·566	·625	·507	·118	·707	8th	·589	30th	·118
·507	·564	·450	·114	·657	31st	·543	12th	·114
·436	·494	·378	·116	·594	1st	·478	15th	·116
·433	·490	·376	·114	·590	4th	·476	8th	·114
·431	·488	·374	·114	·588	13th	·474	26th	·114
·507	·564	·450	·114	·657	30th	·543	2nd	·114
·726	·783	·669	·114	·883	28th	·769	7th	·114
·852	·909	·795	·114	1·009	18th	·895	10th	·114
·913	·970	·856	·114	1·070	19th	·956	5th	·114
·431	·488	·374	·114	1·070	...	·478	...	·592

55. NAGPUR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	·961	1·029	·892	·137	1·183	4th	·707	31st	·476
February	·901	·974	·827	·147	1·060	14th	·708	25th	·352
March	·824	·900	·748	·152	1·012	14th	·679	28th	·333
April	·710	·783	·636	·147	·899	9th	·512	30th	·387
May	·605	·675	·535	·140	·821	31st	·470	21st & 26th	·351
June	·557	·613	·500	·113	·788	1st	·394	6th	·394
July	·559	·608	·510	·098	·783	4th	·320	1st	·463
August	·601	·658	·543	·115	·801	13th	·390	26th	·411
September	·674	·728	·619	·109	·872	30th	·464	6th	·408
October	·867	·923	·810	·113	1·025	27th	·681	6th	·344
November	·906	·963	·848	·115	1·058	18th	·769	1st	·289
December	1·032	1·091	·973	·118	1·190	21st	·853	4th	·337
Year	·766	·829	·703	·125	1·190	...	·320	...	·870

56. SEONI.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
27+	27+	27+		27+		27+		
·958	1·017	·898	·119	1·160	4th	·721	31st	·439
·913	·973	·853	·120	1·053	14th	·762	25th	·291
·850	·914	·785	·129	1·010	14th	·721	28th	·289
·757	·817	·697	·120	·919	9th	·577	30th	·342
·652	·709	·595	·114	·831	31st	·532	26th	·299
·581	·629	·533	·096	·820	1st	·466	6th	·354
·580	·625	·534	·091	·880	18th	·315	1st	·565
·629	·678	·579	·099	·821	13th	·447	26th	·374
·690	·738	·641	·097	·891	30th	·500	6th & 8th	·391
·890	·943	·837	·106	1·034	28th	·728	6th	·306
·913	·966	·859	·107	1·050	20th	·804	9th & 10th	·246
1·019	1·071	·967	·104	1·160	21st	·847	4th	·313
·786	·840	·732	·109	1·160	...	·315	...	·845

57. JUBBULPORE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	·667	·731	·602	·129	·872	4th	·433	24th	·439
February	·623	·682	·564	·118	·775	14th	·489	26th	·286
March	·543	·608	·477	·131	·729	14th	·396	28th	·333
April	·430	·494	·365	·129	·612	9th	·230	30th	·382
May	·311	·374	·248	·126	·485	31st	·181	21st	·304
June	·229	·285	·173	·112	·450	1st	·087	13th	·363
July	·238	·282	·193	·089	·447	4th	·042	1st	·405
August	·287	·341*	·232*	·109	·475	7th	·106	26th	·369
September	·364	·420	·308	·112	·580	30th	·152	7th	·428
October	·586	·640	·531	·109	·742	28th	·392	6th	·350
November	·617	·677	·556	·121	·768	20th	·458	10th	·310
December	·743	·803	·683	·120	·909	21st	·585	3rd	·324
Year	·470	·528	·411	·117	·909	...	·042	...	·867

58. SAUGOR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	27+	27+		28+		27+		
January	Untrustworthy.								
February	1·185	1·240	1·129	·111	·321	14th	1·043	26th	·278
March	1·107	1·163	1·050	·113	·301	14th	·979	28th	·322
April	Untrustworthy.								
May	·882	·944	·820	·124	·066	30th	·743	4th	·323
June	·809	·861	·756	·105	·032	1st	·676	10th	·356
July	·808	·848	·768	·080	·021	4th	·668	1st	·353
August	·867	·914	·820	·094	·056	13th	·703	30th	·353
September	·935	·984	·885	·099	·136	30th	·731	7th	·405
October	1·144	1·192	1·096	·096	·295	28th	·978	3rd	·317
November	1·171	1·221	1·120	·101	·304	20th	1·033	10th	·271
December	1·285	1·340	1·230	·110	·425	21st	1·141	16th	·284
Year	?	?	?	?	?	...	?	...	?

* Mean of 30 days.

59. PACHMARHI.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	26+	26+	26+		26+		25+		
January	·523	·568	·478	·090	·718	4th	1·303	25th	·415
February	·500	·545	·455	·090	·613	14th	1·391	26th	·222
March	·461	·510	·411	·099	·592	14th	1·352	9th	·240
April	·399	·451	·347	·104	·547	8th	1·260	29th	·287
May	·311	·361	·261	·100	·448	31st	1·186	27th	·262
June	·227	·271	·183	·088	·440	1st	1·101	27th	·339
July	·194	·229	·159	·070	·405	4th	·957	1st	·448
August	·258	·299	·217	·082	·438	13th&14th	1·089	26th	·349
September	·312	·354	·270	·084	·512	30th	1·112	6th	·400
October	·501	·545	·456	·089	·621	27th	1·375	6th	·246
November	·504	·545	·462	·083	·620	18th	1·386	10th	·234
December	·592	·635	·548	·087	·714	21st	1·459	4th	·255
Year	·399	·443	·354	·089	·718	...	·957	...	·761

60. HOSHANGABAD.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	·981	1·045	·916	·129	1·191	4th	·706	25th	·485
February	·941	1·008	·874	·134	1·076	14th	·789	25th&26th	·287
March	·864	·933	·795	·138	1·060	13th	·711	28th	·349
April	·747	·814	·680	·134	·917	9th	·571	30th	·346
May	·645	·712	·577	·135	·800	31st	·503	20th&21st	·297
June	·570	·631	·508	·123	·789	1st	·424	14th	·365
July	·572	·621	·522	·099	·792	4th	·359	2nd	·433
August	·632	·686	·578	·108	·831	13th	·443	26th	·388
September	·697	·749	·644	·105	·907	30th	·485	6th	·422
October	·899	·954	·843	·111	1·063	28th	·719	6th	·344
November	·940	1·001	·879	·122	1·107	30th	·781	10th	·326
December	1·067	1·127	1·006	·121	1·207	20th	·909	2nd	·298
Year	·796	·857	·735	·122	1·207	...	·359	...	·848

61. KHANDWA *

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	·930	·992	·867	·125	1·130	4th	·708	24th	·422
February	·895	·960	·829	·131	1·055	14th	·741	28th	·314
March	·836	·905	·767	·138	1·010	13th to 15th	·693	28th	·317
April	·722	·786	·657	·129	·871	21st	·565	30th	·306
May	·629	·697	·560	·137	·765	16th	·486	21st	·279
June	·554	·609	·499	·110	·759	1st	·418	13th	·341
July	·565	·611	·518	·093	·769	4th	·397	9th	·372
August	·627	·677	·576	·101	·808	13th	·435	26th	·373
September	·698	·749	·646	·103	·893	30th	·472	6th	·421
October	·856	·913	·799	·114	·997	28th	·665	9th	·332
November	·888	·940	·836	·104	1·028	19th	·756	11th	·272
December	1·023	1·078	·967	·111	1·166	21st	·869	1st	·297
Year	·769	·826	·710	·116	1·166	...	·397	...	·769

* The readings of the first six months have been corrected to the present elevation of 1043·7 feet.

62. CHANDA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	29+	28+		29+		28+		
January	1·359	·428	1·290	·138	·586	4th	1·086	31st	·500
February	1·287	·361	1·213	·148	·428	14th	1·089	25th	·339
March	1·210	·283	1·136	·147	·370	13th	1·045	28th	·325
April	1·092	·169	1·014	·155	·261	8th	·882	30th	·379
May	·987	·055	·918	·137	·207	31st	·843	21st	·364
June	·955	·013	·896	·117	·164	1st	·815	5th	·349
July	·966	·016	·915	·101	·179	4th	·804	14th	·375
August	·996	·052	·940	·112	·188	13th	·777	26th	·411
September	1·081	·136	1·025	·111	·269	30th	·889	6th	·380
October	1·255	·312	1·197	·115	·410	27th	1·072	6th	·338
November	1·303	·356	1·249	·107	·442	18th	1·175	1st	·267
December	1·433	·494	1·372	·122	·580	21st	1·239	4th	·341
Year	1·160	·223	1·097	·126	·586	...	·777	...	·809

63. SIRONCHA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·649	·718	·579	·139	·860	5th	·396	31st	·464
February	·574	·649	·499	·150	·734	21st	·376	26th	·358
March	·512	·588	·435	·153	·694	14th	·355	29th	·339
April	·398	·476	·319	·157	·568	9th	·201	29th	·367
May	·283	·353	·212	·141	·495	31st	·156	26th	·339
June	·278	·338	·217	·121	·503	2nd	·138	8th	·365
July	·290	·338	·242	·096	·473	4th	·136	14th	·337
August	·320	·370	·270	·100	·504	14th	·100	26th	·404
September	·398	·451	·345	·106	·542	30th	·238	7th	·304
October	·521	·578	·464	·114	·662	28th	·335	6th	·327
November	·575	·633	·516	·117	·712	20th	·426	1st	·286
December	·692	·752	·632	·120	·839	21st	·489	4th	·350
Year	·458	·520	·394	·126	·860	...	·100	...	·760

64. CHIKALDA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	26+	26+	26+		26+		25+		
January	·392	·443	·340	·103	·604	4th	1·156	25th	·448
February	·365	·418	·312	·106	·489	14th	1·223	1st	·266
March	·331	·384	·278	·106	·451	14th	1·219	10th	·232
April	·269	·322	·216	·106	·417	9th	1·134	30th	·283
May	·189	·235	·142	·093	·314	31st	1·069	26th	·245
June	·099	·142	·056	·086	·330	1st	·990	14th	·340
July	·086	·125	·047	·078	·290	4th	·868	1st	·422
August	·138	·180	·095	·085	·319	13th	·946	26th	·373
September	·195	·238	·151	·087	·370	30th	1·008	6th	·362
October	·360	·406	·313	·093	·491	27th	1·226	7th	·265
November	·366	·413	·318	·095	·493	18th	1·245	10th	·248
December	·453	·498	·407	·091	·568	21st	1·312	4th	·256
Year	·270	·317	·223	·094	·604	...	·868	...	·736

The register is of doubtful accuracy.

65. BULDANA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	27+	27+		27+		27+		
January	·851	·906	·795	·111	1·062	4th	·600	25th	·462
February	·808	·871	·744	·127	·942	19th	·687	28th	·255
March	·765	·830	·699	·131	·895	14th	·628	26th	·267
April	·677	·740	·614	·126	·813	9th	·530	30th	·283
May	·603	·664	·542	·122	·726	16th	·479	26th	·247
June	·530	·582	·478	·104	·736	1st	·402	13th	·334
July	·548	·591	·504	·087	·722	4th	·407	14th	·315
August	·597	·644	·549	·095	·786	13th	·397	26th	·389
September	·657	·704	·609	·095	·827	30th	·444	6th	·383
October	·803	·853	·752	·101	·948	28th	·664	6th	·284
November	·824	·873	·775	·098	·946	18th	·694	10th	·252
December	·926	·976	·875	·101	1·050	21st	·778	4th	·272
Year	·716	·770	·661	·108	1·062	...	·397	...	·665

66. AKOLA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	·050	1·119	·981	·138	1·283	4th	·773	25th	·510
February	·996	1·069	·923	·146	1·147	14th	·850	25th	·297
March	·932	1·006	·858	·148	1·093	14th	·782	29th	·311
April	·820	·890	·750	·140	·968	9th	·648	30th	·320
May	·729	·799	·658	·141	·901	31st	·585	20th	·316
June	·674	·734	·614	·120	·889	1st	·519	13th	·370
July	·687	·741	·633	·108	·892	4th	·515	14th	·377
August	·736	·794	·678	·116	·924	13th & 14th	·531	26th	·393
September	·810	·869	·751	·118	1·000	30th	·601	6th	·399
October	·969	1·024	·913	·111	1·128	27th	·815	7th	·313
November	1·005	1·062	·947	·115	1·151	18th	·865	10th	·286
December	1·133	1·199	1·066	·133	1·300	21st	·964	4th	·336
Year	·878	·942	·814	·128	1·300	...	·515	...	·785

67. AMRAOTI.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	·756	·824	·688	·136	·979	4th	·484	25th	·495
February	·702	·773	·631	·142	·849	14th	·539	25th	·310
March	632	·704	·559	·145	·803	14th	·485	29th	·318
April	·527	·601	·453	·148	·694	9th	·352	30th	·342
May	·433	·503	·362	·141	·620	31st	·289	21st	·331
June	·378	·437	·318	·119	·628	1st	·236	10th	·392
July	·386	·439	·333	·106	·610	4th	·201	1st	·409
August	·426	·486	·365	·121	·626	14th	·208	26th	·418
September	·502	·558	·446	·112	·693	30th	·286	6th	·407
October	·675	·734	·615	·119	·827	28th	·504	7th	·323
November	·710	·772	·648	·124	·858	18th	·566	10th	·292
December	·834	·898	·769	·129	·986	21st	·651	4th	·335
Year	·580	·644	·516	·129	·986	...	·201	...	·785

68. NEEMUCH.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	27+	27+		28+		27+		
January	1·335	1·393	1·276	·117	·561	4th	1·004	25th	·557
February	1·328	1·386	1·270	·116	·489	14th	1·109	26th	·380
March	1·233	1·288	1·177	·111	·456	14th	1·111	2nd	·345
April	1·142	1·203	1·081	·122	·307	8th	·959	30th	·348
May	1·032	1·084	·979	·105	·197	30th	·888	21st	·309
June	·945	·995	·894	·101	·191	1st	·815	13th	·376
July	·944	·986	·902	·084	·137	4th	·757	2nd	·380
August	1·010	1·053	·966	·087	·187	13th	·824	26th	·363
September	1·089	1·136	1·042	·094	·286	30th	·847	5th	·439
October	1·283	1·335	1·230	·105	·432	28th	1·111	7th	·321
November	1·311	1·362	1·259	·103	·456	18th	1·143	10th	·313
December	1·435	1·489	1·381	·108	·570	21st	1·280	2nd	·290
Year	1·174	1·226	1·121	·104	·570	...	·757	...	·813

69. NOWGONG.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+		28+		
January	1·268	1·325	1·210	·115	1·498	4th	·983	25th	·515
February	1·238	1·296	1·179	·117	1·380	14th	1·086	28th	·294
March	1·124	1·185	1·063	·122	1·332	14th	·982	28th	·350
April	·983	1·043	·923	·120	1·170	8th	·781	30th	·389
May	·857	·912	·801	·111	1·077	30th	·703	20th & 21st	·374
June	·767	·822	·712	·110	1·002	1st	·631	10th	·371
July	·784	·829	·739	·090	·996	4th	·662	24th	·334
August	·846	·893	·798	·095	1·021	13th	·711	30th	·310
September	·917	·969	·864	·105	1·131	30th	·728	7th	·403
October	1·160	1·210	1·109	·101	1·345	28th	·955	6th	·390
November	1·207	1·262	1·151	·111	1·360	18th	1·037	10th	·323
December	1·343	1·400	1·285	·115	1·493	21st	1·176	16th	·317
Year	1·041	1·096	·986	·109	1·498	...	·631	...	·867

70. SUTNA.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
28+	28+	28+		28+		28+		
·975	1·032	·918	·114	1·168	5th	·722	25th	·446
·938	·996	·879	·117	1·075	2nd	·824	28th	·251
·836	·899	·773	·126	1·022	14th	·676	28th	·346
·689	·751	·627	·124	·861	9th	·496	30th	·365
·561	·622	·500	·122	·778	30th	·410	20th	·368
·480	·536	·423	·113	·722	1st	·325	10th	·397
·477	·527	·426	·101	·683	4th	·349	24th	·334
·557	·610	·504	·106	·735	13th	·405	26th	·330
·638	·690	·585	·105	·852	30th	·426	7th	·426
·869	·917	·820	·097	1·033	28th	·677	6th	·356
·910	·960	·860	·100	1·055	19th	·760	9th	·295
1·043	1·098	·988	·110	1·192	21st	·888	16th	·304
·748	·803	·692	·111	1·192	...	·325	...	·867

71. INDORE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	27+	27+		27+		27+		
January	1·140	1·199	1·080	·119	1·372	5th	·852	25th	·520
February	1·117	1·178	1·056	·122	1·266	14th	·973	25th	·293
March	1·060	1·123	·997	·126	1·245	14th	·929	28th	·316
April	·965	1·028	·901	·127	1·129	1st	·804	30th	·325
May	·872	·933	·810	·123	1·022	3rd	·727	26th	·295
June	·786	·838	·733	·105	·995	1st	·650	13th	·345
July	·783	·826	·740	·086	·987	4th	·585	2nd	·402
August	·851	·900	·802	·098	1·038	13th	·643	26th	·395
September	·913	·963	·863	·100	1·115	30th	·684	6th	·431
October	1·094	1·144	1·044	·100	1·233	28th	·928	7th	·305
November	1·117	1·167	1·066	·101	1·242	18th	·974	10th	·268
December	1·230	1·280	1·179	·101	1·352	21st	1·085	3rd	·267
Year	·994	1·048	·939	·109	1·372	...	·585	...	·787

72. BICKANEER.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
28+	28+	28+		28+		28+		
1·254	1·305	1·202	·103	1·488	4th	·887	25th	·601
1·240	1·293	1·187	·106	1·419	14th	·984	28th	·435
1·118	1·168	1·067	·101	1·332	14th	·952	30th	·380
·977	1·035	·919	·116	1·152	9th	·782	27th	·370
·835	·884	·786	·098	1·052	30th	·646	21st	·406
·734	·783	·685	·098	1·013	1st	·587	27th	·426
·741	·789	·692	·097	·956	4th	·628	26th	·328
·804	·857	·750	·107	·993	13th	·631	29th	·358
·921	·970	·871	·099	1·155	30th	·652	5th	·503
1·148	1·200	1·096	·104	1·331	28th	·951	7th	·380
1·208	1·256	1·160	·096	1·382	18th	·981	10th	·401
1·350	1·399	1·300	·099	1·507	31st	1·176	15th	·331
1·028	1·078	·976	·102	1·507	...	·587	...	·920

73 JEYPORE.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Range	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	28+	28+	28+	28+	28+	...	28+	...	27+	...	...
January	·559	·533	·620	·516	·566	·104	·802	4th, 10h.	1·195	25th, 4h.	·607
February	·546	·517	·609	·503	·554	·106	·712	14th, „	1·376	28th, 16h.	·356
March	·446	·419	·505	·403	·457	·102	·661	14th, „	1·298	27th, „	·363
April	·330	·314	·395	·277	·333	·118	·512	9th, „	1·145	30th, „	·367
May	·209	·198	·260	·161	·215	·099	·429	30th, „	1·026	20th, „	·403
June	·120	·111	·171	·073	·124	·098	·373	1st „	·989	5th, „	·384
July	·125	·115	·168	·079	·138	·089	·322	4th, „	1·009	2nd, „	·313
August	·185	·176	·236	·136	·191	·100	·373	14th, „	1·052	27th, „	·321
September	·279	·260	·330	·231	·295	·099	·498	30th, „	1·023	5th, „	·475
October	·493	·476	·545	·447	·505	·098	·662	28th, „	1·315	6th, „	·347
November	·524	·499	·581	·482	·532	·099	·699	18th, „	1·329	10th, „	·370
December	·652	·625	·711	·612	·660	·099	·795	21st, „	1·478	16th, 4h.	·317
Year	·372	·354	·428	·327	·381	·101	·802	...	·989	...	·813

74. SAMBHAR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+	...	28+	...	28+	...	...
January	·737	·798	·687	·111	·983	4th	·398	25th	·585
February	·727	·784	·674	·110	·896	14th	·533	28th	·363
March	·617	·676	·569	·107	·828	14th	·471	2nd	·357
April	·499	·563	·449	·114	·691	8th	·323	30th	·368
May	·375	428	·329	·099	·590	30th	·204	20th	·386
June	·295	·335	·245	·090	·542	1st	·177	5th	·365
July	·290	·337	·251	·086	·475	4th	·174	2nd	·301
August	·350	·404	·299	·105	·538	13th & 14th	·159	26th	·379
September	·442	·490	·402	·088	·625	29th	·195	6th	·430
October	·655	·709	·605	·104	·832	28th	·480	6th	·352
November	·703	·749	·655	·094	·863	18th	·471	11th	·392
December	·831	·887	·778	·109	·986	11th	·669	16th	·317
Year	·543	·597	·495	·101	·986	...	·159	...	·827

75. AJMERE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	28+	27+	..	28+	...	27+	...	...
January	1·382	·436	1·338	·098	·620	4th	1·046	25th	·574
February	1·374	·432	1·320	·112	·546	14th	1·182	28th	·364
March	1·279	·333	1·235	·098	·490	14th	1·121	3rd	·369
April	1·168	·230	1·120	·110	·348	8th	·995	27th	·353
May	1·058	·108	1·015	·093	·254	30th	·889	21st	·365
June	·980	·017	·934	·083	·211	1st	·852	28th	·361
July	·961	·001	·929	·072	·081	1st	·838	2nd	·243
August	1·028	·075	·984	·091	·216	14th	·865	29th	·351
September	1·117	·165	1·076	·089	·333	30th	·862	6th	·471
October	1·334	·382	1·289	·093	·499	28th	1·166	6th	·333
November	1·377	·421	1·330	·091	·526	18th	1·161	10th	·365
December	1·488	·535	1·445	·090	·605	19th & 20th	1·273	1st	·332
Year	1·212	·261	1·168	·093	·620	...	·838	...	·782

76. PACHBUDRA.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29		29+		29+		
January	·651	·715	·587	·128	·826	10th	·357	24th	·469
February	·639	·704	·574	·130	·841	14th	·354	28th	·487
March	·508	·569	·446	·123	·748	14th	·318	27th	·430
April	·400	·467	·332	·135	·568	8th	·234	28th	·334
May	·278	·341	·214	·127	·457	30th	·132	20th	·325
June	·204	·256	·151	·105	·399	1st	·116	8th	·283
July	·145	·186	·104	·082	·313	4th	·023	26th	·290
August	·207	·262	·152	·110	·418	13th	·017	28th	·401
September	·313	·370	·256	·114	·523	18th	·042	5th	·481
October	·502	·557	·447	·110	·644	27th	·323	7th	·321
November	·573	·624	·522	·102	·752	19th	·311	10th	·441
December	·712	·767	·657	·110	·879	10th & 21st	·561	3rd	·318
Year	·428	·485	·370	·115	·879	...	·017	...	·862

77. JACOBABAD.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·866	·931	·801	·130	1·111	4th	·450	25th	·661
February	·842	·909	·774	·135	1·046	14th	·563	28th	·483
March	·707	·773	·640	·133	·943	14th	·483	17th	·460
April	·537	·605	·469	·136	·760	9th	·304	27th	·456
May	·372	·431	·313	·118	·572	30th	·157	21st	·415
June	·230	·289	·170	·119	·526	1st	·067	27th	·459
July	·251	·302	·199	·103	·431	4th	·081	6th	·350
August	·310	·365	·254	·111	·490	14th	·091	1st	·399
September	·454	·513*	·394*	·119	·710	30th	·204	6th	·506
October	·706	·763	·649	·114	·926	28th	·488	7th	·438
November	·794	·852	·735	·117	·984	21st	·504	10th	·480
December	·955	1·016	·893	·123	1·150	31st	·784	2nd	·366
Year	·585	·646	·524	·122	1·150	...	·067	...	1·083

78. HYDERABAD.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·954	1·016	·892	·124	1·188	4th	·616	25th	·572
February	·929	·989	·868	·121	1·107	4th & 14th	·614	28th	·493
March	·801	·860	·741	·119	1·029	14th	·648	28th	·381
April	·661	·718	·604	·114	·814	9th	·479	30th	·335
May	·507	·561	·453	·108	·681	30th	·290	26th	·391
June	·388	·434	·342	·092	·622	1st	·208	28th	·414
July	·381	·423	·338	·085	·523	1st	·187	3rd	·336
August	·457	·498	·416	·082	·632	14th	·273	1st	·359
September	·587	·632	·541	·091	·811	30th	·345	5th	·466
October	·799	·857	·740	·117	·995	28th	·601	6th	·394
November	·887	·938	·836	·102	1·063	18th	·614	10th	·449
December	1·043	1·100	·986	·114	1·237	31st	·871	2nd	·366
Year	·700	·752	·646	·106	1·237	...	·187	...	1·050

* Mean of 28 days.

79. KURRACHEE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	1·009	1·077	·959	·118	1·231	4th	·698	24th	·533
February	·997	1·060	·946	·114	1·170	14th	·751	28th	·419
March	·895	·948	·853	·095	1·097	14th	·752	27th	·345
April	·786	·830	·740	·090	·899	1st	·595	30th	·304
May	·605	·649	·571	·078	·758	4th	416	27th	·342
June	·492	·526	·455	·071	·702	1st	·345	28th & 29th	·357
July	·485	·514	·454	·060	·603	30th	·256	3rd	·347
August	·591	·619	·554	·065	·749	14th	·454	1st	·295
September	·688	·721	·648	·073	·888	30th	·467	6th	·421
October	·872	·916	·820	·096	1·053	28th	·699	6th	·354
November	·937	·989	·888	·101	1·128	18th	·677	9th	·451
December	1·085	1·142	1·033	·109	1·300	31st	·937	2nd	·363
Year	·787	·833	·743	·089	1·300	...	·256	...	1·044

80. BHUJ.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		28+		
January	·599	·662	·535	·127	·816	4th	1·299	25th	·517
February	·591	·656	·525	·131	·751	14th	1·391	28th	·360
March	·507	·565	·449	·116	·694	14th	1·346	27th	·348
April	·387	·443	·331	·112	·516	1st & 9th	1·244	23rd	·272
May	·269	·312	·225	·087	·422	16th	1·107	27th	·315
June	·152	·197	·106	·091	·395	1st	·964	28th	·431
July	·148	·183	·112	·071	·267	30th	·816	3rd	·451
August	·249	·284	·213	·071	·412	14th	1·098	26th	·314
September	·335	·389	·290	·090	·547	30th	1·097	4th	·450
October	·495	·552	·437	·115	·663	28th	1·325	6th	·338
November	·554	·606	·502	·104	·730	18th	1·331	10th	·399
December	·696	·751	·641	·110	·885	31st	1·546	2nd	·339
Year	·415	·466	·364	·102	·885	...	·816	...	1·069

81. RAJKOT.

Month.	Mean.	10 hours.	16 hours.	Range	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		28+		
January .	·562	·627	·496	·131	·750	4th	1·283	25th	·467
February .	·549	·613	·485	·128	·704	14th	1·398	28th	·306
March .	·482	·548	·416	·132	·649	13th	1·326	28th	·323
April .	·376	·438	·313	·125	·505	1st	1·233	30th	·272
May .	·267	·322	·212	·110	·431	16th	1·109	28th	·322
June .	·156	·210	·102	·108	·398	1st	·984	28th	·414
July .	·165	·203	·126	·077	·287	30th	1·017	3rd	·270
August .	·246	·294	·198	·096	·423	13th	1·079	29th	·344
September .	·332	·383	·280	·103	·539	30th	1·099	5th	·440
October .	·472	·532	·412	·120	·631	28th	1·309	7th	·322
November .	·514	·569	·458	·111	·673	18th	1·303	10th	·370
December .	·644	·704	·584	·120	·810	31st	1·489	2nd	·321
Year .	·397	·454	·340	·113	·810	...	·984	...	·826

82. DEESA.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
29+	29+	29+		29+		28+		
·514	·591	·465	·126	·752	4th	1·203	25th	·549
·502	·579	·450	·129	·681	14th	1·295	28th	·386
·427	·496	·368	·128	·638	14th	1·279	28th	·359
·301	·373	·237	·136	·438	1st	1·136	23rd	·302
·197	·264	·130	·134	·376	16th	1·034	26th	·342
·098	·154	·032	·122	·319	1st	·939	14th	·380
·097	·141	·046	·095	·260	4th	·910	2nd	·350
·171	·237	·105	·132	·370	14th	·989	28th	·381
·269	·323	·205	·118	·485	30th	·983	5th	·502
·439	·507	·378	·129	·603	28th	1·229	7th	·374
·484	·548	·430	·118	·651	18th	1·285	10th	·366
·619	·687	·568	·119	·773	21st & 31st	1·470	1st	·303
·343	·408	·285	·124	·773	...	·910	...	·863

83. SURAT.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January .	·961	1·021	·900	·121	1·147	5th	·734	25th	·413
February .	·934	·997	·870	·127	1·072	20th	·812	24th	·260
March .	·891	·952	·829	·123	1·039	12th	·767	2nd	·272
April .	·787	·848	·726	·122	·909	21st	·663	30th	·246
May .	·708	·766	·649	·117	·865	16th	·542	28th	·323
June .	·597	·648	·546	·102	·827	1st	·431	29th	·396
July .	·608	·654*	·562*	·092	·735	30th	·459	2nd	·276
August .	·684	·734	·634	·100	·862	13th	·523	27th	·239
September .	·757	·806	·708	·098	·919	30th	·524	5th	·395
October .	·871	·926	·815	·111	1·017	28th	·720	7th	·297
November .	·906	·962	·850	·112	1·047	19th	·772	11th	·275
December .	1·038	1·099	·976	·123	1·172	21st	·883	2nd	·289
Year .	·814	·868	·755	·112	1·172	...	·431	...	·741

84. MALEGAON.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
28+	28+	28+		28+	...	28+	...	...
·558	·627	·488	·139	·726	13th	·303	25th	·423
·511	·579	·443	·136	·618	3rd & 21st	·371	28th	·247
·474	·548	·399	·149	·632	13th	·331	28th	·301
·392	·457	·327	·130	·532	9th	·255	30th	·277
·309	·373	·245	·128	·470	16th	·173	28th	·297
·228	·283	·173	·110	·455	1st	·118	14th	·337
·227	·278	·175	·103	·368	5th	·097	14th	·271
·290	·343	·236	·107	·474	13th	·105	26th	·369
·361	·410	·311	·099	·530	30th	·145	6th	·385
·476	·529	·423	·106	·618	28th	·346	6th	·272
·518	·579	·457	·122	·655	18th	·371	11th	·284
·635	·700	·569	·131	·785	21st	·452	4th	·333
·415	·476	·354	·122	·785	...	·097	...	·688

* Mean of 29 days.

85. BOMBAY.

Month.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	29+	29+	29+	29+	29+	...	29+	...	29+	...	...
January	·941	·938	1·010	·888	·961	·122	1·141	4th, 10 h.	·780	25th, 16 h.	·361
February	·910	·908	·979	·856	·940	·123	1·047	11th, „	·802	1st, „	·245
March	·893	·898	·958	·838	·912	·120	1·023	18th, „	·771	31st, „	·252
April	·802	·812	·865	·744	·818	·121	·921	21st, „	·669	17th, „	·252
May	·747	·749	·803	·701	·766	·102	·903	16th, „	·642	30th, „	·261
June	·650	·650	·688	·610	·679	·078	·853	1st, 22 h.	·524	10th, „	·329
July	682	·677	·719	·649	·708	·070	·829	4th, 10 h. & 22h.	·493	14th, „	·336
August	·729	·723	·774	·692	·751	·082	·893	13th, 10 h.	·561	26th, „	·332
September	·798	·791	·845	·757	·829	·088	·952	30th, „	·603	6th, „	·349
October	·857	·866	·911	·808	·886	·103	·990	28th, „	·740	14th, „	·250
November	·880	·887	·938	·829	·906	·109	1·036	18th, „	·721	1st, „	·315
December	1·001	1·004	1·065	·951	1·020	·114	1·128	21st, „	·858	1st, „	·270
Year	·824	·825	·880	·777	·848	·103	1·141	...	·493	...	·648

86. POONA.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
27+	27+	27+	...	28+	...	27+	...	...
1·114	1·181	1·045	·136	·336	4th	·920	25th	·416
1·082	1·154	1·006	·148	·225	21st	·927	1st	·298
1·060	1·120	·982	·138	·171	25th	·936	2nd	·235
·982	1·042	·906	·136	·086	9th, & 21st	·854	27th	·232
·928	·979	·863	·116	·071	16th	·826	29th	·245
·860	·897	·816	·081	·047	1st	·747	10th	·300
·882	·916	·846	·070	·025	4th	·707	14th	·318
·919	·962	·878	·084	·074	13th	·740	26th	·334
·988	1·028	·938	·090	·129	30th	·813	6th	·316
1·065	1·121	1·004	·117	·208	28th	·939	5th	·269
1·082	1·140	1·023	·117	·228	18th	·924	1st	·304
1·193	1·257	1·126	·131	·318	21st	1·034	2nd	·284
1·013	1·066	·953	·114	·336	...	·707	...	·629

87. SHOLAPUR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range
	28+	28+	28+	...	28+	...	27+	...	...
January	·387	·448	·326	·122	·607	4th	1·178	31st	·429
February	·347	·411	·282	·129	·489	20th	1·208	1st	·281
March	·301	·367	·235	·132	·445	14th	1·173	28th, &31st	·272
April	·216	·289	·142	·147	·351	9th	1·099	30th	·252
May	·148	·225*	·071*	·154	·277	1st	1·039	26th & 27th	·238
June	·107	·171	·043	·128	·315	1st	1·002	6th	·313
July	·112	·175	·048	·127	·267	4th	·977	14th	·290
August	·138	·196	·080	·116	·288	13th	·982	26th	·306
September	·187	·254	·120	·134	·324	17th	1·031	6th	·293
October	·283	·346	·220	·126	·440	27th	1·144	8th	·296
November	·302	·357	·247	·110	·428	4th	1·163	2nd	·265
December	·427	·483	·371	·112	·572	26th	1·271	1st	·301
Year	·246	·310	·182	·128	·607	...	·977	...	·630

88. RATNAGIRI.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range
29+	29+	29+		29+		29+		
·841	·902	·780	·122	1·039	5th	·696	31st	·343
·812	·871	·752	·119	·927	20th & 21st	·681	1st	·246
·801	·859	·743	·116	·915	7th	·689	23rd	·226
·720	·775	·664	·111	·828	9th	·579	23rd	·249
·668	·717	·619	098	·810	16th	·551	10th	·259
·605	·639	·570	·069	·758	2nd	·505	24th	·253
·650	·683	·617	·066	·771	4th	·510	14th	·261
·665	·704	·625	·079	·805	13th	·501	26th	·304
·738	·778	·697	·081	·882	30th	·584	6th	·298
·763	·814	·712	·102	·875	27th	·627	14th	·248
·775	·827	·722	·105	·907	18th	·607	1st	·300
·890	·945	·834	·111	1·014	21st	·749	2nd	·265
·744	·793	·695	·098	1·039	...	·501	...	·538

* Mean of 24 days.

89. BELGAUM.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	27+	27+	27+		27+		27+		
January	·416	·489	·356	·133	·629	4th	·264	31st	·365
February	·391	·464	·324	·140	·532	21st	·251	1st	·281
March	·366	·437	·299	·138	·500	7th	·248	20th	·252
April	·306	·367	·243	·124	·421	9th	·176	30th	·245
May	·256	·311	·207	·104	·395	16th	·136	5th	·259
June	·218	·249	·186	·063	·377	1st	·138	24th	·239
July	·240	·273	·211	·062	·376	4th	·119	14th	·257
August	·247	·292	·203	·089	·393	13th	·077	26th	·316
September	·326	·362	·279	·083	·427	30th	·169	6th	·258
October	·360	·414	·306	·108	·481	28th	·233	31st	·248
November	·367	·424	·320	·104	·497	18th	·214	2nd	·283
December	·468	·531	·412	·119	·593	22nd	·319	2nd	·274
Year	·330	·384	·279	·106	·629	...	·077	...	·552

90. KARWAR.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·918	·984	·851	·133	1·120	5th	·772	31st	·348
February	·891	·955	·827	·128	1·015	21st	·746	2nd	·269
March	·883	·944	·821	·123	1·011	7th	·775	23rd	·236
April	·808	·861	·755	·106	·928	1st	·685	26th	·243
May	·761	·806	·716	·090	·886	16th	·661	10th	·225
June	·739	·773	·704	·069	·877	2nd	·645	10th	·232
July	·777	·808	·746	·062	·893	4th & 17th	·694	2nd	·199
August	·767	·806	·728	·078	·881	7th & 13th	·592	26th	·289
September	·847	·888	·805	·083	·978	30th	·704	6th	·274
October	·845	·897	·793	·104	·952	20th	·701	31st	·251
November	·841	·891	·791	·100	·967	18th	·648	2nd	·319
December	·949	1·003	·895	·108	1·056	22nd	·816	1st	·240
Year	·836	·885	·786	·099	1·120	...	·592	...	·528

91. GOPALPORE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	1·001	1·056	·946	·110	1·195	4th	·790	31st	·405
February	·926	·984	867	·117	1·046	10th	·772	26th	·274
March	·841	·905	·776	·129	1·004	8th	·676	30th	·328
April	·733	·792	·674	·118	·885	8th	·561	27th & 30th	·324
May	·607	·660	·554	·106	·793	31st	·456	27th	·337
June	·536	·576	·495	·081	·776	1st	·406	7th	·370
July	·522	·557	·486	·071	·691	16th	·378	13th	·313
August	·579	·624	·534	·090	·782	13th	·352	25th	·430
September	·652	·700	·604	·096	·872	30th	·418	6th	·454
October	·857	·905	·809	·096	·990	27th	·669	6th	321
November	·904	·951	·856	·095	1·052	19th	·765	14th	·287
December	1·035	1·087	·983	·104	1·194	21st	·802	5th	·392
Year	·766	·816	·715	·101	1·195	...	·352	...	·843

92. VIZAGAPATAM.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	29+	29+	29+	29+	29+	...	29+	...	29+	...	...
January	1·003	·971	1·072	·945	1·024	·127	1·215	4th, 10h.	·799	27th, 16h.	·416
February	·939	·899	1·013	·878	·967	·135	1·098	10th, „	·787	1st, 4h.	·311
March	·874	·838	·947	·817	·895	·130	1·029	7th, „	·730	20th, 16h.	·299
April	·769	·734	·835	·710	·795	·125	·908	8th, „	·580	30th, 4h.	·328
May	·656	·633	·714	·595	·682	·119	·836	31st, 22h.	·461	23rd, 16h.	·375
June	·581	·560	·626	·528	·609	·098	·815	1st, 10h.	·420	6th, „	·395
July	·578	·559	·617	·527	·608	·090	·768	15th, 22h.	·411	14th, 4h.	·357
August	·624	·599	·671	·568	·657	·103	·827	13th, 10h.	·408	25th, „	·419
September	·695	·669	·750	·630	·732	·120	·897	30th, „	·496	6th, 16h.	·401
October	·865	·836	·920	·804	·898	·116	1·005	27th, 22h.	·674	9th, „	·331
November	·905	·874	·963	·847	·936	·116	1·053	18th, 10h.	·785	10th, „	·268
December	1·026	·986	1·089	·974	1·055	·115	1·193	21st, „	·727	4th, „	·466
Year	·793	·763	·851	·735	·822	·116	1·215	...	·408	...	·807

93. MASULIPATAM.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	29+	29+	29+	29+	...	29+	...	29+	...	...
January	·989	1·060	·935	1·015	·130	1·167	5th, 10h.	·809	31st, 16h.	·358
February	·971*	1·038*	·915*	1·001*	·125*	1·094	10th, ,,	·835	1st, ,,	·259
March	Untrustworthy.									
April	Ditto.									
May	Ditto.									
June	Ditto.									
July	Ditto.									
August	Ditto.									
September	Ditto.									
October	Ditto.									
November	Ditto.									
December	Ditto.									
Year	.....									

94. SECUNDERABAD.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	27+	27+	27+	27+	...	28+	...	27+	...	...
January	1·184	1·263	1·128	1·208	·142	·416	4th, 10h.	·945	31st, 16h.	·471
February	1·139	1·210	1·077	1·171	·136	·281	20th, ,,	·984	26th, ,,	·297
March	1·087	1·162	1·022	1·115	·145	·241	14th, ,,	·956	29th, ,,	·285
April	1·007	1·075	·940	1·030	·143	·154	9th, ,,	·826	30th, ,,	·328
May	·920	·989	·856	·935	·141	·077	31st, ,,	·802	26th, ,,	·275
June	·894	·941	·831	·920	·116	·097	2nd, ,,	·764	7th, ,,	·333
July	·906	·949	·845	·931	·111	·081	4th, ,,	·717	14th, ,,	·364
August	·923	·973	·863	·946	·115	·080	13th, ,,	·725	26th, ,,	·355
September	·992	1·041	·931	1·022	·116	·125	30th, ,,	·805	6th, ,,	·320
October	1·101	1·155	1·044	1·131	·120	·238	27th, ,,	·946	6th, ,,	·292
November	1·124	1·186	1·068	1·159	·129	·273	18th, ,,	·970	1st, ,,	·303
December	1·228	1·294	1·173	1·260	·129	·372	21st, ,,	1·043	4th, ,,	·329
Year	1·042	1·103	·982	1·069	·129	416	...	·717	...	·699

* Mean of 20 days.

95. KURNOOL.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+	...	28+		28+		
January	Not recorded.								
February	1·000	1·082*	·930*	·155	1·167	11th	·834	27th	·333
March	·920	·998	·843	·161	1·089	14th	·782	28th	·307
April	·850	·919	·765	·162	·998	9th	·627	30th	·371
May	·788	·856	·696	·169	·899	8th	·652	18th	·247
June	·770	·820	·699	·128	·943	1st	·635	17th	·308
July	·789	·836	·722	·120	·923	18th	·630	14th	·293
August	·810	·861	743	·123	·938	13th & 14th	·644	28th	·294
September	·878	·925	·818	·112	1·037	30th	·712	6th	·325
October	·953	1·006	·895	·119	1·078	28th	·816	8th	·262
November	1·065	1·066	·966	·108	1·182	20th	·851	3rd	·331
December	1·122	1·199	1·057	·157	1·303	30th	·945	3rd	·358
Year	...	...	...	...	...	...	...	...	...

96. BELLARY.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	28+	28+	28+	28+		28+		28+		
January	·488	·571	·432	·508	·145	·721	4th, 10h.	·299	31st, 16h.	·422
February	·447	·524	·389	·471	·138	·594	19th ,,	·278	1st ,,	·316
March	·388	·470	·327	·405	·148	·554	14th ,,	·278	29th ,,	276
April	·318	·390	·250	·340	·148	·463	9th ,,	·146	30th ,,	·317
May	·260	·334	·194	·273	·148	·382	16th ,,	·150	20th ,,	·232
June	·253	·294	·200	·272	·099	·422	1st ,,	·142	8th ,,	·280
July	·280	·317	·226	·306	·097	·414	4th ,,	·145	14th ,,	·269
August	·277	·328	·213	·299	·118	·466	13th ,,	·117	26th ,,	·349
September	·348	·405	·284	·378	·127	·481	30th ,,	·204	6th ,,	·277
October	·403	·466	·341	·434	·135	·535	28th ,,	·257	6th ,,	·278
November	·423	·486	·368	·455	·129	·567	18th ,,	·245	1st ,,	·322
December	·528	·597	·475	·555	·130	·678	22nd ,,	·365	5th ,,	·313
Year	·368	·432	·308	·391	·130	·721	...	·117	...	·604

* Mean of 20 days.

97. MANGALORE.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·898	·959	·836	·123	1·066	5th	·754	30th	·312
February	·880	·944	·816	·128	1·013	21st	·736	3rd	·277
March	·872	·935	·809	·126	·992	7th	·756	23rd	·236
April	·810	·869	·751	·118	·941	1st	·675	30th	·266
May	·763	·810	·716	·094	·893	16th	·655	1st	·238
June	·766	·805	·727	·078	·892	2nd	·672	10th	·220
July	·806	·842	·770	·072	·913	17th	·677	14th	236
August	·783	·825	·741	·084	·884	22nd	·664	26th	·220
September	864	·908	·820	·088	·979	30th	·735	6th	·244
October	·850	·904	·795	·109	·960	1st	·679	31st	·281
November	·831	·882	·780	·102	·942	18th	·658	2nd	·284
December	·935	·988	·882	·106	1·037	30th	·792	2nd	·245
Year	·838	·889	·787	·102	1·066	...	·655	...	·411

98. MERCARA.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
26+	26+	26+		26+		26+		
·277	·327	·226	·101	·428	4th	·143	31st	·285
·272	·322	·222	·100	·379	21st	·139	1st	·240
·270	·322	·217	·105	·370	18th	·184	10th	·186
·222	·271	·172	·099	·325	1st	·111	30th	·214
·183	·221	·144	·077	·300	16th	·100	1st	·200
·170	·205	·135	·070	·291	2nd	·062	8th	·229
·193	·224	·162	·062	·289	4th	·088	14th	·201
·171	·208	·133	·075	·262	12th	·057	26th	·205
·240	·278	·201	·077	·347	30th	·130	6th	·217
·238	284	·192	·092	·330	20th	·105	31st	·225
·223	·264	·181	·083	·326	18th	·067	1st	·259
·306	·347	·264	·083	·385	17th & 22nd	·186	2nd	·199
·230	·273	187	·085	·428	,,,	·057	...	·371

99. BANGALORE.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	26+	26+	26+	26+		26+		26+		
January	1·003	1·065	·939	1·047	·132	1·194	4th, 10h.	·826	31st, 16h.	·368
February	·986	1·049	·923	1·026	·129	1·113	20th ,,	·825	1st ,,	·288
March	·961	1·020	·888	1·009	·137	1·075	14th ,,	·851	29th ,,	·224
April	·896	·953	·824	·932	·136	1·007	1st ,,	·723	30th ,,	·284
May	·845	·895	·781	·874	·122	·975	16th ,,	·727	1st ,,	·248
June	·834	·870	·780	·861	·095	·975	2nd ,,	·723	17th ,,	·252
July	·852	·890	·802	·871	·093	·968	4th ,,	·721	14th ,,	·247
August	·837	·884	·774	·865	·115	·955	7th ,,	·699	26th ,,	·256
September	·911	·959	·851	·941	·114	1·035	30th ,,	·761	6th ,,	·274
October	·931	·984	·871	·966	·122	1·047	20th ,,	·780	31st ,,	·267
November	·934	·988	·882	·969	·116	1·063	18th ,,	·740	1st ,,	·323
December	1·025	1·079	·975	1·060	·111	1·148	22nd ,,	·881	2nd ,,	·267
Year	·918	·970	·858	·952	·119	1·194	...	·699	...	·495

100. MADRAS.

Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
29+	29+	29+	29+		29+		29+		
·990	1·051	·932	1·027	·124	1·197	4th, 10h.	·800	31st, 16h.	·397
·959	1·024	·897	·998	·130	1·101	20th, ,,	·802	1st ,,	·299
·901	·967	·839	·931	·133	1·027	7th, ,,	·773	20th, ,,	·254
·810	·867	·737	·849	·137	·950	9th, ,,	·614	30th, ,,	·336
·709	·758	·640	·747	·125	·873	9th, 22h.	·572	21st, ,,	·301
·696	·748	·625	·727	·130	·841	1st, 10h.	·544	7th, ,,	·297
·724	·769	·649	·764	·128	·849	16th, 22h.	·560	14th, ,,	·289
·718	·764	·641	·761	·128	·873	13th, ,,	·555	26th, ,,	·318
·791	·848	·717	·832	·137	·914	30th, 10h	·638	5th, ,,	·276
·876	·928	·813	·917	·124	1·012	20th, ,,	·712	30th, ,,	·300
·906	·956	·852	·946	·114	1·027	20th, ,,	·757	1st, ,,	270
1·014	1·065	·957	1·056	·115	1·156	22nd, ,,	·792	3rd, ,,	·364
·841	·895	·775	·880	·127	1·197	...	·544	...	·653

101. SALEM.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	28+	28+	28+	28+		28+		28+		
January .	1·039	1·115	·978	1·073	·143	1·252	4th, 10h.	·856	31st, 16h.	·396
February	1·026	1·103	·959	1·061	·147	1·177	20th, „	·854	2nd, „	·323
March .	·976	1·054	·903	1·010	·156	1·116	18th, „	·850	29th, „	·266
April .	·903	·977	·826	·932	·159	1·041	1st, „	·739	30th, „	·302
May .	·842	·906	·767	·873	·147	·967	16th, „	·713	18th, „	·254
June .	·841	·900	·768	·866	·140	·980	1st, „	·716	10th, „	·264
July .	·867	·924	·797	·891	·134	·981	18th, „	·699	14th, „	·282
August .	·847	·903	·782	·871	127	·957	13th, „	·711	26th, „	·246
September	·922	·986	·857	·947	·136	1·034	30th, „	·801	6th, „	·233
October .	·956	1·019	·892	·980	·136	1·090	20th, „	·788	31st, „	·302
November	·960	1·026	·903	·993	·134	1·087	19th, „	·789	1st, „	·298
December	1·058	1·124	1·007	1·085	·124	1·211	28th, „	·894	2nd, „	·317
Year .	·936	1·003	·870	·966	·140	1·252	...	·699	...	·553

102. WELLINGTON.

Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
24+	24+	24+	24+		24+		24+		
·258	·296	·216	·289	·083	·391	4th & 10th, 22h.	·142	31st, 16h.	·249
·267	·302	·224	·298	·080	·346	20th, 22h.	·151	1st, „	·195
·273	·312	·228	·301	·087	·347	18th, 10h.	·198	20th, „	·149
·238	·271†	·193†	·263†	·082	·325	1st, „	·147	3rd, „	·178
·195	·220	·152	·222	·073	·285	16th, „	·116	1st, „	·169
·171	·193	·135	·189	·062	·278	1st, 22h.	·093	7th, „	·185
·179	·201	·142	·198	·062	·273	4th, „	·071	14th, „	202
·166	·192	·123	·190	·073	·248	13th, 10h.	·049	26th, „	·199
·222	·249	·179	·249	·074	·304	30th, „	·108	6th, „	·196
·228	·264	·182	·258	·089	·315	20th, „	·097	31st, „	·218
·214	·244	·172	·248	·079	·309	9th, 22h.	·076	1st, „	·233
·275	·308†	·235†	·307†	·077	·361	26th, 10h.	·163	1st & 2nd, 16h.	·198
·224	·254	·182	·251	·077	·391	...	·049	...	·342

* Mean of 28 days. † Mean of 29 days.

103 COIMBATORE.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
	28+	28+	28+	28+		28+*		28+		
January .	·602	·680	·530	·650	·157	·810	4th, 10h.	·418	31st, 16h.	·392
February	·576	·661	·497	·623	·167	·723	8th, „	·408	1st, „	·315
March .	·550	·630	·465	·598	·171	·689	18th, „	·418	20th, „	·271
April .	·492	·554	·401	·547	·161	·623	1st, „	·323	30th, „	·300
May .	·442	·484	·362	·498	·130	·551	31st, 22h.	·297	1st, „	·254
June .	·453	·485	·392	·491	·098	·573	1st, „	·316	17th & 18th 16h.	·257
July .	·472	·502	·417	·505	·091	·580	4th, „	·347	31st, „	·233
August .	·452	·491	·384	·493	·112	·554	13th, 10h.	·333	26th, „	·221
September	·524	·575	·452	·568	·128	·645	30th, „	·404	27th, „	·241
October .	·539	·602	·458	·594	·155	·673	19th, „	·350	31st, „	·323
November	·536	·598	·464	·592	·146	·654	18th, „	·335	1st, „	·319
December	·636	·700	·566	·689	·143	·764	22nd, „	·453	2nd, „	·311
Year .	·523	·580	·449	·571	·138	·810	...	·297	...	·513

104. TRICHINOPOLY.

Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Absolute range.
29+	29+	29+	29+		29+		29+		
·727	·797	·660	·770	·143	·906	4th, 10h.	·540	31st, 16h.	·366
·711	·786	·638	·755	·151	·869	20th, „	·548	2nd, „	·321
·660	·739	·591	·702	·160	·793	8th, „	·484	20th, „	·309
·579	·649	·496	·618	·161	·714	9th, „	·385	30th, „	·329
·518	·573	·440	·562	·141	·636	16th, „	·359	18th, „	·277
·512	·558	·442	·546	·122	·644	1st, „	·360	18th, „	·284
·540	·586	·468	·575	·126	·664	16th, 22h.	·405	14th, „	·259
·522	·573	·443	·564	·135	·633	13th, 10h.	·366	26th, „	·267
·591	·652	·514	·631	·144	·720	30th, „	·458	6th, „	·262
·629	·692	·560	·668	·142	·762	21st, „	·447	31st, „	·315
·642	·700	·584	·682	·127	·757	19th, „	·462	1st, „	·295
·749	·807	·692	·788	·122	·888	22nd, „	·565	3rd, „	·323
·615	·676	·544	·655	·140	·906	...	·359	...	·547

105. NEGAPATAM.

Month.	Mean	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Abso-lute range.
	29+	29+	29+	29+		29+		29+		
January	·959	1·022	·911	·983	·117	1·171	4th, 10h.	·786	31st, 16h.	·385
February	·927	·992*	·879*	·946*	·115	1·054	10th & 11th, 10h.	·791	1st, „	·263
March	·911	·978	·856	·932	·126	1·043	18th, „	·796	29th, „	·247
April	·821	·890	·753	·843	·145	·993	1st, „	·640	30th, „	·353
May	·734	·786	·670	·763	·123	·879	11th, „	·606	25th, „	·273
June	·741	·791	·675	·765	·123	·878	2nd, „	·611	8th & 18th, 16h.	·267
July	·763	·813	·696	·789	·123	·902	16th, „	·648	10th, „	·254
August	·756	·807	·692	·780	·120	·882	31st, „	·621	28th, „	·261
September	·823	·885	·758	·848	·133	·968	30th, „	·701	5th, „	·267
October	·864	·924	·805	·893	·128	·992	20th, „	·716	31st, „	·276
November	·877	·939	·825	·907	·124	1·000	15th, „	·707	1st, „	·293
December	·977	1·036	·927	1·007	·115	1·131	19th, „	·798	4th, „	·333
Year	·846	·905	·787	·871	·124	1·171	...	·606	...	·565

* Mean of 18 days.

106. MADURA.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Abso-lute range.
	29+	29+	29+	29+		29+		29+		
January	·498	·588	·407	·562	·189	·716	4th, 10h.	·330	31st, 16h.	·386
February	·488	·570	·405	·543	·168	·645	20th, „	·253	4th, „	·392
March	·447	·526	·359	·499	·173	·574	12th, „	·276	25th, „	·298
April	·344	·410	·261	·388	·158	·519	1st, „	·214	10th, „	·305
May	·313	·391	·209	·368	·194	·461	16th, „	·132	4th, „	·329
June	·305	·357	·236	·333	·128	·450	1st, „	·137	19th, „	·313
July	·336	·392	·277	·347	·122	·462	16th, „	·217	14th, „	·245
August	·313	·371	·242	·339	·134	·436	21st, „	·153	26th, „	·283
September	·388	·449	·316	·424	·139	·493	18th, „	·247	6th, „	·246
October	·413	·482	·337	·457	·156	·605	21st, „	·272	7th, „	·333
November	·422	·486	·359	·465	·138	·547	19th, „	·282	29th, „	·265
December	·495	·565	·425	·543	·148	·661	29th, „	·277	1st, „	·384
Year	·397	·466	·319	·439	·154	·716	...	·132	...	·584

107. COCHIN.

Month.	Mean.	10 hours.	16 hours.	22 hours.	Range.	Highest reading.	Date and hour.	Lowest reading.	Date and hour.	Abso-lute range.
	29+	29+	29+	29+		29+		29+		
January	·917	·987	·857	·953	·136	1·098	4th, 10h.	·786	29th, 16h	·312
February	·912	·985	·840	·956	·148	1·063	20th, „	·746	3rd, „	·317
March	·906	·973	·833	·949	·146	1·038	13th, 22h.	·795	10th & 22nd, 16h.	·243
April	·851	·908	·782	·885	·132	·963	1st, 10h.	·719	30th, „	·244
May	·821	·861	·765	·850	·102	·936	16th, „	·682	1st, „	·254
June	·854	·887	·807	·875	·085	·965	2nd, „	·737	18th, „	·228
July	·887	·920	·837	·912	·089	1·012	16th, „	·768	31st, „	·244
August	·862	·896	·805	·893	·096	·969	22nd „	·748	26th, „	·221
September	·923	·968	·868	·951	·104	1·031	30th, „	·807	6th, „	·224
October	·898	·954	·837	·932	·126	1·003	1st, „	·731	31st, „	·272
November	·865	·923	·811	·899	·121	·986	7th, „	·746	1st & 2nd, 16h.	·240
December	·956	1·016	·903	·988	·120	1·063	30th, „	·825	2nd, „	·238
Year	·888	·940	·829	·920	·117	1·098	....	·682	...	·416

108. COLOMBO.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Abso-lute range.
	29+	29+	29+	...	29+	...	29+	...	...
January	·870	·931	·809	·122	1·053	4th	·739	29th	·314
February	·876	·937	·815	·122	1·023	20th	·695	3rd	·328
March	·876	·941	·811	·130	1·001	18th	·752	21st	·249
April	·823	·883	·762	·121	·937	1st & 9th	·666	30th	·271
May	·794	·838	·750	·088	·932	31st	·683	1st	·249
June	·822	·864	·779	·085	·921	25th	·698	19th	·223
July	·842	·888	·796	·092	·960	16th	·729	31st	·231
August	·816	·863	·769	·094	·922	21st	·708	6th & 7th	·214
September	·866	·934	·798	·136	·997	30th	·784	6th	·213
October	·864	·918	·809	·109	·964	1st	·730	30th	·234
November	·827	·882	·771	·111	·935	7th	·713	27th	·222
December	·919	·979	·859	·120	1·031	17th	·768	1st	·263
Year	·850	·905	·794	·111	1·053	....	·666	...	·387

109. JAFFNA.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	...	29+	...	29+	...	...
January	·967	1·020	·913	·107	1·155	4th	·798	31st	·357
February	·954	1·011	·896	·115	1·086	20th	·785	1st	·301
March	·913	·978	·847	·131	1·035	18th	·799	20th	·236
April	·831	·895	·766	·129	·966	1st	·665	30th	·301
May	·765	·815	·715	·100	·889	15th	·654	25th	·235
June	·771	·818	·723	·095	·894	2nd	·638	18th	·256
July	·798	·851	·744	·107	·922	16th	·679	31st	·243
August	·775	·832	·718	·114	·894	15th & 31st	·662	25th	·232
September	·852	·912	·791	·121	·966	30th	·730	6th	·236
October	·868	·922	·814	·108	·990	20th	·728	31st	·262
November	·870	·924	·816	·108	·979	19th	·726	1st	·253
December	·972	1·027	·916	·111	1·100	28th	·816	3rd	·284
Year	·861	·917	·805	·112	1·155	...	·638	...	·517

110. TRINCOMALEE.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	...	29+	...	29+	...	...
January	·752	·804	·699	·105	·929	4th	·603	31st	·326
February	·748	·802	·694	·108	·880	20th	·577	2nd	·303
March	·722	·784	·659	·125	·828	4th	·597	20th	·231
April	·644	·707	·581	·126	·779	1st	·494	30th	·285
May	·594	·658	·529	·129	·825	10th	·469	25th	·356
June	·589	·641	·537	·104	·705	3rd	·474	4th	·231
July	·613	·656	·569	·087	·725	17th	·496	31st	·229
August	·598	·647	·548	·099	·750	31st	·481	26th	·269
September	·657	·716	·598	·118	·752	29th	·552	5th	·200
October	·674	·733	·615	·118	·810	21st	·560	12th	·250
November	·679	·731	·626	·105	·777	19th	·554	29th	·223
December	·764	·821	·707	·114	·866	22nd	·580	4th	·286
Year	·670	·725	·614	·112	·929	...	·469	...	·460

111. BATTICALOA.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+	...	...
January	·908	·953	·863	·090	1·064	4th	·777	31st	·287
February	·911	·958	·863	·095	1·029	20th	·734	2nd	·295
March	·893	·945	·840	·105	·991	18th	·770	20th	·221
April	·820	·874	·765	·109	·934	1st	·678	30th	·256
May	·760	·806	·713	·093	·877	31st	·651	25th	·226
June	·768	·814	·722	·092	·879	1st	·643	19th	·236
July	·787	·831	·742	·089	·898	16th	·688	15th	·210
August	·767	·811	·722	·089	·874	12th	·678	26th	·196
September	·850	·894	·805	·089	·954	30th	·763	6th	·201
October	·871	·911	·831	·080	·974	17th	·786	6th	·188
November	·879	·920	·838	·082	·985	13th	·793	3rd	·192
December	Not recorded.								
Year	...	...	...	...	...	...	...	...	...

112. HAMBANTOTA.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	...	29+	...	29+	...	...
January	·879	·932	·825	·107	1·045	4th	·763	30th	·282
February	·872	·929	·815	·114	1·021	20th	·712	2nd	·309
March	·870	·930	·810	·120	·994	4th	·746	20th	·248
April	·816	·879	·753	·126	·942	1st	·660	30th	·282
May	·773	·825	·720	·105	·902	10th	·667	21st	·235
June	·778	·824	·732	·092	·888	2nd	·666	18th	·222
July	·795	·843	·746	·097	·900	16th	·666	31st	·234
August	·773	·822	·723	·099	·895	31st	·658	5th	·237
September	·830	·894	·766	·128	·931	18th	·696	22nd	·235
October	·819	·878	·760	·118	·928	4th & 9th	·700	30th	·228
November	·794	·846	·741	·105	·908	7th & 13th	·664	2nd & 29th	·244
December	·865	·917	·812	·105	·980	16th	·706	1st	·274
Year	·822	·877	·767	·110	1·045	...	·658	...	·387

113. GALLE.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	...	29+	...	29+	...	...
January	·865	·919	·810	·109	1·031	4th	·738	30th	·293
February	·868	·928	·808	·120	1·016	20th	·683	3rd	·333
March	·870	·930	·809	·121	·988	18th	·742	20th	·246
April	·818	·876	·759	·117	·938	2nd	·669	30th	·269
May	·791	·839	·743	·096	·912	31st	·685	2nd	·227
June	·817	·858	·775	·083	·918	2nd & 25th	·690	19th	·228
July	·838	·884	·791	·093	·964	16th	·725	31st	·239
August	·797	·854	·739	·115	·957	22nd	·639	26th	·318
September	·876	·929	·823	·106	·987	30th	772	6th	·215
October	·854	·907	·801	·106	·954	9th	·732	30th	·222
November	·817	·869	·764	·105	·930	7th	·688	27th	·242
December	·907	·964	·850	·114	1·092	14th	·747	1st	·345
Year	·843	·896	·789	·107	1·092	...	·639	...	·453

114. KANDY.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	28+	28+	28+		28+	...	28+	...	...
January	·216	·266	·166	·100	·363	4th	·095	28th	·268
February	·214	·269	·158	·111	·357	20th	·063	3rd	·294
March	·208	·268	·148	·120	·329	18th	·107	21st	·222
April	·160	·214	·106	·108	·270	1st	·035	30th	·235
May	·131	·177	·084	·093	·302	17th	·031	25th	·271
June	·158	·192	·123	·069	·245	2nd	·053	19th	·192
July	·161	·201	·121	·080	·308	9th	·060	31st	·248
August	·147	·190	·103	·087	·264	31st	·045	9th	·219
September	·179	·228	·130	·098	·291	4th	·081	28th	·210
October	·194	·249	·139	·110	·293	1st	·083	30th	·210
November	·164	·218	·110	·108	·268	14th	·051	2nd	·217
December	·246	·301	·190	·111	·348	17th	·112	1st	·236
Year	·182	·231	·132	·100	·363	...	·031	...	·332

115. NEWERA ELIYA.

Month.	Mean.	9h hours.	15h hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	23+	24+	23+	...	24+	...	23+	...	...
January	1·018	·079	·957	·122	·124	8th	?	?	?
February	1·038	·086	·989	·097	·126	21st	·945	1st	·181
March	1·045	·101	·989	·112	·123	5th	·967	28th & 29th	·156
April	1·031	·082	·979	·103	·107	6th & 8th	·969	19th	·138
May	1·022	·074	·969	·105	·113	16th	·943	6th	·170
June	1·012	·066	·958	·108	·091	1st	·931	18th	·160
July	1·009	·064	·953	·111	·101	22nd	·929	14th	·172
August	·996	·049	·943	·106	·091	5th	·897	27th	·194
September	1·032	·089	·974	·115	·117	5th	·923	1st	·194
October	1·019	·073	·965	·108	·095	5th	·913	9th	·182
November	1·057	·084	1·029	·055	·115	18th	1·015	29th	·100
December	1·050	·092	1·007	·085	·107	16th & 17th	·943	9th & 17th	·164
Year	1·027	·078	·976	·102	·126	...	·897	...	·229

116. AKYAB.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29 +	29 +	29 +		29 +		29 +		
January	1·013	1·075	·958	·117	1·236	4th	·795	30th	·441
February	·946	1·014	·891	·123	1·082	10th	·816	1st	·266
March	·900	·965	·847	·118	1·046	4th	·779	20th	·267
April	·820	·886	·762	·124	·953	27th	·657	5th	·296
May	·749	·792	·697	·095	·910	9th	·563	25th	·347
June	·663	·703	·617*	·086	·884	21st	·482	6th	·402
July	·646	·682	·603	·079	·849	16th	·473	26th	·376
August	·701	·746	·648	·098	·864	13th	·507	23rd	·357
September	·773	·823	·716	·107	·918	29th	·554	5th	·364
October	·880	·934	·820	·114	1·014	27th	·650	6th	·364
November	·892	·942†	·838‡	·104	1·034	19th	·697	13th	·337
December	1·031	1·083	·978	·105	1·173	21st	·839	5th	·334
Year	·835	·887	·781	·106	1·236	...	·473	...	·763

* Mean of 29 days. ‡ Mean of 25 days.
† „ „ 27 „

117. THAYETMYO.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·871	·943	·798	·145	1·105	4th	·591	30th	·514
February	·781	·861	·700	·161	·937	10th	·641	24th	·296
March	·719	·802	·636	·166	·976	4th	·577	29th	·399
April	·632	·715	·548	·167	·777	22nd	·452	6th	·325
May	·592	·662	·521	·141	·842	10th	·412	23rd	·430
June	·563	·613	·512	·101	·762	21st	·366	6th	·396
July	·548	·602	·493*	·109	·722	15th	·403	11th & 25th	·319
August	·583	·637	·529	·108	·743	12th	·433	23rd	·310
September	·657	·721	·592	·129	·804	26th	·479	6th	·325
October	·754	·815	·692	·123	·898	15th	·534	6th	·364
November	·762	·824	·699	·125	·897	18th	·546	14th	·351
December	·916	·979	·852	·127	1·092	30th	·696	2nd	·396
Year	·698	·765	·631	·134	1·105	...	·366	...	·739

* Mean of 30 days.

118. TOUNGOO.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
29+	29+	29+		29+		29+		
Untrustworthy.								
Ditto.								
Ditto.								
Ditto.								
·587	·655	·519	·136	·798	9th	·414	25th	·384
·561	·602	·519	·083	·745	20th	·389	7th	·356
·545	·586	·503	·083	·704	16th	·365	11th	·339
·565	·613	·517	·096	·714	7th	·397	23rd	·317
·627	·684	·569	·115	·763	3rd	·435	5th	·328
·689	·731	·646	·085	·817	15th	·485	6th	·332
·713	·751	·675	·076	·813	8th	·623	10th	·190
·843	·885	·800	·085	·984	29th	·712	1st & 2nd	·272
?	?	?	?	?	...	·365	...	?

119. BASSEIN.

Month.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·975	1·039	·911	·128	1·200	5th	·756	29th	·444
February	·906	·970*	·841*	·129	1·017	10th	·711	2nd	·306
March	·881	·937	·824	·113	1·032	5th	·750	20th & 21st	·282
April	·803	·863	·743	·120	·928	22nd	·643	5th	·285
May	·742	·793	·691	·102	·905	8th	·557	25th	·348
June	·715	·755	·675	·080	·876	21st	·547	6th	·333
July	·698	·733	·663	·070	·854	16th	·542	11th	·312
August	·725	·765	·685	·080	·881	13th	·575	23rd	·306
September	·789	·836	·741	·095	·907	26th	·627	5th	·280
October	·853	·908	·798	·110	·986	15th	·666	6th	·326
November	·856	·908	·804	·104	·981	18th	·647	12th	·334
December	·991	1·044	·937	·107	1·114	30th	·838	1st	·276
Year	·828	·879	·776	·103	1·200	...	·542	...	·658

120. DIAMOND ISLAND.

Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
29+	29+	29+		29+		29+		
·967	1·022	·912	·110	1·177	4th	·747	31st	·430
·918	·976	·860	·116	1·050	10th	·768	1st	·282
·885	·943	·826	·117	1·039	4th	·754	20th	·285
·816	·875†	·756	·119	·926	21st	·644	5th	·282
·754	·805	·703	·102	·910	8th	·574	25th	·336
·720	·759	·680	·079	·880	21st	·571	5th	·309
·707	·744	·670	·074	·872	16th	·534	11th	·338
·738	·779‡	·696‡	·083	·889	13th	·538	23rd	·351
·803	·852	·753	·099	·933	25th	·621	5th	·312
·857	·912	·801	·111	·993	15th	·648	6th	·345
·844	·898	·790	·108	·980	18th	·549	12th	·431
·978	1·029	·927	·102	1·106	21st	·830	1st & 2nd	·276
·832	·883	·781	·102	1·177	...	·534	...	·643

* Mean of 19 days. † Mean of 29 days. ‡ Mean of 30 days.

121. RANGOON.

Months.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	Untrustworthy.								
February	Ditto.								
March	Ditto.								
April	Ditto.								
May	Ditto.								
June	·725	·768	·682	·086	·875	21st	·542	6th	·333
July	·707	·746	·668	·078	·875	15th	·524	11th	·351
August	·734	·778	·690	·088	·892	13th	·569	23rd	·323
September	·792	·846	·737	·109	·912	25th & 26th	·640	5th	·272
October	·851	·908	·793	·115	·993	15th	·643	5th	·350
November	·859	·910	·807	·103	·982	18th	·740	12th	·242
December	·989	1·042*	·935*	·107	1·124	30th	·824	1st	·300
Year	?	?	?	?	?	?	·524	...	?

122. MOULMEIN.

Months.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·882	·946	·817	·129	1·122	4th & 5th	·630	30th	·492
February	·813	·878	·748	·130	·949	10th	·659	1st	·290
March	·783	·850	·715	·135	·933	3rd	·647	20th	·286
April	·714	·782	·646	·136	·834	22nd	·545	30th	·289
May	·663	·722	·603	·119	·855	8th	·503	25th	·352
June	·660	·705	·614	·091	·864	22nd	·499	6th	·365
July	·656	·700	·611	·089	·821	3rd	·475	11th	·346
August	·663	·712	·614	·098	·815	13th	·521	3rd	·294
September	·719	·776	·661	·115	·830	3rd	·548	5th	·282
October	·753	·817	·688	·129	·903	15th	·556	5th	·347
November	·756	·811	·701	·110	·867	19th	·652	12th	·215
December	·889	·947	·830	·117	1·003	30th	·722	2nd	·281
Year	·746	·804	·687	·117	1·122	...	·475	...	·647

123. MERGUI.

Months.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+		29+		29+		
January	·871	·924	·818	·106	1·104	4th	·653	30th	·451
February	·818	·872	·763	·109	·949	21st	·680	1st	·269
March	·811	·865	·756	·109	·929	25th	·696	31st	·233
April	·755	·816	·694	·122	·931	22nd	·584	3rd	·347
May	·724	·777	·671	·106	·872	9th	·598	1st	·274
June	·751	·788	·714	·074	·873	26th	·657	6th	·216
July	·743	·778	·708	·070	·879	4th	·629	11th	·250
August	·738	·778	·698	·080	·847	14th	·618	1st	·229
September	·787	·837	·736	·101	·893	13th	·667	5th	·226
October	·797	·846	·748	·098	·905	17th	·661	5th	·244
November	·784	·836	·732	·104	·895	9th	·675	10th	·220
December	·888	·928	·848	·080	1·041	16th	·770	1st & 2nd	·271
Year	·789	·837	·741	·097	1·104	...	·584	...	·520

124. PORT BLAIR.

Months.	Mean.	10 hours.	16 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	...	29+	...	29+	...	...
January	·902	·955	·848	·107	1·070	5th	·723	30th	·347
February	·883	·938	·828	·110	1·003	19th	·725	1st	·278
March	·863	·918	·808	·110	·980	4th & 7th	·754	20th	·226
April	·804	·859	·748	·111	·917	22nd	·665	30th	·252
May	·754	·800	·708	·092	·882	8th	·631	22nd	·251
June	·743	·782	·704	·078	·850	21st	·620	6th	·230
July	·745	·781	·708	·073	·872	16th	·596	11th	·276
August	·748	·786	·709	·077	·863	13th	·607	23rd	·256
September	·815	·860	·770	·090	·899	3rd, 18th & 29th	·666	5th	·233
October	·824	·872	·775	·097	·947	18th	·670	6th	·277
November	·803	·854	·752	·102	·916	19th	·607	11th	·309
December	·921	·968	·873	·095	1·019	13th	·767	1st	·252
Year	·817	·864	·769	·095	1·070	...	·596	...	·474

125. NANCOWRY.

Month.	Mean.	10 hours.	15 hours.	Range.	Highest reading.	Date.	Lowest reading.	Date.	Absolute range.
	29+	29+	29+	.	29+	...	29+	...	...
January	·839	·894	·783	·111	1·029	4th	·669	15th	·360
February	·818	·874	·762	·112	·951	14th	·583	5th	·268
March	·824	·877	·771	·106	·947	7th	·695	20th	·252
April	·770	·816	·723	·093	·865	22nd	·655	29th	·210
May	·759	·799	·718	·081	·886	9th	·653	1st	·233
June	·774	·805	·742	·063	·864	1st	·698	5th	·166
July	·782	·815	·749	·066	·874	3rd	·681	31st	·193
August	·758	·790	·726	·064	·905	14th	·655	23rd	·250
September	·804	·841	·766	·075	·880	17th & 24th	·699	5th	·181
October	·784	·827	·741	·086	·899	19th	·683	24th	·216
November	·768	·809	·726	·083	·860	7th & 18th	·665	23rd	·195
December	·857	·901	·813	·088	·958	17th	·737	1st	·221
Year	·795	·837	·752	·086	1·029	...	·653	...	·376

TABLE VIII.—MONTHLY MEANS OF PRESSURE IN 1883, REDUCED TO THEIR SEA-LEVEL VALUES.

Stations.	January.	February.	March.	April.	May.	June.	July	August.	September.	October.	November.	December.	Year.
	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+
Zanzibar	·872	·893	·887	·920	·997	1·085	1·116	1·090	1·091	1·027	·944	·952	·990
Aden	1·029	1·013	·965	·877	·819	·697	·667	·689	·786	·931	·983	1·104	·880
Seychelles	?	?		?	?	·961	·998	·993	1·003	·993	·931	·978	?
Bushire	1·092	1·087	1·007	·865	·729	·553	·480	·557	·705	·950	1·044	1·162	·853
Mooltan	1·076	1·056	·912	·758	·580	·415	·462	·509	·646	·910	1·008	1·173	·792
Dera Ismail Khan	1·099	1·058	·949	·778	·607	·439	·455	·503	·661	·929	1·018	1·174	·806
Peshawar	1·131	1·102	·978	·823	·596	·427	·450	·510	·665	·954	1·046	1·211	·824
Rawal Pindi	1·112	1·085	·966	·809	·612	·448	·475	·530	·693	·955	1·044	1·208	·828
Sialkot	1·060	1·031	·910	·750	·577	·439	·470	·543	·674	·906	·984	1·144	·791
Lahore	1·065	1·045	·903	·738	·561	·424	·450	·511	·669	·907	·988	1·157	·785
Ludhiana	1·079	1 047	·909	·746	·575	·467	·488	·536	·679	·913	·997	1·157	·799
Delhi	1·072	1·030	·900	·711	·563	·465	·491	?	?	?	?	?	?
Sirsa	1·072	1·061	·904	·734	·573	·462	·484	·534	·674	·928	1·001	1·165	·799
Dehra	1·087	1·025	·916	·741	·600	·536	·550	·605	·711	·963	1·031	1·169	·828
Roorkee	1·059	1·007	·877	·688	·561	·473	·496	·554	·664	·906	·986	1·134	·784
Meerut	1·064	1·019	·873	·699	·542	·451	·476	·529	·636	·896	·985	1·131	·775
Bareilly	1·073	·999	·873	·692	·566	·485	·504	·560	·667	·910	·982	1·132	·787
Agra	1·069	1·040	·895	·722	·582	·490	·521	·573	·678	·918	·988	1·150	·802
Lucknow	1·064	1·017	·884	·707	·574	·511	·516	·582	·677	·915	·985	1·133	·797
Gorakhpur	1·060	·990	·860	·704	·583	·532	·517	·582	·675	·905	·962	1·112	·790
Jhansi	1·051	1·030	·896	·731	·602	·512	·537	·601	·679	·910	·975	1·132	·805
Allahabad	1·060	1·011	·870	·707	·570	·502	·510	·580	·669	·915	·979	1·128	·792
Benares	1·066	1·013	·879	·704	·568	·510	·506	·578	·663	·910	·974	1·129	·792
Ghazipur	1·069	1·001	·863	·690	·550	·501	·500	·562	·648	·883	·940	1·113	·777
Sibsagar	1·100	1·010	·915	·822	·719	·622	·585	·653	·746	·935	·978	1·132	·851
Dhubri	1·071	·984	·859	·767	·681	·596	·565	·636	·729	·919	·950	1·106	·822
Silchar	1·058	·990	·893	·810	·713	·626	·584	·657	·748	·906	·917	1·064	·831
Purneah	1·051	·964	·839	·719	·620	·538	·533	·605	·698	·903	·944	1·098	·793
Durbhunga	1·083	·994	·861	·732	·621	·542	·531	·604	·693	·915	·963	1·117	·805
Patna	1·078	1·001	·862	·717	·589	·532	·528	·598	·684	·911	·968	1·126	·800
Hazaribagh	1·079	1·016	·894	·727	·587	·540	·550	·612	·693	·938	·990	1·132	·813
Berhampore	1·054	·978	·853	·725	·620	·553	·539	618	·700	·902	·939	1·088	·797
Burdwan	1·057	·984	·866	·728	·619	·545	·539	·618	·697	·903	·946	1·092	·800
Jessore	1·056	·980	·866	·753	·642	·563	·542	·627	·708	·899	·936	1·075	·804
Dacca	1·057	·982	·874	·775	·666	·591	·567	·646	·734	·901	·924	1·075	·816
Chittagong	1·055	·991	·919	·830	·732	·619	·620	·692	·770	·909	·920	1·065	·844
Calcutta (Alipore)	1·049	·980	·871	·743	·629	·541	·531	·610	·690	·895	·932	1·074	·795

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+
Saugor Island	1·046	·979	·888	·770	·653	·559	·557	·631	·703	·905	·946	1·081	·810
Cuttack	1·043	·972	·878	·753	·638	·558	·555	·626	·689	·903	·946	1·089	·804
False Point	1·058	·988	·896	·779	·657	·566	·557	·638	·702	·911	·954	1·095	·817
Sambalpur	1·015	·939	·855	·704	·559	·509	·533	·598	·664	·867	·930	1·069	·770
Raipur	1·032	·954	·870	·725	·582	·544	·560	·611	·687	·914	·972	1·121	·798
Nagpur	1·033	·961	·865	·730	·612	·584	·594	·633	·716	·920	·975	1·119	·812
Seoni	1·055	·992	·888	·753	·627	·584	·602	·649	·723	·948	1·004	1·145	·831
Jubbulpore	1.073	1·020	·907	·763	·622	·557	·583	·631	·718	·962	1·019	1·176	·836
Saugor	?	1·011	·897	?	·608	·551	·570	·631	·708	·941	·995	1·142	?
Hoshangabad	1·044	·997	·898	·757	·643	·578	·595	·656	·727	·949	1·009	1·157	·834
Khandwa	1·042	·999	·920	·783	·680	·618	·620	·683	·760	·930	·979	1·137	·846
Chanda	1·042	·959	·871	·737	·625	·607	·624	·654	·745	·925	·988	1·128	·825
Sironcha	1·069	·987	·920	·797	·677	·683	·698	·727	·808	·932	·995	1·119	·868
Buldana	1·032	·961	·893	·764	·684	·643	·679	·733	·806	·961	1·002	1·134	·858
Akola	1·019	·953	·872	·740	·640	·602	·623	·672	·755	·922	·974	1·121	·824
Amraoti	1·014	·946	·858	·730	·627	·594	·611	·647	·737	·920	·968	1·111	·814
Neemuch	1·048	1·040	·905	·773	·648	·562	·583	·648	·741	·955	1·011	1·166	·840
Nowgong	1·073	1·041	·903	·738	·602	·511	·544	·604	·679	·939	1·003	1·157	·816
Sutna	1·082	1·039	·908	·732	·589	·508	·522	·602	·690	·939	1·004	1·159	·815
Indore	1·029	1·001	·910	·776	·661	·589	·606	·677	·749	·954	1·006	1·151	·842
Bickaneer	1·047	1·027	·886	·716	·564	·455	·475	·536	·663	·901	·985	1·149	·784
Jeypore	1·067	1·046	·913	·749	·623	·525	·547	·602	·709	·946	1·011	1·168	·826
Sambhar	1·068	1·053	·907	·748	·610	·527	·541	·595	·701	·936	1·017	1·172	·823
Ajmere	1·079	1·066	·929	·767	·643	·562	·565	·625	·731	·976	1·038	1·201	·850
Pachbudra	1·061	1·044	·902	·781	·655	·578	·523	·585	·697	·891	·976	1·123	·818
Jacobabad	1·068	1·042	·902	·726	·556	·411	·435	·495	·641	·900	·992	1·157	·777
Hyderabad	1·099	1·073	·940	·797	·640	·521	·515	·591	·723	·936	1·028	1·188	·838
Kurrachee	1·061	1·049	·947	·837	·654	·541	·535	641	·738	·923	·989	1·137	·838
Bhuj	1·017	1·008	·916	·785	·665	·545	·544	·648	·737	·898	·968	1·117	·821
Rajkot	1·014	1·001	·925	·808	·697	·585	·599	·680	·772	·911	·963	1·101	·838
Deesa	1·004	·990	·905	·765	·659	·559	·566	·639	·741	·915	·971	1·113	·819
Surat	·999	·972	928	·824	·744	·634	·645	·721	·794	·908	·944	1·076	·849
Malegaon	1·043	·984	·929	·818	·726	·658	·668	·737	·814	·940	1·001	1·146	·872
Bombay	·979	·948	·931	·840	·785	·688	·720	·767	·836	·895	·918	1·040	·862
Poona	1·000	·946	·911	·807	·753	·712	·746	·783	·864	·935	·964	1·103	·877
Sholapur	1·024	·961	·898	·791	·717	·705	·709	·737	·793	·892	·922	1·075	·852
Ratnagiri	·956	·926	·915	·832	·779	·717	·762	·777	·852	·877	889	1·005	·857
Belgaum	·993	·934	·894	·821	·768	·766	·800	·801	·896	·918	·936	1·060	·882
Karwar	·963	·936	·928	·853	·806	·784	·822	·812	·892	·890	·886	·994	·881

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+	29+
Gopalpore	1·051	·976	·891	·783	·657	·586	·572	·629	·702	·907	·954	1·085	·816
Vizagapatam	1·035	·971	·906	·800	·687	·612	·609	·655	·727	·897	·937	1·059	·825
Masulipatam	1·000	·981	?	?	?	?	?	?	?	?	?	?	?
Secunderabad	1·020	·948	·879	·769	·662	·675	·699	·717	·796	·912	·956	1·080	·843
Kurnool	?	·950	·856	·776	·710	·708	·732	·753	·825	·904	·976	1·097	?
Bellary	·985	·925	·844	·757	·695	·706	·741	·739	·812	·879	·914	1·033	·836
Mangalore	·952	·934	·926	·864	·817	·820	·860	·837	·918	·904	·885	·989	·892
Mercara	·967	·933	·909	·848	·809	·832	·869	·833	·919	·906	·902	1·014	·895
Bangalore	1·012	·966	·903	·813	·762	·775	·817	·792	·875	·907	·929	1·048	·883
Madras	1·013	·982	·924	·833	·731	·718	·747	·741	·814	·899	·929	1·037	·864
Salem	1·006	·988	·925	·844	·783	·788	·819	·800	·874	·917	·926	1·032	·892
Coimbatore	·986	·951	·912	·846	·799	·818	·843	·821	·893	·914	·917	1·027	·894
Trichinopoly	1·012	·995	·941	·856	·795	·790	·818	·801	·870	·912	·926	1·036	·896
Negapatam	·975	·943	·927	·837	·749	·757	·779	·772	·839	·880	·893	·993	·862
Madura	·963	·948	·901	·796	·764	·756	·790	·765	·842	·871	·883	·958	·853
Cochin	·928	·923	·917	·862	·832	·865	·898	·873	·934	·909	·876	·967	·899
Colombo	·911	·917	·917	·864	·835	·863	·883	·857	·907	·905	·868	·960	·891
Jaffna	·976	·963	·922	·840	·774	·780	·807	·784	·861	·877	·879	·981	·870
Trincomalee	·932	·928	·901	·821	·771	·756	·790	·775	·834	·851	·858	·944	·848
Batticaloa	·936	·939	·920	·847	·787	·795	·813	·794	·877	·898	·906	?	?
Hambantota	·920	·913	·911	·857	814	·818	·835	·814	·871	·860	·835	·906	·863
Galle	·915	·918	·920	·868	·841	·867	·888	·847	·926	·904	·867	·957	·893
Kandy	·945	·941	·919	·869	·835	·873	·879	·863	·897	·916	·888	·977	·900
Akyab	1·035	·968	·921	·841	·770	·684	·667	·722	·794	·901	·914	1·053	·856
Thyetmio	1·013	·921	·855	·767	·728	·700	·685	·720	·794	·892	·900	1·058	·836
Toungoo	?	?	?	?	·760	·735	·718	·738	·801	·862	·888	1·021	?
Bassein	1·012	·942	·917	·839	·778	·751	·734	·761	·825	·889	·892	1·027	·864
Diamond Island	1·010	·959	·926	·857	·795	·761	·748	·779	·844	·898	·885	1·019	·873
Rangoon	?	?	?	?	?	·767	·749	·776	·834	·893	·901	1·031	?
Moulmein	·981	·911	·880	·810	·759	·757	·753	·759	·815	·849	·852	·987	·843
Mergui	·971	·917	·910	·854	·823	·850	·842	·837	·886	·897	·883	·988	·888
Port Blair	·965	·946	·926	·867	·817	·806	·808	·811	·878	·887	·866	·984	·880
Nancowry	·923	·902	·928	·853	·842	·857	·866	·841	·888	·868	·852	·941	·880

TABLE IX.—DIRECTION AND MEAN MOVEMENT OF WINDS IN 1883 (127 STATIONS).

1.—ZANZIBAR (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	19	1	20	4	...	4	4	...	4	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	2	...	2	2	3	2	5	19	...	19
North-East	2	12	14	6	1	7	8	6	14	...	...	...	...	...	...	...	...	...	...	1	1	...	1	1	..	2	2	1	4	5	3	3	6	5	7	12
East	1	12	13	...	9	9	...	11	11	...	3	3	...	...	...	...	1	1	...	4	4	...	1	1	...	4	4	2	7	9	...	13	13	...	20	20
South-East	...	...	...	...	2	2	...	3	3	2	6	8	1	8	9	...	15	15	1	15	16	...	20	20	3	11	14	1	13	14	...	5	5	...	1	1
South	1	1	2	1	2	3	...	2	2	2	7	9	3	13	16	1	12	13	...	8	8	...	7	7	1	3	4	...	2	2	1	...	1	...	...	...
South-West	2	1	3	7	6	13	6	3	9	14	3	17	18	8	26	19	2	21	17	2	19	17	...	17	14	...	14	11	...	11	8	3	11	1	3	4
West	1	...	1	2	...	2	3	1	4	3	1	4	9	1	10	10	...	10	13	...	13	14	...	14	12	1	13	13	1	14	8	1	9	...	...	...
North-West	...	...	...	2	1	3	9	1	10	...	1	1	...	...	...	...	...	...	..	1	1	...	2	2	...	3	3	2	2	4	7	2	9	6	...	6
Calm	1	...	1	...	...	..	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	4	4	1	...	1	...	...	...	...	...	...
Variable	...	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	60			8			21			65			75			68			54			53			34			19			7			58		
Resultant Direction	N. 38° E.			S. 39° E.			N. 28° E.			S. 17° W.			S. 28° W.			S. 19° W.			S. 20° W.			S. 20° W.			S. 28° W.			S. 11° W.			N. 36° W.			N. 38° E.		
Mean diurnal velocity of wind in miles	214·2			?			?			?			203·6			218·1			181·1			126·2			70·0			93·7			79·0			158·6		
Average Resultant Percentage (3-4 Years.)	59			21			7			74			72			75			65			60			46			40			9			30		
Average Resultant Direction (3-4 Years.)	N. 25° E.			N. 26° E.			N. 71° E.			S. 10° W.			S. 14° W.			S. 10° W.			S. 3° W.			S. 6° W.			S. 12° W.			S. 4° W.			S. 6° W.			N. 26° E.		
Average diurnal velocity of wind in miles (3-4 Years.)	201·0			157·8			141·0			165·1			182·1			197·2			173·1			129·0			112·5			107·1			102·5			141·9		

2.—ADEN (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	...	..	...	...	1	1	1	...	1	3	1	4	1	...	1	...	...	...	...	...	...	2	...	2	3	1	4	...	1	1	2	...	2
North-East	24	9	33	20	8	28	20	14	34	19	13	32	10	8	18	6	...	6	1	...	1	4	...	4	4	2	6	19	8	27	16	9	25	19	7	26
East	2	5	7	5	6	11	7	6	13	7	7	14	4	3	7	2	...	2	...	...	...	1	...	1	3	2	5	2	6	8	7	6	13	3	7	10
South-East	3	8	11	...	9	9	3	5	8	...	4	4	4	6	10	4	13	17	9	17	26	2	11	13	3	15	18	2	8	10	1	5	6	...	10	10
South	...	2	2	...	1	1	...	2	2	...	1	1	6	7	13	9	11	20	17	10	27	10	17	27	8	7	15	...	2	2	1	4	5	3	3	6
South-West	...	1	1	...	1	1	...	2	2	1	1	2	1	1	2	7	2	9	4	4	8	10	3	13	6	4	10	3	2	5	2	...	2	1	1	2
West	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	1	...	1	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...
Calm	1	6	7	2	4	6	1	1	2	2	4	6	2	4	6	1	4	5	...	...	..	4	...	4	4	...	4	1	3	4	2	5	7	4	2	6
Variable	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	64			68			71			70			38			59			84			69			54			50			56			50		
Resultant Direction	N. 70° E.			N. 72° E.			N. 69° E.			N. 64° E.			S. 79° E.			S. 20° E.			S. 15° E.			S. 5° E.			S. 28° E.			N. 69° E.			N. 76° E.			S. 88° E.		
Mean diurnal velocity of wind in miles	265·6			315·1			398·0			403·9			268·4			187·8			275·3			212·3			184·5			271·0			263·3			295·3		
Average Resultant Percentage (3-4 Years.)	72			68			?			50			44			66			?			67			55			47			64			69		
Average Resultant Direction (3-4 Years.)	N. 82° E.			N. 81° E.			?			N. 83° E.			S. 66° E.			S. 12° E.			?			S. 15° E.			S. 32° E.			N. 83° E.			N. 84° E.			N. 84° E.		
Average diurnal velocity of wind in miles (3-4 Years.)	309·1			314·8			?			374·7			275·9			186·1			249·3			296·9			208·5			282·0			265·6			302·9		

3.—Bushire (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	8	1	9	9	...	9	10	...	10	5	2	7	1	1	2	...	...	...	1	...	1	1	...	1	6	.	6	9	...	9	6	2	8	7	...	7
North-East	13	...	13	6	...	6	5	1	6	5	...	5	3	...	3	...	...	...	...	...	...	1	...	1	4	..	4	6	...	6	11	1	12	13	3	16
East	1	1	2	1	1	2	3	...	3	2	1	3	...	...	...	...	...	...	...	...	...	1	...	1	2	...	3	2	...	2	4	...	4	5		5
South-East	5	4	9	2	1	3	1	...	1	2	1	3	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	3	3	6	1	5	6
South	...	2	2	5	7	12	3	3	6	2	2	4	1	1	2	2	...	2	7	4	11	1	...	1	1	...	1	1	1	2	3	2	5	2	1	3
South-West	...	...	..	2	1	3	1	3	4	1	5	6	2	2	4	1	3	4	3	4	7	6	4	10	...	1	1	2	4	6	1	5	6	...	1	1
West	...	1	1	1	2	3	2	7	9	...	7	7	6	5	11	3	6	9	6	15	21	6	12	18	3	7	10	2	3	5	...	3	3	...	2	2
North-West	3	21	24	2	16	18	6	17	23	13	12	25	18	22	40	24	21	45	14	8	22	14	15	29	13	22	35	8	22	30	2	14	16	3	19	22
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	..	...	...	...	...	...	.	...	...	...	...	...	...	...		...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	45			24			47			45			78			86			67			73			72			62			24			42		
Resultant Direction	N. 1° W.			N. 44° W.			N. 44° W.			N. 49° W.			N. 55° W.			N. 58° W.			N. 89° W.			N. 73° W.			N. 43° W.			N. 41° W.			N. 7° W.			N. 5° E.		
Mean diurnal velocity of wind in miles	156·0			190·7			163·5			168·6			191·6			202·0			206·1			?			162·6			158·6			120·3			126·8		
Average Resultant Percentage (6-8 Years.)	38			36			35			38			66			66			57			59			50			47			38			39		
Average Resultant Direction (6-8 Years.)	N. 10° W.			N. 16° W.			N. 46° W.			N. 63° W.			N. 54° W.			N. 59° W.			N. 75° W.			N. 74° W.			N. 50° W.			N. 34° W.			N. 8° W.			N. 5° E.		
Average diurnal velocity of wind in miles (6-8 Years.)	190·7			205·6			203·4			211·9			211·8			256·9			216·7			192·0			193·9			169·3			158·4			160·1		

4.—Quetta (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	5	7	6	2	8	3	3	6	2	1	3	3	3	6	1	4	5	3	...	3	2	5	7	6	5	11	3	5	8	8	7	15	4	9	13
North-East	1	1	2	2	1	3	3	1	4	3	3	6	2	2	4	1	1	2	1	...	1	2	1	3	1	...	1	5	..	5	5	1	6	5	2	7
East	...	...	...	1	...	1	1	3	4	1	1	2	...	...	...	1	1	2	1	...	1	1	...	1	...	...	...	1	...	1	2	...	2	5	...	5
South-East	6	...	6	2	...	2	4	1	5	1	2	3	...	...	...	3	1	4	3	2	5	...	2	2	...	...	...	1	...	1	1	...	1	3	...	3
South	8	4	12	1	2	3	3	4	7	4	5	9	1	...	1	1	1	2	2	6	8	2	1	3	...	1	1	...	..	..	...	...	...	2	1	3
South-West	4	5	9	2	3	5	7	9	16	3	3	6	4	2	6	2	2	4	5	8	13	4	5	9	2	2	4	3	3	6	...	1	1	2	2	4
West	2	3	5	2	7	9	3	5	8	2	7	9	6	11	17	2	7	9	3	8	11	3	7	10	2	4	6	3	10	13	2	7	9	1	4	5
North-West	6	12	18	7	10	17	5	5	10	8	8	16	10	12	22	7	11	18	9	6	15	7	10	17	6	10	16	5	13	18	5	13	18	3	12	15
Calm	2	1	3	5	3	8	2	...	2	6	...	6	5	...	5	12	2	14	4	1	5	10	...	10	6	...	6	10	...	10	7	1	8	6	1	7
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...
Resultant Percentage	30			44			28			28			64			36			42			42			61			51			57			35		
Resultant Direction	S. 85° W.			N. 55° W.			S. 70° W.			N. 79° W.			N. 61° W.			N. 58° W.			S. 76° W.			N. 67° W.			N. 45° W.			N. 52° W.			N. 27° W.			N. 17° W.		
Mean diurnal velocity of wind in miles	97·0			89·0			116·6			93·6			116·9			114·2			138·1			115·3			75·8			67·5			73·1			76·7		
Average Resultant Percentage (5-6 Years.)	24			26			34			35			44			41			31			34			49			50			45			34		
Average Resultant Direction (5-6 Years.)	N. 78° W.			N. 85° W.			S. 53° W.			N. 75° W.			N. 72° W.			N. 63° W.			S. 84° W.			N. 76° W.			N. 52° W.			N. 53° W.			N. 30° W.			N. 43° W		
Average diurnal velocity of wind in miles (4-5 Years.)	83·3			106·9			112·9			125·6			116·0			125·2			125·2			120·3			82·8			75·9			69·1			64·8		

5.—LEH (*up to August 2, afterwards 4 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.				OCTOBER.				NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	2	4	4	4	8	1	7	8	3	5	8	...	2	2	2	4	6	1	4	5	2	...	2	6	3	4	5	18	5	4	8	1	18	...	...	1	1	2	1	...	...	...	1
North-East	9	2	11	19	11	30	7	9	16	5	7	12	3	3	6	7	9	16	9	3	12	2	1	3	5	4	1	1	11	7	2	2	4	15	12	8	1	6	27	...	1	1	1	3
East	3	...	3	2	...	2	3	...	3	1	2	3	...	1	1	...	...	...	...	...	...	...	...	...	1	...	1	3	2	2	...	2	6	5	3	...	2	10	...	...	...	...	...
South-East	1	...	1	2	...	2	5	1	6	1	...	1	1	...	1	...	...	...	...	...	...	...	1	1	1	3	...	...	4	2	2	...	1	5	1	4	1	1	7	...	1	...	1
South	1	5	6	...	...	...	7	5	12	4	...	4	3	2	5	2	1	3	2	1	3	1	3	4	2	2	6	4	14	...	3	6	3	12	1	4	6	2	13	20	18	21	21	80
South-West	9	15	24	1	7	8	5	.	5	11	9	20	...	5	15	12	2	14	3	9	12	2	11	13	2	5	8	4	19	2	3	8	2	15	4	6	11	4	25	10	11	9	9	39
West	2	4	6	...	5	5	2	4	6	5	4	9	9	12	21	5	10	15	10	13	23	6	11	17	2	2	9	12	25	9	9	7	12	37	7	5	6	11	29	...	...	...	...	...
North-West	4	3	7	...	1	1	1	5	6	...	3	3	5	6	11	2	4	6	5	1	6	7	4	11	4	5	...	1	10	3	3	...	3	9	...	...	3	2	5	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	11	...	11	7	6	1	2	16	1	3	...	3	7	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	29			47			10			22			54			33			45			50			27				28				17			87		
Resultant Direction	S. 67° W.			N. 30° E.			N. 52° E.			S. 89° W.			S. 86° W.			N. 64° W.			N. 77° W.			S. 86° W.			N. 85° W.				N. 75° W.				S. 56° W.			S. 13° W.		
Mean diurnal velocity of wind in miles	17·3			30·1			44·7			55·7			49·8			36·2			24·4			12·1			10·5				16·3				50·3			63·2		
Average Resultant Percentage (10 Years.)	32			26			31			41			40			38			38			32			36				40				42			55		
Average Resultant Direction (10 Years.)	S. 21° W.			S. 15° W.			S. 47° W.			S. 48° W.			S. 69° W.			S. 78° W.			S. 67° W.			S. 68° W.			S. 51° W.				S. 52° W.				S. 31° W.			S. 15° W.		
Average diurnal velocity of wind in miles (8-9 Years.)	17·1			26·3			42·4			65·3			61·8			44·3			30·6			23·6			23·3				34·2				40·9			26·4		

6.—MOOLTAN (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	1	3	...	...	...	2	1	3	...	1	1	...	...	...	...	...	...	...	1	1	...	...	...	...	1	1	...	..	...	...	...	...	...	...	...
North-East	10	5	15	8	7	15	8	4	12	14	10	24	11	10	21	1	2	3	7	3	10	1	...	1	3	6	9	3	2	5	3	4	7	1	4	5
East	..	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	.	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	2	...	2	1	2	3	1	2	3	2	1	3	2	2	4	5	4	9	3	...	3	..	...	...	3	...	3	1	...	1	4	4	8
South	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2	...	1	1	1	1	2	2	1	3	...	1	1	...	1	1	1	...	1	...	...	...
South-West	6	4	10	6	4	10	8	7	15	2	3	5	7	9	16	21	18	39	17	13	30	23	19	42	18	17	35	13	16	29	7	9	16	12	13	25
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	3	...	3	3	2	5	7	3	10	4	3	7	1	2	3	1	3	4	...	3	3	1	2	3	3	1	4	4	5	9	6	5	11	1	4	5
Calm	10	21	31	9	15	24	5	14	19	9	11	20	9	8	17	2	2	4	2	5	7	2	9	11	4	4	8	8	6	14	12	11	23	13	6	19
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	14			10			15			34			8			67			33			68			46			41			23			33		
Resultant Direction	N. 9° E.			N. 14° E.			N. 51° W.			N. 32° E.			N. 61° E.			S. 39° W.			S. 26° W.			S. 43° W.			S. 50° W.			S. 57° W.			S. 89° W.			S. 36° W.		
Mean diurnal velocity of wind in miles	32·7			43·1			77·3			62·8			65·2			81·1			74·5			52·7			62·5			39·8			32·7			43·8		
Average Resultant Percentage (10-15 Years.)	31			22			25			15			20			31			39			14			34			21			6			11		
Average Resultant Direction (10-15 Years.)	N. 5° W.			N. 4° E.			N. 4° W.			N. 46° W.			N. 68° W.			S. 39° W.			S. 28° W.			S. 3° W.			S. 30° W.			S. 70° W.			N. 82° W.			N. 14° E.		
Average diurnal velocity of wind in miles (6-8 Years.)	40·6			62·3			53·9			61·3			76·6			100·5			81·0			71·1			65·7			50·5			39·4			33·7		

7.—Dera Ismail Khan (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	...	1	1	...	...	...	2	...	2	1	1	2	2	...	2	1	1	2	...	1	1	2	1	3	1	3	4	2	2	4
North-East	6	11	17	6	6	12	7	13	20	13	6	19	6	3	9	8	5	13	14	12	26	13	13	26	14	12	26	6	8	14	7	10	17	2	10	12
East	1	2	3	2	4	6	2	5	7	4	4	8	11	11	22	9	5	18	3	3	6	5	1	6	4	1	5	3	2	5	...	1	1	1	1	2
South-East	1	3	4	2	9	11	1	6	7	3	7	10	4	8	12	4	5	9	4	10	14	6	9	15	4	5	9	4	3	7	...	3	3	1	2	3
South	..	...	...	..	...	...	...	...	...	...	2	2	2	5	7	4	4	8	...	..	.	...	1	1	1	...	1	...	...	...	...	1	1	...	1	1
South-West	...	1	1	1	...	1	3	1	4	1	2	3	...	...	...	...	4	4	1	..	1	1	...	1	...	5	5	...	...	...	4	3	7	1	..	1
West	...	...	...	...	1	1	1	...	1	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...
North-West	14	5	19	13	2	15	10	2	12	3	...	3	5	1	6	1	...	1	2	...	2	...	1	1	1	...	1	6	2	8	5	3	8	12	3	15
Calm	9	9	18	4	6	10	7	3	10	6	9	15	1	2	3	3	2	5	5	6	11	5	5	10	6	6	12	10	15	25	12	6	18	12	12	24
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	36			26			34			41			51			51			55			56			45			32			23			31		
Resultant Direction	N. 10° E.			N. 43° E.			N. 41° E.			N. 80° E.			S. 85° E.			S. 80° E.			N. 71° E.			N. 75° E.			N. 70° E.			N. 46° E.			N. 15° E.			N. 4° E.		
Mean diurnal velocity of wind in miles	35·7			44·8			48·0			52·6			47·0			43·4			58·5			55·3			59·9			37·6			28·2			22·9		
Average Resultant Percentage (15 Years.)	30			27			30			25			41			46			48			52			51			39			21			16		
Average Resultant Direction (15 Years.)	N. 7° W.			N. 4° W			N. 40° E.			N. 46° E.			N. 79° E.			N. 87° E.			S. 79° E.			S. 75° E.			S. 88° E.			N. 75° E.			N. 51° E.			N. 3° E.		
Average diurnal velocity of wind in miles (11-12 Years.)	34·1			48·2			48·1			58·3			50·7			58·3			54·3			45·9			36·8			24·9			17·0			16·5		

8.—Peshawar (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	3	3	...	2	2	2	3	5	2	4	6	3	3	6	3	1	4	3	3	6	4	6	10	8	6	14	4	1	5	2	...	2	...	1	1
North-East	2	4	6	2	8	10	6	3	9	4	9	13	3	5	8	11	6	17	7	15	22	12	12	24	11	14	25	5	11	16	4	7	11	4	1	5
East	2	1	3	2	1	3	5	7	12	5	4	9	8	4	12	8	7	15	7	6	13	7	5	12	4	5	9	6	4	10	4	2	6	3	3	6
South-East	5	...	5	3	1	4	6	4	10	1	1	2	2	4	6	1	2	3	3	1	4	4	2	6	1	1	2	1	1	2	5	3	8	3	1	4
South	6	2	8	1	3	4	3	3	6	...	2	2	2	5	7	1	2	3	1	3	4	...	1	1	...	1	1	2	1	3	1	1	2	2	6	8
South-West	2	3	5	3	...	3	..	2	2	2	2	4	...	3	3	1	4	5	2	2	4	...	1	1	...	...	...	1	...	1	1	1	2	3	1	6	7
West	4	2	6	3	3	6	4	2	6	5	2	7	3	2	5	1	4	5	...	...	...	1	...	1	1	...	1	1	5	6	...	2	2	1	1	2
North-West	1	6	7	6	7	13	4	5	9	4	1	5	9	2	11	4	1	5	1	1	2	3	3	6	1	1	2	4	2	6	1	4	5	...	1	1
Calm	9	10	19	8	3	11	1	2	3	7	5	12	1	3	4	...	3	3	7	...	7	...	1	1	4	2	6	7	6	13	12	9	21	17	11	28
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	8			18			20			23			15			34			49			60			67			31			20			19		
Resultant Direction	S. 52° W.			N. 25° W.			N. 74° E.			N. 27° E.			N. 49° E.			N. 57° E			N. 64° E.			N. 47° E.			N. 40° E.			N. 37° E.			N. 73° E.			S. 24° E.		
Mean diurnal velocity of wind in miles	59·4			83·3			94·3			77·1			160·0			111·0			100·6			108·0			86·3			78·4			47·7			37·2		
Average Resultant Percentage (6-8 Years.)	9			9			11			19			27			32			49			51			51			40			19			10		
Average Resultant Direction (6-8 Years.)	S. 19° E.			N. 51° W.			N. 11° E.			N. 16° E.			N. 32° E.			N. 56° E.			N. 59° E.			N. 44° E.			N. 45° E.			N. 65° E.			N. 84° E.			S. 4° E.		
Average diurnal velocity of wind in miles (7-8 Years.)	58·8			83·1			91·4			93·7			112·7			107·4			107·0			97·8			76·8			64·5			53·1			48·9		

9.—MURREE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	1	1	...	...	...	...	...	...	1	1	2	...	...	...	..	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	3	3	..	..	...	1	1	2	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	2	3	5	1	2	3	3	3	6	1	2	3	1	1	2	...	...	...	...	1	1	2	...	2	1	...	1	1	3	4	1	1	2	1	1	2
South-East	23	13	36	10	7	17	7	9	16	4	7	11	10	7	17	8	6	14	5	6	11	4	7	11	6	4	10	10	4	14	7	3	10	13	9	22
South	2	2	4	6	4	10	7	4	11	10	5	15	8	3	11	8	8	16	2	2	4	3	2	5	2	1	3	...	2	2	4	1	5	2	1	3
South-West	2	...	2	1	1	2	..	...	...	2	...	2	1	...	1	3	1	4	...	...	...	1	...	1	...	...	...	...	...	...	1	1	2	...	...	...
West	...	...	...	...	...	...	...	...	...	2	5	7	1	2	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	1	3	4	2	2	4	1	2	3	4	2	6	4	6	10	3	1	4	3	4	7	1	1	2	3	...	3	...	1	1	...	3	3	1	7	8
Calm	1	7	8	8	11	19	12	12	24	7	9	16	5	11	16	8	13	21	21	17	38	20	21	41	18	25	43	20	19	39	17	21	38	14	12	26
Variable	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	62			40			40			33			24			43			11			23			17			29			21			28		
Resultant Direction	S. 48° E.			S. 29° E.			S. 41° E.			S. 5° W.			S. 12° E.			S. 11° E.			S. 33° E.			S. 32° E.			S. 37° E.			S. 50° E.			S. 26° E.			S. 43° S.		
Mean diurnal velocity of wind in miles	183·4			170·4			172·6			144·3			163·4			110·7			92·4			82·7			95·9			134·1			107·4			85·3		
Average Resultant Percentage (10 Years)	30			24			20			15			7			6			7			9			5			5			15			31		
Average Resultant Direction (10 Years)	S. 68° E.			S. 44° E.			S. 37° E.			S. 73° E.			S. 11° E.			S. 1° E.			S. 3° W.			S. 6° W.			N. 84° E.			S. 13° E.			S. 57° E.			S. 68° E.		
Average diurnal velocity of wind in miles (3 Years)	?			?			?			?			?			?			?			?			92·2			113·1			99·4			113·1		

10.—RAWALPINDI (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	...	...	...	1	...	1	3	3	6	1	2	3	...	...	...	1	1	2	...	1	1	...	...	...	...	1	1	...	...	...	2	...	2
North-East	8	4	12	2	...	2	5	3	8	4	...	4	...	3	3	4	2	6	2	2	4	5	3	8	1	...	1	2	1	3	1	1	2	1	1	2
East	1	1	2	...	...	...	1	1	2	1	2	3	2	1	3	4	1	5	1	1	2	3	3	6	...	1	1	2	1	3	1	1	2	...	...	...
South-East	7	3	10	1	4	5	2	4	6	2	1	3	10	3	13	10	7	17	8	3	11	10	5	15	4	6	10	4	5	9	1	...	1	...	...	...
South	3	2	5	6	...	6	1	...	1	4	2	6	2	4	6	4	7	11	4	8	12	2	3	5	1	1	2	...	...	...	3	...	3	...	...	...
South-West	4	4	8	5	7	12	10	4	14	6	2	8	3	6	9	2	6	8	5	6	11	...	1	1	5	4	9	1	4	5	2	4	6	1	1	2
West	3	9	12	7	11	18	4	12	16	2	8	10	3	4	7	1	3	4	1	2	3	...	...	...	...	...	...	1	3	4	2	8	10	...	8	8
North-West	3	8	11	6	6	12	6	6	12	5	10	15	6	6	12	2	2	4	2	...	2	...	...	...	...	1	1	2	1	3	2	6	8	1	7	8
Clam	1	...	1	1	...	1	1	...	1	2	...	2	4	2	6	3	2	5	7	8	15	11	15	26	19	17	36	19	13	32	17	10	27	24	12	36
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	13			56			37			34			18			39			34			38			24			8			27			27		
Resultant Direction	S. 87° W.			S. 75° W.			W.			N. 73° W.			S. 43° W.			S. 22° E.			S. 1° E.			S. 66° E.			S. 7° E.			S. 21° E.			S. 87° W.			N. 61° W.		
Mean diurnal velocity of wind in miles	48·6			61·4			56·9			54·8			70·3			56·6			47·3			35·5			14·8			31·0			29·0			21·1		
Average Resultant Percentage (10-15 Years)	25			31			25			24			15			5			36			27			12			16			25			32		
Average Resultant Direction (10-15 Years)	N. 71° W.			N. 74° W.			N. 71° W.			N. 68° W.			N. 50° W.			S. 20° E.			S. 84° E.			S. 58° E.			S. 40° E.			S. 62° W.			S. 82° W.			N. 65° W.		
Average diurnal velocity of wind in miles (8-9 Years)	47·1			59·9			64·4			73·0			69·2			62·1			49·0			36·2			32·7			30·3			28·1			29·9		

11.—SIALKOT (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	2	4	4	...	4	4	...	4	6	5	11	2	3	5	4	3	7
North-East	5	2	7	2	...	2	6	3	9	5	3	8	8	4	12	11	3	14
East	4	5	9	1	1	2	2	3	5	1	1	2	5	2	7	5	6	11
South-East	5	2	7	4	2	6	1	3	4	2	...	2	6	3	9	6	5	11
South	...	...	...	2	1	3	1	...	1	3	1	4	2	3	5		1	1
South-West	...	...	...	3	2	5	1	2	3	...	3	3	...	5	5	2	5	7
West	2	9	11	5	13	18	5	12	17	3	10	13	2	5	7	1	3	4
North-West	6	2	8	5	6	11	8	4	12	8	4	12	4	5	9	1	4	5
Calm	7	9	16	2	3	5	3	4	7	2	3	5	2	1	3	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	16			39			30			38			11			29		
Resultant Direction	N. 13° E.			N. 84° W.			N. 46° W.			N. 40° W.			N. 45° E.			N. 68° E.		
Mean diurnal velocity of wind in miles	51·2			55·4			66·1			59·6			57·1			89·8		
Average Resultant Percentage (10 Years.)	26			35			38			17			16			8		
Average Resultant Direction (10 Years.)	N. 66° W.			N. 74° W.			N. 62° W.			N. 54° W.			N. 17° W.			N. 82° E.		
Average diurnal velocity of wind in miles (7 Years.)	29·9			44·0			45·2			58·7			59·1			63·0		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	2	4	3	1	4	...	2	2	5	1	6	5	1	6	1	2	3
North-East	5	3	8	9	3	12	5	3	8	12	...	12	3	...	3	5	2	7
East	8	3	11	9	7	16	8	2	10	6	3	9	8	3	11	3	2	5
South-East	6	4	10	5	2	7	9	2	11	5	5	10	3	2	5	5	...	5
South	2	1	3	1	2	3	3	3	6	...	2	2	4	...	4	2	1	3
South-West	3	5	8	1	5	6	2	1	3	...	...	...	1	2	3	4	2	6
West	3	8	11	1	4	5	...	9	9	...	13	13	4	16	20	6	13	19
North-West	2	4	6	1	1	2	2	6	8	3	7	10	2	6	8	3	6	9
Calm	...	1	1	1	6	7	1	2	3	...	...	...	...	...	...	2	3	5
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	5			30			12			21			20			27		
Resultant Direction	S. 57° E.			N. 85° E.			S. 69° E.			N. 20° E.			N. 70° W.			N. 78° W.		
Mean diurnal velocity of wind in miles	72·9			86·6			47·5			53·9			45·6			31·2		
Average Resultant Percentage (10 Years.)	38			27			8			17			36			35		
Average Resultant Direction (10 Years.)	S. 89° E.			N. 89° E.			N. 11° E.			N. 47° W.			N. 71° W.			N. 85° W.		
Average diurnal velocity of wind in miles (7-8 Years.)	55·9			52·1			34·8			29·6			23·4			24·3		

12.—LAHORE (*4 observations daily*).

	January.					February.					March.					April.					May.					June.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	4	4	...	10	1	4	2	1	8	7	6	7	1	21	7	6	5	2	20	4	3	3	3	13	1	1	...	...	2
North-East	...	...	3	2	5	1	1	2	1	5	...	6	2	3	11	3	5	2	2	12	2	2	4	3	11	1	3	4	2	10
East	6	8	7	7	28	3	6	2	1	12	2	7	5	6	20	3	3	5	6	17	6	13	3	2	24	6	11	6	6	29
South-East	...	1	1	1	3	...	1	...	...	1	1	...	...	...	1	...	1	...	...	1	...	1	...	...	1	2	...	...	...	2
South	..	...	..	...	...	..	...	...	...	...	1	...	...	...	1	...	1	...	..	1	...	...	...	...	...	...	1	1	..	2
South-West	...	...	...	...	...	...	1	...	...	1	...	...	...	...	...	...	...	2	...	2	1	...	1	...	2	...	...	2	...	2
West	...	3	4	...	7	1	4	13	1	19	1	4	9	2	16	4	5	13	..	22	3	4	10	3	20	7	12	13	4	36
North-West	1	3	6	...	10	2	6	7	...	15	4	5	6	2	17	2	6	3	3	14	2	4	4	1	11	1	2	1	2	6
Calm	22	12	6	21	61	20	5	2	24	51	15	3	2	17	37	11	3	...	17	31	13	4	6	19	42	12	...	3	16	31
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	22					22					32					30					21					8				
Resultant Direction	N. 47° E.					N. 34° W.					N. 1° E.					N. 11° W.					N. 7° E.					N. 26° W.				
Mean diurnal velocity of wind in miles	35·2					31·1					57·4					63·0					55·2					58·8				
Average Resultant Percentage (10-15 Years.)	21					30					33					26					23					14				
Average Resultant Direction (10-15 Years.)	N. 25° W.					N. 25° W.					N. 10° W.					N. 19° W.					N. 8° E.					N. 22° W.				
Average diurnal velocity of wind in miles (11 Years.)	46·8					58·8					75·3					82·0					79·2					84·4				

	July.					August.					September.					October.					November.					December.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	4	2	5	1	12	...	...	1	...	1	...	...	1	...	1	1	3	1	...	5	2	4	5	1	12	4	12	7	...	23
North-East	2	6	3	1	12	3	3	4	2	12	2	2	1	2	7	2	2	1	2	7	1	2	...	3	6	1	1	...	1	3
East	9	4	7	8	28	13	16	7	9	45	6	8	8	2	24	4	10	4	2	20	3	7	5	2	17	1	3	1	1	6
South-East	...	1	...	...	1	...	...	...	...	...	...	1	...	...	1	1	...	...	...	1	...	2	...	...	2	...	...	1	...	1
South	...	...	...	...	...	..	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	1	...	...	1
South-West	...	...	...	...	...	...	2	...	...	2	...	1	1	...	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	6	10	15	3	34	2	5	9	7	23	...	7	2	1	10	1	3	4	1	9	2	...	4	1	7	...	1	...	...	1
North-West	...	1	...	...	1	...	1	2	1	4	...	1	...	...	1	2	2	1	...	5	...	2	1	...	3	...	1	2	...	3
Calm	10	7	1	18	36	13	4	8	12	37	22	10	17	25	74	20	11	20	26	77	22	13	15	23	73	25	12	20	29	86
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	17					23					15					15					18					21				
Resultant Direction	N. 7° E.					N. 67° E.					N. 76° E.					N. 46° E.					N. 39° E.					N. 13° E.				
Mean diurnal velocity of wind in miles	48·5					49·3					25·9					26·0					30·8					19·6				
Average Resultant Percentage (10-15 Years.)	38					27					16					12					22					22				
Average Resultant Direction (10-15 Years.)	S. 73° E.					S. 83° E.					N. 70° E.					N. 3° W.					N. 47° W.					N. 36° W.				
Average diurnal velocity of wind in miles (11-12 Years.)	79·7					70·1					49·5					38·8					35·3					37·0				

13.—LUDHIANA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	1	1	1	3	4	5	3	8	...	...	...	...	...	...	...	..	...	...	5	5	...	1	1	1	...	1	...	...	...	...	1	1
North-East	...	...	...	...	2	2	1	3	4	1	...	1	2	...	2	...	...	...	...	1	1	1	1	2	2	1	3	2	1	3	1	...	1	1	...	1
East	1	3	4	4	7	11	...	2	2	...	...	...	1	...	1	3	1	4	...	...	...	...	...	...	...	1	1	2	...	2	...	3	3	...	...	...
South-East	4	2	6	2	...	2	2	1	3	2	...	2	3	2	5	5	1	6	3	1	4	8	1	9	4	...	4	3	1	4	2	1	3	2	1	3
South	3	3	6	...	...	...	1	2	3	...	...	...	2	1	3	1	1	2	1	1	2	3	3	6	1	...	1	...	...	...	1	...	1	...	...	...
South-West	1	1	2	...	...	...	...	...	...	...	...	...	1	1	2	..	1	1	...	2	2	2	2	4	...	...	...	1	...	1	...	...	...	...	...	...
West	4	6	10	6	7	13	5	5	10	9	20	29	5	11	16	2	8	10	4	2	6	4	5	9	6	10	16	2	7	9	2	3	5	3	5	8
North-West	1	2	3	3	3	6	4	3	7	4	5	9	1	3	4	1	...	1	2	2	4	1	5	6	2	7	9	1	5	6	1	1	2	3	3	6
Calm	17	14	31	13	8	21	17	12	29	9	2	11	16	13	29	18	18	36	21	22	43	12	9	21	15	10	25	19	17	36	23	22	45	22	21	43
Variable	...	...	..	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	..	...	...	...	...	...	..	...	...	..	...	...	...	...	...	...	...
Resultant (Percentage)	18			11			17			60			24			12			12			15			29			13			2			16		
Resultant (Direction)	S. 29° W.			N. 33° W.			N. 50° W.			N. 68° W.			S. 75° W.			S. 27° W.			S. 68° W.			S. 61° W.			N. 71° W.			N. 61° W.			S. 30° W.			N. 68° W.		
Mean diurnal velocity of wind in miles	25·9			25·9			28·9			85·8			59·0			61·3			39·2			31·4			21·4			15·1			15·5			13·0		
Average Resultant (Percentage)	30			42			35			20			12			12			30			15			12			31			46			25		
Average Resultant (Direction). 10 Years.	N. 46° W.			N. 42° W.			N. 38° W.			N. 56° W.			N. 24° W.			N. 55° W.			S. 49° E.			S. 75° E.			N. 14° W.			N. 32° W.			N. 42° W.			N. 4° W.		
Average diurnal velocity of wind in miles. 7-8 Years.	30·9			43·8			47·3			56·2			61·7			64·1			54·8			42·3			30·4			24·6			21·8			24·4		

14.—KAILANG (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	The observatory opened in July.																		...	1	1	...	1	1	...	...	...	...	...	...	1	1	2	...	...	...
North-East																			...	...	...	...	...	...	...	...	...	...	1	1	2	...	2	..	1	1
East																			...	...	...	...	1	1	...	...	...	...	2	2	...	...	...	...	...	...
South-East																			...	1	1	1	2	3	1	1	2	...	1	1	1	1	2	1	3	4
South																			1	1	2	3	2	5	.5	2	7	2	7	9	5	4	9	4	4	8
South-West																			18	10	28	20	10	30	21	19	40	20	17	37	15	16	31	9	10	19
West																			5	6	11	4	6	10	1	2	3	6	2	8	6	5	11	5	3	8
North-West																			6	11	17	3	9	12	2	6	8	...	1	1	...	3	3	2	2	4
Calm																			...	...	...	...	...	...	...	...	...	3	...	3	...	...	...	10	7	17
Variable																			...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	...			...			...			...			...			...			72			66			79			75			70			48		
Resultant (Direction)	...			...			...			...			...			...			S. 77° W.			S. 63° W.			S. 49° W.			S. 42° W.			S. 50° W.			S. 45° W.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...			19·9			8·8			2·3			2·1			0·7			0·2		
Average Resultant (Percentage)	...			...			...			...			...			...			...			...			...			...			...			...		
Average Resultant (Direction). Years.	...			...			...			...			...			...			...			...			...			...			...			...		
Average diurnal velocity of wind in miles. Years.	...			...			...			...			...			...			...			...			...			...			...			...		

15.—SIMLA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	...	4	4	6	2	8	7	6	13	9	11	20	4	7	11	6	5	11	10	8	18	8	9	17	6	8	14	6	3	9	...	1	1
North-East	...	...	...	...	..	...	.	...	1	1	2	2	2	4	1	4	5	3	2	5	1	1	2	2	1	3	1	1	2	3	4	7	4	5	9
East	...	...	...	...	..	...	..	...	...	...	...	...	..	2	1	3	1	...	1	1	..	1	..	...	...	...	...	...	...	...	3	3	...	...	...	...
South-East	2	2	4	...	..	...	1	...	1	...	...	...	...	..	1	1	...	...	...	...	...	...	...	...	1	1	1	...	1	2	3	5	1	...	1
South	11	8	19	8	6	14	9	10	19	1	1	2	8	4	12	...	1	1	3	..	3	1	...	1	1	2	3	3	3	6	4	3	7	1	2	3
South-West	3	4	7	7	7	14	4	6	10	2	8	10	5	7	12	7	3	10	2	...	2	3	...	3	2	1	3	7	4	11	5	5	10	10	10	20
West	...	3	3	1	1	2	2	6	8	4	5	9	3	2	5	8	5	13	3	5	8	4	4	8	7	4	11	4	7	11	2	2	4	...	1	1
North-West	3	...	3	...	...	...	3	3	4	2	6	2	2	4	4	7	11	3	8	11	4	11	15	4	7	11	4	8	12	2	7	9	9	10	19
Calm	12	13	25	12	10	22	9	4	13	11	7	18	...	..	..	4	2	6	10	11	21	7	7	14	6	5	11	5	...	5	6	...	6	6	2	8
Variable	..	...	...	...	...	...	..	..	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	40			41			38			35			23			43			35			52			46			43			11			35		
Resultant Direction	S. 17° W.			S. 31° W.			S. 45° W.			N. 63° W.			N. 71° W.			N. 56° W.			N. 35° W.			N. 34° W.			N. 41° W.			N. 69° W.			N. 66° W.			N. 82° W.		
Mean diurnal velocity of wind in miles	16·4			19·6			23·6			24·1			55·7			40·9			36·7			43·4			43·8			59·0			60·2			46·2		
Average Resultant Percentage (3-4 Years.)	31			34			35			37			33			37			18			31			43			49			37			23		
Average Resultant Direction (3-4 Years.)	S. 48° W.			S. 38° W.			S. 52° W.			S. 81° W.			N. 82° W.			N. 57° W.			N. 73° W.			N. 62° W.			N. 53° W.			N. 36° W.			S. 88° W.			N. 66° W.		
Average diurnal velocity of wind in miles (3-4 Years.)	39·4			59·0			64·2			67·7			68·3			53·5			36·8			36·0			42·0			60·5			48·1			42·8		

16.—DELHI (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	2	2	3	2	5	4	6	10	3	6	9	3	4	7	4	4	8	1	3	4	2	3	5	2	12	14	2	15	17	...	8	8	2	7	9
North-East	2	2	4	...	1	1	2	2	4	...	3	3	3	4	7	2	5	7	2	4	6	2	2	4	...	4	4	3	4	7	1	2	3	2	...	2
East	1	1	2	...	1	1	1	2	3	...	1	1	1	1	2	1	1	2	1	2	3	1	6	7	2	...	2	...	...	...	3	3	6	...	2	2
South-East	10	8	18	3	2	5	4	2	6	3	1	4	4	4	8	7	1	8	8	7	15	6	3	9	5	2	7	3	1	4	4	3	7	4	2	6
South	...	3	3	1	1	2	3	3	6	1	1	2	1	...	1	2	3	5	2	2	4	1	...	1	2	1	3	2	...	2	1	...	1	...	...	...
South-West	3	...	3	3	1	4	4	2	6	2	1	3	4	1	5	3	2	5	4	3	7	1	4	5	3	...	3	2	...	2	2	...	2	2	...	2
West	12	4	16	11	6	17	5	7	12	7	4	11	7	6	13	3	5	8	6	3	9	6	5	11	6	4	10	10	4	14	11	5	16	16	7	23
North-West	3	11	14	7	14	21	7	7	14	14	13	27	8	11	19	8	8	16	7	6	13	12	8	20	10	7	17	8	6	14	7	6	13	4	12	16
Calm	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	...	1	1	...	1	1	...	...	...	...	...	...	1	1	2	1	3	4	1	1	2
Variable	..	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	18			57			29			58			37			24			9			27			39			50			30			52		
Resultant Direction	S. 73° W.			N. 68° W.			N. 63° W.			N. 48° W.			N. 49° W.			N. 45° W.			S. 68° W.			N. 48° W.			N. 37° W.			N. 34° W.			N. 49° W.			N. 60° W.		
Mean diurnal velocity of wind in miles	65·2			76·9			86·1			95·2			105·2			99·9			89·8			115·1			89·5			59·2			62·2			57·7		
Average Resultant Percentage (8 Years.)	41			35			47			37			6			23			17			8			16			48			51			52		
Average Resultant Direction (8 Years.)	N. 74° W.			N. 65° W.			N. 62° W.			N. 67° W.			N. 32° W.			N. 61° W.			S. 45° E.			S. 6° E.			N. 40° W.			N. 52° W.			N. 59° W.			N. 68° W.		
Average diurnal velocity of wind in miles (9 Years.)	73·1			86·2			91·7			96·4			107·5			124·1			113·4			110·2			98·4			62·2			58·4			66·7		

17.—SIRSA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	3	4	1	8	9	2	5	7	3	4	7	1	1	2	2	1	3	...	1	1	...	...	...	1	...	1	...	3	3	1	3	4	2	4	6
North-East	..	2	2	2	2	4	...	..	2	4	..	4	..	...	...	...	...	...	...	2	2	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...
East	3	4	7	...	...	...	3	2	5	1	1	2	3	2	5	2	2	4	2	3	5	1	2	3	...	5	5	...	...	...	3	2	5	...	...	...
South-East	2	2	4	3	1	4	1	...	1	2	...	2	..	...	.	1	4	5	5	1	6	4	2	6	2	...	2	1	1	2	...	1	1	3	1	4
South	2	3	5	1	...	1	...	...	...	...	...	...	..	1	1	...	1	1	..	...	...	...	...	...	...	1	1	...	...	...	1	...	1	...	...	...
South-West	1	1	2	..	...	...	1	1	2	1	...	1	2	..	2	3	2	5	3	3	6	3	4	7	2	...	2	...	...	...	...	1	1	1	...	1
West	3	2	5	...	1	1	2	6	8	3	6	9	11	15	26	12	7	19	11	10	21	14	15	29	8	6	14	2	3	5	2	1	3	...	...	...
North-West	...	4	4	1	3	4	3	6	9	...	3	3	...	3	3	3	4	7	...	...	...	...	...	...	2	...	2	2	4	6	1	3	4	...	1	1
Calm	19	10	29	20	12	32	17	11	28	16	15	31	14	9	23	7	9	16	10	11	21	9	7	16	15	18	33	26	20	46	22	19	41	25	25	50
Variable	..	...	..	...	1	1	...	...	...	...	...	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...
Resultant Percentage	4			20			25			19			40			33			25			44			18			16			7			6		
Resultant Direction	S. 63° E.			N. 10° E.			N. 34° W.			N. 30° W.			N. 86° W.			W.			S. 67° W.			S. 72° W.			S. 82° W.			N. 53° W.			N. 11° W.			N. 24° E.		
Mean diurnal velocity of wind in miles	26·8			30·4			38·5			37·4			54·2			75·2			48·8			51·0			22·9			20·0			20·9			17·1		
Average Resultant Percentage (7-8 Years.)	16			28			26			29			20			32			23			20			21			30			24			22		
Average Resultant Direction (7-8 Years.)	N. 17° W.			N. 26° W.			N. 34° W.			N. 83° W.			N. 85° W.			S. 88° W.			S. 4° E.			S. 35° W.			N. 77° W.			N. 71° W.			N. 50° W.			N. 27° W.		
Average diurnal velocity of wind in miles (7-8 Years.)	58·9			80·8			86·2			97·5			113·5			137·5			123·1			120·3			82·7			59·9			48·8			48·4		

18.—CHAKRATA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	1	...	1	1	...	1	1	...	1	...	1	1	...	...	...	...	...	...	1	...	1	...	..	...	...	...	...	...	2	2	...	...	...
North-East	1	3	4	...	1	1	3	2	5	4	...	4	1	...	1	2	2	4	3	...	3	1	2	3	1	1	2	3	2	5	8	1	9	10	...	10
East	15	6	21	12	2	14	13	1	14	7	4	11	12	3	15	..	...	..	4	3	7	3	1	4	5	2	7	13	1	14	12	4	16	13	4	17
South-East	2	...	2	5	...	5	5	1	6	2	...	2	2	...	2	2	...	2	...	...	...	..	...	...	2	...	2	5	...	5	3	...	3	1	1	2
South	1	...	1	2	...	2	1	...	1	3	1	4	4	...	4	1	1	2	..	...	...	2	..	2	1	1	2	1	...	1	...	...	...	...	1	1
South-West	3	1	4	1	...	1	1	3	4	8	6	14	10	16	26	12	5	17	3	3	6	5	6	11	3	...	3	4	5	9	2	3	5	5	4	9
West	7	19	26	3	23	26	6	24	30	5	18	23	2	10	12	13	21	34	16	25	41	16	21	37	11	26	37	3	21	24	3	18	21	2	20	22
North-West	...	1	1	2	1	3	...	...	...	...	1	1	...	1	1	...	1	1	4	..	4	3	1	4	4	...	4	1	2	3	2	2	4	.	1	1
Calm	1	1	2	2	1	3	1	...	1	...	...	...	...	...	...	.	...	...	1	...	1	...	...	...	3	...	3	1	...	1	...	...	...	...	...	...
Variable	...	...	.	...	...	..	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	7			19			19			35			41			74			63			69			54			20			10			6		
Resultant Direction	S. 81° W.			S. 77° W.			S. 72° W.			S. 60° W.			S. 33° W.			S. 74° W.			N. 89° W.			S. 85° W.			S. 88° W.			S. 65° W.			N. 27° W.			S. 74° W.		
Mean diurnal velocity of wind in miles	118·4			142·5			156·2			168·7			173·6			154·6			131·0			127·9			102·4			121·2			146·0			112·9		
Average Resultant Percentage (10-15 Years.)	4			6			7			19			23			43			39			36			32			30			28			11		
Average Resultant Direction (10-15 Years.)	S. 30° W.			S. 78° E.			S. 18° W.			S. 60° W.			S. 52° W.			S. 63° W.			S. 62° W.			S. 62° W.			S. 64° W.			S. 64° W.			S. 55° W.			S. 30° W.		
Average diurnal velocity of wind in miles (11-12 Years.)	116·7			131·0			138·8			142·2			142·4			134·9			113·5			100·7			109·2			126·1			110·4			103·2		

19.—MUSSOOREE (S. G. OFFICE) (*4 observations daily*).

	January.					February.					March.					April.					May.					June.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	...	...	...	...	..	..	.	...	...	...	...	...	...	...	...	...	...	15	5	...	11	31	4	1	...	7	12
North-East	...	...	...	...	..	.	..	...	...	..	...	...	...	...	...	...	...	...	...	.	7	5	1	5	18	6	2	1	4	13
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	6	1	1	9	...	2	...	1	3
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	3	8	6	1	18	2	5	4	...	11
South	..	...	...	...	...	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	4	18	3	27	7	17	19	7	50
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	3	2	2	8	4	2	4	6	16
West	...	...	..	...	...	...	..	...	..	.	...	..	...	...	...	...	...	...	...	...	...	...	1	5	6	4	...	...	3	7
North-West	...	...	...	...	..	...	...	...	..	..	...	...	..	...	...	...	...	...	...	...	2	...	2	3	7	2	1	2	2	7
Calm	..	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...					...					...					...					15					36				
Resultant Direction	...					...					...					...					N. 80° E.					S. 4° W.				
Mean diurnal velocity of wind in miles	...					...					...					...					281·1					265·1				
Average Resultant Percentage (5-6 Years.)	...					...					...					...					11					25				
Average Resultant Direction (5-6 Years.)	...					...					...					...					S. 25° E.					S. 4° W.				
Average diurnal velocity of wind in miles (6 Years.)	...					...					...					...					300·0					270·5				

	July.					August.					September.					October.					November.					December.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	1	3	1	3	8	4	7	1	...	12	2	1	...	3	6	7	4	..	9	20	...	...	...	...	...	...	...	...	...	...
North-East	1	3	...	2	6	1	6	...	1	8	8	2	..	4	14	9	3	1	5	18	...	...	...	...	...	...	...	...	...	...
East	2	4	2	...	8	...	1	...	...	1	1	3	2	1	7	1	5	...	2	8	...	...	...	...	...	...	...	...	...	...
South-East	4	7	2	4	17	...	1	..	...	1	3	4	1	1	9	2	2	...	...	4	...	...	...	...	...	...	...	...	...	...
South	5	6	17	10	38	3	7	14	4	28	8	12	14	5	39	2	6	15	...	23	...	...	...	...	...	...	...	...	...	...
South-West	5	5	5	5	20	5	1	7	8	21	3	3	9	9	24	1	...	4	2	7	...	...	...	...	...	...	...	...	...	...
West	7	3	3	4	17	5	...	1	7	13	2	1	1	2	6	...	...	1	1	2	...	...	...	...	...	...	...	...	...	...
North-West	6	...	1	3	10	6	1	...	3	10	2	...	...	4	6	...	2	...	2	4	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	38					36					38					17					...					...				
Resultant Direction	S. 17° W.					S. 56° W.					S. 5° W.					N. 71° E.					...					...				
Mean diurnal velocity of wind in miles	*196·4					199·5					189·1					202·1*					...					...				
Average Resultant Percentage (6-7 Years.)	25					21					25					6					...					...				
Average Resultant Direction (6-7 Years.)	S. 1° E.					S 13° E.					S. 23° E.					S. 66° E.					...					...				
Average diurnal velocity of wind in miles (6-7 Years.)	216·8					205·5					200·6					212·0					...					...				

* Mean of 21·4 days.

20.—DEHRA (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	5	5	2	3	15	3	2	...	...	5	10	9	1	5	25	11	8	...	4	23	3	3	1	2	9	4	2	2	4	12
North-East	5	4	2	2	13	1	1	...	...	2	4	3	2	3	12	8	8	...	2	18	6	4	...	1	11	1	3	2	1	7
East	2	4	1	5	12	1	2	...	...	3	1	1	2	...	4	3	2	1	2	8	1	3	..	2	6	2	3	3	5	13
South-East	3	2	5	3	13	...	1	3	2	6	1	2	2	2	7	1	1	...	1	3	3	3	3	1	10	6	5	1	3	15
South	3	3	7	5	18	2	2	5	4	13	...	1	12	1	14	...	3	...	1	4	2	3	2	3	10	1	3	7	2	13
South-West	2	3	8	2	15	8	8	9	10	35	5	5	11	7	28	1	...	6	2	9	2	1	5	4	12	3	8	6	3	20
West	4	3	4	5	16	9	7	10	9	35	3	3	1	7	14	2	1	16	8	27	...	7	12	4	23	4	3	5	5	17
North-West	3	4	1	3	11	2	4	...	2	8	4	4	...	5	13	3	5	6	9	23	10	7	8	13	38	3	2	3	1	9
Calm	2	...	1	1	4	2	1	1	1	5	3	3	...	1	7	...	...	...	...	..	4	...	...	1	5	6	1	1	6	14
Variable	...	...	...	...	..	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	6					57					21					41					34					14				
Resultant Direction	S. 34° W.					S. 62° W.					N. 81° W.					N. 34° W.					N. 64° W.					S. 32° W.				
Mean diurnal velocity of wind in miles	56·1					55·5					61·7					75·1					76·7					54·3				
Average Resultant Percentage, 14-15 Years.	17					19					25					21					17					12				
Average Resultant Direction, 14-15 Years.	S. 75° W.					S. 85° W.					N. 78° W.					N. 79° W.					S. 76° W.					S. 66° W.				
Average diurnal velocity of wind in miles 6-8 Years.	47·2					52·0					56·8					66·2					62·0					39·1				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	3	3	4	2	12	7	6	11	10	34	5	2	...	5	12	12	9	3	14	38	7	8	4	8	27	11	9	7	15	42
North-East	3	3	...	2	8	6	7	2	3	18	2	1	1	1	5	7	5	...	4	16	1	3	2	2	8	4	4	1	2	11
East	2	3	1	4	10	2	1	2	2	7	1	1	...	1	3	2	2	...	1	5	6	5	...	1	12	4	3	1	3	11
South-East	5	7	3	4	19	2	4	...	1	7	2	2	...	...	4	3	3	1	2	9	...	...	3	3	6	2	2	1	1	6
South	1	3	4	1	9	...	1	2	1	4	...	1	4	...	5	...	...	2	1	3	...	1	3	2	6	...	...	2	3	5
South-West	3	4	8	1	16	2	1	4	2	9	1	2	1	...	4	3	2	6	4	15	2	3	4	5	14	1	1	3	3	8
West	1	3	5	2	11	1	3	2	1	7	1	1	5	1	8	...	...	5	3	8	...	1	2	3	6	...	...	4	1	5
North-West	2	2	5	1	10	3	4	5	5	17	2	...	8	3	13	1	...	9	2	12	1	...	5	1	7	2	1	9	3	15
Calm	11	3	1	14	29	6	2	...	3	11	9	13	5	13	40	3	10	5	...	18	13	9	7	5	34	7	11	3	...	21
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	7					38					19					31					15					37				
Resultant Direction	S. 2° W.					N. 1° W.					N. 37° W.					N. 7° W.					N. 3° E.					N. 2° E.				
Mean diurnal velocity of wind in miles	39·1					40·1					23·4					41·9					34·1					40·3				
Average Resultant Percentage, 15 Years.	10					10					18					19					18					16				
Average Resultant Direction, 15 Years.	S. 37° W.					S. 43° W.					N. 80° W.					N. 38° W.					N. 76° W.					N. 73° W.				
Average diurnal velocity of wind in miles 8-9 Years.	31·0					28·0					27·4					39·1					44·4					44·8				

21.—PAORI (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	1	4	7	3	10	13	5	18	11	4	15	2	1	3	5	...	5
North-East	11	1	12	13	...	13	6	...	6	4	7	11	7	6	13	6	1	7
East	9	1	10	4	...	4	6	3	9	3	8	11	4	8	12	2	5	7
South-East	5	...	5	...	1	1	1	3	4	1	1	2	1	5	6	...	4	4
South	...	3	3	...	3	3	...	5	5	...	3	3	5	1	6	3	3	6
South-West	...	13	13	1	13	14	...	6	6	...	3	3	1	2	3	1	7	8
West	1	4	5	...	7	7	...	3	3	1	2	3	1	2	3	1	3	4
North-West	2	1	3	3	1	4	5	6	11	10	2	12	10	2	12	6	4	10
Calm	...	7	7	...	...	...	...	...	...	...	...	...	...	4	4	6	3	9
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	9			18			29			43			23			5		
Resultant { Direction	S. 79° E.			N. 35° W.			N. 3° E.			N. 15° E.			N. 55° E.			N. 38° W.		
Mean diurnal velocity of wind in miles	42·2			66·6			77·0			72·6			42·2			53·8		
Average Resultant { Percentage	?			?			?			?			?			17		
Average Resultant { Direction	?			?			?			?			?			N. 47° W.		
3 Years.																		
Average diurnal velocity of wind in miles. Years.	?			?			?			?			?			?		

	JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	...	2	3	...	3	1	...	1	3	...	3	8	1	9	Observatory abolished.		
North-East	1	...	1	3	2	5	...	1	1	9	1	10	7	...	7			
East	...	...	...	...	1	1	...	...	...	3	...	3	...	...	...			
South-East	...	...	...	1	5	6	...	...	...	1	1	2	...	2	2			
South	...	2	2	...	5	5	...	1	1	...	4	4	...	4	4			
South-West	2	5	7	1	6	7	...	13	13	...	12	12	...	7	7			
West	1	13	14	1	6	7	1	10	11	...	9	9	...	9	9			
North-West	...	...	...	...	2	2	...	1	1	1	1	2	...	2	2			
Calm	25	10	35	21	4	25	28	4	32	12	2	14	15	5	20			
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...			
Resultant { Percentage	31			13			36			13			17			...		
Resultant { Direction	S. 77° W.			S. 36° W.			S. 69° W.			S. 72° W.			N. 61° W.			...		
Mean average velocity of wind in miles	47·6			66·8			65·6			75·1			54·2			...		
Average Resultant { Percentage	22			12			33			12			10			...		
Average Resultant { Direction	N. 64° W.			N. 85° W.			N. 87° W.			N. 58° W.			N. 46° W.			...		
3 Years.																		
Average diurnal velocity of wind in miles. 3 Years.	43·7			63·6			86·0			78·2			61·9			...		

22.—ROORKEE (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North		...	...	...	...	...	...	...	...	...	9	9	13	5	36	4	3	5	5	17
North-East	1	...	...	...	1	...	...	...	1	1	4	3	5	1	13	5	3	5	4	17
East	1	1	...	1	3	...	...	...	...	...	...	1	1	...	2	2	1	...	1	4
South-East	3	4	8	3	18	1	...	1	1	3	...	2	...	...	2	1	4	1	2	8
South	1	3	3	...	7	...	1	1	...	2	1	1	1	...	3	...	3	2	1	6
South-West	1	2	1	1	5	1	1	2	1	5	1	2	2	1	6	...	1	3	2	6
West	1	5	7	4	17	5	9	11	7	32	...	...	2	1	3	4	5	10	7	26
North-West	3	3	6	5	17	5	9	11	8	33	2	3	1	1	7	4	3	4	4	15
Calm	19	12	3	16	50	14	6	...	8	28	10	6	4	19	39	9	6	...	4	19
Variable	...	...	...	...	...	...	...	...	...		...	...	...	...	...	...	...	...	...	...
Resultant Percentage	16					56					37					26				
Resultant Direction	S. 57° W.					N. 74° W.					N. 1° E.					N. 39° W.				
Mean diurnal velocity of wind in miles	46·9					64·1					56·7					99·5				
Average Resultant Percentage (15 Years.)	16					23					23					10				
Average Resultant Direction (15 Years.)	N. 72° W.					N. 52° W.					N. 58° W.					N. 73° W.				
Average diurnal velocity of wind in miles (12-13 Years.)	56·3					70·1					72·3					76·8				

	MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	2	1	2	7	...	...	1	...	1
North-East	...	3	1	1	5	1	...	1	3	5
East	1	6	1	3	11	2	4	...	...	6
South-East	2	5	4	1	12	13	17	6	6	42
South	...	...	4	2	6	3	5	8	2	18
South-West	...	4	1	3	8	1	1	4	3	9
West	7	3	14	6	30	2	1	3	4	10
North-West	3	4	5	4	16	1	2	5	1	9
Calm	15	3	...	8	26	5	...	2	9	16
Variable	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	20					40				
Resultant Direction	N. 86° W.					S. 21° E.				
Mean diurnal velocity of wind in miles	69·6					98·2				
Average Resultant Percentage (15 Years.)	6					11				
Average Resultant Direction (15 Years.)	S. 68° W.					S. 4° E				
Average diurnal velocity of wind in miles (12-13 Years.)	89·9					101·5				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	1	...	...	1	1	1	2	1	5	...	1	1	1	3	...	1	2	1	4
North-East	...	...	2	..	2	1	...	...	1	2	...	...	...	...	...	...	...	...	...	...
East	2	...	2	1	5	3	3	2	2	10	1	..	...	...	1	...	...	...	...	...
South-East	6	16	6	5	33	10	14	12	7	43	4	13	5	2	24	1	5	...	1	7
South	1	3	7	4	15	2	1	1	3	7	1	5	5	2	13	3	7	3	...	13
South-West	...	2	2	...	4	...	1	2	1	4	1	3	3	2	9	2	3	2	2	9
West	1	2	3	2	8	1	3	4	3	11	1	1	5	2	9	...	...	1	...	1
North-West	...	3	2	1	6	...	3	6	3	12	3	4	9	6	22	1	5	7	3	16
Calm	17	2	6	14	39	9	2	1	7	19	8	1	2	15	36	21	7	13	21	62
Variable	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	..	...	...	..
Resultant Percentage	33					28					19					15				
Resultant Direction	S. 23° E.					S. 38° E.					S. 36° W.					S. 57° W.				
Mean diurnal velocity of wind in miles	51·3					62·9					45·4					17·7				
Average Resultant Percentage (15 Years.)	33					27					9					11				
Average Resultant Direction (15 Years.)	S. 39° E.					S. 36° E.					S. 6° E.					S. 27° E.				
Average diurnal velocity of wind in miles (12-13 Years.)	75·8					65·1					56·1					36·5				

	NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	1	...	1	2	...	...	...	...	...
North-East	...	1	2	1	4	...	...	1	...	1
East	3	1	2	1	7	...	...	...	...	...
South-East	6	...	4	2	...	6	...	2	1	... 3
South	1	4	2	1	8	...	2	1	...	3
South-West	...	2	1	...	3	...	4	3	1	8
West	...	4	4	...	8	...	5	9	1	15
North-West	3	5	7	...	15	4	4	6	2	16
Calm	21	6	8	24	59	25	12	8	25	70
Variable	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	6					25				
Resultant Direction	N. 81° W.					N. 88° W.				
Mean diurnal velocity of wind in miles	32·1					18·4				
Average Resultant Percentage (15 Years.)	28					11				
Average Resultant Direction (15 Years.)	S. 36° W.					N. 82° W.				
Average diurnal velocity of wind in miles (12-13 Years.)	31·9					35·5				

23.—RANIKHET (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	2	2	4	1	1	2	...	...	...	2	...	2	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	7	6	13	4	1	5	...	2	2	...	...	...	2	..	2	3	1	4	..	.	...	1	...	1	...	...	...	...	...	...	2	1	3	...	...	...
East	6	2	8	4	...	4	5	2	7	1	1	2	5	6	11	...	...	...	...	1	1	1	2	3	2	...	2	...	...	...	4	3	7	6	2	8
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	..	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	1	...	1	...	1	1	...	1	1	...	...	...	1	...	1	1	...	1	1	...	1	...	1	1	5	...	5	...	...	...	...	...	...	...	...	...
South-West	8	9	17	10	13	23	12	9	21	15	23	38	11	10	21	16	17	33	11	10	21	15	15	30	13	15	28	18	25	43	6	7	13	4	7	11
West	...	4	4	1	4	5	3	8	11	4	4	8	7	13	20	4	8	12	6	14	20	5	11	16	1	5	6	2	4	6	1	4	5	2	2	4
North-West	...	...	...	1	8	9	...	4	4	...	...	...	...	..	...	1	2	3	1	..	1	1	...	1	...	1	1	...	...	...	...	...	...	...	...	...
Calm	9	10	19	8	1	9	9	3	12	9	1	10	5	2	7	3	1	4	11	5	16	8	2	10	9	9	18	11	2	13	17	15	32	19	20	39
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	6			38			35			69			43			66			60			65			57			76			14			14		
Resultant { Direction	S. 17° E.			S. 70° W.			S. 69° W.			S. 53° W.			S. 57° W.			S. 63° W.			S. 66° W.			S. 59° W.			S. 45° W.			S. 50° W.			S. 36° W.			S. 26° W.		
Mean diurnal velocity of wind in miles	29·3			47·9			56·2			94·4			112·7			82·0			73·8			93·4			50·2			40·9			20·5			27·9		
Average Resultant { Percentage	12			22			49			48			45			47			25			25			38			51			33			16		
Average Resultant { Direction	S. 81° W.			S. 54° W.			S. 52° W.			S. 63° W.			S. 63° W.			S. 65 W.			S. 66° W.			S. 71° W.			S. 59° W.			S. 53° W.			S. 49° W.			S. 48° W.		
10 Years. Average diurnal velocity of wind in miles 10-12 Years.	61·1			66·8			87·1			93·7			90·9			90·2			107·8			103·6			90·3			77·5			63·3			62·9		

24.—PITHORAGARH (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	...	2	2	...	2	...	...	...	...	1	1	2	1	3	2	3	5	1	...	1	1	2	3	...	...	...	...	2	2	...	1	1	1	3	4
North-East	1	...	1	1	...	1	1	1	2	1	...	1	1	1	2	1	...	1	1	2	3	1	...	1	...	1	1	...	1	1	...	1	1	1	1	2
East	1	1	2	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2
South-East	2	3	5	2	5	7	1	5	6	7	9	16	2	7	9	2	...	2	...	1	1	...	...	...	3	2	5	4	1	5	...	1	1	1	2	3
South	4	7	11	1	9	10	...	12	12	3	13	16	8	17	25	4	15	19	4	11	15	7	15	22	3	13	16	...	7	7	1	8	9	2	4	6
South-West	...	9	9	...	3	3	...	3	3	...	1	1	...	...	...	...	..	...	...	1	1	...	...	...	...	1	1	...	...	...	...	1	1	...	...	...
West	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	..	1	...	...	...	...	1	1	...	2	2	...	...	...
North-West	...	..	..	...	...	...	...	...	...	...	2	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	21	10	31	22	10	32	30	10	40	19	4	23	18	5	23	21	12	33	25	16	41	21	14	35	24	13	37	27	19	46	28	15	43	26	20	46
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	29			27			29			45			45			25			22			29			33			14			14			10		
Resultant { Direction	S. 4° W.			S. 18° E.			S. 9° E.			S. 22° E.			S. 16° E.			S. 8° E.			S. 9° E.			S. 1° W.			S. 10° E.			S. 23° E.			S. 9° W.			S. 55° E.		
Mean diurnal velocity of wind in miles	24·9			19·3			28·0			50·3			64·2			29·1			16·3			22·4			22·0			22·2			16·0			16·8		
Average Resultant { Percentage	?			?			?			?			37			30			17			35			41			35			36			29		
Average Resultant { Direction	?			?			?			?			S. 8° E.			S. 12° E.			S. 30° E.			S. 5° E.			S. 5° E.			S. 18° E.			S. 12° E.			S. 54° E.		
3 Years. Average diurnal velocity of wind in miles. 3 Years.	?			?			?			?			98·5			67·9			52·7			54·9			60·9			55·1			45·2			38·9		

25.—MEERUT (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	1	...	1	3	2	5	2	...	2	...	..	...	2	2	4	1	...	1	1	4	5	1	1	2	5	2	7	4	2	6	3	1	4
North-East	...	1	1	1	..	1	2	3	5	...	...	...	3	2	5	...	3	3	1	1	2	...	...	...	...	2	2	1	...	1	1	...	1	.	...	...
East	1	1	2	...	...	...	2	1	3	...	...	...	...	...	...	2	...	2	...	...	...	1	...	1	1	...	1	1	...	1	1	...	1	...	...	...
South-East	9	8	17	2	1	3	6	4	10	6	4	10	5	7	12	10	8	18	8	12	20	11	10	21	10	8	18	3	2	5	9	7	16	3	3	6
South	1	2	3	...	1	1	2	1	3	3	...	3	2	...	2	3	1	4	5	1	6	1	...	1	2	1	3	...	1	1	...	2	2	...	...	...
South-West	1	1	2	2	...	2	2	1	3	...	2	2	5	4	9	2	2	4	2	2	4	1	3	4	1	...	1	2	1	3	...	1	1	1	2	3
West	1	5	6	5	5	10	1	2	3	...	...	...	1	...	1	2	1	3	1	...	1	3	1	4	1	...	1	...	...	...	1	2	3	...	...	..
North-West	14	10	24	16	19	35	10	15	25	19	24	43	15	17	32	6	13	19	11	11	22	13	13	26	14	16	30	12	21	33	13	15	28	24	24	48
Calm	4	3	7	1	2	3	3	2	5	...	...	...	...	1	1	3	...	3	2	4	6	..	...	...	1	1	2	7	4	11	1	1	2	...	1	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	16			71			27			54			33			4			10			17			19			52			27			72		
Resultant { Direction	N. 83° W.			N. 57° W.			N. 33° W.			N. 50° W.			N. 63° W.			W.			S. 37° W.			N. 63° W.			N. 44° W.			N. 40° W.			N. 40° W.			N. 45° W.		
Mean diurnal velocity of wind in miles	46·2			60·3			62·6			63·0			54·3			52·5			56·7			60·1			43·7			40·2			39·1			39·5		
Average Resultant { Percentage	46			52			44			44			24			22			23			5			17			41			45			51		
Average Resultant { Direction, 14-15 Years.	N. 49° W.			N. 54° W.			N. 51° W.			N. 53° W.			N. 32° W.			N. 26° W.			S. 86° E.			N. 80° E.			N. 34° W.			N. 48° W.			N. 51° W.			N. 52° W.		
Average diurnal velocity of wind in miles, 9-11 Years.	48·6			59·0			63·0			54·5			63·3			63·6			57·2			55·0			58·4			36·2			31·5			40·9		

26.—BAREILLY (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	2	...	2	...	1	1	2	...	2	...	...	...	...	1	1	...	2	2	...	4	4	...	1	1	...	...	...	...	1	...	...	...	...
North-East	3	1	4	1	1	2	2	1	3	1	1	2	1	1	2	4	4	8	5	2	7	4	3	7	6	4	10	6	3	9	...	...	...	5	...	5
East	...	...	...	1	...	1	3	...	3	1	...	1	11	7	18	11	11	22	8	6	14	9	4	13	4	4	8	4	...	4	4	2	6	...	...	...
South-East	9	8	17	...	1	1	2	2	4	5	3	8	6	...	6	5	3	8	5	3	8	...	1	1	11	2	13	1	2	3	4	4	8	1	4	5
South	...	...	...	...	...	...	...	...	...	...	1	1	...	1	1	...	1	1	...	1	1	...	...	...	...	1	1	...	1	1	...	1	1	...	1	1
South-West	3	2	5	2	4	6	1	3	4	5	3	8	3	4	7	4	1	5	4	7	11	1	2	3	4	5	9	3	3	6	2	2	4	3	2	5
West	...	...	...	5	11	16	7	7	14	2	4	6	2	7	9	2	4	6	3	5	8	7	6	13	2	2	4	11	7	18	9	2	11	11	2	13
North-West	12	11	23	15	8	23	12	13	25	13	17	30	7	10	17	3	4	7	1	3	4	7	10	17	1	6	7	5	11	16	5	12	17	7	17	24
Calm	3	9	12	2	3	5	4	4	8	1	1	2	1	1	2	1	1	2	5	2	7	3	1	4	2	5	7	1	4	5	5	6	11	4	5	9
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	11			65			49			46			6			30			12			32			16			38			25			47		
Resultant { Direction	N. 48° W.			N. 66° W.			N. 60° W.			N. 64° W.			N. 36° W.			N. 85° E.			S. 52° E.			N. 25° W.			S. 68° E.			N. 64° W.			N. 76° W.			N. 65° W.		
Mean diurnal velocity of wind in miles	68·0			101·9			104·5			139·8			118·9			115·8			93·4			70·0			52·3			40·3			52·2			46·4		
Average Resultant { Percentage	39			43			44			38			2			15			31			16			8			23			42			45		
Average Resultant { Direction, 15 Years.	N. 55° W.			N. 62° W.			N. 55° W.			N. 57° W.			N. 66° W.			S. 84° E.			S. 61° E.			S. 56° E.			N. 75° E.			N. 59° W.			N. 56° W.			N. 60° W.		
Average diurnal velocity of wind in miles, 11-13 Years.	68·5			101·8			104·3			107·6			121·1			120·7			98·9			88·4			74·9			48·1			45·0			54·6		

27.—AGRA (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	...	2	1	...	1	1	1	2	2	...	2	1	...	1	1	1	2
North-East	1	3	4	1	2	3	2	3	5	...	...	...	...	4	4	1	5	6
East	5	8	13	4	2	6	5	3	8	2	1	3	1	1	2	4	1	5
South-East	5	3	8	4	1	5	3	1	4	1	...	1	2	...	2	1	2	3
South	4	...	4	2	...	2	1	2	3	3	1	4	...	4	4	2	...	2
South-West	5	3	8	2	4	6	3	2	5	4	4	8	7	6	13	1	6	7
West	4	10	14	7	10	17	8	16	24	11	9	20	14	5	19	16	4	20
North-West	2	4	6	4	9	13	3	3	6	2	15	17	6	11	17	3	11	14
Calm	3	...	3	3	...	3	5	...	5	5	...	5	...	...	...	1	...	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	11			34			28			57			55			41		
Resultant Direction	S. 21° W.			N. 82° W			N. 89° W.			N. 84° W.			N. 88° W.			N. 73° W.		
Mean diurnal velocity of wind in miles	63·7			69·5			106·4			102·9			146·3			124·2		
Average Resultant Percentage (15 Years.)	35			38			39			44			30			28		
Average Resultant Direction (15 Years.)	N. 64° W.			N. 75° W.			N. 70° W.			N. 84° W.			N. 72° W.			N. 60° W.		
Average diurnal velocity of wind in miles (11 Years.)	81·4			95·2			109·6			116·0			145·7			136·6		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	1	2	3	...	1	1	1	...	1	4	...	4	5	...	5
North-East	3	1	4	...	2	2	...	2	2	...	...	...	2	3	5	1	3	4
East	7	5	12	8	6	14	10	7	17	1	1	2	2	3	5	2	...	2
South-East	2	5	7	2	2	4	1	1	2	2	...	2	2	...	2	1	2	3
South	2	5	7	...	...	...	1	...	1	3	...	3	...	...	...	2	2	4
South-West	4	10	14	4	12	16	...	1	1	3	4	7	1	...	1	...	...	...
West	6	...	6	11	4	15	8	9	17	13	14	27	10	6	16	14	22	36
North-West	2	4	6	3	3	6	10	9	19	7	12	19	9	18	27	4	2	6
Calm	4	1	5	2	...	2	...	...	..	1	...	1	...	...	...	2	...	2
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	22			22			28			68			59			55		
Resultant Direction	S. 2° W.			S. 66° W.			N. 42° W.			N. 83° W.			N. 47° W.			N. 80° W.		
Mean diurnal velocity of wind in miles	132·0			125·5			98·8			92·3			85·2			78·5		
Average Resultant Percentage (15 Years.)	13			10			13			40			36			28		
Average Resultant Direction (15 Years.)	N. 63° E.			S. 22° E.			N. 26° W.			N. 78° W.			N. 81° W.			N. 64° W.		
Average diurnal velocity of wind in miles (10-11 Years.)	119·9			106·6			97·3			71·8			60·5			60·8		

28.—LUCKNOW (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	2	1	1	4	1	2	3	2	8	6	5	3	4	18	...	1	..	...	1	1	1	1	3	6	...	2	1	3	6
North-East	...	2	2	1	5	...	...	...	1	1	1	4	2	1	8	3	3	1	3	10	4	6	2	2	14	3	4	4	4	15
East	1	2	1	2	6	...	...	...	...	...	...	1	2	1	4	2	3	1	1	7	2	6	1	4	13	8	8	12	10	38
South-East	2	1	1	...	4		...	...	...	...	...	1	2	1	4	...	1	3	...	4	3	3	2	...	8	4	5	1	3	13
South	...	1	..	...	1	..	1	...	1	2	...	...	1	...	1	...	...	...	2	2	...	...	2	2	4	3	4	1	1	9
South-West	..	3	3	...	6	2	3	4	...	9	2	5	4	1	12	...	2	1	...	3	4	4	3	1	12	1	3	1	..	5
West	1	5	9	2	17	6	7	8	6	27	7	8	11	8	34	13	13	16	15	57	7	6	16	9	38	...	2	3	2	7
North-West	2	7	9	1	19	3	8	10	2	23	6	7	5	6	24	9	7	7	8	31	5	5	4	4	18	3	2	6	1	12
Calm	25	8	5	24	62	16	7	3	16	42	9	...	1	9	19	3	...	1	1	5	5	...	...	6	11	8	...	1	6	15
Variable	...	...	...	...	...	...	...	..	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	21					46					44					57					26					32				
Resultant Direction	N. 60° W.					N. 71° W.					N. 59° W.					N. 70° W.					N. 71° W.					N. 85° E.				
Mean diurnal velocity of wind in miles	38·2					76·7					109·4					136·9					120·8					102·1				
Average Resultant Percentage (10-15 Years.)	49					53					62					44					15					12				
Average Resultant Direction (10-15 Years.)	N. 66° W.					N. 64° W.					N. 58° W.					N. 53° W.					N. 15° E.					N. 63° E.				
Average diurnal velocity of wind in miles (10-12 Years.)	48·9					64·7					87·0					90·4					93·4					97·4				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	4	3	5	4	16	4	7	6	4	21	3	3	13	5	24	7	11	14	5	37	3	9	8	3	23	1	1	4	3	9
North-East	4	3	3	2	12	...	2	3	2	7	1	...	...	1	2	...	...	...	...	...	1	4	2	...	7	1	2	...	1	4
East	4	7	6	2	19	4	6	5	5	20	1	2	3	1	7	...	...	...	...	...	...	...	...	...	...	1	1	2	2	6
South-East	3	2	3	..	8	1	...	1	...	2	2	3	3	3	11	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	1	2	1	2	6	...	...	...	1	1	..	...	1	...	1	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...
South-West	5	5	3	4	17	4	3	2	...	9	...	...	...	...	..	2	2	2	1	7	1	...	1	...	2	...	...	...	...	...
West	2	5	5	4	16	5	6	5	5	21	...	1	2	...	3	1	2	2	1	6	7	8	10	7	32	1	1	4	2	8
North-West	2	2	5	3	12	4	6	6	3	19	4	6	8	4	22	6	10	11	5	32	4	4	5	5	18	1	...	9	2	12
Calm	6	2	.	10	18	9	1	3	11	24	19	15	...	16	50	15	6	2	18	41	14	5	4	15	38	26	26	12	21	85
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	8					27					27					51					47					18				
Resultant Direction	N. 20° W.					N. 25° W.					N. 4° W.					N. 32° W.					N. 46° W.					N. 21° W.				
Mean diurnal velocity of wind in miles	107·7					95·2					48·2					39·6					47·7					20·8				
Average Resultant Percentage (10 Years)	25					18					10					38					57					57				
Average Resultant Direction (10 Years)	S. 55° E.					S. 51° E					S. 89° E.					N. 30° W.					N. 53° W.					N. 48° W.				
Average diurnal velocity of wind in miles (11-12 Years.)	92·9					66·0					63·4					41·2					27·9					31·6				

29.—GORAKHPUR (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	...	1	1	...	1	1	..	...	...	1	...	1	..	1	1	...	...	...	...	...	...	...	...	...	1	...	1	1	...	1	...	...	...
North-East	...	1	1	...	1	1	1	1	2	1	1	2	1	2	3	3	2	5	1	...	1	1	...	1	3	1	4	1	1	2	1	...	1	1	1	2
East	4	3	7	3	3	6	4	3	7	10	8	18	20	7	27	15	13	28	13	14	27	11	11	22	15	15	30	6	6	12	3	6	9	3	4	7
South-East	3	1	4	2	...	2	1	...	1	3	2	5	4	4	8	7	7	14	10	8	18	7	9	16	9	10	19	4	3	7	1	...	1	2	2	4
South	...	...	...	...	2	2	...	...	...	...	...	...	...	...	...	1	1	2	...	2	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	6	7	13	1	1	2	2	1	3	1	...	1	...	2	2	.	1	1	...	1	1	3	1	4	...	...	...	3	2	5	1	1	2	2	1	3
West	15	16	31	18	15	33	19	21	40	11	15	26	4	13	17	4	5	9	5	4	9	8	10	18	1	2	3	11	15	26	17	17	34	17	19	36
North-West	3	2	5	4	5	9	4	4	8	4	4	8	1	3	4	...	...	...	2	2	4	1	...	1	2	2	4	5	4	9	6	6	12	6	4	10
Calm	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	55			59			63			16			22			55			49			29			69			28			57			55		
Resultant Direction	S. 78° W.			N. 84° W.			N. 82° W.			N. 73° W.			S. 85° E.			S. 76° E.			S. 67° E.			S. 44° E.			S. 79° E.			N. 89° W.			N. 76° W.			N. 84° W.		
Mean diurnal velocity of wind in miles	49·1			79·9			102·4			107·4			104·0			72·0			77·5			67·7			59·9			30·6			35·0			23·3		
Average Resultant Percentage (15 Years.)	45			44			39			22			28			52			52			38			32			17			47			52		
Average Resultant Direction (15 Years.)	S. 85° W.			N. 84° W.			N. 81° W.			N. 67° W.			S. 82° E.			S. 74° E.			S. 69° E.			S. 62° E.			S. 70° E.			N. 83° W.			N. 79° W.			N. 86° W.		
Average diurnal velocity of wind in miles (3·5 Years.)	?			57·3			90·5			93·5			99·0			88·4			73·5			66·4			54·7			30·5			23·0			19·9		

30.—JHANSI (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	2	2	4	1	5	2	1	3	...	3	3	1	1	2	..	1	1	1	...	1	...	1	1	1	1	2	...	2	2	2	2	4	1	1	2
North-East	10	12	22	12	11	23	8	7	15	8	1	9	3	1	4	2	3	5	5	5	10	8	11	19	7	6	13	6	6	12	9	6	15	5	6	11
East	4	2	6	3	1	4	2	1	3	2	...	2	...	...	...	2	1	3	2	1	3	1	...	1	1	1	2	2	2	4	1	...	1	...	1	1
South-East	6	2	8	4	...	4	4	...	4	5	...	5	1	1	2	4	5	9	5	4	9	1	...	1	5	4	9	5	3	8	1	1	2	3	...	3
South	2	1	3	..	2	2	3	1	4	2	2	4	6	4	10	5	1	6	4	4	8	4	2	6	...	...	...	1	...	1	3	1	4	3	1	4
South-West	2	3	5	1	2	3	5	14	19	8	9	17	12	15	27	11	11	22	11	12	23	10	11	21	7	3	10	3	2	5	10	3	13	10	3	13
West	...	...	...	...	...	...	2	3	5	2	4	6	4	2	6	2	2	4	2	3	5	2	3	5	1	4	5	...	2	2	...	2	2	...	2	2
North-West	2	9	11	3	11	14	2	4	6	2	11	13	3	7	10	4	6	10	1	2	3	5	3	8	5	8	13	5	10	15	1	12	13	3	12	15
Calm	5	...	5	1	...	1	3	...	3	1	...	1	1	...	1	...	...	...	...	...	...	...	...	...	3	3	6	9	4	13	3	3	6	6	5	11
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	33			48			11			26			54			36			35			17			13			18			19			19		
Resultant Direction	N. 50° E.			N. 25° E.			S. 69° W.			S. 86° W.			S. 56° W.			S. 40° W.			S. 19° W.			S. 82° W.			N. 28° W.			N. 10° E.			N. 39° W.			N. 65° W.		
Mean diurnal velocity of wind in miles	Not recorded.																																			
Average Resultant Percentage (14-15 Years.)	26			12			7			28			22			17			26			22			21			19			21			26		
Average Resultant Direction (14-15 Years.)	N. 34° E.			N.			N. 80° W.			S. 78° W.			N. 81° W.			S. 76° W.			S. 49° W.			S. 64° W.			N. 50° W.			N. 30° W.			N. 1° E.			N. 26° E.		
Average diurnal velocity of wind in miles (3·5 Years.)	47·4			64·8			77·2			107·0			128·6			145·9			96·3			85·0			83·7			61·8			40·8			54·2		

31.—ALLAHABAD (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	2	5	1	8	...	2	4	...	6	...	1	2	1	4
North-East	2	4	4	2	12	1	3	1	...	5	2	6	4	...	12
East	2	4	3	1	10	...	1	1	...	2	...	2	3	2	7
South-East	...	3	1	1	5	...	2	...	...	2	...	2	...	1	3
South	...	1	...	...	1	...	2	...	...	2	...	2	...	...	2
South-West	...	2	3	1	6	3	4	...	1	8	1	3	1	1	6
West	...	1	...	...	1	...	5	3	...	8	...	6	4	...	10
North-West	2	9	9	...	20	1	7	12	1	21	2	6	14	2	24
Calm	25	5	6	25	61	23	2	7	26	58	26	3	3	24	56
Variable	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	18					24					20				
Resultant Direction	N. 7° E.					N. 55° W.					N. 33° W.				
Mean diurnal velocity of wind in miles	35·1					51·7					73·0				
Average Resultant (10 Years) Percentage	23					33					41				
Average Resultant (10 Years) Direction	N. 46° W.					N. 72° W.					N. 74° W.				
Average diurnal velocity of wind in miles (8-9 Years)	40·4					56·1					59·3				

	APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North		...	1	1	2	...	1	1	...	2	...	...	3	...	3
North-East	4	3	5	2	14	4	2	4	2	12	4	6	10	6	26
East	...	2	1	...	3	2	2	1	2	7	6	5	4	4	19
South-East	2	2	...	...	4	3	4	...	...	7	...	1	1	2	4
South	...	...	...	...	...	...	1	...	...	1	1	...	...	...	1
South-West	...	3	...	...	3	2	2	1	2	7	1	4	1	...	6
West	...	4	2	...	6	3	7	3	...	13	...	4	...	...	4
North-West	3	15	19	...	37	3	10	20	1	34	...	3	5	...	8
Calm	21	1	2	27	51	14	2	1	24	41	18	7	6	18	49
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	32					26					27				
Resultant Direction	N. 29° W.					N. 42° W.					N. 54° E.				
Mean diurnal velocity of wind in miles	69·5					82·4					72·6				
Average Resultant (10 Years) Percentage	25					18					17				
Average Resultant (10 Years) Direction	N. 57° W.					N. 30° W.					N. 36° W.				
Average diurnal velocity of wind in miles (8-9 Years)	70·2					81·7					79·6				

	JULY.					AUGUST.					SEPTEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	2	2	...	4	...	...	3	...	3	...	...	4	...	4
North-East	4	5	2	2	13	5	3	6	3	17	3	4	7	2	16
East	2	6	5	2	15	2	7	1	2	12	1	6	4	2	13
South-East	...	...	3	1	4	1	...	2	1	4	2	1	...	...	3
South	...	..	1	1	2	1	...	1	1	3	...	...	...	...	...
South-West		2		6	19	6	6	4	3	19	2	6	2	2	12
West	4	2	1	...	7	...	2	2	...	4	...	...	...	...	...
North-West	2	10	8	...	20	1	7	6	1	15	...	3	1	...	4
Calm	13	4	4	18	39	14	6	6	20	46	22	10	12	24	68
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..
Resultant Percentage	10					5					14				
Resultant Direction	N. 40° W.					N. 11° W.					N. 64° E.				
Mean diurnal velocity of wind in miles	100·2					85·5					52·5				
Average Resultant (10 Years) Percentage	2					6					12				
Average Resultant (10 Years) Direction	N. 47° E.					N. 32° E.					N.				
Average diurnal velocity of wind in miles (9-10 Years)	89·3					75·3					63·9				

	OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	1	6	...	7	...	..	2	...	2	...	...	2	...	2
North-East	...	2	4	...	6	...	1	6	...	7	3	3	6	...	12
East	...	...	...	1	1	1	...	1	...	2	2	2	3	2	9
South-East	...	2	3	...	5	2	1	1	...	4	2	1	1	...	4
South	...	1	...	1	2	...	1	...	...	1	...	...	...	...	...
South-West	...	3	4	...	7	...	7	1	...	8	...	7	1	...	8
West	...	2	...	...	2	...	...	1	...	1	...	2	3	...	5
North-West	...	5	4	...	10	...	5	2	...	7	...	8	6	...	14
Calm	30	15	10	29	84	27	15	16	30	88	24	8	9	29	70
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	16					30					27				
Resultant Direction	N. 50° W.					N. 76° W.					N. 67° W.				
Mean diurnal velocity of wind in miles	33·1					26·1					28·4				

32.—BENARES (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	..	1	...	2	2	...	...	...	...	1	1	...	4	4	...	5	5	...	1	1	...	...	...	...	1	1	...	1	1	...	1	1	...	1	1
North-East	3	4	7	2	1	3	3	3	6	5	2	7	4	2	6	7	7	14	3	3	6	2	5	7	1	4	5	...	3	3	...	1	1	...	4	4
East	4	2	6	1	...	1	1	2	3	2	...	2	3	1	4	7	2	9	7	8	15	9	8	17	8	5	13	2	1	3	4	4	8	...	...	...
South-East	1	1	·2	2	...	2	1	1	2	...	...	...	1	...	1	1	2	3	1	...	1	...	1	1	1	1	2	...	...	...	3	..	3	1	...	1
South	1	...	1	1	...	1	3	2	5	1	...	1	1	...	1	...	...	...	3	1	4	2	...	2	...	1	1	...	...	...	...	1	1	1	...	1
South-West	6	2	8	7	2	9	5	1	6	6	2	8	1	3	4	4	1	5	6	5	11	3	2	5	5	2	7	7	5	12	4	...	4	4	1	5
West	7	18	25	11	17	28	13	17	30	11	19	30	14	13	27	1	3	4	6	5	11	10	12	22	5	7	12	9	9	18	10	18	28	14	15	29
North-West	2	..	2	...	1	1	2	...	2	...	3	3	4	5	9	2	5	7	1	3	4	1	1	2	...	2	2	2	2	4	...	...	...	...	4	4
Calm	6	4	10	4	5	9	3	5	8	5	3	8	3	2	5	8	5	13	4	5	9	4	2	6	10	7	17	11	10	21	9	5	14	11	6	17
Variable	...	..	...	..	...	...	...	...	...	..	...	...	..	..	...	..	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	32			55			44			51			48			28			8			7			2			39			34			51		
Resultant Direction	S. 88° W.			S. 85° W.			S. 80° W.			N. 87° W.			N. 70° W.			N. 31° E.			S. 21° W.			N. 88° W.			S. 16° W.			S. 84° W.			S. 78° W.			N. 87° W.		
Mean diurnal velocity of wind in miles.	81·8			94·7			126·8			107·9			142·3			174·8			126·7			119·5			87·5			71·7			69·0			65·3		
Average Resultant Percentage (15 Years.)	29			40			49			44			23			10			9			11			3			32			42			47		
Average Resultant Direction (15 Years.)	N. 78° W.			N. 88° W.			N. 88° W.			N. 80° W.			N. 43° W.			N. 56° W.			S. 1° W.			S. 49° E.			S. 70° E.			N. 79° W.			N. 84° W.			N. 83° W.		
Average diurnal velocity of wind in miles (12-13 Years.)	68·1			89·6			108·2			112·4			118·6			120·1			111·6			98·4			92·8			59·0			49·0			54·5		

33.—GHAZIPUR (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	1	2	...	...	...	Not recorded.			...	...	...	..	1	1	1	1	2	...	...	...	...	1	1	...	...	...	1	...	1	2	...	2	...	...	...
North-East	...	...	...	...	...	...				...	2	2	2	1	3	...	3	3	...	1	1	...	3	3	1	4	5	...	1	1	...	...	...	1	...	1
East	4	3	7	1	1	2				7	5	12	18	4	22	14	6	20	10	12	22	12	11	23	13	11	24	7	2	9	9	2	11	5	1	6
South-East	2	2	4	1	...	1				1	...	1	2	1	3	2	3	5	4	4	8	3	...	3	5	3	8	5	4	9	2	1	3	2	1	3
South	...	1	1	...	...	...				...	...	...	...	...	...	1	...	1	1	...	1	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...
South-West	5	...	5	4	..	4				6	...	6	1	...	1	2	...	2	4	2	6	2	1	3	1	2	3	...	1	1	2	1	3	2	...	2
West	11	16	27	17	19	36				14	19	33	4	16	20	1	4	5	7	6	13	11	12	23	8	7	15	16	20	36	13	14	27	15	14	29
North-West	...	1	1	1	2	3				1	3	4	2	7	9	1	2	3	2	3	5	...	1	1	...	1	1	1	2	3	1	2	3	1	3	4
Calm	8	7	15	4	6	10				1	1	2	2	1	3	8	11	19	3	3	6	3	2	5	2	2	4	...	1	1	1	10	11	5	12	17
Variable	...	...	.	...	...	...				...	...	...	...	...	...	...	...	...	...	...	...	..	..	..	..	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	35			68			?			43			11			29			14			2			26			37			30			39		
Resultant Direction	S. 78° W.			S. 88° W.			?			S. 88° W.			N. 7 W.			N. 89° E.			S. 49° E.			S. 74° E.			S. 77° E.			S. 79° W.			W.			W.		
Mean diurnal velocity of wind in miles	36·5			47·4			70·1			86·2			81·6			63·8			72·1			64·1			55·5			34·0			27·8			23·0		
Average Resultant Percentage (Years.)	...			...			..			...			...			...			...			...			...			...			...			...		
Average Resultant Direction (Years.)	...			...			...			...			...			...			...			...			...			...			...			...		
Average diurnal velocity of wind in miles (Years.)	...			...			...			...			...			...			...			...			...			...			...			...		

34.—SIBSAGAR (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	3	4	...	3	3	...	...	...	1	1	2	1	2	3	...	1	1
North-East	10	16	26	11	15	26	21	26	47	18	20	38	15	14	29	12	16	28
East	7	4	11	2	1	3	4	...	4	2	...	2	2	...	2	4	...	4
South-East	6	1	7	3	2	5	5	...	5	6	6	12	4	2	6	3	2	5
South	...	1	1	3	...	3	...	...	...	...	...	...	...	2	2	1	...	1
South-West	6	5	11	7	5	12	1	3	4	2	1	3	9	11	20	10	11	21
West	...	...	...	1	...	1	...	...	...	...	1	1	...	...	...	...	...	...
North-West	1	...	1	...	2	2	...	2	2	...	...	...	...	...	...	...	...	...
Calm	...	1	1	1	...	1	...	...	...	1	1	2	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	44			29			74			65			21			21		
Resultant Direction	N. 70° E.			N. 61° E.			N. 52° E.			N. 62° E.			N. 76° E.			N. 84° E.		
Mean diurnal velocity of wind in miles	45·2			54·9			66·5			71·0			69·9			64·9		
Average Resultant Percentage (8-10 Years.)	46			54			56			51			34			14		
Average Resultant Direction (8-10 Years.)	N. 65° E.			N. 63° E.			N. 61° E.			N. 61° E.			N. 57° E.			S. 83° E.		
Average diurnal velocity of wind in miles. 10 Years.	41·1			53·4			71·6			70·4			70·6			64·3		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	...	1	1	1	4	5	1	...	1	1	...	1	2	1	3
North-East	6	9	15	5	9	14	12	10	22	25	24	49	21	25	46	14	18	32
East	...	...	...	6	4	10	2	2	4	1	1	2	4	3	7	6	6	12
South-East	7	5	12	7	2	9	7	7	14	3	3	6	3	...	3	2	...	2
South	2	...	2	2	...	2	1	...	1	...	1	1	...	1	1	...	1	1
South-West	12	14	26	7	15	22	5	4	9	1	1	2	...	...	...	1	1	2
West	..	...	...	3	..	3	...	...	...	...	...	...	...	...	...	...	...	...
North-West	3	3	6	1	...	1	2	3	5	...	...	...	...	...	...	1	...	1
Calm	...	...	...	...	...	...	...	...	...	...	1	1	1	1	2	5	4	9
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	22			23			35			79			86			66		
Resultant Direction	S. 15° W.			S. 30° E.			N. 71° E.			N. 54° E.			N. 54° E.			N. 56° E.		
Mean diurnal velocity of wind in miles	65·5			59·8			61·7			41·8			41·6			33·9		
Average Resultant Percentage (10 Years.)	8			7			17			50			65			58		
Average Resultant Direction (10 Years.)	S. 11° W.			S. 57° W.			N. 66° E.			N. 66° E.			N. 64° E.			N. 67° E.		
Average diurnal velocity of wind in miles. 10 Years.	69·6			65·1			61·2			45·5			36·2			34·1		

35.—DHUBRI (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	1	...	1	2	4	3	1	1	1	6	2	1	...	1	4	3	2	1	2	8	2	3	1	1	7	...	2	...	...	2
North-East	11	12	10	11	44	2	12	1	1	16	2	8	3	3	16	7	12	8	7	34	6	11	7	6	30	8	8	2	3	21
East	8	13	9	4	34	1	3	2	1	7	7	10	...	2	19	8	12	6	9	35	8	10	10	9	37	8	10	10	7	35
South-East	1	3	...	...	4	2	3	1	1	7	1	2	...	1	4	1	1	2	1	5	1	1	...	1	3	2	2	4	5	13
South	...	...	1	...	1	...	3	1	1	5	2	1	2	1	6	1	1	4	2	8	...	1	3	2	6	3	1	6	4	14
South-West	5	2	4	4	15	12	3	16	10	41	14	7	15	16	52	4	2	5	1	12	2	3	5	3	13	4	4	5	...	13
West	1	...	2	3	6	3	1	3	3	10	...	1	6	3	10	...	...	2	1	3	1	...	1	...	2	...	...	1	...	1
North-West	2	1	...	1	4	3	...	2	1	6	...	1	5	2	8	2	...	1	4	7	2	...	...	1	3	1	2	1	...	4
Calm	2	...	4	6	12	2	2	1	9	14	3	...	...	2	5	3	...	...	2	5	4	...	2	5	11	4	1	1	11	17
Variable	...	...	..	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	43					24					25					42					44					40				
Resultant { Direction	N. 64° E.					S. 49° W.					S. 38° W.					N. 70° E.					N. 75° E.					S. 75° E.				
Mean diurnal velocity of wind in miles	113·9					69·4					143·1					166·3					193·0					120·9				
Average Resultant { Percentage						?					?					38					48					31				
Average Resultant { Direction (3 Years.)	?					?					?					N. 86° E.					N. 78° E.					S. 79° E.				
Average diurnal velocity of wind in miles (3 Years.)	?					?					?					175·4					174·1					109·2				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	2	2	1	5	...	5	...	...	5	1	3	2	1	7	4	1	4	2	11	6	2	3	6	17	4	2	...	2	8
North-East	2	8	3	5	18	5	8	1	1	15	4	7	4	1	16	12	13	10	6	41	11	12	9	7	39	12	5	10	8	35
East	5	4	3	2	14	5	7	4	4	20	2	7	5	4	18	4	8	1	2	15	4	11	9	4	28	8	18	13	9	48
South-East	4	4	...	3	11	1	4	1	4	10	5	3	2	1	11	1	...	...	...	1	...	1	1	...	2	...	4	2	...	6
South	4	4	9	6	23	1	1	3	5	10	4	2	3	3	12	...	...	2	...	2	1	2	1	...	4	...	...	...	...	...
South-West	11	7	11	5	34	4	5	13	5	27	4	6	7	5	22	1	4	4	3	12	4	2	4	2	12	...	...	1	...	1
West	...	1	1	...	2	...	1	1	2	4	...	...	2	1	3	...	1	3	2	6	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	3	1	4	2	10	1	...	...	...	1	2	...	...	1	3	...	1	1	1	3
Calm	5	1	2	9	17	13	...	7	8	28	7	1	1	12	21	7	2	5	15	29	2	...	3	10	15	5	1	4	10	20
Variable	...	..	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	31					21					13					35					47					66				
Resultant { Direction	S. 13° E.					S. 35° E.					S. 49° E.					N. 45° E.					N. 55° E.					N. 68° E.				
Mean diurnal velocity of wind in miles	76·1					67·3					61·2					73·5					114·5					151·2				
Average Resultant { Percentage	26					20					18					41					61					58				
Average Resultant { Direction (3 Years.)	S. 70° E.					S. 36° E.					S. 70° E.					N. 51° E.					N. 59° E.					N. 67° E.				
Average diurnal velocity of wind in miles (3 Years.)	88·0					71·8					69·2					91·3					117·8					105·5				

TABLE IX.—DIRECTION AND MEAN MOVEMENT OF WINDS IN 1883.

36.—TURA (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	The observatory opened in June.															...	...	...
North-East																...	...	...
East																2	1	3
South-East																7	11	18
South																7	8	15
South-West																10	3	*13
West																...	...	...
North-West																...	1	1
Calm																...	4	4
Variable																...	...	...
Resultant Percentage	...			...			...			...			...			68		
Resultant Direction	...			...			...			...			...			S. 9° E.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...		
Average Resultant Percentage (Years.)	...			...			...			...			...			...		
Average Resultant Direction (Years.)	...			...			...			...			...			...		
Average diurnal velocity of wind in miles (Years.)	...			...			...			...			...			...		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	2	3	...	1	1	...	1	1	1	...	1	...	2	2	1	2	3
North-East	1	1	2	1	2	3	2	2	4	...	3	3	2	2	4	2	3	5
East	...	3	3	...	12	12	1	2	3	6	13	19	6	7	13	6	11	17
South-East	2	5	7	3	3	6	2	7	9	4	5	9	11	8	19	7	5	12
South	15	15	30	13	7	20	11	13	24	10	5	15	7	3	10	7	5	12
South-West	10	5	15	12	5	17	12	5	17	9	2	11	4	7	11	7	4	11
West	...	...	...	1	1	2	2	...	2	1	1	2	...	1	1	1	1	2
North-West	...	...	...	1	...	1	...	...	...	...	2	2	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	69			53			64			48			48			47		
Resultant Direction	S. 2° W.			S. 6° E.			S. 3° W.			S. 34° E.			S. 45° E.			S. 42° E.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...		
Average Resultant Percentage (Years.)	...			...			...			...			...			...		
Average Resultant Direction (Years.)	...			...			...			...			...			...		
Average diurnal velocity of wind in miles (Years.)	...			...			...			...			...			...		

37.—SILCHAR (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	1	1	...	3	3	...	...	...	...	3	3	...	...	..	2	1	3	...	1	1	...	3	3	...	2	2
North-East	1	...	1	2	...	2	3	...	3	1	2	3	3	1	4	2	1	3	3	...	3	1	1	2	5	...	5	2	...	2	2	3	5	4	1	5
East	6	...	6	8	1	9	8	1	9	8	2	10	12	5	17	4	1	5	1	...	1	2	...	2	4	1	5	11	1	12	12	...	12	11	3	14
South-East	8	3	11	6	...	6	2	...	2	5	...	5	3	3	6	2	4	6	2	1	3	3	1	4	3	1	4	5	...	5	7	1	8	7	2	9
South	1	3	4	2	2	4	...	4	4	...	1	1	...	2	2	1	...	1	1	...	1	2	1	3	2	2	4	3	1	4	3	1	4	2	...	2
South-West	...	5	5	...	11	11	...	8	8	1	2	3	...	1	1	...	4	4	...	2	2	1	2	3	2	2	4	2	1	3	1	2	3	...	2	2
West	...	4	4	...	7	7	...	6	6	1	2	3	...	6	6	..	3	3	2	6	8	1	10	11	1	10	11	...	10	10	...	5	5	...	2	2
North-West	...	...	...	...	...	...	...	1	1	...	5	5	1	4	5	...	6	6	...	6	6	1	7	8	1	9	10	...	6	6	...	1	1	...	...	...
Calm	15	16	31	10	7	17	18	11	29	14	15	29	12	6	18	21	11	32	22	13	35	20	9	29	10	4	14	8	11	19	5	14	19	7	19	26
Variable	...	...	..	..	..	...	..	..	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	25			26			13			12			23			4			16			20			17			5			24			34		
Resultant { Direction	S. 25° E.			S.			S. 1° E.			E.			N. 80° E.			S. 37° E.			N. 60° W.			S. 86° W.			N. 68° W.			S. 11° E.			S. 71° E.			S. 78° E.		
Mean diurnal velocity of wind in miles	44·0			56·3			60·7			82·5			108·8			64·8			66·2			64·1			71·0			55·3			46·9			48·8		
Average Resultant { Percentage	27			25			22			21			10			9			3			7			2			9			30			35		
Average Resultant { Direction, 14-15 Years.	S. 29° E.			S. 33° E.			S. 60° E.			S. 86° E.			N. 75° E.			N. 58° E.			N. 6° W.			S. 63° W.			S. 89° W.			S. 56° E.			S. 77° E.			S. 57° E.		
Average diurnal velocity of wind in miles, 12-13 Years.	48·4			65·3			75·9			81·3			82·8			75·4			75·8			73·3			64·6			52·4			49·8			45·3		

38.—DARJEELING (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	5	...	5	...	...	...	1	...	1	3	1	4	...	...	...	...	...	...	...	...	...	2	...	2	3	...	3	...	...	...
North-East	3	...	3	5	...	5	3	...	3	5	...	5	1	1	2	6	2	8	4	1	5	5	...	5	7	1	8	8	2	10	8	2	10	8	...	8
East	7	...	7	4	2	6	6	1	7	1	...	1	2	...	2	10	8	18	18	12	30	17	16	33	6	7	13	4	...	4	5	2	7	7	1	8
South-East	2	...	2	3	...	3	...	...	...	1	...	1	...	...	...	...	1	1	2	5	7	2	2	4	2	5	7	...	...	...	1	1	2	1	1	2
South	...	..	...	1	...	1	1	1	2	...	...	...	1	...	1	...	1	1	...	1	1	1	...	1	1	1	2	...	...	...	...	...	...	2	1	3
South-West	3	5	8	...	3	3	4	5	9	3	8	11	10	2	12	...	4	4	...	1	1	...	3	3	6	4	10	1	12	13	1	6	7	1	5	6
West	1	11	12	8	17	25	10	19	29	11	15	26	9	18	27	3	7	10	5	8	13	2	3	5	5	6	11	5	9	14	1	9	10	...	9	9
North-West	1	2	3	1	3	4	...	...	...	1	...	1	...	3	3	1	...	1	1	...	1	...	1	1	..	...	...	2	...	2	2	1	3	...	1	1
Calm	14	13	27	6	2	8	2	...	2	6	4	10	6	1	7	7	4	11	1	2	3	4	6	10	3	3	6	9	...	9	8	7	15	12	13	25
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	16			33			46			54			63			21			40			51			18			25			11			4		
Resultant { Direction	S. 73° W.			N. 87° W.			S. 87° W.			S. 82° W.			S. 82° W.			N. 62° E.			S. 84° E.			S. 87° E.			S. 34° E.			N. 85° W.			N. 15° W.			S. 26° E.		
Mean diurnal velocity of wind in miles	50·0			140·5			204·9			191·4			169·6			102·8			68·9			69·0			95·5			78·6			53·7			40·7		
Average Resultant { Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Average Resultant { Direction, Years.	...			...			...			...			...			...			...			...			...			...			...			...		
Average diurnal velocity of wind in miles, Years.	...			...			...			...			...			...			...			...			...			...			...			...		

39.—PURNEAH (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	1	3	1	...	1	5	1	6	3	...	3	1	1	2	2	...	2	...	...	...	...	...	...	1	...	1	...	1	1	1	1	2	..	1	1
North-East	4	5	9	...	...	...	3	...	3	1	3	4	6	7	13	2	2	4	2	.	2	...	1	1	2	3	5	1	...	1	1	...	1	6	...	6
East	2	3	5	...	...	...	4	1	5	16	12	28	20	16	36	16	18	34	15	9	24	11	8	19	9	8	17	2	...	2	1	...	1	...	1	1
South-East	...	...	...	...	...	...	...	...	...	2	1	3	1	1	2	1	2	3	1	2	3	2	2	4	2	1	3	...	...	...	1	...	1	...	...	...
South	2	1	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	3	2	5	1	...	1	1	1	2	...	...	...	...	...	...
South-West	...	1	1	1	3	4	...	1	1	1	1	2	...	...	...	...	...	...	1	2	3	1	1	2	1	3	4	2	...	2	2	2	4	1	...	1
West	12	13	25	17	23	40	12	24	36	6	12	18	1	3	4	...	2	2	...	1	1	2	2	4	1	...	1	1	1	2	2	6	8	3	4	7
North-West	4	5	9	7	1	8	4	3	7	1	1	2	1	3	4	3	2	5	...	1	1	...	...	...	1	...	1	2	3	5	5	1	6	3	1	4
Calm	4	2	6	2	1	3	3	1	4	...	...	...	1	...	1	6	4	10	12	15	27	10	13	23	12	15	27	22	25	47	17	20	37	18	24	42
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	39			81			59			21			67			57			39			33			30			8			22			25		
Resultant Direction	N. 60° W.			N. 85° W.			N. 70° W.			N. 73° E.			N. 72° E.			N. 79° E.			S. 83° E.			S. 64° E.			S. 88° E.			N. 67° W.			N. 75° W.			N. 35° W.		
Mean diurnal velocity of winds in miles	49·4			75·9			105·7			115·8			105·8			79·6			37·7			25·4			25·4			9·4			13·6			15·1		
Average Resultant Percentage	48			56			24			11			68			72			57			54			40			13			45			60		
Average Resultant Direction	N. 83° W.			S. 89° W.			N. 84° W.			N. 62° E.			N. 89° E.			N. 89° E.			S. 77° E.			S. 77° E.			S. 78° E.			N. 14° E.			N. 60° W.			N. 70° W.		
Average diurnal velocity of wind in miles 7-9 Years.	44·1			68·5			93·9			102·1			94·7			92·6			79·3			60·1			53·9			36·9			31·5			31·6		

40.—DURBHUNGA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	1	1	2	...	...	...	...	...	...	...	2	2	...	1	1	2	2	4	1	2	3	...	1	1	1	...	1	1	1	2	2	1	3
North-East	6	1	7	...	...	...	2	1	3	3	1	4	6	3	9	7	5	12	3	3	6	4	4	8	5	2	7	3	1	4	2	1	3	1	2	3
East	4	5	9	2	...	2	6	2	8	14	9	23	17	14	31	15	13	28	12	11	23	15	9	24	16	13	29	10	9	19	1	2	3	1	2	3
South-East	5	3	8	1	1	2	3	...	3	5	7	12	6	8	14	7	6	13	10	7	17	6	8	14	7	10	17	6	8	14	4	2	6	4	3	7
South	1	1	2	...	1	1	...	1	1	...	...	...	...	...	...	1	1	2	1	3	4	...	2	2	1	1	2	...	...	...	...	1	1	1	2	3
South-West	4	5	9	9	8	17	5	5	10	2	4	6	...	1	1	...	1	1	1	3	4	2	3	5	1	1	2	...	3	3	4	4	8	4	1	5
West	8	9	17	9	13	22	11	17	28	4	7	11	...	2	2	...	...	...	...	2	2	2	2	4	...	1	1	6	6	12	8	12	20	7	13	20
North-West	3	3	6	6	4	10	4	4	8	2	2	4	2	1	3	1	3	4	2	...	2	1	1	2	...	1	1	5	4	9	10	7	17	11	7	18
Calm	...	3	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	14			68			47			30			68			70			55			50			73			18			48			43		
Resultant Direction	S. 64° W.			S. 82° W.			S. 85° W.			S. 66° E.			E.			N. 88° E.			S. 74° E.			S. 80° E.			S. 78° E.			S. 81° E.			N. 80° W.			N. 76° W.		
Mean diurnal velocity of wind in miles	57·6			87·5			105·9			131·7			157·0			132·9			112·7			102·5			92·3			40·7			49·0			46·3		
Average Resultant Percentage	50			47			22			9			59			73			55			56			54			10			53			59		
Average Resultant Direction	S. 76° W.			S. 71° W.			S. 62° W.			S. 54° E.			S. 88° E.			N 86° E.			S. 87° E.			S. 84° E.			S. 86° E.			S. 84° E.			S. 81° W.			S 79 W.		
Average diurnal velocity of wind in miles 7-8 Years.	51·9			79·3			95·5			116·7			132·7			127·9			113·1			100·4			86·0			48·4			44·0			44·6		

41.—PATNA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	...	2	2	...	5	5	...	2	2	...	7	7	...	5	5	...	1	1	...	...	...	...	1	1	...	6	6	3	4	7	...	1	1
North-East	3	1	4	1	2	3	1	2	3	5	4	9	6	7	13	6	6	12	4	5	9	4	5	9	3	6	9	2	6	8	1	3	4	3	5	8
East	5	5	10	2	...	2	2	...	2	11	6	17	14	6	20	15	9	24	11	13	24	11	8	19	16	12	28	5	2	7	1	1	2	4	2	6
South-East	2	2	4	1	...	1	3	...	3	2	..	2	6	1	7	6	3	9	7	3	10	5	4	9	4	3	7	2	2	4	...	...	...	2	2	4
South	1	1	2	1	...	1	2	...	2	...	...	..	1	...	1	...	3	3	...	3	3	1	2	3	2	...	2	5	...	5	...	...	...	1	...	1
South-West	4	1	5	8	2	10	4	1	5	6	...	6	...	...	...	...	...	...	1	1	2	1	2	3	2	2	4	10	...	10	8	...	8	3	...	3
West	11	10	21	10	12	22	12	7	19	1	7	8	...	...	...	...	...	...	5	3	8	4	6	10	2	...	2	4	4	8	8	6	14	16	10	26
North-West	4	9	13	5	10	15	7	16	23	5	11	16	4	10	14	3	4	7	3	2	5	5	3	8	1	6	7	3	9	12	9	14	23	2	11	13
Calm	1	1	2	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	1	1	...	...	...	...	2	2	...	2	2	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	31			63			58			23			51			58			40			23			49			16			62			40		
Resultant Direction	N. 76° W.			N. 80° W.			N. 64° W.			N. 5° E.			N. 50° E.			N. 75° E.			S. 89° E.			N. 88° E.			N. 85° E.			N. 57° W.			N. 57° W.			N. 64° W.		
Mean diurnal velocity of wind in miles	82·3			92·0			109·6			142·0			164·6			130·2			113·8			97·9			97·0			46·0			47·8			57·8		
Average Resultant Percentage	45			47			48			27			38			45			41			34			42			4			29			52		
Average Resultant Direction .14-15 Years.	N. 83° W.			N. 79° W.			N. 74° W.			N. 38° W.			N. 54° E.			N. 73° E.			N. 85° E.			S. 19° E.			S. 77° E.			N. 21° E.			N. 64° W.			N. 83° W.		
Average diurnal velocity of wind in miles 12-13 Years.	49·0			64·5			79·0			99·0			108·8			95·1			82·9			74·9			69·5			46·0			37·3			42·0		

42.—GYA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	1	2	...	4	4	1	3	4	1	4	5	3	2	5	1	3	4	2	...	2	2	...	2	2	2	4	...	...	...	...	...	...	...	2	2
North-East	...	2	2	1	1	2	1	2	3	3	3	6	5	7	12	5	10	15	2	2	4	4	4	8	1	1	2	...	2	2	1	...	1	1	...	1
East	1	...	1	2	1	3	1	...	1	2	1	3	3	1	4	5	1	6	9	7	16	11	11	22	9	6	15	1	...	1	..	...	...	...	...	...
South-East	4	...	4	2	...	2	3	1	4	1	...	1	1	...	1	3	...	3	1	...	1	1	...	1	2	2	4	...	...	...	...	1	1	...	...	...
South	1	...	1	1	...	1	4	...	4	1	...	1	2	1	3	2	...	2	...	2	2	2	1	3	...	...	...	1	...	1	1	...	1	1	...	1
South-West	2	1	3	1	...	1	4	1	5	3	...	3	...	...	...	1	...	1	1	3	4	1	...	1	...	1	1	1	...	1	...	...	...	2	...	2
West	6	6	12	12	7	19	10	5	15	11	6	17	10	10	20	3	4	7	8	1	9	7	5	12	4	...	4	4	1	5	9	8	17	11	7	18
North-West	1	7	8	1	9	10	4	15	19	5	14	19	2	7	9	2	1	3	3	3	6	1	3	4	...	...	...	1	...	1	2	3	5	3	6	9
Calm	15	14	29	8	6	14	3	5	8	2	1	3	5	3	8	8	11	19	5	12	17	2	7	9	12	18	30	23	28	51	17	18	35	13	16	29
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...
Resultant Percentage	24			38			45			53			34			25			8			23			24			7			32			42		
Resultant Direction	N. 78° W.			N. 66° W.			N. 72° W.			N. 53° W.			N. 39° W.			N. 37° E.			N. 44° E.			N. 65° E.			N. 83° E.			N. 84° W.			N. 82° W			N. 75° W.		
Mean diurnal velocity of wind in miles	31·2			48·1			78·1			78·5			87·4			64·2			64·7			64·4			37·6			25·0			29·3			25·1		
Average Resultant Percentage	24			35			42			33			30			24			19			23			28			4			17			29		
Average Resultant Direction 10 Years.	N. 57° W.			N. 73° W.			N. 84° W.			N. 57° W.			N. 31° E.			N. 72° E.			S. 68° E.			S. 61° E.			S. 78° E.			N. 38° W.			N. 37° W.			N. 65° W.		
Average diurnal velocity of wind in miles 11-13 Years.	38·7			59·3			74·7			81·1			84·4			76·7			65·8			59·2			52·9			35·2			29·6			31·1		

43.—HAZARIBAGH (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	6	2	3	6	17	1	...	...	4	5	1	...	...	1	2	1	...	...	2	3	5	4	...	4	13	2	1	3	4	10
North-East	9	10	10	6	35	4	6	5	3	18	2	3	...	1	6	1	2	...	5	8	8	5	1	3	17	11	3	2	4	20
East	4	7	6	4	21	3	3	4	3	13	2	2	4	1	9	4	...	...	1	5	3	2	1	1	7	...	4	1	2	7
South-East	2	2	...	1	5	2	2	4	2	10	10	4	...	1	15	10	6	...	...	16	7	15	14	6	42	4	9	7	5	25
South	2	2	1	2	7	2	1	1	1	5	10	7	11	13	41	7	7	3	3	20	1	3	6	6	16	2	2	4	1	9
South-West	4	4	5	3	16	5	7	4	5	21	1	10	10	6	27	6	10	17	13	46	1	1	3	3	8	3	6	8	7	24
West	1	2	4	2	9	5	7	8	6	26	1	2	4	3	10	1	4	8	5	18	...	...	4	2	6	...	2	4	1	7
North-West	2	1	1	2	6	2	2	2	1	7	...	1	2	2	5	...	1	2	1	4	3	...	2	4	9	5	3	1	4	13
Calm	1	1	1	5	8	4	...	...	3	7	4	1	...	3	8	...	...	...	...	...	2	...	...	2	4	3	...	...	2	5
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	28					12					50					51					30					10				
Resultant Direction	N. 46° E.					S. 72° W.					S. 8° W.					S. 31° W.					S. 57° E.					S. 29° E.				
Mean diurnal velocity of wind in miles	131·9					162·6					195·5					228·4					221·7					205·0				
Average Resultant Percentage (15 Years.)	54					60					61					49					15					19				
Average Resultant Direction (15 Years.)	N. 62° W.					N. 68° W.					N. 75° W.					N. 74° W.					S. 77° W.					S. 36° W.				
Average diurnal velocity of wind in miles (14-15 Years.)	114·4					152·0					171·9					191·4					206·3					212·4				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	3	1	2	8	4	1	...	2	7	1	1	3	2	7	1	2	...	2	5	2	...	...	1	3	2	3	3	4	12
North-East	10	9	4	9	32	6	5	2	3	16	3	4	1	1	9	8	4	4	5	21	10	4	5	8	27	7	6	9	12	34
East	1	3	8	3	15	1	5	8	1	15	...	2	2	3	7	8	5	7	9	29	6	6	9	8	29	5	4	5	4	18
South-East	1	3	6	2	12	1	3	5	1	10	1	5	6	3	15	6	10	15	9	40	8	10	11	7	36	8	9	9	5	31
South	...	...	...	...	...	1	1	...	1	3	1	...	3	...	4	...	3	3	2	8	...	5	4	1	10	2	3	1	...	6
South-West	4	8	4	3	19	1	2	2	2	7	1	2	2	1	6	1	3	...	...	4	1	3	1	...	5	...	4	1	1	6
West	2	1	5	4	12	1	3	6	2	12	4	8	8	7	27	...	1	...	...	1	...	...	...	...	...	1	1	...	1	3
North-West	4	3	2	3	12	12	11	8	10	41	14	7	5	11	37	4	3	2	1	10	...	2	...	1	3	5	1	2	1	9
Calm	6	...	1	4	11	4	...	...	9	13	5	1	...	2	8	3	...	...	3	6	3	...	...	4	7	1	...	1	3	5
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	17					28					33					50					58					41				
Resultant Direction	N. 35° E.					N. 21° W.					N. 58° W.					S. 79° E.					S. 78° E.					N. 79° E.				
Mean diurnal velocity of wind in miles	184·9					150·8					149·9					119·8					123·5					135·7				
Average Resultant Percentage (14-15 Years.)	19					7					21					34					55					64				
Average Resultant Direction (14-15 Years.)	S. 16° E.					S. 50° W.					S. 64° E.					N. 42° W.					N. 42° W.					N. 54° W.				
Average diurnal velocity of wind in miles (14-15 Years.)	203·0					179·3					165·7					119·2					100·0					107·0				

44.—BERHAMPORE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	8	10	1	3	4	1	...	1	...	1	1	...	1	1	...	2	2	...	...	...	...	...	...	...	...	...	6	4	10	13	6	19	12	11	23
North-East	2	...	2	1	...	1	...	1	1	...	3	3	1	3	4	3	2	5	3	2	5	2	2	4	1	1	2	3	...	3	2	...	2	2	1	3
East	4	...	4	1	1	2	...	...	...	6	5	11	7	5	12	9	11	20	10	11	21	6	3	9	8	12	20	1	1	2	...	1	1	...	2	2
South-East	...	...	...	...	...	...	2	1	3	4	1	5	4	3	7	1	1	2	4	2	6	5	4	9	5	...	5	2	...	2	...	1	1	...	...	...
South	...	...	...	...	1	1	1	2	3	6	3	9	10	6	16	8	8	16	4	4	8	5	5	10	6	5	11	2	1	3	...	...	...	...	...	...
South-West	2	...	2	4	2	6	9	10	19	11	2	13	6	4	10	5	2	7	6	6	12	7	5	12	3	4	7	4	2	6	...	1	1	1	1	2
West	3	6	9	4	10	14	9	13	22	3	10	13	...	1	1	...	...	...	1	2	3	1	1	2	...	...	..	...	10	10	...	2	2	...	2	2
North-West	6	7	13	5	5	10	5	2	7	...	3	3	...	3	3	...	...	...	...	...	...	...	...	...	...	...	...	2	3	5	9	6	15	9	4	13
Calm	12	10	22	12	6	18	4	2	6	...	2	2	3	5	8	4	4	8	3	4	7	5	11	16	7	8	15	11	10	21	6	13	19	7	10	17
Variable	...	...	...	..	...	...	...	...	...	..	..	..	...	...	...	.	...	...	...	..	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	38			42			64			30			39			44			39			38			45			23			52			55		
Resultant Direction	N. 36° W.			N. 74° W.			S. 72° W.			S. 25° W.			S. 23° E.			S. 50° E.			S. 45° E.			S. 19° E.			S. 48° E.			N. 60° W.			N. 19° W.			N. 14° W.		
Mean diurnal velocity of wind in miles	44·6			55·8			103·4			134·6			150·0			142·0			121·6			96·1			96·5			55·7			47·9			48·1		
Average Resultant Percentage (15 Years.)	50			44			44			32			37			48			51			45			36			16			54			62		
Average Resultant Direction (15 Years.)	N. 41° W.			N. 72° W.			S. 76° W.			S. 23° W.			S. 36° E.			S. 33° E.			S. 41° E.			S. 40° E.			S. 41° E.			N. 12° W.			N. 25° W.			N. 26° W.		
Average diurnal velocity of wind in miles. 11-14 Years.	40·4			53·8			75·5			123·1			132·5			133·0			120·6			99·1			86·3			50·2			38·9			36·1		

45.—BURDWAN (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	9	8	17	6	6	12	2	...	2	...	2	2	2	2	4	...	...	...	1	...	1	1	...	1	2	...	2	5	10	15	10	11	21	8	10	18
North-East	5	...	5	4	1	5	...	2	2	2	1	3	3	4	7	5	4	9	3	3	6	2	2	4	2	3	5	7	1	8	9	2	11	4	3	7
East	2	2	4	4	...	4	1	1	2	...	3	3	...	3	3	3	4	7	7	8	15	9	2	11	12	7	19	3	...	3	1	1	2	1	...	1
South-East	2	...	2	1	...	1	2	...	2	3	5	8	6	6	12	3	11	14	5	3	8	3	7	10	1	8	9	...	...	...	...	...	...	...	...	...
South	2	...	2	2	3	5	2	4	6	13	5	18	10	15	25	11	7	18	3	9	12	9	12	21	7	10	17	4	6	10	...	1	1	...	...	...
South-West	...	...	...	2	2	4	3	6	9	6	2	8	8	1	9	5	2	7	6	6	12	1	4	5	3	2	5	5	...	5	...	...	1	1	1	2
West	3	8	11	2	12	14	12	9	21	...	8	8	..	...	...	...	2	2	4	2	6	3	2	5	1	...	1	1	1	2	1	...	1	2	3	5
North-West	7	11	18	7	4	11	9	7	16	6	3	9	1	...	1	3	...	3	2	...	2	3	2	5	1	...	1	4	10	14	8	14	22	13	13	26
Calm	1	2	3	...	...	...	...	2	2	...	1	1	1	...	1	...	...	...	...	...	...	...	...	...	1	...	1	2	3	5	1	1	2	2	1	3
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	54			39			55			35			51			47			35			42			52			30			73			71		
Resultant Direction	N. 26° W.			N. 48° W.			N. 88° W.			S. 26° W.			S. 17° E.			S. 30° E.			S. 25° E.			S. 20° E.			S. 49° E.			N. 22° W.			N. 9° W.			N. 25° W.		
Mean diurnal velocity of wind in miles	42·1			53·6			74·2			119·5			141·0			112·0			92·1			77·9			77·8			44·0			47·4			53·2		
Average Resultant Percentage (10 Years.)	44			43			45			49			53			59			47			48			40			30			70			69		
Average Resultant Direction (10 Years.)	N. 32° W.			N. 56° W.			S. 78° W.			S. 34° W.			S. 9° E.			S. 18° E.			S. 27° E.			S. 30° E.			S. 27° E.			N. 23° E.			N. 8° W.			N. 22° W.		
Average diurnal velocity of wind in miles. 10-11 Years.	45·9			57·2			81·9			139·9			137·5			123·0			107·1			90·7			78·8			52·5			47·8			47·1		

46.—JESSORE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	4	7	8	4	12	2	2	4	...	...	...	1	2	3	...	...	...	2	4	6	...	...	...	...	1	1	5	2	7	16	6	22	12	6	18
North-East	2	1	3	1	1	2	...	1	1	1	2	3	...	...	...	1	...	1	3	2	5	...	...	...	1	1	2	3	4	7	3	6	9	4	...	4
East	2	...	2	1	...	1	...	1	1	4	...	4	2	...	2	3	3	6	6	2	8	2	1	3	4	7	11	3	5	8	...	2	2	...	1	1
South-East	1	2	3	2	...	2	...	1	1	1	3	4	4	3	7	3	7	10	7	6	13	7	7	14	7	6	13	3	4	7	1	...	1	...	1	1
South	...	...	...	3	4	7	2	3	5	7	15	23	10	24	34	13	16	29	4	12	16	16	19	35	12	13	25	...	5	5	...	1	1	...	...	...
South-West	2	...	2	1	2	3	7	1	8	4	2	6	4	2	6	4	1	5	4	1	5	1	...	1	3	2	5	...	2	2	...	...	...	...	...	...
West	4	11	15	1	9	10	12	14	26	10	7	17	4	...	4	4	2	6	1	2	3	1	1	2	2	...	2	9	1	10	1	2	3	2	5	7
North-West	13	13	26	7	6	13	5	6	11	1	...	1	2	...	2	1	...	1	...	1	1	1	...	1	...	...	...	4	1	5	6	8	14	8	13	21
Calm	4	...	4	4	2	6	3	2	5	2	...	2	4	...	4	1	1	2	4	1	5	3	3	6	1	...	1	4	7	11	3	5	8	5	4	9
Variable	...	...	..	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	60			38			60			50			63			64			37			74			65			8			61			64		
Resultant Direction	N. 50° W.			N. 55° W.			N. 88° W.			S. 26° W.			S. 4° W.			S. 5° E.			S. 36° E.			S. 12° E.			S. 24° E.			N. 36° E.			N. 6° W.			N. 26° W.		
Mean diurnal velocity of wind in miles	43·1			48·0			74·2			102·3			137·6			129·3			110·0			86·2			93·6			37·6			38·3			43·6		
Average Resultant Percentage, 14-15 Years.	51			40			38			54			61			66			65			61			61			23			57			66		
Average Resultant Direction, 14-15 Years.	N. 24° W.			N. 65° W.			S. 62° W.			S. 11° W.			S. 10° E.			S. 19° E.			S. 17° E.			S. 20° E.			S. 26° E.			N. 65° E.			N. 2° E.			N. 13° W.		
Average diurnal velocity of wind in miles, 11-13 Years.	37·9			48·5			78·4			110·7			115·7			119·3			110·2			97·5			81·5			51·3			42·3			39·7		

47.—DACCA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	5	2	7	9	1	10	5	...	5	..	1	1	...	1	1	...	...	...	...	..	...	...	...	...	...	...	...	7	4	11	11	7	18	11	7	18
North-East	2	1	3	2	...	2	1	...	1	1	1	2	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	3	1	4	3	2	5	6	4	10
East	2	...	2	1	1	2	2	1	3	1	...	1	3	1	4	4	7	11	4	...	4	...	...	...	2	1	3	1	2	3	4	...	4	1	...	1
South-East	2	1	3	...	...	...	1	1	2	2	3	5	3	5	8	6	2	8	13	10	23	16	5	21	13	8	21	2	4	6	...	...	...	...	...	...
South	7	2	9	5	2	7	11	13	24	14	19	33	24	22	46	20	19	39	12	19	31	14	24	38	15	20	35	7	4	11	3	5	8	1	1	2
South-West	1	1	2	2	3	5	3	5	8	6	2	8	..	...	...	...	1	1	1	1	2	1	...	1	...	1	1	4	2	6	1	1	2	3	4	7
West	1	10	11	2	14	16	4	7	11	1	3	4	...	1	1	...	1	1	1	1	2	...	1	1	...	...	...	6	14	20	7	13	20	6	9	15
North-West	4	5	9	2	2	4	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	1	...	1	1	2	3	3	4	7
Calm	7	8	15	5	5	10	4	3	7	5	1	6	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1
Variable	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1
Resultant Percentage	21			34			45			69			81			80			83			88			89			25			36			46		
Resultant Direction	N. 77° W.			N. 79° W.			S. 24° W.			S. 6° W.			S. 12° E.			S. 18° E.			S. 21° E.			S. 13° E.			S. 19° E.			S. 72° W.			N. 48° W.			N. 36° W.		
Mean diurnal velocity of wind in miles	44·2			55·3			113·2			177·1			166·6			137·0			105·5			91·0			86·0			37·1			46·0			50·4		
Average Resultant Percentage, 15 Years.	32			35			54			60			60			75			80			72			57			4			38			44		
Average Resultant Direction, 15 Years.	N. 53° W.			S. 76° W.			S. 23° W.			S. 4° E.			S. 19° E.			S. 16° E.			S. 19° E.			S. 14° E.			S. 11° E.			S. 55° E.			N. 17° W.			N. 36° W.		
Average diurnal velocity of wind in miles, 15 Years.	51·2			65·3			113·4			161·2			150·1			180·3			178·9			146·2			110·8			57·5			45·9			47·2		

48.—CHITTAGONG (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	11	20	1	4	36	5	18	1	2	26	1	4	...	...	5	...	3	1	3	7	...	1	...	1	2	...	...	1	...	1
North-East	3	10	2	...	15	2	4	1	.	7	3	6	1	2	12	3	3	...	1	7	3	6	...	...	9	1	8	1	1	11
East	...	...	...	...	...	1	1	...	...	2	6	5	2	2	15	8	5	2	5	20	10	8	2	5	25	6	7	3	5	21
South-East	...	...	1	...	1	3	...	2	1	6	9	4	2	6	21	12	7	3	4	26	12	5	6	7	30	16	9	4	12	41
South	...	...	1	1	2	...	...	1	...	1	1	3	9	9	22	4	7	10	8	29	3	4	10	12	29	4	3	9	9	25
South-West	2	.	9	3	14	1	...	7	3	11	2	1	6	3	12	1	2	10	5	18	1	3	7	4	15	2	1	7	2	12
West	1	..	13	9	23	3	...	13	13	29	1	...	2	3	6	1	...	3	2	6	...	...	5	1	6	...	...	2	...	2
North-West	11	1	4	9	25	10	3	1	6	20	3	1	2	2	8	1	2	1	2	6	1	1	1	1	4	...	...	1	...	1
Calm	3	...	...	5	8	1	...	...	1	2	2	...	1	1	4	...	1	...	...	1	1	1	...	...	2	...	...	...	...	...
Variable	...	...	..	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	52					49					30					40					49					62				
Resultant Direction	N. 37° W.					N. 51° W.					S. 35° E.					S. 25° E.					S. 34° E.					S. 41° E.				
Mean diurnal velocity of wind in miles	70·3					82·5					124·2					140·8					184·4					163·9				
Average Resultant Percentage (15 Years.)	48					30					20					37					38					56				
Average Resultant Direction (15 Years.)	N. 24° W.					N. 38° W.					S. 54° W.					S. 12° W.					S.					S. 31° E.				
Average diurnal velocity of wind in miles (14-15 Years.)	99·5					112·2					144·1					171·1					157·5					168·0				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	...	...	1	...	...	...	1	...	...	...	...	...	3	16	4	...	23	6	9	5	3	23	9	5	3	4	21
North-East	1	9	...	1	11	1	8	1	...	10	2	2	...	1	5	1	12	...	...	13	...	3	...	...	3	7	4	2	2	15
East	11	11	1	1	24	8	13	...	2	23	6	7	1	4	18	1	...	...	1	2	1	...	3	2	6	1	1	4	3	9
South-East	16	8	7	24	55	17	6	3	19	45	18	18	5	15	56	2	2	2	2	8	1	...	...	...	1	1	8	...	1	10
South	2	2	18	3	25	4	4	17	10	35	2	3	11	8	24	2	...	...	2	4	...	1	...	1	2	...	7	...	1	8
South-West	...	1	3	1	5	...	...	10	...	10	1	...	11	1	13	1	...	3	1	5	2	...	1	1	4	2	...	5	...	7
West	...	...	2	...	2	...	...	...	...	...	...	...	2	1	3	8	...	10	9	27	5	2	8	5	20	1	1	7	3	12
North-West	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	11	...	10	10	31	12	6	10	12	40	9	4	10	9	32
Calm	1	...	...	1	2	...	...	...	...	...	...	...	..	...	...	2	...	1	4	7	...	...	...	3	3	1	...	...	8	9
Variable	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	71					69					71					45					63					30				
Resultant Direction	S. 48° E.					S. 40° E.					S. 35° E.					N. 41° W.					N. 41° W.					N. 21° W.				
Mean diurnal velocity of wind in miles	178·6					143·3					137·2					57·0					48·6					63·4				
Average Resultant Percentage (15 Years.)	63					55					31					14					53					59				
Average Resultant Direction (15 Years.)	S. 40° E.					S. 32° E.					S. 29° E.					N. 10° W.					N. 20° W.					N. 23° W.				
Average diurnal velocity of wind in miles (15 Years.)	172·6					144·7					109·3					76·2					78·9					83·8				

49.—DEMAGIRI (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	7	1	8	6	...	6	3	2	5	1	1	2	3	1	4	5	1	6
North-East	...	...	...	...	...	...	12	1	13	13	4	17	1	3	4	1	3	4
East	2	...	2	1	...	1	1	1	2	...	1	1	1	1	2	...	...	...
South-East	1	7	8	...	2	2	4	5	9	2	3	5	4	6	10	2	3	5
South	...	7	7	...	2	2	1	1	2	2	1	3	6	2	8	6	5	11
South-West	3	6	9	1	10	11	3	14	17	4	8	12	4	8	12	6	7	13
West	1	8	9	...	6	6	...	1	1	2	5	7	2	2	4	2	2	4
North-West	17	2	19	20	8	28	7	6	13	6	3	9	8	3	11	8	9	17
Calm	...	...	...	...	...	...	...	...	...	...	4	4	2	5	7	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	34			61			9			13			20			31		
Resultant (Direction)	N. 83° W.			N. 65° W.			N. 57° W.			N. 45° W.			S. 43° W.			S. 81° W.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...		
Average Resultant (Percentage)	30			33			21			13			4			24		
Average Resultant (Direction)	N. 74° W.			N. 69° W.			S. 83° W.			S. 59° W.			S. 40° W.			S. 27° E.		
6 Years. Average diurnal velocity of wind in miles. Years.	...			...			...			...			...			...		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	1	3	1	1	2	3	2	5	5	2	7	5	2	7	4	2	6
North-East	4	...	4	1	2	3	...	...	...	1	...	1	2	1	3	1	...	1
East	1	1	2	3	...	3	1	...	1	...	...	...	...	...	...	...	...	...
South-East	7	3	10	4	6	10	3	3	6	1	...	1	1	1	2	1	2	3
South	8	10	18	10	9	19	3	5	8	2	...	2	...	...	...	...	...	...
South-West	2	6	8	5	5	10	7	7	14	1	1	2	4	1	5	...	6	6
West	4	6	10	3	6	9	5	4	9	4	6	10	4	7	11	2	8	10
North-West	2	3	5	4	2	6	8	9	17	17	22	39	14	18	32	23	13	36
Calm	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	36			42			44			79			72			73		
Resultant (Direction)	S. 19° W.			S. 18° W.			S. 79° W.			N. 50° W.			N. 51° W.			N. 55° W.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...		
Average Resultant (Percentage)	24			23			4			17			37			36		
Average Resultant (Direction)	S. 23° E.			S. 27° E.			N. 16° W.			N. 33° W.			N. 60° W.			N. 70° W.		
6 Years. Average diurnal velocity of wind in miles. Years.	...			...			...			...			...			...		

50.—CALCUTTA (ALIPORE) (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	9	9	14	11	43	5	7	3	4	19	2	4	2	...	8	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...
North-East	4	6	...	4	14	5	5	3	2	15	2	1	2	2	7	1	...	1	...	2	...	1	1	...	2	1	1	1	1	4
East	1	2	2	2	7	1	1	1	1	4	...	...	...	...	...	...	...	...	2	2	1	2	1	1	5	5	3	3	4	15
South-East	1	2	...	1	4	...	2	...	2	4	1	...	...	...	1	2	2	...	4	8	3	1	2	5	11	4	6	7	4	21
South	1	1	...	1	3	1	1	3	1	6	2	1	4	5	12	13	4	11	14	42	15	11	13	13	52	10	4	9	14	37
South-West	3	2	2	1	8	5	4	4	7	20	12	9	8	14	43	11	19	13	9	52	11	15	13	11	50	9	12	7	6	34
West	4	4	6	4	18	5	4	6	4	19	8	8	9	7	32	3	3	3	1	10	1	1	1	1	4	1	2	2	1	6
North-West	5	5	7	7	24	4	3	8	7	22	4	8	6	3	21	...	2	1	...	3	...	...	...	...	...	...	2	1	...	3
Calm	3	...	...	...	3	2	1	..	...	3	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...
Resultant { Percentage	50					34					59					74					81					59				
Resultant { Direction	N. 20° W.					N. 55° W.					S. 78° W.					S. 26° W.					S. 15° W.					S.				
Mean diurnal velocity of wind in miles	56·3					79·7					129·9					190·1					203·4					153·8				
Average Resultant { Percentage (15 Years.)	38					23					49					73					66					59				
Average Resultant { Direction (15 Years.)	N. 38° W.					S. 81° W.					S. 32° W.					S. 3° W.					S. 11° E.					S. 4° E.				
Average diurnal velocity of wind in miles (7-8 Years.)	73·2					95·2					135·2					183·2					174·5					152·5				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	1	1	...	...	...	2	2	...	...	...	...	...	5	7	8	8	28	11	16	15	13	55	12	13	12	13	50
North-East	2	1	2	1	6	1	...	...	1	2	...	...	1	1	2	5	7	1	...	13	4	5	2	3	14	3	4	2	1	10
East	2	4	3	2	11	...	4	2	1	7	3	4	4	2	13	2	4	3	3	12	...	...	...	...	...	1	1	2	2	6
South-East	6	9	6	3	24	5	7	5	6	23	7	5	5	6	23	1	1	1	1	4	...	...	...	...	...	1	1	...	1	3
South	4	4	8	10	26	6	4	8	9	27	12	7	8	14	41	6	...	1	5	12	...	...	...	...	...	1	...	...	...	1
South-West	12	7	9	11	39	8	9	11	6	34	7	10	9	6	32	3	4	5	4	16	..	...	...	...	...	1	...	1	1	3
West	4	4	2	2	12	6	6	4	3	19	...	3	3	1	7	2	5	4	3	14	3	1	3	3	10	1	1	1	2	5
North-West	...	2	1	1	4	4	1	1	2	8	1	1	...	...	2	3	3	8	7	21	6	7	10	11	34	10	10	13	11	44
Calm	1	...	...	...	1	1	...	...	1	2	...	...	...	...	...	3	...	...	...	3	6	1	...	...	7	1	1	...	...	2
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	53					52					64					25					77					69				
Resultant { Direction	S. 9° W.					S. 22° W					S.					N. 32° W.					N. 15° W.					N. 16° W.				
Mean diurnal velocity of wind in miles	634·1					113·9					96·5					68·1					68·9					81·5				
Average Resultant { Percentage (15 Years.)	65					57					43					11					58					60				
Average Resultant { Direction (15 Years.)	S. 11° E.					S. 17° E.					S. 27° E.					N. 48° W.					N. 17° W.					N. 26° W.				
Average diurnal velocity of wind in miles (8-9 Years.)	121·6					127·6					111·8					80·1					68·2					73·5				

51.—SAUGOR ISLAND (*4 observations daily*).

	January.					February.					March.					April.					May.					June.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	3	8	10	3	24	4	10	6	3	23	1	5	1	...	7	...	...	...	1	1	...	...	...	...	...	2	...	1	1	4
North-East	9	12	4	9	34	6	7	1	5	19	1	1	1	3	6	1	1	...	1	3	1	...	1	...	2	2	2	1	1	6
East	4	2	...	3	9	...	1	...	2	3	1	...	...	1	2	1	...	...	...	1	...	...	...	1	1	...	1	...	...	1
South-East	3	...	2	3	8	2	...	4	6	12	1	...	4	1	6	4	1	9	5	19	4	2	6	3	15	...	2	4	2	8
South	2	2	7	7	18	4	3	8	9	24	9	10	16	18	53	12	18	21	15	66	13	16	20	17	66	9	10	16	16	51
South-West	3	1	8	2	14	4	4	2	1	11	10	11	5	6	32	11	8	...	6	25	9	10	4	7	30	12	11	4	7	34
West	1	1	...	...	2	...	...	1	..	1	2	2	1	...	5	..	...	...	1	1	1	...	...	...	1	1	1	...	1	3
North-West	1	2	...	...	3	2	3	5	1	11	5	2	3	...	10	...	2	...	...	2	...	...	...	...	...	...	1	...	...	1
Calm	4	1	...	3	8	5	...	...	...	5	1	...	...	...	1	...	...	...	...	...	2	...	...	2	4	4	1	2	1	8
Variable	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	25					9					54					79					81					64				
Resultant Direction	N. 56° E.					N. 65° E.					S. 21° W.					S. 2° W.					S. 5° W.					S. 13° W.				
Mean diurnal velocity of wind in miles	150·4					169·3					293·5					507·9					411·3					347·3				
Average Resultant Percentage (15 Years.)	19					23					60					76					69					69				
Average Resultant Direction (15 Years.)	N. 1° E.					S. 50° W.					S. 33° W.					S. 20° W.					S. 12° W.					S. 15° W.				
Average diurnal velocity of wind in miles (12-14 Years.)	140·4					181·2					274·7					385·4					343·7					327·6				

	July.					August.					September.					October.					November.					December.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	2	...	2	4	1	1	...	2	4	2	1	...	1	4	6	6	12	9	33	12	15	19	14	60	20	22	20	21	83
North-East	2	1	1	...	4	1	3	1	1	6	2	2	...	1	5	5	7	2	2	16	5	6	3	5	19	2	5	1	2	10
East	2	3	2	2	9	2	2	1	1	6	...	3	3	3	9	2	2	1	2	7	1	1	...	...	2	1	...	1	...	2
South-East	3	3	6	4	16	3	5	6	6	20	4	3	9	5	21	2	1	...	2	5	...	...	...	...	...	...	...	1	...	1
South	6	6	7	11	30	6	6	13	8	33	10	9	12	13	44	2	1	2	3	8	...	...	...	...	...	1	...	1	2	4
South-West	8	10	10	8	36	12	10	7	6	35	10	7	4	5	26	9	3	7	7	26	1	...	...	2	3	1	...	1	1	3
West	5	2	3	3	13	3	3	2	3	11	1	1	1	...	5	3	4	4	2	13	3	...	1	2	6	1	...	2	1	4
North-West	3	3	2	1	9	2	1	...	2	5	1	1	...	...	2	2	6	3	1	12	5	3	4	2	14	5	3	4	3	15
Calm	2	...	...	...	2	...	...	...	1	1	...	...	...	...	...	..	...	...	1	1	...	...	...	2	2	...	...	...	1	1
Variable	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	..	...	...	...	...	...	...	...
Resultant Percentage	47					51					59					24					77					77				
Resultant Direction	S. 22° W.					S. 14° W.					S. 2° E.					N. 38° W.					N. 2° W.					N. 4° W.				
Mean diurnal velocity of wind in miles	381·9					341·2					283·6					177·3					199·0					214·6				
Average Resultant Percentage (14-15 Years.)	59					54					48					13					58					56				
Average Resultant Direction (14-15 Years.)	S. 24° W.					S. 17° W.					S. 4° W.					N. 10° E.					N. 5° E.					N. 7° E.				
Average diurnal velocity of wind in miles (12-13 Years.)	319·0					272·3					226·2					148·0					143·9					144·3				

52.—CUTTACK (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	5	6	1	12	...	1	...	...	1	...	...	...	...	...
North-East	1	3	5	...	9	4	10	10	4	28	3	5	1	1	10
East	..	2	1	...	3	.	3	2	...	5	...	...	2	...	2
South-East	...	5	3	1	9	1	4	2	2	9	...	4	4	3	11
South	...	1	3	...	4	...	4	4	3	11	4	9	9	10	32
South-West	...	2	2	1	5	...	4	4	2	10	4	11	5	8	28
West	..	...	2	...	2	...	...	2	...	2	...	1	8	...	9
North-West	3	4	6	...	13	...	...	4	...	4	1	...	2	1	4
Calm	27	9	3	28	67	23	2		17	42	19	1	...	8	28
Variable	...	...	...	...	...	...	...	..	.	...	...	...	...	...	...
Resultant Percentage	11					17					42				
Resultant Direction	N. 4° E.					S. 88° E.					S. 17° W.				
Mean diurnal velocity of wind in miles	23·9					57·5					76·1				
Average Resultant (15 Years.) Percentage	11					13					43				
Average Resultant (15 Years.) Direction	N. 45° E.					S. 16° W.					S. 16° W.				
Average diurnal velocity of wind in miles (12-13 Years.)	34·9					51·5					86·2				

	APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	..	...		..	...	...	1	...	1	2	2	4	2	10
North-East	...	1	2	1	4	...	...	...	...	...	1	...	1	...	2
East	1	2	1	2	6	...	...	...	...	...	...	...	1	...	1
South-East	1	3	2	1	7	...	...	...	3	3	...	1	1	...	2
South	7	12	15	10	44	...	...	1	4	5	...	...	1	2	3
South-West	9	10	8	9	36	...	1	2	1	4	1	1	1	1	4
West	...	...	...	...	...	7	7	14	8	36	4	6	10	8	28
North-West	1	1	1	1	4	20	23	13	13	69	13	20	11	9	53
Calm	8	...	...	3	11	4	...	...	2	6	9	...	...	8	17
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	63					76					64				
Resultant Direction	S. 12° W.					N. 65° W.					N. 57° W.				
Mean diurnal velocity of wind in miles	142·8					173·7					81·2				
Average Resultant (15 Years.) Percentage	62					61					53				
Average Resultant (15 Years.) Direction	S. 17° W.					S 5° W.					S. 31° W.				
Average diurnal velocity of wind in miles (12-13 Years.)	125·6					126·0					95·1				

	JULY.					AUGUST.					SEPTEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	3	4	5	14	1	1	1	...	3	...	..	1	...	1
North East	...	...	...	.	...	1	3	4	3	11	2	3	2	1	8
East	...	1	...	...	1	2	2	1	2	7	1	1	1	2	5
South-East	2	1	5	1	9	3	3	2	1	9	5	6	4	3	18
South	..	1	1	2	4	4	5	7	1	17	7	8	9	5	29
South-West	7	8	9	6	30	8	14	13	5	40	6	7	7	2	22
West	3	5	6	5	19	2	2	1	3	8	1	2	3	1	7
North-West	5	10	6	4	25	...	...	...	...	...	...	1	...	...	1
Calm	12	2	...	8	22	8	...	1	15	24	6	...	2	14	22
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	41					37					44				
Resultant Direction	W					S. 20° W.					S.				
Mean diurnal velocity of wind in miles	66·2					48·9					29·9				
Average Resultant (15 Years.) Percentage	52					45					20				
Average Resultant (15 Years.) Direction	S. 44° W.					S. 44° W.					S. 10° W.				
Average diurnal velocity of wind in miles (13 Years.)	77·1					64·7					53·4				

	OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	2	2	2	8	4	2	5	3	14	2	6	6	2	16
North East	8	18	16	3	45	6	5	14	6	31	6	11	11	5	33
East	1	2	4	2	9	...	...	...	...	...	...	3	5	2	10
South-East	5	5	5	2	17	...	...	...	...	.	1	2	1	...	4
South	...	1	1	1	3	...	...	...	...	...	...	..	...	...	...
South-West	1	2	2	1	6	...	...	...	...	...	...	1	...	...	1
West	...	...	...	...	...	1	1	1	...	3	...	1	1	...	2
North-West	1	4	4	1	10	3	2	4	3	12	1	4	4	1	10
Calm	13	...	...	19	32	15	19	4	16	54	17	...	1	18	36
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	44					40					45				
Resultant Direction	N. 67° E.					N. 13° E.					N. 32° E.				
Mean diurnal velocity of wind in miles	21·1					21·9					27·8				
Average Resultant (15 Years.) Percentage	25					43					35				
Average Resultant (15 Years.) Direction	N. 32° E.					N. 1° W.					N. 12° E.				
Average diurnal velocity of wind in miles (13 Years.)	44·3					37·1					30·7				

53.—FALSE POINT (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	9	1	10	5	...	5	...	...	...	...	...	...	...	...	...	...	...	...
North-East	5	8	13	9	8	17	4	...	4	1	1	2	...	...	...	1	...	1
East	4	9	13	2	7	9	...	2	2	...	1	1	1	...	1	...	2	2
South-East	1	8	9	1	3	4	3	4	7	1	2	3	2	4	6	1	1	2
South	2	5	7	3	6	9	5	8	13	6	8	14	9	10	19	6	8	14
South-West	2	...	2	5	3	8	15	17	32	21	18	39	19	16	35	15	13	28
West	2	...	2	...	1	1	...	...	...	1	...	1	...	1	1	6	6	12
North-West	5	...	5	1	...	1	4	...	4	...	...	...	...	...	...	...	...	...
Calm	1	...	1	2	...	2	...	...	...	...	...	...	...	...	...	1	...	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	37			29			62			81			84			74		
Resultant Direction	N. 70° E.			N. 89° E.			S. 24° W.			S. 30° W.			S. 23° W.			S. 39° W.		
Mean diurnal velocity of wind in miles	?			?			?			?			311·7			266·4		
Average Resultant Percentage, 14-15 Years	22			16			58			79			71			63		
Average Resultant Direction, 14-15 Years	N. 51° E.			S. 12° W.			S. 38° W.			S. 38° W.			S. 31° W.			S. 45° W.		
Average diurnal velocity of wind in miles, 5 Years	147·3			177·8			257·5			320·5			285·2			251·1		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	...	...	...	...	...	...	5	1	6	7	1	8	15	...	15
North-East	2	1	3	1	1	2	2	2	4	6	11	17	10	19	29	12	20	32
East	...	2	2	2	1	3	...	2	2	3	8	11	...	6	6	...	7	7
South-East	1	3	4	3	4	7	3	6	9	1	5	6	...	2	2	...	3	3
South	3	1	4	1	6	7	3	6	9	1	4	5	...	...	...	...	...	...
South-West	12	16	28	13	14	27	8	11	19	2	...	2	...	...	...	...	...	...
West	8	7	15	10	4	14	7	1	8	6	...	6	4	...	4	1	...	1
North-West	4	1	5	1	1	2	5	1	6	5	...	5	9	...	9	2	1	3
Calm	...	...	...	...	...	...	2	1	3	2	2	4	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	60			61			44			32			65			77		
Resultant Direction	S. 58° W.			S. 42° W.			S. 34° W.			N. 56° E.			N. 28° E.			N. 37° E.		
Mean diurnal velocity of wind in miles	274·3			227·4			191·7			111·2			130·4			165·8		
Average Resultant Percentage, 14-15 Years	64			53			36			25			57			64		
Average Resultant Direction, 14-15 Years	S. 59° W.			S. 57° W.			S. 25° W.			N. 40° E.			N. 22° E.			N. 43° E.		
Average diurnal velocity of wind in miles, 4-6 Years	243·0			218·0			178·0			137·4			148·3			159·3		

54.—SAMBALPUR (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	5	4	9	2	2	4	2	3	5	...	1	1	2	1	3	3	3	6	6	2	8	5	6	11	6	7	13	8	8	16	7	12	19	11	6	17
North-East	10	6	16	11	3	14	5	1	6	3	3	6	1	5	6	...	2	2	...	1	1	5	6	11	2	2	4	9	9	18	12	8	20	11	13	24
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	1	1	1	2	3	1	3	4	1	2	3	1	1	2	1	1	2
South-East	1	3	4	1	1	2	1	1	2	1	1	2	1	...	1	...	...	...	...	...	...	1	2	3	1	1	2	3	3	6	...	...	...	...	...	...
South	2	1	3	1	...	1	2	2	4	4	1	5	1	1	2	4	2	6	5	3	8	5	5	10	2	4	6	...	...	...	...	...	...	...	...	...
South-West	...	5	5	4	7	11	11	10	21	14	13	27	21	14	35	15	10	25	15	13	28	9	6	15	6	1	7	3	2	5	1	1	2	1	2	3
West	2	...	2	1	3	4	2	4	6	3	4	7	1	8	9	2	4	6	3	4	7	...	...	...	...	1	1	1	1	2	1	...	1	1	...	1
North-West	9	4	13	4	7	11	3	7	10	2	7	9	2	2	4	4	7	11	2	7	9	5	2	7	8	10	18	3	4	7	8	8	16	6	9	15
Calm	2	8	10	4	5	9	5	3	8	3	...	3	2	...	2	1	2	3	...	...	...	...	2	2	4	1	5	3	2	5	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	32			25			36			50			58			50			55			5			32			44			72			69		
Resultant Direction	N. 2° W.			N. 36° W.			S. 80° W.			S. 63° W.			S. 61° W.			S. 74° W.			S. 68° W.			N. 69° W.			N. 33° W.			N. 20° E.			N. 3° E.			N. 7° E.		
Mean diurnal velocity of wind in miles	Untrustworthy.																																			
Average Resultant Percentage (10 Years.)	32			9			29			39			38			39			38			41			15			3			49			50		
Average Resultant Direction (10 Years.)	N. 50° W.			N. 49° W.			W.			S. 82° W.			S. 60° W.			S. 59° W.			S. 49° W.			S. 57° W.			S. 33° W.			N 1° W.			N. 11° W.			N. 22° W.		
Average diurnal velocity of wind in miles. (3 Years.)	45·4			50·8			55·5			74·0			79·9			91·7			93·3			78·5			61·9			?			11·8			34·7		

55.—RAIPUR (*2 observations daily.*)

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	2	2	4	...	...	...	1	3	4	3	3	6	3	5	8	...	1	1	2	2	4	...	...	...	8	11	19	14	17	31	8	9	17
North-East	11	9	20	7	3	10	6	2	8	8	3	11	1	...	1	...	...	...	...	...	...	3	2	5	...	...	...	8	11	19	8	7	15	16	16	32
East	2	...	2	3	...	3	2	...	2	...	1	1	...	...	...	...	1	1	...	...	...	1	4	5	2	2	4	...	3	3	...	...	...	...	...	...
South-East	2	1	3	2	...	2	...	1	1	...	...	...	...	1	1	...	1	1	...	...	...	...	1	1	1	1	2	1	1	2	...	...	...	...	...	...
South	1	1	2	...	...	...	1	...	1	...	...	...	...	...	...	...	2	2	...	...	...	1	...	1	...	...	...	2	2	4	...	...	...	...	...	...
South-West	7	6	13	5	4	9	7	7	14	14	12	26	3	4	7	16	11	27	11	15	26	3	...	3	18	16	34	3	...	3	...	...	...	...	...	...
West	4	5	9	2	4	6	8	4	12	2	1	3	14	11	25	11	7	18	18	12	30	18	16	34	6	10	16	1	1	2	1	1	2	2	...	2
North-West	2	6	8	5	11	16	3	13	16	5	10	15	10	12	22	...	3	3	1	3	4	2	4	6	2	1	3	3	...	3	...	...	...	1	1	2
Calm	2	2	4	2	4	6	4	4	8	...	...	...	...	...	...	...	...	...	...	1	1	1	2	3	1	...	1	5	2	7	7	5	12	4	5	9
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	15			34			41			39			76			65			86			52			73			47			71			73		
Resultant Direction	N. 37° W			N. 40° W.			N. 78° W.			N. 80° W.			N. 69° W.			S. 73° W.			S. 74° W.			N. 76° W.			S. 58° W.			N. 23° E.			N. 12° E.			N. 25° E.		
Mean diurnal velocity of wind in miles	62·5			74·8			104·7			?			252·6			305·9			296·9			190·6			224·7			95·4			84·2			73·4		
Average Resultant Percentage (14-15 Years.)	21			13			20			35			39			66			77			64			29			37			57			48		
Average Resultant Direction (14-15 Years.)	N. 5° E.			N. 40° W.			N. 79° W.			N. 88° W.			N. 78° W.			S. 74° W.			S. 68° W.			S. 76° W.			S. 69° W.			N. 28° E.			N. 31° E.			N. 35° E.		
Average diurnal velocity of wind in miles. (12-14 Years.)	57·9			82·6			103·7			124·2			166·6			188·0			273·2			156·5			128·8			85·1			70·5			54·8		

56.—NAGPUR (*4 observations daily*).

	January.					February.					March.					April.					May.					June.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours	22 hours.	Total.
North	6	2	1	1	10	7	4	2	3	16	5	2	1	8	16	2	3	2	2	9	5	4	1	6	16	1	1	3	1	6
North-East	11	12	2	1	26	10	12	3	7	32	8	9	2	2	21	6	3	3	2	14	1	2	...	2	5	...	1	3	...	4
East	4	5	5	4	18	2	6	1	5	14	2	8	2	1	13	1	2	4	2	9	...	1	1	...	2	1	...	1	2	4
South-East	2	6	3	4	15	3	...	1	3	7	5	5	1	2	13	1	3	2	2	8	2	...	...	1	3	1	1	2	1	5
South	1	1	6	6	14	...	2	4	3	9	2	2	...	2	6	3	1	...	3	7	...	1	...	2	3	3	1	4	5	13
South-West	3	1	7	2	13	1	2	8	3	14	3	3	5	2	13	4	4	2	3	13	2	3	6	5	18	8	7	3	7	25
West	...	...	2	1	3	1	...	5	1	7	2	...	10	4	16	1	3	10	9	23	6	8	14	5	33	7	12	8	7	34
North-West	1	...	3	1	5	3	2	3	3	11	3	2	10	9	24	8	8	6	4	26	14	11	9	8	42	2	6	5	4	17
Calm	3	4	2	11	20	1	...	...	...	1	1	...	...	1	2	...	...	...	...	...	...	...	...	1	1	6	...	...	2	8
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	25					25					19					28					60					47				
Resultant Direction	S. 87° E.					N. 37° E.					N. 12° W.					N. 59° W.					N. 65° W.					S. 76° W.				
Mean diurnal velocity of wind in miles	89·1					136·3					140·7					165·8					234·4					213·9				
Average Resultant Percentage (14-15 Years.)	30					17					6					20					44					52				
Average Resultant Direction (14-15 Years.)	N. 72° E.					N. 55° E.					N. 20° W.					N. 63° W.					N. 41° W.					N. 76° W.				
Average diurnal velocity of wind in miles (13-15 Years.)	69·6					84·8					99·9					119·3					151·6					168·3				

	July.					August.					September.					October.					November.					December.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	2	1	1	6	6	7	2	4	19	1	2	2	...	5	3	4	...	1	8	3	3	...	1	7	8	10	2	3	23
North-East	...	...	...	1	1	1	1	3	4	9	1	3	2	...	6	15	15	11	7	48	15	15	15	9	54	20	19	15	10	64
East	...	...	...	...	...	...	...	...	1	1	1	1	2	1	5	4	6	11	9	30	6	9	10	8	33	...	...	9	7	16
South-East	...	...	1	...	1	1	2	1	...	4	...	...	3	1	4	...	3	4	...	7	2	2	3	1	8	...	...	2	...	2
South	1	1	...	1	3	1	1	2	2	6	1	...	1	...	2	1	...	...	3	4	2	...	...	1	3	...	...	...	...	...
South-West	6	2	5	4	17	1	3	4	6	14	6	3	5	3	17	...	1	2	1	4	...	...	...	...	...	...	...	...	...	...
West	10	14	14	10	48	6	6	11	5	28	8	11	8	10	37	1	...	1	1	3	...	...	...	...	...	...	...	1	...	1
North-West	9	12	10	8	39	8	11	8	7	34	4	5	5	5	19	...	1	...	1	2	...	...	...	...	...	1	...	...	...	1
Calm	3	...	...	6	9	7	...	...	2	9	7	4	2	10	23	6	...	1	7	14	2	1	2	10	15	1	...	2	10	13
Variable	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	··	...
Resultant Percentage	71					49					43					58					71					76				
Resultant Direction	N. 78° W.					N. 59° W.					N. 83° W.					N. 63° E.					N. 65° E.					N. 42° E.				
Mean diurnal velocity of wind in miles	233·8					165·9					154·5					92·1					72·0					77·8				
Average Resultant Percentage (15 Years.)	69					62					37					51					60					52				
Average Resultant Direction (15 Years.)	N. 88° W.					N. 76° W.					N. 54° W.					N. 37° E.					N. 60° E.					N. 64° E.				
Average diurnal velocity of wind in miles (14-15 Years.)	169·6					131·7					109·6					82·1					66·4					60·5				

57.—SEONI (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	2	2	2	3	5	3	3	6	3	6	9	6	2	8	...	3	3	2	1	3	4	1	5	2	5	7	3	1	4	2	7	9	5	6	11
North-East	3	3	6	10	4	14	4	2	6	2	3	5	1	2	3	1	1	2	1	1	2	1	1	2	3	2	5	5	9	14	8	9	17	9	8	17
East	4	2	6	4	...	4	5	1	6	5	2	7	...	...	...	1	2	3	...	3	3	2	5	7	1	5	6	11	13	24	6	9	15	8	7	15
South-East	7	3	10	1	1	2	6	...	6	4	1	5	...	...	...	...	1	1	1	...	1	...	2	2	3	...	3	6	5	11	5	2	7	3	2	5
South	7	9	16	4	4	8	3	2	5	1	...	1	1	1	2	1	4	5	...	1	1	2	2	4	1	1	2	...	2	2	1	...	1	1	...	1
South-West	4	10	14	3	9	12	3	8	11	3	6	9	4	3	7	9	10	19	5	7	12	2	4	6	3	5	8	1	...	1	1	2	3	1	3	4
West	2	1	3	...	2	2	2	11	13	3	5	8	6	11	17	9	4	13	13	12	25	9	7	16	7	7	14	...	1	1	1	1	2	1	...	1
North-West	1	...	1	1	4	5	3	3	6	6	7	13	11	11	22	8	3	11	8	5	13	9	6	15	7	4	11	2	...	2	2	1	3	2	2	4
Calm	3	1	4	3	1	4	2	1	3	3	...	3	2	1	3	1	2	3	1	1	2	2	3	5	3	1	4	3	...	3	3	1	4	1	3	4
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	42			2			17			24			65			50			61			36			30			63			38			49		
Resultant { Direction	S. 8° E.			N. 68° E.			S. 76° W.			N. 41° W.			N. 62° W.			S. 77° W.			N. 85° W.			N. 71° W.			N. 62° W.			N. 83° E.			N. 46° E.			N. 52° E.		
Mean diurnal velocity of wind in miles	71·0			72·2			92·6			108·8			148·5			141·8			185·1			105·5			106·4			47·2			41·7			52·0		
Average Resultant { Percentage	11			10			16			29			39			47			57			50			29			49			54			38		
Average Resultant { Direction (14-15 Years)	N. 75° E.			N. 40° W.			N. 71° W.			N. 71° W.			N. 58° W.			S. 83° W.			S. 78° W.			N. 86° W.			N. 56° W.			N. 28° E.			N. 55° E.			N. 44° E.		
Average diurnal velocity of wind in miles (13-14 Years)	66·8			72·3			80·7			89·0			104·2			134·1			139·7			107·4			92·1			78·5			65·4			63·9		

58.—JUBBULPORE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	2	2	2	11	13	1	2	3	...	3	3	1	1	2	...	...	...	...	...	...	...	1	1	...	1	1	1	1	2	1	1	2	...	4	4
North-East	2	3	5	4	2	6	7	1	8	5	1	6	...	...	...	...	1	1	3	2	5	1	3	4	...	5	5	3	13	16	3	12	15	1	9	10
East	1	1	2	4	1	5	...	1	1	2	1	3	...	...	...	...	2	2	1	1	2	...	...	...	...	...	...	...	4	4	...	2	2	...	2	2
South-East	2	2	4	1	...	1	3	...	3	1	...	1	...	1	1	...	2	2	1	...	1	2	1	3	2	...	2	3	4	7	2	...	2	5	1	6
South	8	3	11	2	...	2	3	...	3	...	1	1	...	2	2	...	2	2	1	2	3	1	1	2	...	3	3	1	1	2	6	...	6	5	...	5
South-West	1	...	1	...	...	...	2	...	2	3	3	6	1	2	3	4	1	5	3	2	5	2	1	3	3	2	5	2	...	2	2	...	2	...	...	...
West	1	...	1	1	2	3	1	8	9	4	5	9	12	8	20	11	2	13	13	11	24	14	8	22	12	9	21	1	1	2	2	...	2	...	...	...
North-West	...	2	2	...	3	3	4	10	14	4	10	14	9	13	22	9	10	19	6	7	13	6	9	15	8	3	11	4	2	6	...	3	3	1	1	2
Calm	16	18	34	14	9	23	10	9	19	11	6	17	8	4	12	6	10	16	3	6	9	5	7	12	5	7	12	16	5	21	14	12	26	19	14	33
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	15			31			27			31			63			45			50			54			64			25			17			20		
Resultant { Direction	S. 35° E.			N. 16° E.			N. 44° W.			N. 54° W.			N. 71° W.			N. 74° W.			N. 80° W.			N. 75° W.			N. 81° W.			N. 54° E.			N. 55° E.			N. 75° E.		
Mean diurnal velocity of wind in miles	51·1			54·7			62·5			66·9			107·9			114·1			126·7			80·0			75·3			42·6			33·2			24·5		
Average Resultant { Percentage	17			20			22			32			44			54			65			64			34			17			25			17		
Average Resultant { Direction (14-15 Years)	N. 8° E.			N. 13° W.			N. 69° W.			N. 66° W.			N. 62° W.			N. 80° W.			N. 87° W.			N. 84° W.			N. 69° W.			N. 3° E.			N. 47° E.			N. 32° E.		
Average diurnal velocity of wind in miles (14-15 Years)	56·5			64·9			75·6			88·6			114·6			137·1			125·3			115·9			86·6			55·1			47·0			45·9		

59.—SAUGOR (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	3	3	1	8	9	1	2	3	3	6	9	...	4	4	...	5	5	2	...	2	1	4	5	3	6	9	3	11	14	2	9	11	2	4	6
North-East	6	4	10	13	4	17	7	...	7	3	3	6	1	...	1	...	2	2	2	1	3	3	4	7	1	2	3	5	5	10	14	5	19	14	15	29
East	4	1	5	7	...	7	5	2	7	5	...	5	1	...	1	...	1	1	...	1	1	2	1	3	...	1	1	2	2	4	3	1	4	4	...	4
South-East	10	1	11	4	1	5	5	...	5	3	...	3	1	...	1	...	1	1	2	...	2	...	...	...	...	2	2	5	4	9	2	...	2	8	4	12
South	5	2	7	1	...	1	2	1	3	...	...	...	...	...	...	...	...	...	1	1	2	...	...	...	...	...	...	...	1	1	1	...	1	1	1	2
South-West	3	5	8	1	2	3	2	4	6	3	3	6	5	6	11	6	6	12	7	7	14	8	6	14	10	7	17	4	1	5	2	1	3	...	1	1
West	...	6	6	1	1	2	3	10	13	3	10	13	9	11	20	10	3	13	9	12	21	10	10	20	6	6	12	4	2	6	3	5	8	1	...	1
North-West	1	7	8	...	10	10	5	10	15	6	7	13	13	7	20	13	9	22	7	5	12	7	6	13	9	5	14	4	3	7	3	9	12	1	6	7
Calm	2	2	4	...	2	2	1	2	3	4	1	5	1	3	4	1	3	4	1	4	5	...	...	...	1	1	2	4	2	6	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	9			43			24			37			66			60			56			52			51			25			47			54		
Resultant Direction	S. 28° E.			N. 28° E.			N. 58° W.			N. 43° W.			N. 75° W.			N. 69° W.			S. 89° W.			N. 73° W.			N. 76° W.			N. 11° E.			N. 1° E.			N. 52° E.		
Mean diurnal velocity of wind in miles	107·3			101·8			111·5			106·9			129·0			110·5			97·4			89·4			82·6			79·1			101·2			100·3		
Average Resultant Percentage (10 Years.)	25			27			33			45			58			65			72			67			43			48			45			38		
Average Resultant Direction (10 Years.)	N. 16° E.			N.			N. 53° W.			N. 72° W.			W.			S. 82° W.			S. 69° W.			S. 73° W.			N. 81° W.			N. 26° W.			N. 19° E.			N. 45° E.		
Average diurnal velocity of wind in miles. 13-14 Years.	60·0			65·6			70·7			85·5			95·9			115·8			109·3			90·2			71·5			59·6			51·2			55·3		

60.—PACHMARHI (*Up to August 2, afterwards 4 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	4 hours.	10 hours.	16 hours.	Total.	4 hours.	10 hours.	16 hours.	Total.	4 hours.	10 hours.	16 hours.	Total.	4 hours.	10 hours.	16 hours.	Total.
North	2	10	12	2	9	11	2	4	6	8	9	17	8	4	12	5	4	9	3	2	5	1	2	3	...	...	2	2	4	...	2	5	3	10	...	4	8	2	14	1	3	7	2	13
North-East	1	1	2	3	...	3	3	1	4	3	2	5	1	1	2	...	2	2	1	...	1	1	1	2	2	3	6	2	13	2	8	16	4	30	2	7	8	1	18	2	9	13	2	26
East	1	1	2	1	...	1	4	...	4	3	...	3	...	...	...	...	...	...	1	1	2	1	1	2	1	4	5	2	...	7	2	12	4	3	21	1	3	3	...	7	1	15	4	...	20
South-East	9	...	9	11	1	12	4	1	5	7	...	7	...	...	...	1	2	3	1	...	1	...	...	...	...	1	...	...	1	1	2	2	1	6	...	2	2	...	4	1	...	2	...	3
South	8	4	12	6	...	6	3	...	3	...	...	...	2	...	2	...	...	...	2	...	2	...	...	...	...	...	...	1	2	...	3	...	...	...	1	...	1	1	1	...	1	3
South-West	4	3	7	3	1	4	2	4	6	2	4	6	1	4	5	2	3	5	2	5	7	3	6	9	2	3	4	3	12	1	2	1	...	4	1	1	1	...	3	1	1	2	...	3
West	...	7	7	...	2	2	2	8	10	...	6	6	6	9	15	6	9	15	16	18	34	7	11	18	8	5	6	7	26	...	1	...	1	...	1	...	...	1	...	...	2	4	1	3
North-West	6	5	11	2	15	17	11	13	24	7	9	16	13	13	26	16	8	24	6	4	10	15	8	23	4	6	3	3	16	1	...	2	...	3	...	2	3	...	5	2	...	3	2	7
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	2	...	1	1	3	3	6	5	...	...	6	11	21	1	...	19	41	18	1	1	21	41	22	1	...	23	46
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	16			17			41			41			71			64			71			66			36			39			31			34		
Resultant Direction	S. 78° W.			N. 34° W.			N. 54° W.			N. 24° W.			N. 54° W.			N. 56° W.			N. 83° W.			N. 69° W.			N. 62° W.			N. 60° E.			N. 33° E.			N. 46° E.		
Mean diurnal velocity of wind in miles	86·1			86·7			115·0			124·0			160·6			149·6			202·8			107·1			192·8			63·1			40·3			55·2		
Average Resultant Percentage (10 Years.)	17			27			41			46			62			64			75			71			52			45			50			19		
Average Resultant Direction (10 Years.)	N. 65° W.			N. 46° W.			N. 54° W.			N. 55° W.			N. 56° W.			N. 70° W.			N. 76° W.			N. 79° W.			N. 58° W.			N. 17° E.			N. 51° E.			N. 31° E.		
Average diurnal velocity of wind in miles. 11-14 Years.	70·3			81·4			94·0			116·1			144·6			170·0			208·6			162·1			137·4			72·8			58·2			61·1		

61. HOSHANGABAD (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	...	1	1	2	1	3	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	2	2	...	1	1	...	1	1
North-East	19	6	25	15	9	24	11	1	12	8	4	12	1	1	2	...	...	...	...	1	1	...	2	2	...	2	2	11	12	23	16	9	25	17	11	28
East	6	4	10	7	6	13	5	...	5	4	1	5	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	8	4	12	10	9	19	12	14	26
South-East	1	1	2	1	...	1	1	...	1	...	3	3	1	...	1	...	2	2	1	1	2	1	1	2	1	3	4	5	5	10	...	1	1	...	2	2
South	1	2	3	...	...	...	...	1	1	1	...	1	...	...	...	1	...	1	...	...	...	1	...	1	...	1	1	...	1	1	...	...	...	1	...	1
South-West	3	11	14	1	2	3	5	11	16	3	10	13	9	9	18	12	6	18	11	9	20	10	7	17	11	5	16	4	...	4	3	...	3	1	1	2
West	1	3	4	2	9	11	6	13	19	5	7	12	13	11	24	14	12	26	14	14	28	15	10	25	15	9	24	3	1	4	...	5	5	...	2	2
North-West	...	3	3	2	1	3	1	4	5	8	5	13	7	10	17	3	10	13	4	6	10	4	11	15	3	9	12	...	6	6	1	5	6	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	24			41			32			27			75			78			75			72			66			43			55			76		
Resultant Direction	N. 64° E.			N. 42° E.			N. 84° W.			N. 67° W.			W.			S. 83° W.			S. 80° W.			S. 87° W.			S. 84° W.			N. 64° E.			N. 52° E.			N. 69° E.		
Mean diurnal velocity of wind in miles	49·8			61·8			73·2			83·8			114·1			126·9			137·3			89·5			107·9			35·7			34·9			59·9		
Average Resultant Percentage (10-15 Years.)	40			16			12			25			47			69			73			73			50			25			66			63		
Average Resultant Direction (10-15 Years.)	N. 52° E.			N. 53° E			N. 42° W.			S. 84° W.			S. 89° W.			N. 89° W.			S. 74° W.			S. 79° W.			N. 83° W.			N. 12° E.			N. 60° E.			N. 61° E.		
Average diurnal velocity of wind in miles (13-14 Years.)	67·6			72·9			67·2			73·8			93·9			115·6			112·2			87·3			65·7			42·2			50·7			66·2		

62.—KHANDWA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	...	3	1	5	6	4	4	8	8	5	13	1	...	1	1	2	3	...	...	...	...	...	...	...	4	4	6	6	12	5	9	14	8	9	17
North-East	2	1	3	12	6	18	6	2	8	2	3	5	1	1	2	...	...	...	...	...	...	...	1	1	...	...	...	8	10	18	10	11	21	14	12	26
East	4	...	4	1	...	1	...	...	...	4	...	4	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	2	3	5	4	...	4	3	3	6
South-East	8	5	13	1	1	2	1	...	1	1	...	1	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	4	6	10	1	2	3	2	2	4
South	4	4	8	...	2	2	...	...	...	...	...	...	...	...	...	...	2	2	2	...	2	...	...	...	...	...	...	...	...	...	2	2	4	2	1	3
South-West	2	4	6	...	1	1	...	2	2	...	...	...	1	...	1	3	8	11	1	2	3	1	1	2	3	...	3	...	...	...	...	...	...	1	...	1
West	3	5	8	2	4	6	2	8	10	6	9	15	10	13	23	16	10	26	24	16	40	19	17	36	17	16	33	1	1	2	...	...	...	...	2	2
North-West	1	5	6	7	9	16	17	15	32	7	12	19	16	15	31	10	8	18	2	12	14	11	12	23	9	10	19	3	3	6	2	3	5	...	1	1
Calm	4	7	11	4	...	4	1	...	1	2	1	3	1	1	2	...	...	...	2	1	3	...	...	...	1	...	1	7	2	9	6	3	9	1	1	2
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	20			47			71			59			78			78			84			89			85			46			53			61		
Resultant Direction	S. 6° W.			N. 6° W.			N. 39° W.			N. 35° W.			N. 62° W.			N. 83° W			N. 84° W.			N. 74° W.			N. 73° W.			N. 40° E.			N. 34° E.			N. 39° E.		
Mean diurnal velocity of wind in miles	62·1			83·3			103·4			140·9			216·6			171·4			190·6			189·2			162·1			66·7			55·0			53·3		
Average Resultant Percentage (10 Years.)	31			30			47			62			69			71			79			78			66			25			51			37		
Average Resultant Direction (10 Years.)	N. 20° E.			N. 11° W.			N. 48° W.			N. 52° W.			N. 61° W.			N. 75° W.			N. 81° W.			N. 81° W.			N. 72° W.			N. 18° E.			N. 70° E.			N. 73° E.		
Average diurnal velocity of wind in miles (8-9 Years.)	64·7			87·8			111·3			137·3			222·1			232·2			209·3			181·7			143·2			71·2			59·7			53·7		

63.—CHANDA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	1	3	4	1	5	1	1	2	...	2	2	2	...	2	1	...	1	1	1	1	2	1	3	1	1	2	4	2	6	4	...	4	14	12	26
North-East	4	4	8	4	3	7	2	...	2	3	2	5	...	1	1	...	...	...	...	...	...	...	1	1	...	1	1	5	2	7	6	3	9	5	7	12
East	1	4	5	1	1	2	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	...	2	2
South-East	12	7	19	9	2	11	11	6	17	9	6	15	1	1	2	1	2	3	...	...	...	1	3	4	3	3	6	3	2	5	2	1	3	1	...	1
South	1	...	1	...	2	2	4	3	7	5	3	8	2	...	2	...	1	1	...	1	1	1	1	2	...	1	1	...	1	1	...	...	...	...	...	...
South-West	...	1	1	4	4	8	6	3	9	3	3	6	4	3	7	11	13	24	8	8	16	5	8	13	3	6	9	...	...	...	...	...	...	...	...	...
West	1	2	3	2	4	6	4	10	14	4	9	13	9	14	23	11	5	16	16	14	30	9	6	15	14	11	25	1	...	1	...	...	...	...	...	...
North-West	4	1	5	4	3	7	2	7	9	4	4	8	13	8	21	3	4	7	6	4	10	11	5	16	4	3	7	...	...	...	1	...	1	...	...	...
Calm	6	11	17	...	8	8	1	...	1	2	1	3	...	4	4	3	5	8	1	3	4	2	6	8	5	4	9	18	23	41	17	26	43	11	10	21
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	28			3			32			24			67			64			78			52			53			17			20			57		
Resultant Direction	S. 80° E.			S. 74° W.			S. 38° W.			S. 37° W.			N. 77° W.			S. 68° W.			S. 85° W.			N. 88° W.			S. 83° W.			N. 53° E.			N. 41° E.			N. 18° E.		
Mean diurnal velocity of wind in miles	77·6			84·4			102·4			115·2			142·3			?			184·6			134·6			155·0			45·8			29·9			34·7		
Average Resultant Percentage (10 Years.)	24			18			9			20			24			48			67			61			39			39			53			41		
Average Resultant Direction (10 Years.)	S. 78° E.			S. 62° E.			N. 87° W.			S. 69° W.			N. 76° W.			N. 84° W.			N. 86° W.			N. 73° W.			N. 58° W.			N. 56° E.			N. 70° E.			N. 76° E.		
Average diurnal velocity of wind in miles. 12-14 Years.	50·0			66·8			78·6			92·6			116·8			147·4			143·7			122·0			93·5			53·4			43·2			37·9		

64.—SIRONCHA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	3	3	...	2	2	1	2	3	...	1	1	5	4	9	...	1	1	...	1	1	...	2	2	...	1	1	5	5	10	12	9	21	18	7	25
North-East	1	3	4	...	3	3	2	2	4	2	3	5	1	3	4	...	1	1	...	...	...	...	1	1	2	1	3	1	5	6	4	7	11	2	5	7
East	1	11	12	2	5	7	2	3	5	...	...	...	1	1	2	...	...	...	...	...	...	...	...	...	1	2	3	3	8	11	5	3	8	...	1	1
South-East	5	4	9	12	1	13	7	5	12	11	4	15	5	4	9	2	3	5	...	2	2	3	3	6	1	1	2	7	4	11	1	2	3	...	3	3
South	12	4	16	5	4	9	13	4	17	10	8	18	8	2	10	5	6	11	...	1	1	3	1	4	3	4	7	3	1	4	2	1	3	...	...	...
South-West	4	2	6	2	3	5	3	4	7	5	6	11	3	2	5	6	11	17	7	5	12	6	7	13	7	7	14	...	1	1	1	1	2	...	...	...
West	3	...	3	2	4	6	2	3	5	...	3	3	1	7	8	13	5	18	20	15	35	14	12	26	10	12	22	2	1	3	...	1	1	...	2	2
North-West	4	...	4	3	4	7	...	4	4	1	3	4	6	7	13	2	...	2	2	6	8	5	4	9	5	1	6	7	6	13	5	6	11	7	12	19
Calm	1	4	5	2	2	4	1	4	5	1	2	3	1	1	2	1	2	3	2	1	3	...	1	1	1	1	2	3	...	3	...	...	...	4	1	5
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	34			24			36			47			15			57			77			61			53			24			52			68		
Resultant Direction	S. 32° E.			S. 17° E.			S. 9° E.			S. 1° E.			N. 83° W.			S. 47° W.			S. 85° W.			S. 77° W.			S. 70° W.			N. 43° E.			N. 14° E.			N. 10° W.		
Mean diurnal velocity of wind in miles	44·8			53·2			73·6			89·3			100·7			101·6			99·6			88·6			84·3			57·7			47·6			48·2		
Average Resultant Percentage (6-8 Years.)	9			26			36			39			20			51			86			62			42			32			58			49		
Average Resultant Direction (6-8 Years.)	N. 60° E			S. 4° E.			S. 4° W.			S. 10° W.			S. 34° W.			S. 69° W.			S. 81° W.			S. 86° W.			N. 84° W.			N. 10° E.			N. 9° E.			N.		
Average diurnal velocity of wind in miles. 7-8 Years.	47·6			68·0			83·0			108·5			118·0			110·3			104·3			84·8			72·6			67·6			64·1			50·0		

65.—CHIKALDA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	..	1	1	3	6	9	8	5	13	8	5	13	15	5	20	11	7	18	4	4	8	7	7	14	5	7	12	1	8	9	2	8	10	3	13	16
North-East	...	...	...	1	...	1	4	...	4	3	1	4	2	3	5	1	...	1	1	...	1	1	1	2	2	1	3	3	3	6	1	3	4	2	...	2
East	...	...	...	...	...	...	...	...	...	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	5	...	5	...	...	...	...	...	...
South-East	5	3	8	2	...	2	3	...	3	3	...	3	1	...	1	...	...	...	1	...	1	...	...	...	...	1	1	8	2	10	2	...	2	1	...	1
South	13	8	21	6	5	11	3	3	6	2	...	2	1	...	1	..	1	1	1	1	2	...	1	1	...	...	...	2	...	2	3	1	4	7	2	9
South-West	9	2	11	11	5	16	1	3	4	2	2	4	...	2	2	3	2	5	3	2	5	1	1	2	1	1	2	...	...	...	1	...	1	8	2	10
West	1	3	4	...	1	1	4	7	11	...	6	6	1	8	9	3	4	7	6	8	14	2	4	6	4	3	7	...	...	...	...	...	...	...	1	1
North-West	1	7	8	2	11	13	6	12	18	7	11	18	11	13	24	7	11	18	14	14	28	21	17	38	14	13	27	1	4	5	3	6	9	4	6	10
Calm	2	7	9	3	...	3	2	1	3	4	4	8	...	...	...	5	5	10	1	2	3	...	...	...	4	4	8	11	14	25	18	12	30	6	7	13
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	49			36			45			43			71			59			68			83			66			24			22			24		
Resultant Direction	S. 23° W.			S. 76° W.			N. 51° W.			N. 34° W.			N. 32° W.			N. 40° W.			N. 58° W.			N. 41° W.			N. 38° W.			N. 59° E.			N. 12° W.			N. 59° W.		
Mean diurnal velocity of wind in miles	119·3			126·9			177·9			183·3			235·5			186·2			230·8			235·2			230·8			87·7			56·7			84·2		
Average Resultant Percentage (7·8 Years.)	23			29			37			52			65			66			65			71			61			50			22			11		
Average Resultant Direction (7·8 Years.)	S. 56° W.			N. 74° W.			N. 46° W.			N. 38° W.			N. 35° W.			N. 44° W.			N. 60° W.			N. 34° W.			N. 22° W.			N. 2° E.			N. 9° W.			N. 66° W.		
Average diurnal velocity of wind in miles (7·8 Years.)	110·9			137·0			166·5			190·3			221·1			225·8			234·9			237·6			217·8			129·2			94·5			4·4		

66.—BULDANA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	6	6	3	6	9	8	8	16	5	7	12	5	2	7	3	4	7	2	4	6	6	7	13	4	7	11	5	7	12	1	6	7	1	9	10
North-East	3	2	5	1	2	3	3	2	5	4	2	6	2	...	2	...	...	...	...	...	...	...	...	...	3	1	4	8	12	20	5	10	15	4	10	14
East	4	5	9	9	2	11	3	1	4	2	1	3	1	1	2	...	1	1	...	...	...	...	...	...	...	1	1	12	6	18	8	11	19	11	8	19
South-East	5	4	9	5	2	7	1	...	1	1	1	2	1	1	2	...	1	1	...	...	...	...	...	...	...	...	...	4	1	5	11	1	12	10	2	12
South	11	2	13	..	4	4	...	2	2	...	...	...	...	...	...	1	1	2	...	1	1	...	...	...	...	1	1	1	...	1	3	1	4	3	...	3
South-West	5	8	13	3	2	5	1	2	3	2	1	3	...	5	5	4	7	11	6	2	8	2	3	5	3	1	4	1	2	3	1	...	1	2	...	2
West	1	...	1	2	3	5	6	9	15	5	8	13	9	13	22	9	7	16	13	13	26	9	7	16	9	7	16	...	...	...	...	...	...	...	...	...
North-West	2	4	6	5	7	12	9	7	16	11	10	21	13	9	22	13	9	22	10	11	21	14	14	28	11	12	23	...	3	3	1	1	2	...	2	2
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	25			13			53			58			66			66			78			79			68			62			61			57		
Resultant Direction	S. 17° E.			N. 8° E.			N. 38° W.			N. 38° W.			N. 62° W.			N. 72° W.			N. 73° W.			N. 53° W.			N. 50° W.			N. 56° E.			N. 81° E.			N. 76° E.		
Mean diurnal velocity of wind in miles	155·1			147·0			210·3			234·9			316·3			224·3			243·8			250·4			220·3			127·8			116·7			115·1		
Average Resultant Percentage (10 Years.)	26			31			51			53			57			66			69			70			62			54			59			49		
Average Resultant Direction (10 Years.)	N. 69° E.			N. 5° W.			N. 29° W.			N. 35° W.			N. 54° W.			N. 78° W.			N. 85° W.			N. 67° W.			N. 52° W.			N. 23° E.			N. 66° E.			N. 78° E.		
Average diurnal velocity of wind in miles (4·5 Years.)	31·3			55·1			87·3			229·3			313·3			78·4			248·0			222·1			209·8			126·6			129·6			120·3		

67.—AKOLA *(2 observations daily)*.

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	...	...	...	4	2	6	3	...	3	...	2	2	1	3	4	1	2	3	3	2	5	3	3	6	1	4	5	...	...	...	3	...	3
North-East	3	...	3	1	...	1	4	...	4	4	2	6	...	...	...	...	1	1	...	...	...	...	1	1	2	2	4	8	5	13	8	3	11	12	10	22
East	5	1	6	8	2	10	1	...	1	4	2	6	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	5	5	10	4	4	8	5	7	12
South-East	2	4	6	3	4	7	...	1	1	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	2	1	3	1	1	2
South	4	1	5	1	...	1	...	1	1	...	1	1	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	3	4	7	4	3	7	4	3	7	1	1	2	1	2	3	4	6	10	6	4	10	2	1	3	2	1	3	...	...	...	...	...	...	...	...	...
West	1	2	3	2	3	5	6	10	16	4	4	8	6	9	15	10	7	17	8	9	17	8	11	19	5	8	13	...	...	...	...	...	...	...	...	...
North-West	1	1	2	1	1	2	6	11	17	9	16	25	20	14	34	12	7	19	15	13	28	17	16	33	12	12	24	1	...	1	...	...	...	...	...	...
Calm	12	17	29	8	15	23	6	3	9	5	3	8	3	4	7	3	5	8	1	3	4	1	...	1	6	4	10	15	17	32	16	22	38	10	13	23
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	16			17			51			45			75			64			75			83			63			38			31			54		
Resultant Direction	S. 17° E.			S. 26° E.			N. 63° W.			N. 37° W.			N. 59° W.			N. 75° W.			N. 70° W.			N. 58° W.			N. 51° W.			N. 54° E.			N. 72° E.			N. 59° E.		
Mean diurnal velocity of wind in miles	68·1			57·1			109·1			143·2			244·9			188·7			221·5			207·7			167·2			84·5			70·7			64·0		
Average Resultant Percentage (10 Years.)	35			28			43			55			72			73			76			80			65			32			51			55		
Average Resultant Direction (10 Years.)	N. 59° E.			N. 11° E.			N. 38° W.			N. 51° W.			N. 52° W.			N. 74° W.			N. 80° W.			N. 78° W.			N. 75° W.			N. 15° E.			N. 64° E.			N. 66° E.		
Average diurnal velocity of wind in miles. 10-11 Years.	82·8			92·8			103·8			132·7			205·7			210·6			199·8			189·2			136·0			76·9			82·2			74·0		

68.—AMRAOTI *(2 observations daily)*.

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	1	2	...	...	...	3	...	3	...	1	1	2	1	3	...	2	2	1	1	2	1	...	1	1	4	5	...	...	...	1	...	1	...	3	3
North-East	4	2	6	5	1	6	5	3	8	6	3	9	2	1	3	2	4	6	...	1	1	...	...	...	1	1	2	7	7	14	9	6	15	19	8	27
East	5	2	7	3	...	3	3	1	4	1	3	4	1	1	2	1	2	3	...	1	1	3	1	4	2	3	5	13	11	24	8	8	16	6	5	11
South-East	6	6	12	9	...	9	3	1	4	3	1	4	3	...	3	1	...	1	...	1	1	...	...	...	1	1	2	7	6	13	10	12	22	6	6	12
South	3	3	6	1	1	2	2	...	2	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	1	1	...	1	1	...	...	...
South-West	5	7	12	3	5	8	9	10	19	7	4	11	3	6	9	11	9	20	10	6	16	10	4	14	7	8	15	...	1	1	...	1	1	...	...	...
West	...	2	2	2	8	10	1	8	9	3	7	10	13	12	25	12	8	20	19	17	36	13	15	28	13	5	18	1	1	2	...	...	...	...	...	...
North-West	1	2	3	1	10	11	4	8	12	9	11	20	7	10	17	3	5	8	1	4	5	4	11	15	4	7	11	3	...	3	...	1	1	...	3	3
Calm	6	6	12	4	3	7	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	4	4	2	1	3	...	6	6
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	26			18			30			35			62			52			79			72			48			62			68			64		
Resultant Direction	S. 26° E.			S. 79° W.			S. 87° W.			N. 62° W.			N. 77° W.			S. 85° W.			S. 83° W.			N. 88° W.			N. 88° W.			N. 88° E.			S. 83° E.			N. 67° E.		
Mean diurnal velocity of wind in miles	41·8			61·6			88·2			127·4			172·2			184·7			216·7			145·0			148·6			81·3			68·1			74·5		
Average Resultant Percentage (10 Years.)	16			5			33			34			52			67			74			71			46			42			58			58		
Average Resultant Direction (10 Years.)	N. 70° E.			N. 6° E.			N. 85° W.			N. 52° W.			N. 51° W.			N. 62° W.			N. 72° W.			N. 68° W.			N. 60° W.			N. 49° E.			N. 78° E.			N. 85° E.		
Average diurnal velocity of wind in miles. 9-10 Years.	74·3			88·4			94·2			105·0			141·8			177·6			180·5			147·1			106·5			63·8			65·5			69·4		

69.—MAKHLA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	1	1	4	2	6	...	1	1	3	1	4	...	...	...
North-East	1	1	2	2	...	2	2	...	2	6	...	6	1	2	3	...	...	...
East	1	...	1	...	1	1	...	...	...	1	1	2	...	1	1	...	...	...
South-East	3	9	12	2	4	6	3	...	3	2	3	5	1	...	1	1	...	1
South	11	6	17	3	5	8	2	3	5	6	6	12	3	2	5	7	9	16
South-West	5	5	10	11	11	22	2	6	8	7	5	12	8	8	16	10	11	21
West	...	6	6	3	2	5	4	9	13	3	4	7	2	5	7	2	3	5
North-West	4	9	13	7	4	11	14	10	24	5	10	15	13	11	24	9	7	16
Calm	...	1	1	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	1	...	1
Resultant Percentage	40			50			55			30			52			61		
Resultant Direction	S. 27° W.			S. 51° W.			N. 70° W.			S. 63° W.			N. 79° W.			S. 56° W.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...		
Average Resultant Percentage (4 Years.)	36			39			46			41			45			51		
Average Resultant Direction (4 Years.)	N. 54° W.			N. 62° W.			N. 43° W.			N. 58° W.			N. 54° W.			N. 66° W.		
Average diurnal velocity of wind in miles (Years.)	...			...			...			...			...			...		

	JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	1	...	1	4	2	6	1	...	1	...	...	...
North-East	...	...	...	1	...	1	1	...	1	8	4	12	6	1	7	3	...	3
East	...	...	...	...	...	...	...	...	...	2	...	2	2	1	3	1	...	1
South-East	...	2	2	1	...	1	1	...	1	3	1	4	3	...	3	5	...	5
South	13	3	16	6	6	12	...	2	2	6	5	11	4	5	9	5	6	11
South-West	11	18	29	14	8	22	13	15	28	5	10	15	8	11	19	12	11	23
West	3	4	7	2	3	5	...	3	3	1	3	4	2	5	7	2	8	10
North-West	3	2	5	2	7	9	3	...	3	2	6	8	4	7	11	3	5	8
Calm	...	...	...	5	7	12	6	5	11	...	...	...	...	...	...	...	1	1
Variable	1	2	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	73			53			60			13			35			55		
Resultant Direction	S. 41° W.			S. 50° W.			S. 52° W.			S. 58° W.			S. 59° W.			S. 48° W.		
Mean diurnal velocity of wind in miles	...			...			...			...			...			...		
Average Resultant Percentage (4 Years.)	55			53			55			51			33			43		
Average Resultant Direction (4 Years.)	S. 75° W.			S. 79° W.			S. 85° W.			N. 50° W.			N. 73° W.			N. 76° W.		
Average diurnal velocity of wind in miles (Years.)	...			...			...			...			...			...		

70.—NEEMUCH (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	2	6	8	...	...	...	3	2	5	...	...	...	...	...	...	...	...	...	1	1	2	...	...	...	...	1	1	...	...	...	1	1	2
North-East	7	...	7	3	1	4	2	...	2	2	1	3	...	1	1	...	...	...	2	...	2	...	...	...	2	1	3	3	3	6	5	...	5	6	1	7
East	6	1	7	5	...	5	3	...	3	...	...	...	1	...	1	...	...	...	...	2	2	...	...	...	1	...	1	4	3	7	4	3	7	7	1	8
South-East	8	2	10	5	...	5	1	1	2	1	...	1	1	...	1	...	2	2	...	...	...	...	...	...	...	...	...	6	4	10	7	5	12	7	3	10
South	6	12	18	7	6	13	3	...	3	1	...	1	3	...	3	2	2	4	2	1	3	...	...	...	2	2	4	2	6	6	9	15	6	14	20
South-West	2	10	12	4	9	13	14	21	35	8	22	30	19	23	42	25	21	46	18	16	34	17	22	39	13	15	28	8	7	15	6	11	17	2	5	7
West	...	1	1	...	...	...	3	4	7	2	1	3	4	6	10	1	2	3	5	7	12	6	2	8	6	6	12	2	5	7	...	2	2	...	2	2
North-West	2	4	6	2	6	8	5	5	10	13	4	17	3	1	4	2	3	5	4	5	9	7	6	13	8	6	14	4	6	10	2	...	2	2	4	6
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	39			18			63			56			81			82			70			77			66			21			51			36		
Resultant Direction	S. 13° E.			S. 21° W.			S. 58° W.			S. 84° W.			S. 53° W.			S. 48° W.			S. 64° W.			S. 70° W.			S. 76° W.			S. 29° W.			S. 7° E.			S. 23° E.		
Mean diurnal velocity of wind in miles	233·3			242·9			269·7			288·6			404·3			320·4			329·7			308·6			266.1			200·0			238·7			203·4		
Average Resultant Percentage (6 Years.)	21			28			40			58			67			77			79			81			56			35			20			22		
Average Resultant Direction (6 Years.)	S. 3° W.			S. 54° W.			S. 76° W.			S. 84° W.			S. 77° W.			S. 68° W.			S. 64° W.			S. 63° W.			N. 89° W.			N. 59° W.			S. 80° E.			S. 15° E.		
Average diurnal velocity of wind in miles (4-5 Years.)	168·0			191·1			203·9			231·1			307·6			351·2			285·5			281·7			231·8			168·0			170·7			178·3		

71.—NOWGONG (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	6	9	15	6	13	19	1	7	8	6	10	16	4	5	9	5	7	12	...	4	4	2	3	5	3	8	11	6	4	10	2	13	15	2	14	16
North-East	2	4	6	3	3	6	4	1	5	2	...	2	1	1	2	...	1	1	4	2	6	1	3	4	3	6	9	...	5	5	4	3	7	3	3	6
East	7	6	13	7	2	9	5	3	8	2	...	2	...	...	...	...	4	4	1	3	4	4	4	8	3	2	5	3	3	6	2	1	3	1	2	3
South-East	5	1	6	4	2	6	3	1	4	1	...	1	...	...	...	...	3	3	2	1	3	3	2	5	3	1	4	1	...	1	...	...	...	1	...	1
South	2	1	3	...	...	...	2	1	3	2	...	2	1	...	1	...	...	...	2	1	3	...	1	1	...	2	2	1	1	2	4	...	4	1	...	1
South-West	1	3	4	2	...	2	4	1	5	...	...	...	2	2	4	3	1	4	7	5	12	2	4	6	8	2	10	4	...	4	4	1	5	6	...	6
West	4	3	7	1	3	4	8	13	21	8	14	22	18	19	37	19	6	25	14	11	25	15	11	26	6	3	9	11	5	16	9	5	14	12	6	18
North-West	4	4	8	5	5	10	4	4	8	8	6	14	5	4	9	3	8	11	1	3	4	3	2	5	3	6	9	1	7	8	3	7	10	5	5	10
Calm	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	...	1	1	1	1	2	1	...	1	4	6	10	2	...	2	...	1	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	26			45			28			62			75			55			42			32			24			32			43			49		
Resultant Direction	N. 22° E.			N. 11° E.			N. 64° W.			N. 48° W.			N. 74° W.			N. 62° W.			S. 84° W.			N. 82° W.			N. 35° W.			N. 46° W.			N. 41° W.			N. 45° W.		
Mean diurnal velocity of wind in miles	35·1			32·9			59·8			56·9			75·0			77·7			86·8			65·0			40·3			24·8			17·5			22·1		
Average Resultant Percentage (6 Years.)	30			29			31			50			46			41			41			36			24			40			36			31		
Average Resultant Direction (6 Years.)	N. 8° W.			N. 35° W.			N. 60° W.			N. 73° W.			N. 69° W.			N. 73° W.			S. 72° W.			S. 76° W.			N. 69° W.			N. 40° W.			N.			N. 31° W.		
Average diurnal velocity of wind in miles (6-7 Years.)	36·0			45·9			61·5			77·7			88·8			111·9			110·3			83·8			61·5			39·1			27·9			30·0		

72.—SUTNA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	3	6	4	4	8	2	1	3	3	2	5	3	2	5	3	5	8	...	...	...	1	4	5	...	8	8	5	18	23	4	13	17	1	9	10
North-East	3	5	8	4	7	11	...	3	3	1	...	1	1	2	3	1	3	4	1	1	2	1	3	4	...	4	4	1	4	5	1	4	5	...	3	3
East	9	5	14	7	3	10	11	6	17	4	...	4	...	...	...	1	2	3	5	6	11	4	6	10	6	4	10	4	3	7	7	3	10	2	3	5
South-East	2	2	4	4	...	4	1	...	1	2	...	2	...	...	...	...	...	...	1	...	1	2	...	2	...	...	...	...	...	...	1	...	1	3	...	3
South	4	2	6	2	...	2	2	...	2	2	...	2	2	...	2	...	1	1	1	1	2	2	...	2	2	...	2	1	...	1	4	...	4	5	...	5
South-West	2	2	4	...	1	1	...	1	1	1	1	2	...	...	...	3	...	3	3	1	4	3	2	5	2	1	3	2	...	2	1	...	1	2	...	2
West	3	3	6	1	6	7	6	13	19	10	12	22	17	14	31	19	13	32	17	18	35	14	13	27	12	7	19	10	1	11	11	1	12	11	2	13
North-West	4	6	10	4	6	10	7	7	14	6	15	21	8	13	21	3	5	8	1	3	4	3	3	6	2	3	5	6	3	9	...	9	9	4	11	15
Calm	1	3	4	2	1	3	2	...	2	1	...	1	...	...	...	...	1	1	2	1	3	1	...	1	6	3	9	2	2	4	1	...	1	3	3	6
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	16			33			24			60			78			61			44			34			26			51			37			34		
Resultant Direction	N. 43° E.			N. 19° E.			N. 40° W.			N. 64° W.			N. 65° W.			N. 69° W.			S. 87° W.			N. 76° W.			N. 49° W.			N. 15° W.			N. 13° W.			N. 48° W.		
Mean diurnal velocity of wind in miles	104·1			113·8			162·7			146·4			207·2			215·7			277·1			182·5			115·6			89·6			95·4			98·6		
Average Resultant Percentage (6-8 Years.)	37			42			44			51			52			50			45			41			32			48			33			44		
Average Resultant Direction (6-8 Years.)	N. 15° W.			N. 42° W.			N. 52° W.			N. 58° W.			N. 53° W.			N. 59° W.			N. 81° W.			N. 70° W.			N. 56° W.			N. 33° W.			N. 25° W.			N. 35° W.		
Average diurnal velocity of wind in miles (6-8 Years.)	94·0			113·2			131·2			166·0			195·2			232·8			225·2			184·1			154·6			105·2			76·3			83·6		

73.—INDORE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	3	3	4	8	12	6	3	9	6	5	11	4	2	6	1	3	4	1	...	1	2	2	4	4	4	8	...	1	1	1	4	5	1	5	6
North-East	3	3	6	9	7	16	4	1	5	4	1	5	...	2	2	...	1	1	2	...	2	...	...	...	...	...	...	9	8	17	7	7	14	6	6	12
East	6	1	7	8	1	9	5	1	6	5	1	6	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	7	7	14	4	3	7	6	1	7
South-East	8	1	9	3	1	4	2	1	3	2	...	2	1	...	1	...	...	...	1	...	1	...	...	...	...	1	1	7	7	14	10	4	14	13	9	22
South	4	2	6	...	1	1	...	...	...	...	...	...	1	...	1	3	3	6	3	1	4	3	...	3	...	2	2	1	...	1	6	2	8	2	1	3
South-West	5	7	12	3	4	7	5	4	9	2	3	5	1	4	5	6	8	14	9	15	24	5	13	18	10	9	19	1	3	4	2	...	2	...	...	...
West	2	6	8	1	3	4	3	10	13	2	8	10	8	14	22	10	6	16	7	9	16	12	7	19	4	6	10	...	...	...	...	1	1	...	...	...
North-West	1	4	5	...	2	2	5	10	15	8	12	20	14	6	20	8	8	16	7	3	10	9	9	18	12	7	19	2	2	4	...	4	4	3	3	6
Calm	2	4	6	...	1	1	1	1	2	1	...	1	1	3	4	2	1	3	1	3	4	...	...	...	...	1	1	4	3	7	...	5	5	...	6	6
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	17			36			38			48			65			61			64			72			61			49			36			43		
Resultant Direction	S. 13° W.			N. 39° E.			N. 51° W.			N. 35° W.			N. 66° W.			W.			S. 72° W.			N. 89° W.			N. 82° W.			N. 86° E.			S. 86° E.			E		
Mean diurnal velocity of wind in miles	65·0			64·0			95·4			121·1			145·1			122·4			139·8			149·4			133·0			51·7			45·8			43·5		
Average Resultant Percentage (6 Years.)	10			11			29			56			60			77			79			82			56			37			56			30		
Average Resultant Direction (6 Years.)	N. 61° E.			N. 9° W.			N. 47° W.			N. 62° W.			N. 72° W.			S. 87° W.			S. 80° W.			S 88° W.			N. 67° W.			N. 31° E.			N. 74 E.°			N. 89° E.		
Average diurnal velocity of wind in miles (5 Years.)	58·7			77·7			90·9			115·4			154·3			175·5			164·6			153·0			129·1			56·4			49·7			45·8		

y

74.—BICKANEER (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	2	5	7	...	4	4	...	4	4	3	2	5	...	2	2	...	...	...
North-East	7	10	17	5	6	11	5	5	10	4	1	5	...	2	2	...	2	2
East	7	2	9	7	2	9	9	2	11	6	...	6	1	...	1	...	...	...
South-East	3	...	3	8	...	8	3	...	3	1	...	1	...	1	1	...	1	1
South	2	...	2	2	1	3	...	1	1	2	1	3	2	...	2	...	2	2
South-West	6	3	9	3	3	6	8	4	12	7	6	13	15	9	24	20	16	36
West	3	1	4	...	3	3	2	6	8	3	9	12	8	12	20	8	9	17
North-West	...	7	7	...	3	3	4	7	11	2	9	11	2	5	7	1	...	1
Calm	1	3	4	3	6	9	...	2	2	2	2	4	3	...	3	1	...	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	25			23			13			32			65			81		
Resultant Direction	N. 30° E.			N. 86° E.			N. 29° W.			N. 80° W.			S. 74° W.			S. 58° W.		
Mean diurnal velocity of wind in miles	73·9			70·8			110·2			120·7			181·5			194·0		
Average Resultant Percentage 4-6 Years.	21			8			21			46			51			73		
Average Resultant Direction 4-6 Years.	N. 44° E.			N. 13° W.			S. 77° W.			S. 70° W.			S. 75° W.			S. 51° W.		
Average diurnal velocity of wind in miles. 4-6 Years.	65·1			89·1			105·7			123·7			162·7			193·2		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	1	1	1	1	2	2	2	4	...	4	4	1	7	8	...	7	7
North-East	1	2	3	1	2	3	2	1	3	...	6	6	1	4	5	2	7	9
East	2	2	4	...	1	1	2	2	4	2	2	4	1	...	1	7	1	8
South-East	1	3	4	...	1	1	1	2	3	3	2	5	4	...	4	5	...	5
South	5	4	9	7	5	12	...	1	1	5	1	6	3	...	3	8	...	8
South-West	15	13	28	17	14	31	10	8	18	6	5	11	8	3	11	3	2	5
West	2	5	7	4	4	8	8	7	15	4	4	8	1	3	4	1	2	3
North-West	...	...	...	1	2	3	4	3	7	4	2	6	1	7	8	1	4	5
Calm	5	1	6	...	1	1	1	4	5	7	5	12	10	6	16	4	8	12
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	54			65			41			15			18			13		
Resultant Direction	S. 32° W.			S. 45° W.			S. 79° W.			S. 60° W.			N. 70° W.			N. 77° E.		
Mean diurnal velocity of wind in miles	162·0			170·3			105·8			76·4			55·5			42·6		
Average Resultant Percentage 6 Years.	39			50			43			47			10			23		
Average Resultant Direction 6 Years.	S. 45° W.			S. 41° W.			S. 53° W.			S. 70° W.			S. 28° W.			N. 55° E.		
Average diurnal velocity of wind in miles. 6-7 Years.	165·1			153·4			130·4			101·8			56·8			57·6		

75.—JEYPORE (*4 observations daily*).

	January.					February.					March.					April.					May.					June.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	4	2	3	6	15	8	4	4	10	26	9	1	4	9	23	8	1	3	8	20	6	1	2	2	11	3	1	2	1	7
North-East	5	1	1	3	10	10	4	2	3	19	6	5	...	3	14	8	1	1	4	14	2	1	...	3	6	...	...	2	2	4
East	5	7	...	6	18	3	7	...	1	11	8	4	2	4	18	7	5	...	1	13	1	...	2	1	4	...	...	1	4	5
South-East	4	10	6	3	23	3	8	2	4	17	1	6	1	...	8	...	3	...	...	3	2	1	...	...	3	1	...	2	1	4
South	...	4	2	1	7	...	1	2	1	4	...	3	2	1	6	...	3	...	...	3	...	2	1	2	5	1	1	1	2	5
South-West	4	3	5	3	15	...	...	4	...	4	1	3	3	2	9	...	4	...	...	4	2	2	3	...	7	7	3	4	4	18
West	4	4	4	3	15	...	...	1	3	4	2	3	4	3	12	1	2	7	5	15	4	7	9	12	32	8	4	7	7	26
North-West	5	...	10	6	21	4	3	13	6	26	4	5	15	9	33	5	11	19	10	45	13	17	13	11	54	10	21	11	8	50
Calm	...	...	...	...	...	...	1	...	...	1	...	1	...	...	1	1	...	...	2	3	1	...	1	...	2	...	...	...	1	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	3					36					32					49					62					57				
Resultant { Direction	N. 16° E.					N. 16° E.					N. 12° W.					N. 25° W.					N. 57° W.					N. 69° W.				
Mean diurnal velocity of wind in miles	85·2					121·5					179·0					163·4					214·0					165·2				
Average Resultant. { Percentage	17					28					26					52					53					48				
Average Resultant. { Direction	N. 7° E.					N. 3° E.					N.					N. 38° W.					N. 45° W.					N. 63° W.				
3 Years.																														
Average diurnal velocity of wind in miles 3 Years.	87·5					105·5					151·8					147·7					182·0					176·2				

	July.					August.					September.					October.					November.					December.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	1	2	...	1	4	2	2	2	2	8	14	6	2	9	31	9	7	4	12	32	9	7	3	8	27	13	8	7	10	38
North-East	2	3	3	...	8	1	...	2	...	3	5	1	3	6	15	11	2	6	10	29	5	1	4	5	15	3	3	...	2	8
East	3	4	4	5	16	1	2	4	2	9	1	1	2	1	5	2	2	1	1	6	...	3	...	...	3	1	3	1	1	6
South-East	2	1	2	1	6	4	2	1	3	10	1	4	1	...	6	2	...	1	2	5	2	2	...	2	6	2	2	2	2	8
South	...	1	...	2	3	...	...	1	2	3	1	1	1	3	6	2	3	2	3	10	...	...	...	...	...	...	2	2	1	5
South-West	3	...	4	2	9	3	2	3	4	12	2	1	1	...	4	2	5	3	1	11	1	3	4	2	10	2	4	2	2	10
West	8	5	10	13	36	5	6	9	8	28	1	1	3	4	9	1	2	4	1	8	4	4	3	2	13	7	5	6	7	25
North-West	10	13	8	6	37	11	17	9	10	47	5	15	16	6	42	1	7	9	1	18	9	9	15	11	44	3	3	11	6	23
Calm	2	2	...	1	5	4	...	...	...	4	...	...	1	1	2	1	3	1	...	5	...	1	1	...	2	...	1	...	...	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	39					46					52					35					55					42				
Resultant { Direction	N. 62° W.					N. 64° W.					N. 20° W.					N. 2° E.					N. 30° W.					N. 36° W.				
Mean diurnal velocity of wind in miles	177·4					150·9					110·2					81·7					78·8					88·4				
Average Resultant. { Percentage	15					48					49					56					43					33				
Average Resultant. { Direction	N. 29° W.					N. 63° W.					N. 31° W.					N. 10° W.					N. 3° E.					N. 13° W.				
3 Years.																														
Average diurnal velocity of wind in miles 3 Years.	153·9					135·1					124·7					95·6					73·1					85·3				

76.—SAMBHAR (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	7	3	10	8	3	11	2	4	6	2	2	4	1	1	2	...	1	1	1	3	4	...	1	1	...	1	1	3	5	8	8	5	13	3	2	5
North-East	6	...	6	7	2	9	4	...	4	1	...	1	1	2	3	...	...	...	1	1	2	...	...	...	...	2	2	2	3	5	1	2	3	8	1	9
East	1	...	1	6	2	8	2	2	4	1	...	1	...	...	...	1	4	5	3	4	7	...	4	4	3	1	4	...	...	...	1	...	1	...	...	...
South-East	5	6	11	1	3	4	2	...	2	6	1	7	2	1	3	...	...	...	1	...	1	2	...	2	1	2	3	3	4	7	2	...	2	1	2	3
South	5	4	9	1	...	1	7	2	9	1	1	2	3	...	3	1	2	3	1	1	2	4	3	7	1	2	3	4	2	6	...	1	1	1	4	5
South-West	4	2	6	1	2	3	1	2	3	1	4	5	...	5	5	2	6	8	1	12	13	3	6	9	...	...	...	1	1	2	2	3	5	2	1	3
West	...	8	8	2	9	11	5	14	19	14	10	24	20	18	38	24	13	37	18	9	27	20	12	32	19	19	38	6	2	8	7	12	19	3	10	13
North-West	3	8	11	2	6	8	7	4	11	3	11	14	4	4	8	2	4	6	3	...	3	2	5	7	6	3	9	12	14	26	6	6	12	7	10	17
Calm	...	...	...	...	1	1	1	3	4	1	1	2	...	...	...	...	...	...	2	1	3	...	...	...	...	...	...	...	...	...	3	1	4	5	2	7
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	11			31			34			52			69			70			48			63			62			42			53			38		
Resultant Direction	N. 82° W.			N. 5° W.			N. 79° W.			N. 82° W.			N. 89° W.			S. 85° W.			S. 82° W.			S. 77° W.			N. 84° W.			N. 48° W.			N. 56° W.			N. 53° W.		
Mean diurnal velocity of wind in miles	120·3			112·5			156·3			170·7			289·6			281·4			224·2			221·7			164·5			106·8			87·0			65·9		
Average Resultant Percentage (3·4 Years.)	5			24			24			60			49			65			37			64			53			69			40			24		
Average Resultant Direction (3·4 Years.)	N. 31 W.			N. 71° W.			N. 73° W.			N. 80° W.			N. 83° W.			S. 78° W.			S. 69° W.			S. 71° W.			N. 76° W.			N. 71° W.			N. 46° W.			N. 54° W.		
Average diurnal velocity of wind in miles (3·4 Years.)	?			?			?			?			269·5			298·8			225·0			200·7			181·2			115·6			83·4			81·9		

77.—AJMERE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	1	3	4	1	...	1	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	2	2	2	1	3	4	3	4
North-East	8	5	13	9	4	13	7	5	12	2	1	3	...	1	1	...	...	...	4	3	7	...	3	3	1	2	3	2	9	11	6	3	9	4	3	7
East	...	...	...	...	...	...	1	...	1	2	...	2	...	...	...	...	...	...	...	2	2	...	...	...	1	1	2	1	1	2	...	...	...	2	...	2
South-East	5	4	9	4	1	5	1	...	1	7	1	8	2	1	3	1	1	2	2	2	4	1	...	1	...	1	1	9	5	14	4	1	5	9	1	10
South	8	4	12	7	7	14	9	5	14	...	1	1	4	1	5	2	1	3	1	...	1	1	1	2	...	...	...	4	...	4	2	1	3	5	6	11
South-West	2	4	6	...	2	2	2	1	3	1	2	3	1	1	2	3	2	5	1	2	3	3	1	4	2	...	2	3	1	4	3	1	4	1	1	2
West	...	3	3	1	4	5	6	13	19	13	20	33	19	21	40	23	21	44	20	19	39	25	24	49	16	15	31	4	7	11	5	8	13	3	7	10
North-West	3	7	10	1	5	6	1	4	5	...	2	2	3	5	8	1	4	5	2	1	3	1	2	3	10	6	16	6	6	12	4	12	16	2	3	5
Calm	4	4	8	5	2	7	2	2	4	5	2	7	1	...	1	...	1	1	1	2	3	...	...	...	...	4	4	2	...	2	5	3	8	4	7	11
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	9			5			25			45			74			83			54			82			68			5			35			11		
Resultant Direction	S. 13° E.			S. 54° E.			S. 75° W.			S. 81° W.			S. 87° W.			S. 85° W.			N. 88° W.			S. 89° W.			N. 72° W.			N. 60° W.			N. 54° W.			S. 8° W.		
Mean diurnal velocity of wind in miles	41·5			40·9			89·7			118·3			232·0			204·5			150·8			?			129·1			69·2			57·8			48·9		
Average Resultant Percentage (15 Years.)	8			8			28			52			63			68			64			56			44			23			10			15		
Average Resultant Direction (15 Years.)	N. 82° E.			S. 77° W.			S. 61° W.			S. 74° W.			S. 60° W.			S. 61° W.			S. 62° W.			S. 70° W.			S 80° W.			N. 76° W.			N. 32° E.			N. 84° E.		
Average diurnal velocity of wind in miles (7·8 Years.)	46·8			65·8			86·2			132·1			183·7			198·7			166·5			117·9			117·0			69·2			39·2			38·8		

78.—MOUNT ABU (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	3	4	3	6	9	4	4	8	2	1	3	...	2	2	1	...	1	1	1	2	...	...	...	2	2	4	1	4	5	1	5	6	1	10	11
North-East	2	6	8	5	5	10	2	1	3	2	...	2	1	...	1	1	...	1	2	1	3	...	...	...	3	3	6	6	8	14	6	9	15	9	6	15
East	1	...	1	2	...	2	2	...	2	...	1	1	2	...	2	...	2	2	1	1	2	...	...	...	3	...	3	9	5	14	5	2	7	7	3	10
South-East	2	...	2	2	...	2	...	...	...	1	...	1	2	...	2	1	1	2	1	...	1	...	...	...	3	3	6	3	1	4	4	1	5	1	...	1
South	3	1	4	1	1	2	4	2	6	1	1	2	2	4	6	4	4	8	4	6	10	2	5	7	2	...	2	3	2	5	2	2	4	...	...	...
South-West	14	7	21	6	5	11	8	10	18	4	10	14	10	15	25	17	15	32	15	14	29	17	16	33	5	7	12	2	1	3	5	4	9	3	2	5
West	7	12	19	4	6	10	9	13	22	15	17	32	12	8	20	5	8	13	3	7	10	12	10	22	10	11	21	4	...	4	3	2	5	4	5	9
North-West	1	2	3	1	2	3	1	...	1	4	...	4	2	1	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	4	3	7	1	1	2	1	...	1	1	...	1	1	...	1	4	1	5	...	...	...	2	4	6	3	10	13	4	5	9	6	5	11
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	47			21			52			70			66			73			60			88			32			34			17			31		
Resultant Direction	S. 73° W.			N. 53° W.			S. 76° W.			S. 83° W.			S. 60° W.			S. 46° W.			S. 43° W.			S. 56° W.			S. 70° W.			N. 77° E.			N. 75° E.			N. 27° E.		
Mean diurnal velocity of wind in miles	122·1			125·9			165·3			191·4			257·1			227·8			286·7			269·3			131·9			81·6			107·2			89·5		
Average Resultant Percentage (6 Years.)	6			21			35			56			71			76			70			76			19			4			24			7		
Average Resultant Direction (6 Years.)	N. 4° E.			S. 81° W.			S. 81° W.			S. 70° W.			S. 55° W.			S. 38° W.			S. 47° W.			S. 52° W.			S. 57° W.			N. 53° E.			S. 87° E.			N. 86° E.		
Average diurnal velocity of wind in miles (4-5 Years.)	107·5			131·0			162·9			189·7			233·0			262·3			259·1			267·0			159·4			93·1			99·0			92·3		

79.—PACHBUDRA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	3	3	...	3	3	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	1	1	1	1	2	3	...	3	2	4	6
North-East	5	8	13	2	4	6	...	1	1	...	1	1	...	1	1	...	...	...	3	2	5	...	...	...	...	1	1	10	9	19	14	13	27	13	16	29
East	9	2	11	9	3	12	3	1	4	...	1	1	1	2	3	...	...	...	...	...	...	1	...	1	2	1	3	3	2	5	14	4	18			
South-East	1	2	3	2	1	3	2	2	4	1	1	2	2	...	2	3	4	7	3	4	7	...	...	...	...	3	3	4	4	8	1	...	1	...	...	...
South	...	...	...	1	...	1	1	...	1	1	1	2	3	5	8	3	1	4	...	2	2	...	...	...	1	1	2	1	1	2	...	...	...	...	...	...
South-West	2	4	6	1	4	5	2	13	15	9	9	18	18	13	31	21	20	41	17	19	36	30	29	59	17	20	37	8	8	16	6	8	14	...	...	...
West	...	4	4	...	...	...	2	7	9	1	9	10	2	6	8	1	4	5	3	3	6	1	2	3	7	2	9	2	4	6	...	1	1	...	...	...
North-West	1	7	8	1	4	5	1	1	2	2	4	6	...	3	3	1	1	2	...	...	...	...	...	...	4	2	6	3	3	6	1	5	6	2	7	9
Calm	13	1	14	12	9	21	20	6	26	16	4	20	5	...	5	1	...	1	5	1	6	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	23			21			29			44			62			79			59			99			72			1			32			74		
Resultant Direction	N. 36° E.			N. 70° E.			S. 48° W.			S. 65° W.			S. 44° W.			S. 40° W.			S. 39° W.			S. 47° W.			S. 56° W.			N. 37° E.			N. 32° E.			N. 44° E.		
Mean diurnal velocity of wind in miles	?			?			66·5			51·6			352·9			330·8			236·5			319·7			109·2			?			?			?		
Average Resultant Percentage (4-5 Years.)	22			6			21			45			72			84			61			83			59			27			36			38		
Average Resultant Direction (4-5 Years.)	N. 61° E.			N. 76° E.			S. 24° W.			S. 45° W.			S. 42° W.			S. 40° W.			S. 36° W.			S. 43° W.			S. 50° W.			S. 43° W.			N. 52° E.			N. 52° E.		
Average diurnal velocity of wind in miles (3-4 Years.)	?			?			94·2			120·9			55·8			311·7			236·6			244·5			130·4			?			?			40·5		

80.—JACOBABAD (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	8	6	14	7	4	11	6	5	11	4	1	5	6	7	13	2	...	2	1	5	6	2	1	3	...	...	...	3	1	4	6	...	6	3	1	4
North-East	4	1	5	4	2	6	7	...	7	2	4	6	6	2	8	...	...	...	3	1	4	4	...	4	2	2	4	2	...	2	2	1	3	1	2	3
East	3	3	6	6	4	10	3	3	6	10	2	12	4	3	7	5	1	6	8	5	13	9	9	18	4	2	6	1	1	2	...	...	...	2	...	2
South-East	2	...	2	3	3	6	3	7	10	8	7	15	3	2	5	6	10	16	5	7	12	7	9	16	6	5	11	4	3	7	1	1	2	2	...	2
South	...	1	1	...	...	...	3	4	7	3	8	11	...	3	3	6	12	18	5	8	13	3	7	10	9	8	17	4	4	8	...	2	2	5	1	6
South-West	1	1	2	...	2	2	...	4	4	...	2	2	...	2	2	3	5	8	1	1	2	2	1	3	4	5	9	2	2	4	2	3	5	6	4	10
West	1	9	10	4	3	7	1	4	5	1	3	4	5	6	11	6	...	6	5	1	6	...	...	...	...	...	...	3	...	3	3	1	4	3	1	4
North-West	7	4	11	4	7	11	7	4	11	2	3	5	7	6	13	2	1	3	1	2	3	...	...	...	...	...	...	8	...	8	13	6	19	6	3	9
Calm	5	6	11	...	3	3	1	...	1	...	...	...	...	...	...	...	1	1	2	1	3	4	4	8	2	5	7	4	20	24	3	16	19	3	19	22
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	37			31			12			34			33			52			31			56			56			9			38			19		
Resultant Direction	N. 21° W.			N. 8° E.			N. 19° E.			S. 60° E.			N. 15° W.			S. 7° E.			S. 51° E.			S. 60° E.			S. 20° E.			S. 34° W.			N. 50° W.			S. 80° W.		
Mean diurnal velocity of wind in miles	60·5			85·9			114·8			104·0			123·0			119·0			111·6			90·7			70·8			51·3			48·3			42·4		
Average Resultant Percentage	34			46			38			23			34			49			57			52			38			19			18			27		
Average Resultant Direction	N. 5° W.			N. 27° E.			N. 67° E.			N. 86° E.			S. 60° E.			S. 32° E.			S. 50° E.			S. 56° E.			S. 45° E.			S. 47° E.			N. 2° E.			N. 2° W.		
5·6 Years. Average diurnal velocity of wind in miles	44·8			76·6			97·4			104·4			125·1			118·8			139·3			100·5			78·0			62·0			42·9			37·1		
4·7 Years.																																				

81.—HYDERABAD (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	7	3	10	8	7	15	4	2	6	...	...	...	2	1	3	...	...	...	2	1	3	...	...	...	...	1	1	3	8	11	9	9	18	3	2	5
North-East	16	16	32	5	4	9	1	...	1	...	...	...	...	...	...	...	...	...	1	2	3	...	...	...	1	1	2	1	...	1	1	4	5	2	1	3
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	1	1	2	...	...	...	1	1	2	...	...	...	...	...	...	1	1	2	1	2	3
South	1	...	1	...	...	...	...	...	...	3	3	6	8	21	12	8	20	9	7	16	5	3	8	8	4	12	7	5	12	1	...	1	...	...	...
South-West	...	1	1	3	5	8	11	11	22	24	19	43	15	19	34	16	18	34	16	19	35	26	26	52	21	24	45	3	5	8	3	3	6	1	3	4
West	4	5	9	4	1	5	8	9	17	3	4	7	1	...	1	1	...	1	1	...	1	...	1	1	...	...	...	7	3	10	...	...	...	1	1	1
North-West	3	5	8	7	10	17	5	8	13	1	1	2	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	5	5	10	12	9	21	20	20	40
Calm	...	1	1	1	1	2	1	1	2	2	3	5	...	2	2	...	3	3	2	2	4	...	...	...	1	...	1	5	5	10	4	4	8	4	2	6
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	60			57			65			84			79			84			66			95			87			36			56			67		
Resultant Direction	N. 11° E.			N. 30° W.			S. 89° W.			S. 51° W.			S. 32° W.			S. 28° W.			S. 31° W.			S. 39° W.			S. 36° W.			N. 87° W.			N. 26° W.			N. 42° W.		
Mean diurnal velocity of wind in miles	215·1			236·9			238·5			261·5			262·5			299·3			249·4			?			?			154·4			199·3			192·5		
Average Resultant Percentage	56			44			48			51			71			83			76			79			71			47			48			66		
Average Resultant Direction	N. 15° W.			N. 34° W.			N. 87° W.			S. 55° W.			S. 45° W.			S. 36° W.			S. 42° W.			S. 42° W.			S. 42° W.			S. 57° W.			N. 26° W.			N. 10° W.		
6 Years. Average diurnal velocity of wind in miles	169·8			177·5			207·8			253·8			311·8			366·1			264·8			347·9			296·0			199·6			168·8			167·7		
5·7 Years.																																				

82.—KURRACHEE (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	4	...	4	3	...	3	3	...	3	...	...	...	..	1	1	...	...	...	...	1	1	...	...	...	...	...	...	4	...	4	11	...	11	4	1	5
North-East	11	3	14	9	4	13	4	...	4	...	...	...	...	..	...	1	...	1	1	...	1	..	...	...	...	...	...	7	...	7	11	3	14	16	1	17
East	8	4	12	4	2	6	1	...	1	...	...	...	1	..	1	...	...	..	1	...	1	..	...	...	...	...	...	2	...	2	1	2	3	8	6	14
South-East	2	1	3	1	1	2	1	...	1	...	...	..	2	1	3	...	...	...	2	1	3	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2
South	...	2	2	...	...	...	...	...	...	...	...	...	2	3	5	2	2	4	1	1	2	...	...	...	1	2	3	...	2	2	1	1	2	...	4	4
South-West	1	10	11	3	12	15	9	20	29	18	18	36	15	11	26	6	7	13	10	14	24	9	17	26	15	16	31	7	20	27	4	19	23	...	10	10
West	...	8	8	5	7	12	8	11	19	11	12	23	9	13	22	10	20	39	12	12	24	20	14	34	12	11	23	4	9	13	...	4	4	1	6	7
North-West	5	3	8	3	2	5	5	...	5	1	...	1	2	2	4	2	1	3	4	2	6	2	...	2	2	1	3	7	...	7	2	1	3	1	2	3
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	13			18			65			92			74			84			71			91			87			50			18			21		
Resultant Direction	N. 19° E.			N. 69° W.			S. 73° W.			S. 63° W.			S. 62° W.			S. 78° W.			S. 70° W.			S. 73° W.			S. 64° W.			S. 77° W.			N. 63° W.			N. 59° E.		
Mean diurnal velocity of wind in miles	225·1			232·1			280·6			362·4			388·0			411·5			439·6			443·9			366·4			202·2			194·6			193·9		
Average Resultant Percentage (14-17 Years.)	26			23			56			68			80			79			79			79			78			59			19			21		
Average Resultant Direction (14-17 Years.)	N. 50° E.			N. 61° W.			N. 84° W.			N. 87° W.			S. 86° W.			S. 81° W.			W.			N. 87° W.			N. 89° W.			S. 88° W.			N. 42° W.			N. 55° E.		
Average diurnal velocity of wind in miles (5-8 Years.)	234·0			253·3			289·0			336·5			435·9			456·1			432·7			412·0			342·3			229·6			193·4			221·4		

83.—BHUJ (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	10	8	18	7	11	18	6	4	10	7	1	8	...	...	...	...	...	...	1	...	1	...	...	...	1	...	1	5	4	9	4	5	9	2	6	8
North-East	5	12	17	8	8	16	3	1	4	1	1	2	...	...	...	1	...	1	1	...	1	3	...	...	...	...	...	4	1	5	9	14	23	12	14	26
East	10	2	12	6	1	7	2	4	6	...	...	...	1	...	1	...	...	...	...	1	1	...	...	...	...	...	...	8	10	18	9	3	12	13	8	21
South-East	1	...	1	...	...	...	1	...	1	...	2	2	1	1	2	1	3	4	...	...	...	...	...	...	...	...	...	2	3	5	2	1	3	2	...	2
South	...	...	...	1	1	2	...	1	1	...	...	...	2	...	2	4	3	7	1	3	4	...	1	1	1	3	4	1	5	6	...	1	1	...	...	...
South-West	...	2	2	...	1	1	3	2	5	1	3	4	7	6	13	8	11	19	4	7	11	10	9	19	7	5	12	2	1	3	4	2	6	...	...	...
West	1	3	4	2	2	4	7	12	19	9	15	24	14	20	34	13	13	26	20	19	39	20	20	40	15	17	32	3	4	7	1	2	3	...	...	1
North-West	4	3	7	4	4	8	9	7	16	12	8	20	6	4	10	3	...	3	3	1	4	1	1	2	5	4	9	5	3	8	...	1	1	2	2	4
Calm	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	1	1	2	1	..	1	1	1	2	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	58			59			55			71			78			72			78			91			79			20			49			75		
Resultant Direction	N. 24° E.			N. 14° E.			N. 52° W.			N. 63° W.			S. 83° W.			S. 62° W.			S. 81° W.			S. 77° W.			S. 84° W.			N. 58° E.			N. 50° E.			N. 53° E.		
Mean diurnal velocity of wind in miles	62·6			137·3			197·6			278·9			404·2			352·6			402·9			?			248·4			134·7			128·4			115·8		
Average Resultant Percentage (6 Years.)	57			40			51			69			80			85			83			87			71			27			60			60		
Average Resultant Direction (6 Years.)	N. 24° E.			N. 4° E.			N. 44° W.			N. 73° W.			S. 88° W.			S. 73° W.			S. 82° W.			S. 83° W.			N. 88° W.			N. 39° W.			N. 44° E.			N. 34° E.		
Average diurnal velocity of wind in miles (6-7 Years.)	137·9			161·7			202·3			269·7			373·8			390·5			408·7			363·2			269·5			140·2			109·3			119·5		

84.—RAJKOT (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	4	3	7	4	8	12	6	4	10	8	3	11	...	...	...	...	...	...
North-East	16	10	26	13	11	24	3	1	4	1	1	2	...	1	1	...	...	...
East	4	4	8	4	2	6	2	...	2	...	1	1	...	...	...	2	1	3
South-East	...	...	...	...	...	...	1	...	1	...	1	1	...	...	...	...	3	3
South	...	...	...	...	...	...	...	...	...	...	...	...	4	...	4	5	4	9
South-West	1	1	2	..	...	...	1	3	4	...	...	...	8	9	17	9	10	19
West	1	7	8	2	3	5	5	9	14	5	10	15	10	14	24	12	6	18
North-West	3	6	9	5	4	9	13	14	27	16	14	30	8	6	14	2	3	5
Calm	2	...	2	...	...	...	...	...	...	...	...	...	1	1	2	...	3	3
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	52			66			67			78			73			61		
Resultant Direction	N. 19° E.			N. 18° E.			N. 47° W.			N. 45° W.			S. 83° W.			S. 55° W.		
Mean diurnal velocity of wind in miles	144·2			164·1			228·5			352·8			352·8			296·0		
Average Resultant Percentage (5-6 Years.)	55			45			55			67			75			74		
Average Resultant Direction (5-6 Years.)	N. 21° E.			N. 1° W.			N. 42° W.			N. 52° W.			N. 85° W.			S. 75° W.		
Average diurnal velocity of wind in miles. 4-5 Years.	127·4			154·6			212·2			282·1			353·5			403·3		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	...	...	...	2	1	3	6	3	9	4	7	11
North-East	...	1	1	...	...	...	...	...	...	8	8	16	13	9	22	10	9	19
East	...	...	...	...	...	...	...	...	...	10	11	21	6	7	13	12	13	25
South-East	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...
South	...	1	1	...	...	...	2	1	3	...	...	...	1	...	1	...	...	...
South-West	8	8	16	7	5	12	4	1	5	...	...	...	1	3	4	...	...	...
West	19	18	37	21	19	40	15	15	30	1	1	2	...	1	1	...	...	...
North-West	3	2	5	3	7	10	8	10	18	3	3	6	...	6	6	3	1	4
Calm	1	1	2	...	...	...	1	3	4	7	6	13	3	1	4	2	1	3
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	84			90			78			52			54			72		
Resultant Direction	S. 81° W.			S. 89° W.			N. 82° W.			N. 56° E.			N. 39° E.			N. 53° E.		
Mean diurnal velocity of wind in miles	375·4			323·9			211·9			120·3			117·4			107·2		
Average Resultant Percentage (6 Years.)	76			79			63			38			62			55		
Average Resultant Direction (6 Years.)	S. 77° W.			S. 80° W.			N. 79° W.			N. 7° W.			N. 47° E.			N. 40° E.		
Average diurnal velocity of wind in miles. 4-6 Years.	386·7			303·8			223·6			138·6			118·5			113·8		

85.—DEESA (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.
North	6	7	6	14	33	9	7	9	13	38	3	5	2	5	15	7	4	1	1	13	...	...	1	...	1	...	...	...	...	...
North-East	18	10	1	7	36	12	12	1	5	30	5	4	...	1	10	6	2	...	...	8	1	...	1	1	3	...	1	...	1	2
East	2	6	...	2	10	4	3	...	...	7	1	1	...	...	2	...	...	...	...	...	1	...	1	1	3	...	...	1	...	1
South-East	1	2	...	1	4	1	1	...	...	2	3	2	2	...	7	...	2	2	...	4	4	3	...	1	8	1	2	2	1	6
South	...	...	2	1	3	...	1	1	...	2	1	...	1	1	3	1	...	3	...	4	4	7	2	3	16	6	7	7	9	29
South-West	1	1	7	2	11	1	...	6	3	10	3	4	11	7	25	4	4	9	8	25	13	14	16	19	62	19	16	17	16	68
West	...	1	5	1	7	...	...	4	1	5	6	8	10	12	36	5	7	14	20	46	5	5	10	6	26	4	3	3	3	13
North-West	2	2	9	1	14	1	4	7	6	18	8	6	4	4	22	7	11	1	1	20	3	2	...	...	5	...	...	...	...	...
Calm	...	...	...	...	...	..		...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	48					55					47					58					69					81				
Resultant Direction	N. 14° E.					N. 5° E.					N. 78° W.					N. 83° W.					S. 47° W.					S. 34° W.				
Mean diurnal velocity of wind in miles	230·7					225·2					206·7					249·7					354·0					375·7				
Average Resultant Percentage (15-17 Years.)	39					36					35					53					76					72				
Average Resultant Direction (15-17 Years.)	N. 3° W.					N. 28° W.					N. 88° W.					N. 89° W.					S. 55° W.					S. 36° W.				
Average diurnal velocity of wind in miles (4·5 Years.)	208·0					219·0					219·2					237·7					327·3					417·8				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.	4½ hours.	10½ hours.	16½ hours.	22½ hours.	Total.
North	...	1	...	1	2	...	...	...	...	...	...	...	1	...	1	...	2	5	...	7	1	...	5	6	12	...	2	9	9	20
North-East	...	...	1	1	2	...	...	...	...	...	...	...	...	2	2	6	6	7	6	25	15	14	6	10	45	22	10	6	15	53
East	...	...	1	...	1	...	...	...	...	...	...	1	...	1	2	14	8	5	14	41	8	10	2	2	22	8	13	1	2	24
South-East	...	...	...	1	1	...	...	...		...	3	3	1	2	9	7	6	6	8	27	2	1	3	2	8	...	4	...	...	4
South	4	3	4	6	17	3	2	2	1	8	11	...	3	10	24	1	4	3	2	10	2	4	3	3	12	...	...	1	...	1
South-West	20	18	18	17	73	12	16	21	22	71	8	6	7	8	29	2	1	3	...	6	...	...	4	2	6	...	...	2	...	2
West	3	4	2	2	11	16	10	8	7	41	6	11	13	7	37	...	1	...	1	2	1	...	2	...	3	...	...	3	1	4
North-West	1	2	2	1	6	...	3	...	1	4	2	9	5	...	16	...	3	2	...	5	...	...	4	4	8	...	...	8	3	11
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	78					88					58					55					47					66				
Resultant Direction	S. 46° W.					S. 60° W.					S. 58° W.					S. 86° E.					N. 59° E.					N. 40° E.				
Mean diurnal velocity of wind in miles	324·2					317·1					179·4					174·9					219·9					201·6				
Average Resultant Percentage (15-16 Years.)	75					72					50					16					31					37				
Average Resultant Direction (15-16 Years.)	S. 40° W.					S. 47° W.					S. 65° W.					N. 62° W.					N. 33° E.					N. 17° E.				
Average diurnal velocity of wind in miles (5 Years.)	340·6					289·0					198·8					162·4					187·3					196·4				

86.—SURAT (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	4	7	8	4	12	2	...	2	4	...	4	2	...	2	...	...	...	...	...	...	...	...	...	1	...	1	1	...	1	1	2	3	2	5	7
North-East	10	1	11	6	2	8	8	...	8	2	...	2	2	...	2	...	1	1	...	...	...	...	...	...	...	...	...	7	9	16	12	8	20	7	11	18
East	9	...	9	6	...	6	3	1	4	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	...	1	1	16	8	24	12	6	18	20	7	27
South-East	2	...	2	1	...	1	...	...	...	...	...	...	...	...	...	1	1	2	1	...	1	...	...	...	1	...	1	1	1	2	1	...	1	2	...	2
South	1	...	1	...	...	...	...	...	...	1	2	3	1	3	4	3	2	5	...	1	1	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...
South-West	...	10	10	1	3	4	5	12	17	8	14	22	19	22	41	18	23	41	21	24	45	16	29	45	14	23	37	3	5	8	1	3	4	...	1	1
West	1	9	10	...	4	4	4	9	13	4	7	11	1	3	4	4	3	7	6	4	10	12	1	13	7	3	10	...	2	2	...	5	5	...	1	1
North-West	3	7	10	5	14	19	4	9	13	11	7	18	4	3	7	2	...	2	1	...	1	3	1	4	5	3	8	3	4	7	2	5	7	...	5	5
Calm	2	...	2	1	1	2	5	...	5	...	...	...	2	...	2	1	...	1	...	...	...	...	...	...	2	...	2	...	1	1	1	1	2	...	1	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	22			51			40			63			71			80			92			90			75			42			46			67		
Resultant { Direction	N. 26° W.			N. 16° W.			N. 79° W.			S. 89° W.			S. 56° W.			S. 46° W.			S. 52° W.			S. 59° W.			S. 63° W.			N. 69° E.			N. 47° E.			N. 60° E.		
Mean diurnal velocity of wind in miles	118·2			129·6			155·6			211·7			321·1			318·3			405·6			293·0			203·8			111·6			125·7			128·8		
Average Resultant { Percentage	31			29			38			43			75			83			82			80			60			14			24			35		
Average Resultant { Direction (6 Years.)	N. 18° E.			N. 13° W.			N. 51° W.			N. 76° W.			S. 56° W.			S. 43° W.			S. 46° W.			S. 58° W.			S. 68° W.			N. 20° W.			N. 58° E.			N. 53° E.		
Average diurnal velocity of wind in miles (3-6 Years.)	123·8			128·8			161·3			196·4			302·7			368·2			375·3			329·4			218·9			122·3			142·3			119·7		

87.—MALEGAON (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	2	2	5	5	10	1	...	1	1	1	1	2	...	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	2	3
North-East	1	1	2	5	...	5	4	1	5	10	1	11	2	...	2	...	...	...	...	...	...	...	...	...	1	2	3	5	5	10	5	5	10	4	12	16
East	...	...	...	3	1	4	5	...	5	5	1	6	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	5	3	8	3	1	4	...	2	2
South-East	1	1	2	1	...	1	1	...	1	...	1	1	...	1	1	1	1	2	...	...	...	...	...	...	...	...	...	5	1	6	5	1	6	1	1	2
South	4	1	5	...	...	...	...	1	1	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	1	...	1
South-West	5	8	13	2	2	4	...	4	4	...	...	...	1	...	1	3	1	4	1	1	2	1	1	2	...	...	...	...	3	3	1	...	1	2	...	2
West	1	4	5	...	5	5	1	10	11	...	...	...	6	2	8	12	13	25	26	30	56	18	26	44	13	22	35	...	6	6	...	1	1	...	...	...
North-West	1	2	3	4	9	13	8	8	16	11	23	34	13	26	39	4	12	16	2	...	2	3	2	5	2	3	5	...	4	4	1	1	2	...	...	...
Calm	18	14	32	13	9	22	7	2	9	3	4	7	9	1	10	6	3	9	2	...	2	9	2	11	14	3	17	16	9	25	15	20	35	22	14	36
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant { Percentage	29			25			42			56			72			63			95			79			61			15			21			27		
Resultant { Direction	S. 48° W.			N. 38° W.			N. 38° W.			N. 17° W.			N. 50° W.			N. 78° W.			W.			N. 88° W.			N. 81° W.			N. 67° E.			N. 78° E.			N. 52° E.		
Mean diurnal velocity of wind in miles	88·3			109·9			157·5			209·8			244·4			221·2			319·4			233·0			189·1			103·8			101·3			87·2		
Average Resultant { Percentage	14			20			36			52			63			68			73			52			43			41			50			27		
Average Resultant { Direction (6 Years.)	N. 66° E.			N. 2° E.			N. 13° W.			N. 22° W.			N. 42° W.			N. 86° W.			S. 87° W.			N. 82° W.			N. 56° W.			N. 47° E.			N. 74° E.			S. 89° E.		
Average diurnal velocity of wind in miles (6-7 Years.)	97·6			128·0			161·4			194·0			255·3			297·2			290·6			245·0			190·1			119·0			101·8			91·5		

88.—BOMBAY (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.				
	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	6	1	2	16	25	15	4	5	14	38	18	6	2	9	35
North-East	14	11	...	5	30	7	12	...	1	20	5	7	...	...	12
East	7	14	...	...	21	2	5	...	...	7	2	5	...	...	7
South-East	2	4	...	...	6	...	2	...	...	2	1	3	...	...	4
South	...	1	...	...	1	...	...	...	...	...	...	...	...	1	1
South-West	...	...	1	2	3	...	...	...	...	...	...	...	...	...	...
West	1	...	16	1	18	...	...	3	1	4	1	1	8	5	15
North-West	1	...	12	7	20	4	5	20	12	41	4	9	21	16	50
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	44					72					66				
Resultant Direction	N. 13° E.					N. 7° W.					N. 23° W.				
Mean diurnal velocity of wind in miles	222·0					265·8					263·2				
Average Resultant Percentage (16 Years.)	56					58					56				
Average Resultant Direction (16 Years.)	N. 12° W.					N. 14° W.					N. 38° W.				
Average diurnal velocity of wind in miles (14 Years.)	243·2					258·2					277·2				

	APRIL.					MAY.					JUNE.				
	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	8	1	...	3	12	8	1	...	2	11	1	...	...	1	2
North-East	4	2	...	...	6	3	1	...	...	4	1	...	...	...	1
East	1	1	...	...	2	...	...	...	1	1	1	2	...	1	4
South-East	5	2	...	...	7	...	...	...	...	...	8	8	...	4	20
South	7	10	..	5	22	3	5	...	2	10	4	5	5	5	19
South-West	3	4	4	4	15	9	10	8	11	38	10	10	12	10	42
West	1	2	13	5	21	3	6	13	5	27	5	5	11	8	29
North-West	1	8	13	13	35	5	8	10	10	33	...	...	2	1	3
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	38					59					60				
Resultant Direction	N. 86° W.					W.					S. 36° W.				
Mean diurnal velocity of wind in miles	279·3					277·3					397·4				
Average Resultant Percentage (16 Years.)	58					74					68				
Average Resultant Direction (16 Years.)	N. 61° W.					N. 85° W.					S. 57° W.				
Average diurnal velocity of wind in miles (14 Years.)	271·3					246·4					396·4				

	JULY.					AUGUST.					SEPTEMBER.				
	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	...	...	...	1	...	2	3	...	...	1	2	3
North-East	...	1	...	...	1	1	...	...	...	1	1	2	...	1	4
East	...	...	1	...	1	...	3	...	...	3	...	1	...	...	1
South-East	2	...	...	...	2	3	2	...	...	5	5	3	...	...	8
South	2	2	1	1	6	2	2	2	1	7	1	5	1	2	9
South-West	5	8	7	10	30	6	7	5	3	21	5	6	2	5	18
West	22	19	21	19	81	13	10	13	19	55	13	9	19	17	58
North-West	...	1	1	1	3	6	6	11	6	29	5	4	7	3	19
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	84					67					63				
Resultant Direction	S. 76° W.					S. 89° W.					S. 84° W.				
Mean diurnal velocity of wind in miles	489·8					275·7					292·3				
Average Resultant Percentage (16-17 Years.)	83					79					56				
Average Resultant Direction (16-17 Years.)	S. 65° W.					S. 70° W.					S. 84° W.				
Average diurnal velocity of wind in miles (14 Years.)	460·5					381·7					285·3				

	OCTOBER.					NOVEMBER.					DECEMBER.				
	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.	6 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	1	2	9	14	2	1	3	20	26	3	...	5	26	34
North-East	14	14	....	5	33	18	15	...	2	35	18	22	3	2	45
East	8	8	1	3	20	9	14	...	...	23	9	9	...	...	18
South-East	4	5	1	2	12	1	...	...	...	1	1	...	...	...	1
South	1	...	...	2	3	...	...	...	...	...	...	...	...	...	...
South-West	1	1	2	1	5	...	...	...	...	...	...	...	1	...	1
West	1	...	8	2	11	...	...	7	3	10	...	...	1	...	1
North-West	...	2	17	7	26	...	...	20	5	25	...	...	21	3	24
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	36					59					70				
Resultant Direction	N. 25° E.					N. 17° E.					N. 21° E.				
Mean diurnal velocity of wind in miles	236·1					243·8					261·5				
Average Resultant Percentage (16-17 Years.)	33					47					55				
Average Resultant Direction (16-17 Years.)	N. 25° W.					N. 4° W.					N. 3° W.				
Average diurnal velocity of wind in miles (14 Years.)	231·4					236·8					235·6				

89.—POONA (*4 observations daily*).

	January.					February.					March.					April.					May.					June.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	2	...	...	2	3	4	1	...	8	2	3	1	...	6	...	5	1	...	6	...	...	...	...	...	...	...	2	...	2
North-East	6	9	4	7	26	3	4	...	...	7	1	2	...	...	3	...	2	2	...	4	...	1	..	...	1	...	...	...	...	...
East	4	8	12	9	33	1	2	3	1	7	...	3	1	...	4	1	...	1	1	3	...	...	...	...	...	...	...	...	...	...
South-East	...	3	4	1	8	...	2	2	...	4	...	2	1	1	4	1	1	...	...	2	1	...	...	1	2	1	...	...	...	1
South	1	...	1	...	2	...	1	1	...	2	...	...	2	...	2	...	...	2	...	2	...	...	...	...	...	1	...	...	1	2
South-West	3	2	3	2	10	1	2	5	1	9	...	...	2	...	2	5	1	4	4	14	5	3	9	5	22	9	15	14	12	50
West	3	5	5	9	22	8	9	12	12	41	16	13	17	20	66	14	7	11	17	49	20	17	13	20	70	17	11	14	14	56
North-West	2	2	2	3	9	5	4	4	12	25	10	7	6	8	31	9	14	9	8	40	4	9	8	4	25	2	4	...	3	9
Calm	12	...	...	...	12	7	...	...	2	9	1	...	...	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	20					48					70					70					84					85				
Resultant Direction	N. 61° E.					N 69° W.					N. 74° W.					N. 73° W.					N. 89° W.					S. 73° W.				
Mean diurnal velocity of wind in miles	171·6					134·1					213·1					265·7					379·4					322·9				
Average Resultant Percentage 17 Years.	24					21					42					49					66					73				
Average Resultant Direction 17 Years.	S. 63° E.					N. 28° W.					N. 41° W.					N. 35° W.					N. 55° W.					S. 79° W.				
Average diurnal velocity of wind in miles. 3-4 Years.	137·0					157·2					202·0					246·9					345·8					386·5				

	July.					August.					September.					October.					November.					December.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	2	4	...	...	...	1	1	4	...	2	2	8
North-East	...	...	...	...	...	...	1	...	...	1	...	1	1	1	3	3	3	10	2	18	8	4	5	11	28	11	8	8	15	42
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	5	9	5	3	22	9	14	15	7	45	9	19	15	8	51
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	7	4	3	15	3	11	7	1	22	...	2	3	...	5
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	3	1	1	7	...	...	1	...	1	...	..	...	...	...
South-West	10	10	8	14	42	4	7	4	4	19	7	4	4	6	21	3	3	3	5	14	1	...	2	2	5	...	...	1	1	2
West	20	19	21	16	76	24	18	20	23	85	20	20	17	18	75	3	4	3	6	16	3	1	...	4	8	...	...	...	...	...
North-West	1	2	2	1	6	3	5	7	4	19	3	5	8	5	21	4	2	4	3	13	2	...	...	1	3	4	2	2	4	12
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	3	...	...	...	3	1	...	...	...	1	2	...	...	...	2
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	91					90					85					9					59					70				
Resultant Direction	S. 77° W.					W.					N. 89° W.					S. 81° E.					N. 88° E.					N. 61° E.				
Mean diurnal velocity of wind in miles	432·7					324·4					311·4					157·2					144·0					138·8				
Average Resultant Percentage 16-17 Years.	85					82					70					17					45					56				
Average Resultant Direction 16-17 Years.	S. 79° W.					S. 84° W.					N. 89° W.					N. 38° E.					S. 83° E.					S. 78° E.				
Average diurnal velocity of wind in miles. 4-5 Years.	415·8					334·7					286·7					139·3					135·6					139·8				

90.—SHOLAPUR (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	1	3	4	7	5	12	4	6	10	3	1	4	1	2	3	...	..	...	6	3	9	...	...	...	...	1	1	...	...	...	1	...	1
North-East	1	5	6	1	..	1	8	8	16	4	3	7	3	1	4	...	...	...	...	...	...	...	1	1	...	...	...	8	5	13	11	14	25	14	12	26
East	6	9	15	...	4	4	2	1	3	1	3	4	1	7	8	...	...	...	...	...	...	...	...	...	...	...	...	12	18	30	11	7	18	11	9	20
South-East	19	9	28	16	8	24	4	3	7	3	2	5	2	4	6	...	3	3	...	...	...	...	...	...	2	...	2	5	2	7	1	2	3	1	2	3
South	1	2	3	2	4	6	1	...	1	2	1	3	...	...	...	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	1	3	4	2	5	7	1	1	2	3	5	8	2	1	3	17	16	33	16	18	34	2	5	7	6	10	16	2	1	3	...	...	...	...	...	...
West	...	2	2	...	...	...	...	1	1	1	...	1	3	4	7	9	7	16	14	11	25	18	13	31	14	8	22	...	1	1	1	3	4	...	2	2
North-West	2	1	3	2	4	6	5	7	12	11	10	21	10	5	15	2	1	3	1	2	3	5	8	13	8	10	18	2	2	4	5	4	9	3	6	9
Calm	...	...	...	4	...	4	3	5	8	1	...	1	..	1	1	...	...	...	...	..	...	...	1	1	...	2	2	2	1	3	1	...	1	1	...	1
Variable	...	...	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	60			41			42			33			25			75			90			75			74			62			59			64		
Resultant Direction	S. 60° E.			S. 33° E.			N. 19° E.			N. 27° W.			N. 23° W.			S. 60° W.			S. 67° W.			N. 73° W.			W.			N. 81° E.			N. 51° E.			N. 54° E.		
Mean diurnal velocity of wind in miles	172·5			144·5			153·2			203·6			260·2			260·1			317·5			239·1			235·6			158·5			164·1			143·7		
Average Resultant Percentage (6 Years.)	54			26			12			20			61			71			77			78			70			34			59			51		
Average Resultant Direction (6 Years.)	S. 63° E.			S. 31° E.			N. 23° E.			N. 10° E.			N. 38° W.			N. 81° W.			S. 80° W.			N. 84° W.			N. 66° W.			N. 36° E.			N. 68° E.			S. 86° E.		
Average diurnal velocity of wind in miles. 5-6 Years.	157·5			149·2			159·2			178·5			241·0			160·8			102·9			205·3			205·8			142·3			158·9			142·6		

91.—RATNAGIRI (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	4	7	...	3	3	3	6	9	1	2	3	2	2	4	1	...	1	...	...	...	2	2	4	...	...	...	1	4	5	5	3	8	5	2	7
North-East	10	...	10	2	...	2	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	...	1	1	...	...	...	1	...	1	7	7	14	20	3	23
East	4	...	4	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	1	3	...	...	...	8	1	9	8	2	10	4	...	4
South-East	5	...	5	2	...	2	..	...	...	...	...	...	...	...	...	3	...	3	...	...	...	1	...	1	...	...	...	4	2	6	3	1	4	1	...	1
South	..	.	..	2	...	2	2	...	2	...	...	...	...	1	1	5	3	8	2	1	3	2	...	2	2	1	3	4	2	6	2	..	2	...	...	...
South-West	4	2	6	7	4	11	7	3	10	12	5	17	12	3	15	14	16	30	11	10	21	7	3	10	16	9	25	6	1	7	4	2	6	1	3	4
West	2	10	12	7	10	17	8	9	17	8	10	18	9	13	22	4	11	15	17	18	35	9	14	23	10	16	26	2	6	8	...	13	13	...	19	19
North-West	3	15	18	8	11	19	11	13	24	9	13	22	8	12	20	2	..	2	1	2	3	8	10	18	2	4	6	5	15	20	1	2	3	..	4	4
Calm	...	...	..	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	..	...	..	...	...	...
Variable	...	...	...	...	..	..	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	38			64			72			77			76			75			88			63			84			22			19			37		
Resultant Direction	N. 37° W.			N. 79° W.			N. 68° W.			N. 82° W.			N. 82° W.			S. 51° W.			S. 73° W.			N. 79° W.			S. 71° W.			N. 70° W.			N. 17° E.			N. 9° W.		
Mean diurnal velocity of wind in miles	?			?			?			?			?			?			?			199·4			219·9			172·0			220·0			249·3		
Average Resultant Percentage (6 Years.)	32			55			61			67			64			72			76			70			59			29			32			35		
Average Resultant Direction (6 Years.)	N. 52° W.			N. 58° W.			N. 80° W.			N. 76° W.			N. 69° W.			S. 52° W.			S. 51° W.			S. 68° W.			S. 86° W.			S. 76° W.			N. 17° W.			N. 8° W.		
Average diurnal velocity of wind in miles. Years.	...			...			...			...			...			...			...			...			...			...			...			...		

92.—Belgaum (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	...	1	1	...	1	5	...	5	6	4	10	2	...	2	...	...	...	...	...	...	...	...	...	...	...	...	3	3	6	...	2	2	1	3	4
North-East	5	1	6	7	4	11	8	6	14	4	8	12	6	3	9	...	...	...	...	...	...	...	...	...	...	...	...	7	6	13	14	17	31	11	13	24
East	14	12	26	10	7	17	6	6	12	7	12	19	13	19	32	...	3	3	...	...	...	...	...	...	...	...	...	8	5	13	15	7	22	14	9	23
South-East	7	8	15	8	6	14	2	1	3	4	3	7	5	5	10	2	...	2	...	...	...	...	...	...	...	...	...	2	2	4	1	2	3	2	2	4
South	...	1	1	...	2	2	1	1	2	2	1	3	1	2	3	3	3	6	...	...	...	...	...	...	1	...	1	2	4	6	...	1	1	...	...	...
South-West	3	5	8	...	5	5	1	8	9	...	...	...	1	...	1	14	12	26	12	8	20	10	13	23	10	15	25	3	4	7	...	...	...	...	...	...
West	...	2	2	...	2	2	4	7	11	4	...	4	1	2	3	10	12	22	19	23	42	11	17	28	17	15	32	3	7	10	...	...	...	...	1	1
North-West	1	1	2	2	...	2	4	2	6	3	2	5	2	...	2	1	...	1	...	...	...	10	1	11	2	...	2	3	...	3	...	...	...	...	2	2	4
Calm	...	1	1	...	2	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	1	1	2
Variable	..	...	...	...	...	..	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	54			50			14			51			65			74			93			85			90			14			84			71		
Resultant Direction	S. 72° E.			S. 79° E.			N. 16° E.			N. 55° E.			S. 89° E.			S. 56° W.			S. 76° W.			S. 81° W.			S. 71° W.			N. 65° E.			N. 66° E.			N. 62° E.		
Mean diurnal velocity of wind in miles	110·2			94·3			117·3			141·4			153·6			173·2			191·8			131·5			148·4			97·5			88·1			86·2		
Average Resultant Percentage (16-17 Years.)	50			23			8			25			73			86			90			89			82			72			67			70		
Average Resultant Direction (16-17 Years.)	S. 71° E.			S. 78° E.			S. 88° W.			S. 88° W.			S. 86° W.			S. 73° W.			S. 70° W.			S. 79° W.			N. 84° W.			N. 88° E.			N. 84° E.			S. 87° E.		
Average diurnal velocity of wind in miles (6-8 Years.)	95·0			86·0			104·1			106·4			165·4			183·7			186·5			169·0			146·0			94·2			98·3			99·6		

93.—Karwar (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...		1	1	...	3	3	4	...	4	2	1	3	1	...	1	...	...	...	...	...	...	1	5	6	1	2	3	...	...	...
North-East	27	10	37	9	...	9	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	5	...	5	13	...	13	24	7	31	31	3	34
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	6	10	16	4	2	6	...	1	1
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	1	2	3	...	...	...	4	2	6	8	4	12	2	3	5	23	23	46	20	19	39	6	4	10	8	9	17	3	3	6	...	...	...	...	...	...
West	1	8	9	17	14	31	18	10	28	14	14	28	9	13	22	5	6	11	6	8	14	13	4	17	12	9	21	7	3	10	1	5	6	...	7	7
North-West	2	11	13	2	14	16	9	18	27	8	9	17	16	15	31	...	...	...	4	4	8	12	23	35	5	12	17	1	10	11	...	13	13	...	19	19
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...
Resultant Percentage	54			72			87			82			85			88			84			84			69			12			53			60		
Resultant Direction	N. 10° E.			N. 64° W.			N. 73° W.			N. 82° W.			N. 65° W.			S. 56° W.			S. 66° W.			N. 70° W.			N. 85° W.			N. 12° W.			N. 20° E.			N. 8° E.		
Mean diurnal velocity of wind in miles.	...			...			...			...			...			...			...			...			...			...			...			...		
Average Resultant Percentage (6 Years.)	48			57			65			69			79			76			77			74			73			50			48			59		
Average Resultant Direction (6 Years.)	N. 2° W.			N. 51° W.			N. 86° W.			S. 87° W.			N. 74° W.			S. 73° W.			S. 71° W.			S. 85° W.			S. 86° W.			N. 82° W.			N. 33° W.			N. 3° E.		
Average diurnal velocity of wind in miles. Years.	...			...			...			...			...			...			...			...			...			...			...			...		

94.—GOPALPORE (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	18	...	18	3	...	3	3	1	4	...	...	...	1	...	1	...	...	...
North-East	1	...	1	2	...	2	1	1	2	...	...	...	...	...	...	...	...	...
East	...	2	2	1	2	3	...	...	...	...	...	...	...	...	...	...	...	...
South-East	1	24	25	5	12	17	1	2	3	...	...	...	2	...	2	1	...	1
South	2	5	7	11	14	25	17	25	42	29	30	59	28	31	59	20	25	45
South-West	...	...	...	...	...	...	3	...	3	1	...	1	...	...	...	7	4	11
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2
North-West	7	...	7	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1
Calm	2	...	2	6	...	6	3	...	3	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...
Resultant Percentage	25			65			72			100			96			89		
Resultant Direction	S. 86° E.			S. 27° E.			S. 2° E.			S. 1° W.			S. 1° E.			S. 11° W.		
Mean diurnal velocity of wind in miles	161·0			210·0			279·7			371·0			421·6			274·8		
Average Resultant Percentage (3 Years.)	22			55			73			94			89			76		
Average Resultant Direction (3 Years.)	N. 84° E.			S. 15° E.			S. 7° E.			S.			S. 4° E.			S. 10° W.		
Average diurnal velocity of wind *in* miles (3 Years.)	165·9			219·4			285·2			372·1			363·4			275·9		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	1	1	2	2	1	3	...	...	...	9	2	11	9	2	11	17	1	18
North-East	...	...	...	1	2	3	...	...	...	1	3	4	...	7	7	...	15	15
East	...	...	...	...	2	2	...	...	...	...	9	9	...	9	9	...	10	10
South-East	...	...	...	2	2	4	1	2	3	1	5	6	...	9	9	...	4	4
South	23	22	45	16	18	34	10	21	31	1	12	13	...	3	3	...	...	...
South-West	5	4	9	5	3	8	6	2	8	2	...	2	...	...	...	...	...	...
West	...	3	3	2	1	3	3	...	3	3	...	3	3	...	3	...	...	...
North-West	2	...	2	2	2	4	3	1	4	14	...	14	18	...	18	14	1	15
Calm	...	1	1	1	...	1	7	4	11	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	79			56			62			9			33			62		
Resultant Direction	S. 13° W.			S. 7° W.			S. 15° W.			N. 19° E.			N. 13° E.			N. 19° E.		
Mean diurnal velocity of wind in miles	253·5			217·5			168·5			?			184·8			197·3		
Average Resultant Percentage (3 Years.)	71			61			43			16			40			43		
Average Resultant Direction (3 Years.)	S. 14° W.			S. 8° W.			S. 9° W.			N. 22° E.			N. 20° E.			N. 35° E.		
Average diurnal velocity of wind in miles (3 Years.)	267·8			214·5			166·9			?			186·1			176·8		

95.—VIZAGAPATAM (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.					APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	1	4	...	1	6	...	...	...	...		...	...	...	...	...	1	...	...	...	1	...	...	...	...	...	...	...	...	...	...
North-East	6	11	5	1	23	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	12	2	13	16	43	4	4	2	4	14	...	...	...	1	1	...	...	...	...		...	...	...	1	1	..	...	...	...	...
South-East	7	4	9	10	30	4	2	6	3	15	2	3	1	1	7	...	1	1	2	4	1	1	3	...	5	...	...	1	...	1
South	1	1	4	1	7	4	4	13	5	26	...	4	23	2	29	1	2	12	2	17	2	7	14	4	27	...	4	8	2	14
South-West	2	1	...	2	5	5	3	4	8	20	5	8	4	5	22	5	16	15	7	43	11	15	12	8	46	6	12	11	6	35
West	...	5	...	...	5	3	12	2	5	22	17	12	2	16	47	17	9	2	13	41	14	7	1	14	36	21	14	10	17	62
North-West	2	3	...	...	5	8	3	...	3	14	7	4	1	6	18	6	2	...	6	14	3	1	1	4	9	3	...	...	5	8
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	55					40					63					73					73					81				
Resultant Direction	S. 85° E.					S. 27° W.					S. 62° W.					S. 63° W.					S. 51° W					S. 70° W.				
Mean diurnal velocity of wind in miles	48·9					45·0					64·7					101·3					97·0					107·3				
Average Resultant Percentage (10 Years.)	47					41					56					58					55					57				
Average Resultant Direction (10 Years.)	S. 54° E.					S. 5° E.					S. 45° W.					S. 43° W.					S. 39° W.					S. 55° W.				
Average diurnal velocity of wind in miles (12 Years.)	44·6					50·4					75·2					96·7					94·7					95·6				

	JULY.					AUGUST.					SEPTEMBER.					OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	1	5	4	...	10	6	17	4	5	32	4	12	1	3	20
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	3	10	4	5	22	6	6	13	7	32	15	15	21	11	62
East	...	...	...	1	1	...	..	1	...	1	...	...	...	...	...	10	1	9	14	34	15	1	9	13	38	9	...	6	14	29
South-East	...	1	1	2	4	1	2	...	3	6	...	1	1	1	3	5	2	4	5	16	...	...	1	2	3	2	...	3	2	7
South	1	1	8	1	11	1	1	6	...	8	2	3	10	...	15	2	1	7	1	11	...	...	3	...	3	...	...	...	...	...
South-West	5	9	7	5	26	7	8	14	2	31	8	10	10	8	36	3	5	1	3	12	...	2	...	...	2	...	...	...	...	...
West	19	20	12	17	68	20	19	8	21	68	17	16	9	18	60	5	5	2	3	15	3	4	...	2	9	...	...	...	...	...
North-West	6	...	3	5	14	2	1	2	5	10	3	...	...	3	6	2	2	...	...	4	...	...	...	1	1	1	4	...	1	6
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	77					77					80					28					59					78				
Resultant Direction	S. 76° W.					S. 74° W.					S. 66° W.					S. 86° E.					N. 47° E.					N. 49° E.				
Mean diurnal velocity of wind in miles	117·6					84·0					77·6					52·1					49·3					54·4				
Average Resultant Percentage (10 Years.)	70					61					40					21					54					58				
Average Resultant Direction (10 Years.)	S. 70° W.					S. 73° W.					S. 52° W.					S. 60° E.					N. 83° E.					S. 86° E.				
Average diurnal velocity of wind in miles (11-12 Years.)	102·4					77·1					57·7					50·6					59·7					52·7				

96.—MASULIPATAM (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	...	...	...	...	1	1	...	...	...	...	...	...	1	...	1	1	1	2	2	...	2	2	1	3	1	1	2	3	2	5	8	...	8	8	2	10
North-East	7	...	7	2	...	2	2	...	2	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	1	...	1	10	7	17	17	5	22	20	9	29
East	9	2	11	3	1	4	...	...	...	...	...	...	2	...	2	...	1	1	...	...	...	...	...	...	1	...	1	7	4	11	3	15	18	3	14	17
South-East	15	27	42	12	9	21	13	10	23	8	7	15	8	5	13	1	...	1	...	1	1	...	2	2	...	...	...	6	10	16	1	10	11	...	6	6
South	...	2	2	7	15	22	9	18	27	12	21	33	6	18	24	..	11	11	...	4	4	3	7	10	1	2	3	...	5	5	...	...	...	...	...	...
South-West	...	...	...	2	3	5	6	3	9	8	2	10	5	6	11	5	7	12	4	8	12	6	8	14	2	8	10	2	1	3	...	...	...	..	...	...
West	..	...	..	2	...	2	..	...	..	...	...	...	6	2	8	5	8	13	7	10	17	5	7	12	3	10	13	..	...	...	...	...	...	.	..	...
North-West	...	...	...	...	...	...	1	...	1	2	...	2	3	...	3	17	2	19	18	8	26	15	6	21	21	9	30	3	1	4	1	...	1	...	...	.
Calm	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	1	1	...	...	...	...	...	..
Resultant Percentage	85			74			79			82			62			55			71			57			70			47			73			80		
Resultant Direction	S. 60° E.			S. 21° E.			S. 13° E.			S. 2° E.			S. 10° W.			S. 83° W.			N. 81° W.			S. 84° W.			N. 71° W.			N. 87° E.			N. 68° E.			N. 58° E.		
Mean diurnal velocity of wind in miles	165·3			137·0			181·7			222·9			258·1			224·4			242·3			231·2			197·9			128·0			117·3			141·4		
Average Resultant Percentage (8 Years.)	87			80			80			84			65			77			83			80			72			41			83			84		
Average Resultant Direction (8 Years.)	N. 61° E.			S. 84° E.			S. 22° E.			S. 4° W.			S. 19° W.			S. 72° W.			S. 77° W.			S. 81° W.			N. 79° W.			N. 17° E.			N. 56° E.			N. 55° E.		
Average diurnal velocity of wind in miles (Year.)	...			...			...			...			...			...			...			...			...			...			...			..		

97.—SECUNDERABAD (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	...	...	...	...	1	1	1	2	3	3	3	6	2	1	3	...	...	...	...	...	...	...		...	...	...	...	2	8	10	4	8	12	6	9	15
North-East	2	4	6	2	2	4	3	6	9	1	4	5	1	5	6	...	...	...	...	...	...	...	1	1	...	...	...	12	13	25	12	16	28	12	14	26
East	19	19	38	11	15	26	5	8	13	4	8	12	.	5	5	...	...	..	...	...	...	...	...	...	...	...	...	7	7	14	12	5	17	10	4	14
South-East	8	5	13	8	6	14	9	7	16	3	7	10	1	3	4	...	...	...	...	...	...	1	1	2	1	...	1	3	1	4	1	1	2	2	1	3
South	1	1	2	2	3	5	3	4	7	5	2	7	2	1	3	...	2	2	..	...	...	...	1	1	...	1	1	1	...	1	...	...	...	...	...	...
South-West	..	1	1	4	...	4	5	1	6	8	2	10	7	5	12	15	13	28	13	15	28	7	12	19	13	12	25	3	1	4	...	...	...	...	...	...
West	...	...	...	...	1	1	2	...	2	2	...	2	10	8	18	12	14	26	17	14	31	18	11	29	14	13	27	2	...	2	...	...	...	...	...	...
North-West	1	1	2	1	..	1	3	1	4	4	2	6	8	2	10	3	1	4	1	2	3	5	4	9	2	4	6	1	1	2	1	...	1	1	3	4
Calm	...	...	..	...	...	...	...	..	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	..	...	...	...	...	2	2	...	2	2	...	1	1	...	...	...	...	..	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	80			65			39			20			35			87			90			77			84			58			81			75		
Resultant Direction	S. 83° E.			S. 69° E.			S. 64° E.			S. 52° E.			W.			S. 69° W.			S. 72° W.			S. 79° W.			S. 73° W.			N. 52° E.			N. 50° E.			N. 43° E.		
Mean diurnal velocity of wind in miles	84·5			70·9			69·7			109·3			180·2			251·0			283·8			200·5			202·1			59·8			51·4			56·3		
Average Resultant Percentage (8 Years.)	70			50			23			15			40			84			85			82			73			40			76			74		
Average Resultant Direction (8 Years.)	S. 87° E.			S. 73° E.			S. 62° E.			S. 20° W.			N. 76° W.			S. 81° W.			S 73° W.			S. 88° W.			N. 81° W.			N. 28° E.			N. 55° E.			N. 66° E.		
Average diurnal velocity of wind in miles (6—9 Years.)	94·8			83·8			112·1			123·8			167·2			299·1			321·0			232·3			162·7			81·2			73·5			69·6		

98.—BELLARY (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	...	...	...	...	1	1	2	...	2	1	2	3	1	...	1	...	...	...	...	...	...	...	1	1	...	...	...	5	3	8	1	2	3	3	2	5
North-East	1	1	2	...	1	1	1	2	3	1	2	3	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	2	4	6	7	9	16	2	5	7
East	6	15	21	3	5	12	...	5	5	...	1	1	...	3	3	1	...	1	...	...	...	...	...	...	...	...	...	8	8	16	15	11	26	18	18	36
South-East	19	12	31	18	12	30	11	9	20	4	8	12	1	6	7	...	...	...	...	...	...	...	...	...	...	...	...	4	5	9	6	3	9	3	4	7
South	2	1	3	3	2	5	2	3	5	3	2	5	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	3	1	4	...	...	...	...	...	...
South-West	1	1	2	...	2	2	1	5	6	2	4	6	2	3	5	8	7	15	2	8	10	3	7	10	2	5	7	1	3	4	...	...	...	...	...	...
West	1	...	1	...	1	1	6	5	11	6	4	10	14	12	26	19	22	41	27	23	50	21	17	38	24	22	46	2	4	6	...	2	2	1	...	1
North-West	1	1	2	4	...	4	8	2	10	13	7	20	11	6	17	2	1	3	2	...	2	7	6	13	4	3	7	6	3	9	1	3	4	4	2	6
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	76			66			20			28			53			89			95			88			93			20			67			67		
Resultant Direction	S. 60° E.			S. 51° E.			S. 5° W.			N. 85° W.			N. 84° W.			S. 81° W.			S. 84° W.			N. 87° W.			W.			N. 65° E.			N. 75° E.			N. 77° E.		
Mean diurnal velocity of wind in miles	80·3			90·2			99·8			141·1			202·1			278·5			300·3			234·4			249·7			95·4			62·0			58·9		
Average Resultant Percentage (8 Years.)	72			55			23			18			62			85			88			88			77			18			57			70		
Average Resultant Direction (8 Years.)	S. 64° E.			S. 53° E.			S. 22° E.			S. 46° W.			N. 74° W.			N. 86° W.			N. 87° W.			N. 81° W.			N. 72° W.			N. 7° E.			N. 89° E.			S. 81° E.		
Average diurnal velocity of wind in miles (10-12 Years.)	81·8			97·7			111·8			129·6			200·5			247·0			278·1			252·4			220·6			102·4			76·3			73·9		

99.—MANGALORE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	3	...	3	1	...	1	...	...	...	1	...	1	1	1	2	...	...	...	...	2	2	...	1	1	...	...	...	1	...	1	...	4	4	...	4	4
North-East	3	1	4	2	...	2	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	16	...	16	9	...	9	1	...	1	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	13	...	13	22	1	23
South-East	1	...	1	2	...	2	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	1	3	2	1	3
South	...	1	1	2	...	2	1	...	1	1	...	1	2	4	6	...	...	...	...	2	2	2	...	2	2	1	3	8	5	13	2	2	4	...	...	...
South-West	...	3	3	3	1	4	2	...	2	5	2	7	3	1	4	5	5	10	...	1	1	...	...	...	2	2	4	3	2	5	...	2	2	...	2	2
West	2	1	19	2	23	25	13	20	33	14	18	32	10	14	24	2	6	8	13	8	21	5	6	11	6	7	13	1	7	8	1	10	11	2	9	11
North-West	3	8	11	3	4	7	11	10	21	5	9	14	8	9	17	1	1	2	2	3	5	5	10	15	5	5	10	3	8	11	3	8	11	1	10	11
Calm	3	1	4	4	...	4	2	...	2	4	1	5	6	2	8	22	18	40	15	15	30	19	14	33	15	15	30	13	8	21	9	3	12	4	5	9
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	22			37			78			79			62			29			42			38			38			32			11			16		
Resultant Direction	N. 44° W.			N. 87° W.			N. 75° W.			N. 84° W.			N. 82° W.			S. 71° W.			N. 84° W.			N. 66° W.			N. 87° W.			S. 60° W.			N. 50° W.			N. 25° E.		
Mean diurnal velocity of wind in miles	113·3			96·6			97·9			85·6			99·3			66·1			65·7			47·8			44·1			65·3			77·2			93·7		
Average Resultant Percentage (3-4 Years.)	10			40			77			84			73			42			60			63			51			45			21			13		
Average Resultant Direction (3-4 Years.)	N. 33° W.			N. 77° W.			N. 86° W.			N. 86° W.			N. 77° W.			S. 87° W.			S. 74° W.			N. 76° W.			S. 87° W.			S. 76° W.			N. 83° W.			N. 13° E.		
Average diurnal velocity of wind in miles. (3-4 Years.	104·8			95·8			91·6			90·5			104·7			83·3			75·0			67·0			54·7			65·3			77·2			93·7		

100.—MERCARA (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	..	1	1	2	2	...	2	2	1	3	...	...	...	...	...	...	...	...	...	2	1	3	...	...	...	1	...	1	1	1	2	...	...	...
North-East	5	8	13	5	8	13	1	1	2	2	...	2	2	...	2	...	...	...	...	...	...	1	...	1	...	...	...	5	3	8	11	7	18	11	11	22
East	18	15	33	11	8	19	3	3	6	2	1	3	1	...	1	...	...	...	...	...	...	1	...	1	...	...	...	7	3	10	14	7	21	15	7	22
South-East	1	...	1	3	2	5	3	...	3	1	...	1	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	1	...	1	1	...	1
South	...	...	...	...	...	...	1	...	1	...	...	...	1	1	2	..	...	...	...	...	...	..	...	...	...	...	...	1	...	1	...	1	1	...	...	...
South-West	...	...	...	1	...	1	3	1	4	2	...	2	...	1	1	2	1	3	...	...	...	1	...	1	1	...	1	1	1	2	...	...	...	...	...	...
West	...	2	2	...	4	4	12	15	27	6	17	23	12	19	31	26	28	54	28	25	53	18	23	41	24	24	48	3	10	13	...	2	2	...	2	2
North-West	1	2	3	...	4	4	1	7	8	4	9	13	9	6	15	2	1	3	3	6	9	6	7	13	5	6	11	2	2	4	...	2	2	...	2	2
Calm	6	4	10	7	1	8	5	4	9	11	2	13	5	4	9	...	...	...	...	...	...	2	...	2	...	...	...	10	12	22	3	10	13	4	9	13
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	65			47			42			51			65			97			96			82			95			10			57			62		
Resultant Direction	N. 75° E.			N. 68° E.			N. 83° W.			N. 68° W.			N. 78° W.			W			N. 84° W.			N. 76° W.			N. 83° W.			N. 8° W.			N. 65° E.			N. 65° E.		
Mean diurnal velocity of wind in miles	114·1			101·9			86·5			104·4			126·6			227·1			322·5			227·3			206·1			94·0			102·4			135·8		
Average Resultant Percentage	76			42			20			54			78			95			95			90			93			31			43			78		
Average Resultant Direction	N. 78° E.			N. 65° E.			N. 77° W.			N. 72° W.			N. 74° W.			N. 83° W.			N. 83° W.			N. 78° W.			N. 80° W.			N. 58° W.			N. 61° E.			N. 75° E.		
3-4 Years. Average diurnal velocity of wind in miles. 3-4 Years.	126·6			103·0			95·3			109·1			145·9			259·2			326·3			242·7			210·8			94·0			102·4			135·8		

101.—BANGALORE (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	2	...	2	2	3	5
North-East	9	5	14	3	...	3	1	1	1	1	...	1	3	1	4	...	1	1	...	...	...	...	...	...	...	...	...	12	13	25	17	19	36	16	13	29
East	17	21	38	12	14	26	2	2	4	1	1	2	...	3	3	...	...	...	...	...	...	...	...	...	...	...	...	5	3	8	5	7	12	11	14	25
South-East	5	5	10	8	9	17	8	9	17	3	2	5	1	1	2	..	...	...	...	...	...	1	1	2	...	...	...	3	5	8	4	3	7	1	1	2
South	...	...	...	2	1	3	6	3	9	3	2	5	...	...	...	...	...	...	...	...	...	1	..	1	1	...	1	...	...	...	...	...	...	...	...	...
South-West	...	..	...	2	2	4	8	10	18	8	8	16	8	3	11	12	12	24	9	11	20	8	7	15	5	6	11	2	...	2	...	...	...	...	...	...
West	...	...	..	1	2	3	6	6	12	8	11	19	14	17	31	18	16	34	22	20	42	17	20	37	22	21	43	6	9	15	...	...	...	...	...	...
North-West	...	...	...	...	...	...	1	...	1	6	6	12	4	5	9	...	1	1	...	...	...	4	3	7	2	3	5	2	1	3	2	1	3	1	...	1
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	89			67			54			57			61			89			93			84			91			30			79			85		
Resultant Direction	N. 87° E.			S. 65° E.			S. 15° W.			S. 72° W.			N. 87° W.			S. 73° W.			S. 76° W.			S. 81° W.			S. 84° W.			N. 43° E.			N. 59° E.			N. 62° E		
Mean diurnal velocity of wind in miles	149·0			132·7			122·8			140·7			170·2			282·4			274·5			221·4			220·6			127·0			103·0			123·3		
Average Resultant Percentage	82			66			52			54			73			89			90			91			87			9			59			84		
Average Resultant Direction	N. 89° E.			S. 69° E.			S. 29° E.			S. 28° W.			S. 69° W.			S. 69° W.			S. 70° W.			S. 77° W.			S. 81° W.			N. 57° W.			N. 60° E.			N. 71° E.		
8 Years. Average diurnal velocity of wind in miles. 12-14 Years.	85·0			79·2			80·5			79·5			123·6			196·1			198·8			172·9			155·0			89·7			84·0			87·0		

102.—MADRAS (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.	12 hours.	24 hours.	Total.
North	4	3	7	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	6	6	12	15	15	30	19	15	34
North-East	18	20	38	7	5	12	...	1	1	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	6	7	13	8	12	20	9	14	23
East	6	5	11	9	11	20	4	4	8	...	2	2	1	...	1	...	2	2	...	...	...	...	1	1	...	5	5	2	6	8	2	...	2	1	...	1
South-East	3	3	6	8	9	17	15	20	35	14	22	36	5	23	28	...	6	6	...	3	3	2	11	13	1	12	13	4	5	9	1	3	4	...	1	1
South	...	...	...	4	3	7	12	6	18	14	6	20	13	7	25	5	11	16	3	10	13	9	8	17	5	7	12	3	2	5	1	...	1	...	...	...
South-West	...	...	...	...	...	...	...	...	...	2	...	2	5	...	5	16	10	26	23	13	36	16	6	22	19	5	24	4	2	6	1	...	1	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	2	...	2	9	1	10	5	5	10	3	5	8	5	1	6	2	2	4	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	4	1	5	2	...	2	2	1	3
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	83			75			87			89			81			74			85			70			65			24			74			87		
Resultant Direction	N. 55° E.			S. 75° E.			S. 39° E.			S. 29° E.			S. 19° E.			S. 30° W.			S. 39° W.			S. 19° W.			S. 13° W.			N. 52° E.			N. 22° E.			N. 17° E.		
Mean diurnal velocity of wind in miles	169·0			129·0			153·0			181·0			240·0			225·0			178·0			196·0			189·8			109·3			163·3			202·2		
Average Resultant Percentage (15 Years.)	76			68			81			83			66			58			65			58			53			10			59			75		
Average Resultant Direction (15 Years.)	N. 48° E.			E.			S. 50° E.			S. 40° E.			S. 15° E.			S. 36° W.			S. 46° W.			S. 40° W.			S. 36° W.			N. 35° E.			N. 24° E.			N. 24° E.		
Average diurnal velocity of wind in miles (14 Years.)	150·7			123·5			154·2			192·3			226·9			218·8			202·1			176·9			158·7			121·3			164·3			183·4		

103.—SALEM (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	1	...	1	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...
North-East	11	...	11	10	...	10	12	...	12	...	...	...	2	...	2	...	...	...	...	...	...	1	...	1	...	...	...	7	...	7	10	...	10	9	...	9
East	9	6	15	9	2	11	12	4	16	2	...	2	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	3	2	5	12	5	17	11	4	15
South-East	6	14	20	1	9	10	2	8	10	1	3	4	1	3	4	...	...	...	...	...	...	1	...	1	...	...	...	2	5	7	4	15	19	8	17	25
South	1	4	5	2	10	12	...	14	14	4	9	13	...	...	...	7	...	7	2	...	2	4	2	6	1	1	2	...	4	4	1	4	5	...	6	6
South-West	3	6	9	5	5	10	4	4	8	13	12	25	18	14	32	19	10	29	18	8	26	22	9	31	18	14	32	11	8	19	2	3	5	2	3	5
West	...	1	1	1	2	3	1	1	2	6	5	11	4	12	16	4	17	21	9	20	29	4	16	20	8	13	21	6	9	15	...	3	3	...	1	1
North-West	...	...	...	...	...	...	...	...	...	3	1	4	5	2	7	...	3	3	2	3	5	...	3	3	3	2	5	2	3	5	...	...	...	1	...	1
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	55			43			48			67			69			84			86			80			86			36			57			63		
Resultant Direction	S. 60° E.			S. 38° E.			S. 53° E.			S. 42° W.			S. 64° W.			S. 60° W.			S. 72° W.			S. 59° W.			S. 66° W.			S. 51° W.			S. 66° E.			S. 59° E.		
Mean diurnal velocity of wind in miles	139·8			153·6			124·8			105·2			97·8			87·0			71·6			67·4			73·2			43·4			55·3			64·5		
Average Resultant Percentage (8 Years.)	60			53			34			30			61			81			79			78			78			27			30			50		
Average Resultant Direction (8 Years.)	N. 81° E.			E.			S. 58° E.			S. 1° W.			S. 54° W.			S. 62° W.			S. 61° W.			S. 61° W.			S. 70° W.			S. 41° W.			N. 78° E.			N. 76° E.		
Average diurnal velocity of wind in miles (11-12 Years.)	137·6			150·0			144·0			126·7			113·4			131·3			122·6			106·2			93·7			67·3			84·5			105·9		

104.—WELLINGTON (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	...	...	...	...	...	...	2	1	3	...	3	3	2	5	7	1	1	2	2	3	5	...	1	1	...	3	3	1	1	2	...	...	...	...	...	...
North-East	...	1	1	3	1	4	3	5	8	5	3	8	5	9	14	...	1	1	...	...	...	2	1	3	...	1	1	4	5	9	...	1	1	2	3	5
East	2	2	4	6	7	13	7	5	12	9	12	21	5	7	12	1	1	2	...	...	...	1	...	1	1	2	3	1	7	8	4	7	11	1	6	7
South-East	8	8	16	10	11	21	9	9	18	11	10	21	9	4	13	3	1	4	1	1	2	5	6	11	4	6	10	16	5	21	12	6	18	11	12	23
South	15	18	33	6	4	10	8	7	15	2	...	2	6	4	10	2	...	2	2	1	3	6	6	12	6	2	8	7	7	14	10	10	20	12	5	17
South-West	6	2	8	3	1	4	1	3	4	...	...	...	3	1	4	9	8	17	12	6	18	8	6	14	12	6	18	2	3	5	2	6	8	2	1	3
West	...	...	...	...	3	3	...	1	1	...	1	1	...	1	1	10	14	24	9	16	25	8	9	17	7	7	14	...	2	2	2	...	2	...	...	...
North-West	...	...	...	...	...	...	1	...	1	2	...	2	1	...	1	4	3	7	5	4	9	1	2	3	...	3	3	...	1	1	...	...	...	...	1	1
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	81			63			54			68			43			62			69			49			47			53			69			70		
Resultant Direction	S. 12° E.			S. 45° E.			S. 51° E.			S. 80° E.			S. 81° E.			S. 75° W.			S. 82° W.			S. 37° W.			S. 39° W.			S. 45° E.			S. 24° E.			S. 38° E.		
Mean diurnal velocity of wind in miles	58·9			75·1			70·3			83·3			87·5			156·9			156·6			110·5			92·4			50·0			48·4			58·5		
Avorage Resultant Percentage	67			64			65			63			19			60			73			48			43			18			51			59		
Avorage Resultant Direction	S. 2° W.			S. 12° E.			S. 27° E.			S. 43° E.			N. 64° E.			N. 75° W.			N. 67° W.			N. 81° W.			N. 86° W.			S. 14° E.			S. 32° E.			S. 23° E.		
Average diurnal velocity of wind in miles. Years.	...			...			...			...			...			...			...			...			...			...			...			...		

105.—COIMBATORE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	6	1	7	2	...	2	7	...	7	1	...	1	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	2	...	2	2	...	2
North-East	14	7	21	11	4	15	7	2	9	4	...	4	2	...	2	...	...	...	...	...	...	...	...	...	...	...	...	2	1	3	7	4	11	8	5	13
East	11	18	29	12	17	29	2	6	8	...	2	2	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	4	5	9	14	13	27	9	13	22
South-East	...	5	5	2	7	9	3	9	12	7	5	12	2	1	3	2	...	2	...	...	...	3	1	4	1	...	1	8	7	15	3	7	10	5	5	10
South	...	...	...	1	...	1	8	9	17	13	15	28	17	19	36	8	3	11	10	7	17	14	11	25	12	10	22	7	9	16	1	3	4	4	5	9
South-West	...	...	...	...	...	...	3	3	6	5	4	9	6	10	16	17	20	37	16	20	36	11	15	26	12	17	29	9	5	14	...	3	3	3	3	6
West	...	...	...	...	...	...	1	1	2	...	1	1	1	1	2	3	7	10	5	4	9	3	4	7	5	3	8	...	3	3	1	...	1	...	...	...
North-West	...	...	...	...	...	...	...	1	1	...	1	1	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2	...	2	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	2	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	82			83			36			64			76			87			88			83			86			54			62			57		
Resultant Direction	N. 69° E.			N. 84° E.			S. 45° E.			S. 8° E.			S. 12° W.			S. 42° W.			S. 39° W.			S. 26° W.			S. 33° W.			S. 14° E.			S. 87° E.			S. 75° E.		
Mean diurnal velocity of wind in miles	58·4			79·0			62·2			63·2			104·3			150·9			155·6			142·3			138·1			63·3			49·0			53·3		
Average Resultant Percentage	77			73			56			54			67			81			83			85			80			47			48			78		
Average Resultant Direction	N. 76° E.			N. 81° E.			S. 81° E.			S. 22° E.			S. 17° W.			S. 41° W.			S 45° W.			S. 34° W.			S. 35° W.			S. 1° W.			N. 75° E.			N. 66° E.		
Average diurnal velocity of wind in miles. 14 Years.	77·7			79·5			80·8			86·3			130·7			193·2			203·7			181·5			162·9			85·3			64·0			74·6		

106.—TRICHINOPOLY (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	3	...	3	1	...	1	1	..	1	1	...	1	...	1	1	...	...	...	...	...	...	...	1	1	...	1	1	2	...	2	3	2	5	7	1	8
North-East	19	13	32	16	9	25	6	4	10	2	5	7	...	...	...	...	...	...	...	...	...	...	2	2	...	...	...	5	6	11	13	12	25	12	13	25
East	9	17	26	7	16	23	8	18	26	...	11	11	11	2	3	...	...	...	...	...	...	...	1	1	...	...	...	4	9	13	5	12	17	1	11	12
South-East	...	1	1	1	2	3	3	7	10	4	6	10	...	2	2	...	...	...	...	...	...	...	1	1	...	1	1	1	1	2	...	1	1	...	1	1
South	...	...	...	1	1	2	2	2	4	1	3	4	3	4	7	...	3	3	...	1	1	2	...	2	...	...	...	...	1	1	1	...	1	...	...	...
South-West	...	...	...	...	...	...	4	...	4	5	1	6	4	5	9	3	6	9	1	3	4	6	4	10	1	...	1	1	...	1	...	...	...	...	1	1
West	...	...	...	1	...	1	3	...	3	8	2	10	13	8	21	18	16	34	21	18	39	15	14	29	15	15	30	6	5	11	3	...	3	6	2	8
North-West	...	...	...	1	...	1	4	...	4	9	2	11	10	9	19	9	5	14	9	9	18	8	6	14	14	13	27	12	9	21	5	3	8	5	2	7
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	2	2	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	89			73			51			3			59			84			89			69			88			35			63			54		
Resultant Direction	N. 63° E.			N. 70° E.			S. 85° E.			S. 32° E.			S. 89° W.			N. 89° W.			N. 81° W.			N. 87° W.			N. 69° W.			N. 11° W.			N. 45° E.			N. 30° E.		
Mean diurnal velocity of wind in miles	73·0			75·0			65·4			51·7			76·1			83·2			92·8			188·9			161·2			44·7			44·4			50·3		
Average Resultant Percentage (8 Years.)	76			73			52			20			61			84			77			85			79			40			50			78		
Average Resultant Direction (8 Years.)	N. 42° E.			N. 64° E.			S. 84° E.			S. 37° E.			S. 79° W.			N. 88° W.			S. 86° W.			N. 82° W.			N. 82° W.			N. 55° W.			N. 23° E.			N. 41° E.		
Average diurnal velocity of wind in miles (13-14 Years.)	119·1			102·3			96·1			100·6			148·7			238·9			251·2			200·9			168·7			92·0			104·8			120·9		

107.—NEGAPATAM (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	2	...	2	2	...	2	...	..	...	.	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	3	1	4	7	4	11	5	1	6
North-East	27	30	57	22	19	41	1	.	1	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	11	11	22	18	23	41	18	23	41
East	1	1	2	2	6	8	2	4	6	...	...	...	..	1	1	...	...	...	...	...	...	...	...	...	...	...	...	2	4	6	...	...	...	...	...	...
South-East	...	...	...	2	3	5	26	24	50	20	21	41	4	6	10	...	...	...	...	...	...	...	3	3	...	1	1	1	...	1	1	...	1	...	...	...
South	...	...	...	...	...	...	1	3	4	5	4	9	3	16	19	...	5	5	...	2	2	...	3	3	...	10	10	...	1	1	...	1	1	...	...	...
South-West	..	...	.	...	...	...	1	...	1	4	5	9	17	7	24	25	23	48	24	27	51	25	18	43	23	19	42	6	10	16	2	2	4	1	1	2
West	1	...	1	...	...	...	...	...	...	1	...	1	6	1	7	5	2	7	7	2	9	5	7	12	6	...	6	6	3	9	...	.	...	1	3	4
North-West	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	1	...	1	1	...	1	2	1	3	2	...	2	6	3	9
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	..	...	...	.	...	...	...	...	...	...
Resultant Percentage	95			87			92			82			73			94			95			87			89			14			75			70		
Resultant Direction	N. 44° E.			N. 50° E.			S. 46° E.			S. 26° E.			S. 20° W.			S. 46° W.			S. 50° W.			S. 50° W.			S. 42° W.			N. 1° W.			N. 35° E.			N. 23° E.		
Mean diurnal velocity of wind in miles	119·7			50·0			79·0			108·1			153·7			102·4			156·6			92·5			84·5			25·8			130·9			182·6		
Average Resultant Percentage (8 Years.)	88			79			69			77			70			89			87			87			86			38			45			87		
Average Resultant Direction (8 Years.)	N. 47° E.			N. 65° E.			S. 66° E.			S. 35° E.			S. 7° W.			S. 45° W.			S. 48° W.			S. 49° W.			S. 45° W.			S. 47° W.			N. 37° E.			N. 39° E.		
Average diurnal velocity of wind in miles (12-13 Years.)	134·8			93·2			91·9			125·7			181·4			191·2			182·6			147·9			129·8			93·3			135·2			171·4		

108.—MADURA (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	1	2	3	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	1	1	3	...	3	2	1	3
North-East	17	19	36	14	21	35	10	18	28	...	1	1	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	23	28	51	28	30	58
East	11	8	19	14	7	21	15	12	27	3	1	4	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	1	1	2	3	1	4	1	...	1
South-East	...	...	...	...	...	...	5	1	6	16	16	32	14	10	24	1	...	1	...	...	...	...	...	...	...	...	...	3	...	3	...	1	1	...	...	...
South	...	...	...	...	...	...	...	...	...	11	12	23	14	21	35	3	4	7	...	...	...	1	...	1	...	...	...	3	4	7	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	2	...	2	9	9	18	13	13	26	9	8	17	3	...	3	11	9	20	...	...	...	...	...	...
West	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	17	17	34	15	18	33	15	20	35	16	15	31	6	9	15	...	...	...	...	...	...
North-West	2	2	4	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	3	...	3	6	3	9	11	15	26	7	7	14	1	...	1	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	84			93			96			88			90			84			90			87			90			60			93			98		
Resultant Direction	N. 53° E.			N. 62° E.			N. 59° E.			S. 31° E.			S. 17° E.			S. 66° W.			S. 73° W.			S. 83° W.			N. 72° W.			S. 71° W.			N. 46° E.			N. 44° E.		
Mean diurnal velocity of wind in miles	180·1			125·4			101·7			98·2			93·5			125·1			110·5			117·6			94·8			64·6			82·6			114·4		
Average Resultant Percentage (8 Years.)	57			80			73			66			58			73			86			86			82			76			47			38		
Average Resultant Direction (8 Years.)	N. 59° E.			N. 77° E.			S. 86° E.			S. 25° E.			S. 24° W.			S. 78° W.			N. 75° W.			N. 71° W.			N. 70° W.			N. 70° W.			N. 45° W.			N. 40° E.		
Average diurnal velocity of wind in miles (14 Years.)	134·9			122·9			101·3			87·9			91·7			124·5			112·8			92·5			85·7			71·5			97·8			121·5		

109.—COCHIN (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.	10 hours.	22 hours.	Total.
North	3	3	6	3	1	4	5	1	6	1	2	3	4	...	4	3	...	3	5	2	7	2	4	6	3	2	5	2	1	3	2	2	4	2	1	3
North-East	5	1	6	9	1	10	1	2	3	1	1	2	2	1	3	4	1	5	1	2	3	...	..	...	2	...	2	2	2	4	8	...	8	8	1	9
East	13	...	13	9	1	10	3	...	3	1	...	1	...	...	...	5	...	5	1	...	1	...	...	...	...	...	...	5	...	5	3	...	3	5	...	5
South-East	5	1	6	1	...	1	...	2	2	4	3	7	4	2	6	3	1	4	2	2	4	1	...	1	...	1	1	5	3	8	9	3	12	7	...	7
South	...	2	2	...	1	1	1	1	2	...	5	5	3	3	6	...	5	5	1	...	1	2	...	2	...	...	...	4	7	11	3	9	12	3	10	13
South-West	1	9	10	...	9	9	1	3	4	3	3	6	3	5	8	9	8	17	6	4	10	6	5	11	2	2	4	2	10	12	1	11	12	1	11	12
West	1	8	9	1	10	11	1	10	11	4	6	10	1	10	11	2	8	10	6	7	13	5	10	15	8	10	18	2	6	8	1	3	4	2	4	6
North-West	3	7	10	5	5	10	19	11	30	16	12	28	14	9	23	4	6	10	9	13	22	15	12	27	15	15	30	9	2	11	3	2	5	3	4	7
Calm	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	1	1	...	...	...	...	1	1	...	1	1	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	7			22			59			46			44			31			53			70			78			25			26			20		
Resultant Direction	N. 22° W.			N. 33° W.			N. 51° W.			N. 69° W.			N. 76° W.			S. 71°·W.			N. 65° W.			N. 70° W.			N. 59° W.			S. 43° W.			S. 4° E.			S. 14° W.		
Mean diurnal velocity of wind in miles	?			?			?			?			?			?			?			?			?			?			?			?		
Average Resultant Percentage (8 Years.)	32			28			42			52			54			52			53			56			62			44			31			26		
Average Resultant Direction (8 Years.)	S. 7° E.			S. 65° W.			S. 83° W.			S. 88° W.			S. 79° W.			S. 69° W.			S. 72° W.			S. 79° W.			S. 86° W.			S. 69° W.			S. 37° W.			S. 34° W.		
Average diurnal velocity of wind in miles (3 Years.)	?			?			?			?			53·2			50·8			46·8			?			?			?			?			?		

110.—COLOMBO (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	241·1			160·9			136·1			166·8			253·6			228·5			253·3			251·6			219·8			175·0			189·6			214·0		
Average Resultant Percentage	55			46			51			62			75			85			85			84			87			74			45			56		
Average Resultant Direction (11 Years.)	N. 3° W.			N. 39° W.			N. 85° W.			S. 67° W.			S. 54° W.			S. 73° W.			S. 74° W.			S. 71° W.			S. 73° W.			S. 75° W.			N. 66° W.			N. 1° E.		
Average diurnal velocity of wind in miles (13-14 Years.)	184·8			136·9			114·9			120·2			193·5			233·1			207·3			197·8			197·0			167·2			130·4			179·9		

111.—JAFNA (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	101·1			73·7			98·9			162·3			314·4			329·0			315·3			282·0			307·9			108·8			72·0			93·9		
Average Resultant Percentage	82			66			38			49			83			96			93			93			94			61			36			69		
Average Resultant Direction (10 Years.)	N. 43° E.			N. 51° E.			S. 69° E.			S. 10° W.			S. 39° W.			S. 43° W.			S. 42° W.			S. 41° W.			S. 44° W.			S. 49° W.			N. 28° E.			N. 34° E.		
Average diurnal velocity of wind in miles (13 Years.)	77·0			72·8			96·3			155·9			280·1			322·6			294·4			281·2			277·5			169·9			72·1			82·4		

112.—TRINCOMALEE (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	..	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	..	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	..	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			..			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	355·4			283·5			250·1			243·0			397·2			507·7			524·0			470·1			403·2			241·4			192·2			247·7		
Average Resultant Percentage	71			74			69			55			61			89			82			67			66			32			35			66		
Average Resultant Direction, 11 Years	N. 43° E.			N. 57° E.			S. 78° E.			S. 54° E.			S. 32° W.			S. 51° W.			S. 50° W.			S. 52° W.			S. 51° W.			S. 51° W.			N. 23° E.			N. 28° E.		
Average diurnal velocity of wind in miles, 12-14 Years.	241·6			197·3			174·4			222·0			338·9			471·7			449·4			378·6			365·1			252·0			161·5			205·8		

113.—BATTICALOA (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	173·2			116·5			119·7			123·7			110·3			79·3			84·7			108·0			121·4			101·0			100·4			109·7		
Average Resultant Percentage	74			69			65			61			42			19			18			30			28			27			45			60		
Average Resultant Direction, 11 Years.	N. 24° E.			N. 34° E.			N. 66° E.			N. 80° E.			S. 85° E.			S. 7° E.			S. 31° E.			S. 66° E.			S. 69° E.			N. 77° E.			N. 28° E.			N. 23° E.		
Average diurnal velocity of wind in miles, 11-14 Years.	229·0			198·5			157·7			149·2			134·7			130·1			138·5			132·3			123·1			124·5			138·9			168·4		

114.—HAMBANTOTA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	?			?			?			?			256·6			262·8			260·5			277·8			316·6			229·3			137·8			140·3		
Average Resultant Percentage	82			73			50			41			87			95			92			94			96			80			12			57		
Average Resultant Direction (11 Years.)	N. 52° E.			N. 61° E.			N. 77° E.			S. 33° W.			S. 44° W.			S. 49° W.			S. 55° W.			S. 50° W.			S. 49° W.			S. 48° W.			S. 38° E.			N. 59° E.		
Average diurnal velocity of wind in miles (11-14 Years.)	244·2			237·5			183·0			181·5			269·5			280·7			288·3			286·9			285·1			218·8			153·2			199·3		

115.—GALLE (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	..	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			..			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	77·5			79·6			90·3			121·9			189·2			200·9			229·4			206·6			168·9			143·2			64·7			70·3		
Average Resultant Percentage	26			11			7			26			61			82			83			83			80			65			30			20		
Average Resultant Direction (11 Years.)	N. 24° W.			N. 5° W.			N. 53° E.			N. 77° W.			S. 86° W.			N. 62° W.			N. 58° W.			N. 60° W.			N. 59° W.			N. 65° W.			N. 41° W.			N. 22° W.		
Average diurnal velocity of wind in miles (10-13 Years.)	58·6			56·8			66·3			92·0			186·1			233·5			196·7			200·4			202·6			176·2			81·8			68·3		

116.—KANDY (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	110·5			91·0			45·0			42·6			56·7			48·2			49·9			32·4			31·4			29·9			35·2			37·3		
Average Resultant Percentage (11 Years.)	55			57			41			35			68			75			77			77			76			66			22			33		
Average Resultant Direction (11 Years.)	S. 84° E.			S. 69° E.			S. 53° E.			S. 43° W.			S. 58° W.			S. 67° W.			S. 67° W.			S. 61° W.			S. 63° W.			S. 61° W.			S. 45° W.			S. 86° E.		
Average diurnal velocity of wind in miles (12-14 Years.)	77·3			77·8			47·9			34·4			53·9			79·1			72·2			66·1			60·9			42·9			42·0			53·2		

117.—NEWERA ELIYA (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.	9½ hours.	15½ hours.	Total.
North	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			...			...			...			...			...			...			...			...			...			...		
Resultant Direction	...			...			...			...			...			...			...			...			...			...			...			...		
Mean diurnal velocity of wind in miles	124·2			85·5			60·4			51·9			69·2			124·5			155·9			192·5			150·2			133·8			147·0			186·7		
Average Resultant Percentage (9-11 Years.)	43			41			57			13			33			82			87			77			74			44			21			44		
Average Resultant Direction (9-11 Years.)	S. 63° E.			S. 58° E.			S. 56° E.			S. 48° E.			N. 74° W.			N. 57° W.			N. 57° W.			N. 60° W.			N. 60° W.			N. 60° W.			S. 66° E.			S. 63° E.		
Average diurnal velocity of wind in miles (11-14 Years.)	66·5			71·1			60·7			56·6			84·8			139·7			116·7			103·9			92·4			68·3			63·2			79·4		

118.—AKYAB (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	7	...	7	9	1	10	4	1	5	2	...	2	...	...	...	...	...	...	2	...	2	...	...	...	1	...	1	6	...	6	5	1	6	10	1	11
North-East	20	1	21	13	...	13	7	...	7	1	2	3	2	1	3	1	...	1	3	...	3	1	...	1	2	...	2	15	1	16	15	...	15	12	5	17
East	3	1	4	3	...	3	7	...	7	8	...	8	10	1	11	4	...	4	...	...	...	3	...	3	5	...	5	5	...	5	5	2	7	2	7	9
South-East	...	2	2	1	...	1	2	...	2	5	...	5	8	1	9	10	5	15	6	4	10	11	2	13	14	1	15	3	1	4	2	4	6	4	2	6
South	...	2	2	...	1	1	2	3	5	2	2	4	7	9	16	9	15	24	11	15	26	8	18	26	6	15	21	1	6	7	...	1	1	...	3	3
South-West	...	7	7	...	2	2	4	7	11	9	9	18	2	13	15	4	5	9	9	10	19	5	7	12	2	11	13	...	5	5	...	2	2	2	2	4
West	...	11	11	...	17	17	...	13	13	3	15	18	...	5	5	...	2	2	...	1	1	1	2	3	...	3	3	...	15	15	...	11	11	...	5	5
North-West	1	7	8	2	7	9	5	7	12	...	2	2	2	1	3	1	2	3	...	1	1	2	2	4	...	...	...	1	3	4	...	4	4	2	5	7
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	31			45			27			39			46			65			68			65			64			12			28			35		
Resultant Direction	N. 4° W			N. 28° W.			N. 75° W.			S. 51° W.			S. 4° E.			S. 7° E.			S. 8° W.			S. 2° W.			S. 7° E.			N. 18° W.			N. 27° E.			N. 35° E.		
Mean diurnal velocity of wind in miles	58·7			81·4			84·0			81·1			75·1			100·8			103·0			72·5			71·5			54·9			60·8			58·5		
Average Resultant Percentage	39			45			26			40			31			58			68			62			41			12			29			39		
Average Resultant Direction (14-15 Years.)	N. 23° W.			N. 27° W.			N. 58° W.			S. 75° W.			S. 33° W.			S. 2° E.			S. 4° E.			S. 1° E.			S. 9° E.			S. 35° E.			N. 6° W.			N. 15° W.		
Average diurnal velocity of wind in miles (11-12 Years.)	64·4			83·1			91·1			98·6			80·8			94·2			87·5			75·7			71·8			56·3			53·4			54·5		

119.—THAYETMYO (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	Untrustworthy.						6	3	9	1	2	3	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	7	6	13	8	6	14	11	14	25
North-East							3	3	6	1	4	5	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	9	8	17	15	15	30	7	6	13
East							2	3	5	6	...	6	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	...	1	1	3	...	3
South-East							13	2	15	7	7	14	16	11	27	12	12	24	17	10	27	15	10	25	17	12	29	9	6	15	4	3	7	5	5	10
South							3	3	6	6	3	9	8	5	13	16	14	30	13	15	28	15	12	27	9	11	20	...	3	3	1	2	3	...	3	3
South-West							2	3	5	6	8	14	4	8	12	2	3	5	1	6	7	1	8	9	4	6	10	1	2	3	...	1	1	1	...	1
West							1	10	11	...	5	5	...	2	2	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...
North-West							1	4	5	3	1	4	1	4	5	...	1	1	...	...	...	...	...	...	...	1	1	4	6	10	2	2	4	4	3	7
Calm							...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable							...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	...			...			6			33			57			86			87			84			81			35			63			51		
Resultant Direction	...			...			S. 28° E.			S. 5° E.			S. 11° E.			S. 14° E.			S. 15° E.			S. 11° E.			S. 15° E.			N. 41° E.			N. 39° E.			N. 26° E.		
Mean diurnal velocity of wind in miles	53·6			63·1			108·8			133·0			137·5			181·0			166·5			150·9			141·3			59·6			75·9			65·3		
Average Resultant Percentage	14			8			16			42			54			80			82			78			73			23			28			58		
Average Resultant Direction (5-6 Years.)	N. 35° E.			S. 19° E.			S. 15° E.			S.			S. 3° E.			S. 3° E.			S. 1° W.			S. 2° E.			S. 11° E.			S. 37° E.			N. 20° E.			N. 18° E.		
Average diurnal velocity of wind in miles (5-6 Years.)	60·7			110·8			135·9			190·9			188·8			203·8			164·9			152·2			123·8			82·9			81·1			89·0		

120.—TOUNGOO (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	1	1	2	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-East	1	...	1	...	...	...	...	2	2	...	1	1	...	3	3	1	1	2	...	1	1	...	1	1	...	...	...	...	...	...	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	...	...	...	...	...	2	...	2	2	6	8	8	8	16	8	15	23	7	14	21	3	6	9	3	4	7	...	...	...	...	1	1	...	...	...
South	...	...	...	...	...	...	1	...	1	5	3	8	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	15	6	21	19	15	34	19	14	33	21	13	34	24	15	39	27	23	50	27	26	53	3	4	7	1	1	2	2	1	3
West	...	...	...	...	...	...	4	3	7	1	...	1	2	1	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
North-West	30	31	61	28	28	56	8	19	27	3	4	7	1	5	6	...	1	1	...	1	1	1	1	2	...	...	...	28	27	55	29	28	57	29	30	59
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	98			100			62			65			55			65			69			80			89			89			93			95		
Resultant Direction	N. 44° W.			N. 45° W.			N. 82° W.			S. 35° W.			S. 30° W.			S. 10° W.			S. 17° W.			S. 37° W.			S. 37° W.			N. 52° W.			N. 47° W.			N. 84° W.		
Mean diurnal velocity of wind in miles	43·3			52·6			Not recorded.																													
Average Resultant Percentage	51			40			29			50			51			69			70			60			47			19			57			74		
Average Resultant Direction. 5-7 Years.	N. 15° W.			N. 8 E.			S. 51° E.			S. 38° E.			S. 29° E.			S. 26° E.			S. 22° E.			S. 11° E.			S. 2° E			N. 63° W.			N. 29° W.			N. 26° W.		
Average diurnal velocity of wind in miles. 4·5 Years.	46·9			49·9			75·4			95·7			102·7			117·7			113·8			99·2			65·9			52·3			44·6			63·8		

121.—BASSEIN (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	9	4	13	6	1	7	6	2	8	2	1	3	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	4	5	9	6	8	14	11	7	18
North-East	7	5	12	4	3	7	1	...	1	1	1	2	1	...	1	...	...	...	...	...	...	...	...	...	...	...	...	4	3	7	13	8	21	10	10	20
East	5	7	12	...	...	...	...	...	...	...	...	...	...	1	1	1	...	1	...	...	...	...	...	...	...	...	...	7	6	13	6	4	10	6	7	13
South-East	2	...	2	...	...	...	...	...	...	1	...	1	...	2	2	3	4	7	3	...	3	3	...	3	1	1	2	5	4	9	3	5	8	4	3	7
South	...	...	...	...	...	...	...	...	...	...	1	1	8	4	12	15	9	24	12	11	23	9	7	16	10	8	18	4	2	6	...	3	3	...	4	4
South-West	...	...	...	1	...	1	1	...	1	2	2	4	5	5	10	7	10	17	10	13	23	11	12	23	6	5	11	...	2	2	1	1	2	...	...	...
West	3	7	10	4	10	14	4	8	12	12	6	18	9	11	20	3	4	7	5	6	11	7	12	19	11	13	24	1	3	4	...	1	1	...	...	...
North-West	5	8	13	13	14	27	19	21	40	12	19	31	7	8	15	1	3	4	1	1	2	1	...	1	2	3	5	6	6	12	1	...	1	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	47			75			87			77			57			69			77			77			69			22			56			64		
Resultant Direction	N. 5° E.			N. 44° W.			N. 48° W.			N. 62° W.			S. 77° W.			S. 23° W.			S. 34° W.			S. 45° W.			S. 55° W.			N. 50° E.			N. 55° E.			N. 54° E.		
Mean diurnal velocity of wind in miles	86·4			125·1			169·2			129·4			126·5			80·6			85·7			70·0			72·2			82·8			103·8			92·8		
Average Resultant Percentage	55			74			84			67			42			65			62			58			47			3			52			67		
Average Resultant Direction. 6 Years.	N. 1° W.			N. 54° W.			N. 61° W.			N. 71° W.			S. 78° W.			S. 15° W.			S. 25° W.			S. 31° W.			S. 19° W.			S. 32° E.			N. 52° E.			N. 26° E.		
Average diurnal velocity of wind in miles. 4·6 Years.	64·4			92·7			117·6			118·5			105·6			95·2			88·4			81·7			80·8			64·7			72·8			62·7		

TABLE IX.—DIRECTION AND MEAN MOVEMENT OF WINDS IN 1883.

122.—DIAMOND ISLAND (*2 observations daily*).

	January.			February.			March.			April.			May.			June.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	12	8	20	12	10	22	8	8	16	3	1	4	...	...	...	...	...	...
North-East	9	3	12	2	1	3	...	...	...	2	...	2	1	...	1	...	...	...
East	5	6	11	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	...	4	4	...	1	1	...	...	...	...	1	1	1	1	2	1	3	4
South	...	...	..	...	...	...	...	...	...	...	...	...	1	3	4	9	9	18
South-West	...	...	...	...	1	1	...	1	1	...	2	2	11	9	20	12	11	23
West	...	...	...	..	...	...	...	...	...	4	6	10	11	12	23	6	7	13
North-West	5	10	15	14	15	29	23	22	45	20	20	40	6	6	12	1	...	1
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1
Resultant Percentage	61			84			92			83			72			76		
Resultant Direction	N. 18° E.			N. 23° W.			N. 35° W.			N. 50° W.			S. 77° W.			S. 37° W.		
Mean diurnal velocity of wind in miles	186·7			174·4			231·7			185·8			158·7			220·8		
Average Resultant Percentage, 5-6 Years	70			86			84			68			42			74		
Average Resultant Direction, 5-6 Years	N. 12° E.			N. 26° W.			N. 39° W.			N. 56° W.			S. 73° W.			S. 31° W.		
Average diurnal velocity of wind in miles, 5-6 Years	162·6			178·6			198·9			175·5			160·6			205·9		

	July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	...	...	...	...	...	...	3	1	4	5	5	10	6	7	13
North-East	...	...	...	...	1	1	...	...	...	7	1	8	12	9	21	16	12	28
East	...	...	...	...	...	...	...	...	...	7	8	15	6	7	13	5	5	10
South-East	...	...	...	1	...	1	2	...	2	3	6	9	4	3	7	4	7	11
South	5	4	9	4	2	6	3	3	6	...	...	...	2	4	6	...	...	...
South-West	18	21	39	16	15	31	12	12	24	1	1	2	...	...	...	...	...	...
West	8	5	13	9	12	21	10	13	23	1	3	4	...	...	...	...	...	...
North-West	...	1	1	...	...	...	2	2	4	9	9	18	1	2	3	...	...	...
Calm	...	...	...	...	...	...	1	...	1	...	2	2	...	...	...	..	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	88			83			78			28			58			73		
Resultant Direction	S. 49° W.			S. 56° W.			S. 62° W.			N. 31° E.			N. 62° E.			N. 56° E.		
Mean diurnal velocity of wind in miles	245·0			170·5			149·1			147·2			210·2			232·1		
Average Resultant Percentage, 6 Years	77			75			59			11			60			71		
Average Resultant Direction, 6 Years	S. 42° W.			S. 40° W.			S. 44° W.			S. 56° E.			N. 61° E.			N. 37° E.		
Average diurnal velocity of wind in miles, 5-6 Years	217·7			178·3			162·0			160·5			200·1			178·9		

123.—RANGOON (*4 observations daily*).

	JANUARY.					FEBRUARY.					MARCH.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	8	5	5	6	24	...	3	2	...	5	...	3	1	...	4
North-East	7	17	6	3	33	...	11	...	1	12	...	3	1	...	4
East	2	4	6	1	13	...	1	1	...	2	...	1	2	...	3
South-East	3	1	4	3	11	1	1	4	...	6	...	1	10	...	11
South	...	...	2	2	4	...	1	5	10	16	1	5	6	10	22
South-West	2	...	...	...	2	10	2	5	12	29	17	7	2	18	44
West	2	1	1	2	6	10	3	5	2	20	12	5	3	3	23
North-West	2	...	3	1	6	1	3	5	1	10	1	5	5	...	11
Calm	2	...	...	10	12	3	...	...	1	4	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	45					37					55				
Resultant (Direction)	N. 40° E.					S. 58° W.					S. 46° W.				
Mean diurnal velocity of wind in miles	111·8					100·7					124·7				
Average Resultant (Percentage) 7-8 Years	37					16					54				
Average Resultant (Direction) 7-8 Years	N. 16° E.					S. 56° W.					S. 24° W.				
Average diurnal velocity of wind in miles 7-8 Years	105·0					100·1					124·8				

	APRIL.					MAY.					JUNE.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	1	...	1	...	...	...	...	...	...	...	...	...	...
North-East	...	...	...	...	...	1	...	1	1	3	...	1	..	...	1
East	...	1	...	...	1	...	1	1	...	2	...	...	...	...	...
South-East	1	2	7	...	9	2	3	3	1	9	1	3	3	...	7
South	3	3	7	12	25	3	3	14	8	28	14	15	12	11	52
South-West	18	12	7	14	51	13	12	5	13	43	10	10	11	13	44
West	6	7	5	1	19	4	6	3	2	15	1	...	2	2	5
North-West	...	2	...	...	2	...	1	1	...	2	...	...	...	1	1
Calm	...	...	...	...	...	4	...	...	3	7	2	..	...	1	3
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	75					65					81				
Resultant (Direction)	S. 37° W.					S. 31° W.					S. 20° W.				
Mean diurnal velocity of wind in miles	142·5					127·5					154·5				
Average Resultant (Percentage) 7-8 Years	54					55					73				
Average Resultant (Direction) 7-8 Years	S. 20° W.					S. 15° W.					S. 11° W.				
Average diurnal velocity of wind in miles 7-8 Years	145·0					122·6					135·5				

	JULY.					AUGUST.					SEPTEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	...	...	...	...	...	...	...	1	...	1	1	...	...	...	1
North-East	...	...	...	...	...	...	1	...	...	1	...	...	...	...	...
East	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-East	1	...	2	...	3	...	1	1	...	2	...	4	1	1	6
South	7	12	8	8	35	3	7	8	2	20	4	4	12	5	25
South-West	17	14	11	15	57	18	16	16	20	70	16	15	9	17	57
West	...	1	6	1	8	5	5	3	6	19	4	4	6	3	17
North-West	1	...	1	3	5	1	...	1	...	2	2	3	1	2	8
Calm	1	...	...	...	1	3	...	...	2	5	3	...	..	1	4
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	82					80					73				
Resultant (Direction)	S. 34° W.					S. 45° W.					S. 43° W.				
Mean diurnal velocity of wind in *miles*	169·7					118·1					103·6				
Average Resultant (Percentage) 8 Years	72					70					62				
Average Resultant (Direction) 8 Years	S. 27° W.					S. 29° W.					S. 21° W.				
Average diurnal velocity of wind in miles 7-8 Years	141·3					122·8					98·6				

	OCTOBER.					NOVEMBER.					DECEMBER.				
	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.	4 hours.	10 hours.	16 hours.	22 hours.	Total.
North	2	2	2	2	8	6	5	1	3	15	7	5	3	8	23
North-East	7	16	7	3	33	14	19	17	9	59	9	16	10	5	40
East	5	4	9	5	23	3	2	4	4	13	5	4	5	4	18
South-East	2	2	6	6	16	2	3	4	2	11	5	2	7	5	19
South	4	2	3	5	14	2	1	2	4	9	...	...	1	...	1
South-West	2	1	2	4	9	...	...	1	...	1	...	...	...	..	...
West	1	...	...	1	2	1	...	1	1	3	...	...	...	...	...
North-West	...	2	...	...	4	...	...	...	...	...	...	..	...	...	...
Calm	6	...	...	5	11	2	...	...	7	9	1	...	...	5	6
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant (Percentage)	39					59					66				
Resultant (Direction)	N. 87° E.					N. 56° E.					N. 58° E.				
Mean diurnal velocity of wind in miles	80·8					122·7					131·7				
Average Resultant (Percentage) 8 Years	31					55					60				
Average Resultant (Direction) 8 Years	S. 54° E.					N. 53° E.					N. 35° E.				
Average diurnal velocity of wind in miles 7-8 Years	79·9					106·1					123·1				

124.—MOULMEIN (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	7	8	15	3	1	4	1	...	1	1	...	1	...	1	1	1	...	1	...	...	...	...	...	...	3	...	3	3	2	5	4	6	10	2	13	15
North-East	11	2	13	13	...	13	1	...	1	3	1	4	4	...	4	4	1	5	...	...	...	1	...	1	2	...	2	10	7	17	10	7	17	10	5	15
East	7	2	9	6	2	8	8	...	8	2	...	2	5	...	5	...	...	...	...	...	...	1	...	1	2	...	2	10	5	15	9	5	14	10	6	15
South-East	5	3	8	1	...	1	2	...	2	2	...	2	4	...	4	5	2	7	2	...	2	2	...	2	4	...	4	5	1	6	7	5	12	9	4	13
South	...	...	...	1	...	1	1	1	2	...	1	1	7	3	10	12	7	19	12	6	18	10	2	12	5	4	9	1	2	3	...	1	1	...	...	...
South-West	1	2	3	2	6	8	18	16	34	16	17	33	10	17	27	6	15	21	13	24	37	13	24	37	9	14	23	...	3	3	...	1	1	...	...	...
West	...	3	3	1	8	9	...	13	13	3	8	11	1	7	8	1	2	3	3	...	3	3	2	5	3	7	10	1	2	3	...	1	1	...	1	1
North-West	...	11	11	1	11	12	...	1	1	3	3	6	...	3	3	1	3	4	1	1	2	1	3	4	2	5	7	1	9	10	...	4	4	...	3	3
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	43			27			60			61			51			56			85			77			52			39			56			59		
Resultant Direction	N. 24° E.			N. 20° W.			S. 48° W.			S. 61° W.			S. 36° W.			S. 21° W.			S. 33° W.			S. 41° W.			S. 53° W.			N. 52° E.			N. 64° E.			N. 60° E.		
Mean diurnal velocity of wind in miles	66·5			71·4			90·1			83·5			90·1			98·3			128·1			104.3.			81·9			56·8			58·0			72·1		
Average Resultant Percentage (4-5 Years.)	43			23			45			46			43			67			68			69			50			15			51			51		
Average Resultant Direction (4-5 Years.)	N. 35° E.			N. 7° W.			S. 54° W.			S. 59° W.			S. 46° W.			S. 19° W.			S. 32° W.			S. 33° W.			S. 35° W.			N. 65° E.			N. 57° E.			N. 56° E.		
Average diurnal velocity of wind in miles (4-5 Years.)	59·9			60·9			75·1			76·1			66·6			77·3			92·2			72·4			68·0			44·5			57·3			60·6		

125.—MERGUI (*2 observations daily*).

	January.			February.			March.			April.			May.			June.			July.			August.			September.			October.			November.			December.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	4	6	10	6	3	9	2	...	2	2	3	5	1	2	3	1	...	1	...	...	...	...	1	1	4	1	5	3	3	6	10	8	18	6	5	11
North-East	10	9	19	1	...	1	...	...	...	1	...	1	2	..	2	...	...	...	...	1	1	1	...	1	...	...	...	3	3	6	9	5	14	12	9	21
East	4	3	7	...	1	1	...	...	...	5	2	7	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	5	5	10	5	4	9	8	8	16
South-East	...	...	...	...	...	...	1	...	1	3	...	3	3	2	5	2	...	2	2	...	2	1	...	1	2	2	4	7	3	10	5	1	6	1	2	3
South	...	...	...	...	...	...	...	...	...	2	...	2	4	2	6	9	5	14	5	5	10	7	3	10	3	1	4	4	4	8	...	3	3	...	...	...
South-West	...	..	...	1	...	1	...	...	...	3	5	8	2	2	4	9	12	21	10	14	24	10	10	20	7	3	10	3	3	6	...	...	...	...	...	...
West	1	3	4	6	6	12	8	9	17	6	10	16	10	13	23	7	10	17	9	11	20	8	15	23	9	12	21	1	1	2	...	...	...	...	...	...
North-West	12	10	22	14	18	32	20	22	42	8	10	18	9	9	18	2	3	5	4	1	5	1	2	6	5	8	13	1	1	2	...	1	1	3	4	7
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	3	3	4	8	12	1	8	9	1	3	4
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	63			82			89			43			53			71			73			71			57			25			52			65		
Resultant Direction	N. 1° E.			N. 47° W.			N. 56° W.			N. 71° W.			N. 82° W.			S. 53° W.			S. 58° W.			S. 65° W.			W.			S. 61° E.			N. 46° E.			N. 44° E.		
Mean diurnal velocity of wind in miles	31·9			30·8			32·7			39·2			34·5			26·2			30·8			19·1			21·4			32·3			33·7			40·4		
Average Resultant Percentage (6-7 Years.)	60			62			44			35			33			64			55			65			62			30			46			60		
Average Resultant Direction (6-7 Years.)	N. 7° W.			N. 42° W.			N. 49° W.			N. 57° W.			S. 67° W.			S. 39° W.			S. 61° W.			S. 55° W.			S. 56° W.			S. 76° W.			N. 17° E.			N. 28° E.		
Average diurnal velocity of wind in miles (6 Years.)	46·8			48·1			47·5			52·5			54·6			51·5			49·0			42·1			37 0			35·2			39·6			43·4		

126.—PORT BLAIR (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	4	3	7	10	3	13	5	...	5	...	...	...	...	...	...		...	...	...	..	...	...	...	...	...	...	1	1	...	1	1	1	1	2
North-East	15	17	32	14	18	32	18	4	22	10	3	13	...	...	...	...	...	...	...	...	...	...	...	...	1	...	1	7	5	12	11	7	18	6	10	16
East	4	5	9	...	3	3	1	14	15	6	6	12	1	...	1	...	...	...	...	..	...	...	...	...	...	...	...	4	5	9	3	6	9	6	4	10
South-East	8	6	14	1	3	4	2	12	14	8	15	23	11	9	20	1	1	2	...	1	1	1	3	4	2	1	3	12	10	22	9	10	19	13	14	27
South	...	..	...	...	...	...	...	...	...	...	..	...	1	1	2	...	...	...	2	1	3	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
South-West	...	...	...	...	...	...	1	...	1	2	...	2	14	15	29	27	26	53	30	30	60	28	27	55	24	24	48	5	4	9	2	2	4	1	1	2
West	...	...	...	1	...	1	...	...	...	1	2	3	3	4	7	...	1	1	...	...	...	...	...	...	1	3	4	2	4	6	3	3	6	1	...	1
North-West	...	...	...	2	1	3	4	1	5	3	4	7	2	2	4	1	1	2	1	...	1	...	..	...	2	2	4	1	2	3	2	1	3	3	1	4
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	74			77			61			47			58			92			97			93			83			34			40			57		
Resultant Direction	N. 65° E.			N 36 E.			N. 70° E.			S. 83° E.			S. 25° W.			S. 44° W.			S. 45° W.			S. 39° W.			S. 49° W.			S. 61° E.			S. 89° E.			S. 83° E.		
Mean diurnal velocity of wind in miles	195·0			138·7			117·8			131·9			198·1			288·7			331·8			239·0			226·7			192·2			181·1			210·0		
Average Resultant Percentage (15 Years.)	78			76			69			45			48			82			89			82			73			24			53			72		
Average Resultant Direction (15 Years.)	N. 39° E.			N. 41° E.			N. 56° E.			N. 84° E.			S. 34° W.			S. 38° W.			S. 44° W.			S. 43° W.			S. 43° W.			S. 5° W.			N. 63° E.			N. 51° E.		
Average diurnal velocity of wind in miles (8·9 Years.)	175·3			124·0			112·6			131·7			187·3			261·5			293·6			243·7			246·2			166·5			176·0			172·4		

127.—NANCOWRY (*2 observations daily*).

	JANUARY.			FEBRUARY.			MARCH.			APRIL.			MAY.			JUNE.			JULY.			AUGUST.			SEPTEMBER.			OCTOBER.			NOVEMBER.			DECEMBER.		
	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.	10 hours.	16 hours.	Total.
North	...	...	...	1	...	1	1	...	1	3	3	6	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	2	1	3
North-East	5	5	10	11	11	22	13	15	28	3	6	9	...	...	...	..	1	1	...	...	...	...	...	...	...	...	...	3	2	5	...	3	3	5	3	8
East	23	20	43	12	13	25	10	8	18	9	6	15	...	1	1	...	...	...	...	...	...	...	...	...	...	...	...	5	7	12	10	4	14	9	14	23
South-East	3	5	8	4	4	8	5	4	9	4	1	5	3	1	4	1	...	1	...	...	...	...	...	...	...	...	...	10	8	18	7	8	15	12	6	18
South	...	...	...	...	...	...	1	2	3	1	1	2	8	4	12	8	8	16	7	4	11	7	1	8	4	4	8	1	2	3	4	3	7	2	4	6
South-West	...	...	...	...	...	...	1	2	3	7	9	16	16	18	34	19	20	39	24	27	51	24	29	53	24	25	49	11	11	22	9	12	21	1	2	3
West	...	...	...	...	...	...	...	...	...	3	3	6	4	6	10	2	...	2	...	...	...	...	...	...	1	1	2	1	...	1	...	..	..	...	1	1
North-West	...	...	...	...	...	...	...	...	...	...	1	1	...	...	...	...	1	1	...	...	...	...	1	1	1	...	1	...	...	...	...	...	...	...	...	...
Calm	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Variable	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Resultant Percentage	90			85			69			13			78			86			93			95			94			47			54			65		
Resultant Direction	N. 89° E			N. 77° E.			N. 78° E.			S. 61° E.			S. 39° W.			S. 34° W			S. 35° W.			S 40° W.			S. 42° W.			S. 24° E.			S. 21° E.			S. 72° E.		
Mean diurnal velocity of wind in miles	250·9			152·9			118·0			67·5			153 8			211·2			259·3			189·8			180·1			107·3			110·0			125·5		
Average Resultant Percentage (8 Years.)	80			81			69			31			57			90			90			90			84			64			41			76		
Average Resultant Direction (8 Years.)	S. 86° E.			N. 82° E.			E			S. 45° E.			S. 48° W.			S. 46° W.			S. 46° W.			S. 47° W.			S. 52° W.			S. 47° W.			S. 41° E.			S. 77° E.		
Average diurnal velocity of wind in miles (9·11 Years.)	229·4			198·9			146·9			115·5			156·0			258·7			271·4			245·9			234·4			144·9			127·2			163·5		

TABLE X.—TEMPERATURE OF EVAPORATION IN 1883 (124 STATIONS).

1. ZANZIBAR.

Month.	Mean	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	75·8	74·6*	76·2*	76·5*	1·9	5·6	3·6	5·0	8·1
February	76·1	75·0†	76·5†	76·9‡	1·9	5·5	3·1	4·5	8·2
March	77·0	75·9§	77·3‖	77·7§	1·8	5·9	3·5	5·7	8·6
April	75·9	75·0‖	76·2‖	76·6†	1·6	5·1	2·8	4·3	7·5
May	73·8	72·5	74·2	74·6	2·1	4·6	3·2	4·0	6·5
June	71·5	70·2	72·1	72·1	1·9	7·5	4·8	5·4	10·9
July	71·2	69·9	71·7	71·9	2·0	5·6	3·6	4·2	8·1
August	70·2	69·0	71·1	70·5	1·5	7·1	4·2	4·9	10·8
September	71·7	70·1	72·2	72·7	2·6	5·8	3·7	5·0	8·5
October	72·9	71·4	73·6	73·7	2·3	5·7	3·2	5·2	8·8
November	74·2	73·0	74·6	74·9	1·9	5·6	3·2	5·6	8·5
December	74·9	73·9	75·4	75·5	1·6	6·2	3·4	5·8	9·4
Year	73·8	72·5	74·3	74·5	1·9	5·9	3·5	5·0	8·7

* Mean of 27 days. † " " 23 " ‡ Mean of 22 days. § " " 30 " ‖ Mean of 21 days.

2. ADEN.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	70·0	67·8	71·3	70·8	3·0	5·5	4·9	6·4	7·5
February	68·5	67·2	69·6	68·7	1·5	7·0	5·8	7·8	9·3
March	72·3	71·0	73·3	72·7	1·7	6·4	4·4	6·7	9·2
April	74·1	72·3	75·8	74·3	2·0	7·5	4·9	7·5	11·7
May	77·5	75·0	78·8	78·6	3·6	6·8	6·1	7·8	8·9
June	77·1	73·8	79·4	78·1	4·3	10·0	9·3	10·5	12·9
July	72·8	70·7	74·4	73·3	2·6	8·7	6·2	8·8	12·8
August	75·9	73·9	77·7	76·0	2·1	8·4	6·6	8·8	12·0
September	77·0	73·7	79·7	77·6	3·9	8·6	7·7	9·3	12·1
October	73·8	71·4	75·0	74·9	3·5	8·1	6·1	11·3	11·3
November	70·0	67·1	71·5	71·3	4·2	6·9	5·9	8·9	9·5
December	68·8	66·6	70·4	69·5	2·9	5·6	4·7	6·6	8·0
Year	73·2	70·9	74·7	73·8	2·9	7·5	6·1	8·4	10·4

3. SEYCHELLES.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	Observatory opened in June.								
February									
March									
April									
May									
June	75·5	72·6*	78·0*	75·8†	3·2	0·8	1·5	2·8	2·7
July	75·9	72·2‡	78·6‡	77·0§	4·8	0·3	1·9	1·3	1·3
August	74·5	72·3‖	76·1¶	75·2‡	2·9	1·7	1·8	3·9	3·1
September	74·0	72·0††	75·1††	74·8**	2·8	2·8	2·5	4·8	4·2
October	74·5	71·7††	76·1††	75·0‡‡	3·3	2·4	2·8	4·0	4·2
November	73·1	70·0††	74·9††	74·3††	4·3	2·4	2·6	5·5	4·1
December	73·9	71·4‡‡	75·5‡‡	74·8‡	3·4	1·0	1·0	3·0	2·6
Year	...	...	...	...	...	...	...	...	...

* Mean of 22 days. † " " 20 " ‡ " " 25 " § Mean of 21 days. ‖ " " 24 " ¶ " " 23 " ** Mean of 26 days. †† " " 29 " ‡‡ " " 28 "

4. BUSHIRE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	54·0	49·9*	55·0*	57·1*	7·2	3·8	3·1	3·8	5·4
February	53·8	49·9	54·8	56·7	6·8	4·2	3·7	5·3	5·7
March	57·1	53·0	58·0	60·4	7·4	5·3	4·2	7·6	7·1
April	65·1	61·2	66·1	67·9	6·7	7·5	5·7	11·9	10·3
May	72·7	68·7	74·1	75·4	6·7	10·3	9·4	12·8	12·4
June	76·2	72·4	77·5	78·7	6·3	9·5	9·1	10·5	11·2
July	79·5	75·8	80·9	81·7	5·9	9·1	9·0	10·6	10·7
August	81·5	76·7	83·4	84·4	7·7	9·0	8·2	11·5	11·7
September	77·3	72·0	78·2	81·6	9·6	8·1	6·3	12·0	10·8
October	71·6	66·7*	72·6*	75·4*	8·7	8·0	5·5	11·2	11·5
November	64·4	60·2	64·9	68·0	7·8	5·9	4·1	8·5	8·2
December	57·2	51·9	57·3	62·4	10·5	3·8	3·8	5·3	3·8
Year	67·5	63·2	68·6	70·8	7·6	7·0	6·0	9·3	9·1

* Mean of 30 days.

5. QUETTA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	34·5	28·2	36·2	39·0	10·8	3·1	2·1	4·3	5·8
February	34·2	27·1*	35·6	40·0	12·9	5·6	2·1	6·9	10·3
March	42·0	35·8	44·7	45·4	9·6	6·4	3·0	9·7	12·5
April	51·3	44·3	54·7	54·8	10·5	8·6	4·5	13·5	16·1
May	54·9	47·7	58·5	58·6†	10·9	12·3	5·9	17·8	22·1
June	58·8	52·2	62·2	61·9	9·7	17·3	9·3	24·1	28·7
July	62·8	59·6†	64·2	64·6	5·0	13·5	5·8	19·1	22·6
August	57·5	51·6	60·0†	61·0	9·4	17·5	8·6	24·4	28·7
September	53·2	43·6‡	57·1‡	58·9§	15·3	15·2	7·9	21·1	26·4
October	43·7	33·2	48·1	49·8	16·6	11·1	5·4	16·6	21·1
November	36·4	26·9	39·9	42·3	15·4	7·5	3·3	11·1	15·3
December	34·6	27·1	35·9	40·9	13·8	6·3	2·1	8·8	11·7
Year	47·0	39·8	49·8	51·4	11·7	10·4	5·0	14·8	18·4

* Mean of 27 days.
† „ „ 30 „
‡ Mean of 23 days.
§ „ „ 22 „

6. LEH.

Month.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Minimum.	Range	Difference, Dry and Wet Bulb. Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Minimum.
January	17·4	22·1	...	8·8	13·3	3·3	...	3·4	5·2	...	2·7		
February	18·0	22·8	...	8·1	14·7	3·2	...	3·6	5·4	...	2·7		
March	26·6	29·2	...	16·5	12·7	5·1	...	6·9	8·8	...	3·8		
April	37·3	38·9	...	27·0	11·9	9·2	...	12·3	15·2	...	6·1		
May	40·4	40·0	...	30·8	9·2	9·1	...	13·2	15·3	...	6·2		
June	46·2	47·5	...	35·5	12·0	13·8	...	16·2	21·1	...	9·6		
July	53·4	55·7	...	41·8	13·9	15·2	...	16·9	22·1	...	11·4		
August	52·4	55·4	...	41·5	13·9	12·8	...	14·0	19·8	...	8·5		
September	47·4	49·0	41·4	37·0	12·0	12·4	6·8	13·5	18·7	10·3	7·7		
October	33·3	36·0	29·5	24·2	11·8	7·7	3·9	9·0	11·6	6·3	4·6		
November	24·1¶	28·4**	20·0**	15·9¶	12·5	5·0	2·6	5·6	7·6	4·3	3·1		
December	17·4	24·0‖	14·1	8·0	16·0	3·5	2·0	4·6	4·6	3·1	2·6		
Year	34·5	37·4	...	24·6	12·8	8·4	...	9·9	13·0	...	5·8		

‖ Mean of 26 days.
¶ „ „ 24 „
** Mean of 25 days.
†† „ „ 29 „

7. MOOLTAN.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	48·9	41·0	50·5	55·1	14·1	6·6	2·2	8·4	12·7
February	48·0	40·0	50·2	53·9	13·9	9·0	3·3	11·0	16·7
March	57·8	51·4	58·7	63·4	12·0	11·0	4·4	13·6	18·4
April	67·8	62·0	67·5	73·9	11·9	14·3	5·5	20·0	22·7
May	73·2	67·8	73·4	78·5	10·7	13·5	5·5	20·3	21·5
June	79·6	77·5	78·5	82·8	5·3	15·2	6·3	20·4	23·0
July	79·8	76·0	79·7	83·7	7·7	9·5	4·8	12·0	14·1
August	79·3	74·5	79·1	84·2	9·7	10·4	6·1	12·0	14·5
September	77·5	72·9	77·4	82·2	9·3	9·8	5·1	12·6	14·4
October	64·8	56·4	66·0	72·0*	15·6	12·6	6·4	16·6	20·0
November	54·4	44·3	56·0	62·9†	18·6	9·3	4·4	12·5	15·8
December	47·7	37·1	49·6	56·4	19·3	8·1	4·2	9·8	13·8
Year	64·9	58·4	65·6	70·8	12·3	10·8	4·9	14·1	17·3

* Mean of 30 days.

8. DERA ISMAIL KHAN.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	48·1	39·2	50·7	54·4	15·2	5·9	2·6	8·5	11·8
February	46·0	36·3	49·1	52·5	16·2	9·1	4·2	12·8	17·1
March	55·5	48·0	58·0	60·4	12·4	10·5	5·1	13·6	18·5
April	66·4	60·2	68·5	70·5	10·3	13·2	6·7	18·0	21·7
May	68·9	63·2	70·8	72·6	9·4	18·2	11·1	23·1	27·2
June	75·2	70·9	76·8	78·0	7·1	20·8	11·9	23·7	31·2
July	79·4	75·9	81·0	81·4	5·5	11·2	5·4	12·5	18·4
August	77·7	74·0	79·0	80·0	6·0	14·4	7·3	14·8	22·8
September	75·2	70·9	76·9	77·9	7·0	11·9	4·4	12·8	20·9
October	62·6	54·5	64·8	68·5	14·0	13·4	7·0	16·9	22·9
November	52·7	42·8	55·6	59·6	16·8	8·6	3·0	11·0	17·1
December	46·8	36·8	48·3	55·4	18·6	7·8	2·7	8·9	14·2
Year	62·9	56·1	65·0	67·6	11·5	12·1	6·0	14·7	20·2

† Mean of 29 days.

9. PESHAWAR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	44·3	37·8	46·0	49·2	11·4	5·6	2·3	6·3	10·4
February	44·2	36·9	46·6	49·2	12·3	7·0	2·1	9·9	13·8
March	52·4	45·5	55·2	56·6	11·1	8·2	3·4	11·1	15·6
April	62·9	56·7	65·4	66·7	10·0	10·5	5·0	16·3	18·3
May	65·3	59·4	67·6	68·8	9·4	19·0	11·8	24·3	28·5
June	71·0	64·6	73·9	74·4	9·8	20·9	12·9	26·0	31·9
July	76·4	72·5	78·0	78·8	6·3	12·2	5·8	14·3	20·1
August	75·2	70·9	77·2	77·5	6·6	13·3	7·1	15·3	21·4
September	71·4	66·5	73·6	74·2	7·7	11·9	5·0	15·3	20·8
October	58·7	51·1	61·7	63·2	12·1	12·4	6·3	17·5	21·5
November	50·2	40·4	53·4	56·9	16·5	7·0	3·3	10·5	13·8
December	44·6	35·3	46·5	51·9	16·6	5·8	2·2	7·1	11·4
Year	59·7	53·1	62·1	64·0	10·8	11·2	5·6	14·5	19·0

10. MURREE.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
33·4	29·7	35·0	35·6	5·9	2·9	3·5	5·3	3·8
34·0	29·2	36·5	36·4	7·2	2·7	3·2	5·3	4·5
40·7	35·1	43·5	43·4	8·3	4·9	5·9	7·1	6·7
51·0	45·0	53·6	54·4	9·4	7·3	7·5	9·5*	9·7
52·7	47·7*	55·4	55·1	7·4	11·8	11·4	14·6	14·8
60·0	55·3	62·2	62·6	7·3	13·3	11·6	15·8	17·0
63·7	59·3	65·5	66·4	7·1	5·8	4·4	6·6	8·8
62·8	58·4	64·8	65·2	6·8	4·3	3·8	8·8	6·8
58·7	53·7	60·7	61·6	7·9	6·2	6·0	8·2	8·4
47·3	42·8	49·4	49·7†	6·9	9·5	9·1	13·5	11·9
39·1	34·5	41·5	41·2	6·7	6·5	8·2	11·4	7·3
35·3	31·5	36·9	37·5*	6·0	5·9	6·6	9·9	6·7
48·2	43·5	50·4	50·8	7·2	6·8	6·8	9·6	8·9

* Mean of 30 days.
† „ 29 „

11. RAWALPINDI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	46·1	38·7	47·4	52·3	13·6	2·8	0·9	2·9	5·9
February	46·4	38·4	49·2	51·7	13·3	3·0	0·6	5·8	8·1
March	54·2	45·9	57·5	59·3*	13·4	4·8	1·9	7·5	10·9
April	63·7	56·1*	66·9*	68·1†	12·0	9·8	5·5	14·1	17·3
May	68·3	58·7	72·3	73·9	15·2	12·6	8·9	16·6	20·2
June	75·9	66·9	79·7	81·0	14·1	14·5	11·2	17·7	21·6
July	77·2	72·3	79·0	80·3	8·0	9·0	4·9	10·9	14·9
August	76·9	71·7	78·6	80·3	8·6	7·6	4·2	10·4	12·8
September	71·0	65·7	73·2	74·2	8·5	8·6	3·2	11·7	16·1
October	60·6	51·5	64·4	65·9*	14·4	9·2	4·7	14·1	17·4
November	51·9	41·1	55·4*	59·3	18·2	3·1	1·6	6·8	7·9
December	44·5	34·7*	48·3*	50·6*	15·9	3·9	1·0	4·4	10·4
Year	61·4	53·5	64·3	66·4	12·9	7·4	4·1	10·2	13·6

12. SIALKOT.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
49·0	42·5	49·7	54·9	12·4	4·9	1·4	4·0	8·9
48·8	41·0	50·4	55·1	14·1	5·9	1·4	5·5	11·8
56·8	49·8	59·1	61·5	11·7	8·2	2·9	9·7	15·7
64·8	59·3	66·9	68·3	9·0	16·0	8·1	20·0	25·9
67·4	62·0‡	69·4	70·8	8·8	19·6	11·2	24·4	29·9
?	?	75·2	76·8	?	?	?	21·6	29·7
76·3	69·1§	79·1	80·8	11·7	12·2	10·2	10·2	16·9
76·2	71·1‖	77·5	80·0	8·9	11·1	6·9	10·5	16·5
?	Not recorded.	76·2	78·0	?	?	?	8·7	14·5
?		63·4	66·3	?	?	?	16·5	23·9
?		55·2	59·2	?	?	?	7·2	15·5
?		47·9	53·9	?	?	?	4·8	12·8
?	?	64·2	67·1	?	?	?	11·9	18·5

* Mean of 29 days.
† „ 28 „

‡ Mean of 22 days.
§ „ 30 „
‖ „ 23 „

13. LAHORE.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.	Difference, Dry and Wet Bulb. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.
January	49·3	44·5	51·1	54·0	47·5	42·1	5·7	2·8	5·8	10·9	3·4	1·9
February	48·2	42·2	51·2	53·0	46·5	40·2	8·0	3·7	8·4	14·9	4·9	2·4
March	57·5	52·2	60·4	61·1	56·1	50 6	11·2	5·8	12·1	18·9	8·1	4·6
April	66·1	61·4	68·2	69·5	65·2	61·1	17·7	11·4	20·3	26 0	13·3	8·3
May	68·4	63·8	71·1	72·0	66·8	63·1	21·0	12·9	24·2	29·3	17·4	10·6
June	75·3	72·6	76·3	77·1	75·1	71·3	20·7	13·2	22·4	30·1	17·1	11·6
July	78·9	77·1	80·1	79·8	78·6	76·1	12·8	6·3	14·1	19·3	11·4	5·9
August	77·8	75·7	79·1	79·1	77·2	75·6	14·1	8·0	16·2	21·2	11·1	6·0
September	75·1	72·2	76 6	76·9	74·7	70·6	8·4	3·8	10·4	14·3	5·2	3·1
October	63·4	58·1	66·2	67·7	61·7	56 4	12·8	6·6	16 2	20·7	7·7	5·3
November	54·3	48·2	57·5	59·5	51·9	45·9	8·0	3·2	10·0	14·3	4·4	2·4
December	47·7	41·3	50·5	54·1	45·0	39·5	6·7	3·1	8·1	12·3	3·3	2·1
Year	63 5	59·1	65·7	67·0	62·2	57 7	12·3	6·7	14·0	19·4	8·9	5·4

14. LUDHIANA.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
49·2	41·4	51·8	54·5	13·1	4·5	2·0	6·4	9·4
48·9	41·1	51·6	54·1	13·0	5·9	2·3	8·2	12·1
58·6	52·4	60·3	63·1	10·7	9·2	4·2	12·3	15·9
68 o	64·6	68·3	71·1	6·5	13·6	2·6	21·7	24·8
73·8	70·2	74·1	77·0	6·8	14·3	3·2	22·3	25·7
?	?	78·3	80·4	?	?	?	18·0	22·8
79·0	76·5	79·6	80·9	4·4	7·8	2·3	10·3	13·9
78·3	75·9	78·9	80·0	4·1	11·6	5·3	14·9	18·5
75·2	72·1	76·6	77·0	4·9	7·3	2·0	10·4	13·9
63·2	57·5	65·7	66·4	8·9	11·8	4·4	17·0	21·6
54·8	48·1	57·3	58·9	10·8	7·1	2·1	10·5	14·7
47·7	40·1	50·1	52·9	12·8	6·4	1·7	8·9	13·4
?	?	66·1	68·0	?	?	?	13·4	17·2

15. KAILANG.

Month.	Mean	Minimum.	10 hours.	16 hours.	Range	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	...	...	...	..	...	...	...	...	...
February	...	...	...	...	...	...	...	...	...
March	...	...	...	...	...	...	...	...	...
April	...	...	...	...	...	...	...	...	...
May	...	...	...	...	...	...	...	...	...
June	...	...	...	...	...	...	...	...	...
July	?	Not recorded.	56·7*	56·0*	?	?	?	12·6	17·0
August	?		56·3	55·0	?	?	?	11·1	16·2
September	?		51·1	50·3	?	?	?	12·0	15·8
October	?		37·8	37·1	?	?	?	10·4	12·4
November	?		25·9	27·6	?	?	?	6·2	7·6
December	?		18·8	21·6*	?	?	?	4 1	4·2
Year	...		..	...	...	...	...	...	...

16. SIMLA.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
34·0	29·0	36·1	36·8	7·8	4·2	5·3	5·9	5·3
35·2	28·5	37·6	39·4	10·9	5·5	6·7	7·7	6·8
39·9	33·8	41·4	44·4	10·6	8·2	8·8	9·8	9·2
48·3	41·7	50·7	52·5	10·8	12·4	12·0	14·3	15·2
53·7	48·6†	55·9‡	56·5‡	7·9	11·5	9·7	14·1	15·5
59·7	55·9	61·6	61·7	5·8	7·0	5·7	9·6	10·1
62·4	58·6	63 6	64·9	6·3	2·1	2·4	2·5	3·0
60·7	56·7	62·0	63·3	6·6	2·6	3·0	3·2	3·6
58·9	55·3	60·2	61·1	5·8	2·9	2·6	4·4	4·5
46·3	42·2	48·3	48·3	6·1	9·6	8·1	11·9	13·2
39·8	35·2	41·3	43·0	7·8	6·9	7·1	9·0	8.0
35·2	31·5	36·8	37·3	5·8	6·9	6·2	9·0	9·2
47·8	43·1	49·5	50·8	7·7	6·7	6·5	8 5	8·6

* Mean of 30 days. † Mean of 28 days. ‡ Mean of 26 days.

TABLE X.—TEMPERATURE OF EVAPORATION IN 1883.

17. DELHI.

MONTH.	Mean.	Minimum.	10 hours.	16 hours.	Range.	DIFFERENCE, DRY AND WET BULB. Mean.	Minimum.	10 hours.	16 hours.
January	51·9	45·7	53·0	56·9	11·2	7·5	3·5	7·0	12·7
February	50·1	43·0	51·9	55·4	12·4	10·7	5·8	11·6	17·4
March	59·9	54·1	61·9	63·8	9·7	12·7	6·6	14·4	20·6
April	66·5	61·3	68·5	69·8	8·5	21·0	13·0	24·3	30·8
May	69·3	64·8	71·0	72·1	7·3	22·7	15·1	25·8	31·9
June	76·7	74·1	77·8	78·2	4·1	17·0	10·0	18·3	25·1
July	78·6	76·3	79·4	80·0	3·7	9·7	5·2	9·6	15·1
August	77·0	74·2	77·9	79·0	4·8	14·5	8·9	16·7	20·8
September	75·4	72·0	77·2	77·0	5·0	10·6	6·5	11·6	16·5
October	63·3	58·8	66·5	64·6	5·8	16·4	8·9	18·4	27·1
November	54·8	47·2	56·5	60·6	13·4	11·6	6·7	13·3	18·2
December	48·3	40·8	49·4	54·6	13·8	10·9	5·9	11·0	17·0
Year	64·3	59·4	65·9	67·7	8·3	13·8	8·0	15·2	21·1

18. SIRSA.

MONTH.	Mean.	Minimum.	10 hours.	16 hours.	Range.	DIFFERENCE, DRY AND WET BULB. Mean.	Minimum.	10 hours.	16 hours.
January	49·6	39·8	52·6	56·3	16·5	6·2	2·8	8·1	12·6
February	48·4	39·6	51·6	54·0	14·4	9·2	4·0	12·0	17·6
March	58·9	50·3	62·5	64·0	13·7	10·0	5·0	14·4	18·5
April	67·8	59·3	72·2	72·0*	12·7	16·9	10·4	22·8	27·6
May	70·6	62·6	74·2	75·0	12·4	18·2	10·9	23·6	29·0
June	74·1	71·9	74·8	75·7	3·8	20·0	11·6	25·5	29·0
July	77·9	74·8	79·4	79·5	4·7	11·3	6·4	13·6	17·7
August	76·2	72·9	78·2	77·6	4·7	16·0	9·2	18·0	24·6
September	74·2	70·6	76·4	75·7	5·1	10·2	4·3	13·8	18·1
October	62·9	55·3	66·5	66·8	11·5	14·6	6·7	19·4	26·1
November	52·4	43·1	56·7	57·5	14·4	10·5	4·4	13·8	20·7
December	46·8	36·3	50·1	53·9	17·6	9·1	3·7	11·8	17·8
Year	63·3	56·4	66·3	67·3	11·0	12·7	6·6	16·4	21·6

* Mean of 29 days.

19 CHAKRATA.

MONTH.	Mean.	Minimum.	10 hours.	16 hours.	Range.	DIFFERENCE, DRY AND WET BULB. Mean.	Minimum.	10 hours.	16 hours.
January	34·7	30·4	37·1	36·5	6·1	4·8	3·3	5·8	4·4
February	35·6	30·3	37·9	38·6	8·3	6·9	4·7	8·2	6·9
March	41·7	36·7	44·0	44·4	7·7	7·7	4·8	10·2	9·4
April	49·5	44·3	51·8	52·4	8·1	12·6	8·7	14·8	15·4
May	52·4	49·9	53·9	53·5	3·6	14·0	7·7	16·6	18·1
June	59·1	54·6	61·0	61·7	7·1	6·6	5·0	7·2	7·2
July	62·6	58·5	64·3	65·0	6·5	1·6	1·6	1·8	1·2
August	61·0	56·6	62·8	63·7	7·1	3·1	2·4	2·8	2·1
September	59·9	54·8	62·4	62·5	7·7	3·3	3·0	3·3	2·3
October	47·5	41·9	50·3	50·3	8·4	10·3	7·7	12·6	11·5
November	40·6	35·6	42·9	43·4	7·8	6·6	4·9	8·7	6·7
December	35·8	30·9	38·3	38·3	7·4	7·7	5·5	9·8	7·2
Year	48·4	43·7	50·6	50·9	7·2	7·1	4·9	8·5	7·7

20. MUSSOOREE (ST. FIDELIS).

MONTH.	Mean.	Minimum.	10 hours.	16 hours.	Range.	DIFFERENCE, DRY AND WET BULB. Mean.	Minimum.	10 hours.	16 hours.
January	38·3	33·6*	40·5*	40·9†	7·3	3·7	4·1	7·3	5·4
February	39·7	33·9‡	42·0‡	43·3‡	9·4	5·6	5·9	9·8	7·5
March	45·3	39·8*	47·6*	48·4§	8·6	7·4	7·0	10·8	10·1
April	52·5	48·2‖	55·4‖	53·8¶	5·6	13·7	11·0	17·2	19·3
May	57·4	52·4**	59·3**	60·5	8·1	12·4	10·2	17·5	16·4
June	64·2	59·2§	66·4††	67·1	7·9	4·9	3·9	6·3	8·0
July	66·1	62·4§	67·8*	68·0††	5·6	0·2	0·8	1·2	1·4
August	64·7	60·9**	66·6**	66·5	5·6	1·5	1·9	2·6	3·0
September	63·4	58·9††	65·5††	65·8†	6·9	1·3	2·5	3·8	2·2
October	52·9	47·3††	56·1††	55·3§	8·0	7·0	7·5	11·9	9·7
November	45·4	40·3†	47·9‡	48·1‡‡	7·8	4·4	5·0	8·5	6·2
December						Imperfect.			
Year	...	...	...	...	...	...	..	...	...

* Mean of 29 days. § Mean of 28 days. ** Mean of 30 days.
† ,, ,, 26 ,, ‖ ,, ,, 22 ,, †† ,, ,, 27 ,,
‡ ,, ,, 25 ,, ¶ ,, ,, 20 ,, ‡‡ ,, ,, 21 ,,

21. DEHRA (S. G. OFFICE).

Month.	Mean	Minimum.	Difference, Dry and Wet Bulb. 9-10 hours.	15-16 hours.	Range.	Mean.	Minimum.	9-10 hours.	15-16 hours.
January	...	Not recorded.	47·3	51·9	...	...	?	5·0	12·2
February	...		47·8	53·6	...	...	?	7·1	15·1
March	...		55·9	58·5	...	...	?	9·8	16·7
April	...		63·4	65·4	...	...	?	18·0	25·3
May	...		66·1	67·8	...	...	?	21·3	26·9
June	...		74·2	75·8	...	...	?	10·9	14·5
July	...		76·4	78·5	...	...	?	4·4	5·8
August	...		75·6	77·2	...	...	?	4·9	7·0
September	...		73·4	75·6	...	...	?	4·9	6·6
October	...		61·7	64·4	...	...	?	9·5	15·6
November	...		54·7	58·3	...	...	?	5·6	11·1
December	...		47·7	53·3	...	...	?	5·8	10·9
Year	...		62·0	65·0	...	...	?	9·0	14·0

22. DEHRA (FOREST SCHOOL).

Month.	Mean.	Minimum	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	46·6	38·6	49·2	51·9	13·3	4·8	1·7	7·5	10·5
February	47·3	38·5	40·9	53·6	15·1	6·1	1·7	8·6	13·0
March	53·7	46·2	57·1	57·8	11·6	8·1	2·9	11·5	16·7
April	61·2	54·7	63·9	65·1	10·4	13·5	4·6	19·6	25·0
May	64·2	59·6	66·2	66·8	7·2	15·3	6·3	23·8	26·3
June	72·3	68·8	73·6	74·6	5·8	9·0	3·9	11·7	15·2
July	74·9	72·0	75·5	77·3	5·3	3·7	1·8	5·2	6·0
August	74·2	70·7	75·3	76·5	5·8	4·2	2·0	6·4	7·6
September	72·3	67·9	74·0	75·0	7·1	3·9	2·0	7·0	7·5
October	59·1	52·2	62·2	63·0	10·8	9·3	2·3	14·1	19·2
November	52·4	45·4	55·0	56·9	11·5	5·3	1·0	8·8	12·1
December	46·0	36·5	49·2	52·3	15·8	5·1	1·4	8·7	12·0
Year	60·4	54·3	62·6	64·2	10·0	7·4	2·6	11·1	14·3

23. PAORI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	39·7	35·2	42·2	41·7	6·5	5·0	3·2	5·6	7·0
February	41·4	36·0	44·2	43·9	7·9	7·5	4·4	7·3	10·0
March	47·1	42·4	50·1*	48·9*	6·5	8·4	5·0	8·1	12·6
April	54·9	49·9	58·5	56·2	6·3	13·7	8·2	12·8	19·7
May	57·9	53·0	61·0	59·7	6·7	14·3	9·4	14·2	19·4
June	65·6	61·9	67·9	66·9	5·0	8·6	5·1	8·6	12·7
July	68·2	65·2	69·8	69·6	4·4	3·5	2·3	3·3	4·9
August	66·9	63·6*	69·0	68·2	4·6	4·2	2·4	3·5	6·2
September	65·4	62·0†	67·7	66·6	4·6	4·0	2·0	3·7	6·3
October	52·8	47·9*	57·0*	53·6*	5·7	8·4	5·3	9·0	13·5
November	46·3	40·9	49·5	48·4	7·5	5·4	3·4	5·1	7·9
December	Abolished.								
Year									

24. ROORKEE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	48·8	39·8	51·7	54·8	15·0	7·9	4·3	7·1	12·3
February	49·5	42·2	52·1	54·1	11·9	7·6	1·9	7·5	15·3
March	?	Imperfect.	60·5	61·4	?	?	?	11·5	18·4
April	63·6	55·1†	67·9	67·8	12·7	20·6	12·2	21·6	28·9
May	66·2	58·4	70·0	70·2	11·8	21·9	14·8	23·3	30·3
June	75·2	69·6	77·6	78·3	8·7	14·1	9·5	13·5	20·1
July	77·8	73·2	79·3	80·8	7·6	6·9	5·3	6·7	9·2
August	76·4	71·5	78·2	79·4	7·9	8·9	6·4	8·5	12·9
September	74·9	69·0	78·0	77·7	8·7	7·0	4·7	6·8	10·7
October	61·9	52·5	66·0	67·3	14·8	12·2	6·2	14·7	19·6
November	54·2	44·8	58·4	59·5	14·7	8·5	5·6	9·5	13·6
December	47·2	35·7	51·2	54·6	18·9	8·0	4·9	7·9	13·0
Year	?	?	65·9	67·2	?	?	?	11·6	17·0

* Mean of 30 days.

† Mean of 29 days.

25. RANIKHET.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	38·0	33·1	40·1	40·8	7·7	5·5	4·5	6·3	6·6
February	39·0	33·2	41·3	42·5	9·3	9·2	7·2	9·1	10·3
March	44·6	39·1	46·9	47·7	8·6	9·1	7·0	9·9	11·1
April	53·1	48·2	55·5	55·5	7·3	14·3	10·2	15·3	17·0
May	55·0	50·3	56·9	57·7	7·4	13·9	10·9	15·5	15·4
June	63·1	58·6	64·8	65·8	7·2	7·0	4·6	7·6	9·4
July	64·6	61·2*	65·8	66·9	5·7	3·2	1·9	3·4	4·3
August	63·4	59·8	64·5	66·0	6·2	4·1	2·4	4·6	5·0
September	62·5	58·3	63·9	65·4	7·1	3·7	2·2	4·3	4·5
October	51·2	45·9	53·4	54·3	8·4	9·5	7·6	11·8	11·5
November	44·2	38·8	46·4	47·3	8·5	7·4	5·7	8·4	8·3
December	39·2	33·3	41·6	42·6	9·3	7·2	6·7	7·9	7·6
Year	51·5	46·7	53·4	54·4	7·7	7·8	5·9	8·7	9·3

* Mean of 30 days.

26. PITHORAGARH.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	41·4	36·3	44·0	43·8	7·5	5·5	2·9	5·8	9·1
February	43·5	37·3†	46·3†	46·8	9·5	8·8	4·4	8·3	12·5
March	48·4	43·0	51·2	51·0	8·0	8·9	4·7	8·9	13·6
April	55·0	47·6	57·9	57·4	7·8	14·2	8·7	14·8	18·6
May	57·3	52·5	59·7	59·7	7·2	13·4	8·7	14·5	16·9
June	65·6	61·2	67·3	68·3	7·1	6·0	3·4	6·0	9·1
July	67·9	64·4	59·4	69·9	5·5	3·6	2·0	3·4	5·5
August	66·9	63·3	68·5	68·9	5·6	4·3	2·2	4·0	6·4
September	65·5	61·4	67·4	67·8	6·4	4·7	2·1	4·6	7·3
October	54·8	49·6	57·7	57·0	7·4	9·0	4·9	9·6	15·7
November	47·1	41·2‡	50·2‡	49·9‡	8·7	8·0	4·0	8·0	12·0
December	41·6	35·5	44·7†	44·7†	9·2	7·7	4·3	8·1	11·3
Year	54·6	49·6	57·0	57·1	7·5	7·8	4·4	8·0	11·5

† Mean of 27 days.
‡ „ „ 29 „

27. MEERUT.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	50·0	42·5	52·1	55·4	12·9	6·7	1·4	6·0	11·7
February	48·8	40·2	51·8	54·5	14·3	9·2	2·9	8·9	15·7
March	58·2	50·4	61·4	62·7	12·3	12·1	5·1	12·8	19·4
April	65·0	57·1	68·4	69·6	12·5	20·0	11·3	23·1	27·7
May	67·5	58·5*	70·9†	73·0*	14·5	21·3	15·7	23·7	26·5
June	74·5	70·1	76·1	77·4	7·3	17·0	10·7	17·6	22·5
July	77·6	73·9	78·6	80·2	6·3	9·1	6·2	8·7	10·8
August	76·0	72·3	77·1	78·6	6·3	12·4	8·2	12·8	15·4
September	73·8	68·9	76·3	76·1	7·2	9·9	5·9	10·5	14·5
October	62·5	55·7	65·4	66·5	10·8	13·0	5·6	15·1	21·8
November	53·6	45·8	56·0	59·1	13·3	9·2	3·0	10·3	16·0
December	47·0	39·2	48·9	53·0	13·8	8·6	1·3	9·0	15·3
Year	62·9	56·2	65·3	67·2	11·0	12·4	6·4	13·2	18·1

* Mean of 28 days. † Mean of 29 days.

28. BAREILLY.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	52·0	45·1	54·2	56·6	11·5	6·9	1·8	6·8	12·1
February	51·6	43·5	54·4	56·8	13·3	8·3	2·7	8·4	14·8
March	61·0	53·6	64·1	65·3	11·7	9·9	3·7	11·2	17·1
April	67·3	60·1	69·9	72·0	11·9	18·1	9·2	21·3	26·8
May	71·9	65·1	75·2	75·3	10·2	16·5	9·7	18·6	25·8
June	78·9	75·2	80·2	81·4	6·2	11·9	5·4	13·2	19·2
July	78·6	76·0	79·2	80·7	4·7	6·1	2·9	6·7	9·6
August	78·6	75·3	79·4	81·0	5·7	7·4	3·8	8·5	12·0
September	76·8	73·8	78·9	77·6	3·8	7·2	2·7	8·0	12·4
October	64·7	59·2	67·7	67·3	8·1	12·1	4·0	15·7	22·0
November	55·9	48·0	58·7	61·1	13·1	8·9	3·4	10·9	16·9
December	48·4	39·3	50·4	55·4	16·1	7·6	2·9	8·6	15·0
Year	65·5	59·5	67·7	69·2	9·7	10·1	4·4	11·5	17·0

29. AGRA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	53·3	47·3	54·4	58·2	10·9	8·9	2·0	9·1	13·6
February	51·4	45·4	52·6	56·3	10·9	11·4	3·3	11·7	18·3
March	59·8	54·6	61·4	63·3	8·7	16·3	6·5	16·6	24·1
April	66·1	61·2	67·8	69·3	8·1	24·8	12·9	25·6	34·1
May	69·0	65·1	70·6	71·4	6·3	25·9	15·7	26·1	34·3
June	75·9	73·7	76·9	77·2	3·5	18·7	10·4	19·8	26·5
July	78·5	76·5	79·2	79·9	3·4	8·0	3·2	7·6	11·1
August	77·5	75·2	78·3	79·0	3·8	13·7	6·6	13·3	17·6
September	75·6	73·6	76·8	76·3	2·7	12·0	4·3	12·6	17·1
October	64·1	59·8	65·8	66·6	6·8	18·2	8·6	19·9	27·0
November	54·9	48·2	56·7	59·7	11·5	14·6	5·7	15·8	22·4
December	49·5	41·3	51·4	55·8	14·5	11·4	3·9	12·0	18·2
Year	64·6	60·2	66·0	67·8	7·6	15·3	6·9	15·8	22·0

30. LUCKNOW.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
53·1	45·1	55·9	58·2	13·1	8·8	1·5	8·9	13·6
51·8	45·0	53·8	56·6	11·6	10·9	3·4	11·7	17·7
60·0	54·6	62·1	63·2	8·6	14·7	5·3	16·9	23·0
69·3	62·0	71·8	74·0	12·0	19·7	10·7	22·5	27·7
74·7	68·3	77·3	78·5	10·2	18·0	9·4	18·5	26·1
77·9	75·1	78·8	79·9	4·8	13·9	6·2	15·1	19·7
79·1	77·0	80·0	80·4	3·4	6·4	3·0	7·1	9·1
78·8	76·8	79·5	80·2	3·4	8·1	3·2	9·5	11·6
77·5	75·1	78·9	78·6	3·5	7·7	1·5	9·3	12·3
66·1	60·3	69·2	68·9	8·6	11·7	2·2	15·8	20·6
56·2	47·9	59·6	61·2	13·3	10·4	2·1	15·1	16·8
50·1	40·4	53·7	56·1	15·7	8·4	1·9	11·3	15·1
66·2	60·6	68·4	69·7	9·0	11·6	4·2	13·5	17·8

31. GORAKHPUR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	?	Imperfect.	57·3	59·3	?	?	?	6·6	10·5
February	54·1	46·2	56·5	59·5	13·3	7·1	3·8	7·2	12·7
March	62·4	55·6	64·9	66·8	11·2	12·1	5·4	12·8	18·8
April	69·2	62·9	71·8	72·8	9·9	16·1	8·4	17·4	24·5
May	75·3	71·1	76·9	77·8	6·7	13·8	6·7	13·2	22·4
June	78·3	75·2	79·5	80·2	5·0	7·8	3·8	8·3	11·4
July	80·4	78·0	81·3	82·0	4·0	4·2	1·8	5·0	6·9
August	80·3	78·2	80·8	81·8	3·6	5·1	1·7	5·8	7·5
September	79·6	77·3	80·7	80·9	3·6	5·4	1·1	5·9	8·3
October	70·4	66·4	72·9	71·9	5·5	9·7	2·0	11·6	17·0
November	59·6	52·6	63·1	63·2	10·6	8·1	2·1	11·6	15·5
December	53·2	43·8	56·9	58·9	15·1	6·9	2·2	8·6	11·8
Year	?	?	70·2	71·3	?	?	?	9·5	13·9

32. JHANSI.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
54·6	47·8	57·3	58·7	10·9	8·9	3·1	9·9	13·0
51·5	47·1	51·1	56·2	9·1	13·0	4·5	17·1	18·1
62·0	57·5	63·6	64·9	7·4	15·2	5·9	17·8	22·7
67·0	62·6	68·5	70·0	7·4	24·5	13·2	29·7	32·4
72·2	70·1	72·9	73·7	3·6	23·3	12·7	27·5	*30·2
76·5	75·2	76·9	77·5	2·3	17·5	7·4	20·9	21·4
76·8	74·6	77·5	78·2	3·6	6·6	2·7	8·2	9·2
76·7	74·7	77·4	78·0	3·3	9·6	3·7	12·1	13·0
75·3	74·2	76·9	74·8	0·6	8·6	2·0	11·1	14·3
67·0	64·5	68·0	68·5	4·0	14·3	3·7	19·9	20·8
55·6	49·5	58·1*	59·3*	9·8	16·0	6·0	20·2*	20·9*
50·0	41·9	53·3	54·8	12·9	12·4	5·7	14·6	17·8
65·4	61·6	66·8	67·9	6·2	14·2	5·9	17·4	19·5

* Mean of 29 days.

33. ALLAHABAD.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.	Difference, Dry and Wet Bulb. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.
January	55·3	50·7	56·7	59·8	54·1	48·4	4·9	1·1	6·3	9·9	2·2	1·0
February	53·1	47·9	54·3	58·2	51·8	46·8	8·7	3·3	10·5	16·1	5·0	1·8
March	60·8	56·1	63·0	65·0	59·0	55·3	14·8	7·1	17·6	23·5	11·1	5·4
April	67·4	62·3	70·5	71·1	65·8	61·0	21·6	12·4	24·5	31·6	17·6	11·0
May	71·8	68·6	74·0	74·1	70·4	67·3	21·6	13·1	24·4	31·7	17·4	11·6
June	77·9	76·0	79·4	79·1	77·0	75·3	12·9	7·2	14·8	18·9	10·7	6·5
July	79·7	78·3	80·5	80·5	79·4*	77·0	5·0	2·7	5·7	8·4	3·4	2·6
August	79·2	77·4*	80·1	80·6	78·8	77·0	6·6	3·4	8·1	10·2	4·5	2·9
September	78·6	77·0	79·8	79·8	77·8	75·9	4·4	1·1	6·1	8·0	2·4	1·0
October	68·0	65·1	70·1	70·4	66·3	63·9	9·2	3·0	12·1	16·5	5·3	2·3
November	57·1	52·3	58·9	62·1	55·1	51·1	9·2	2·9	12·5	16·2	5·3	1·3
December	51·0	45·0	52·5	57·4	49·0	43·0	7·2	2·0	9·3	13·8	3·7	1·2
Year	66·7	63·1	68·3	69·8	65·4	61·8	10·5	4·9	12·7	17·1	7·4	4·1

* Mean of 30 days.

34. BENARES.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	54·9	48·4*	56·9	59·3	10·9	6·7	1·4	6·7	12·7
February	52·7	46·6	54·3	57·1	10·5	10·5	3·1	12·3	18·7
March	60·4	55·1	62·3	63·9*	8·8	15·6	6·4	18·3	25·2
April	67·9	63·1	70·1	70·5	7·4	20·3	9·5	23·8	32·1
May	72·5	69·5	74·3	73·6*	4·1	20·1	10·3	21·5	32·0
June	77·4	75·4	78·7	78·0	2·6	11·0	5·5	12·3	16·5
July	79·0	77·1	79·6	80·2	3·1	5·7	3·1	6·5	8·9
August	78·7	76·7	79·5	79·8	3·1	7·4	3·6	8·1	10·6
September	78·1	75·9	79·3	79·2	3·3	6·1	2·3	7·0	10·7
October	67·6	63·5	69·9	69·3	5·8	10·8	3·6	13·8	19·6
November	57·9	51·9	59·7	62·2	10·3	9·6	2·3	13·4	17·3
December	50·5	42·2	53·0	56·4	14·2	8·0	2·3	10·3	15·7
Year	66·5	62·1	68·1	69·1	7·0	11·0	4·5	12·8	18·3

35. GHAZIPUR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	...	Not recorded.	56·2	58·6	...	...	...	6·7	12·4
February	...		54·4	56·9	...	...	...	11·0	17·7
March	...		62·5	63·2	...	...	...	18·7	25·2
April	...		68·5	69·6	...	...	...	25·5	31·7
May	...		74·7*	73·5	...	...	...	20·2	29·8
June	...		78·8	78·3	...	...	...	12·3	14·6
July	...		80·1	80·3	...	...	...	6·8	8·8
August	...		80·0	80·1	...	...	...	7·8	9·8
September	...		80·1	80·7	...	...	...	7·3	8·5
October	...		72·7	75·4	...	...	...	10·3	13·6
November	...		59·9	62·3	...	...	...	11·6	16·0
December	...		52·3	57·0	...	...	...	8·2	13·4
Year	...		68·4	69·7	...	...	...	12·2	16·8

36. KATMANDU.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	45·0	35·6	48·4	51·0	15·4	2·4	1·0	3·7	7·1
February	44·4	34·4	46·1	52·8	18·4	5·4	1·4	5·4	11·0
March	51·3	42·1	53·7	58·0	15·9	6·6	1·2	8·8	14·5
April	57·1	48·2	60·4	62·6	14·4	6·4	1·0	11·6	15·1
May	64·8	56·4	67·5	70·5	14·1	3·3	0·9	9·1	8·4
June	68·7	63·3	70·7	72·1	8·8	3·3	0·9	7·3	7·6
July	70·3	65·8	72·2	72·8	7·0	2·6	0·8	6·3	6·3
August	69·6	65·8	71·1	71·8	6·0	2·3	1·1	5·9	5·1
September	67·9	64·2	69·5	69·9	5·7	3·2	1·0	8·7	7·0
October	59·3	51·7	62·5	63·8	12·1	4·3	1·0	9·2	10·7
November	49·9	38·9	53·9	56·8	17·9	3·4	1·3	7·3	9·5
December	40·9	30·4	42·8	49·5	19·1	4·8	2·0	5·0	9·5
Year	57·4	49·7	59·9	62·6	12·9	4·0	1·1	7·4	9·3

* Mean of 30 days.

37. SIBSAGAR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	55·8	49·3	57·0	61·0	11·7	3·1	0·2	1·0	6·4
February	57·7	51·6	59·3	62·1	10·5	4·0	0·3	1·9	8·1
March	63·1	58·0	64·5	66·7	8·7	4·7	0·6	3·8	8·6
April	69·6	65·1	70·5	73·1	8·0	4·8	1·0	4·4	8·4
May	74·3	70·9	75·4	76·6	5·7	4·0	0·9	3·4	6·4
June	78·6	75·6	79·5	80·7	5·1	4·9	1·3	3·9	7·0
July	79·5	76·8	79·9	81·9	5·1	5·4	1·4	4·1	8·7
August	79·1	76·7	79·6	81·1	4·4	4·1	1·2	3·2	7·2
September	78·3	75·3	79·4	80·1	4·8	3·9	1·0	3·3	6·3
October	73·3	69·1	74·8	76·0	6·9	3·9	0·8	3·4	7·5
November	64·4	58·9	66·2	68·1	9·2	4·0	0·5	3·7	7·9
December	56·5	49·8	58·4	61·3	11·5	3·2	0·2	1·0	5·9
Year	69·2	64·8	70·4	72·4	7·6	4·2	0·8	3·1	7·4

38. DHUBRI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	58·6	53·4	59·3	63·0	9·6	3·7	0·7	2·5	7·4
February	56·8	51·6	58·0	60·8	9·2	7·8	2·2	6·8	14·5
March	64·2	59·8	65·7	67·2	7·4	10·8	4·0	9·7	19·0
April	70·7	67·3	72·0	72·8	5·5	8·6	3·8	7·7	14·6
May	73·3	70·3	73·7	75·8	5·5	3·7	1·9	3·5	5·9
June	78·0	76·3	78·5	79·2	2·9	3·0	1·6	3·3	4·8
July	79·3	77·4	79·9	80·6	3·2	3·7	2·3	4·2	5·6
August	78·6	76·8	79·3	79·7	2·9	2·6	1·7	3·0	4·2
September	77·6	75·6	78·3	78·9	3·3	3·0	1·9	3·4	4·8
October	73·2	70·6	74·0	75·0	4·4	4·6	2·1	5·0	7·8
November	64·7	60·8	65·6	67·8	7·0	5·6	2·0	5·7	9·9
December	58·5	53·7	59·5	62·2	8·5	4·0	1·1	3·5	8·0
Year	69·5	66·1	70·3	71·9	5·8	5·1	2·1	4·9	8·9

39. TURA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	Observatory opened in June.								
February									
March									
April									
May									
June	...	...	75·9	76·0	?	...	...	4·5	5·2
July	...	Wet mint. not recorded.	76·9	76·9	?	...	...	3·9	5·0
August	...		76·6	76·3	?	...	...	3·4	3·6
September	...		76·0	76·2	?	...	...	3·9	4·2
October	...		72·4	73·0	?	...	...	7·1	6·4
November	...		64·4	66·0	?	..	...	8·8	9·5
December	...		59·0	60·7	?	...	..	7·1	8·0
Year	...	...	...	...	...	...	...	...	...

40. SILCHAR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	58·3	50·8	61·2	62·9	12·1	5·4	0·9	5·0	11·8
February	58·5	51·3	61·7	62·6	11·3	7·1	1·0	7·0	15·0
March	67·4	62·7	68·8	70·7	8·0	6·5	0·9	6·6	13·2
April	71·7	66·9	73·0	75·3	8·4	6·1	1·1	6·9	11·3
May	73·0	70·3	74·2	74·6	4·3	3·2	0·6	3·5	5·6
June	78·2	75·7	79·2	79·6	3·9	3·4	0·6	4·3	5·6
July	79·3	76·3	80·2	81·3	5·0	4·5	0·8	5·5	7·5
August	78·5	75·7	79·1	80·6	4·9	3·2	0·5	3·4	6·0
September	78·1	75·6	78·7	80·0	4·4	3·6	0·7	3·9	6·5
October	74·8	70·4	76·5	77·5	7·1	4·5	0·7	4·8	8·8
November	67·8	62·0	70·0	71·3	9·3	4·9	1·0	5·8	9·9
December	60·5	54·2	62·4	64·8	10·6	4·0	0·5	3·9	8·8
Year	70·5	66·0	72·1	73·4	7·4	4·7	0·8	5·1	9·2

41. DARJEELING (ST. PAUL'S SCHOOL).

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean	Minimum.	10 hours.	16 hours.
January	36·8	33·1*	38·1	39·1†	6·0	1·1	1·2	1·4	1·1
February	37·7	32·5‡	39·8	40·9§	8·4	1·6	1·3	1·6	2·0
March	?	Not recorded.	45·9†	46·5*	?	?	?	4·6	4·8
April	?		52·7‖	54·0§	?	?	?	4·8	4·5
May	?		56·6†	57·1¶	?	?	?	2·2	3·3
June	?		60·1	61·4‖	?	?	?	1·4	1·6
July	60·8	56·5‖	62·7	63·1†	6·6	1·0	0·6	1·4	1·3
August	59·9	56·5	61·4	61·7	5·2	0·9	0·7	1·0	1·2
September	58·6	55 1	60·2	60·5§	5·4	0·8	0·6	1 1	1·1
October	52·3	47·5§	54·9§	54·5**	7·0	1·8	1·4	2·1	2·3
November	43·7	38·2¶	46·1*	46·8*	8·6	2·5	1·7	4·1	2·5
December	37·7	32·6	39·6	40·8	8·2	3·5	2·4	5·2	4·0
Year	?	?	51·5	52·2	?	?	?	2·6	2·5

42. PURNEAH.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean	Minimum.	10 hours.	16 hours.
January	55·8	48·1†	58·5†	60·7	12·6	6·2	1·1	5·7	12·0
February	?	48·2††	56·7††	Imperfect		?	1·8	9·4	?
March	61·4	55·0	64·3	65·0	10·0	13·4	3·3	14·9	22·7
April	69·3	64·2	71·6	72·1	7·9	13·8	4·5	14·0*	22·9
May	76·1	72·3	77·3	78·6	6·3	7·5	1·7	8·4	12·5
June	78·4	75·6	79·5	80·1	4·5	5·9	2·1	6·7	9·5
July	80·6	78·0	81·9	81·9	3·9	4·3	1 2	5·0	6·1
August	79·6	76·9‡‡	80·8‡‡	81·2‡‡	4·3*	3·8	0·9	4·0	5·5
September	79·3	76·6	80·4	80·8	4·2	4·1	1·0	4·6	5·9
October	72·8	68·1	75·3	74·9	6·8	6·0	1·4	7·8	10·6
November	61·3	53·4	64·4	66·0	12·6	7·4	1·4	9·4	12·9
December	53·8	43·8	57·1	60·5	16·7	5·8	0·9	6·7	11·5
Year	?	63·4	70·7	?	?	?	1·8	8·1	?

* Mean of 26 days. † Mean of 30 days. ** Mean of 23 days. †† Mean of 19 days. ‡‡ Mean of 29 days.
‡ ,, ,, 24 ,, § ,, ,, 27 ,,
‖ ,, ,, 28 ,, ¶ ,, ,, 25 ,,

43. DURBHUNGA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean	Minimum.	10 hours.	16 hours.
January	57·7	5·25	59·1	61·4	8·9	4·7	1·1	4·5	9·1
February	55·8	50·0	57·5	59·9	9·9	7·7	2·6	7·6	13·5
March	63·0	57·6	64·9	66·5*	8·9	11·7	4·1	12·4	19·1
April	70·8	66·3	72·2	74·0	7·7	12·8	4·2	14·0	20·0
May	76·7	73·1	77·6	79·5	6·4	8·4	3·3	8·7	13·2
June	78·9	76·7	79·6	80·3	3·6	6·1	2·4	6·2	9·8
July	80·9	78·9	81·6	82·2	3·3	4·0	1·7	4·4	5·4
August	80·7	77·8	81·6	82·8	5·0	3·1	2·0	2·8	3·8
September	80·7	77·3	81·7	83·0	5·7	3·2	1·7	3·2	4·2
October	73·9	70·3	75·4	76·0	5·7	5·9	2·1	6·2	10·1
November	62·1	56·5	63·8	65·9	9·4	7·4	2·7	7·9	13·0
December	55·7	48·8	57·2	61·0	12·2	6·1	2·2	6·2	10·6
Year	69·7	65·5	71·0	72·7	7·2	6·8	2·5	7·0	11·0

44. PATNA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean	Minimum.	10 hours.	16 hours.
January	55·9	49·6	58·0	60·2	10·6	6·2	2·0	6·0	11·0
February	54·6	47·6	57·2	59·1	11·5	9·4	3·5	9·8	15·7
March	61·7	55·9	63·9	65·3	9·4	15·0	6·3	16·6	22·9
April	68·5	63·4	70·6	71·4	8·0	18·8	8·6	19·9	28·0
May	75·4	72·5	76·9	76·8	4·3	14·7	5·5	14·6	24·1
June	77·9	76·0	78·8	78·9	2·9	8·3	3·9	9·1	12·0
July	79·6	78·2	80·1	80·6	2·4	4·8	2·0	5·2	6·4
August	79·4	77·7	80·0	80·6	2·9	4·8	2·2	5·3	6·1
September	79·4	77·4	80·2	80·6	3·2	5·3	2·1	5·7	7·5
October	70·6	68·2	72·1	71·4	3·2	9·8	3·0	11·5	15·5
November	59·8	54·0	62·2	63·3	9·3	9·8	3·4	11·5	15·8
December	53·1	45·6	55·2	58·5	12·9	7·7	2·6	8·6	12·8
Year	68·0	63·8	69·6	70·6	6·7	9·6	3·8	10·3	14·8

* Mean of 30 days.

45. GYA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	55·8	50·1	58·2	59·0	8·9	8·2	2·6	9·1	13·7
February	54·0	48·3	56·2	57·5	9·2	12·6	5·7	14·0	19·1
March	61·1	56·1	63·3	63·8	7·7	18·3	10·6	20·6	25·3
April	67·1	62·9	69·2	69·1	6·2	24·7	14·6	28·0	33·1
May	72·4	70·9	71·5	74·7	3·8	23·0	10·3	27·2	30·7
June	77·7	74·9	79·2	79·1	4·2	10·1	5·7	10·9	13·7
July	79·1	76·5*	80·0	80·7	4·2	5·0	2·4	5·8	7·3
August	79·2	76·5	80·4	80·7	4·2	6·5	3·4	7·8	8·4
September	78·6	76·0	80·4	79·5	3·5	6·7	2·5	7·7	9·5
October	68·9	64·8	71·6	70·2	5·4	12·6	5·1	15·2	17·6
November	59·6	54·0	62·6	62·2	8·2	11·3	4·1	14·8	16·6
December	51·9	44·1	55·5	56·0	11·9	10·2	3·5	12·6	16·2
Year	67·1	62·9	69·0	69·4	6·5	12·4	5·9	14·5	17·6

* Mean of 30 days.

46. HAZARIBAGH.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
52·4	47·8	54·3	55·7	7·9	8·0	3·3	10·0	12·8
50·6	45·2	52·4	55·0	9·8	11·8	6·5	15·1	17·7
59·0	54·3	60·3	62·1	7·8	14·2	8·3	17·4	20·9
63·8	59·8	65·6	66·4	6·6	22·2	13·6	25·8	30·1
68·7	65·8	70·1	69·2	3·4	20·5	11·2	24·6	28·9
73·8	72·0	74·3	74·5	2·5	7·6	3·2	10·6	11·1
74·8	72·8	75·0	75·6	2·8	2·8	0·8	4·1	4·7
74·3	72·2	74·7	75·1	2·9	4·1	1·4	5·5	5·7
73·9	71·8	74·8	74·5	2·7	4·2	1·1	5·8	6·9
63·6	60·3	65·2	65·3	5·0	11·7	6·3	14·3	17·0
54·8	50·3	56·6	57·9	7·6	10·3	5·5	12·6	15·3
48·7	43·2	51·3	52·3	9·1	9·3	4·8	11·2	14·5
63·2	59·6	64·6	65·3	5·7	10·6	5·5	13·1	15·5

47. BERHAMPORE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	57·9	51·8	60·2	61·8	10·0	5·9	1·4	6·3	12·5
February	56·7	50·6	58·4	61·1	10·5	9·8	3·2	11·8	18·3
March	64·7	59·6	66·8	67·7	8·1	11·9	4·5	15·0	21·9
April	72·5	66·7	75·8	74·9	8·2	12·2	7·2	13·4	23·4
May	78·6	73·9	80·7	81·3	7·4	5·7	3·7	7·1	12·7
June	79·4	76·3	80·8	81·0	4·7	3·2	1·8	5·0	6·8
July	79·6	77·3	80·4	81·2	3·9	2·8	1·5	3·8	5·2
August	79·2	77·1	80·2	80·2	3·1	2·4	1·4	4·0	4·4
September	79·3	77·0	80·3	80·5	3·5	3·6	1·2	5·0	7·5
October	74·2	71·1	76·2	75·4	4·3	6·0	1·8	8·0	12·1
November	63·2	57·7	65·4	66·6	8·9	7·7	2·3	10·0	14·1
December	56·6	49·7	58·4	61·6	11·9	5·7	1·7	6·8	11·4
Year	70·2	65·7	72·0	72·8	7·0	6·4	2·6	8·0	12·5

48. BURDWAN.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
57·6	52·6	59·2	60·9	8·3	7·1	0·9	9·3	14·1
58·0	53·4	58·7	61·8	8·4	9·4	2·0	12·7	17·4
66·5	63·6	67·6	68·4	4·8	10·8	3·5	13·1	20·7
72·8	69·7	75·3	73·5	3·8	11·4	4·6	12·7	23·7
78·8	75·7	79·8	80·8	5·1	6·5	2·9	8·9	14·0
78·8	76·6	79·7	80·0	3·4	4·7	2·2	6·8	9·3
79·1	77·5	79·3	80·4	2·9	3·5	1·6	4·8	6·2
78·6	76·7	79·1	79·9	3·2	3·1	1·7	4·7	5·6
79·0	77·6	79·5	79·8	2·2	3·9	1·5	5·5	7·2
73·2	71·6	74·5	73·5	1·9	7·0	1·6	10·0	13·7
62·0	58·1	63·5	64·4	6·3	9·1	3·0	12·2	15·4
55·8	50·9	57·0	59·6	8·7	7·2	2·4	8·9	13·0
70·0	67·0	71·1	71·9	4·9	7·0	2·3	9·1	13·4

49. JESSORE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	57·9	50 2	61·6	61·9	11·7	6·0	1·3	7·5	12·6
February	58·6	51·9	61·1	62·8	10·9	8·6	2·6	11·0	16·3
March	68·3	63·8	71·0	70·1	6·3	9·2	4·0	10·0	18·9
April	74·5	69·0	77·2	77·2	8·2	7·3	3·5	9·5	15·9
May	79·2	74·6	81·3	81·7	7·1	4·5	2·5	7·1	9·8
June	79·8	76·9	81·6	80·9	4·0	2·8	1·8	5·2	5·2
July	79·9	77·6	80·9	81·3	3·7	2·5	1·3	3·7	4·7
August	9·8	77·6	81·0	80·7	3·1	2·4	1·3	4·2	4·2
September	79·5	77·4	80·8	80·2	2·8	2·6	1·0	4·3	5·0
October	75·5	71·8	77·5	77·2	5·4	4·9	1·5	7·7	9·6
November	63·9	57·2	67·2	67·4	10·2	7·1	1·7	10·8	12·6
December	58·3	51·3	61·2	62·5‡	11·2	5·0	1·3	6·9	9·5
Year	71·3	66·6	73·5	73·7	7·1	5·2	2·0	7·3	10·4

50. DACCA.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
59·4	52·2*	62·6	63·3	11·1	6·4	1·4	6·8	11·8
59·5	52·4†	62·0	64·2	11·8	9·5	1·3	11·2	16·0
69·8	65·8	72·0	71·6	5·8	9·3	2·2	10·0	17·0
75·4	71·4*	77·7*	77·2	5·8	8·0	2·0	8·9	13·5
79·0	73·9	81·1	81·9	8·0	4·6	1·9	5·1	7·0
79·6	77·3	81·0	80·4	3·1	3·5	1·1	4·3	4·4
80·0	77·5	81·1	81·5	4·0	3·9	1·4	4·3	5·1
80·0	77·6	81·1	81·3	3·7	3·7	1·3	3·6	4·6
79·7	77·7	80·8	80·6	2·9	4·1	1·0	4·7	5·4
76·6	73·4	78·6	77·7	4·3	6·0	0·9	6·9	8·6
66·9	61·6	69·6	69·6	8·0	7·1	1·9	9·1	10·3
61·1	54·6	63·9‡	64·7	10·1	5·3	1·1	6·0	8·3
72·3	68·0	74·3	74·5	6·6	6·0	1·5	6·7	9·3

* Mean of 29 days. † Mean of 26 days. ‡ Mean of 30 days.

51. CHITTAGONG.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	59·4	52·3	62·5	63·3	11·0	6·4	1·6	5·3	10·1
February	60·0	53·5	62·2	64·3	10·8	9·0	2·3	9·0	13·1
March	70·5	66·3	72·2	72·9	6·6	8·6	1·2	6·1	8·5
April	74·5	70·7	76·0	76·9	6·2	8·9	1·7	6·8	7·6
May	77·0	73·4	78·1	79·5	6·1	6·6	1·8	5·7	5·3
June	76·2	72·4	78·0	78·3	5·9	6·9	3·5	3·7	3·6
July	77·5	75·2*	78·5	78·9	3·7	6·4	0·8	3·6	3·4
August	?	Not recorded.	78·2	78·8	?	?	?	3·3	3·4
September	?		78·7	78·8	?	?	?	3·8	4·1
October	?		77·8	78·2	?	?	?	3·9	6·1
November	?		71·9	72·3	?	?	?	4·6	6·8
December	?		65·2	65·9	?	?	?	2·9	5·8
Year	?		73·3	74·0	?	?	?	4·9	6·5

52. CALCUTTA (CHOWRINGHEE).

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
60·6	55·4	61·7	63·2	7·8	6·0	1·3	8·1	12·5
61·9	56·9	62·7	64·5	7·6	7·5	3·2	9·4	14·9
70·9	67·1	72·2	71·5	4·4	7·9	3·1	9·4	17·5
76·9	72·4	78·7	78·9	6·5	6·8	3·3	9·0	14·2
80·1	76·7	81·6	81·8	5·1	5·5	3·2	8·2	10·3
79·8	76·8	81·1	80·8	4·0	3·6	2·4	5·9	6·8
79·8	77·5	80·7	80·9	3·4	2·6	1·5	4·1	4·5
79·3	77·3	80·3	80·4	3·1	2·5	1·4	4·3	4·0
79·6	77·8	80·4	80·4	2·6	2·9	1·2	4·8	5·0
75·9	72·8	76·4	76·6	3·8	5·0	2·0	8·2	10·4
64·6	59·8	66·4	66·5	6·7	7·1	2·6	10·1	12·8
58·7	53·5	59·8	61·7	8·2	5·5	2·0	7·3	10·7
72·3	68·7	73·5	73·9	5·3	5·2	2·3	7·4	10·3

* Mean of 25 days.

53 CALCUTTA (ALIPORE).

MONTH.	Mean.	6 hours.	16 hours	16 hours.	22 hours.	Minimum.	DIFFERENCE, DRY AND WET BULB. Mean.	6 hours.	10 hours	16 hours.	22 hours	Minimum.
January . .	58·2	53·9	60·3	61·4	57·5	52·2	5·7	1·0	8·0	13·5	2·5	0·8
February .	60·6	57·2	61·1	62·4	60·2	55·4*	6·9	2·2	9·6	15·4	3·5	1·7
March . .	70·6	68·0	71·1	70·4	71·5	66·0	7·3	1·8	9·4	17·0	3·5	3·3
April . .	76·8	74·7	80·3	81·1	76·1	71·9	7·0	1·4	6·7	10·4	3·5	3·1
May . .	80·0	77·9	80·6	80·6	78·5	75·0	6·1	2·2	8·1	10·4	4·1	3·0
June . .	79·7	78·1	80·3	80·1	78·0	75·5	4·2	1·7	5·9	6·7	3·1	2·2
July . .	79·5	77·9	79·9	80·1	78·7	76·8	3·3	1·5	4·2	4·6	2·0	1·7
August . .	79·2	77·7	79·5	79·5	78·3	76·6	3·2	1·4	4·5	4·1	2·2	1·7
September .	79·5	77·9	79·5	79·6	78·6	77·1	3·2	1·2	4·7	5·0	1·9	1·3
October . .	75·3	72·7	75·6	75·5	74·4	72·2	4·8	1·6	7·8	10·4	2·8	1·7
November .	63·5	59·2	64·5	65·1	62·1	58·8	6·3	2·7	10·3	14·3	3·3	2·2
December .	57·1	52·9	58·2	60·3	56·2	52·1	5·3	2·0	7·5	11·6	2·1	1·8
Year . .	71·7	69·0	72·6	73·0	70·8	67·5	5·3	1·7	7·2	10·3	2·9	2·0

* Mean of 26 days.

54. SAUGOR ISLAND.

MONTH.	Mean.	4 hours.	10 hours	16 hours.	22 hours.	Minimum.	DIFFERENCE, DRY AND WET BULB. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.
January . .	61·3	57·7	63·6	64·3	59·7	55·7†	5·4	2·1	6·8	9·5	3·1	2·1
February .	64·2	61·4	65·0	67·0	63·3	57·7	5·4	2·1	7·2	9·1	3·1	3·0
March . .	74·0	71·9	75·0	76·0	73·2	70·2	5·1	3·3	6·4	7·4	3·3	3·6
April . .	78·6	76·9	80·1	80·4	76·8	75·6‡	5·1	3·2	6·6	6·9	3·9	2·9
May . .	80·8	79·4	82·1	82·3	79·4	78·9	5·0	3·4	6·2	6·6	3·6	2·7
June . .	80·3	79·1	81·2	81·5	79·2	76·7	4·4	3·2	5·7	5·6	3·4	4·7
July . .	79·7	78·2	80·3	80·8	79·5	77·6‡	3·2	2·3	4·0	4·2	2·4	1·9
August . .	79·4	78·3	79·9	80·8	78·6	77·7	3·1	2·3	3·2	4·0	2·7	1·8
September .	79·4	78·2	80·2	80·6	78·6	77·7	3·2	2·1	3·7	4·3	2·7	1·6
October . .	75·7	74·0	77·0	77·1	74·7	73·1	5·2	3·2	6·7	7·8	3·2	2·9
November .	65·5	63·4	67·3	67·3	64·1	61·0	7·0	4·2	7·9	11·7	4·2	4·3
December .	58·8	56·8	61·1	62·1	57·9	54·6	5·1	2·7	5·9	8·9	2·9	2·9
Year . .	73·2	71·3	74·4	75·0	72·1	69·7	4·8	2·8	5·9	7·2	3·2	2·9

† Mean of 30 days. ‡ Mean of 29 days.

55. CUTTACK.

MONTH.	Mean.	Minimum.	10 hours.	16 hours.	Range.	DIFFERENCE, DRY AND WET BULB. Mean.	Minimum.	10 hours.	16 hours.
January . .	63·7	58·8	65·5	66·9	8·1	8·4	1·5	8·9	15·2
February . .	66·6	62·2	67·8	69·7	7·5	9·2	2·2	9·8	17·1
March . . .	72·9	70·3	74·0	74·3	4·0	10·2	2·0	11·0	19·3
April . . .	77·3	75·6	77·8	78·5	2·9	10·9	2·6	13·1	18·5
May . . .	79·4	76·9	80·9	80·4	3·5	10·1	2·8	12·9	16·0
June . . .	78·3	76·3	79·2	79·5	3·2	5·8	2·1	7·2	8·8
July . . .	78·3	76·3	78·8	79·7	3·4	4·5	1·8	5·6	6·7
August . .	78·6	76·2	79·5	80·1	3·9	4·6	1·7	6·1	6·0
September .	78·7	76·5	79·7	80·0	3·5	4·6	1·6	5·7	6·4
October . .	75·8	72·8	77·3	77·3	4·5	6·5	1·6	8·4	10·2
November . .	66·3	61·0	67·8	70·2	9·2	7·6	1·4	9·8	12·2
December . .	59·1	53·1	60·9	63·2*	10·1	6·9	1·2	8·6	12·6
Year . . .	72·9	69·7	74·1	75·0	5·3	7·4	1·9	8·9	12·4

* Mean of 30 days.

56. FALSE POINT.

MONTH.	Mean.	Minimum.	10 hours.	16 hours.	Range.	DIFFERENCE, DRY AND WET BULB. Mean.	Mini. mum.	10 hours.	16 hours.
January . .	63·8	59·6	65·4	66·5*	6·9	3·1	0·4	5·0	7·3
February . .	66·9	63·3	68·6	68·9†	5·6	2·8	0·6	4·7	6·6
March . . .	75·0	71·8	76·1	77·1	5·3	2·9	1·5	4·5	5·3
April . . .	78·5	75·2	80·1	80·3	5·1	2·6	1·7	5·6	4·9
May . . .	80·1	76·5	81·8	82·1	5·6	2·7	1·7	5·2	5·2
June . . .	78·9	76·2	79·9	80·7	4·5	3·1	1·9	5·1	5·1
July . . .	78·4	76·5	79·2	79·6	3·1	2·3	1·2	4·5	4·1
August . .	78·2	75·7	79·2	79·7	4·0	2·5	1·4	5·1	4·5
September .	78·7	76·7	79·4	80·0	3·3	2·7	1·2	4·6	4·8
October . .	76·1	73·4	77·8	77·0	3·6	3·7	0·3	7·7	8·9
November . .	66·0	61·1	68·5	68·3	7·2	4·4	0·4	8·8	11·0
December . .	58·8	52·5	61·7	62·3	9·8	3·8	0·8	7·3	9·5
Year . . .	73·3	69·9	74·8	75·2	5·3	3·1	1·1	5·7	6·4

† Mean of 27 days.

TABLE X.—TEMPERATURE OF EVAPORATION IN 1883.

57. SAMBALPUR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	62·5	54·9	65·4	67·1	12·2	6·2	1·4	9·4	13·9
February	64·4	57·6	66·8	68·8	11·2	9·7	3·3	14·0	18·5
March	71·3	63·7	73·8	76·5	12·8	9·5	4·1	13·0	17·3
April	73·1	66·9	75·7	76·8	9·9	17·9	10·5	21·7	27·7
May	78·9	75·9	80·6	80·2	4·3	17·6	8·7	20·7	28·2
June	78·8	76·2	79·8	80·4	4·2	8·9	5·1	10·5	13·6
July	77·7	75·1	78·8	79·1	4·0	2·7	1·9	3·9	4·6
August	78·8	75·6	79·9	80·8	5·2	3·5	2·2	4·7	5·9
September	78·3	75·4	79·0	80·6	5·2	3·6	1·9	4·0	5·8
October	74·1	70·6	75·9	75·7	5·1	5·6	1·6	8·2	11·5
November	63·5	58·1	66·5	66·0	7·9	5·6	1·1	9·9	13·0
December	56·4	48·6	59·6	60·9	12·3	5·4	1·4	9·4	12·6
Year	71·5	66·6	73·5	74·4	7·9	8·0	3·6	10·8	14·4

58. SAMBALPUR (NEW OBSERVATORY).

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
Observatory opened on 16th October.								
Imperfect.								
63·2	57·4	66·5	65·8	8·4	6·1	1·4	10·9	13·9
56·0	47·8	59·9	60·3*	12·5	5·7	1·7	10·3	13·5
...	...	...	...	...	...	...	...	...

* Mean of 30 days.

59. RAIPUR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	58·7	53·3	60·7	62·0	8·7	9·0	3·1	12·1	16·9
February	59·7	54·2	60·9	64·1	9·9	13·0	5·7	17·0	21·3
March	65·4	61·4	66·8	67·9	6·5	15·2	7·3	18·8	24·5
April	?	63·4	Imperfect		?	?	14·8	?	?
May	71·0	67·9	72·0	73·2	5·3	25·6	17·0	28·7	35·1
June	75·3	72·4	76·5	76·9	4·5	7·8	3·6	10·4	13·2
July	75·2	72·4	76·2	76·9	4·5	3·9	1·8	5·6	7·0
August	76·1	73·5	75·6	77·7	4·2	5·7	1·9	7·6	10·5
September	74·9	72·0	76·0	76·8	4·8	3·7	1·0	5·6	7·4
October	70·5	67·3	72·0	72·2	4·9	6·3	1·4	10·0	12·6
November	61·6	55·3	62·8	66·8	11·5	6·6	1·7	11·0	12·6
December	51·3	44·4	53·8	55·7	11·3	9·2	2·5	12·4	18·3
Year	?	63·1	?	?	?	?	5·2	?	?

60. NAGPUR.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
59·1	53·3	61·0	62·9	9·6	9·6	3·1	21·4	18·1
58·6	52·4	59·4	63·9	11·5	15·3	6·8	18·3	24·6
62·2	56·4	64·1	66·0	9·6	19·6	10·9	23·4	30·3
66·6	62·0	68·3	69·6	7·6	23·9	14·5	30·6	34·8
70·3	66·3	71·8	72·7	6·4	25·3	16·8	30·2	35·4
75·1	73·6	76·2	75·6	2·0	8·0	3·4	11·5	13·6
75·2	73·7	75·6	76·2	2·5	4·5	1·2	6·5	8·3
74·8	73·0	75·4	75·9	2·9	7·3	2·9	9·5	12·3
74·6	72·7	75·4	75·8	3·1	3·6	0·9	6·4	6·9
69·3	66·4	71·2	70·2	3·8	7·4	2·1	10·8	14·6
59·8	54·5	62·3	62·6	8·1	9·4	2·9	13·5	18·3
51·7	44·6	53·9	56·5	11·9	10·7	4·3	14·6	19·4
66·4	62·4	67·9	69·0	6·6	12·1	5·8	15·6	19·7

61. SEONI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	56·6	50·2	59·1	60·5	10·3	7·8	2·5	11·3	15·6
February	58·3	48·7	58·0	68·3	19·6	10·6	6·4	16·5	14·3
March	60·3	53·2	63·1	64·5	11·3	17·0	10·0	20·8	26·8
April	65·6	58·7	68·5	69·6	10·9	20·7	14·4	27·1	29·9
May	67·8	62·9	70·0	70·6	7·7	22·5	14·9	27·9	32·1
June	72·8	70·2	74·7	73·6	3·4	7·2	4·4	11·3	11·7
July	72·6	70·1	73·5	74·2	4·1	3·9	1·9	5·4	6·7
August	73·0	69·8	74·3	74·8	5·0	5·1	2·4	8·3	9·1
September	71·7	69·5	73·1	72·6	3·1	3·9	1·7	6·5	7·4
October	65·4	61·6	67·4	67·2	5·6	7·5	3·1	13·0	13·9
November	55·7	49·2	58·6	59·3	10·1	9·5	3·6	15·5	18·3
December	48·5	40·9	51·0	53·6	12·7	10·2	4·1	15·5	18·7
Year	64·0	58·8	65·9	67·4	8·7	10·5	5·8	14·9	17·0

62. JUBBULPORE.

Month.	Mean.	Minimum	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	56·3	49·0	57·6	62·2	13·2	7·7	3·3	9·5	13·5
February	54·4	47·5	55·6	60·0	12·5	12·4	5·4	14·2	20·7
March	59·4	53·1	61·6	63·6	10·5	17·6	10·3	19·8	27·0
April	63·4	57·5	65·4	67·2	9·7	24·1	16·4	29·7	33·9
May	68·8	65·3	69·9	71·1	5·8	25·7	19·5	26·8	33·1
June	74·5	72·1	75·8	75·5	3·4	11·2	6·8	12·4	16·9
July	74·8	72·6	75·3	76·4	3·8	3·9	1·6	4·4	6·8
August	74·7	72·2	75·6	76·3	4·1	5·9	2·7	7·2	9·9
September	74·6	72·2	75·3	75·8	3·6	3·6	1·0	4·4	7·3
October	66·9	62·5	69·5	68·6	6·1	6·9	2·0	9·8	14·4
November	55·9	47·8	58·9	61·1	13·3	8·7	2·3	11·1	18·0
December	47·4	37·6	50·4	54·3	16·7	8·4	1·8	10·9	17·9
Year	64·3	59·1	66·0	67·7	8·6	11·3	6·1	13·4	18·3

63. SAUGOR.

Month.	Mean.	Minimum	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	55·5	49·3	57·9	59·4	10·1	8·8	4·3	11·0	15·5
February	53·0	46·2	54·7	58·2	12·0	13·1	6·9	16·4	20·9
March	59·8	53·6	61·9	63·9	10·3	16·3	9·4	20·7	25·2
April	64·6	59·7	66·5	67·6	7·9	23·2	15·1	29·8	33·1
May	75·2	68·0	77·5	80·2	12·2	15·3	10·6	18·9	22·2
June	74·3	71·6	75·3	75·9	4·3	10·1	4·9	13·4	16·3
July	74·2	71·9	75·0	75·7	3·8	4·1	1·6	4·4	7·3
August	73·8	70·7	75·1	75·6	4·9	5·3	2·4	7·3	9·5
September	74·3	70·7	75·5	76·6	5·9	3·2	1·2	5·6	6·5
October	67·0	61·5	68·8	70·7	9·2	7·4	4·1	12·2	12·5
November	59·4	50·0	62·2	66·0	16·0	8·0	6·2	13·6	12·6
December	52·8	42·4	54·0	61·9	19·5	7·3	5·7	13·6	10·1
Year	65·3	59·6	67·0	69·3	9·7	10·2	6·0	13·9	16·0

64. PACHMARHI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	51·2	45·1	53·6	54·9	9·8	7·2	3·3	12·5	13·4
February	51·0	44·5	53·3	55·2	10·7	11·3	5·9	16·8	18·9
March	54·8	49·9	56·4	58·2	8·3	16·2	10·1	20·3	23·8
April	58·8	55·2	59·8	61·4	6·2	22·4	15·2	27·5	30·5
May	64·1	61·0	65·1	66·2	5·2	20·7	14·5	22·4	27·9
June	69·8	67·3	71·0	71·2	3·9	7·3	3·8	8·7	11·8
July	68·6	66·4	69·1	70·2	3·8	1·7	0·8	1·7	3·2
August	68·9	65·9	69·7	71·0	5·1	2·7	1·3	3·5	4·9
September	68·5	65·5	69·7	70·2	4·7	1·3	0·8	2·5	3·1
October	61·1	56·4	63·3	63·5	7·1	5·1	3·0	10·1	9·4
November	51·4	43·6	54·8	55·7	12·1	6·3	3·1	13·2	12·9
December	44·0	35·1	47·7	49·1	14·0	7·2	3·9	14·3	14·3
Year	59·4	54·7	61·1	62·2	7·6	9·1	5·5	12·8	14·5

* Mean of 28 days.

65. HOSHANGABAD.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	57·0	50·4	58·3	62·2	11·8	10·0	4·2	9·8	17·1
February	55·2	47·4	56·3	61·8	14·4	14·3	7·6	15·9	22·2
March	60·1	53·0	61·9	65·5	12·5	18·8	11·5	21·9	27·8
April	64·3	57·5	66·5	69·0	11·5	25·1	17·0	30·1	35·2
May	70·1	65·0	71·9	73·3	8·3	23·0	15·3	24·4	32·5
June	75·8	72·7	77·2	77·5	4·8	10·5	5·1	10·8	17·2
July	75·3	72·9	76·1	76·8	3·9	3·7	2·1	4·4	6·2
August	74·8	71·6	75·9	76·8	5·2	5·0	2·7	6·1	8·5
September	74·7	71·8	75·5	76·9	5·1	3·6	1·7	3·4	6·1
October	68·6	64·7	70·6	70·5	5·8	6·8	2·6	8·5	12·9
November	58·3	50·5	60·6	63·7	13·2	9·0	3·9	11·4	16·4
December	49·9	40·7	51·9	57·0	16·3	9·3	4·3	10·9	16·4
Year	65·3	59·9	66·9	69·3	9·4	11·6	6·5	13·1	18·2

66. KHANDWA.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean	Minimum.	10 hours.	16 hours.
56·9	49·9	59·3	61·5	11·6	11·0	3·8	15 8	20·6
55·6	47·9	57·6	61·3	13·4	15·2	6·7	19·3	25·7
60·3	54·6	61·8	64·4	9·8	19·0	10·1	23·6	29·5
65·7	61·8	67·1	68·3	6·5	23·8	13·7	30·3	35·1
71·8	69·3	72·8	72·4	3·1	20·8	11·6	22·8	31·8
75·0	72·8	76·2	75·9	3·1	9·4	4·2	11·2	15·9
74·3	72·3	75·0	75·7	3·4	4·8	2·3	5·4	7·9
73·5	71·3	73·8	75·3	4·0	6·3	2·4	6·6	10·5
73·1	70·6	73·7	75·1	4·5	4·7	2·0	4·6	7·8
68·2	64·3	70·3	70·0	5·7	6·9	1·9	9·7	13·9
57·0	49·3	60·3	61·4	12·1	10·4	3·3	16·1	20·8
49·0	39·1	52·6	55·4	16·3	10·3	3·2	14·9	20·9
65·0	60·3	66·7	68·1	7·8	11·9	5·4	15·0	20·0

67. CHANDA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	60·5	53·7	63·4	64·5	10·8	8·5	1·6	11·3	18·1
February	62·2	55·8	64·3	66·6	10·8	13·8	4·5	15·8	25·0
March	66·3	61·8	68·4	68·8	7·0	16·3	6·5	20·9	28·1
April	68·0	62·7	70·4	71·0	8·3	23·8	14·7	27 8	35·1
May	70·6	65·8	71·9	74·2	8·4	26·4	18·4	29·9	35·5
June	76·3	74·3	76·9	77·6	3·3	8·7	4·2	10·1	13·9
July	75·1	73·6	75·4	76·2	2·6	5·7	2·5	7·5	9·2
August	75·6	73·6	75·9	77·2	3·6	6·0	2·3	8·8	10·0
September	74·8	72·7	75·3	76·3	3·6	3·8	1·3	5·9	6·8
October	72·5	68·1	74·2	75·2	7·1	4·9	1·1	7·9	10·4
November	62·7	55·1	65·4	67·7	12·6	4·9	0·7	8·2	11·7
December	53·8	44·5	56·7	60·2	15·7	6·7	0·4	9·2	15·9
Year	68·2	63·5	69·9	71·3	7·8	10·8	4·9	13·6	18·3

68. SIRONCHA.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
63·4	57·8	65·8	66·7	8·9	8·4	2·5	8·4	16·5
65·6	61·3	66·8	68·6	7·3	13·1	4·4	13·1	23·1
70·6	67·8	72·0	72·1	4·3	14·2	6·8	12·9	22·9
72·0	69·3	73·4	73·2	3·9	20·4	11·2	17·4	31·0
75 1	73·0	76·4	75·8	2·8	22·3	13·7	21·0	32·3
76·4	74·5	76·9	77·8	3·3	7·7	4·4	7·4	11·4
76·0	74·2	76·5	77·4	3·2	4·2	2·3	4·9	6·4
76·4	74·4	76·9	77·8	3·4	4·6	2·5	5·3	7·2
75·7	73·9	76·2	77·0	3·1	3·3	1·8	4·0	5·3
74·0	71·2	75·2	75·5	4·3	5·6	2·1	6·9	10·4
64·4	59·4	66·4	67·4	8·0	7·0	2·0	6·4	14·0
57·2	50·9	58·2	62·6	11·7	8·1	2·1	7·2	15·0
70·6	67·3	71·7	72·7	5·4	9·9	4·7	9·6	16·3

69. CHIKALDA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	53·8	50·3	55·0	56·2	5·9	9·6	6·3	11·2	14·0
February	55·3	50·0	57·0	58·9	8·9	13·5	10·4	15·2	18·2
March	56·8	52·2	58·0	60·1	7·9	17·4	13·1	19·1	22·9
April	59·8	56·6	60·8	62·1	5·5	23·2	18·0	25·7	29·2
May	64·2	60·5	65·9	66·3	5·8	18·5	12·3	19·0	26·2
June	68·7	65·6	69·8	70·7	5·1	4·8	2·2	5·3	8·4
July	67·4	65·1	67·7	69·4	4·3	1·3	0·2	1·2	2·7
August	67·2	64·4	67·9	69·3	4·9	2·1	0·6	2·4	4·3
September	66·6	64·2	68·0	67·5	3·3	0·2	0·5	1·3	1·3
October	62·6	58·8	64·4	64·5	5·7	4·7	4·2	8·0	7·1
November	55·7	51·0	57·6	58·4	7·4	7·8	6·1	11·2	11·4
December	48·7	44·2	50·2	51·7	7·5	10·1	7·6	13·9	14·0
Year	60·6	56·9	61·9	62·9	6·0	9·4	6·8	11·1	13·3

70. BULDANA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	61·0	51·4	64·0	67·6	16·2	7·4	7·0	9·5	10·8
February	61·3	51·5	63·7	68·6	17·1	12·7	10·9	14·2	16·9
March	64·5	55·7	66·3	71·5	15·8	14·9	13·2	15·4	18·4
April	70·4	60·7	73·1	77·5	16·8	17·6	16·6	19·2	21·1
May	72·6	64·6	74·8	78·3	13·7	15·7	12·4	15·8	21·3
June	73·4	68·7	74·6	77·0	8·3	5·4	2·7	6·1	9·1
July	71·5	68·1	72·3	74·1	6·0	3·1	1·5	4·0	5·4
August	70·3	67·0	71·0	72·9	5·9	4·2	1·8	4·5	7·3
September	70·2	66·8	70·8	72·9	6·1	2·1	1·2	2·9	3·6
October	68·8	63·9	70·7	71·9	8·0	3·9	3·3	7·1	6·3
November	61·5	54·3	64·0	66·3	12·0	6·9	5·3	11·4	10·8
December	54·9	46·6	57·7	60·3	13·7	8·3	6·9	11·9	12·5
Year	66·7	59·9	68·6	71·6	11·6	8·5	6·9	10·2	12·0

71. AKOLA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	57·7	49·7	60·8	62·7	13·0	11·7	5·6	14·2	20·8
February	57·6	48·4	59·9	64·5	16·1	15·6	8·9	20·3	26·6
March	61·2	54·2	63·1	66·2	12·0	20·4	12·0	25·0	30·8
April	64·5	58·2	67·0	68·2	10·0	25·9	17·1	31·6	37·3
May	69·7	65·8	71·8	71·4	5·6	24·4	15·6	25·7	35·3
June	75·0	71·9	76·2	76·8	4·9	·4	3·0	9·2	15·0
July	74·1	71·3	74·8	76·2	4·9	5·0	1·9	6·0	8·8
August	73·2	70·3	74·3	74·9	4·6	7·0	3·1	8·0	12·0
September	73·2	70·3	74·2	75·2	4·9	4·0	1·6	5·1	7·2
October	70·0	65·9	72·3	71·8	5·9	5·6	1·7	8·5	11·8
November	60·1	52·6	63·2	64·5	11·9	8·6	2·5	13·2	17·8
December	51·1	41·1	54·4	57·7	16·6	9·8	3·0	13·6	19·9
Year	65·6	60·0	67·7	69·2	9·2	12·3	6·3	15·0	20·3

72. AMRAOTI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	58·3	51·0	61·2	62·6	11·6	11·7	6·7	13·9	19·7
February	60·9	51·9	63·4	67·3	15·4	14·6	9·5	17·2	22·2
March	63·8	54·6	67·3	69·6	15·0	18·0	12·9	21·0	26·4
April	67·3	60·6	70·5	70·8	10·2	22·9	15·8	28·5	33·1
May	69·1	64·1	71·7	71·6	7·5	23·5	14·9	26·8	34·6
June	74·5	71·7	76·2	75·5	3·8	7·2	2·7	9·2	13·5
July	73·7	70·9	74·9	75·3	4·4	3·9	1·7	5·3	7·3
August	73·2	70·0	74·7	75·0	5·0	6·7	2·6	7·6	12·1
September	73·1	70·1	74·6	74·5	4·4	2·6	1·0	5·0	5·8
October	68·8	64·9	71·2	70·3	5·4	6·1	2·5	9·9	12·1
November	59·6	53·5	62·3	63·0	9·5	9·7	4·2	13·9	17·8
December	52·1	44·6	54·4	57·4	12·8	11·8	6·3	15·8	19·5
Year	66·2	60·7	68·5	69·4	8·8	11·6	6·7	14·5	18·7

73. MAKHLA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	55·9	51·2	56·6	59·9	8·7	8·6	6·1	9·8	11·8
February	56·6	51·1	57·6	61·0	9·9	12·2	8·8	14·4	16·7
March	59·5	54·6	59·9	64·0	9·4	16·0	11·1	17·5	21·3
April	64·0	59·7	65·1	67·2	7·5	20·9	15·5	23·6	27·4
May	67·8	63·4	69·5	70·6	7·2	17·4	10·9	18·9	25·4
June	70·7	67·3	72·1	72·6	5·3	4·6	2·8	5·9	7·8
July	69·4	66·8	70·0	71·5	4·7	1·4	0·9	1·6	2·3
August	69·1	65·7	69·8	71·7	6·0	1·9	1·0	2·2	3·6
September	67·8	65·5*	68·8*	69·1*	3·6	0·9	1·3	1·3	1·4
October	64·5	60·0	66·1	67·4	7·4	3·9	3·5	6·7	5·9
November	56·5	51·6	57·4	60·6	9·0	7·0	5·3	9·2	9·5
December	50·3	44·8	51·0	55·2	10·4	12·8	14·2	10·6	12·0
Year	62·7	58·5	63·7	65·9	7·4	9·0	6·8	10·1	12·1

* Mean of 25 days.

74. NEEMUCH.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	51·9	45·7	53·0	57·1	11·4	10·7	4·0	11·7	18·4
February	50·5	42·6	52·3	56·6	14·0	12·6	6·5	16·1	20·5
March	57·3	52·4	58·4	61·0	8·6	16·4	8·1	23·0	25·8
April	62·7	57·9	63·1	67·2	9·3	23·5	14·2	32·1	33·1
May	65·5	63·1	65·0	68·5	5·4	22·0	11·8	28·2	31·5
June	72·1	70·6	72·0	73·6	3·0	13·5	6·1	16·4	20·9
July	73·8	71·8	74·1	75·5	3·7	4·3	1·3	6·6	7·6
August	72·8	70·5	73·3	74·5	4·0	6·7	1·8	9·9	12·1
September	73·0	70·5	73·8	74·8	4·3	3·6	0·8	6·5	7·0
October	65·1	60·4	66·4	68·6	8·2	9·1	3·2	15·6	16·1
November	52·5	46·5	54·1	57·0	10·5	13·5	5·3	21·2	23·2
December	48·0	40·0	50·5	53·4	13·4	11·0	5·4	16·0	19·2
Year	62·1	57·7	63·0	65·7	8·0	12·2	5·7	16·9	19·6

75. NOWGONG.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	54·6	47·9	56·7	59·2	11·3	6·2	1·3	8·8	13·2
February	53·4	44·8	56·2	59·1	14·3	8·8	3·2	12·1	17·2
March	Imperfect.								
April	...	63·6	Untrustworthy.				7·5	?	?
May	...	69·1*	Ditto.				10·5	?	?
June	78·2	74·2	79·9	80·4	6·2	13·0	8·4	15·2	19·4
July	77·3	75·1†	78·2	78·5	3·4	4·9	2·7	6·1	8·1
August	76·7	74·1	78·1	77·9	3·8	7·1	4·2	9·2	11·4
September	76·4	74·0	77·6	77·5‡	3·5	5·7	2·1	8·0	10·6
October	66·6	61·9	69·3	68·6	6·7	9·6	3·9	13·3	17·9
November	55·4	47·7	57·6§	60·8§	13·1	9·9	3·2	13·9	18·9
December	48·5	39·0	51·0	55·6	16·6	8·3	2·6	10·7	16·4
Year	?	?	?	?	?	?	?	?	?

76. SUTNA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean	Minimum.	10 hours.	16 hours.
January	53·4	46·4	55·9	57·9	11·5	6·8	2·2	9·4	13·9
February	49·7	44·0	52·7	52·3	8·3	12·5	4·3	14·7	23·7
March	58·0	52·4	60·0	61·5	9·1	16·1	7·4	21·1	26·8
April	62·8	57·3	65·1	66·1	8·8	23·6	13·8	30·8	35·5
May	67·6	63·1	69·7	70·1	7·0	23·7	14·8	30·1	34·5
June	74·4	71·5	76·2	75·6	4·1	14·6	9·5	17·7	21·3
July	75·8	73·6	76·5	77·2	3·6	5·3	2·6	6·5	8·7
August	75·4	72·9	76·4	77·0	4·1	7·1	3·9	8·8	11·1
September	75·5	72·8	76·9	76·9	4·1	4·8	2·0	6·8	8·9
October	65·4	61·4	67·9	67·0	5·6	9·6	3·6	14·2	17·9
November	54·2	46·4*	57·5	58·7	12·3	10·4	4·0	16·4	20·0
December	47·2	38·1	50·6	53·0	14·9	9·7	3·8	13·6	18·8
Year	63·3	58·3	65·5	66·1	7·8	12·0	6·0	15·8	20·1

* Mean of 25 days. † Mean of 30 days. ‡ " " 29 " § " " 28 " • Mean of 29 days.

77. INDORE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	54·6	47·5	57·1	59·3	11·8	9·6	3·9	15·1	17·6
February	52·3	43·1	55·5	58·3	15·2	13·1	7·0	18·5	22·4
March	57·6	50·7	60·2	61·8	11·1	16·2	8·9	21·8	56·2
April	61·9	55·4	64·3	65·9	10·5	22·8	15·1	30·6	32·9
May	67·8	63·5	69·8	70·2	6·7	19·6	11·5	23·4	29·6
June	73·4	69·5	75·4	75·4	5·9	8·3	4·6	10·1	13·9
July	72·7	70·1	73·6	74·4	4·3	3·6	1·5	4·1	6·6
August	72·0	68·6	73·4	74·1	5·5	4·6	1·6	6·4	8·9
September	71·9	68·5	73·0	74·1	5·6	2·8	1·3	4·4	5·4
October	65·3	61·0	67·9	67·1	6·1	6·2	2·1	11·8	13·0
November	55·4	47·3	59·2	59·8	12·5	8·9	3·3	16·9	18·2
December	49·2	39·8	53·1	54·6	14·8	8·2	3·0	16·3	17·4
Year	62·8	57·1	65·2	66·3	9·2	10·3	5·3	15·0	17·7

78. BICKANEER.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
47·9	43·8	46·8	53·0	9·2	12·1	7·0	14·5	16·1
49·3	44·5	48·2	55·1	10·6	13·6	7·9	18·5	18·3
59·1	53·9	58·9	64·4	10·5	15·1	9·7	18·4	20·3
69·5	64·6	69·7	74·3	9·7	20·0	15·2	23·4	26·8
73·1	68·0	73·7	77·7	9·7	19·7	14·4	21·0	25·4
78·8	75·8	78·8	81·7	5·9	18·2	11·9	18·8	24·5
77·9	75·7	78·0	80·0	4·3	11·3	6·5	12·0	16·1
76·8	74·5	76·6	79·4	4·9	14·8	8·1	14·7	21·2
75·7	73·3	75·8	77·9	4·6	11·3	6·9	12·8	15·9
66·3	62·7	66·2	69·9	7·2	16·7	10·2	20·2	23·2
55·3	51·1	54·9	59·9	8·8	14·0	8·1	15·5	19·5
47·6	43·1	46·2	53·5	10·4	13·5	7·1	15·2	18·5
64·8	60·9	64·5	68·9	8·0	15·0	9·3	17·1	20·5

79. JEYPORE.

Month.	Mean.	4 hours.	10 hours	16 hours.	22 hours	Minimum.	Difference, Dry and Wet Bulb. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.
January	53·3	48·4	55·8	58·8	50·3	43·6	7·5	4·3	9·0	12·0	4·6	6·4
February	50·7	45·1	52·8	56·4	48·4	39·9	11·3	7·0	13·4	17·2	7·7	9·5
March	58·9	53·7	61·8	63·4	56·8	48·0	14·7	9·0	16·9	21·7	10·9	12·2
April	64·1	59·3	67·3	67·9	62·0	53·3	23·6	16·0	27·1	32·6	18·7	18·8
May	70·1	65·5	73·0	73·6	68·2	57·8	19·1	11·9	21·3	27·3	16·1	17·0
June	75·9	73·0	77·6	77·8	75·3	65·6	13·0	7·2	15·9	19·4	9·4	12·9
July	75·6	73·8	76·2	77·2	75·0	66·5	6·9	3·3	8·0	11·1	5·2	9·0
August	73·9	71·6	75·1	75·6	73·1	63·6	11·9	6·0	13·8	18·1	9·9	12·4
September	73·5	71·0	75·5	75·0	72·5	70·1	9·1	5·2	10·4	14·8	5·8	4·3
October	62·6	57·9	65·9	66·0	60·4	56·9	15·7	8·5	19·1	23·9	11·3	6·5
November	53·4	46·8	57·5	59·2	50·1	44·3	13·3	6·9	17·0	20·3	9·1	6·3
December	48·9	41·8	52·9	55·8	44·9	39·4	10·5	5·7	13·5	16·6	6·5	5·0
Year	63·4	59·0	66·0	67·2	61·4	54·1	13·1	7·6	15·5	19·6	9·6	10·0

80. SAMBHAR.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
50·8	41·9	53·6	56·9	15·0	7·0	4·3	7·9	13·7
51·3	39·8	54·4	59·8	20·0	8·9	6·2	9·7	13·9
57·6	49·8	60·4	62·6	12·8	14·6	7·5	17·1	22·7
64·3	58·4*	66·9†	67·6†	9·2	23·2	12·7	26·5	32·2
?	66·1	Not recorded.			?	13·3	?	?
?	72·5	Imperfect.			?	9·7	?	?
75·8	73·3‡	76·6	77·4	4·1	7·2	4·3	7·9	11·4
73·9	71·5	75·0	75·2	3·7	12·0	6·7	12·6	19·4
73·5	70·8	75·1	74·5	3·7	8·7	5·0	10·0	15·2
?	56·2	Imperfect.			?	8·0	?	?
?	42·3	Ditto.			?	8·0	?	?
47·6	35·7	51·0	56·1	20·4	8·5	6·4	11·6	15·9
?	56·5	?	?	?	?	7·7	?	?

* Mean of 26 days. † Mean of 20 days. ‡ Mean of 30 days.

81. AJMERE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb.			
						Mean.	Minimum.	10 hours.	16 hours.
January	51·0	42·3	53·3	57·3	15·0	7·4	4·2	9·3	13·6
February	47·7	36·1	51·2	55·7	19·6	12·5	9·5	14·0	17·8
March	57·6	49·8	59·8	63·1	13·3	13·9	7·7	16·8	20·6
April	64·8	58·5	66·9	69·0	10·5	21·3	13·0	23·7	28·9
May	71·3	69·1	71·4	73·3	4·2	17·5	9·8	18·6	26·2
June	74·8	71·7	75·5	77·1	5·4	13·0	9·2	13·5	19·2
July	75·2	73·3	75·3	77·0	3·7	5·6	2·6	6·8	9·1
August	73·9	70·8	74·1	76·8	6·0	9·8	6·6	9·9	15·4
September	73·6	70·1	74·9	75·8	5·7	6·6	4·8	7·3	11·0
October	63·6	54·8	67·3	68·7	13·9	11·7	8·1	15·8	19·2
November	54·2	41·6	58·9	62·0	20·4	9·2	6·3	15·1	16·2
December	48·8	35·4	53·6	57·3	21·9	7·3	4·9	11·2	15·1
Year	63·0	56·1	65·2	67·8	11·6	11·3	7·2	13·5	17·7

82. MOUNT ABU.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb.			
						Mean.	Minimum.	10 hours.	16 hours.
January	47·3	44·7	47·7	49·5	4·8	10·1	6·6	13·2	13·9
February	46·2	42·8	46·7	49·0	6·2	12·8	9·5	15·8	16·7
March	52·5	49·4	53·1	55·0	5·6	13·7	9·7	16·3	18·2
April	59·9	56·6	60·5	62·5	5·9	18·3	14·1	21·2*	23·2
May	60·6	57·3	60·2	64·4	7·1	17·0	12·0	20·5	21·4
June	66·9	65·2	66·3	69·2	4·0	8·5	3·7	9·7	12·7
July	65·8	64·9	65·4	67·2	2·3	3·3	1·9	4·3	4·2
August	64·2	62·1	64·2	66·2	4·1	5·3	2·2	6·3	8·5
September	64·8	63·4	64·8	66·3	2·9	3·1	1·9	5·8	4·1
October	59·3	57·4	60·0	60·5	3·1	9·1	5·9	14·5	12·9
November	50·0	47·8	51·0	51·2	3·4	10·4	6·8	16·1	15·0
December	46·3	43·3	47·5	48·1	4·8	9·7	6·4	14·9	14·1
Year	57·0	54·6	57·3	59·1	4·5	10·1	6·7	13·2	13·7

83. PACHBUDRA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb.			
						Mean.	Minimum.	10 hours.	16 hours.
January	49·1	38·2	51·9	57·1	18·9	10·3	3·2	14·2	20·2
February	47·6	39·9	48·5	54·3	14·4	15·2	5·8	18·1	25·6
March	60·5	49·9	62·9	68·8	18·9	13·4	8·0	19·6	21·0
April	67·1	58·8	68·8	73·8	15·0	20·8	12·9	27·5	30·3
May	73·3	67·9	74·3	77·8	9·9	17·3	7·9	18·0	27·5
June	77·7	74·5	78·3	80·2	5·7	15·3	7·3	15·9	23·9
July	76·5	74·5	77·0	77·9	3·4	9·5	4·2	11·3	15·3
August	74·0	72·2	74·4	75·4	3·2	13·5	4·8	13·1	22·6
September	74·4	72·0	75·6	75·6	3·6	8·9	3·3	10·4	15·7
October	65·1	59·8	67·9	67·5	7·7	14·9	5·6	20·3	27·1
November	52·6	42·9*	56·2*	58·8	15·9	13·7	5·9	18·2	25·0
December	46·8	36·7	49·0	54·6	17·9	12·2	4·5	15·2	22·1
Year	63·7	57·3	65·4	68·5	11·2	13·8	6·1	16·8	23·0

* Mean of 29 days.

84. JACOBABAD.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb.			
						Mean.	Minimum.	10 hours.	16 hours.
January	48·4	38·7	50·5	56·0	17·3	9·3	4·9	11·1	15·8
February	47·1	37·9	49·2	54·3	16·4	13·0	7·3	15·5	20·6
March	57·0	49·0	58·8	63·1	14·1	15·7	9·1	17·8	24·1
April	67·2	59·6	69·8	72·3	12·7	20·4	12·5	24·0	30·8
May	70·7	63·9	73·1	75·2	11·3	22·9	13·9	28·1	34·1
June	77·6	72·3	80·2	80·4	8·1	20·4	11·6	21·6	31·7
July	80·0	75·4	82·1	82·4	7·0	11·3	6·2	11·9*	18·5
August	77·1	71·5	78·6	81·3	9·8	13·8	7·3	12·9	21·7
September	75·3	69·9*	77·6*	78·3*	8·4	13·3	6·9	14·6	22·0
October	62·5	52·5	65·7	69·3	16·8	13·9	8·3	19·4	22·7
November	52·7	41·4	56·2	60·6	19·2	10·6	6·0	15·8	18·6
December	48·8	37·9	51·4	57·3	19·4	8·3	4·0	10·2	15·0
Year	63·7	55·8	66·1	69·2	13·4	14·4	8·2	16·9	23·0

* Mean of 28 days.

85. HYDERABAD.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	52·6	45·5	54·7	57·6	12·1	9·8	5·2	12·5	16·4
February	51·5	45·3	53·1*	56·2*	10·9	13·6	7·7	16·0	20·9
March	60·4	56·1	61·5	63·5	7·4	15·5	7·2	18·0	25·0
April	71·8	66·7	73·2	75·6	8·9	15·7	6·5	19·8	26·2
May	74·	72·1	74·7	77·2	5·1	16·8	6·0	20·9	27·7
June	?	Imperfect.	75·8	77·7	?	?	?	19·6	22·9
July	77·5	76·1†	77·4	79·1	3·0	8·8	3·4	11·9	14·0
August	74·6	72·1	75·4	76·4	4·3	10·6	5·0	12·9	16·8
September	75·3	72·4	76·1	77·3	4·9	9·1	3·3	11·7	15·8
October	70·4	63·5	72·8	75·0	11·5	12·3	6·1	14·9	20·7
November	60·3	50·5	63·2	67·1	16·6	8·9	5·4	11·6	15·4
December	52·4	44·5	53·7	59·0	14·5	10·0	4·4	13·2	16·8
Year	?	?	67·6	70·1	?	?	?	15·3	19·9

* Mean of 27 days. † Mean of 29 days.

86. KURRACHEE.

Mean.	Minimum	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
57·0	48·8	58·2	61·7	12·9	8·8	6·4	11·5	13·5
59·8	50·7	60·3	64·2	13·5	8·0	6·1	10·6	11·7
68·1	60·9	67·9	70·4	9·5	6·5	3·9	9·7	10·0
76·2	70·8	76·8	78·3	7·5	4·8	2·5	8·3	7·5
80·1	75·9	80·1	81·5	5·6	5·1	2·4	8·9	7·6
82·0	79·3	82·3	83·3	4·0	5·6	3·0	8·6	7·8
78·5	76·5	79·2	79·6	3·1	4·9	3·2	6·1	6·3
75·8	73·8	76·4	77·3	3·5	5·1	3·4	6·6	6·4
75·9	73·8	76·5	77·1	3·3	5·4	3·1	7·4	6·8
70·2	64·8	71·7	75·7	10·9	10·0	5·3	15·2	11·8
58·9	50·5	61·6	66·0	15·5	11·4	8·2	15·5	15·0
55·2	46·1	55·6	61·0	14·9	10·7	6·9	14·2	15·5
69·8	64·3	70·6	73·0	8·7	7·2	4·5	10·2	10·0

87. BHUJ.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	55·2	49·4	57·0	59·1	9·7	11·9	6·6	15·0	19·0
February	54·3	49·3	55·7	58·0	8·7	14·1	6·9	17·7	22·6
March	63·8	60·7	65·0	65·8	5·1	12·5	4·7	16·0	21·3
April	69·2	65·8	70·5	71·2	5·4	16·6	7·2	22·6	27·4
May	73·8	69·7	75·8	76·0	6·3	12·0	6·3	17·9	19·5
June	76·8	75·2	77·6	77·7	2·5	11·1	5·9	15·0	16·9
July	76·1	74·1	77·1	77·1	3·0	?	?	7·0	8·1
August	74·3	72·1	75·3	75·4	3·3	7·6	4·5	10·7	11·7
September	73·9	71·5	75·2	75·1	3·6	5·8	2·8	9·2	9·9
October	68·8	65·5	70·6	70·4	4·9	13·8	6·6	18·4	22·7
November	57·1	49·9	60·8	60·7	10·8	14·3	9·3	19·2	22·9
December	52·8	44·9	56·2	57·4	12·5	12·4	7·6	16·6	20·4
Year	66·3	62·3	68·1	68·7	6·3	?	?	15·4	18·5

88. RAJKOT.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
53·3	44·5	55·6	59·7	15·2	14·3	7·8	15·7	23·1
52·9	42·5	56·1	60·0	17·5	15·4	8·9	16·1	25·1
61·0	54·7	63·9	64·4	9·7	15·3	6·3	17·8	27·2
66·5	62·1	68·8	68·6	6·5	19·3	7·6	23·8	33·2
71·9	69·2	73·9	72·5	3·3	16·1	5·4	19·5	28·9
76·0	73·6	77·2	77·1	3·5	11·0	4·7	13·4	18·5
75·1	72·6	76·5	76·2	3·6	5·8	2·8	6·9	10·1
73·2	70·6	74·1	74·8	4·2	9·1	3·5	11·2	15·7
73·5	70·5	74·8	75·3	4·8	4·8	1·7	7·3	9·1
68·4	63·8	71·4	70·0	6·2	10·5	4·2	14·9	19·7
56·3	47·5	59·8	61·5	14·0	14·0	7·2	20·9	24·4
50·7	40·7	54·3	57·0	16·3	13·5	7·0	18·2	23·7
64·9	59·4	67·2	68·1	8·7	12·4	5·6	15·5	21·6

89. DEESA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range	Difference, Dry and Wet Bulb.			
						Mean.	Minimum.	10 hours.	16 hours.
January	55·3	46·8	56·3	59·3	12·5	12·7	6·2	17·0	21·2
February	53·3	44·8	55·2	58·8	14·0	16·9	8·8	19·6	24·3
March	62·2	55·6	63·4	64·2	8·6	16·8	7·9	19·5	26·0
April	67·7	61·8	68·6	69·8	8·0	23·4	11·3	26·0	33·8
May	73·4	68·6	74·1	73·8	5·2	17·6	6·8	17·2	29·8
June	77·1	74·8	77·1	76·9	2·1	13·7	6·8	14·2	23·1
July	76·5	74·1	76·9	77·3	3·2	5·7	3·2	6·6	9·7
August	74·1	70·9	74·7	75·8	4·9	10·3	5·1	10·1	17·1
September	74·5	72·1	75·1	75·8	3·7	7·0	3·0	8·3	11·9
October	67·2	63·0	70·4	69·4	6·4	13·0	5·5	17·1	21·2
November	56·4	47·6	60·7	62·0	14·4	14·9	7·3	19·1	23·3
December	52·1	41·9	55·1	57·8	15·9	14·1	7·0	17·8	22·5
Year	65·8	60·2	67·4	68·4	8·2	13·8	6·6	16·0	22·0

90. SURAT.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb.			
					Mean.	Minimum.	10 hours.	16 hours.
62·1	54·0	63·4	68·8	14·8	8·1	4·0	10·0	13·6
60·4	50·6	62·0	68·7	18·1	11·2	6·7	12·4	17·2
67·3	59·4	68·6	73·8	14·4	10·1	4·7	12·2	16·8
70·6	65·8	70·8	75·1	9·3	13·5	6·6	17·7	20·7
72·6	68·5	72·3	77·0	8·5	13·5	8·9	17·9	17·7
72·8	69·3	72·8	76·4	7·1	10·4	8·8	13·1	11·9
73·4	70·2*	73·8*	76·1*	5·9	7·5	7·2	8·9	8·3
73·9	70·4	74·6	76·8	6·4	7·6	6·7	9·3	9·0
74·1	70·5	74·8	77·0	6·5	4·4	4·2	6·4	5·2
71·9	66·4	73·3	76·0	9·6	6·8	4·5	9·7	10·4
64·5	56·7	66·5	70·4	13·7	8·2	4·1	11·9	14·1
59·0	49·4	60·8	66·7	17·3	8·5	4·4	10·7	14·4
68·6	62·6	69·5	73·6	11·0	9·2	5·9	11·7	13·3

* Mean of 29 days.

91. MALEGAON.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb.			
						Mean.	Minimum.	10 hours.	16 hours.
January	54·9	46·0	57·6	61·2	15·2	13·2	7·4	15·7	21·5
February	60·3	46·5	63·9	70·5	24·0	11·0	7·5	14·2	18·1
March	59·7	51·9	62·0	65·3	13·4	17·7	9·1	23·1	28·4
April	63·9	58·7	65·2	67·9	9·2	22·3	12·7	30·7	33·0
May	70·3	67·1	70·5	73·4	6·3	18·0	7·8	23·2	28·3
June	72·5	69·5	73·5	74·5	5·0	8·8	3·8	10·9	14·8
July	71·5	68·8	72·4	73·3	4·5	6·0	3·3	8·3	9·6
August	69·8	66·1	70·8	72·4	6·3	7·0	3·5	9·7	11·5
September	70·5	67·4	71·4	72·6	5·2	5·2	2·5	6·6	8·8
October	68·3	64·2	69·6	71·0	6·8	6·7	3·0	9·7	11·8
November	58·0	51·0	60·6	62·4	11·4	9·9	4·2	14·2	18·2
December	54·9	40·8	59·5	64·4	23·6	5·7	3·6	9·3	12·3
Year	64·6	58·2	66·4	69·1	10·9	11·0	5·7	14·6	18·0

92. BOMBAY.

Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Minimum.	Difference, Dry and Wet Bulb.					
						Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Minimum
68·3	64·9	67·5	70·9	67·8	63·5	7·2	4·9	9·5	11·0	5·8	5·5
68·3	64·2	67·5	71·1	67·6	62·7	6·7	4·7	10·1	9·7	5·4	5·1
71·6	68·7	72·1	73·1	70·4	67·6	6·5	3·8	9·1	9·6	5·6	4·3
77·2	74·9	78·0	78·1	76·4	74·1	5·3	3·2	7·6	8·3	4·1	3·5
78·6	76·6	79·2	79·4	77·5	75·6	5·9	4·1	8·2	8·7	4·9	4·4
78·8	77·5	79·7	79·5	77·6	75·4	3·2	2·6	4·6	4·7	3·2	2·7
77·8	76·7	78·6	78·3	76·8	74·5	2·7	2·3	3·4	3·7	2·3	2·3
76·8	75·6	77·5	77·2	75·7	74·1	3·4	2·5	4·0	5·2	3·1	2·9
76·1	74·8	77·2	76·3	75·1	73·1	2·4	1·6	3·4	4·2	2·4	2·1
76·3	73·9	76·7	77·9	75·3	72·5	3·8	2·5	5·2	6·2	3·2	3·1
71·4	66·6	71·1	73·3	70·6	67·6	6·4	6·2	8·8	9·8	4·6	4·2
65·1	61·5	64·0	68·8	64·2	60·6	8·2	6·2	10·5	11·1	5·8	5·9
73·9	71·3	74·1	75·3	72·9	70·1	5·1	3·7	7·0	7·7	4·2	3·8

93. POONA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry And Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	58·0	49·8	58·5	60·3	10·5	14·2	4·2	15·7	22·1
February	59·6	50·9	58·9	63·3	12·4	18·5	6·3	21·0	26·3
March	62·0	54·7	61·5	63·9	9·2	19·2	7·4	22·2	28·5
April	66·8	61·4	65·9	68·1	6·7	20·1	8·0	26·5	30·0
May	69·1	64·6	69·0	70·9	6·3	16·6	7·3	22·2	24·9
June	71·9	69·1	73·3	72·4	3·3	4·8	2·6	7·2	7·5
July	70·6	68·1	71·9	71·5	3·4	4·0	2·2	5·1	5·6
August	69·6	66·6	70·8	70·7	4·1	5·5	2·1	6·3	7·5
September	69·0	66·1	70·2	69·8	3·7	4·0	1·7	5·3	6·0
October	68·7	65·0	69·9	69·8	4·8	7·0	1·8	8·2	10·2
November	61·7	55·0	63·0	63·5	8·5	11·3	1·9	12·7	17·0
December	53·2	44·3	54·3	57·1	12·8	14·0	3·2	16·8	21·3
Year	65·0	59·6	65·6	66·8	7·1	11·6	4·1	14·1	17·2

94. SHOLAPUR.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
58·1	50·3	61·8	62·3	12·0	12·2	6·5	14·6	21·5
60·5	52·4	63·2	65·9	13·5	16·8	9·8	19·8	26·4
65·6	58·3	67·8	70·8	12·5	16·4	9·2	21·1	25·6
68·8	64·0	71·1	71·4	7·4	18·8	9·5	22·1	30·2
70·5	67·2*	71·3*	72·9*	5·7	18·0	7·5	20·0	29·4
68·9	66·9	69·0	70·7	3·8	8·8	2·8	11·7	14·9
69·7	68·1	69·8	71·2	3·1	8·7	3·1	10·5	14·3
70·0	68·6	69·8	71·5	2·9	7·9	2·6	9·1	13·1
70·1	69·0	70·1	71·1	2·1	6·4	2·4	7·5	10·5
70·3	68·0	71·1	71·9	3·9	7·3	2·8	10·2	12·4
67·8	64·9	68·1	70·4	5·5	6·6	3·0	10·2	10·5
57·9	50·5	60·5	62·6	12·1	9·7	5·2	13·3	16·9
66·5	62·4	67·8	69·4	7·0	11·5	5·4	14·2	18·8

* Mean of 24 days.

95. RATNAGIRI.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	67·0	60·8	68·0	72·3	11·5	7·6	5·3	15·4	10·7
February	68·3	61·6	70·3	72·9	11·3	7·2	5·8	13·1	10·6
March	71·2	66·7	72·5	74·4	7·7	6·2	4·6	10·5	9·1
April	75·8	72·5	77·2	77·8	5·3	6·1	4·6	9·9	8·8
May	77·2	75·3	78·0	78·2	2·9	7·1	4·7	10·8	10·3
June	76·0	72·7	77·5	77·8	5·1	3·1	3·3	4·5	4·3
July	75·8	72·3	77·3	77·7	5·4	2·5	3·1	3·2	3·4
August	75·5	72·0	77·2	77·4	5·4	3·0	3·0	4·3	4·5
September	74·9	70·6	77·1	76·9	6·3	2·1	2·9	3·5	3·5
October	75·0	70·3	77·0	77·7	7·4	3·3	3·1	7·9	5·5
November	70·6	64·2	72·6	75·0	10·8	5·3	4·2	12·7	8·4
December	64·6	58·2	65·1	70·5	12·3	8·2	5·6	17·4	11·2
Year	72·7	68·1	74·2	75·7	7·6	5·1	4·2	9·4	7·5

96. BELGAUM.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
58·8	53·3	59·9	61·0	7·7	11·1	3·5	12·9	18·1
60·6	55·4	60·7	63·2	7·8	15·8	4·8	19·4	23·4
?	Imperfect.	63·4	67·3	?	?	?	20·6	21·3
67·3	62·9	67·7	69·0	6·1	13·1	4·2	18·9	19·0
70·0	66·3	69·7	72·0	5·7	10·2	2·7	15·2	14·4
68·9	66·5	70·3	69·4	2·9	3·2	1·3	4·2	3·6
68·2	65·5	69·4	69·0	3·5	2·0	0·9	2·7	2·5
68·0	65·3	69·4	69·7	4·4	3·3	0·6	4·5	4·8
66·8	63·4	68·3	68·3	4·9	3·1	1·1	4·4	4·6
67·7	64·1	69·0	68·9	4·8	5·0	0·8	6·7	7·9
61·8	57·1	63·2	64·0	6·9	8·7	1·7	10·3	13·8
56·0	51·2	57·3	58·7	7·5	11·7	3·4	13·5	17·8
?	?	65·7	66·7	?	?	?	11·1	12·6

TABLE X.—TEMPERATURE OF EVAPORATION IN 1883.

97. KARWAR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	66·9	62·6	67·3	70·8	8·2	8·3	2·9	9·0	14·1
February	69·9	64·8	70·8	74·1	9·3	5·9	1·9	7·1	10·8
March	72·6	69·6	73·1	75·2	5·6	5·6	2·1	8·6	9·5
April	73·0	74·1	77·1	77·8	3·7	8·6	2·7	8·5	8·5
May	77·3	75·2	77·9	78·9	3·7	6·1	3·7	8·4	8·9
June	75·4	72·1	76·7	77·4	5·3	2·1	1·7	3·7	3·8
July	74·9	72·1	76·5	76·2	4·1	1·8	1·8	3·2	3·3
August	75·5	73·5	76·4	76·7	3·2	1·7	0·4	3·5	3·8
September	74·4	71·6	75·6	75·9	4·3	1·8	0·6	3·2	4·3
October	74·5	71·6	75·6	76·4	4·8	2·0	0·4	4·5	4·5
November	70·4	65·6	71·4	74·3	8·7	4·1	1·3	7·0	7·8
December	65·7	60·7	65·7	70·7	10·0	7·0	2·7	9·9	11·2
Year	72·5	69·5	73·7	75·4	5·9	4·6	1·9	6·4	7·5

98. GOPALPORE.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
...	Not recorded.	66·3	68·1	...	...	?	7·0	5·0
...		70·2	73·9	...	...	?	6·9	5·0
...		75·5	76·7	...	...	?	6·2	5·6
...		78·4	79·1	...	...	?	4·6	3·9
...		79·4	80·1	...	...	?	4·7	4·0
...		79·6	79·8	...	...	?	4·1	4·0
...		78·5	78·6	...	...	?	3·4	3·3
...		79·4	79·8	...	...	?	3·9	4·3
...		79·0	79·1	...	...	?	4·2	4·8
...		76·5	77·1	...	...	?	6·1	7·1
...		67·2	68·9	...	...	?	7·3	8·9
...		60·6	63·6	...	...	?	6·2	8·3
...		74·2	75·4	...	...	...	5·4	5·4

99. VIZAGAPATAM.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.	Difference, Dry and Wet Bulb. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Minimum.
January	67·6	66·6	67·7	68·4	67·7	60·1	7·7	5·9	8·1	9·6	7·0	11·0
February	70·3	69·5	69·9	71·1	70·7	63·5	9·0	7·0	10·2	11·1	7·5	11·4
March	74·7	74·0	74·1	75·6	75·2	69·1	8·9	7·4	10·8	9·5	7·6	11·3
April	77·5	77·0	76·7	78·4	77·7	71·5	8·6	7·0	11·1	8·9	7·6	12·0
May	80·2	79·5	79·8	81·1	80·5	73·7	8·5	7·1	10·6	8·8	7·3	12·6
June	78·1	77·7	77·8	78·3	78·6	72·1	9·3	7·8	10·5	10·8	8·2	13·1
July	77·0	76·1	77·1	77·5	77·4	70·6	8·5	7·3	9·0	9·9	7·8	12·5
August	78·2	77·8	78·1	78·7	78·2	72·8	7·7	6·7	8·4	8·4	7·1	11·2
September	77·6	77·2	77·4	78·0	77·9	71·5	7·2	6·0	7·6	8·5	6·6	11·3
October	76·3	75·9	76·3	76·3	76·7	71·6	7·3	6·2	8·0	8·8	6·3	9·8
November	68·0	67·4	67·9	68·5	68·3	63·5	8·7	6·8	9·6	10·7	7·7	9·6
December	63·4	62·7	62·2	64·4	64·3	57·6	9·4	8·3	10·7	10·3	8·3	12·2
Year	74·1	73·5	73·8	74·7	74·4	68·1	8·4	7·0	9·6	9·6	7·4	11·5

100. MASULIPATAM.

Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
67·8	64·1	69·9	69·5	67·5	5·4	6·2	2·4	8·4	9·2	5·9
69·7	65·4	72·5	71·3	69·4	4·0	6·1	1·6	9·0	10·8	4·0
75·8	72·6	77·4	77·2	75·6	4·6	5·0	1·3	8·6	8·2	3·0
79·2	76·4	80·4	80·6	78·9	4·2	4·8	0·9	9·2	7·7	2·5
83·4	80·6	84·8	85·3	82·0	4·7	5·6	2·0	9·7	8·6	3·6
81·2	78·6	81·7	83·1	80·9	4·5	4·3	0·9	6·6	8·1	2·7
78·5	76·2	79·6	80·1	77·8	3·9	4·3	0·8	6·4	8·4	2·5
77·4	76·1	77·7	78·1	77·5	2·0	6·5	1·9	9·5	10·7	4·3
76·5	75·0	77·0	77·2	76·4	2·2	7·5	2·3	10·1	12·7	5·2
76·7	75·0	77·6	77·3	76·8	2·3	3·9	0·9	6·3	6·3	2·7
70·5	67·7	71·9	72·0	70·2	4·9	4·3	1·5	6·7	8·1	3·9
66·9	62·4	68·4	70·0	66·7	7·6	4·5	1·4	6·8	7·1	4·1
75·3	72·5	76·6	76·8	75·0	4·2	5·3	1·5	8·1	8·8	3·7

101. SECUNDERABAD.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	60·7	56·6	62·9	63·3	59·9	6·7	8·8	3·2	9·0	16·4	8·0
February	62·2	57·6	64·2	65·4	61·2	7·8	14·6	7·1	15·6	23·1	14·1
March	67·0	63·8	68·8	68·6	66·3	4·8	13·5	5·8	14·4	22·8	12·3
April	68·1	64·3	70·3	69·9	67·3	5·6	19·6	11·9	21·1	28·8	18·2
May	70·6	67·7	72·5	71·8	69·7	4·1	21·3	13·5	22·3	30·3	20·9
June	72·0	69·4	72·9	73·5	71·6	4·1	7·9	4·2	9·2	12·5	6·8
July	71·1	68·4	71·8	72·9	70·8	4·5	5·7	3·0	6·7	9·6	4·4
August	71·5	68·6	72·4	73·1	71·5	4·5	5·6	3·1	6·9	9·0	4·2
September	70·9	68·1	71·5	72·7	70·6	4·6	4·4	2·1	5·7	7·5	3·0
October	69·6	66·8	71·3	70·7	69·5	3·9	5·8	2·6	7·9	9·4	3·8
November	60·7	56·4	63·1	63·5	59·6	7·1	8·5	2·3	11·4	14·6	6·5
December	55·0	49·5	57·8	59·0	53·6	9·5	10·6	4·6	12·3	18·1	9·5
Year	66·6	63·1	68·3	68·7	66·0	5·6	10·5	5·3	11·9	16·8	9·3

102. KURNOOL.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	...	...	...	...	...	...	...	...	...
February	64·2	57·5*	66·4*	69·0*	11·5	15·0	6·0	18·5	25·0
March	70·7	68·3	71·4	72·4	4·1	14·8	6·1	17·6	25·1
April	76·9	72·1	77·7	79·8	7·7	13·2	6·9	17·1	22·7
May	80·5	75·3	81·0	83·4	8·1	10·3	7·2	13·4	18·9
June	76·8	73·9	77·2	78·0	4·1	5·5	2·0	8·8	11·5
July	75·5	72·1	76·3	77·0	4·9	4·1	1·3	7·2	8·9
August	75·7	72·4	75·1	78·2	5·8	4·0	1·2	7·3	7·7
September	74·5	70·6	74·9	76·6	6·0	4·7	2·0	6·3	9·4
October	74·0	70·6	75·5	75·7	5·1	4·1	1·4	6·0	7·2
November	69·8	Imperfect.	69·8	71·2	?	3·5	?	8·2	11·3
December	64·2	55·2	67·5	71·4	16·2	4·6	1·2	6·5	9·6
Year	?	?	?	?	?	?	?	?	?

* Mean of 20 days.

103. BELLARY.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	61·7	56·6	64·9	65·0	60·2	8·4	10·2	4·1	11·0	18·2	8·9
February	61·4	53·6	64·3	66·5	60·8	12·9	16·1	10·1	18·0	24·7	13·2
March	67·1	61·9	69·2	70·4	66·6	8·5	17·2	11·1	18·6	25·4	15·5
April	68·7	63·5	71·2	71·2	67·9	7·7	20·7	14·3	22·1	29·7	18·5
May	71·9	67·9	73·3	73·3	72·5	5·4	18·1	10·8	18·8	28·4	16·1
June	71·6	68·5	73·1	73·4	71·0	4·9	11·7	8·1	13·5	17·1	9·1
July	71·1	68·4	72·1	72·8	70·6	2·4	9·6	6·1	11·7	14·7	7·0
August	71·7	68·7	72·4	73·6	71·3	4·9	8·5	5·2	9·7	13·0	7·3
September	69·8	65·8	71·0	72·0	69·7	6·2	11·1	7·0	11·8	17·1	9·0
October	71·1	67·6	72·5	72·4	71·3	4·8	6·6	3·6	8·3	11·1	4·8
November	64·0	59·5	67·0	66·4	62·9	6·9	8·8	3·2	11·0	15·7	6·2
December	59·0	53·6	62·0	62·9	57·5	9·3	10·2	4·7	11·9	17·8	8·4
Year	67·4	63·0	69·4	70·0	66·9	6·9	12·4	7·4	13·9	19·4	10·3

104. MANGALORE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	69·2	65·3	69·0	73·2	7·9	7·5	4·0	12·7	10·8
February	72·2	68·9	72·4	75·4	6·5	6·5	3·6	11·3	9·5
March	74·8	72·4	75·8	76·2	3·8	5·9	3·3	8·3	9·4
April	78·1	75·7	78·7	79·8	4·1	4·4	2·0	7·4	7·4
May	78·2	76·4	78·8	79·3	2·9	4·7	2·5	7·2	7·6
June	76·1	73·2	77·5	77·7	4·5	2·2	1·6	3·3	4·0
July	75·1	72·8	76·2	76·4	3·6	1·4	1·1	2·3	2·7
August	75·4	73·5	76·1	76·5	3·0	1·8	1·1	3·0	3·2
September	75·3	72·6	76·7	76·6	4·0	2·5	1·4	4·3	5·0
October	75·1	72·7	76·3	76·3	3·6	2·4	1·1	4·7	4·9
November	72·3	69·4	72·9	74·7	5·3	5·1	2·1	9·1	8·6
December	68·4	65·0	68·7	71·4	6·4	7·0	3·4	11·7	10·9
Year	74·2	71·5	74·9	76·1	4·6	4·3	2·3	7·1	7·0

105. MERCARA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	58·7	53·9	60·1	62·0	8·1	5·2	1·6	6·2	10·2
February	59·3	54·5	61·1	62·3	7·8	8·2	2·3	10·3	15·8
March	64·1	59·2	65·9	67·1	7·9	5·5	2·2	10·3	10·6
April	66·8	61·9	68·6	70·0	8·1	3·9	1·9	8·7	7·6
May	68·0	63·7	69·4	70·9	7·2	2·5	1·5	5·0	4·9
June	65·3	62·9	66·9	66·0	3·1	0·2	0·8	1·3	1·2
July	63·9	62·2	64·9	64·7	2·5	0·1	0·5	0·4	0·6
August	64·9	62·4	66·0	66·4	4·0	0·6	0·7	1·6	1·4
September	63·7	60·8	64·9	65·4	4·6	0·8	0·5	2·5	2·2
October	64·5	61·2	66·3	66·6	4·8	1·4	1·0	3·4	3·5
November	61·3	57·2	62·9	63·7	6·5	2·9	1·6	4·0	5·9
December	58·0	53·4	59·2	61·4	8·0	3·8	2·1	5·4	6·6
Year	63·2	59·4	64·7	65·5	6·1	2·9	1·4	4·9	5·9

106. BANGALORE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	58·9	52·9	61·0	62·3	59·2	9·4	7·4	1·0	8·4	14·0	7·8
February	60·4	56·3	61·3	63·0	60·5	6·7	10·7	2·0	12·4	19·1	11·0
March	66·4	62·8	68·6	68·4	65·4	5·6	10·8	2·7	11·7	19·4	10·6
April	67·2	63·3	69·9	68·9	66·1	5·6	13·1	5·7	13·3	21·7	13·0
May	69·5	65·1	71·6	72·0	68·6	6·9	9·8	2·8	10·8	17·1	10·2
June	68·1	64·3	69·6	70·4	67·3	6·1	6·6	1·5	8·5	11·7	6·4
July	67·1	62·9	68·7	69·5	66·3	6·6	4·1	1·4	5·5	7·5	3·8
August	67·5	62·5	69·2	70·7	66·5	8·2	5·0	1·9	5·5	8·8	5·3
September	65·7	60·8	67·3	68·6	65·4	7·8	6·7	1·8	7·0	11·5	7·1
October	66·3	61·4	68·4	68·9	65·8	7·5	4·4	1·2	5·7	7·8	4·5
November	61·7	56·4	63·6	64·5	61·9	8·1	5·7	1·1	6·9	10·2	5·7
December	58·1	52·3	59·8	61·8	58·5	9·5	6·3	1·3	7·9	10·9	6·9
Year	64·7	60·1	66·6	67·4	64·3	7·3	7·6	2·0	8·6	13·3	7·7

107. MADRAS.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	69·3	65·9	71·5	71·2	68·7	5·3	6·3	2·2	9·1	9·1	5·6
February	71·0	66·0	73·4	74·4	70·1	8·4	5·4	1·3	9·0	8·6	3·7
March	75·4	71·9	76·7	77·3	75·2	5·4	5·3	1·5	9·3	7·6	4·1
April	77·9	74·9	78·2	79·8	78·1	4·9	5·8	2·0	11·3	7·4	3·8
May	79·7	77·2	80·6	80·9	79·6	3·7	7·8	4·5	13·8	8·8	5·1
June	78·2	75·2	78·4	80·2	78·4	5·0	8·4	5·0	12·4	12·0	5·4
July	76·3	73·5	77·2	78·3	75·8	4·8	6·9	4·0	9·5	10·4	4·8
August	77·4	74·7	77·8	79·5	77·0	4·8	6·5	3·0	10·5	9·1	4·3
September	76·6	73·7	76·9	77·9	77·6	4·2	8·1	4·2	12·3	11·7	4·5
October	75·6	73·2	76·9	76·3	75·3	3·1	3·0	1·3	4·8	5·4	1·7
November	71·8	69·0	73·4	73·2	71·2	4·2	4·5	1·9	6·4	7·0	3·3
December	68·9	66·5	70·3	70·2	68·6	3·7	4·7	2·0	6·6	7·1	3·7
Year	74·8	71·8	75·9	76·6	74·6	4·8	6·1	2·7	9·6	8·7	4·2

108. SALEM.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	65·5	57·1*	68·3	69·7	66·3	12·6	9·7	7·2	10·4	15·4	7·8
February	67·5	?	68·5	69·6	67·0	?	10·0	?	12·0	19·9	10·4
March	72·0	Imperfect.	73·3	74·3	71·1	?	11·0	?	11·2	21·5	10·9
April	75·2	71·9	77·3	76·5	74·4	4·6	10·9	4·1	11·1	20·3	10·0
May	76·0	71·2	77·7	79·6	74·3	8·4	8·6	3·7	9·7	15·7	7·4
June	75·3	70·8	76·8	78·2	74·7	7·3	6·1	2·1	6·9	12·3	4·6
July	74·6	69·4	75·9	77·7	74·6	8·3	5·0	2·2	5·3	10·1	4·1
August	75·0	68·9	76·6	78·9	74·2	10·0	3·7	2·3	4·4	6·8	3·2
September	74·5	68·5	75·7	78·5	74·2	10·0	6·0	2·2	6·1	12·2	4·7
October	72·9	67·3	74·6	76·1	72·9	8·8	3·9	2·4	4·3	7·0	3·1
November	69·9	63·5	71·9	74·4	69·5	10·9	4·1	2·7	5·0	6·4	3·4
December	67·2	59·7	69·4	72·6	67·3	12·9	4·6	3·5	5·5	6·8	4·0
Year	72·1	?	73·8	75·5	71·7	?	7·0	?	7·7	12·9	6·1

* Mean of 30 days.

109. WELLINGTON.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	51·5	45·0	53·6	55·2	52·0	7·0	3·6	2·2	5·6	5·9	2·1
February	49·8	42·3	52·2	54·8	49·8	12·5	7·8	4·1	12·4	11·4	4·1
March	55·0	50·0	56·7	57·6	55·3	7·6	7·5	3·7	11·4	11·4	4·8
April	57·8	53·2*	58·9*	59·8*	58·1	6·6	7·9	3·9	12·7	11·6	5·5
May	60·1	55·6	62·1	61·9	59·9	6·3	6·7	3·4	11·4	10·2	4·4
June	58·0	54·3	60·2	60·0	57·0	5·7	5·6	4·5	7·7	6·8	4·5
July	58·0	54·6	60·2	59·5	57·2	4·9	5·2	4·0	6·6	6·9	4·2
August	59·0	55·3	61·2	60·8	57·8	5·5	4·1	2·9	5·9	5·5	3·2
September	57·0	51·6	59·7	60·1	55·4	8·5	5·0	3·0	7·9	6·6	3·7
October	58·0	54·1	60·1	60·2	57·0	6·1	2·1	1·0	4·1	3·2	1·1
November	54·1	47·6	56·9	58·3	53·1	10·7	3·2	2·2	6·1	3·6	1·9
December	51·0	45·4†	53·4†	55·0†	50·1†	9·6	3·9	3·1	6·2	5·1	2·6
Year	55·8	50·8	57·9	58·6	55·2	7·6	5·2	3·2	8·2	7·4	3·5

110. COIMBATORE.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	65·1	61·6	66·3	67·1	65·3	5·5	9·0	3·2	9·2	16·2	8·7
February	65·4	60·6	67·2	67·2	66·5	6·6	11·4	4·1	12·4	21·1	9·3
March	70·5	67·1	72·2	70·9	71·3	3·8	10·8	3·4	10·8	22·4	8·0
April	73·6	70·7	75·1	73·9	74·2	3·2	9·7	3·2	11·5	19·4	6·3
May	73·9	69·9	75·5	76·0	73·5	6·1	7·5	3·6	9·7	13·1	5·1
June	71·4	68·3	72·8	73·3	70·6	5·0	7·0	3·3	8·9	11·3	5·9
July	70·7	67·1	72·1	72·7	70·1	5·6	5·9	3·4	7·8	9·1	4·7
August	71·3	67·5	72·7	73·4	70·9	5·9	5·7	2·0	7·4	9·8	4·7
September	70·5	66·9	71·8	72·7	70·1	5·8	7·2	2·6	9·2	12·3	5·1
October	71·0	67·6	72·1	73·0	70·9	5·4	5·1	2·6	6·4	9·0	3·4
November	69·0	65·3	70·0	71·0	69·4	5·7	5·1	2·1	6·5	9·7	3·2
December	65·8	62·0	67·2	68·1	66·0	6·1	6·3	2·5	7·4	11·8	4·9
Year	69·9	66·2	71·3	71·6	69·9	5·4	7·6	3·0	8·9	13·8	5·8

* Mean of 29 days. † Mean of 28 days.

111. TRICHINOPOLY.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	69·3	65·9	70·3	71·5	69·3	5·6	7·1	2·8	9·5	12·9	4·2
February	68·9	65·0	70·7	70·5	69·1	5·5	9·0	1·8	10·9	18·4	6·2
March	72·6	69·3	74·4	74·4	72·1	5·1	11·5	3·9	13·1	21·0	9·2
April	75·1	71·0	76·7	76·2	75·8	5·2	13·6	6·5	15·4	23·5	10·5
May	76·9	73·9	78·0	78·7	76·6	4·8	11·5	5·4	13·1	20·2	8·5
June	76·2	73·1	77·4	77·9	75·9	4·8	10·2	5·3	12·9	17·7	6·2
July	75·2	71·6	76·6	76·9	74·9	5·3	9·7	6·4	11·9	15·6	6·5
August	74·9	71·9	76·2	76·8	74·2	4·9	9·3	4·7	10·9	15·1	7·3
September	74·0	70·7	75·3	76·3	73·1	5·6	10·5	4·8	12·8	17·6	7·5
October	74·2	71·*	75·3	76·0	74·0	5·0	4·9	2·4	6·4	8·4	3·3
November	71·1	68·1	72·6	72·7	71·0	4·6	5·4	2·3	7·3	8·6	3·7
December	68·6	65·2	70·0	70·6	68·5	5·4	5·8	2·9	7·9	9·5	4·2
Year	73·1	69·7	74·4	74·9	72·9	4·2	9·0	4·1	11·0	15·7	6·4

112. NEGAPATAM.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	70·8	68·1	72·2	72·1	70·9	4·0	5·7	3·3	6·9	7·3	5·6
February	70·3	67·2	71·6	71·9	70·4	4·7	7·1	4·0	9·0	9·2	6·7
March	74·2	71·4	75·6	75·4	74·2	4·0	7·2	3·3	9·9	10·1	6·0
April	77·7	75·0	78·2	79·2	77·7	4·2	7·1	3·8	10·8	9·4	5·7
May	77·5	75·2	77·7	78·9	78·0	3·7	8·7	4·9	13·2	11·4	6·5
June	75·5	72·6	75·3	77·7	75·8	5·1	9·2	5·3	13·7	12·3	6·8
July	75·0	72·3	74·6	77·0	75·8	4·7	9·0	5·1	12·8	12·7	6·6
August	75·8	73·2	75·7	77·8	76·1	4·6	7·7	3·9	10·5	10·6	6·7
September	75·2	71·8	74·7	77·7	75·8	5·9	7·7	4·5	11·3	9·5	6·4
October	74·4	71·8	75·1	75·6	74·7	3·8	4·8	2·7	6·0	6·9	4·3
November	71·5	69·1	72·8	72·4	71·6	3·3	5·3	2·9	6·0	7·2	5·7
December	69·9	67·2	70·8	71·0	70·7	3·8	4·7	2·6	5·7	6·6	4·7
Year	74·0	71·2	74·5	75·6	74·3	4·3	7·0	3·9	9·7	9·4	6·0

113. MADURA.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	69·5	66·9	69·8	72·7	68·6	5·8	8·3	2·0	11·8	12·9	7·9
February	69·5	66·8	70·7	71·5	69·1	4·7	9·0	1·9	10·9	16·1	8·0
March	Not recorded										
April	Ditto.										
May	Ditto.										
June	74·6	72·3	75·4	76·5	73·6	4·2	11·1	4·9	16·0	17·0	8·0
July	74·4	72·5	75·2	75·0	74·6	2·5	9·0	2·6	15·4	14·8	4·2
August	75·5	73·1	76·9	76·7	74·8	3·6	8·1	2·1	12·6	15·1	3·5
September	75·6	72·1	76·6	78·5	74·4	6·4	8·4	2·1	13·2	15·2	3·9
October	74·7	71·7	76·2	76·8	73·9	5·1	4·8	0·7	7·9	8·4	3·1
November	72·7	69·9	74·2	74·3	72·3	4·4	4·3	0·6	6·4	6·7	4·1
December	69·9	66·7	71·3	72·3	69·5	5·6	5·6	1·4	7·9	8·7	5·6
Year	?	?	?	?	?	?	?	?	?	?	?

114. COCHIN.

Month.	Mean.	Minimum.	10 hours.	16 hours.	22 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.	22 hours.
January	72·0	68·5	72·3	74·4	72·9	5·9	7·3	3·5	10·8	11·1	4·5
February	73·1	69·9	73·0	75·4	74·0	5·5	6·6	2·8	10·1	10·3	3·9
March	76·8	74·2	77·5	78·6	76·5	4·4	5·6	2·8	7·2	8·6	4·8
April	77·7	74·8	78·6	79·9	76·7	5·1	5·6	3·3	7·4	8·0	4·8
May	78·0	75·2	78·8	79·6	77·6	4·4	4·2	2·4	5·5	6·4	3·7
June	76·2	72·8	77·3	77·9	76·2	5·1	2·7	1·8	3·7	4·1	2·0
July	75·0	72·2	76·2	76·2	75·1	4·0	2·2	1·7	2·8	3·5	1·5
August	75·7	73·4	76·5	76·7	75·7	3·3	2·4	1·5	3·4	3·6	1·8
September	75·7	73·3	76·7	77·0	75·5	3·7	3·8	1·8	4·7	5·9	3·1
October	75·1	72·6	76·6	76·5	74·5	3·9	3·2	1·4	4·8	5·5	1·9
November	74·1	71·8	75·1	75·5	73·8	3·7	4·2	1·7	6·4	6·9	2·5
December	71·6	68·5	72·4	73·3	72·0	4·8	5·3	2·6	8·1	9·0	3·5
Year	75·1	72·3	75·9	76·8	75·0	4·5	4·4	2·3	6·2	6·9	3·2

115. AKYAB.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	63·1	57·1	65·4	66·9	9·8	6·7	2·5	5·9	11·1
February	63·6	55·6	65·5	69·8	14·2	7·9	3·1	8·7	9·8
March	71·0	66·4	72·4	74·3	7·9	7·7	2·7	8·8	9·4
April	76·0	71·5	77·8	78·8	7·3	7·1	3·1	7·7	8·4
May	78·0	74·2	79·1	80·6	6·4	5·2	3·1	5·0	5·7
June	77·1	74·3	78·5	78·4*	4·1	4·1	3·3	3·3	3·8
July	77·1	74·8	78·1	78·4	3·6	3·5	2·8	2·5	3·1
August	76·8	74·3	78·0	78·1†	3·8	3·3	2·8	2·5	2·8
September	77·1	74·6	78·4	78·4	3·8	4·2	3·2	3·6	4·4
October	77·4	74·2	78·7	79·4	5·2	5·0	2·7	4·9	6·7
November	71·1	67·3‡	72·8‡	73·1§	5·8	5·7	3·0	5·4	7·8
December	66·2	62·0	67·4	69·3	7·3	5·2	3·0	4·7	6·8
Year	72·9	68·9	74·3	75·5	6·6	5·5	2·9	5·3	6·7

116. THAYETMYO.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	61·3	52·1	64·6	67·3	15·2	?	?	8·0	17·2
February	62·0	51·6	65·3	69·1	17·5	?	?	11·7	22·8
March	68·6	61·8	71·9	72·0	10·2	13·3	4·1	15·2	25·9
April	77·2	72·0	79·5	80·2	8·2	9·8	4·1	12·0	17·7
May	78·0	73·5	80·0	80·5	7·0	6·2	3·1	8·8	11·3
June	77·5	74·7*	78·6	79·1	4·4	2·6	1·3	4·9	5·0
July	77·6	75·0	78·4	79·3	4·3	2·8	1·4	4·3	5·0
August	7·4	75·1	78·5	78·7	3·6	3·2	1·7	5·6	5·6
September	7·9	74·4	79·0	80·3	5·9	3·1	1·3	5·0	6·0
October	77·3	73·1	78·9	80·0	·69	3·8	1·1	5·5	8·0
November	71·8	67·3	73·0	75 0	7·7	3·2	0·9	4·8	6·8
December	66·1	59·6	66·7	72·0	12 4	3·7	1·2	5·6	6·8
Year	72·7	67·5	74·5	76·1	8·6	?	?	7·6	11·5

* Mean of 29 days. † " " 30 " ‡ Mean of 27 days. § " " 25 " • Mean of 28 days.

117. TOUNGOO.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	62·5	52·8	60·1	68·7	15·9	6·7	3·1	7·2	13·8
February	64·1	54·9	68·3	69·9	15·0	9·2	3·7	10·1	18·7
March	70·2	61·0	74·7	75·0	14·0	9·3	3·6	10·8	19·3
April	Untrustworthy.		76·5	77·0	?	?	?	10·7	15·7
May	Ditto.		78·3	78·7	?	?	?	7·7	12·0
June	74·4	69·3	77·2	76·6	7·3	3·4	4·1	4·9	5·5
July	75·1	72·6	76·4	76·3	3·7	2·5	2·0	4·5	4·3
August	75·3	73·3	70·2	76·5	3·2	2·4	1·2	4·3	4·3
September	75·8	73·4	76·9	77·0	3·6	2·6	1·2	5·3	5·1
October	76·8	73·4	78·7	78·4	5·0	3·9	1·2	8·0	8·3
November	72·8	68·9	74·9	74·5	5·6	3·3	1·6	5·7	7·1
December	67·4	60·6	70·1	71·6	11·0	3·7	2·4	6·3	7·6
Year	?	?	74·5	75·0	?	?	?	7·1	10·1

118. BASSEIN.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
66·0	58·8	68·0	71·3	12·5	4·9	0·7	8·8	10·9
67·8	61·6	69·9	71·8	10·2	7·6	1·7	11·3	15·6
72·1	68·5	74·0	73·7	5·2	8·1	1·6	11·6	16·5
75·7	73·1	76·8	77·2	4·1	7·0	1·5	11·2	13·6
78·0	75·5	78·8	79·7	4·2	5·0	1·8	8·0	8·9
76·9	74·7	78·5	77·6	2·9	1·4	1·2	3·0	3·1
76·6	74·4	78·1	77·4	3·0	1·4	1·0	3·1	3·2
77·0	75·2	78·2	77·7	2·5	1·7	1·1	3·3	3·3
76·3	73·9*	77·8	77·3	3·4	?	?	3·4	3·2
77·2	73·8	79·1	78·8	5·0	?	?	5·0	5·6
73·2	69·6	74·6	75·4	5·8	?	?	4·7	5·2
69·2	63·9†	70·7	73·1	9·2	3·5	1·9	5·6	6·5
73·8	70·3	75·4	75·9	5·7	?	?	6·6	8·0

* Mean of 25 days. † Mean of 23 days.

119. DIAMOND ISLAND.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	68·5	66·7	69·1	69·8	3·1	6·0	3·2	8·1	9·2
February	70·3	68·4	71·3	71·3	2·9	5·8	3·2	8·4	9·3
March	73·7	71·8	74·4	74·9	3·1	4·8	3·0	7·7	7·2
April	76·4	74·9*	76·9*	77·4	2·5	4·8	2·7	7·7	7·4
May	78·2	75·7	79·6	79·2	3·5	4·1	2·9	6·3	6·7
June	76·7	74·4	77·9	77·7	3·3	1·9	1·4	3·9	3·6
July	76·4	74·1	77·9	77·1	3·0	1·6	1·3	4·1	3·5
August	76·7	74·6	78·1	77·4	2·8	1·6	1·3	3·9	3·2
September	75·9	73·6	77·3	76·9	3·3	2·0	1·3	3·8	4·0
October	77·3	75·1	78·8	77·9	2·8	3·1	2·0	5·1	5·8
November	74·3	72·1	75·4	75·3	3·2	3·2	1·9	4·8	5·6
December	70·8	68·5	71·1	72·7	4·2	5·2	2·5	6·7	8·2
Year	74·6	72·5	75·7	75·6	3·1	3·7	2·2	5·9	6·1

120. RANGOON.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
66·3	61·2	68·5	69·1	7·9	8·1	3·1	9·3	15·4
68·4	61·9	70·4	73·0	11·1	9·0	3·0	9·4	16·8
73·1	68·3	74·5	76·4	8·1	8·3	3·0	8·7	15·0
76·8	72·7	78·2	79·5	6·8	6·3	2·6	7·2	11·4
78·2	75·2	80·1	79·2	4·0	3·6	2·3	5·9	6·8
77·0	74·3	78·4	78·2	3·9	2·0	1·9	3·1	3·5
76·2	73·9	78·2	76·5	2·6	1·0	1·9	3·0	2·1
76·7	74·7	78·6	76·9	2·2	1·4	1·9	3·3	2·6
76·1	73·6	77·3	77·5	3·9	2·1	1·7	2·9	3·5
77·3	74·1	79·6	78·2	4·1	3·7	2·0	5·2	7·6
74·0	70·6	75·8	75·6	5·0	3·9	2·8	4·7	6·8
69·2	64·8	71·2	71·6	6·8	5·8	3·1	7·0	10·4
74·1	70·4	75·9	76·0	5·5	4·6	2·4	5·8	8·5

* Mean of 29 days.

121. MOULMEIN.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	65·6	60·8	67·4	68·7	7·9	8·4	1·9	9·5	16·6
February	70·7	66·5	72·8	72·8	6·3	7·8	1·1	7·5	16·5
March	73·9	70·2	75·7	75·9	5·7	7·1	1·9	9·6	13·9
April	72·8	73·2	77·7	77·6	4·4	9·9	2·0	8·3	12·6
May	77·1	73·4	78·8	79·0	5·6	4·1	1·4	6·0	8·5
June	75·8	73·2	77·0	77·1	3·9	1·5	1·0	2·4	3·3
July	75·4	72·7	76·7	76·9	4·2	1·3	1·0	2·0	2·8
August	75·9	72·9	77·5	77·3	4·4	1·7	1·2	2·5	3·7
September	75·4	72·6	76·6	77·1	4·5	1·9	0·9	2·7	4·0
October	76·3	72·9	77·8	78·1	5·2	4·3	1·3	6·1	8·8
November	73·5	69·9	75·2	75·5	5·6	4·0	1·5	7·5	8·1
December	68·6	64·5	70·0	71·2	6·7	6·9	1·9	9·5	13·3
Year	73·4	70·2	75·3	75·6	5·4	4·9	1·4	6·1	9·3

122. MERGUI.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
72·0	67·3	73·4	75·2	7·9	4·4	1·5	6·5	8·8
75·6	72·4	77·0	77·5	5·1	5·0	0·3	9·2	10·9
76·0	71·9	77·7	78·3	6·4	4·4	0·7	9·2	9·9
77·1	72·2	79·2	80·0	7·8	3·2	0·9	7·2	7·4
77·2	73·2	79·3	79·1	5·9	2·5	0·9	5·1	6·1
75·5	72·1	77·3	77·0	4·9	0·8	0·7	2·6	2·7
75·0	71·5	76·8	76·8	5·3	0·8	0·8	2·4	2·4
75·8	71·6	78·3	77·5	5·9	0·3	0·9	2·5	2·2
74·7	71·1	76·5	76·5	5·4	1·1	0·9	2·4	3·0
74·9	70·9	76·9	76·8	5·9	2·1	0·9	5·5	5·4
73·7	69·5	75·3	76·2	6·7	3·1	0·9	7·5	7·0
70·5	65·9	71·4	74·1	8·2	4·6	1·3	9·6	8·8
74·8	70·8	76·6	77·1	6·3	2·7	0·9	5·8	6·2

123. PORT BLAIR.

Month.	Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
January	74·0	70·7	74·9	76·3	5·6	5·3	4·5	6·8	7·0
February	74·7	70·4	76·0	77·7	7·3	5·0	2·9	5·9	8·3
March	76·6	72·3	77·8	79·8	7·5	5·0	2·2	6·8	8·8
April	79·1	75·6	80·3	81·3	5·7	4·6	1·9	6·8	8·6
May	79·3	76·5	80·7	80·8	4·3	2·9	1·7	4·6	5·4
June	78·2	75·7	79·3	79·6	3·9	2·6	2·2	3·6	4·1
July	76·8	73·8	78·2	78·4	4·6	2·6	3·0	3·3	3·6
August	77·2	74·5	78·9	79·1	4·6	2·6	2·3	3·3	3·6
September	76·6	73·9	78·1	77·8	3·9	1·9	1·9	2·7	3·3
October	77·8	74·6	79·5	79·3	4·7	2·7	2·5	3·9	4·5
November	76·6	73·8	78·0	78·0	4·2	3·0	2·7	4·0	4·7
December	74·9	72·2	76·1	76·5	4·3	3·1	2·8	3·6	4·4
Year	76·8	73·7	78·2	78·7	5·1	3·4	2·6	4·6	5·5

124. NANCOWRY.

Mean.	Minimum.	10 hours.	16 hours.	Range.	Difference, Dry and Wet Bulb. Mean.	Minimum.	10 hours.	16 hours.
73·9	72·9	74·7	74·0	1·1	5·8	4·4	7·9	8·0
74·3	73·2	74·9	74·7	1·5	6·1	3·7	9·0	9·2
75·6	74·5	76·4	75·8	1·3	5·5	3·2	9·4	8·6
77·4	76·2	77·8	78·3	2·1	5·1	2·9	9·6	7·6
77·9	76·2	78·6	78·8	2·6	4·8	3·3	7·2	7·0
77·0	75·0	78·1	77·9	2·9	4·1	3·5	6·3	5·8
76·6	74·7	77·3	77·6	2·9	?	?	6·7	6·4
76·7	72·8	79·6	77·8	5·0	?	?	4·2	4·7
76·3	73·1	78·2	77·6	4·5	?	?	3·9	4·6
76·3	73·5*	78·2	77·1*	3·6	?	?	5·9	5·7
75·1	71·7	77·1	76·4	4·7	?	?	4·9	4·0
74·0	70·9	75·6	75·4	4·5	?	?	5·8	5·5
75·9	73·7	77·2	76·8	3·1	?	?	6·7	6·4

* Mean of 30 days.

TABLE XI.—TENSION OF ATMOSPHERIC VAPOUR IN 1883 (130 STATIONS).

(In Decimals of an inch of Mercury).

Month.	1. Zanzibar. Mean.	10 hours.	16 hours.	From Minima.	2. Aden. Mean.	10 hours.	16 hours.	From Minima.	3. Seychelles. Mean.	10 hours.	16 hours.	From Minima.	4. Bushire. Mean.	10 hours.	16 hours.	From Minima.
January	·817	·837*	·804*	·810*	·652	·685	·656	·615					·369	·388*	·399*	·319*
February	·833	·853†	·816‡	·830‡	·601	·623	·588	·593					·356	·367	·391	·311
March	·849	·862§	·834§	·850§	·706	·730	·685	·702	Observatory opened in June.				·391	·389	·440	·345
April	·832	·848	·818‖	·831¶	·738	·792	·696	·727					·500	·484	·548	·467
May	·773	·792	·771	·757	·847	·883	·865	·792					·658	·673	·718	·583
June	·680	·719	·644	·677	·791	·867	·791	·714	·856	·926‡	·858¶	·784††	·771	·804	·833	·676
July	·695	·723	·677	·685	·686	·736*	·651	·672	·881	·963††	·911‖	·769††	·880	·918	·944	·777
August	·652	·698	·603	·655	·776	·838	·739	·750	·819	·851†	·836**	·770**	·945	·996	1·024	·814
September	·700	·724	·692	·685	·800	·889	·792	·729	·790	·811‡‡	·806§§	·753‡‡	·817	·811	·936	·705
October	·733	·759	·712	·728	·711	·722	·717	·694	·800	·847‡‡	·811‖‖	·742‡‡	·659	·662*	·731*	·584*
November	·769	·784	·754	·769	·629	·654	·643	·590	·764	·794‡‡	·797‡‡	·702‡‡	·531	·512	·607†	·475
December	·784	·804	·755	·792	·621	·657	·614	·593	·811	·842‖‖	·834††	·756‖	·398	·405	·448*	·342
Year	·760	·784	·740	·756	·713	·756	·703	·681	...	...	...	...	·606	·617	·668	·533

* Mean of 27 days. § Mean of 30 days.
† „ „ 23 „ ‖ „ „ 21 „
‡ „ „ 22 „ ¶ „ „ 20 „

** Mean of 24 days.
†† „ „ 25 „
‡‡ „ „ 20 „
§§ „ „ 26 „
‖‖ „ „ 28 „

Month.	5. Quetta. Mean.	10 hours.	16 hours.	From Minima.	6. Leh. Mean.	6 hours.	10 hours.	16 hours.	22 hours.	From Minima.	7. Mooltan. Mean.	10 hours.	16 hours.	From Minima.	8. Dera Ismail Khan. Mean.	10 hours.	16 hours.	From Minima.
January	·164	·172	·182	·138	·065	...	·071	·079	...	·046	·254	·259	·271	·232	·247	·260	·272	·208
February	·137	·144	·136	·131*	·067	...	·072	·082	...	·047	·209	·220	·199	·208	·174	·184	·172	·165
March	·180	·191	·167	·183	·083	...	·091	·091	...	·066	·330	·318	·344	·327	·288	·308	·285	·272
April	·267	·291	·267	·244†	·110	...	·119	·110	...	·100	·481	·412	·540	·492	·453	·460	·462	·438
May	·282	·308	·263‡	·275‡	·126	...	·138	·116	...	·123	·620	·552	·699	·610	·441	·447	·437	·439
June	·293	·313	·258	·309	·150	...	·175	·147	...	·127	·792	·700	·815	·862	·581	603	·538	·601
July	·418	·412	·379	·463‡	·229	...	·268	·250	...	·168	·886	·856	·964	·838	·848	·891	·825	·827
August	·268	·266‡	·239	·299	·245	...	·275	·269	...	·192	·866	·834	·987	·777	·764	·827	·717	·749
September	·213	·231§	·198‖	·210§	·193	·180	·217	·192	·181	·167†	·811	·775	·908	·749	·715	·756	·678	·711
October	·152	·169	·146	·141	·113	·109‡	·111	·117	·114	·096‡	·377	·425	·321‡	·384	·384	·394	·414	·344
November	·125	·139	·118	·117	·082	·071¶	·082**	·099**	·075††	·075‡‡	·298	·288	·368††	·238	·277	·301	·289	·240
December	·132	·126	·138	·131	·067	·051†	·062‡	·094‡	·062‡	·054*	·224	·228	·275	·168	·221	·225	·253	·186
Year	·219	·230	·208	·220	·128		·140	·137	...	·105	·512	·489	·558	·490	·449	·471	·445	·432

* Mean of 27 days. § Mean of 23 days. ¶ Mean of 26 days. †† Mean of 25 days.
† „ „ 29 „ ‖ „ „ 22 „ ** „ „ 24 „ ‡‡ „ „ 21 „
‡ „ „ 30 „

Month.	9. Peshawar				10. Murree.				11. Rawalpindi.				12. Sialkot.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·222	·237	·227	·202	·153	·152	·174	·132	·285	·295	·332	·228	·295	·307	·319	·258
February	·191	·198	·183	·193	·156	·163	·172	·132	·267	·282	·289	·229	·273	·297	·280	·242
March	·281	·303	·270	·269	·193	·214	·218	·147	·352	·388	·377†	·292	·349	·378	·343	·325
April	·422	·428	·433	·405	·292	·321	·329	·227	·451	·489†	·476‡	·389†	·384	·399	·349	·404
May	·364	·376	·348	·367	·261	·289	·284	·209*	·524	·590	·593	·390	·379	·394	·353	·389§
June	·478	·518	·458	·458	·373	·401	·395	·323	·708	·798	·799	·528	?	·585	·523	?
July	·736	·774	·697	·736	·529	·560	·569	·458	·815	·861	·849	·736	·753	·862	·821	·577*
August	·697	·743	·675	·672	·523	·564	·552	·454	·831	·896	·867	·729	·761	·804	·805	·673‖
September	·614	·646	·592	·604	·423	·451	·465	·354	·642	·672	·648	·606	?	·795	·769	?
October	·319	·337	·317	·304	·213	·218	·237†	·184	·396	·434	·423†	·331	?	·367	·331	?
November	·266	·285	·298	·215	·148	·151	·174	·119	·340	·361†	·416	·243	?	·344	·301	?
December	·221	·233	·247	·182	·130	·120	·157*	·113	·227	·251†	·241†	·188†	?	·274	·250	?
Year	·401	·423	·395	·384	·283	·300	·311	·238	·487	·526	·526	·407	?	·484	·454	?

* Mean of 30 days.
† „ „ 29 „
‡ Mean of 28 days.
§ Mean of 22 days.
‖ „ „ 23 „

Month.	13. Lahore.						14. Ludhiana.				15. Kailang.				16. Simla.			
	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hour.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·281	·259	·302	·276	·286	·247	·281	·303	·303	·236	...	...	...	...	·143	·153	·166	·110
February	·239	·225	·266	·209	·255	·225	·256	·276	·260	·231	...	...	...	...	·138	·148	·170	·095
March	·332	·320	·369	·292	·345	·313	·360	·365	·373	·343	...	...	...	...	·157	·162	·201	·109
April	·411	·398	·422	·377	·448	·432	·475	·408	·436	·582	...	...	...	...	·207	·228	·246	·146
May	·420	·423	·440	·391	·426	·443	·610	·546	·588*	·696	...	...	...	...	·292	·312§	·316§	·249‖
June	·606	·633	·613	·528	·648	·615	?	·730	·730†	?	...	...	...	...	·432	·451	·452	·393
July	·818	·842	·837	·760	·831	·819	·875	·873	·867	·885	?	·351*	·303*	?	·540	·563	·586	·471
August	·764	·783	·778	·709	·787	·809	·803	·793	·780	·836‡	?	·360	·294	?	·500	·523	·547	·431
September	·768	·752	·783	·737	·801	·720	·768	·782	·752	·771	?	·275	·232	?	·463	·480	·496	·414
October	·425	·404	·433	·406	·456	·394	·399	·412	·364	·420	?	·141	·116	?	·204	·220	·204	·188
November	·324	·299	·342	·322	·332	·283	·317	·333	·306	·311	?	·093	·089	?	·167	·169	·197	·136
December	·251	·223	·262	·259	·258	·220	·235	·247	·227	·230	?	·072	·083	?	·126	·127	134	·118
Year	·470	·463	·487	·439	·489	·460	?	·506	·499	?	...	...	...	...	·218	·295	·310	·238

* Mean of 30 days.
† „ „ 29 „
‡ „ „ 24 „
§ Mean of 26 days.
‖ „ „ 28 „

17. DELHI. 18. SIRSA. 19. CHAKRATA. 20. MUSSOOREE.

MONTH.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·294	·314	·299	·268*	·267	·294	·294	·212	·159	·165	·173	·140	·180	·182*	·205†	·152*
February	·219	·239	·212	·205	·203	·228	·187	·194	·146	·146	·166	·125	·169	·166‡	·206‡	·135‡
March	·340	·364	·320	·336	·347	·380	·359	·303	·187	·186	·201	·173	·212	·220*	·239§	178*
April	·355	·375	·318	·371	·434	·500	·425†	·376	·227	·236	·240	·205	·238	·265‖	·219¶	·230‖
May	·398	·416	·361	·416	·482	·533	·484	·429	·253	·248	·228	·282	·326	·327*	·361	·289*
June	·683	·710	·628	·712	·551	·520	·502	·631	·439	·464	·481	·373	·546	·585††	·586	·468§
July	·846	·877	·820	·840	·789	·823	·766	·778	·555	·586	·604	·476	·632	·665**	·671††	·556¶
August	·726	·736	·711	·730	·671	·708	·616	·690	·517	·545	·572	·434	·589	·630*	·621	·517*
September	·735	·783	·714	·708	·701	·747	·653	·702	·495	·532	·543	·409	·561	·593††	·614†	·475†
October	·387	·411	·366	·385	·358	·395	·316	·363	·225	·233	·251	·190	·308	·330††	·344§	·251††
November	·273	·285	·293	·242	·238	·282	·204	·228	·189	·193	·214	·160	·242	·248†	·276‡‡	·201†
December	·197	·209	·203	·179	·186	·208	·182	·169	·140	·139	·158	·122	?	Imperfect.		
Year	·454	·477	·437	·449	·436	·468	·416	·423	·294	·306	·319	·257	?	?	?	?

* Mean of 30 days. † Mean of 29 days.

* Mean of 29 days. ¶ Mean of 20 days.
† „ „ 26 „ ** „ „ 30 „
‡ „ „ 25 „ †† „ „ 27 „
§ „ „ 28 „ ‡‡ „ „ 21 „
‖ „ „ 22 „

21. DEHRA (S. G. O.) 22. DEHRA (FOREST SCHOOL). 23. PAORI. 24. ROORKEE.

MONTH.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	...	·256	·240		·249	·263	·266	·217	·191	·211	·188	·173	·252	·294	·268	·194
February	...	·247	·229		·244	·258	·257	·217	·183	·209	·176	·165	·255	·293	·222	·250
March	...	·332	·290		·298	·328	·272	·294	·236	·280*	·211*	·217	?	·378	·305	?
April	...	·365	·318		·352	·358	·319	·380	·283	·350	·231	·268	·327	·399	·301	·280†
May	...	·376	·345		·376	·354	·337	·436	·325	·375	·304	·295	·354	·426	·336	·299
June	...	·716	·712		·678	·694	·679	·662	·534	·586	·517	·500	·690	·767	·704	·600
July	...	·856	·901		·829	·828	·874	·784	·660	·692	·671*	·617	·866	·916	·930	·751
August	...	·825	·850		·787	·805	·825	·731	·618	·670*	·618	·566*	·793	·856	·834	·690
September	...	·765	·804		·736	·759	·785	·665	·586	·638	·584	·536†	·777	·872	·811	·649
October	...	·435	·414		·372	·391	·357	·369	·302	·368†	·262*	·275†	·393	·446	·414	·319
November	...	·360	·354		·314	·326	·318	·299	·257	·298	·254	·219	·310	·368	·333	·229
December	...	·262	·273		·234	·246	·252	·203	Abolished.				·224	·275	·248	·148*
Year	...	·483	·478		·456	·468	·462	·438	...	...	...	...	?	·524	·476	?

Wet minimum observation not recorded.

* Mean of 30 days.
† „ „ 29 „

Month.	25. Ranikhet. Mean.	10 hours.	16 hours.	From Minima.	26. Pithoragarh. Mean.	10 hours.	16 hours.	From Minima.	27. Meerut. Mean.	10 hours.	16 hours.	From Minima.	28. Bareilly. Mean.	10 hours.	16 hours.	From Minima.	29. Agra Mean.	10 hours.	16 hours.	From Minima.
January	·174	·186	·192	·145	·200	·227	·187	·185	·285	·315	·286	·253	·305	·333	·301	·281	·309	·310	·312	·305
February	·151	·167	·168	·119	·193	·222†	·180	·176†	·236	·272	·220	·216	·279	·312	·271	·253	·243	·245	·217	·267
March	·204	·223	·220	·170	·243	·280	·224	·226	·331	·376	·316	·300	·405	·452	·398	·365	·312	·325	·264	·348
April	·265	·286	·271	·238	·280	·315	·264	·260	·357	·390	·358	·322	·435	·466	·432	·406	·327	·344	·262	·376
May	·293	·304	·319	·257	·322	·347	·322	·297	·392	·436‡	·456‖	·285‖	·552	·627	·532	·496	·371	·387	·309	·416
June	·505	·527	·539	·450	·567	·601	·592	·508	·632	·667	·638	·590	·826	·858	·814	·806	·643	·661	·575	·694
July	·573	·601	·615	·504*	·645	·679	·671	·585	·835	·864	·888	·754	·894	·910	·918	·853	·877	·898	·868	·874
August	·546	·562	·589	·487	·615	·652	·634	·558	·738	·758	·772	·685	·874	·894	·896	·831	·780	·791	·756	·793
September	·535	·557	·581	·468	·581	·621	·598	·523	·698	·740	·715	·640	·825	·886	·787	·802	·745	·763	·690	·781
October	·277	·291	·307	·233	·323	·371	·289	·308§	·391	·430	·363	·379	·434	·468	·378	·457	·360	·373	·297	·411
November	·219	·232	·243	·181	·239	·275‡	·225‡	·216‡	·295	·317	·295	·273	·323	·353	·318	·297	·248	·252	·220	·272
December	·165	·180	·195	·121	·179	·205§	·172§	·161	·219	·228	·203	·226	·243	·263	·257	·208	·214	·225	·206	·210
Year	·326	·343	·353	·281	·366	·400	·363	·334	·451	·483	·459	·410	·533	·569	·525	·505	·452	·465	·415	·479

* Mean of 30 days. † Mean of 27 days. ‡ ,, ,, 29 ,, § ,, ,, 30 ,, ‖ Mean of 28 days.

Month.	30. Lucknow. Mean.	10 hours.	16 hours.	From Minima.	31. Gorakhpur. Mean.	10 hours.	16 hours.	From Minima.	32. Jhansi. Mean.	10 hours.	16 hours.	From Minima.	33. Allahabad. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.
January	·309	·330	·310	·287	?	·386	·367	Imperfect.	·320	·342	·323	·295	·381	·361	·381	·388	·392	·331
February	·252	·266	·229	·261	·328	·368	·347	·268	·246	·254	·217	·268	·298	·297	·288	·281	·325	·296
March	·325	·337	·277	·360	·409	·446	·408	·372	·349	·352	·313	·383	·343	·364	·346	·305	·355	·371
April	·463	·489	·479	·422	·505	·554	·487	·473	·332	·303	·300	·394	·393	·407	·418	·343	·404	·396
May	·628	·698	·627	·558	·694	·751	·656	·676	·478	·440	·425	·568	·497	·534	·515	·422	·515	·519
June	·779	·782	·760	·795	·869	·898	·879	·829	·691	·643	·653	·776	·786	·805	807	·743	·790	·793
July	·916	·932	·924	·891	·981	1·004	1·004	·935	·834	·837	·844	·820	·944	·933	·951	·931	·962†	·894
August	·869	·856	·879	·871	·968	·974	·988	·943	·793	·780	·787	·812	·914	·899†	·923	·907	·925	·880
September	·848	·872	·817	·855	·947	·970	·945	·925	·790	·776	·774	·821	·924	·918	·940	·912	·925	·885
October	·485	·513	·437	·504	·618	·661	·559	·635	·472	·425	·424	·568	·569	·587	·582	·526	·580	·573
November	·317	·323	·315	·314	·394	·429	·378	·376	·245	·222*	·232*	·280	·355	·361	·341	·346	·370	·367
December	·252	·266	·261	·229	·319	·352	·345	·261	·207	·215	·196	·209	·287	·276	·275	·293	·303	·263
Year	·537	·555	·526	·529	?	·649	·614	?	·480	·466	·457	·516	·558	·562	·564	·533	·571	·548

* Mean of 29 days. † Mean of 30 days.

Month.	34. Benares. Mean.	10 hours.	16 hours.	From Minima.	35. Ghazipur. Mean.	10 hours.	16 hours.	From Minima.	36. Katmandu. Mean.	10 hours.	16 hours.	From Minima.	37. Sibsagar. Mean.	10 hours.	16 hours.	From Minima.	38. Dhubri. Mean.	10 hours.	16 hours.	From Minima.
January	·347	·376	·341	·323*	...	·368	·331	Wet Minimum not recorded.	·266	·301	·296	·200	·421	·455	·454	·353*	·452	·475	·478	402
February	·257	264	·225	·283	...	·283	·235		·239	·253	·276	·188	·440	·483	·453	·384	·368	·395	·343	·367
March	·311	·321	·258*	·353	...	·319	·248		·297	316	·317	·257	·529	·563	·544	·479	·451	·470	·416	·466
April	·401	·421	·319	·463	...	·362	·307		·376	·397	·398	·332	·670	·693	·704	·613	·642	·684	·620	·623
May	·522	·563	·401	·601	...	·588*	·428		·557	·568	·654	·449	·810	·845	·838	·748	·779	·793	·822	·722
June	·795	·820	·756	·810	...	·819	·779		·649	·667	·703	·577	·929	·957	·957	·872	·920	·935	·937	·888
July	·908	·924	·909	·892	...	·945	·920		·694	·718	·736	·627	·949	·970	·972	·906	·950	·968	·970	·912
August	·882	·899	·875	·872	...	·919	·898		·680	·695	·718	·627	·948	·969	·970	·906	·940	·961	·959	·900
September	·876	·910	·853	·866	...	·930	·938		·623	·621	·654	·593	·926	·967	·945	·865	·907	·926	·929	·865
October	·518	·552	·457	·546	...	·678	·721		·439	·465	·473	·378	·779	·824	·803	·711	·758	·780	·765*	·728
November	·344	·345	·333	·353	...	·370	·357		·305	·334	·355	·225	·561	·599	·586	·497	·541	·560	·553	·511
December	·254	·271	·251	·241	...	·286	·295		·208	·224	·249	·150	·438	·482	·467	·364	·442	·467	·456	·403
Year	·535	·556	·498	·550	...	·572	·538		·444	·463	·486	·384	·700	·734	·724	·642	·679	·701	·687	·649

* Mean of 30 days.

Month.	39. Silchar. Mean.	10 hours.	16 hours.	From Minima.	40. Darjeeling. (*St. Paul's School*). Mean.	10 hours.	16 hours.	From Minima.	41. Purneah. Mean.	10 hours.	16 hours.	From Minima.	42. Durbhunga. Mean.	10 hours.	16 hours.	From Minima.
January	·419	·477	·419	·362	·207	·217	·227††	·178‖	·372	·418††	·375	·323††	·418	·444	·425	·386
February	·403	·460	·372	·377	·213	·233	·237†	·169*	?	·341‡‡	Imperfect.	·319‡‡	·352	·382	·341	·333
March	·587	·620	·578	·563	?	·265††	·276‖	?	·372	·406	·317	·394	·431	·454	·417††	·422
April	·701	·725	·731	·647	?	·351§	·374†	?	·547	·599	·491	·552	·595	·609	·579	·597
May	·779	·807	·791	·738	?	·437††	·437‡	?	·807	·831	·814	·775	·814	·833	·832	·778
June	·922	·941	·941	·883	?	·508	·530§	?	·895	·920	·902	·863	·907	·928	·906	·888
July	·946	·960	·979	·899	·525	·557	·565††	·453§	·991	1·022	1·008	·944	1·004	1·019	1 027	·967
August	·932	·948	·967	·882	·506	·533	·535	·450	·968	·999**	·992**	·914**	1·016	1 045	1·075	·929
September	·919	·933	·941	·882	·487	·512	·517†	·431	·953	·980	·972	·906	1·012	1·041	1·076	·919
October	·807	·851	·827	·743	·399	·414†	·464¶	·318†	·732	·782	·731	·682	·769	·807	·777	·724
November	·621	·666	·641	·555	·258	·273**	·288**	·212‡	·456	·487	·475	·406	·465	·494	·470	·432**
December	·480	·518	·497	·425	·191	·193	·217	·163	·346	·381	·377	·281	·371	·391	·401	·320
Year	·710	·742	·724	·663	?	·374	·389	?	?	·681	?	·613	680	·704	·694	·641

* Mean of 21 days.
† " " 27 "
‡ " " 25 "
§ " " 28 "
‖ Mean of 26 days.
¶ " " 23 "
** " " 29 "
†† Mean of 30 days.
‡‡ " " 19 "

Month.	43. Patna.				44. Gya.				45. Hazaribagh.				46. Berhampore.				47. Burdwan.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·372	·406	·377	·333	·340	·369	·319	·333	·296	·303	·291	·296	·398	·439	·383	·372	·375	·387	·350	·389
February	·310	·344	·298	·288	·256	·273	·225	·269	·224	·216	·221	·229	·324	·338	·302	·331	·353	·337	·328	·395
March	·355	·373	·322	·369	·294	·309	·258	·315	·343	·314*	·300	·325	·434	·461	·387	·453	·492	·508	·422	·546
April	·455	·488	·401	·476	·340	·343	·273	·405	·316	·312	·274	·353	·615	·718	·559	·567	·632	·713	·513	·669
May	·688	·733	·601	·729	·556	·597	·451	·620	·448	·433	·356	·501	·885	·959	·903	·794	·874	·901	·867	·854
June	·848	·866	·828	·850	·819	·853	·812	·791	·740	·716	·719	·747	·935	·983	·939	·883	·905	·926	·899	·890
July	·953	·957	·962	·939	·924	·942	·949	·881*	·828	·819	·828	·797	·971	·990	1·000	·923	·943	·942	·956	·930
August	·947	·956	·962	·923	·913	·934	·937	·869	·798	·793	·803	·774	·947	·949	·976	·915	·915	·933	·915	·898
September	·939	·956	·947	·914	·894	·935	·882	·865	·786	·793	·771	·770	·941	·967	·941	·914	·928	·933	·920	·930
October	·622	·641	·565	·659	·545	·578	·508	·550	·443	·449	·418	·453	·756	·803	·722	·744	·712	·725	·649	·763
November	·390	·412	·376	·382	·375	·383	·351	·392	·303	·310	·297	·306	·474	·499	·467	·456	·430	·429	·409	·453
December	·308	·325	·324	·276	·254	·277	·239	·247	·229	·243	·218	·224	·382	·403	·402	·340	·347	·350	·343	·348
Year	·599	·622	·580	·595	·543	·566	·517	·545	·480	·475	·458	·481	·672	·709	·665	·641	·659	·674	·631	·671

* Mean of 30 days.

Month.	48. Jessore.				49. Dacca.				50. Chittagong.				51. Calcutta (Chowringhee).			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·397	·452	·392	·348	·427	·480	·425	·376*	·439	·497	·446	·374	·452	·449	·417	·426
February	·376	·399	·365	·364	·398	·416	·396	·381†	·423	·441	·435	·389	·464	·455	·421	·432
March	·557	·633	·490	·547	·609	·658	·553	·615	·684	·714	·701	·638	·656	·669	·547	·626
April	·739	·810	·731	·675	·780	·831*	·761	·748*	·791	·813	·826	·734	·838	·863	·807	·759
May	·921	·974	·956	·833	·940	1·000	1·000	·820	·879	·893	·940	·804	·957	·969	·944	·880
June	·963	1·009	·982	·898	·972	1·007	·982	·926	·888	·915	·925	·824*	·972	·985	·963	·892
July	·978	1·002	1·003	·930	·971	1·008	1·012	·894	·912	·928	·945	·863§	·986	·993	·994	·927
August	·977	1·003	·994	·933	·984	1·013	1·007	·932	?	·921	·928	?	·968	·976	·983	·918
September	·964	·997	·967	·928	·966	·988	·971	·940	?	·934	·933	?	·976	·974	·970	·940
October	·811	·852	·810	·770	·849	·887	·839	·822	?	·899	·886	?	·833	·867	·787	·788
November	·498	·529	·507	·457	·579	·611	·591	·535	?	·727	·711	?	·523	·519	·486	·487
December	·422	·454	·437‡	·375	·479	·516‡	·506	·414	?	·590	·568	?	·428	·421	·414	·389
Year	·717	·760	·720	·672	·746	·785	·754	·700	?	·773	·770	?	·754	·757	·728	·705

* Mean of 29 days.
† „ „ 26 „
‡ Mean of 30 days.
§ „ „ 25 „

Month.	52. Calcutta (Alipore.)						53. Saugor Island.						54. Cuttack.				55. False Point.			
	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·415	·407	·422	·366	·445	·384	·479	·456	·502	·480	·477	·420*	·483	·511	·458	·479	·541	·559	·553*	·510
February	·447	·455	·423	·371	·486	·430††	·549	·532	·539	·565†	·558	·446†	·533	·564	·502	·532	·616	·641	·626†	·582
March	·659	·669	·644	·525	·735	·600	·778	·744	·791	·798	·780	·699	·671	·700	·594	·720	·822	·844	·858	·764
April	·840	·843	·949	·924	·858	·746	·910	·883	·938	·944	·874	·848‡	·786	·777	·727	·853	·926	·953	·968	·856
May	·944	·929	·937	·908	·922	·858	·987	·959	1·016	1·016	·958	·955	·866	·881	·826	·890	·981	1·018	1·028	·896
June	·960	·941	·955	·938	·923	·856	·974	·955	·980	1·004	·956	·855‡	·894	·902	·893	·883	·943	·959	·984	·885
July	·972	·940	·967	·968	·958	·900	·974	·937	·983	·998	·977	·925‡	·903	·896	·928	·884	·933	·940	·960	·899*
August	·964	·934	·950	·954	·942	·893	·967	·938	·982	1·002	·947	·926	·920	·927	·949	·883	·928	·951	·958	·875
September	·968	·944	·948	·946	·953	·915	·965	·941	·986	·987	·946	·934	·925	·940	·943	·892	·936	·943	·961	·903
October	·819	·792	·787	·748	·821	·776	·828	·803	·845	·840	·822	·784	·807	·828	·802	·790	·830	·854	·814	·823
November	·510	·476	·476	·434	·521	·476	·544	·537	·568	·520	·552	·490	·554	·554	·581	·528	·560	·585	·551	·543
December	·405	·382	·391	·375	·431	·371	·449	·434	·466	·444	·450	·394	·411	·422	·416*	·396	·431	·459	·441	·393
Year	·742	·726	·737	·705	·750	·684	·784	·760	·800	·800	·775	·723	·729	·427	·718	·728	·787	·809	·809	·744

* Mean of 30 days. ‡ Mean of 29 days.
† „ „ 27 „ †† „ „ 26 „

Month.	56. Sambalpur.				57. Sambalpur (*New Observatory*).				58. Raipur.				59. Nagpur.				60. Seoni.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·467	·500	·483	·419					·359	·373	·335	·369	·374	·398	·351	·373	·347	·368	·338	·335
February	·458	·476	·460	·439					·328	·314	·319	·351	·295	·283	·288	·314	·275	·282	·275	·269
March	·631	·664	·689	·540					·409	·411	·361	·454	·298	·309	·261	·325	·295	·325	·274	·286
April	·558	·598	·549	·526					?	Imperfect.		·389	·328	·311	·292	·382	·346	·363	·352	·323
May	·734	·768	·651	·782	Observatory opened on 16th October.				·404	·402	·351	·460	·403	·404	·363	·441	·378	·389	·353	·393
June	·858	·878	·858	·837					·757	·775	·747	·749	·754	·757	·716	·790	·697	·720	·685	·687
July	·908	·936	·940	·849					·811	·829	·833	·772	·808	·808	·800	·815	·747	·759	·766	·716
August	·930	·958	·975	·856					·815	·833	·811	·801	·762	·763	·741	·781	·731	·743	·748	·701
September	·921	·940	·968	·855					·807	·825	·824	·771	·800	·800	·807	·793	716	·734	·711	·703
October	·755	·790	·941	·734	Imperfect.				·647	·655	·628	·658	·609	·633	·562	·633	·516	·520	·505	·523
November	·491	·523	·471	·480	·479	·511	·457	·468	·416	·438	·383	·428	·383	·400	·347	·403	·302	·307	·285	·314
December	·365	·395	·371	·329	·349	·381	·351*	·314	·241	·254	·205	·264	·232	·235	·218	·244	·191	·185	·182	·207
Year	·673	·702	·680	·637	?	?	?	?	?	?	?	·539	·504	·508	·479	·524	·462	·475	·456	·455

* Mean of 30 days.

Month.	61. Jubbulpore. Mean.	10 hours.	16 hours.	From Minima.	62. Saugor. Mean.	10 hours.	16 hours.	From Minima.	63. Pachmarhi. Mean.	10 hours.	16 hours.	From Minima.	64. Hoshangabad. Mean.	10 hours.	16 hours.	From Minima.
January	.357	.361	.397	.313	.323	.346	.319	.303	.274	.273	.280	.268	.349	.376	.352	.320
February	.265	.265	.265	.265	.231	.231	.229	.233	.223	.218	.221	.231	.259	.260	.280	.237
March	.279	.303	.253	.281*	.292	.297	.281	.299	.229	.226	.213	.247	.278	.285	.284	.264
April	.259	.258	.244	.274	.291	.281	.265	.328	.221	.200	.195	.268	.272	.279	.271	.267
May	.377	.400	.347	.385†	.677	.713	.754	.564	.353	.362	.322	.374	.443	.483	.414	.433
June	.705	.738	.671	.705*	.707	.710	.690	.721	.640	.661	.630	.628	.756	.798	.728	.743
July	.812	.822	.828	.786‡	.795	.816	.802	.766	.680	.694	.705	.641	.827	.848	.849	.785
August	.779	.798	.783	.757	.758	.780	.768	.725	.672	.687	.704	.625	.795	.822	.820	.743
Sepetmber	.806	.837	.803	.779	.797	.817	.835	.739	.674	.698	.704	.621	.818	.839	.854	.760
October	.562	.605	.526	.555	?	?	?	?	.465	.476	.487	.432	.607	.648	.589	.584
November	.335	.369	.319	.317	?	?	?	?	.282	.287	.302	.257	.369	.393	.389	.325
December	.213	.232	.203	.204	?	?	?	?	.173	.169	.187	.162	.241	.255	.264	.205
Year	.479	.499	.470	.468	?	?	?	?	.407	.413	.413	.396	.501	.524	.508	.478

* Mean of 29 days.
† ,, ,, 28 ,,
‡ ,, ,, 30 ,,

Month.	65. Khandwa. Mean.	10 hours.	16 hours.	From Minima.	66. Chanda. Mean.	10 hours.	16 hours.	From Minima.	67. Sironcha. Mean.	10 hours.	16 hours.	From Minima.	68. Chikalda. Mean.	10 hours.	16 hours.	From Minima.
January	.308	.314	.292	.319	.400	.437	.364	.398	.469	.524	.435	.449	.299	.308	.294	.296
February	.241	.239	.226	.257	.368	.396	.318	.391	.453	.485	.391	.484	.277	.294	.291	.245
March	.269	.263	.240	.305	.407	.418	.332	.471	.562	.614	.482	.591	.256	.265	.259	.245
April	.312	.291	.257	.388	.349	.375	.290	.382	.521	.592	.400	.572	.238	.240	.222	.252
May	.499	.522	.398	.576	.399	.426	.369	.402	.572	.628	.459	.630	.386	.422	.344	.391
June	.740	.767	.698	.756	.780	.789	.760	.792	.807	.827	.798	.795	.643	.669	.656	.605
July	.785	.800	.791	.765	.786	.782	.782	.795	.840	.848	.855	.816	.659	.667	.692	.618
August	.746	.754	.746	.739	.795	.783	.800	.801	.846	.856	.859	.822	.642	.657	.669	.599
September	.758	.773	.774	.727	.801	.803	.814	.787	.842	.854	.860	.813	.643	.673	.660	.596
October	.603	.627	.569	.612	.721	.745	.737	.682	.758	.785	.747	.741	.502	.521	.531	.454
November	.312	.329	.289	.318	.499	.527	.527	.444	.520	.574	.489	.497	.340	.349	.362	.308
December	.200	.214	.184	.203	.313	.341	.309	.288*	.373	.396	.371	.351	.212	.206	.226	.204
Year	.481	.491	.455	.496	.552	.569	.533	.553	.630	.665	.596	.630	.425	.439	.434	.401

* Mean of 29 days.

Month.	69. Buldana.				70. Akola.				71. Amraoti.				72. Neemuch.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	Untrustworthy.				·311	·349	·297	·288	·319	·358	·308	·290	·257	·263	·245	·263
February	Ditto.				·243	·248	·254	·226	·334	·358	·377	·267	·202	·200	·206	·199
March	Ditto.				·250	·249	·233	·267	·343	·393	·377	·260	·242	·207	·219	·300
April	Ditto.				·232	·243	·192	·262	·334	·365	·314	·322	·247	·179	·255	·308
May	Ditto.				·389	·437	·298	·433	·379	·419	·312	·406	·336	·268	·303	·436
June	·755	·781	·817	·668	·749	·781	·720	·745	·743	·781	·704	·743	·609	·584	·570	·674
July	·730	·743	·777	·670	·772	·783	·789	·744	·772	·797	·782	·737	·773	·763	·788	·767
August	·689	·706	·718	·642	·716	·740	·705	·703	·722	·757	·709	·699	·709	·697	·704	·727
September	·711	·719	·769	·645	·760	·778	·779	·723	·765	·794	·778	·723	·756	·756	·775	·736
October	·646	·668	·709	·560	·647	·685	·629	·627	·606	·640	·587	·590	·488	·463	·506	·495
November	·446	·460	·514	·366	·387	·409	·375	·376	·365	·384	·347	·363	·198	·159	·180	·254
December	·313	·332	·372	·235	·228	·246	·216	·222	·216	·217	·217	·214	·177	·172	·173	·185
Year	?	?	?	?	·474	·496	·457	·468	·492	·522	·484	·468	·416	·393	·410	·445

Month.	73. Nowgong.				74. Sutna.				75. Indore.				76. Bickaneer.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·338	·360	·332	·323	·307	·328	·301	·292	·288	·286	·291	·287	·173	·132	·192	·196
February	·279	·298	·279	·261	·205	·207	·172	·235	·209	·216	·212	·199	·168	·108	·199	·196
March	Imperfect.				·244	·240	·192	·301	·247	·255	·231	·255	·299	·263	·343	·292
April	?	?	?	·497	·224	·211	·169	·291	·238	·224	·228	·262	·450	·420	·492	·439
May	?	?	?	·568*	·327	·326	·277	·377	·420	·441	·371	·448	·555	·555	·614	·496
June	·782	·824	·786	·736	·640	·667	·600	·654	·710	·757	·706	·667	·739	·733	·752	·731
July	·864	·889	·868	·836†	·812	·825	·817	·795‡	·755	·777	·770	·718	·803	·798	·810	·802
August	·812	842	·804	·791	·779	·792	·788	·756	·718	·743	·732	·680	·728	·717	·721	·746
September	·821	·842	·804‡	·818	·808	·835	·810	·778	·741	·761	·779	·683	·733	·724	·743	·731
October	·508	·544	·466	·515	·481	·500	·433	·510	·572	·521	·543	·653	·414	·379	·423	·441
November	·295	·300§	·288§	·296	·256	·262	·234	·272	·292	·298	·290	·289	·255	·232	·261	·272
December	·223	·234	·228	·206	·177	·192	·156	·183	·209	·204	·213	·210	·156	·114	·167	·187
Year	?	?	?	?	·438	·449	·412	·454	·450	·457	·447	·446	·456	·431	·476	·461

* Mean of 25 days. ‡ Mean of 29 days.
† „ „ 30 „ § „ „ 28 „

TABLE XI.—TENSION OF ATMOSPHERIC VAPOUR IN 1883.

77. JEYPORE.

Month.	Mean.	4 hours	10 hours.	16 hours.	22 hours.	From Minima.
January	·327	·292	·342	·359	·313	·211
February	·241	·222	·240	·248	·252	·135
March	·324	·305	·344	·316	·331	·191
April	·317	·314	·342	·283	·330	·180
May	·501	·484	·551	·490	·480	·271
June	·739	·725	·750	·718	·761	·469
July	·803	·797	·811	·796	·806	·541
August	·689	·703	·700	·661	·690	·435
September	·723	·713	·756	·691	·732	·688
October	·383	·386	·405	·346	·395	·393
November	·254	·242	·267	·250	·255	·221
December	·224	·198	·237	·245	·217	·185
Year	·460	·448	·479	·450	·463	·326

78. SAMBHAR.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	·271	·310	·287	·215
February	·271	·305	·338	·171
March	·279	·301	·272	·263
April	·313	·322*	·266*	·350†
May	?	?	?	·467
June	?	Imperfect.		·672
July	·788	·812	·787	·766‡
August	·667	·700	·617	·685
September	·695	·740	·655	·691
October	?	Imperfect.		·356
November	?	Ditto.		·173
December	·198	·224	·243	·128
Year	?	?	?	·411

79. AJMERE.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	·276	·297	·310	·222
February	·206	·210	·231	·176
March	·304	·319	·323	·269
April	·350	·368	·351	·330
May	·549	·537	·491	·591
June	·691	·716	·692	·664
July	·802	·801	·818	·786
August	·726	·737	·734	·708
September	·740	·779	·758	·682
October	·432	·484	·470	·341
November	·289	·314	·359	·194
December	·237	·275	·287	·148
Year	·466	·486	·485	·426

80. MT. ABU.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	·203	·186	·199	·224
February	·159	·144	·161	·171
March	·230	·220	·227	·244
April	·295	·285	·300	·300
May	·330	·291	·361	·338
June	·563	·537	·568	·584
July	·598	·579	·618	·596
August	·538	·530	·549	·534
September	·572	·547	·602	·566
October	·384	·357	·385	·409
November	·219	·192	·207	·257
December	·181	·160	·176	·208
Year	·356	·336	·363	·369

* Mean of 20 days.
† " " 26 "
‡ " " 30 "

81. PACHBUDRA.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	·198	·203	·202	·190
February	·125	·109	·089	·177
March	·342	·324	·444	·259
April	·367	·339	·433	·330
May	·594	·610	·586	·585
June	·742	·756	·711	·760
July	·777	·777	·754	·800
August	·661	·678	·576	·730
September	·722	·747	·674	·744
October	·395	·416	·318	·452
November	·202	·225*	·175*	·207*
December	·148	·148	·136	·161
Year	·439	·444	·425	·450

82. JACOBABAD.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	·215	·225	·244	·175
February	·146	·149	·154	·136
March	·253	·264	·262	·234
April	·381	·412	·382	·349
May	·427	·444	·419	·418
June	·666	·743	·615	·640
July	·865	·938	·859	·799
August	·752	·804	·777	·674
September	·693	·755†	·677†	·646†
October	·368	·385	·421	·298
November	·241	·248	·288	·188
December	·232	·246	·272	·177
Year	·437	·468	·448	·395

83. HYDERABAD.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	·257	·267	·264	·241
February	·198	·201‡	·185‡	·208
March	·313	·314	·262	·363
April	·555	·555	·537	·573
May	·617	·580	·560	·711
June	?	·629	·643	Imperfect.
July	·815	·782	·805	·859*
August	·723	·762	·684	·724
September	·740	·745	·723	·753
October	·576	·616	·598	·515
November	·402	·437	·466	·303
December	·252	·240	·279	·238
Year	?	·511	·501	?

84. KURRACHEE.

Month.	Mean	10 hours.	16 hours.	From Minima.
January	·353	·339	·380	·268
February	·418	·393	·452	·303
March	·609	·564	·617	·493
April	·842	·825	·871	·725
May	·964	·916	·979	·868
June	1·019	·992	1·038	·963
July	·913	·918	·928	·871
August	·825	·823	·852	·788
September	·823	·812	·839	·796
October	·609	·582	·731	·556
November	·354	·351	·448	·270
December	·297	·259	·337	·225
Year	·669	·648	·706	·594

* Mean of 29 days. † Mean of 28 days. ‡ Mean of 27 days.

85. BHUJ. 86. RAJKOT. 87. DEESA. 88. SURAT.

Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·265	·272	·254	·269	·215	·239	·210	·196	·274	·236	·229	·241	·450	·455	·526	·368
February	·227	·219	·193	·270	·200	·246	·188	·165	·188	·180	·179	·185	·384	·395	·473	·283
March	·415	·409	·359	·477	·322	·364	·249	·352	·341	·332	·259	·349	·533	·538	·612	·448
April	·465	·448	·401	·545	·369	·388	·258	·460	·369	·354	·275	·407	·555	·516	·596	·552
May	·650	·656	·640	·653	·551	·582	·418	·653	·589	·615	·437	·616	·609	·556	·690	·581
June	·755	·747	·721	·797	·736	·755	·684	·770	·750	·739	·614	·774	·663	·633	·753	·602
July	?	·840	·824	?	·786	·820	·772	·766	·838	·836	·810	·801	·717	·718*	·790*	·642*
August	·729	·733	·724	·729	·684	·694	·654	·703	·705	·725	·662	·692	·730	·734	·801	·656
September	·743	·753	·739	·736	750	·767	·757	·726	·764	·764	·731	·749	·777	·777	·860	·693
October	·499	·508	·444	·546	·534	·576	·478	·548	·503	·525	·443	·515	·682	·694	·759	·593
November	·251	·281	·230	·242	·235	·240	·224	·240	·262	·282	·252	·241	·488	·495	·558	·411
December	·212	·233	·203	·200	·166	·184	·151	·164	·205	·199	·184	·177	·384	·392	·464	·295
Year	?	·508	·478	?	·462	·488	·420	·479	·482	·482	·423	·479	·581	·575	·657	·510

* Mean of 29 days.

89. MALEGAON. 90. BOMBAY. 91. POONA. 92. SHOLAPUR.

Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·262	·285	·276	·224	·581	·554	·548	·611	·609	·520	·308	·297	·252	·309	·320	·374	·298	·287
February	·393	·424	·526	·228	·583	·543	·542	·637	·608	·507	·283	·240	·256	·298	·305	·334	·308	·274
March	·274	·273	·272	·278	·674	·658	·671	·691	·675	·623	·322	·277	·242	·341	·411	·420	·435	·378
April	·285	·239	·272	·344	·848	·824	·859	·853	·856	·800	·413	·312	·316	·451	·453	·485	·393	·480
May	·500	·459	·471	·571	·880	·863	·889	·890	·879	·828	·507	·438	·448	·524	·512	·520*	·442*	·573*
June	·678	·689	·667	·677	·928	·910	·953	·945	·905	·846	·725	·731	·704	·682	·586	·564	·566	·627
July	·687	·692	·704	·665	·909	·889	·934	·921	·892	·825	·699	·719	·704	·661	·613	·600	·588	·650
August	·628	·633	·653	·598	·865	·851	·892	·868	·849	·806	·654	·674	·658	·629	·633	·616	·613	·669
September	·674	·688	·692	·642	·857	·842	·892	·852	·841	·787	·660	·675	·654	·621	·651	·642	·632	·680
October	·601	·609	·616	·578	·845	·808	·855	·874	·841	·758	·621	·637	·607	·602	·640	·638	·630	·652
November	·343	·356	·341	·331	·674	·654	·646	·703	·694	·624	·418	·426	·381	·423	·587	·565	·614	·583
December	·371	·406	·493	·213	·500	·465	·458	·551	·527	·452	·235	·217	·205	·253	·347	·365	·363	·313
Year	·475	·479	·499	·446	·762	·738	·762	·783	·765	·698	·487	·470	·452	·483	·505	·510	·490	·514

* Mean of 24 days.

Month.	93. Ratnagiri.				94. Belgaum.				95. Karwar.				96. Gopalpore.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·532	·480	·652	·465	·359	·359	·315	·366	·550	·550	·568	·531	...	·557	·593	?
February	·570	·568	·668	·473	·335	·291	·289	·381	·651	·661	·701	·590	...	·652	·775	?
March	·663	·662	·731	·595	?	·331	·407	Imperfect.	·717	·703	·746	·702	...	·804	·841	?
April	·795	·804	·838	·743	·510	·446	·477	·527	·823	·821	·839	·810	...	·914	·943	?
May	·820	·815	·830	·815	·609	·540	·609	·613	·846	·844	·866	·829	...	·947	·976	?
June	·847	·885	·896	·761	·669	·691	·675	·635	·842	·871	·890	·766	...	·960	·969	?
July	·852	·896	·905	·755	·664	·687	·679	·619	·833	·871	·861	·768	...	·931	·934	?
August	·834	·877	·881	·745	·647	·665	·670	·619	·854	·866	·872	·825	...	·954	·963	?
September	·825	·884	·880	·712	·620	·638	·639	·574	·818	·845	·840	·768	...	·936	·931	?
October	·803	·827	·879	·704	·620	·628	·611	·591	·816	·825	·850	·772	...	·836	·839	?
November	·650	·640	·758	·551	·452	·460	·431	·456	·684	·683	·746	·622	...	·578	·593	?
December	·469	·390	·602	·416	·308	·307	·277	·339	·537	·506	·605	·500	...	·451	·481	?
Year	·722	·727	·793	·645	?	·504	·507	?	·748	·754	·782	·707	...	·793	·820	?

Month.	97. Vizagapatam.						98. Masulipatam.					99. Secunderabad.					100. Kurnool.			
	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	·575	·575	·572	·568	·586	·376	·598	·619	·600	·597	·571	·423	·464	·377	·418	·422	...	...	...	...
February	·625	·631	·598	·616	·654	·432	·648	·677	·625	·668	·607	·379	·410	·340	·368	·390	·401	·402*	·377*	·398*
March	·743	·741	·698	·759	·774	·565	·824	·826	·824	·845	·784	·495	·528	·416	·497	·523	·556	·531	·458	·603
April	·827	·832	·772	·852	·851	·631	·938	·908	·942	·990	·901	·446	·482	·373	·443	·462	·756	·726	·729	·704
May	·920	·914	·878	·944	·944	·663	1·076	1·032	1·104	1·050	1·027	·483	·520	·403	·468	·512	·905	·893	·896	·802
June	·839	·848	·812	·826	·869	·612	1·013	·997	1·025	1·022	·972	·687	·694	·669	·693	·666	·850	·820	·812	·810
July	·816	·803	·811	·811	·837	·583	·921	·929	·918	·922	·894	·694	·699	·691	·699	·660	·831	·815	·809	·773
August	·864	·864	·851	·870	·870	·656	·857	·821	·818	·890	·878	·705	·712	·703	·722	·662	·843	·777	·863	·782
September	·853	·859	·838	·845	·871	·627	·811	·793	·796	·843	·837	·703	·702	·712	·713	·664	·793	·788	·786	·727
October	·812	·812	·804	·793	·837	·644	·870	·856	·851	·892	·858	·657	·670	·635	·676	·631	·787	·804	·792	·734
November	·576	·586	·561	·560	·597	·462	·684	·697	·683	·692	·669	·435	·442	·409	·437	·439	·687	·626	·620	Imperfect.
December	·464	·464	·421	·473	·497	·321	·601	·609	·642	·604	·548	·308	·331	·278	·297	·301	·545	·588	·642	·425
Year	·743	·744	·718	·743	·766	·548	·820	·814	·819	835	·796	·535	·555	·501	·536	·528	?	?	?	?

* Mean of 20 days

Month.	101. Bellary. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	102. Mangalore. Mean.	10 hours.	16 hours.	From Minima.	103. Mercara. Mean.	10 hours.	16 hours.	From Minima.	104. Bangalore. Mean.	10 hours.	16 hours.	22 hours.	From Minima.
January	·427	·480	·394	·416	·412	·596	·540	·675	·572	·434	·451	·441	·410	·408	·435	·391	·409	·393
February	·346	·382	·345	·373	·291	·689	·649	·758	·661	·404	·425	·385	·402	·393	·391	·343	·394	·434
March	·451	·484	·428	·460	·422	·768	·776	·776	·753	·514	·521	·538	·482	·515	·556	·454	·497	·539
April	·448	·489	·395	·455	·412	·889	·881	·917	·868	·595	·603	·647	·536	·507	·568	·498	·481	·512
May	·557	·585	·464	·597	·561	·889	·887	·901*	·878	·647	·664	·703	·575	·601	·641	·571	·572	·586
June	·632	·646	·611	·647	·598	·868	·901	·905	·797	·612	·644	·626	·565	·605	·617	·597	·590	·585
July	·641	·642	·625	·661	·627	·849	·878	·876	·792	·591	·611	·606	·556	·612	·634	·630	·601	·557
August	·671	·676	·669	·677	·639	·848	·855	·871	·819	·606	·625	·634	·559	·611	·646	·644	·586	·544
September	·594	·615	·575	·620	·554	·830	·863	·842	·785	·573	·587	·603	·528	·553	·584	·559	·538	·512
October	·680	·698	·660	·709	·634	·826	·845	·842	·790	·581	·604	·607	·533	·592	·626	·616	·584	·531
November	·496	·531	·458	·506	·482	·717	·703	·752	·697	·506	·538	·525	·454	·484	·509	·482	·489	·448
December	·379	·415	·358	·377	·360	·584	·548	·627	·577	·434	·445	·468	·390	·410	·420	·420	·410	·381
Year	·527	·554	499	·542	·499	·779	·777	·812	·749	541	·560	·565	·499	·524	·552	·517	·513	·502

Month.	105. Madras. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	106. Salem. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	107. Wellington. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	108. Coimbatore. Mean.	10 hours.	16 hours.	22 hours.	From Minima.
January	·636	·652	·647	·627	·610	·501	·554	·533	·545	·375*	·345	·356	·376	·370	·277	·509	·532	·463	·520	·511
February	·689	·696	·736	·690	·624	·543	·540	·450	·525	?	·281	·263	·311	·318	·238	·486	·512	·413	·540	·482
March	·805	·793	·836	·821	·763	·639	·675	·562	·620	Imperfect.	·359	·346	·359	·391	·327	·612	·659	·486	·672	·627
April	·880	·820	·903	·916	·841	·727	·791	·645	·724	·730	·397	·371‡	·395‡	·428‡	·367‡	·709	·729	·598	·770	·712
May	·912	·861	937	·943	·876	·784	·823	·801	·755	·721	·451	·441	·461	·473	·408	·746	·762	·737	·764	·689
June	·848	·803	·872	·906	·808	·797	·830	·798	·799	·726	·423	·443	·450	·419	·378	·684	·701	·680	·679	·653
July	·817	·814	·830	·825	·778	·792	·824	·816	·803	·690	·431	·456	·441	·430	·387	·678	·691	·689	·680	·623
August	·855	·815	·886	·872	·820	·819	·858	·899	805	·679	·459	·482	·479	·467	·408	·697	·711	·703	·698	·650
September	·769	·761	·807	·887	·778	·775	809	·814	·780	·668	·414	·440	·453	·400	·353	·660	·667	·650	·673	·630
October	·847	·862	·849	851	·801	·758	·801	·808	·767	·639	·462	·478	·489	·456	·412	·697	·709	·701	·715	·644
November	·723	·743	·727	·730	·690	·680	·723	·774	·679	·556	·392	·406	·452	·394	·320	·648	·657	·644	·680	·603
December	·652	·671	·614	·653	·628	·609	·644	·709	·619	·471	·339	·352†	·384	·343†	·282†	·561	·577	·546	·584	·528
Year	·786	·774	·804	·810	·751	·702	·739	·717	·702	?	·396	·403	·421	·407	·346	·641	·659	·609	·665	·613

* Mean of 30 days. † Mean of 28 days.
‡ „ „ 29 „

TABLE XI.—TENSION OF ATMOSPHERIC VAPOUR IN 1883.

Months.	109. Trichinopoly. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	110. Negapatam. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	111. Madura. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	112. Cochin. Mean.	10 hours.	16 hours.	22 hours.	From Minima.
January	·621	·618	·595	·663	·602	·680	·699	·692	·683	·647	·611	·573	·629	·595	·636	·690	·649	·705	·749	·653
February	·586	·607	·502	·633	·596	·646	·654	·660	·655	·628	·604	·607	·559	·607	·633	·729	·682	·740	·789	·696
March	·647	·679	·574	·666	·667	·750	·753	·745	·765	·731	Wet Bulb. Not recorded.					·847	·849	·866	·852	·808
April	·691	·711	·591	·753	·677	·856	·823	·869	·876	·819	Ditto.					·877	·881	·915	·860	·825
May	·773	·784	·703	·801	·766	·832	·776	·835	·879	·813	Ditto.					·902	·913	·925	·896	·843
June	·767	·767	·717	·813	·745	·760	·693	·781	·800	·733	·710	·665	·688	·726	·732	·869	·892	·907	·883	·785
July	·743	·760	·717	·786	·689	·744	·698	·758	·803	·722	·732	·667	·672	·804	·765	·847	·870	·859	·855	·772
August	·743	·758	·717	·751	·721	·792	·717	·813	·822	·765	·776	·758	·718	·818	·789	·857	·869	·874	·866	·804
September	·702	·675	·674	·705	·689	·770	·708	·823	·808	·724	·773	·741	·770	·800	·760	·840	·857	·850	·842	·798
October	·784	·794	·788	·796	·740	·787	·794	·796	·802	·747	·798	·798	·809	·793	·759	·830	·854	·838	·827	·785
November	·693	·713	·692	·711	·664	·703	·730	·705	·702	·674	·748	·762	·759	·739	·723	·786	·786	·789	·804	·757
December	·624	·631	·613	·648	·587	·671	·680	·672	·688	·636	·660	·665	·680	·649	·640	·703	·693	·701	·739	·668
Year	·698	·708	·657	·727	·679	·749	·727	·762	·774	·720	?	?	?	?	?	·815	·816	·831	·830	·766

Stations.	January.	February.	March	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
113. Colombo	·723	·694	·768	·803	·844	·816	·794	·828	·795	·772	·750	·700	·774
114. Jaffna	·746	·686	·775	·911	·951	·901	·866	·918	·871	·873	·804	·752	·838
115. Trincomalle	·746	·708	·799	·826	·821	·893	·808	·810	·791	·791	·789	·766	·796
116. Batticaloa	·841	·761	·856	·915	·985	853	·781	·802	·822	·809	·711	·752	·824
117. Hambantota	·793	·795	·857	·905	·912	·889	·864	·866	·884	·868	·828	·801	·855
118. Galle	·815	·780	·829	·889	·930	·925	·904	·918	·914	·893	·876	·823	·875
119. Kandy	·649	·599	·649	·707	·743	·703	·699	·699	·664	·698	·695	·656	·680
120. Newera Eliya	·392	·354	·352	·395	·454	·439	·437	·429	·418	·417	·440	·373	·408

Month.	121. Akyab. Mean.	10 hours.	16 hours.	From Minima.	122. Thayetmyo. Mean.	10 hours.	16 hours.	From Minima.	123. Toungoo. Mean	10 hours.	16 hours.	From Minima	124. Bassein. Mean.	10 hours.	16 hours.	From Minima.	125. Diamond Island. Mean.	10 hours.	16 hours.	From Minima.
January	·501	·551	·513	·438	?	·505	·441	Imperfect	·474	·546	·517	·359	·562	·568	·627	·491	·610	·607	·607	·616
February	·511	·519	·605	·408	?	·475	·412	Imperfect	·477	·561	·483	·388	·563	·584	·574	·532	·653	·658	·646	·656
March	·675	·683	·725	·617	·508	·583	·438	·503	·605	·716	·607	·493	·658	·684	·616	·675	·754	·750	·770	·741
April	·822	·850	·882	·734	·787	·731	·832	·798	?	·772	·715	?	·775	·773	·754	·799	·832	·823**	·840	·832**
May	·904	·934	·971	·807	·864	·912	·891	·789	?	·864	·819	?	·879	·878	·896	·863	·897	·927	·910	·854
June	·889	·937	·922*	·808	·898	·919	·933	·841‖	·792	·869	·845	·663	·897	·936	·908	·846	·883	·909	·903	·837
July	·896	·929	·933	·825	·901	·914	·938	·852	·827	·851	·850	·779	·887	·921	·899	·841	·872	·902	·886	·828
August	·890	·930	·926†	·814	·886	·901	·910	·848	·836	·845	·859	·805	·896	·922	·905	·860	·885	·913†	·898†	·843†
September	·879	·913	·909	·816	·906	·924	·957	·836	·840	·853	·860	·807	?	·908	·896	Imperfect	·859	·890	·874	·813
October	·882	·918	·915	·813	·881	·918	·921	·804	·847	·875	·860	·807	?	·927	·910	?	·881	·917	·880	·846
November	·698	·740‡	·716§	·639‡	·735	·754	·784	·666	·749	·790	·770	·688	?	·798	·812	?	·798	·820	·806	·767
December	·583	·585	·632	·531	·599	·589	·702	·507	·613	·664	·668	·508	·661	·683	·725	·575¶	·682	·679	·695	·671
Year	·761	·791	·804	·688	?	·760	·763	?	?	·767	·738	?	?	·799	·794	?	·801	·816	·810	·775

* Mean of 29 days. ‖ Mean of 28 days. ¶ Mean of 23 days. ** Mean of 29 days.
† ,, ,, 30 ,,
‡ ,, ,, 27 ,,
§ ,, ,, 25 ,,

Month.	126. Rangoon. Mean	10 hours.	16 hours.	From Minima.	127. Moulmein. Mean.	10 hours.	16 hours.	From Minima.	128. Mergui. Mean.	10 hours.	16 hours.	From Minima.	129. Port Blair. Mean.	10 hours.	16 hours.	From Minima.	130. Nancowry. Mean.	10 hours.	16 hours.	From Minima.
January	·528	·575	·508	·502	·515	·548	·483	·515	·718	·738	·758	·659	·752	·761	·800	·695	·748	·756	·734	·753
February	·578	·624	·592	·518	·646	·709	·589	·639	·796	·802	·795	·791	·790	·820	·839	·711	·751	·746	·736	·771
March	·702	·738	·709	·658	·731	·765	·712	·716	·813	·828	·837	·774	·843	·863	·899	·766	·788	785	·765	·813
April	·833	·869	·860	·771	·803	·839	·777	·794	·870	·902	·930	·778	·922	·948	·955	·863	·849	·825	·855	·866
May	·901	·951	·908	·845	·862	·903	·876	·808	·886	·933	·917	·809	·956	·991	·983	·894	·878	·884	·892	·859
June	·892	·932	·920	·824	·863	·896	·888	·806	·860	·905	·896	·780	·924	·956	·956	·860	·861	·879	·881	·824
July	·876	·929	·888	·811	·858	·893	·890	·791	·851	·894	·893	·765	·881	·922	·925	·796	?	·851	·861	?
August	·889	·938	·892	·836	·867	·914	·850	·796	·875	·941	·918	·766	·907	·947	·949	·824	?	·960	·893	?
September	·869	·899	·900	·809	·851	·883	·880	·791	·837	·882	·879	·751	·885	·927	·914	·813	?	·920	·894	?
October	·875	·942	·866	·818	·836	·872	·844	·792	·816	·851	·851	·746	·908	·956	·941	·827	?	·886	·854*	?
November	·781	·830	·796	·716	·747	·776	·751	·713	·766	·778	·810	·711	·868	·907	·897	·801	?	·868	·855	?
December	·630	·674	·636	·579	·593	·609	·586	·584	·667	·647	·728	·625	·822	·853	·858	·754	?	·809	·807	?
Year	·780	·825	·790	·724	·764	·801	·764	·729	·813	842	·851	·746	·872	·904	·910	·800	?	·847	·836	?

* Mean of 30 days.

TABLE XII.—MEAN RELATIVE HUMIDITY OF THE AIR IN 1883 (130 STATIONS).

Month.	1. Zanzibar. Mean.	10 hours.	16 hours.	From Minima.	2. Aden. Mean.	10 hours.	16 hours.	From Minima.	3. Seychelles. Mean.	10 hours.	15 hours.	From Minima.	4. Bushire. Mean.	10 hours.	16 hours.	From Minima.	5. Quetta. Mean.	10 hours.	16 hours.	From Minima.
January	77	79*	67*	84*	72	72	68	77	...	...	...	...	77	81§	71§	79§	72	71	65	81
February	78	80†	68‡	86‡	66	66	60	73	...	...	...	...	68	70	68	66	59	54	41	81*
March	76	76§	66§	85§	71	71	63	80	...	...	...	...	67	61	64	75	53	46	37	77
April	80	82‖	70‖	87¶	68	69	57	78	...	...	...	...	60	53	58	69	50	43	36	70‡‡
May	80	82	73	85	70	69	67	75	...	...	...	...	57	54	55	61	42	34	27*	66§
June	70	76	57	78	60	62	54	63	90	88‡	88¶	93‡	61	61	59	63	33	25	18	55
July	77	81	67	83	64	65§	53	73	93	94**	94‖	91**	63	62	62	65	46	36	31	72§
August	72	78	57	80	65	66	56	72	87	83†	86††	91††	63	61	60	67	33	23§	18	57
September	75	78	65	82	63	65	56	68	83	80‡‡	82§§	88‡‡	64	57	62	73	31	24†	17‡	53†
October	75	77	64	85	63	59	57	73	83	82‖‖	81‖	87‡‡	62	56§	56§	74§	36	27	19	61
November	76	76	66	85	66	63	61	73	82	77‡‡	82‡‡	88‡‡	69	62	67*	79	43	36	24	70
December	75	76	63	85	71	71	65	78	90	86‖	88**	95‖	72	71	69§	75	53	42	36	81
Year	76	78	65	84	67	67	60	74	...	...	...	...	65	62	63	71	46	38	31	69

* Mean of 27 days.
† „ „ 23 „
‡ „ „ 22 „
§ Mean of 30 days.
‖ „ „ 21 „
¶ „ „ 20 „
** Mean of 25 days.
†† „ „ 24 „
‡‡ „ „ 29 „
§§ Mean of 26 days.
‖‖ „ „ 28 „

Month.	6. Leh. Mean.	6 hours.	10 hours.	16 hours.	22 hours.	From Minima.	7. Mooltan. Mean.	10 hours.	16 hours.	From Minima.	8. Dera Ismail Khan. Mean.	10 hours.	16 hours.	From Minima.	9. Peshawar. Mean.	10 hours.	16 hours.	From Minima.	10. Murree. Mean.	10 hours.	16 hours.	From Minima.
January	59	...	62	54	...	60	59	53	41	83	57	52	43	76	62	59	46	81	71	66	74	72
February	58	...	61	53	...	61	47	41	27	74	40	33	23	65	53	44	34	80	67	62	68	72
March	49	...	47	41	...	58	48	40	32	73	46	41	29	68	54	49	36	78	59	55	62	60
April	40	...	39	27	...	54	44	31	31	69	45	37	30	67	50	40	36	73	57	58	55	57
May	40	...	35	29	...	56	49	36	37	74	36	31	24	53	33	27	21	51	43	42	42	44†
June	32	...	32	21	...	43	49	38	36	74	36	31	22	54	32	27	20	48	44	42	40	49
July	36	...	36	29	...	42	64	58	54	80	60	57	45	77	56	53	39	76	72	73	65	79
August	43	...	43	32	...	53	62	57	54	74	52	52	35	70	52	50	37	70	74	75	71	75
September	44	59	40	29	46	55*	62	55	53	77	56	54	37	78	53	47	36	76	66	65	65	69
October	50	66†	43	35	55	61†	46	38	35†	65	42	36	28	62	41	34	27	63	43	38	43*	48
November	56	69‡	49§	49§	56‖	74¶	49	42	37*	68	52	47	32	78	55	50	41	75	45	40	50	45
December	62	66*	56†	59†	68†	77**	49	45	38	65	53	48	35	76	61	58	44	80	48	39	55†	50
Year	47	...	45	38	...	58	52	45	40	73	48	43	32	69	50	45	35	79	57	55	58	60

* Mean of 29 days.
† „ „ 30 „
‡ „ „ 26 „
§ „ „ 24 „
‖ Mean of 25 days.
¶ „ „ 21 „
** „ „ 27 „
* Mean of 29 days.
† „ „ 30 „

Month.	11. Rawalpindi.				12. Sialkot.				13. Lahore.						14. Ludhiana.				15. Kailang.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima	Mean.	10 hours.	16 hours.	From Minima	Mean.	10 hours.	16 hours.	From Minima.
January	80	80	68	92	72	74	55	86	67	79	65	47	77	85	66	62	51	83	...	...	...	...
February	72	64	57	95	66	67	43	88	56	73	51	31	67	80	59	54	41	81	...	...	...	...
March	68	64	52*	88	59	55	39	82	51	66	48	31	58	76	53	47	39	74	...	...	...	...
April	53	47*	40†	72*	38	32	22	61	38	50	32	23	46	60	47	29	26	86	...	...	...	...
May	47	45	38	59	32	28	21	47‡	35	48	29	22	39	54	49	33	29§	85	...	...	...	...
June	47	45	39	56	?	34	23	?	38	51	33	23	43	55	?	44	36*	?	...	...	...	...
July	65	63	53	79	56	64	48	57§	58	73	53	44	62	76	69	63	55	89	?	49§	38§	?
August	68	66	57	82	61	62	49	71‖	54	68	47	39	60	75	57	50	43	78¶	?	54	39	?
September	63	58	48	84	?	66	52	?	69	83	62	52	78	85	65	52	53	90	?	48	38	
October	50	44	34*	72	?	36	23	?	49	65	39	30	63	71	46	36	28	75	?	42	35	?
November	74	67*	65	89	?	63	37	?	61	78	51	40	73	82	57	49	38	83	?	53	48	?
December	67	63*	46*	91*	?	68	38	?	61	75	52	40	76	83	57	49	36	86		57	59	?
Year	63	59	50	80	?	54	38	?	53	67	47	35	62	74	?	47	40	?	...	...	...	...

* Mean of 29 days.
† „ „ 28 „
‡ Mean of 22 days.
§ „ „ 30 „
‖ Mean of 23 days.
¶ „ „ 24 „

Month.	16. Simla.				17. Delhi.				18. Sirsa.				19. Chakrata.				20. Mussooree.			
	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	61	61	65	58	60	61	43	76‡	59	56	43	77	70	64	71	74	63	56¶	66††	68¶
February	51	50	57	47	43	42	27	59	44	39	25	69	55	47	55	62	52	43*	56*	56*
March	46	45	52	41	46	43	29	65	48	42	34	68	56	48	52	67	52	47¶	52‡‡	57*
April	47	36	36	68	29	25	17	44	35	30	22§	53	41	36	36	51	35	33†	27‡	45†
May	47	45*	43*	53†	37	27	20	63	36	32	24	53	44	37	34	61	44	38**	41	53**
June	63	60	59	71	46	43	32	62	36	27	25	55	70	68	69	74	74	74§	68	81‡‡
July	87	88	86	87	65	65	52	78	58	54	46	74	92	91	93	91	94	94¶	93§	95‡‡
August	84	84	83	84	50	46	38	65	45	41	30	63	87	86	90	86	88	88**	86	90**
September	81	79	79	86	59	59	47	72	60	54	45	80	85	84	89	83	86	83§	89††	87§
October	43	42	37	51	38	34	25	56	38	31	20	63	46	41	45	53	54	49§	55‡‡	58§
November	51	48	55	51	42	39	30	57	43	38	22	68	59	52	61	64	62	55††	65‡	66††
December	46	43	41	53	41	40	26	56	43	37	24	69	51	42	53	58			Imperfect.	
Year	59	57	58	63	46	44	32	63	45	40	30	66	63	58	62	69	?	?	?	?

* Mean of 26 days.
28 „
‡ Mean of 30 days.
§ Mean of 29 days.
* Mean of 25 days.
† „ „ 22 „
‡ „ „ 20 „
§ „ „ 27 „
‖ „ „ 21 „
¶ „ „ 29 „
** „ „ 30 „
†† „ „ 26 „
‡‡ „ „ 28 „

TABLE XII.—MEAN RELATIVE HUMIDITY OF THE AIR IN 1883.

21. DEHRA (S. G. O.). 22. DEHRA (FOREST SCHOOL.) 23. PAORI. 24. ROORKEE. 25. RANIKHET.

Month.	21. Mean.	21. 9-30 hours.	21. 15-30 hours.	21. From Minima.	22. Mean.	22. 10 hours.	22. 16 hours.	22. From Minima.	23. Mean.	23. 10 hours.	23. 16 hours.	23. From Minima.	24. Mean.	24. 10 hours.	24. 16 hours.	24. From Minima.	25. Mean.	25. 10 hours.	25. 16 hours.	25. From Minima.
January	...	64	42	Wet minimum observations not recorded.	63	57	47	86	65	64	56	75	56	60	41	66	63	61	61	66
February	...	58	33		59	52	39	86	55	56	42	66	58	58	31	85	45	46	42	48
March	...	54	36		55	47	35	84	56	59*	42*	68	?	49	33	?	52	51	48	57
April	...	34	22		42	31	22	73	42	45	26	55	29	29	17	41†	40	38	34	48
May	...	31	25		41	27	26	69	45	46	34	54	29	30	21	37	46	43	43	51
June	...	61	52		63	58	50	82	64	65	53	75	52	54	41	60	68	66	62	77
July	...	82	77		84	79	76	98	84	85	79*	89	73	75	67	77	85	84	81	89*
August	...	80	73		79	74	71	91	82	84*	74	88*	65	68	56	72	81	79	78	86
September	...	79	74		78	72	72	91	81	83	72	88†	71	73	62	77	82	79	79	88
October	...	56	40		54	43	33	87	55	57†	40*	67†	46	42	32	63	51	47	48	57
November	...	69	50		65	56	47	93	67	70	56	75	53	55	41	62	57	54	55	61
December	...	64	46		60	51	42	88	Abolished.				50	55	37	58*	52	52	54	51
Year	...	61	48		62	54	47	86	?	?	?	?	?	54	40	?	60	58	57	65

* Mean of 30 days. † Mean of 29 days.

26. PITHORAGARH. 27. MEERUT. 28. BAREILLY. 29. AGRA. 30. LUCKNOW.

Month.	26. Mean.	26. 10 hours.	26. 16 hours.	26. From Minima.	27. Mean.	27. 10 hours.	27. 16 hours.	27. From Minima.	28. Mean.	28. 10 hours.	28. 16 hours.	28. From Minima.	29. Mean.	29. 10 hours.	29. 16 hours.	29. From Minima.	30. Mean.	30. 10 hours.	30. 16 hours.	30. From Minima.
January	63	64	49	77	65	65	44	87	64	62	44	86	58	51	40	83	61	54	40	89
February	51	52*	36	66*	54	52	31	78	56	54	35	80	47	40	25	76	48	42	27	76
March	55	56	40	69	49	47	31	68	57	54	40	78	40	36	21	64	44	36	25	72
April	41	39	30	53	31	26	20	47	37	32	23	56	26	22	12	44	35	30	24	52
May	48	45	41	57	30	29‡	27§	34§	43	41	30	59	27	24	15	41	44	43	30	59
June	73	73	63	83	48	44	42	57	58	55	42	78	42	40	28	59	56	51	42	74
July	84	84	77	90	68	67	62	74	76	75	66	87	73	71	61	86	76	73	69	87
August	81	82	73	88	57	55	49	66	71	69	59	84	57	53	45	72	70	66	60	85
September	79	79	70	88	62	61	51	73	72	70	58	87	61	56	46	80	72	66	57	92
October	54	55	36	71†	46	41	27	69	49	41	27	78	35	29	18	58	54	42	32	88
November	56	57‡	41‡	71‡	53	48	34	78	53	49	34	77	38	31	20	63	51	37	32	85
December	53	52†	40†	66	55	47	29	89	55	52	35	77	44	38	24	70	53	43	34	83
Year	62	62	50	73	52	49	37	68	58	53	41	77	46	41	30	66	55	49	39	79

* Mean of 27 days. ‡ Mean of 29 days.
† „ „ 30 „ § „ „ 28 „

Month.	31. Gorakhpur. Mean.	10 hours.	16 hours.	From Minima.	32. Jhansi. Mean.	10 hours.	16 hours.	From Minima.	33. Allahabad. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.	34. Benares. Mean.	10 hours.	16 hours.	From Minima.	35. Ghazipur. Mean	10 hours.	16 hours.	From Minima.
January	?	65	51	Imperfect.	57	52	42	78	75	93	66	54	86	92	66	64	45	89†	...	64	44	Wet minimum not recorded.
February	60	62	44	73	44	37	25	70	57	78	47	33	70	87	48	40	26	78	...	44	28	
March	52	49	36	70	42	35	25	67	43	63	36	24	50	70	40	33	21†	65	...	32	19	
April	43	41	28	61	27	17	15	48	31	47	26	17	35	50	33	27	16	57	...	23	15	
May	53	53	34	71	33	24	22	53	36	51	31	20	41	54	38	35	19†	60	...	37	21	
June	72	70	62	84	49	38	39	71	58	71	53	45	62	74	62	58	51	77	...	59	55	
July	82	80	74	92	74	69	66	87	81	89	77	70	86†	89	77	75	68	87	...	75	68	
August	80	77	72	92	66	57	56	84	75	86†	70	64	81	87	72	70	63	84	...	70	64	
September	81	77	70	95	70	60	59	90	83	95	76	71	89	95	75	73	63	89	...	71	69	
October	62	65	41	89	49	33	32	82	63	85	53	39	75	89	55	48	35	81	...	60	51	
November	58	49	38	86	36	23*	23*	62	57	81	44	35	69	92	52	41	33	81	...	47	36	
December	61	56	45	83	39	31	24	63	62	85	50	38	76	90	53	46	32	81	..	53	39	
Year	?	61	50	?	49	40	36	71	60	77	52	43	68	81	56	51	39	77	...	53	42	

* Mean of 29 days. † Mean of 30 days.

Month.	36. Katmandu. Mean.	10 hours.	16 hours.	From Minima.	37. Sibsagar. Mean.	10 hours.	16 hours.	From Minima.	38. Dhubri. Mean.	10 hours.	16 hours.	From Minima.	39. Silchar. Mean.	10 hours.	16 hours.	From Minima.	40. Darjeeling. (St. Paul's School). Mean.	10 hours.	16 hours.	From Minima.
January	76	77	61	91	87	94	68	98	82	86	65	95	73	75	50	94	89	89	90*	89†
February	67	66	47	88	83	90	61	98	63	64	39	86	66	66	40	93	86	88	86‡	84§
March	63	57	42	90	80	82	63	96	56	58	34	77	72	71	50	95	?	72*	74†	?
April	62	52	43	92	80	80	66	95	67	68	51	82	75	71	59	94	?	75‖	76‡	?
May	75	63	67	95	85	86	74	95	84	85	77	91	87	85	78	97	?	88*	83¶	?
June	78	70	69	95	84	84	73	94	87	86	81	93	86	82	78	98	?	93	91‖	?
July	81	74	74	96	81	83	68	93	84	83	78	90	83	78	74	97	94	93	93*	96‖
August	83	76	79	94	84	86	72	94	87	87	83	92	87	86	77	98	94	94	93	96
September	76	65	72	91	86	87	75	95	86	86	80	92	85	84	75	97	95	94	94‡	97
October	69	59	55	93	84	85	70	96	79	78	68*	90	81	80	66	97	89	88‡	87**	91‡
November	69	62	56	89	81	82	65	97	73	73	58	88	77	76	61	95	81	75††	82††	85¶
December	66	68	50	81	87	94	70	98	78	80	62	92	79	80	61	96	73	66	74	78
Year	72	66	60	91	84	86	69	96	76	78	65	89	79	78	64	96	?	85	85	?

* Mean of 30 days. ‖ Mean of 28 days.
† ,, ,, 26 ,, ¶ ,, 25 ,,
‡ ,, ,, 27 ,, ** ,, 23 ,,
§ ,, ,, 21 ,, †† ,, 29 ,,

	41. PURNEAH.				42. DURBHUNGA.				43. PATNA.				44. GYA.				45. HAZARIBAGH.			
MONTH.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	71	70*	47	92*	75	75	57	93	68	68	49	86	60	56	41	83	56	51	42	78
February	?	54†	?	87†	62	61	42	83	54	52	35	76	42	37	25	64	40	31	28	59
March	49	42	26	80	54	50	34*	77	43	38	26	66	34	29	21	51	40	36*	29	58
April	53	51	32	77	56	50	38	80	39	35	22	60	26	21	14	43	26	22	16	43*
May	72	68	58	91	69	67	55	85	53	51	31	76	38	34	21	59	33	28	22	55
June	77	74	67	91	77	76	67	89	70	68	60	83	66	63	58	77	69	63	63	86
July	84	80	77	95	85	82	80	92	82	79	76	91	79	76	73	88*	88	83	81	96
August	86	84‡	78‡	96‡	88	88	85	91	82	79	76	90	75	70	69	85	82	78	77	93
September	84	81	77	95	87	87	83	92	80	77	72	91	75	71	65	88	81	77	73	95
October	74	69	60	93	75	74	62	89	62	56	45	85	54	46	40	75	51	45	39	69
November	66	58	48	91	65	62	47	85‡	55	49	37	79	51	40	36	76	49	43	36	66
December	69	64	48	94	68	67	52	85	59	54	42	81	48	40	30	75	48	43	33	65
Year		66	?	90	72	70	59	87	62	59	48	80	54	49	41	72	55	50	45	72

* Mean of 30 days.
† ,, ,, 19 ,,
‡ ,, ,, 29 ,,

	46. BERHAMPORE.				47. BURDWAN.				48. JESSORE.				49. DACCA.				50. CHITTAGONG.			
MONTH.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	74	67	46	91	63	55	40	94	67	63	46	91	69	67	49	91*	72	73	54	89
February	59	46	31	79	55	44	33	88	57	51	37	84	61	52	39	91†	64	58	47	86
March	55	44	30	75	55	50	33	82	59	60	38	78	64	61	42	89	76	73	66	90
April	56	54	34	67	55	55	31	79	65	64	49	83	70	66*	55	90*	78	73	70	92
May	76	72	58	83	69	67	54	87	76	73	65	89	81	80	73	91	82	77	78	91
June	86	79	75	92	77	73	67	90	84	79	80	92	87	83	82	95	87	84	85	92*
July	89	84	80	93	83	81	76	92	87	85	81	94	86	83	80	94	88	85	85	95§
August	89	83	82	93	84	81	78	92	87	83	83	94	87	85	81	94	?	86	85	?*
September	85	79	71	94	81	78	72	93	86	82	80	95	85	81	78	96	?	85	83	?
October	75	68	55	91	68	61	50	92	76	70	64	93	79	73	67	96	?	83	75	?
November	68	56	45	86	57	48	39	83	65	55	49	90	70	62	57	90	?	79	71	?
December	73	64	50	89	61	55	43	84	71	66	56‡	92	75	70‡	62	93	?	85	72	?
Year	74	66	55	86	67	62	51	88	73	69	61	90	76	72	64	93	?	78	73	?

* Mean of 29 days.
† ,, ,, 26 ,,
‡ ,, ,, 30 ,,

§ Mean of 25 days.

51. CALCUTTA (CHOWRINGHEE). 52. CALCUTTA (ALIPORE). 53. SAUGOR ISLAND. 54. CUTTACK.

Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	69	61	47	92	71	93	60	42	86	95	74	87	67	57	83	86†	65	60	43	91
February	64	57	43	81	67	87	56	40	80	90*	75	88	67	62‡	84	81‡	62	58	40	88
March	67	63	41	84	71	91	62	41	84	84	78	85	73	69	85	83	64	60	40	91
April	73	66	53	85	74	93	74	63	85	85	79	86	74	73	83	86§	61	54	42	88
May	78	69	64	86	76	90	69	63	83	86	80	85	76	74	84	88	64	56	49	88
June	85	77	75	89	83	92	77	74	87	90	82	86	78	78	85	80§	77	72	68	91
July	89	83	82	93	87	93	83	81	91	92	86	90	83	83	89	90§	81	77	75	92
August	89	82	84	93	87	94	82	83	90	92	87	90	87	84	88	92	81	76	76	92
September	88	81	80	95	87	95	81	80	91	94	87	91	85	82	88	93	82	77	75	93
October	78	68	61	90	80	92	68	60	87	91	78	85	73	69	85	87	74	67	62	92
November	67	56	48	86	71	85	55	43	82	88	69	79	65	52	79	78	68	58	53	93
December	70	63	52	87	73	87	61	48	88	89	74	84	70	58	84	82	70	58	47†	94
Year	76	69	61	88	77	91	69	60	86	90	79	86	75	70	85	86	71	64	56	91

* Mean of 26 days. † Mean of 30 days. ‡ Mean of 27 days. § Mean of 29 days.

55. FALSE POINT. 56. SAMBALPUR. 57. SAMBALPUR (*New observatory*). 58. RAIPUR. 59. NAGPUR.

Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	80	76	66*	98	65	58	46	92					54	47	34	81	55	50	33	81
February	81	77	70†	96	54	46	36	81					42	33	27	67	37	29	21	62
March	84	80	78	93	58	52	44	79					42	35	25	65	30	25	15	49
April	83	77	80	92	38	34	25	56	Observatory opened on 16th October 1883.				?	Imperfect.			41	24	17	13	41
May	83	79	79	92	44	39	27	65					26	22	15	40	25	21	15	40
June	84	80	80	92	67	64	57	80					68	63	57	85	67	60	56	86
July	86	82	83	94*	86	84	82	91					80	77	72	91	79	74	69	94
August	86	81	82	94	83	81	77	90					74	70	62	91	70	65	58	87
September	86	81	81	95	84	83	77	91					81	77	71	95	81	74	73	96
October	78	70	66	98	72	67	57	92	Imperfect.				68	60	53	92	65	58	48	89
November	72	62	55	98	66	57	48	93	64	54	45	92	60	51	38	90	53	44	33	82
December	72	64	57	95	64	57	45	90	60	52	42	87	49	40	25	81	43	34	24	70
Year	81	76	73	95	65	60	52	83	...	...	...	...	?	?	?	77	52	46	38	73

* Mean of 30 days
† „ „ 27 „

	60. Seoni.				61. Jubbulpore.				62. Saugor.				63. Pachmarhi.				64. Hoshangabad.			
Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	57	49	38	83	59	54	44	79	54	50	38	73	54	42	41	78	54	54	35	74
February	40	33	25	61	42	35	25	66	37	31	23	57	40	30	26	63	37	33	24	55
March	33	29	19	50	31	29	18	45*	34	28	22	53	31	25	20	49	29	25	18	44
April	26	21	18	39	20	15	12	34	22	16	13	37	21	15	13	35	20	16	12	31
May	28	23	18	42	25	25	17	34†	45	42	36	58	31	29	21	44	30	29	19	42
June	67	61	60	81	60	58	48	73*	61	54	50	79	70	68	60	83	63	62	48	79
July	80	77	73	91	82	81	73	93‡	82	82	72	93	91	92	86	96	83	82	76	90
August	74	68	66	89	74	71	64	87	75	71	65	89	85	84	79	93	78	76	69	88
September	78	73	70	92	83	81	72	95	82	78	75	94	90	89	86	96	84	85	76	92
October	60	50	47	84	65	60	47	89	62	54	53	79	67	57	60	84	68	65	53	86
November.	47	36	30	76	55	49	31	84	52	44	50	63	53	41	42	77	54	49	37	75
December.	40	28	23	69	50	43	25	83	51	37	55	60	43	30	32	68	48	45	32	68
Year	53	46	41	71	54	50	40	72	55	49	46	70	56	50	47	72	54	52	42	69

* Mean of 29 days.
† ,, 28 ,,
‡ ,, 30 ,,

	65. Khandwa.				66. Chanda.				67. Sironcha.				68. Chikalda.				69. Buldana.			
Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	46	36	27	76	58	51	33	90	62	62	38	85	51	48	40	64	58	59	56	60
February	34	25	17	60	45	39	21	74	51	48	27	77	38	37	31	46	42	43	40	44
March	29	22	15	50	40	32	21	68	51	52	31	69	31	29	23	40	41	43	39	40
April	24	17	12	43	25	21	13	40	38	41	19	55	21	20	15	29	37	38	37	35
May	35	32	19	55	23	22	15	33	35	36	20	50	37	37	24	50	45	47	38	50
June	64	60	49	83	67	63	55	82	71	71	61	81	78	78	68	89	76	75	67	87
July	79	77	70	89	74	70	65	88	81	79	75	90	94	94	88	99	84	82	78	92
August	75	73	62	89	72	63	63	90	80	78	73	89	89	89	82	96	81	81	72	91
September	80	80	69	91	80	75	71	93	84	83	78	91	95	94	93	97	89	87	85	94
October	67	62	50	89	74	68	60	94	74	72	61	90	71	65	69	78	76	70	74	83
November.	47	36	26	78	70	62	53	96	68	70	46	88	54	49	49	65	59	52	55	69
December.	42	32	20	74	61	53	34	96*	63	63	39	86	41	35	36	53	49	45	46	57
Year	52	46	36	73	57	52	42	79	63	63	47	79	58	56	52	67	61	60	57	67

*Mean of 29 days.

TABLE XII.—MEAN RELATIVE HUMIDITY OF THE AIR IN 1883.

70. AKOLA.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	44	40	26	65
February	30	24	17	48
March	25	19	14	42
April	17	13	9	30
May	26	25	13	40
June	67	65	50	86
July	77	75	66	91
August	71	68	58	86
September	81	78	71	93
October	71	65	56	92
November	54	44	34	84
December	45	36	23	76
Year	51	46	36	69

71. AMRAOTI.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	43	41	28	61
February	36	34	27	48
March	30	29	22	38
April	23	20	15	35
May	26	24	14	41
June	69	65	54	88
July	81	78	72	92
August	72	70	58	87
September	83	79	76	95
October	67	60	55	86
November	50	42	33	74
December	36	29	23	57
Year	51	48	40	67

72. NEEMUCH.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	47	43	27	72
February	36	29	22	56
March	32	21	18	57
April	21	11	13	39
May	30	19	18	52
June	52	45	38	74
July	79	73	70	94
August	70	62	56	92
September	81	74	73	96
October	56	42	43	82
November	33	18	17	65
December	36	26	21	61
Year	48	39	35	70

73. NOWGONG.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	64	57	43	91
February	51	44	31	78
March	Imperfect.			
April	?	?	?	64
May	?	?	?	53*
June	54	52	44	67
July	78	76	70	87†
August	69	65	60	81
September	74	69	62‡	90
October	55	49	38	79
November	49	39§	29§	78
December	50	42	29	78
Year	?	?	?	?

74. SUTNA.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	59	53	40	84
February	40	31	19	69
March	33	25	16	59
April	19	12	8	38
May	24	19	14	40
June	49	44	38	64
July	76	74	67	88†
August	70	66	61	82
September	77	73	67	90
October	55	46	37	81
November	42	30	23	72‡
December	40	32	19	68
Year	49	42	34	70

* Mean of 25 days. ‡ Mean of 29 days.
† „ „ 30 „ § „ „ 28 „

75. INDORE.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	47	36	31	75
February	34	26	20	55
March	31	24	18	50
April	20	14	12	34
May	34	29	20	52
June	66	64	54	80
July	82	82	73	92
August	77	73	65	92
September	84	81	78	93
October	64	54	51	88
November	47	33	30	78
December	44	28	27	76
Year	53	45	40	72

76. BICKANEER.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	34	25	27	51
February	29	15	24	48
March	35	28	28	50
April	33	27	25	46
May	37	35	31	46
June	43	41	33	56
July	59	57	48	73
August	51	49	38	67
September	57	54	48	70
October	37	30	28	54
November	37	31	27	54
December	31	21	21	51
Year	40	34	32	56

77. JEYPORE.

Month.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	From Minima.
January	62	72	55	47	72	57
February	45	56	38	29	56	37
March	43	55	37	28	50	37
April	24	35	17	14	31	22
May	40	53	36	27	42	32
June	57	71	48	43	64	38
July	73	85	69	60	78	61
August	57	74	51	43	61	48
September	67	78	62	52	75	80
October	41	58	33	24	49	65
November	41	57	31	25	49	58
December	45	60	36	30	55	62
Year	50	63	43	35	57	50

78. SAMBHAR.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	54	57	39	67
February	48	50	40	53
March	38	34	24	56
April	28	21*	14*	48†
May	?	?	?	49
June	?	Imperfect.		62
July	70	69	59	81‡
August	55	54	39	71
September	63	62	49	77
October	?	Imperfect.		57
November	?	Ditto.		45
December	39	39	31	48
Year	?	?	?	60

79. AJMERE.

Month.	Mean.	10 hours.	16 hours.	From Minima.
January	54	53	41	69
February	40	34	28	57
March	41	46	29	58
April	29	26	19	43
May	43	40	27	61
June	53	53	42	63
July	76	75	66	87
August	63	64	51	73
September	71	72	61	79
October	46	43	36	58
November	44	38	38	56
December	47	45	36	59
Year	51	48	40	64

* Mean of 20 days. ‡ Mean of 30 days.
† „ „ 26 „

Month.	80. Mt. Abu. Mean.	10 hours.	16 hours.	From Minima.	81. Pachbudra. Mean.	10 hours.	16 hours.	From Minima.	82. Jacobabad. Mean.	10 hours.	16 hours.	From Minima.	83. Hyderabad. Mean.	10 hours.	16 hours.	From Minima.	84. Kurrachee. Mean.	10 hours.	16 hours.	From Minima.
January	42	34	33	58	42	32	22	73	44	41	31	60	45	40	31	64	54	46	43	60
February	31	25	25	43	27	17	9	56	29	25	18	45	32	27‡	19‡	49	60	51	50	62
March	37	32	29	49	38	29	30	54	33	30	21	48	37	31	19	62	70	59	60	78
April	31	27	24	41	27	20	20	42	30	27	19	44	44	36	27	70	79	68	71	89
May	37	30	31	49	45	42	27	66	29	25	18	43	45	36	26	74	80	68	72	89
June	66	61	53	83	50	47	33	70	39	38	23	55	?	39	33	Imperfect.	78	68	71	87
July	84	80	81	90	63	58	50	82	60	60	46	74	65	57	53	86*	80	76	75	86
August	75	72	64	89	54	52	32	79	53	55	37	68	58	53	44	78	78	73	74	84
September	82	75	81	90	64	61	47	84	51	50†	35†	69†	63	57	47	85	77	70	72	86
October	52	41	46	69	40	31	19	70	38	32	28	54	50	46	35	70	59	47	56	74
November	40	29	32	60	33	26*	15*	59*	33	32	29	57	52	50	41	66	47	38	42	53
December	39	28	31	58	34	25	15	62	49	45	35	66	45	36	31	68	47	36	38	55
Year	51	45	44	65	43	37	27	66	41	38	28	57	?	42	34	?	67	58	60	75

* Mean of 29 days. † Mean of 28 days. ‡ Mean of 27 days.

Month.	85. Bhuj. Mean.	10 hours.	16 hours.	From Minima.	86. Rajkot. Mean.	10 hours.	16 hours.	From Minima.	87. Deesa. Mean.	10 hours.	16 hours.	From Minima.	88. Surat. Mean.	10 hours.	16 hours.	From Minima.	89. Malegaon. Mean.	10 hours.	16 hours.	From Minima.
January	40	34	26	59	33	31	19	49	40	29	22	60	60	55	48	76	38	35	25	54
February	34	26	18	57	28	30	15	40	25	21	16	45	48	47	38	60	45	43	39	53
March	48	40	29	75	38	34	17	64	35	31	19	60	56	51	43	74	31	23	17	52
April	40	29	23	67	34	26	13	64	26	23	13	50	48	39	36	69	24	14	14	44
May	51	42	39	72	45	38	21	75	41	42	21	70	48	39	43	62	40	30	24	66
June	57	50	45	75	59	53	43	80	53	50	34	72	58	53	58	63	64	60	49	82
July	?	72	68	?	74	72	63	87	76	73	64	85	66	64*	67*	68*	71	66	63	84
August	65	59	56	80	62	57	46	84	60	60	44	77	67	64	65	71	67	61	57	82
September	71	64	62	87	76	70	65	92	72	68	57	86	78	73	79	81	75	72	65	87
October	45	38	28	69	53	47	35	78	48	40	32	72	67	61	61	78	67	61	55	84
November	32	28	20	47	32	23	18	55	34	28	21	54	58	51	47	76	49	41	32	74
December	33	29	21	50	29	24	14	49	32	25	18	51	55	50	44	71	61	58	53	72
Year	...	43	36	?	47	42	31	68	45	41	30	65	59	54	52	71	53	47	41	70

* Mean of 29 days.

	90. BOMBAY.						91. POONA.				92. SHOLAPUR.				93. RATNAGIRI.				94. BELGAUM.			
Months.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	66	76	59	56	73	73	39	35	23	73	43	41	26	62	58	43	58	72	49	45	32	79
February	67	76	57	60	74	74	29	24	18	64	33	29	20	49	59	50	58	70	37	29	23	72
March	70	82	63	61	75	79	30	24	16	61	37	31	25	56	67	59	63	78	?	29	30	Imperfect.
April	77	86	70	68	82	84	32	20	18	62	36	31	19	58	69	62	66	80	50	36	38	79
May	74	82	68	67	80	81	42	31	27	67	41	35*	22*	67*	67	60	62	79	60	46	50	75
June	84	89	81	81	86	88	79	71	70	88	62	54	47	86	83	81	82	85	85	81	83	93
July	88	90	86	84	90	89	82	78	76	89	64	58	48	85	86	86	85	86	90	87	88	95
August	84	88	83	79	86	87	75	73	69	90	68	63	53	87	83	82	81	86	85	80	79	97
September	88	93	86	82	89	90	82	77	74	91	72	68	59	88	85	85	85	86	85	80	80	95
October	82	88	79	75	86	85	70	66	61	90	67	60	54	86	78	70	78	85	77	71	68	95
November	71	81	63	61	79	79	50	47	37	88	67	58	58	85	66	53	66	78	60	56	46	90
December	63	69	54	55	72	70	35	28	21	76	49	43	36	68	54	35	56	70	45	40	30	78
Year	76	83	71	69	81	82	54	43	43	78	53	43	39	73	71	64	70	80	?	57	54	?

* Mean of 24 days.

	95. KARWAR.				96. GOPALPORE.				97. VIZAGAPATAM.						98. MASULIPATAM.					99. SECUNDERABAD.				
Months.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	4 hours	10 hours	16 hours	22 hours	From Minima.	Mean.	10 hours	16 hours	22 hours	From Minima.	Mean.	10 hours	16 hours	22 hours	From Minima.
January	65	61	48	85	...	68	67	?	66	72	64	59	68	49	71	64	61	73	88	59	59	38	61	82
February	73	69	59	90	...	70	78	?	63	69	58	57	68	50	73	63	57	82	91	42	41	25	42	64
March	73	65	63	90	...	74	77	?	65	69	58	63	69	55	78	66	68	87	94	48	48	29	53	73
April	74	67	67	88	...	81	84	?	67	71	59	66	70	53	80	65	71	89	96	34	33	20	36	51
May	72	67	66	84	...	81	84	?	68	72	61	67	72	53	80	67	71	85	92	33	32	20	33	49
June	86	84	83	92	...	83	84	?	65	69	61	61	68	51	83	74	72	89	96	68	64	57	73	81
July	88	86	86	92	...	86	86	?	67	70	65	63	69	51	82	75	69	89	96	76	72	64	81	86
August	89	85	84	99	...	83	82	?	70	73	68	68	72	56	74	64	62	82	91	76	72	66	82	86
September	88	86	82	97	...	83	81	?	71	75	70	67	73	56	70	62	55	78	89	80	75	70	86	90
October	86	80	81	98	...	75	72	?	71	74	68	66	74	60	83	73	75	88	96	75	67	63	83	88
November	77	70	68	93	...	67	62	?	62	68	59	56	66	56	77	71	67	82	92	60	52	43	67	86
December	66	57	56	85	...	68	61	?	58	61	52	55	62	44	78	69	69	81	92	48	45	30	52	72
Year	78	73	70	91	...	77	77	?	66	70	62	62	69	53	77	68	66	84	93	58	55	44	62	76

Month.	100. Kurnool. Mean.	10 hours.	16 hours.	From Minima.	101. Bellary. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	102. Mangalore. Mean.	10 hours.	16 hours.	From Minima.	103. Mercara. Mean.	10 hours.	16 hours.	From Minima.	104. Bangalore. Mean.	10 hours.	16 hours.	22 hours.	From Minima.
January	Not recorded.				54	53	35	59	77	63	50	58	80	72	70	56	90	63	60	43	61	94
February	40	34*	24*	69*	37	35	24	45	50	68	56	63	84	61	55	40	87	52	48	32	51	89
March	46	40	26	73	39	38	26	42	53	71	66	63	85	68	58	58	89	55	54	35	55	85
April	54	45	35	71	32	31	20	36	43	78	72	71	91	76	65	73	90	49	50	31	48	72
May	62	55	43	72	40	39	24	45	56	77	71	70	89	83	78	79	92	60	58	42	58	86
June	77	66	59	91	56	51	43	63	65	87	86	83	93	94	93	94	95	70	64	54	71	92
July	83	72	66	94	61	56	49	70	73	91	90	88	95	98	98	97	98	80	75	69	81	92
August	83	71	70	94	66	62	55	70	77	89	86	86	96	94	93	93	96	76	75	65	75	90
September	80	75	63	91	56	55	43	63	68	85	82	79	93	91	88	89	97	70	69	55	68	90
October	82	75	71	94	72	67	59	79	84	85	80	79	95	88	84	84	95	79	74	68	79	93
November	84	65	56	Imperfect.	61	56	42	70	82	74	66	66	90	81	80	73	91	71	68	57	72	93
December	77	70	61	92	52	49	35	58	73	64	53	57	82	77	73	70	87	67	62	51	66	92
Year	?	?	?	?	52	49	38	58	67	78	72	72	89	82	78	76	92	66	63	50	65	89

* Mean of 20 days.

Month.	105. Madras. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	106. Salem. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	107. Wellington. Mean.	10 hours.	16 hours.	22 hours.	From Minima.	108. Coimbatore. Mean.	10 hours.	16 hours.	22 hours.	From Minima.
January	72	63	62	74	88	57	56	44	65	60*	79	71	70	88	83	60	60	40	62	83
February	76	64	65	83	93	58	53	34	56	?	59	45	50	75	73	53	51	32	60	78
March	77	64	69	82	93	56	58	34	57	Imperfect.	63	51	51	75	79	57	59	31	67	84
April	76	59	71	83	91	59	59	39	63	81	63	48‡	52‡	73‡	78‡	62	57	39	74	85
May	70	54	67	79	80	66	64	49	70	84	69	55	62	77	82	70	63	54	78	83
June	68	56	59	79	79	75	72	57	80	90	72	65	68	77	76	70	65	57	75	85
July	72	64	62	80	83	78	77	63	82	89	74	70	68	78	78	74	68	64	78	84
August	73	61	66	81	86	84	81	74	86	89	79	72	74	82	84	75	69	62	79	89
September	68	55	59	81	81	75	75	57	79	89	74	67	69	80	82	70	63	54	77	87
October	87	81	78	92	94	82	81	73	85	88	89	79	84	94	94	78	72	65	84	87
November	79	73	71	85	91	81	78	75	84	86	82	71	82	89	84	76	72	61	84	89
December	78	71	69	82	89	78	75	71	81	81	77	70†	74†	84†	78†	71	67	54	77	86
Year	75	64	67	82	87	71	69	56	74	?	73	64	67	81	81	68	64	51	75	85

* Mean of 30 days.

† Mean of 28 days.
‡ „ „ 29 „

Month.	109. Trichinopoly.					110. Negapatam.					111. Madura.					112. Cochin.				
	Mean.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	22 hours.	From Minima.	Mean.	10 hours.	16 hours.	22 hours.	From Minima.
January	68	61	50	80	86	74	71	69	74	84	64	53	51	65	90	69	58	58	80	83
February	61	56	38	72	91	69	63	62	70	78	62	57	43	65	90	72	60	61	83	86
March	55	52	34	63	82	70	61	61	74	84	Wet bulb thermometer not recorded.					76	71	67	80	87
April	49	48	32	61	72	71	60	64	76	83	Ditto					77	71	69	80	86
May	58	54	40	67	77	67	54	59	74	79	Ditto					82	78	75	84	89
June	61	54	43	75	77	64	51	56	72	77	58	46	44	68	79	88	84	83	91	92
July	62	57	48	74	75	64	53	55	72	77	64	47	49	82	88	90	88	85	93	92
August	64	59	49	70	79	69	60	61	72	82	67	55	49	84	90	89	86	85	92	93
September	60	53	42	70	78	68	57	64	73	80	66	53	49	82	90	84	80	76	86	91
October	79	74	68	85	88	79	75	72	81	87	79	69	68	86	97	86	81	77	92	94
November	76	69	65	83	86	76	73	69	75	86	81	73	72	81	96	81	73	71	89	92
December	73	66	61	81	85	78	74	72	78	87	75	67	65	75	93	76	67	64	84	87
Year	64	59	48	73	81	71	63	64	74	82	?	?	?	?	?	81	75	73	86	89

Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Year.
113. Colombo	73	67	71	72	76	77	75	84	73	74	76	73	74
114. Jaffna	80	73	68	74	80	78	78	80	77	86	84	83	78
115. Trincomalee	76	71	74	68	69	78	70	70	67	74	81	81	73
116. Batticaloa	87	81	83	81	83	71	64	66	71	78	76	82	77
117. Hambantota	80	82	83	85	86	84	83	82	76	84	84	81	83
118. Galle	86	80	79	82	87	95	88	93	88	90	91	87	87
119. Kandy	79	71	67	72	73	77	77	77	73	80	83	80	76
120. Newera Eliya	85	78	74	78	84	90	88	88	85	86	89	80	84

	121. AKYAB.				122. THAYETMYO.				123. TOUNGOO.				124. BASSEIN.				125. DIAMOND ISLAND.			
Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	70	72	54	85	?	63	38	Imperfect	64	67	46	80	71	61	56	96	70	65	61	84
February	67	61	60	81	?	51	27	Imperfect	54	54	36	71	63	54	44	91	70	65	61	85
March	71	63	63	86	49	45	24	78	59	59	38	81	64	56	43	92	74	68	70	85
April	75	70	69	85	61	56	45	81	?	60	47	?	68	58	52	93	76	69*	70	88
May	80	79	77	85	71	67	61	86	?	70	57	?	76	69	67	93	78	74	73	88
June	85	86	84*	85	84	80	80	93‖	79	80	77	80	89	86	86	94	87	84	84	94
July	88	89	87	87	85	82	80	94	85	81	82	91	89	86	86	96	87	82	85	94
August	88	89	88†	87	82	77	77	92	86	81	82	94	88	85	85	95	88	83†	86†	94†
September	84	85	82	86	83	79	76	94	83	77	79	94	?	85	86	Imperfect	87	84	83	94
October	80	80	73	88	81	78	70	95	77	69	68	94	?	79	77	?	82	79	77	91
November	76	76‡	68§	85‡	82	79	73	95	80	76	71	92	?	79	78	?	82	79	77	91
December	77	77	70	84	80	74	72	93	75	72	67	87	78	74	71	89¶	75	70	66	88
Year	78	77	73	85	?	69	60	?	?	71	63	?	?	73	69	?	80	75	75	90

* Mean of 29 days. ‡ Mean of 27 days. ‖ Mean of 28 days. ¶ Mean of 23 days.
† „ 30 „ § „ 25 „

	126. RANGOON.				127. MOULMEIN.				128. MERGUI.				129. PORT BLAIR.				130. NANCOWRY.			
Month.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.	Mean.	10 hours.	16 hours.	From Minima.
January	62	60	43	83	62	58	39	90	76	72	65	92	74	72	72	79	72	68	67	80
February	62	61	43	83	68	68	43	94	74	64	59	98	76	75	68	86	72	64	63	83
March	66	65	49	85	68	63	51	91	75	65	63	97	77	73	67	90	72	64	65	86
April	73	72	60	87	72	68	56	91	79	71	72	95	77	73	68	91	73	69	69	87
May	80	77	74	89	79	76	68	93	84	79	76	96	84	82	79	92	76	72	72	85
June	88	87	85	91	90	89	86	95	91	89	88	97	86	85	83	90	78	75	76	84
July	90	87	91	91	91	91	88	95	92	90	90	96	86	86	85	86	?	73	74	?
August	89	87	89	91	89	89	84	95	92	89	90	96	87	86	85	89	?	83	81	?
September	88	87	85	92	89	89	83	95	90	89	87	95	88	88	86	92	?	83	81	?
October	80	79	71	91	75	75	67	84	84	77	78	96	85	83	82	83	?	76	76*	?
November	80	80	73	87	75	69	62	93	79	69	72	95	84	83	81	88	?	80	83	?
December	70	69	58	84	67	60	50	90	74	61	68	93	84	84	82	87	?	76	77	?
Year	77	76	68	88	77	75	65	92	83	76	76	96	82	81	78	88	?	73	74	?

* Mean of 30 days.

TABLE XIII.—MEAN PROPORTION OF CLOUDED SKY IN 1883 (127 STATIONS).

Month.	1. Zanzibar. Mean.	10 hours.	16 hours.	2. Aden. Mean.	10 hours.	16 hours.	3. Quetta. Mean.	10 hours.	16 hours.	4. Leh. Mean.	6 hours.	10 hours.	16 hours.	22 hours.	5. Mooltan. Mean.	10 hours.	16 hours.	6. Dera Ismail Khan. Mean.	10 hours.	16 hours.
January	4·95	6·19*	3·70*	3·74	5·42	2·06	5·20	5·00	5·39	7·21	...	6·84	7·58	...	3·06	2·93	3·19	3·28	3·26	3·29
February	3·35	3·70†	3·00‡	4·81	6·50	3·11	4·48	3·75	5·21	7·09	...	7·07	7·11	...	2·73	2·57	2·89	2·27	2·03	2·50
March	4·64	5·20§	4·07§	4·37	6·35	2·39	5·42	4·42	6·42	6·84	...	6·32	7·35	...	2·73	2·10	3·36	3·29	3·06	3·52
April	4·76	4·81‡	4·71‡	3·42	4·13	2·70	5·69	4·61	6·77	6·54	...	6·40	6·67	...	1·68	1·63	1·73	3·53	3·03	4·03
May	6·51	6·20	6·81	3·15	3·55	2·74	1·62	1·00	2·23§	7·91	...	7·52	8·29	...	0·97	1·23	0·71	2·44	2·00	2·87
June	4·10	4·07	4·13	1·87	1·60	2·13	1·38	0·66	2·10	4·15	...	3·87	4·43	...	0·30	0·23	0·37	2·74	1·67	3·80
July	5·95	6·06	5·84	3·49	3·71	3·26	2·91	2·10	3·71	3·52	...	3·26	3·77	...	1·90	1·71	2·09	2·12	1·52	2·71
August	4·89	4·81	4·97	2·37	2·81	1·94	1·02	0·55	1·48	4·19	...	4·06	4·32	...	0·98	0·64	1·32	1·41	1·10	1·71
September	4·34	4·97	3·70	2·12	2·30	1·94	0·45	0·26‖	0·64¶	3·44	3·40	3·67	4·00	2·70	0·90	0·80	1·00	1·29	1·30	1·27
October	4·39	5·29	3·48	1·89	2·48	1·29	0·33	0·39	0·26	4·76	4·45	4·39	7·35	2·84	0·44	0·89	0·48	0·87	0·68	1·06
November	4·13	5·53	2·73	2·75	3·33	2·17	0·62	0·56	0·67	5·53	4·80	6·10	7·12**	4·11**	0·43	6·13	0·73	0·95	0·67	1·23
December	3·79	5·58	2·00	3·63	4·77	2·48	3·26	2·42	4·10	5·19	5·29	3·61	7·97	3·89	0·97	0·97	0·97	1·97	2·00	1·93
Year	4·65	5·20	4·10	3·13	3·91	2·35	2·70	2·14	3·25	5·53	...	5·26	6·33	...	1·42	1·28	1·57	2·18	1·86	2·49

* Mean of 27 days.
† „ „ 20 „
‡ „ „ 21 „
§ „ „ 30 „
‖ Mean of 23 days.
¶ „ „ 22 „
** Mean of 29 days.

Month.	7. Peshawar. Mean.	10 hours.	16 hours.	8. Murree. Mean.	10 hours.	16 hours.	9. Rawalpindi. Mean.	10 hours.	16 hours.	10. Sialkot. Mean.	10 hours.	16 hours.	11. Lahore. Mean.	4 hours.	10 hours.	16 hours.	22 hours.	12. Ludhiana. Mean.	10 hours.	16 hours.
January	5·89	6·26	5·52	7·02	6·90	7·13	4·68	4·84	4·52	6·00	5·71	6·29	3·34	3·22	3·90	4·03	2·22	4·33	3·94	4·71
February	3·54	3·50	3·57	4·48	4·53	4·43	3·00	2·75	3·25	3·52	3·82	3·21	2·63	3·00	2·11	3·03	2·36	3·07	2·96	3·18
March	5·04	4·55	5·52	6·23	5·58	6·87	3158	3·55	3·61	4·54	4·52	4·55	2·69	3·00	2·42	3·48	1·87	3·71	3·39	4·03
April	5·40	3·77	7·03	6·60	5·80	7·40	3·70	3·37	4·03	4·57	3·73	5·40	2·76	3·13	2·33	3·53	2·03	2·48	1·43	3·53
May	1·76	1·09	2·42	4·33	3·26	5·40	2·05	1·71	2·39	3·03	2·64	3·42	1·95	1·74	1·93	2·52	1·61	0·38	1·23	1·52
June	2·55	1·57	3·53	3·43	3·23	3·63	1·67	1·97	1·37	1·47	2·00	0·93	2·63	2·33	2·70	2·90	2·57	1·70	1·50	1·90
July	3·19	3·06	3·32	5·34	5·81	4·87	2·95	3·45	2·45	3·50	3·52	3·48	3·46	4·48	3·03	4·13	2·19	4·63	4·26	5·00
August	2·53	2·29	2·77	5·57	5·68	5·45	2·53	2·64	2·42	3·23	3·45	3·00	2·58	2·29	2·00	4·39	1·64	3·53	2·58	4·48
September	1·77	0·60	2·93	3·82	3·83	3·80	2·05	2·53	1·57	2·94	3·07	2·80	1·93	2·07	2·33	2·07	1·23	3·24	3·10	3·37
October	2·11	1·03	3·19	2·97	2·81	3·13	1·89	1·77	2·00	1·13	1·00	1·26	0·44	0·61	0·32	0·52	0·32	0·94	1·13	0·74
November	1·85	1·60	2·10	2·99	2·80	3·17	2·55	2·03	3·06	2·32	2·07	2·57	1·15	1·07	1·03	1·47	1·03	1·70	1·73	1·67
December	3·04	2·52	3·55	4·00	3·52	4·48	2·26	2·24*	2·28*	3·21	3·19	3·23	1·53	1·55	1·65	1·97	0·93	2·47	2·55	2·39
Year	3·22	2·65	3·79	4·73	4·48	4·96	2·74	2·74	2·75	3·29	3·23	3·35	2·26	2·37	2·15	2·84	1·67	2·77	2·48	3·04

* Mean of 29 days.

TABLE XIII.—MEAN PROPORTION OF CLOUDED SKY IN 1883.

Month.	13. Kailang. Mean.	10 hours.	16 hours.	14. Simla. Mean.	10 hours.	16 hours.	15. Delhi. Mean.	10 hours.	16 hours.	16. Sirsa. Mean.	10 hours.	16 hours.	17. Chakrata. Mean.	10 hours.	16 hours.	18. Dehra. Mean.	9-30 hours.	15-30 hours.
January	Not recorded.			6·26	5·39	7·13	2·73	2·42	3·03	4·78	4·29	5·26	6·02	5·19	6·84	5·16	4·84	5·48
February				4·36	3·46	5·25	1·91	1·71	2·11	3·27	3·18	3·36	3·17	3·04	3·29	2·86	2·89	2·82
March				5·55	5·36	5·74	2·77	2·64	2·90	4·53	4·16	4·90	4·81	4·23	5·39	4·53	4·32	4·74
April				3·70	2·87	4·53	1·12	0·50	1·73	3·07	2·23	3·90	3·20	2·37	4·03	2·57	1·83	3·30
May				3·74	3·34*	4·14*	1·50	1·29	1·71	2·05	1·13	2·97	2·71	2·68	2·74	2·00	1·45	2·55
June				4·47	3·00	5·93	2·79	2·80	2·77	3·04	2·97	3·10	4·75	3·50	6·00	4·10	3·80	4·40
July	5·74	5·38*	6·10†	8·06	7·77	8·35	6·08	5·93	6·23	5·10	4·81	5·39	8·83	8·55	9·10	7·84	7·58	8·10
August	5·31	4·87	5·74	6·65	6·29	7·00	4·11	3·03	5·19	3·39	2·97	3·81	7·68	6·61	8·74	6·40	6·35	6·45
September	4·49	3·87	5·10	5·87	5·53	6·20	3·92	3·30	4·53	4·15	3·60	4·70	7·07	5·87	8·27	5·52	4·97	6·07
October	4·32	2·74	5·90	1·66	1·64	1·68	1·21	0·97	1·45	1·16	1·19	1·13	0·94	0·61	1·26	0·82	0·45	1·19
November	4·75	4·20	5·30	3·22	2·90	3·53	1·45	1·10	1·80	1·82	1·70	1·93	2·68	2·93	2·43	2·17	2·50	1·83
December	4·77	4·26	5·27†	2·27	2·19	2·35	1·26	0·87	1·65	2·02	1·58	2·45	2·34	2·26	2·42	2·28	2·26	2·29
Year	...	...	...	4·65	4·15	5·15	2·57	2·21	2·93	3·20	2·82	3·58	4·52	3·99	5·04	3·85	3·60	4·10

* Mean of 29 days. † Mean of 30 days.

Month.	19. Paori. Mean.	10 hours.	16 hours.	20. Roorkee. Mean.	10 hours.	16 hours.	21. Ranikhet. Mean.	10 hours.	16 hours.	22. Pithoragarh. Mean.	10 hours.	16 hours.	23. Meerut. Mean.	10 hours.	16 hours.	24. Bareilly. Mean.	10 hours.	16 hours.
January	4·97	4·65	5·29	4·73	4·00	5·45	5·19	4·61	5·77	4·49	3·81	5·16	3·71	3·52	3·90	3·16	2·74	3·58
February	3·52	3·39	3·64	2·68	2·75	2·60	3·05	3·14	2·96	3·06	3·04	3·07	2·46	2·14	2·78	2·81	2·57	3·04
March	5·39	4·97	5·81	0·35	0·35	0·35	4·35	3·35	5·35	3·74	3·10	4·37*	3·26	3·45	3·06	3·25	3·10	3·39
April	3·02	1·53	4·50	1·82	1·50	2·13	1·84	1·20	2·47	2·74	1·70	3·77	1·04	0·77	1·30	0·98	0·63	1·33
May	3·10	2·58	3·61	1·76	1·77	1·74	3·23	2·52	3·94	3·69	2·68	4·70*	1·81	1·84	1·77	1·70	1·87	1·52
June	4·07	4·07	4·07	2·62	2·90	2·33	4·94	4·47	5·40	5·00	4·87	5·13	2·35	2·57	2·13	2·24	2·40	2·07
July	8·25	8·13	8·37*	7·13	7·22	7·03	9·16	9·13	9·19	7·65	7·94	7·35	6·26	6·35	6·16	7·00	7·61	6·39
August	6·50	6·84	6·16	4·93	5·12	4·74	7·21	7·39	7·03	6·90	7·35	6·45	4·40	3·77	5·03	5·94	5·77	6·10
September	5·68	6·03	5·33	4·00	4·16	3·83	6·42	6·63	6·20	6·02	5·90	6·13	3·38	3·10	3·66	4·90	5·43	4·37
October	1·19	0·80*	1·57*	0·68	0·58	0·77	1·60	1·32	1·87	1·83	1·52	2·13	0·29	0·26	0·32	0·61	0·48	0·74
November	2·27	2·40	2·13	1·52	1·40	1·63	1·94	1·50	2·37	1·83	1·48†	2·17†	1·14	1·17	1·10	0·60	0·80	0·40
December	Abolished.			1·50	1·45	1·55	1·60	1·77	1·42	1·89	1·77	2·00	1·07	0·97	1·16	0·68	0·68	0·68
Year	?	?	?	2·81	2·77	2·85	4·21	3·92	4·50	4·07	3·76	4·37	2·60	2·49	2·70	2·82	2·84	2·80

* Mean of 30 days. † Mean of 29 days.

	25. AGRA.			26. LUCKNOW:			27. GORAKHPUR.			28. JHANSI.			29. ALLAHABAD.				30. BENARES.		
MONTH.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean.	10 hours.	16 hours.
January	3·21	2·77	3·65	2·84	2·35	3·32	1·83	1·84	1·81	1·83	1·81	1·84	2·25	2·06	2·26	3·06	1·61	2·68	2·52	2·84
February	2·50	2·14	2·86	2·49	2·86	2·11	1·57	1·57	1·57	0·34	0·68	0	2·71	2·75	2·36	3·14	2·57	2·50	2·04	2·96
March	3·39	2·61	4·16	3·07	3·26	2·87	2·34	2·32	2·35	0·52	0·35	0·68	2·33	2·58	2·90	2·52	1·32	2·13	2·10	2·16
April	0·73	0·46	1·00	0·74	0·67	0·80	0·75	0·50	1·00	0	0	0	0·68	0·47	0·87	0·97	0·40	0·65	0·50	0·80
May	2·00	2·16	1·84	1·16	1·09	1·22	0·82	0·61	1·03	0·41	0·23	0·58	1·33	1·03	1·13	1·30	1·87	1·15	1·03	1·26
June	3·65	2·27	5·03	4·16	3·74	4·57	4·32	4·30	4·33	2·00	1·73	2·27	5·27	4·47	6·03	5·59	4·97	5·73	5·53	5·93
July	7·21	7·23	7·19	7·50	7·42	7·58	4·97	5·23	4·71	3·82	4·29	3·32	7·37	6·71	7·77	7·84	7·17*	7·53	7·32	7·74
August	4·47	3·48	5·45	6·62	6·68	6·55	4·50	4·94	4·06	2·16	1·45	2·87	6·41	6·07*	7·68	7·35	4·52	6·86	6·94	6·77
September	4·53	3·53	5·53	4·58	5·03	4·13	4·17	4·27	4·07	1·87	1·37	2·37	5·26	4·03	6·03	5·73	5·23	5·54	5·57	5·50
October	0·94	0·58	1·29	1·18	0·97	1·39	1·44	1·19	1·68	0·74	0·71	0·77	2·32	2·23	2·68	2·16	2·19	2·24	2·35	2·13
November	0·77	0·40	1·13	0·09	0·17	0	0	0	0	0	0	0	0·21	0·30	0·30	0·13	0·10	0·37	0·30	0·43
December	0·29	0	0·58	0·45	0·45	0·45	0·32	0·16	0·48	0	0	0	0·56	0·48	0·77	0·65	0·32	0·79	0·68	0·90
Year	2·81	2·30	3·31	2·91	2·89	2·92	2·25	2·24	2·26	1·14	1·05	1·23	3·06	2·77	3·40	3·37	2·69	3·18	3·07	3·29

* Mean of 30 days.

	31. GHAZIPUR.			32. KATMANDU.			33. SIBSAGAR.			34. DHUBRI.			35. TURA.			36. SILCHAR.		
MONTH.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	2·67	2·65	2·68	5·23	5·55	4·90	5·47	6·45	4·48	2·53	3·06	2·00	Not recorded.			2·36	2·52	2·19
February	2·46	1·92	3·00	2·36	2·64	2·07	5·61	5·86	5·36	1·20	1·04	1·36				2·50	2·00	3·00
March	2·05	2·22	1·87	4·66	4·81	4·51	6·63	7·26	6·00	2·44	2·23	2·65				4·44	4·77	4·10
April	0·65	0·43	0·86	5·90	5·90	5·90	5·79	6·47	5·10	3·12	3·90	2·33				4·29	4·27	4·30
May	0·97	0·87	1·06	5·84	5·65	6·03	7·94	7·97	7·90	5·76	7·00	4·52				7·99	8·03	7·94
June	5·62	5·23	6·00	6·52	6·23	6·80	8·87	9·40	8·33	7·25	7·80	6·70	6·64	7·04†	6·23	8·57	8·63	8·50
July	6·95	6·74	7·16	6·58	5·55	7·61	7·71	8·61	6·81	6·67	6·65	6·68	6·38	7·03	5·73	7·73	7·84	7·62
August	6·66	6·77	6·54	8·00	7·71	8·29	8·83	9·26	8·39	7·35	7·35	7·35	8·18	8·61	7·74	8·55	8·81	8·29
September	5·20	5·37	5·03	7·05	6·50	7·60	8·00	8·50	7·50	6·08	6·23	5·93	6·19	7·57	4·80	7·65	8·17	7·13
October	2·62	2·70	2·54	2·99	3·29	2·68	4·54	5·13	3·94	1·46	1·29*	1·63	2·87	3·06	2·68	4·17	4·81	3·52
November	0·47	0·23	0·70	1·77	2·73	0·80	4·37	5·03	3·70	0·42	0·53	0·30	1·08	0·83	1·33	3·95	4·97	2·93
December	0·67	0·51	0·83	2·17	3·81	0·52	4·69	5·19	4·19	1·62	1·68	1·55	2·41	1·71	3·10	3·79	4·32	3·26
Year	3·08	2·97	3·19	4·92	5·03	4·81	6·54	7·09	5·98	3·83	4·06	3·58	...	...	...	5·50	5·76	5·23

* Mean of 30 days. † Mean of 27 days.

Month.	37. Darjeeling (St. Paul's School.)			38. Purneah.			39. Durbhunga.			40. Patna.			41. Gya.			42. Hazaribagh.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	4·39	3·74	5·03	1·67	1·73†	1·61	2·13	2·13	2·13	3·08	3·26	2·90	3·57	3·81	3·32	2·52	2·55	2·48
February	4·60	3·64	5·56*	1·25	1·29	1·21	1·49	1·36	1·61	2·77	2·50	3·04	3·63	3·64	3·61	2·57	1·75	3·39
March	4·56	4·47†	4·65‡	2·00	1·90	2·10	1·78	1·84	1·71	3·31	3·29	3·32	3·42	2·87	3·97	3·53	3·00	4·06
April	5·86	6·18§	5·54§	1·55	2·43	0·67	0·88	1·20	0·56	0·84	0·80	0·87	0·60	0·67	0·53	1·39	0·60	2·17
May	7·11	7·47†	6·74*	3·78	4·71	2·84	2·11	2·61	1·61	1·84	1·94	1·74	1·58	1·48	1·68	3·69	2·48	4·90
June	8·60	9·03	8·17‖	6·97	7·57	6·37	5·72	5·97	5·47	7·24	7·10	7·37	7·30	6·70	7·90	8·52	8·07	8·97
July	8·38	8·58	8·17†	8·23	8·74	7·71	6·46	6·65	6·26	8·71	8·90	8·52	9·39	9·23	9·55	9·41	9·39	9·42
August	9·62	9·65	9·58	8·66	8·97‖	8·34‖	6·05	6·35	5·74	8·18	8·19	8·16	9·97	9·97	9·97	9·75	9·94	9·55
September	8·72	8·80	8·63*	7·25	8·00	6·50	5·57	6·20	4·93	6·37	6·50	6·23	8·00	8·17	7·83	8·37	8·37	8·37
October	5·22	5·70*	4·74¶	3·15	3·39	2·90	2·46	2·52	2·39	3·32	3·00	3·64	2·90	2·77	3·03	2·95	2·48	3·42
November	3·66	2·83‖	4·48‖	0·45	0·43	0·47	0·25	0·33	0·17	0·50	0·40	0·60	1·00	1·00	1·00	1·42	1·20	1·63
December	2·39	2·16	2·61	1·23	1·65	0·81	0·28	0·23	0·32	0·94	0·77	1·10	0·54	0·65	0·42	1·91	1·71	2·10
Year	6·09	6·02	6·16	3·85	4·23	3·46	2·93	3·12	2·74	3·93	3·89	3·96	4·33	4·23	4·40	4·67	4·30	5·04

* Mean of 27 days.
† „ „ 30 „
‡ „ „ 26 „
§ „ „ 28 „
‖ „ „ 29 „
¶ „ „ 23 „

Month.	43. Berhampore.			44. Burdwan.			45. Jessore.			46. Dacca.			47. Chittagong.			48. Demagiri.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	1·71	1·42	2·00	2·15	1·74	2·55	1·67	1·39	1·94	1·00	0·90	1·10	1·33	0·84	1·81	0·33	0·65	0
February	1·91	1·57	2·25	2·38	2·14	2·61	2·20	2·39	2·00	1·81	1·93	1·68	2·04	1·71	2·36	1·27	1·29	1·25
March	2·81	2·74	2·87	2·87	3·19	2·55	3·68	3·58	3·77	2·52	2·65	2·39	4·18	4·84	3·52	2·48	2·61	2·35
April	2·77	2·73	2·80	2·52	2·13	2·90	4·18	4·53	3·83	4·08	4·52†	3·63	4·65	5·53	3·77	2·75	2·83	2·67
May	5·86	5·52	6·19	4·49	3·94	5·03	6·76	6·77	6·74	6·42	7·48	5·35	5·86	5·87	5·84	6·11	6·06	6·16
June	8·69	8·50	8·87	7·75	7·37	8·13	8·72	8·63	8·80	7·64	8·10	7·17	7·60	7·37	7·83	7·27	7·27	7·27
July	9·13	9·45	8·81	8·96	9·16	8·76	9·69	9·61	9·77	6·65	7·48	5·81	7·58	7·06	8·10	7·15	5·45	8·84
August	9·47	9·68	9·26	9·29	9·10	9·48	9·34	9·26	9·42	7·71	8·29	7·13	7·31	7·32	7·29	7·50	7·06	7·94
September	7·73	8·23	7·23	7·82	8·00	7·63	8·50	8·67	8·33	6·29	6·67	5·90	6·70	6·67	6·73	6·70	6·39	7·00
October	3·33	3·26	3·39	3·02	2·58	3·45	3·55	3·42	3·68	2·45	2·58	2·32	3·13	3·16	3·10	3·20	4·00	2·39
November	1·43	1·03	1·83	1·72	1·50	1·93	2·94	2·30	3·57	1·97	1·77	2·17	3·02	2·83	3·20	2·10	1·90	2·30
December	2·13	1·94	2·32	2·16	2·29	2·03	2·96	2·84	3·07*	2·42	1·97	2·87	3·81	3·52	4·10	2·53	2·71	2·35
Year	4·75	4·67	4·82	4·59	4·43	4·75	5·35	5·29	5·41	4·25	4·53	3·96	4·77	4·73	4·80	4·12	4·02	4·21

* Mean of 30 days. † Mean of 29 days.

Month.	49. Calcutta (Alipore).					50. Saugor Island.					51. Cuttack.			52. False Point.			53. Sambalpur.		
	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Mean.	6 hours	10 hours.	16 hours.	22 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	1·66	1·52	1·81	1·97	1 32	1·25	0·71	1·84	1·45	0·98	2·00	1·81	2·19	1·77	2·19	1·35	1·67	1·68	1·65
February	2·43	2·82	2·43	2·54	1·93	2·50	1·79	3·57	2·96	1·68	2·79	2·68	2·89	3·52	4 07	2·96	1·56	1·53	1·58
March	3·42	4·19	3·39	2·65	3·45	3·19	1·94	4·32	4·42	2·06	3·62	2·65	4·58	2·65	2·35	2·94	2·05	1·78	2·32
April	3·12	3·80	3·13	2·03	3·53	4·26	3·23	4·60	4·03	5·17	2·59	1·47	3·70	3·32	3·07	3·57	1·39	0·67	2·11
May	4·49	4·68	5·00	3·61	4·65	5·26	5·32	6·74	3·94	5·03	3·74	3·16	4·32	3·95	4·35	3·55	2·00	1·03	2·97
June	7·94	7·60	7·87	8·40	7 87	6 96	6·70	6·90	7·27	6·97	7·82	7·43	8·20	7·62	7·73	7·50	6·17	5·43	6·90
July	8·76	8·48	9·06	9·00	8·48	7·90	7·97	7·58	8·10	7·94	8·44	8·45	8·42	8·50	8·55	8·45	7·84	7·58	8·10
August	8·78	8·13	9·13	9·06	8·81	8·20	8·77	7·65	7·81	8·55	7·47	7·19	7·74	8·04	7·94	8·13	7·00	6·71	7·29
September	8·17	7·67	8·70	8·33	7·97	7·28	8·30	7·63	6·93	6·27	6·95	6·87	7·03	7·32	7·30	7·33	5·99	6·30	5·67
October	3·10	3·00	3·23	3·65	2·52	3·94	3·00	5·06	4·74	2·94	4·33	3·94	4·71	5·04	5·42	4·65	2·41	2·26	2·55
November	1·81	2·07	1·73	1·87	1·57	1·91	1·60	2·10	2·70	1·23	1·44	1·57	1·30	2·90	2·67	3·13	0·13	0·13	0·12
December	2·03	2·26	1·94	2·45	1·48	2·99	2·35	3·42	4·23	1·94	2·20	2·00	2·39	2·60	2·32	2·87	1·40	1·08	1·72
Year	4·64	4·69	4·79	4·63	4·47	4·64	4·31	5·13	4·88	4·23	4·45	4·10	4·79	4·77	4·83	4·70	3·30	3·02	3·58

Month.	54. Raipur.			55. Nagpur.			56. Seoni.			57. Jubbulpore.			58 Saugor.			59. Pachmarhi.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	1·94	1·84	2·03	2·97	2·58	3·35	3·26	2·94	3·58	2·97	2·55	3·39	3·92	3·42	4·42	3·46	2·94	3·97
February	1·41	1·21	1·61	3·20	2·46	3·93	2·68	2·32	3·04	2·68	1·89	3·46	3·09	2·75	3·43	2·81	2·04	3·57
March	2·58	2·06	3·10	2·87	2·00	3·74	2·96	2·39	3·52	3·02	2·32	3·71	3·34	2·68	4·00	2·29	2·32	2·26
April	2·00	0·73	3·27	3·25	1·43	5·07	2·87	2·07	3·67	2·82	1·47	4·17	2·49	1·47	3·50	3·00	2·33	3·67
May	1·76	1·16	2·35	3·66	2·42	4·90	3·02	2·58	3·45	2·26	1·29	3·23	2·54	1·84	3·23	2·23	1·65	2·81
June	7·85	6·87	8·83	7·97	7·33	8·60	4·64	3·50	5·77	6·22	4·73	7·70	5·58	4·33	6·83	7·38	6·93	7·83
July	8·73	8·90	8·55	8·66	8·87	8·45	4·94	4·61	5·26	9·15	9·39	8·90	7·18	7·29	7·06	9·34	9·61	9·06
August	7·31	7·19	7·42	7·48	7·06	7·90	3·73	3·23	4·23	6·71	6·35	7·06	5·92	5·35	6·48	7·92	8·06	7·77
September	8·10	8·53	7·67	8·42	8·37	8·47	4·85	4·26	5·43	7·59	7·67	7·50	5·65	5·67	5·63	8·82	8·70	8·93
October	3·42	3·19	3·65	3·86	2·97	4·74	3·25	2·97	3·52	3·81	3·39	4·23	3·53	3·03	4·03	4·41	3·84	4·97
November	1·45	1·60	1·30	1·09	1·27	0·90	2·27	2·30	2·23	1·52	1·03	2·00	1·18	0·83	1·53	1·72	1·53	1·90
December	0·65	0·77	0·52	0·78	0·42	1·13	2·24	2·16	2·32	1·16	0·97	1·35	0·84	0·71	0·97	1·21	0·94	1·48
Year	3·93	3·67	4·19	4·52	3·93	5·10	3·39	2·94	3·84	4·16	3·59	4·73	3·77	3·28	4·26	4·55	4·24	4·85

Month.	60. Hoshangabad.			61. Khandwa.			62. Chanda.			63. Sironcha.			64. Chikalda.			65. Buldana.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	2·73	2·48	2·97	3·16	2·87	3·45	1·95	0·90	3·00	2·05	1·68	2·42	2·82	2·35	3·29	3·32	2·90	3·74
February	1·56	0·93	2·18	2·34	1·75	2·93	1·95	1·21	2·68	1·13	0·61	1·64	1·50	1·32	1·68	2·45	2·11	2·79
March	2·02	1·84	2·19	2·29	2·16	2·42	2·33	1·52	3·13	3·12	2·58	3·65	1·52	1·06	1·97	2·52	2·13	2·19
April	2·14	1·10	3·17	1·77	1·43	2·10	2·12	1·00	3·23	1·77	1·33	2·20	2·35	1·60	3·10	2·32	1·57	3·07
May	2·03	1·03	3·03	2·18	1·58	2·77	2·11	1·61	2·61	2·32	1·16	3·48	1·86	1·45	2·26	2·04	1·55	2·52
June	5·53	4·83	6·23	6·73	6·73	6·73	7·47	7·23	7·70	7·35	7·27	7·43	8·30	8·13	8·47	6·90	6·80	7·00
July	8·08	8·55	7·61	8·06	8·06	8·06	7·81	8·03	7·58	7·47	7·68	7·26	9·20	9·55	8·84	7·84	8·23	7·45
August	6·73	6·26	7·19	6·92	7·03	6·81	7·18	6·32	8·03	6·68	6·32	7·03	6·50	6·58	6·42	7·05	7·03	7·06
September	7·52	8·07	6·97	7·70	8·10	7·30	7·53	7·43	7·63	7·35	7·80	6·90	9·00	9·13	8·87	7·92	8·40	7·43
October	3·81	3·39	4·23	4·45	4·00	4·90	3·02	2·77	3·26	3·49	3·13	3·84	4·21	3·35	5·06	4·77	4·48	5·06
November	0·80	0·40	1·20	1·30	0·97	1·63	1·54	1·40	1·67	1·38	1·33	1·43	1·37	1·47	1·27	2·32	2·17	2·47
December	0·71	0·58	0·84	1·18	1·06	1·29	2·07	1·65	2·48	1·99	2·03	1·94	1·07	0·84	1·29	1·92	1·68	2·16
Year	3·64	3·29	3·98	4·01	3·81	4·20	3·92	3·42	4·42	3·84	3·58	4·10	4·14	3·90	4·38	4·28	4·09	4·47

Month.	66. Akola.			67. Amraoti.			68. Makhla.			69. Neemuch.			70. Nowgong.			71. Sutna.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	2·15	1·55	2·74	2·94	2·42	3·45	3·58	2·55	4·61	3·60	3·35	3·84	3·92	3·71	4·13	3·11	3·03	3·19
February	1·14	0·71	1·57	2·63	2·36	2·89	2·66	1·75	3·57	3·82	3·71	3·93	3·32	3·25	3·39	2·29	1·93	2·64
March	1·02	0·87	1·16	2·10	1·65	2·55	2·46	1·68	3·23	3·78	3·55	4·00	3·39	2·81	3·97	2·00	1·61	2·39
April	1·29	1·07	1·50	2·17	1·10	3·23	4·27	3·70	4·83	1·50	1·13	1·87	2·10	1·20	3·00	1·54	0·77	2·30
May	1·29	1·23	1·35	2·26	2·06	2·45	2·72	2·21	3·23	2·09	1·65	2·52	3·36	1·81	4·90	1·62	0·94	2·29
June	7·02	6·90	7·13	7·68	7·33	8·03	8·39	7·97	8·80	5·67	5·23	6·10	5·95	4·47	7·43	4·62	3·99	5·33
July	7·55	8·03	7·06	8·56	8·77	8·35	9·08	9·32	8·84	8·91	9·26	8·55	8·68	8·58	8·77	6·79	6·84	6·74
August	6·58	6·42	6·74	7·38	7·10	7·65	8·02	8·29	7·74	6·50	6·26	6·74	7·42	6·68	8·16	5·58	5·13	6·03
September	8·00	7·53	8·47	8·44	8·70	8·17	9·34	9·28	9·40	7·35	6·87	7·83	6·05	5·77	6·33	4·80	5·13	4·46
October	3·10	2·58	3·61	4·54	4·26	4·81	4·84	3·87	5·81	3·42	1·61	5·23	3·26	2·42	4·10	2·48	2·35	2·61
November	0·85	0·80	0·90	1·14	1·10	1·17	2·87	1·60	4·13	1·05	0·73	1·37	0·77	0·40	1·13	0·35	0·20	0·50
December	0·24	0·13	0·35	1·61	1·35	1·87	2·42	1·35	3·48	1·57	1·00	2·13	1·13	0·87	1·39	0·63	0·68	0·58
Year	3·35	3·15	3·55	4·29	4·02	4·55	5·05	4·46	5·64	4·11	3·70	4·51	4·11	3·50	4·73	2·98	2·71	3·26

	72. INDORE.			73. BICKANEER.			74. JEYPORE.				75. SAMBHAR.			76. AJMERE.			77. MT. ABU.		
MONTH.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	3·31	2·97	3·65	4·03	3·87	4·19	3·06	2·51	3·32	4·02	2·38	3·18	3·19	3·16	1·83	1 68	1·97	3·15	3·03	3·26
February	2·22	2·11	2·32	3·72	3·64	3·79	3·06	2·82	2·77	3·42	3·22	2·52	2·36	2·68	1·50	1·29	1·71	2·93	2·71	3·14
March	2·42	2·35	2·48	4·60	4·06	5·13*	3·07	2·38	3·35	3·74	2·80	2·55	2·16	2·94	1·44	0·94	1·93	3·29	3·16	3·42
April	1·82	1·33	2·30	2·57	1·54†	3·60	1·48	0·83	1·13	2·66	1·30	0·94	0·60	1·27	0·45	0·37	0·53	1·15	0·83	1·47
May	1·68	1·58	1·77	2·48	1·62‡	3·33‡	1·97	2·29	1·32	2·77	1·48	1·23	0·68	1·77	0·58	0·39	0·77	2·02	2·00	2·03
June	7·47	6·87	8·07	1·99	1·08§	2·89§	3·49	3·60	2·90	3·96	3·50	2·94	2·40	3·47	1·60	1·47	1·73	5·03	5·73	4·33
July	9·24	9·35	9·13	6·28	5·48	7·07*	6·97	6·96	7·58	7·51	5·83	5·89	5·77	6·00	4·44	4·74	4·13	9·00	9·13	8·87
August	8·32	8·35	8·29	3·29	2·90	3·67*	3·68	2·58	3·90	5·32	2·90	3·28	2·61	3·94	1·97	2·00	1·94	5·70	6·26	5·13
September	8·27	7 93	8·60	5·72	4·77	6·67	4·93	3·77	3·86	6·43	5·66	4·62	4·40	4·83	3·70	3·83	3·57	7·04	6·70	7·37
October	4·39	3·87	4·90	3·13	1·81	4·45	2·61	2·38	2·06	3·74	2·25	1·55	0·90	2·19	1·39	0·81	1·97	2·52	1·90	3·13
November	0·65	0·27	1·03	1·27	1·13	1·40	1·33	1·10	1·26	1·83	1·13	0·95	0·83	1·07	0·69	0·57	0·80	1·24	1·10	1·37
December	0·68	0·65	0·71	1·42	0·94	1·90*	0·80	0·16	0·67	1·61	0·77	0·69	0·48	0·90	0·37	0·26	0·48	0·95	0·58	1·32
Year	4·21	3·97	4·44	3·38	2·74	4·01	3·04	2·62	2·84	3·92	2·77	2·53	2·20	2·85	1·66	1·53	1·79	3·67	3·59	3·74

* Mean of 30 days.
† " " 26 "
‡ " " 24 "
§ " " 28 "
‖ " " 25 "

	78. PACHBUDRA.			79. JACOBABAD.			80. HYDERABAD.			81. KURRACHEE.			82. BHUJ.			83. RAJKOT.		
MONTH.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	1·90	1·90	1·90	1·94	1·87	2·00	1·52	1·84	1·19	2·52	2·32	2·71	1·78	1·81	1·74	1·05	1·10	1·00
February	1·77	1·46	2·07	2·61	3·00	2·21	2·04	2·43	1·64	3·79	3·25	4·32	2·06	2·07	2·04	1·25	1·29	1·21
March	1·87	1·13	2·61	2·23	2·55	1·90	0·95	1·00†	0·90	2·89	2·51	3·26	2·79	3·32	2·26	1·76	1·84	1·68
April	0·37	0·23	0·50	1·35	1·33	1·37	0·60	0·80	0·40	1·63	1·60	1·66	0·54	0·50	0·57	0·52	0·40	0·63
May	1·95	1·45	2·45	0·48	0·61	0·35	0·53	0·61	0·45	2·84	2·68	3·00	1·29	1·23	1·35	1·32	1·32	1·32
June	2·70	2·13	3·27	0·25	0·30	0·20	1·19	1·27	1·10	4·19	3·97	4·40	3·85	4·00	3·70	5·17	4·17	6·17
July	5·82	6·32	5·32	2·32	2·19	2·45	3·29	3·68	2·90	7·89	8·23	7·55	8·84	8·81	8 87	8·20	7·94	8·45
August	5·23	6·00	4·45	0·47	0·71	0·23	0·96	0·94	0·97	6·81	7·48	6·13	7·71	8·19	7·23	6·52	6·45	6·58
September	5 93	5·23	6·63	0·58	0·63*	0·52	1·64	1·57	1·70	5·38	5·73	5·03	6·95	7·33	6·57	7·00	6·63	7·37
October	2 53	1·29	3·77	0·55	0·32	0·77	0·24	0	0·48	0·89	1·00	0·77	1·31	0·55	2·06	1·73	0·87	2·58
November	1·20	1·00	1·40	1·24	1·20	1·27	0·59	0·50	0·67	1·02	1·07	0·97	1·25	1·23	1·27	0·54	0·50	0·57
December	1·21	1·00	1·42	2·23	2·65	1·81	0·92	0·84	1·00	1·68	1·61	1·74	0·60	0·48	0·71	0·33	0·26	0·39
Year	2·71	2·43	2·98	1·35	1·45	1·26	1·21	1·29	1·12	3·46	3·45	3·46	3·25	3·29	3·20	2·95	2·73	3·16

* Mean of 28 days. † Mean of 30 days.

TABLE XIII.—MEAN PROPORTION OF CLOUDED SKY IN 1883.

Month.	84. Deesa.			85. Surat.			86. Malegaon.			87. Bombay.					88. Poona.			89. Sholapur.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	6 hours.	10 hours.	16 hours.	22 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	2·02	1·84	2·19	0·82	0·90	0·74	2·39	1·71	3·06	1·34	1·61	1·49	1·41	0·85	2·48	2·06	2·90	1·62	1·00	2·23
February	2·31	2·18	2·43	0·39	0·64	0·14	1·25	0·82	1·68	1·34	1·51	1·74	1·39	0·71	2·36	2·11	2·61	1·30	1·21	1·39
March	1·82	1·90	1·74	0·60	0·61	0·58	2·02	1·16	2·87	1·64	2·14	2·30	1·38	0·73	2·48	1·77	3·19	1·81	1·29	2·32
April	0·52	0·43	0·60	0·57	0·73	0·40	1·97	1·03	2·90	1·54	2·38	1·88	1·13	0·75	2·74	1·60	3·87	2·60	0·97	4·23
May	1·28	1·52	1·03	1·94	2·58	1·29	1·81	1·71	1·90	2·59	3·75	2·30	2·34	1·98	3·23	2·42	4·03	2·56	1·75†	3·37†
June	3·89	4·20	3·57	6·50	7·20	5·80	8·29	7·80	8·77	9·01	9·34	8·66	8·84	9·21	9·12	8·93	9·30	9·03	9·13	8·93
July	8·20	8·52	7·87	8·19	8·48*	7·90*	8·63	9·00	8·26	9·24	9·35	9·48	9·31	8·83	8·55	8·61	8·48	8·57	8·68	8·45
August	6·42	6·97	5·87	6·37	7·16	5·58	7·47	7·71	7·23	8·23	8·91	8·26	7·74	7·99	8·05	8·10	8·00	7·68	7·81	7·55
September	6·84	6·60	7·07	6·87	7·60	6·13	8·65	8·33	8·97	8·76	9·09	8·75	9·09	8·09	8·05	8·03	8·07	7·72	7·77	7·67
October	2·21	1·13	3·29	2·42	2·39	2·45	4·70	3·97	5·42	4·42	5·04	3·83	4·31	4·51	5·44	4·81	6·06	4·81	4·77	4·84
November	1·04	0·70	1·37	0·17	0·27	0·07	0·84	0·57	1·10	0·80	0·75	0·91	1·16	0·38	2·30	2·30	2·30	1·70	1·80	1·60
December	0·87	0·58	1·16	0·37	0·61	0·13	0	0	0	1·61	1·49	2·30	2·01	0·65	1·84	1·90	1·77	2·55	2·23	2·87
Year	3·12	3·05	3·18	2·93	3·26	2·60	4·00	3·65	4·35	4·21	4·61	4·33	4·18	3·72	4·72	4·39	5·05	4·33	4·03	4·62

* Mean of 29 days.

† Mean of 24 days.

Month.	90. Ratnagiri.			91. Belgaum.			92. Karwar.			93. Gopalpore.			94. Vizagapatam.				95. Masulipatam.		
	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	4 hours.	10 hours.	16 hours.	22 hours.	Mean.	10 hours.	22 hours.
January	0·37	0·39	0·35	3·09	2·49	3·68	1·07	0·87	1·26	0·98	1·06	0·90	1·77	1·39	2·16	1·77	1·77	2·11	2·39	1·82
February	0·36	0·68	0·04	1·72	1·36	2·07	0·70	0·50	0·89	1·70	2·07	1·32	1·04	0·71	1·57	0·89	1·00	2·92	3·36	2·48
March	1·16	1·26	1·06	3·18	2·06	4·29	2·16	2·16	2·16	1·66	1·00	2·32	2·73	3·03	2·68	2·16	3·06	3·92	4·10	3·74
April	0·95	0·70	1·20	2·30	0·63	3·97	2·58	2·23	2·93	2·65	1·50	3·80	2·67	2·33	2·10	3·40	2·83	4·27	4·73	3·81
May	1·39	1·13	1·65	3·81	3·61	4·00	2·86	2·87	2·84	3·47	2·23	4·71	3·40	3·58	3·13	3·45	3·45	4·18	4·39	3·97
June	8·65	8·77	8·53	8·87	9·07	8·67	7·80	7·87	7·73	6·04	5·80	6·27	6·79	6·27	6·63	7·87	6·37	7·00	7·03	6·97
July	8·15	8·10	8·19	9·26	9·19	9·32	7·12	6·81	7·42	6·99	7·16	6·81	6·98	6·23	7·16	7·84	6·68	6·53	6·45	6·61
August	6·65	7·16	6·13	8·48	8·19	8·77	5·63	5·35	5·90	6·12	6·29	5·94	6·17	5·74	6·48	6·97	5·48	5·60	5·65	5·54
September	6·97	7·03	6·90	8·14	8·37	7·90	5·37	4·87	5·87	7·10	7·07	7·13	6·00	6·30	6·30	6·17	5·23	4·24	4·50	3·97
October	2·89	2·39	3·39	6·70	6·39	7·00	4·78	3·74	5·81	3·50	3·10	3·90	3·95	3·48	4·06	4·65	3·61	4·12	4·23	4·00
November	1·55	1·50	1·60	3·12	2·90	3·33	1·64	1·17	2·10	0·97	1·13	0·80	1·44	0·87	1·93	2·13	0·83	5·65	5·53	5·77
December	1·28	1·32	1·23	3·78	3·58	3·97	1·79	1·52	2·06	1·79	1·97	1·61	2·91	1·97	3·65	3·84	2·16	5·63	5·42	5·84
Year	3·36	3·37	3·36	5·20	4·82	5·58	3·63	3·33	3·91	3·58	3·37	3·79	3·82	3·49	3·99	4·26	3·54	4·68	4·82	4·54

Month.	96. Secunderabad. Mean.	10 hours.	22 hours.	97. Kurnool. Mean.	10 hours.	16 hours.	98. Bellary. Mean.	10 hours.	22 hours.	99. Mangalore. Mean.	10 hours.	16 hours.	100. Mercara. Mean.	10 hours.	16 hours.	101. Bangalore. Mean.	10 hours.	22 hours.
January	3·00	2·81	3·18	Not recorded.			2·33	2·29	2·37	8·40	8·77	8·03	4·83	5·20	4·45	3·04	3·13	2·94
February	1·63	1·32	1·93	0·45	0·30*	0·60*	0·96	1·21	0·71	5·31	4·86	5·75	2·84	2·68	3·00	2·34	2·50	2·18
March	3·24	2·45	4·02	2·73	1·61	3·84	2·81	1·90	3·71	3·81	4·00	3·61	5·23	3·71	6·74	2·85	2·64	3·06
April	2·85	1·63	4·07	2·08	0·73	3·43	3·38	2·13	4·63	2·95	3·37	2·53	6·12	4·83	7·40	3·15	2·83	3·47
May	3·75	2·58	4·92	1·68	0·87	2·48	4·20	3·84	4·56	5·66	6·03	5·29	7·81	7·45	8·16	3·78	3·58	3·98
June	7·79	7·50	8·08	5·32	5·50	5·13	8·55	8·50	8·60	8·92	9·03	8·80	9·80	9·77	9·83	5·31	5·27	5·35
July	7·98	7·94	8·02	5·82	5·77	5·87	8·44	8·26	8·61	8·54	8·23	8·84	9·95	9·90	10·00	6·53	6·42	6·63
August	7·26	6·81	7·71	5·88	5·81	5·94	7·79	7·84	7·73	7·87	7·58	8·16	9·24	9·06	9·42	5·80	5·68	5·92
September	7·62	7·53	7·70	25·2	2·50	2·53	6·40	6·50	6·30	6·07	5·80	6·33	8·83	8·73	8·93	4·76	4·76	4·75
October	6·17	5·61	6·73	2·63	2·55	2·71	7·29	7·42	7·16	6·42	5·52	7·32	8·99	8·94	9·03	5·76	5·61	5·90
November	2·40	2·63	2·17	1·85	2·10	1·60	3·11	4·13	2·08	2·95	2·77	3·13	5·88	5·73	6·03	4·58	4·67	4·48
December	2·73	2·17	2·69	0·96	0·87	1·03	3·34	4·00	2·68	2·49	2·84	2·13	5·46	6·26	4·65	4·43	4·55	4·31
Year	4·70	4·30	5·10	?	?	?	4·88	4·84	4·93	5·78	5·73	5·83	7·08	6·86	7·30	4·36	4·30	4·41

* Mean of 20 days.

Month.	102. Madras. Mean.	10 hours.	22 hours.	103. Salem. Mean.	10 hours.	22 hours.	104. Wellington. Mean.	10 hours.	22 hours.	105. Coimbatore. Mean.	10 hours.	22 hours.	106. Trichinopoly. Mean.	10 hours.	22 hours.	107. Negapatam. Mean.	10 hours.	22 hours.
January	4·64	5·03	4·24	2·34	1·97	2·71	5·28	3·94	6·61	3·51	3·68	3·34	4·04	4·52	3·55	5·26	5·87	4·64
February	2·64	3·14	2·13	1·70	1·68	1·71	2·22	1·89	2·54	1·78	1·89	1·66	2·87	3·75	1·98	4·18	4·86	3·50
March	3·08	3·90	2·26	1·72	1·55	1·89	4·00	3·03	4·97	3·03	2·74	3·32	1·97	2·52	1·42	3·78	5·00	2·55
April	3·15	3·83	2·47	2·24	1·80	2·67	4·51	3·07	5·95	2·89	2·60	3·17	3·36	3·77	2·95	3·48	4·63	2·32
May	3·62	3·55	3·68	2·68	1·90	3·45	5·16	4·00	6·31	3·91	3·61	4·21	4·74	4·36	5·11	5·11	5·26	4·95
June	6·69	6·07	7·30	2·88	2·13	3·62	6·91	6·50	7·32	5·41	5·53	5·28	5·72	4·97	6·47	5·75	5·73	5·77
July	7·50	7·23	7·77	3·62	2·71	4·53	7·27	6·87	7·66	5·78	5·74	5·81	7·10	6·77	7·42	5·80	5·71	5·89
August	5·87	5·68	6·06	3·97	3·26	4·68	7·69	7·39	7·98	5·25	5·29	5·21	6·04	5·55	6·52	5·37	5·45	5·29
September	6·05	6·17	5·92	3·12	2·43	3·80	5·57	4·87	6·27	3·85	3·87	3·83	5·41	4·80	6·02	5·29	5·23	5·35
October	7·66	7·87	*7·44	5·01	4·52	5·50	7·20	6·74	7·66	5·69	6·06	5·32	8·17	7·91	8·43	6·76	6·97	6·55
November	6·10	6·07	6·12	4·00	3·70	4·30	6·81	6·07	7·55	5·35	5·77	4·92	6·58	6·07	7·08	7·00	6·97	7·02
December	6·75	6·74	6·76	3·79	3·61	3·97	7·19	7·18*	7·20*	4·95	5·13	4·76	6·62	6·74	6·50	6·49	6·58	6·40
Year	5·31	5·44	5·18	3·09	2·61	3·57	5·82	5·13	6·50	4·28	4·33	4·24	5·22	5·14	5·29	5·36	5·69	5·02

* Mean of 28 days.

	108. Madura.			109. Cochin.			110.	111.	112.	113.	114.	115.	116.	117.
Month.	Mean.	10 hours.	22 hours.	Mean.	10 hours.	22 hours.	Colombo.	Jaffna.	Trincomalee.	Batticota.	Hambantota.	Galle.	Kandy.	Newera Eliya.
January	4·28	4·29	4·26	3·60	3·93	3·27	5·8	4·6	7·5	7·6	6·6	5·7	5·3	6·0
February	4·16	3·86	4·45	2·62	2·11	3·12	4·7	3·2	7·3	6·0	5·5	4·6	5·4	3·5
March	4·00	3·68	4·31	3·90	3·61	4·19	4·3	1·9	4·9	4·8	5·4	5·0	5·0	4·5
April	4·67	4·43	4·90	5·49	5·40	5·58	6·1	3·7	5·9	5·2	6·1	4·8	5·7	5·9
May	5·11	4·87	5·34	7·12	7·42	6·81	7·2	4·2	4·9	6·3	6·3	6·5	6·3	5·3
June	4·63	4·43	4·83	8·59	8·77	8·40	8·0	5·4	5·6	7·2	6·6	6·2	7·3	7·8
July	4·37	4·16	4·58	8·18	8·16	8·19	7·8	7·0	5·2	7·3	6·5	6·1	7·0	7·6
August	5·04	4·81	5·26	6·84	6·06	7·61	7·8	6·1	5·8	8·2	7·8	5·5	7·2	8·1
September	5·03	5·00	5·05	5·10	5·77	4·42	8·2	5·1	5·3	7·8	6·4	5·9	6·0	6·6
October	6·31	6·06	6·56	6·92	6·87	6·96	8·4	7·5	6·9	8·6	7·4	6·0	7·1	7·8
November	5·97	5·77	6·17	5·10	4·87	5·33	8·4	7·9	8·3	9·0	8·1	6·4	6·9	7·8
December	5·75	5·65	5·84	3·31	3·23	3·39	7·5	7·1	7·3	9·0	6·3	4·6	6·4	7·6
Year	4·94	4·75	5·13	5·56	5·52	5·61	7·02	5·31	6·24	7·25	6·58	5·61	6·30	6·54

	118. Akyab.			119. Thayetmyo.			120. Toungoo.			121. Bassein.			122. Diamond Island.		
Month.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January	1·03	1·16	0·90	1·49	1·26	1·71	0	0	0	1·05	0·39	1·71	2·50	2·32	2·68
February	0·91	1·11	0·71	0·49	0·29	0·68	0	0	0	0·04	0	0·07	1·98	1·89	2·07
March	2·40	2·45	2·35	1·71	1·29	2·13	0·15	0·23	0·06	0·40	0·35	0·45	2·86	2·90	2·81
April	3·17	4·23	2·10	2·23	0·73	3·73	1·85	2·03	1·67	2·57	3·20	1·93	3·29	3·31	3·27
May	5·81	6·52	5·10	4·63	3·55	5·71	5·15	5·32	4·97	6 89	6·81	6·97	5·21	5·16	5·26
June	8·46	8·70	8·21*	7·43	7·33	7·53	9·02	9·00	9·03	8·47	7·77	9·17	8·25	8·07	8·43
July	8·91	8·94	8·87	7·28	7·32	7·23	9·32	9·61	9·03	8·84	8·23	9·45	7·73	7·48	7·97
August	8·94	8·90	8·97	7·03	6·87	7·19	9·61	9·61	9·61	8·92	8·61	9·23	7·75	7·30§	8·20§
September	7·15	7·47	6·83	6·60	6·57	6·63	7·88	7·53	8·23	8·60	8·23	8·97	7·13	7·06	7·20
October	3·44	4·00	2·87	4·81	4·68	4·94	3·99	3·32	4·65	5·69	5·61	5·77	4·55	4·16	4·94
November	3·22	3·48†	2·96‡	4·67	4·03	5·30	4·05	4·03	4·07	6·00	5·60	6·40	5·35	4·83	5·87
December	4·21	4·13	4·29	4·03	4·00	4·06	2·50	2·74	2·26	5·79	5·97	5·61	4·34	4·16	4·52
Year	4·80	5·09	4·51	4·37	3·99	4·74	4·46	4·45	4·47	5·27	5·06	5·48	5·08	4·89	5·27

* Mean of 29 days.
† " " 27 "
‡ " " 26 "
§ Mean of 30 days.

123. RANGOON. 124. MOULMEIN. 125. MERGUI. 126. PORT BLAIR. 127. NANCOWRY.

Month.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.	Mean.	10 hours.	16 hours.
January . .	1·52	0·19	2·84	0	0	0	0·81	0·90	0·71	4·42	4·65	4·19	5·53	5·71	5·35
February . .	1·98	1·14	2·82	0·59	1·07	0·11	3·31	3·18	3·43	1·70	1·71	1·68	4·15	4·11	4·18
March . .	2·39	1·68	3·10	0·98	1·90	0·06	3·86	3·74	3·97	2·26	2·06	2·45	5·66	5·71	5·61
April . . .	3·35	3·37	3·33	2·19	2·80	1·57	6·95	6·43	7·47	3·97	3·53	4·40	6·47	6·03	6·90
May . .	6·65	6·58	6·71	4·91	5·87	3·94	8·37	8·39	8·35	6·76	6·19	7·33	7·04	6·94	7·13
June . . .	7·05	7·10	7·00	8·58	9·23	7·93	9·39	9·27	9·50	7·70	7·80	7·60	7·81	7·57	8·07
July . . .	6·76	5·81	7·71	8·52	9·10	7·94	9·31	9·29	9·32	7·81	7·74	7·87	7·23	6·97	7·48
August . .	7·31	7·03	7·58	7·24	8·03	6·45	9·13	8·87	9·39	7·36	7·32	7·39	6·58	6·19	6·97
September . .	7·83	8·13	7·53	6·27	7·10	5·43	9·14	8·77	9·50	7·22	7·00	7·43	7·15	6·97	7·33
October . .	4·26	5·06	3·45	2·13	2·55	1·71	7·49	6·26	8·71	5·53	5·55	5·50	6·87	6·45	7·29
November . .	5·12	5·03	5·20	2·50	1·87	3·13	7·15	6·03	8·27	5·55	5·70	5·40	7·87	7·53	8·20
December . .	3·00	2·58	3·42	0·84	0·81	0·87	4·44	3·39	5·48	6·71	7·00	6·42	7·08	7·03	7·13
Year . .	4·77	4·48	5·07	3·73	4·19	3·26	6·61	6·21	7·01	5·58	5·52	5·64	6·62	6·48	6·80

TABLE XIV.—INCHES OF RAINFALL IN EACH MONTH OF 1883 (462 STATIONS).

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
AFRICA	Seychelles	?	?	?	?	?	?	?	?	?	?	4·35+?	11·42	?
	Zanzibar	2·49	6·13+?	2·44	11·65	7·26	...	7·21	0·53	1·13	1·05	3·16	0·83	43·88+?
ARABIA	Aden	0·05	0·09	...	0·88	1·12	...	...	0·31	...	...	0·61	...	3·06
PERSIAN GULF	Bushire	4·01	5·55	0·47	1·06	...	...	...	...	...	..	2·02	8·97	22·08
BELUCHISTAN	Quetta	2·32	0·26	3·83	0·69	0·88	0·13	1·46	...	...	..	...	0·19	9·76
CASHMERE	Leh	0·33	0·15	0·16	0·07	0·12	...	...	0·32	0·07	0·18	0·23	0·02	1·65
PUNJAB	Kailang	?	?	?	?	?	?	0·50	1·12	2·45	1·67	4·28*	1·02	?
	Peshawar (Observatory.)	1·98	0·74	0·89	0·53	0·16	0·10	4·57	0·07	0·24	0·07	1·93	0·17	11·45
	Peshawar (Cutchery.)	1·70	0·70	0·70	0·70	...	0·80	3·20	...	0·30	...	1·50	0·20	9·80
	Kohat	1·20	0·20	1·50	1·30	0·10	0·40	5·70	2·70	...	0·60	1·80	...	15·50
	Bannu	0·70	...	0·60	0·20	0·10	1·00	3·50	1·40	0·20	...	0·20	...	7·90
	Dera Ismail Khan	0·21	0·03	0·19	0·41	0·58	0·05	2·02	0·99	0·26	0·71	0·81	...	6·26
	Dera Ghazi Khan	0·50	...	0·05	...	...	0·60	0·10	...	...	...	...	...	1·25
	Muzaffargarh	0·30	...	...	...	0·10	...	3·30	...	...	...	...	...	3·70
	Mooltan (Observatory.)	1·00	...	0·18	...	1·59	...	3·56	...	2·03	...	...	...	8·36
	Mooltan (Cutchery.)	1·00	...	0·20	...	1·50	...	1·80	...	2·00	...	...	...	6·50
	Jhang	1·00	...	...	...	0·90	0·60	2·50	...	...	...	...	...	5·00
	Montgomery	1·10	...	...	...	1·90	0·90	2·20	1·40	3·70	...	0·20	...	11·40
	Shahpur	2·70	...	...	...	0·30	...	9·10	2·20	...	...	1·40	...	15·70
	Rawal Pindi	6·44	0·74	2·03	0·38	1·44	0·34	5·41	4·05	6·22	0·74	3·42	0·45	31·66
	Jhelum	3·90	0·20	2·50	0·90	2·60	3·80	6·80	1·80	3·20	...	4·30	0·20	30·20
	Gujrat	4·20	0·50	1·00	0·60	1·20	3·20	2·30	3·50	5·10	...	4·60	...	26·20
	Sialkot Observatory.)	2·75	0·19	1·04	0·13	1·21	0·37	8·85	8·34	4·62	...	1·09	0·15	28·24
	Sialkot (Cutchery)	3·50	0·10	0·90	...	1·00	1·20	5·80	8·90	6·40	...	1·10	...	28·90
	Gujranwala	3·10	0·10	0·70	0·30	0·70	0·10	8·20	3·20	7·70	...	2·90	...	27·00
	Gurdaspur	2·90	...	...	...	0·30	0·60	2·60	4·50	6·50	...	0·08	...	17·48
	Lahore	2·39	0·33	0·43	0·18	3·05	0·58	2·27	0·70	10·72	...	0·66	0·07	21·38
	Amritsar	2·70	...	0·30	0·60	13·0	...	6·10	4·20	7·80	...	1·20	..	24·20
	Ferozepore	1·90	...	0·10	0·90	0·50	...	2·80	0·40	9·20	..	0·60	...	16·40
	Jullundur	2·90	0·20	0·56	0·11	0·54	0·36	1·00	1·10	5·80	...	..	0·60	13·17
	Hoshiarpur	3·40	0·03	0·04	...	0·50	0·30	2·90	2·80	9·70	...	0·20	0·20	20·07
	Ludhiana	3·44	0·43	0·93	0·10	1·00	1·52	12·66	0·40	13·21	...	0·72	0·75	35·16
	Umballa	2·20	...	0·30	...	1·40	1·20	6·20	0·80	5·00	...	1·90	0·10	19·10
	Sirsa	1·98	...	1·60	0·05	1·83	1·28	3·22	...	7·15	0·04	0·21	...	17·36
	Hissar	1·90	...	1·20	..	1·40	0·70	4·00	0·10	2·00	0·20	0·20	...	11·70
	Rohtak	0·70	...	0·40	...	1·10	1·70	3·70	0·30	5·20	0·10	0·30	...	13·50
	Delhi (Observatory.)	1·70	...	1·79	0·15	0·68	3·53	2·57	...	6·53	...	0·09	0·01	17·05

* Snow water.

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Punjab—*concld.*	Delhi (Cutchery)	1·80	...	2·40	0·10	1·00	4·40	3·00	...	7·70	...	...	...	20·40
	Gurgaon	0·80	...	1·20	...	0·37	3·13	6·10	...	7·20	...	...	...	18·80
	Karnal	2·90	0·10	1·40	0·10	1·10	3·00	3·60	0·60	7·50	...	0·75	0·40	21·45
	Abbottabad	7·00	2·80	0·90	2·30	9·70	1·00	8·30	6·60	3·50	0·30	3·80	0·75	46·95
	Murree (Observatory.)	5·75	0·35	3·52	1·54	4·39	0·43	8·19	6·82	8·25	1·25	5·41	0·28*	46·18
	Murree (Cutchery)	26·40	0·50	2·90	1·30	3·90	0·10	5·00	9·10	5·50	1·40	...	1·30*	57·40
	Dharmsala	6·50	1·40	2·00	0·80	1·80	7·40	24·70	24·10	14·10	...	2·20	0.50	85·50
	Kilba	8·10	1·30	2·90	7·57	4·90	...	2·40	4·60	4·70	1·00	13·00	3·60*	54·07
	Simla (Observatory.)	4·74	0·61	2·98	0·87	10·92	7·39	14·41	17·03	5·94	0·85	5·02	0·20	70·96
	Simla (Cutchery).	4·57	0·30	1·80	2·50	10·00	6·50	15·70	20·20	5·60	1·00	6·90	0·50	75·57
Rajputana	Bickaneer	0·58	...	0·04	...	3·62	...	5·12	0·10	1·55	0·03	0·66	...	11·70
	Jeysulmere	0·84	...	...	...	1·02	0·22	2·75	0·01	2·13	...	...	...	6·97
	Ulwur	0·66	...	0·27	0·07	1·10	1·44	9·37	1·60	7·28	...	...	...	21·79
	Bhurtpore	1·98	...	0·26	...	0·35	2·26	5·51	1·13	5·28	...	0·05	...	16·82
	Jeypore	1·22	...	0·21	...	2·05	3·15	7·20	0·95	7·73	0·33	...	...	22·84
	Sambhar	0·38	...	...	...	2·46	0·68	8·69	0·58	2·67	...	...	...	15·46
	Beawar	0·30	...	...	...	1·16	0·60	5·00	0·30	5·20	0·20	...	...	12·76
	Pachbudra	0·50	...	0·30	...	2·01	0·20	1·46	0·03	4·46	0·05	0·04	...	9·05
	Jodhpore	0·66	0·12	0·21	...	2·13	0·31	2·18	0·02	3·88	2·58	...	...	12·09
	Ajmere	0·38	...	0·02	...	2·19	1·09	9·24	0·45	3·91	...	...	...	17·28
	Nusseerabad	0·25	0·05	0·01	...	2·55	1·61	5·85	2·14	3·41	0·46	...	...	16·33
	Tonk	0·54	...	...	...	2·28	2·60	4·58	3·87	5·14	0·60	...	...	19·61
	Deoli	0·29	0·06	1·08	...	2·32	3·66	7·16	1·44	3·35	...	...	...	19·36
	Kotah	0·48	...	0·45	...	1·68	4·62	4·78	5·06	10·83	0·24	...	...	28·14
	Jhalrapatam	0·64	...	0·42	...	1·29	6·38	4·87	4·94	14·90	0·19	...	...	33·63
	Kotra	0·16	...	0·24	...	2·87	2·83	13·62	2·21	12·33	1·01	...	...	35·27
	Oodeypore	?	?	...	...	1·90	1·80	5·42	3·16	8·26	0·37	...	...	?
	Kherwara	0·24	...	...	...	6·04	3·32	8·58	2·01	2·82	0·45	...	...	23·46
	Banswara	0·65	...	...	...	3·50	2·29	10·44	5·68	6·69	0·80	...	...	30·05
	Mount Abu	0·47	...	0·36	...	4·96	3·12	25·53	0·75	12·15	2·15	0·04	...	49·53
	Erinpura	0·30	...	0·05	...	2·20	1·06	4·65	...	5·94	2·49	...	...	16·69
	Shahpoora	0·50	0·01	0·34	...	5·06	1·71	4·82	0·38	10·74	0·10	...	...	23·66
	Partabgarh	0·61	...	...	...	2·21	8·07	7·30	11·49	10·61	1·15	...	...	41·44
	Barmer	?	?	?	...	0·14	0·28	2·18	...	3·99	...	...	...	?
Central India	Neemuch (Observatory.)	0·27	...	0·31	...	2·75	3·51	4·35	6·60	11·21	1·27	...	...	30·27
	Neemuch (Cutchery).	0·30	...	0·05	...	2·51	4·31	5·55	5·35	8·77	1·34	...	...	28·18
	Sirdarpore	...	...	...	...	0·43	3·97	12·07	2·13	8·47	1·55	...	...	28·62
	Agar	0·88	...	...	...	2·71	7·34	8·27	5·09	12·48	3·09	...	...	39·46
	Rutlam	0·58	...	...	...	2·37	8·97	14·25	7·57	11·38	1·25	...	...	46·37

* Snow water.

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Central India—*contd.*	Indore	0·18	...	...	...	0·37	6·90	7·49	4·01	4·48	2·33	...	...	25·76
	Bhopal	0·39	...	...	...	1·47	9·00	13·00	6·47	17·06	2·03	...	...	49·42
	Goona	1·30	...	...	...	1·08	6·86	3·68	1·72	16·41	0·55	...	...	31·60
	Morar	1·56	0·09	0·69	...	1·95	0·96	6·19	6·07	3·40	...	...	...	20·91
	Nowgong	1·51	...	0·06	...	0·96	4·30	12·51	1·59	4·57	0·77	...	...	26·27
	Sutna	1·41	0·01	0·21	...	0·45	5·63	15·88	4·28	11·44	0·53	...	...	39·84
	Nagode	2·05	...	...	...	1·01	5·33	15·48	5·59	7·65	1·07	...	...	38·18
	Maihar	2·44	...	...	...	0·56	2·57	12·85	2·44	4·26	0·50	...	...	25·62
	Rewah	1·28	...	0·20	...	...	2·60	14·29	6·22	7·65	0·38	...	...	32·62
	Chandia	1·16	...	0·39	...	0·28	6·54	16·64	3·61	5·64	0·88	...	...	35·14
	Ramnagar	1·75	...	...	...	...	5·51	9·44	3·70	7·41	...	...	...	27·81
	Sihawal	2·41	...	1·25	...	0·14	5·70	7·41	4·21	6·82	0·66	...	...	28·60
	Sitlaha	1·01	...	0·29	...	0·51	4·48	7·97	8·02	10·28	1·35	...	...	33·91
	Sohagpur	1·80	...	0·34	...	...	7·06	14·28	3·55	8·01	...	0·18	...	35·22
N.-W. Provinces	Chakrata	5·61	0·44	2·07	0·91	3·64	8·87	15·83	14·36	5·43	0·06	0·81	0·23	58·26
	Mussooree	2·24	0·64	2·40	0·88	1·40	8·87	26·90	14·52	11·70	...	3·20	0·30	73·05
	Ranikhet	2·64	...	4·48	0·36	3·53	2·12	5·95	7·69	7·39	...	1·22	0·17	35·55
	Naini Tal	9·70	0·60	5·60	0·40	6·40	11·30	28·20	17·40	5·60	...	0·70	...	85·90
	Almora	3·60	0·70	2·80	0·10	3·20	2·00	5·70	5·20	4·20	...	0·30	...	27·80
	Dehra Dun	6·00	...	1·66	0·31	1·26	13·96	17·23	14·27	6·60	...	1·54	0·09	62·92
	Dehra Dun (Forest School low level)	5·68	...	1·64	0·35	1·36	14·47	16·51	13·77	6·80	...	1·53	0·11	62·22
	Saharanpur	3·77	...	2·18	0·25	1·44	4·97	4·66	0·88	4·55	...	1·05	0·11	23·86
	Roorkee	5·37	0·02	1·48	0·32	1·17	9·53	10·59	6·07	4·89	...	0·65	0·03	40·12
	Muzaffarnagar	3·55	0·07	1·58	...	2·10	6·42	3·87	0·20	3·95	...	0·57	...	22·31
	Meerut	2·51	...	1·08	...	0·42	2·12	4·65	0·94	4·87	...	0·14	0·03	16·76
	Bulandshahr	2·80	...	1·00	...	2·30	3·70	5·70	0·70	5·30	...	...	...	21·50
	Aligarh	2·83	...	0·66	0·30	1·12	5·50	8·42	1·06	1·01	...	...	...	20·90
	Bijnor	2·62	...	1·06	...	0·53	5·79	5·68	5·10	4·11	...	...	...	24·89
	Moradabad	4·30	...	0·80	...	1·30	2·83	17·20	7·46	4·06	...	...	...	37·95
	Bareilly	2·81	0·01	2·04	0·15	1·58	1·23	9·04	3·46	3·23	...	0·05	0·02	23·62
	Budaun	2·40	...	0·70	...	0·78	0·59	5·09	2·35	4·19	...	...	...	16·10
	Shahjahanpur	2·42	...	0·81	...	1·01	4·11	8·11	6·91	2·66	...	...	...	26·03
	Muttra	3·02	...	0·14	...	1·28	3·31	7·84	0·22	1·39	...	...	...	17·20
	Agra	1·97	...	0·10	0·06	0·50	1·15	12·71	0·12	3·65	...	...	...	20·26
	Mainpuri	2·30	...	0·60	...	1·00	1·10	7·70	0·70	10·50	...	...	...	23·90
	Farrukhabad	2·32	...	0·45	...	0·70	1·22	7·06	6·82	4·69	...	...	...	23·26
	Etawah	1·99	...	0·68	...	0·38	0·82	10·04	1·70	5·89	...	...	...	21·50
	Etah	2·30	...	0·20	...	1·20	2·10	5·60	3·20	6·40	...	...	...	21·00
	Cawnpore	3·10	0·10	1·10	...	...	0·80	9·60	4·10	2·70	...	...	...	21·50

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
N.-W. Provinces —*contd.*	Fatehpur	3·28	0·41	0·09	...	1·33	5·09	23·68	1·55	4·77	...	...	...	40·20
	Banda	3·20	...	...	...	1·60	6·16	15·11	3·95	3·65	0·16	...	...	33·83
	Allahabad	2·68	0·02	0·39	...	0·34	3·87	13·48	2·10	4·92	0·79	...	...	28·59
	Hamirpur	1·83	0·15	0·14	...	0·07	2·73	15·02	1·41	7·59	0·04	...	...	28·98
	Jaunpur	3·02	0·11	0·38	...	0·18	5·36	11·77	3·58	7·58	...	...	...	31·98
	Azamgarh	3·08	0·12	0·12	...	0·24	6·36	12·74	3·40	3·57	...	...	...	29·63
	Mirzapur	2·70	...	0·30	...	0·70	1·32	10·09	5·81	4·65	1·29	...	...	26·86
	Dudhi	1·40	0·20	1·10	...	...	6·20	8·58	8·37	5·59	0·42	0·45	...	32·31
	Robertsganj	2·20	...	0·60	...	...	2·25	6·13	3·72	5·08	0·60	...	...	20·58
	Benares	2·24	0·12	0·59	...	0·54	5·00	14·84	5·66	3·42	1·26	...	...	33·67
	Gorakhpur	3·55	0·10	0·28	0·76	0·25	10·89	7·96	4·81	1·48	...	...	...	30·08
	Basti	3·15	...	0·11	...	0·10	6·82	13·44	4·26	4·76	...	...	...	32·64
	Ghazipur	1·61	0·02	...	...	0·22	5·09	14·19	4·09	4·87	0·80	...	...	30·89
	Jalaun	1·80	0·10	0·10	...	0·80	0·80	12·00	4·40	6·60	...	...	...	26·60
	Jhansi	2·02	...	0·30	...	1·07	3·32	7·13	1·49	2·88	0·45	...	...	18·66
	Lalitpur	1·15	...	0·07	...	1·19	2·40	6·07	3·39	7·86	1·61	...	...	23·74
	Srinagar	4·40	...	2·90	0·30	1·90	1·70	6·40	6·40	2·80	...	2·20	0·10	29·10
	Pithoragarh	4·54	...	2·87	0·18	5·53	5·70	8·36	7·76	3·13	...	0·18	0·08	38·33
	Pauri	3·60	...	3·46	0·35	3·26	3·34	9·44	7·15	2·12	...	1·48	0·12	34·32
	Pilibhit	2·20	...	1·40	...	1·10	4·20	10·90	5·90	2·40	...	...	...	28·10
	Ballia	1·40	0·10	...	...	0·40	6·70	11·40	2·10	3·80	0·50	...	...	26·40
	Rudarpur	3·90	...	1·20	...	1·70	6·60	14·10	5·70	3·80	...	...	...	37·00
Oudh	Lucknow	4·72	...	0·82	...	0·29	3·60	19·14	3·31	4·18	...	...	...	36·06
	Unao	3·36	0·11	0·31	...	0·17	1·07	14·39	2·36	5·58	...	...	...	27·35
	Nawabganj	5·43	...	0·79	...	1·08	7·74	11·59	1·28	6·66	...	...	...	34·57
	Sitapur	4·18	...	0·88	...	2·52	2·32	12·76	1·04	3·23	...	0·04	10·07	27·04
	Hardoi	2·93	...	0·56	...	0·20	1·20	16·32	4·07	5·00	...	...	...	30·28
	Kheri	4·68	...	0·39	0·14	2·68	3·96	12·78	3·01	3·59	...	...	0·05	31·28
	Fyzabad	4·02	...	0·20	...	1·10	4·50	9·42	5·50	3·10	...	...	...	27·84
	Bahraich	2·16	...	0·08	0·22	0·80	6·40	16·00	0·90	3·20	...	...	...	29·76
	Gonda	4·10	...	0·40	...	0·62	6·44	13·84	5·41	7·13	...	...	...	37·94
	Rae Bareli	2·78	0·12	0·15	...	0·09	1·91	9·06	3·53	10·58	...	...	...	28·22
	Sultanpur	3·20	0·20	0·10	...	...	4·70	13·30	3·50	4·30	...	...	...	29·30
	Partabgarh	2·20	0·10	0·25	...	0·55	1·11	9·52	3·95	5·37	...	...	...	23·05
Nepal	Katmandu	5·40	...	0·55	2·01	3·54	8·42	14·63	18·25	6·61	...	...	0·52	59·93
Bengal	Burdwan	0·11	0·72	4·24	4·09	6·84	12·08	21·84	14·01	1·66	0·70	...	1·18	67·47
	Bankoora	0·46	0·45	2·07	1·16	2·51	7·20	18·80	12·94	5·32	0·06	0·11	1·44	52·52
	Soory	0·27	0·03	1·73	0·82	4·74	18·91	19·41	16·87	3·58	0·01	0·16	0·79	67·32
	Midnapore	3·13	0·52	1·96	3·22	1·10	7·36	9·32	16·72	4·28	0·45	0·01	1·04	49·11

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Bengal—*contd.*	Tumlook	...	2·00	2·55	1·50	2·10	7·50	16·80	15·00	3·30	1·50	...	2·00	54·25
	Hooghly	0·15	0·73	0·92	4·62	3·70	8·70	20·56	9·00	3·34	2·83	0·03	1·85	56·43
	Howrah	0·28	2·02	0·62	3·70	1·14	9·21	14·94	7·67	4·34	0·47	...	2·45	46·84
	Saugor Island	...	1·09	1·55	3·01	3·37	12·77	20·74	9·96	11·27	0·57	...	2·32	66·65
	Alipore (Jail)	0·10	2·07	1·29	3·13	1·16	9·49	16·27	7·41	5·35	0·77	0·01	3·34	50·39
	Alipore (Observatory).	0·07	2·09	1·52	2·96	1·18	10·20	16·16	8·15	6·96	0·75	...	2·54	52·58
	Busseerhat	0·08	1·97	0·32	3·98	3·08	13·85	23·08	11·13	5·14	0·30	...	2·75	65·68
	Calcutta (Chowringhee).	0·05	2·13	1·25	3·21	1·19	11·96	15·97	8·75	5·73	0·86	...	2·70	53·80
	Calcutta (St. Xavier's College).	0·04	2·20	1·18	3·18	1·62	14·84	16·30	9·04	5·47	1·18	...	2·73	57·78
	Kishnaghur	...	0·15	0·78	1·20	3·88	3·63	8·43	4·56	2·69	2·26	...	0·22	27·80
	Jessore	0·45	0·59	2·09	5·53	3·66	6·90	14·16	7·81	5·73	1·27	...	2·35	50·54
	Khoolna	0·08	0·84	2·79	3·60	2·16	12·26	9·78	6·91	7·85	0·13	...	3·35	49·75
	Berhampore	0·12	0·02	1·65	0·25	6·59	8·48	9·84	9·02	2·74	0·22	...	1·08	40·01
	Dinagepore	0·84	0·03	0·04	2·35	9·75	12·91	7·43	14·15	7·21	0·03	...	0·57	55·31
	Maldah	0·48	0·11	0·26	0·85	3·19	9·68	10·65	6·20	3·28	0·10	...	1·93	36·73
	Beauleah	0·36	0·03	1·82	0·29	4·60	6·60	5·66	7·48	3·72	1·41	...	1·09	33·06
	Rungpore	0·50	0·09	0·04	7·43	11·14	10·28	6·05	13·66	8·41	...	...	0·32	57·92
	Bogra	0·58	0·16	0·17	3·02	6·88	7·31	16·19	8·91	2·82	0·31	...	0·79	47·14
	Pubna	0·50	...	0·34	2·43	11·16	9·85	8·43	4·50	3·08	1·51	0·02	1·24	43·06
	Darjeeling	1·86	0·50	...	2·14	7·78	39·52	19·26	30·85	11·06	0·68	...	0·10*	113·75
	Monghoo	1·83	0·10	0·13	3·27	12·43	41·31	21·62	28·83	8·20	0·50	...	0·07	118·29
	Julpigoree	1·33	0·12	...	3·99	8·77	33·74	23·62	38·80	30·80	0·86	...	...	142·03
	Baxa	1·54	0·09	1·89	9·92	28·87	47·08	35·71	47·08	31·05	4·85	0·03	1·97	210·08
	Cooch Behar	0·18	0·02	...	6·99	14·59	25·89	22·20	34·90	28·72	0·20	...	...	133·69
	Dacca	0·26	0·13	1·08	5·80	7·04	8·81	19·01	7·43	3·65	1·70	...	1·59	56·50
	Furreedpore	0·63	0·32	4·96	5·14	9·05	5·84	14·21	10·07	4·32	0·43	...	1·33	56·30
	Burrisal	...	1·70	6·23	4·50	9·25	13·11	12·93	9·27	7·44	3·46	...	3·28	71·17
	Mymensingh	0·48	0·24	0·33	4·78	10·07	9·50	11·13	11·45	7·83	0·84	...	0·78	57·43
	Atia	0·22	0·08	0·54	5·54	9·82	8·87	17·47	10·11	2·69	...	...	1·20	56·54
	Kishorganj	0·07	0·04	0·42	8·64	15·96	7·89	16·34	18·78	2·38	3·62	...	1·63	75·77
	Chittagong	...	0·85	2·93	3·83	19·20	37·76	24·71	16·02	15·67	3·59	0·07	8·49	133·12
	Cox's Bazar	...	0·03	5·10	2·44	10·75	49·48	33·41	30·98	17·10	3·93	0·32	0·94	154·48
	Demagiri	...	0·74	4·34	4·37	22·38	20·22	15·35	42·33	15·13	0·85	0·87	5·42	132·00
	Noakholly	...	1·41	10·71	6·16	7·47	36·40	25·48	24·05	19·87	3·27	...	7·86	142·68
	Tipperah	0·19	0·52	3·78	7·25	8·81	20·75	22·27	13·00	9·43	2·57	...	4·66	93·23
	Rangamatia Hill	...	0·55	5·12	5·13	20·10	18·66	11·65	20·57	10·48	3·61	...	6·41	102·28
	Agartalla	0·45	...	1·40	4·63	13·87	14·89	14·14	10·12	8·88	2·81	...	4·53	75·72
	Patna	1·93	0·15	0·39	0·16	0·15	14·83	9·20	7·53	5·01	0·40	...	...	39·75

* Snow water.

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Barh	1·16	0·12	0·40	0·02	0·05	14·39	11·29	8·66	4·01	0·47	...	...	40·57
	Gya	1·65	0·07	0·30	...	0·89	14·60	18·68	5·47	4·18	0·52	0·11	0·01	46·48
	Arrah	1·89	0·09	0·26	...	0·06	11·62	8·23	5·43	4·06	0·55	...	...	32·19
	Sasseram	1·46	...	0·59	...	0·89	7·55	8·72	2·91	7·58	1·03	...	...	30·73
	Buxar	1·47	0·05	0·50	...	0·21	7·67	13·92	5·40	6·47	1·03	...	...	36·72
	Mozufferpore	1·78	0·03	0·04	0·74	0·94	20·09	8·83	12·08	4·88	0·08	...	...	49·49
	Durbhunga	0·91	0·13	...	0·70	1·42	19·10	6·44	10·68	2·62	0·13	...	...	42·13
	Chupra	1·43	...	0·51	0·03	...	11·87	16·18	4·67	3·83	0·36	...	...	38·88
	Sewan	2·06	0·13	0·27	0·20	0·25	7·58	13·90	6·30	4·59	0·06	...	...	35·34
	Motiharee	1·72	...	...	0·73	2·45	5·24	10·94	15·59	0·78	0·03	...	...	37·48
	Monghyr	0·62	...	0·89	0·25	1·32	8·82	8·20	4·35	3·86	0·65	...	...	28·96
	Jamooee	1·22	...	0·46	...	0·12	6·83	14·24	9·23	5·82	1·00	...	...	38·92
	Bhagalpore	0·53	0·09	0·41	0·57	0·88	14·53	7·96	13·40	2·25	0·28	...	0·26	41·16
	Muddehpoora	0·67	0·09	0·24	0·96	2·74	29·51	12·51	7·48	4·17	0·03	...	...	58·40
	Purneah	0·96	0·07	0·11	1·13	2·62	10·10	8·90	8·68	5·42	0·09	...	0·10	38·38
	Kissengunge	0·92	...	...	3·02	2·97	22·63	10·34	16·40	8·30	...	...	0·12	64·70
	Nya Doomka	0·40	...	0·95	...	1·43	14·03	13·60	13·27	3·05	...	0·13	0·98	47·84
	Godda	1·27	...	0·62	0·15	0·94	5·52	12·44	7·79	8·39	0·35	...	0·80	38·27
	Cuttack	...	0·18	1·26	0·08	4·96	23·09	14·32	8·61	12·93	0·55	0·30	0·96	67·24
Bengal—*contd.*	Banki	...	0·20	1·00	0·30	3·05	15·19	13·65	9·56	16·21	0·93	1·19	1·33	62·61
	Barreepudda	0·05	1·36	2·15	2·51	3·56	11·15	12·07	11·93	7·80	0·02	0·06	...	52·66
	Dhenkanal	0·19	1·03	1·66	1·78	2·96	14·66	16·99	8·34	13·18	1·05	...	...	61·84
	Angul	...	1·31	1·16	2·00	4·31	13·53	13·92	13·33	5·53	7·44	0·42	0·98	63·93
	Bispara	0·05	0·09	0·11	0·09	2·52	24·31	6·70	4·72	6·36	3·65	0·29	0·50	49·39
	Kunjabangar	...	...	2·52	...	...	13·19	11·55	10·43	10·45	1·90	1·02	0·25	51·31
	Talcher	...	1·83	1·33	2·17	1·86	20·29	13·15	13·99	6·98	0·22	1·10	...	62·92
	Keonjhar	...	0·20	0·70	0·15	0·50	2·50	3·65	2·75	1·10	...	...	0·20	11·75
	False Point	0·12	0·52	2·40	0·33	2·38	19·07	15·51	18·58	8·76	2·31	0·26	2·95	73·19
	Pooree	0·04	0·19	1·50	...	0·48	18·54	13·86	4·57	13·61	4·85	1·44	2·10	61·18
	Balasore	...	3·88	2·01	1·74	4·91	17·69	10·73	15·39	3·76	1·70	...	1·40	63·21
	Jellasore	...	2·80	2·04	2·55	2·21	15·49	15·87	12·29	5·49	1·48	...	...	60·22
	Bhuddruck	...	0·54	2·61	2·40	2·88	16·87	11·91	10·04	8·36	0·58	0·05	1·20	57·44
	Hazaribagh	1·11	0·14	2·64	...	1·54	7·06	19·61	6·53	11·56	0·20	0·47	0·36	51·22
	Ranchee	0·55	0·10	3·16	0·47	2·16	13·49	20·43	10·01	9·46	0·28	2·09	0·47	62·67
	Lohardugga	?	?	?	?	?	?	?	?	?	0·31	1·69	0·19	?
	Palamow	2·14	...	2·11	0·38	0·45	5·31	10·14	7·99	7·35	0·49	1·62	...	37·98
	Sirguja	0·99	...	2·95	...	1·16	6·28	13·52	7·05	11·72	1·26	3·80	...	48·73
	Jushpore	1·48	...	3·92	...	1·42	9·13	15·19	10·62	6.67	4·79	...	...	53·22
	Gangpur	...	...	2·84	...	0·70	7·59	13·38	14·33	12·03	1·42	0·78	0·32	53·39

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Bengal—*concld.*	Chybassa	1·53	0·55	3·74	0·92	1·21	8·44	15·92	17·74	7·02	0·62	0·11	1·10	58·90
	Purulia	0·36	0·35	3·70	0·64	1·81	13·90	16·18	16·60	8·00	0·89	1·00	1·26	64·69
	Gobindpur	0·79	0·66	0·95	0·15	1·96	7·29	10·97	8·70	5·77	0·04	0·15	0·61	37·44
Assam	Silchar	1·18	0·15	10·15	6·58	51·74	15·05	15·92	28·49	17·73	3·92	2·20	7·33	160·44
	Sibsagar	1·77	0·71	5·83	3·46	9·46	7·67	23·34	16·45	12·21	3·03	0·23	1·28	85·44
	Sylhet	0·13	0·15	5·42	5·91	36·30	24·19	19·27	29·71	22·21	2·50	...	2·57	148·36
	Goalpara	0·59	0·06	0·13	6·16	21·61	10·23	8·67	14·41	10·78	0·70	...	0·10	73·44
	Tura	0·42	0·25	0·04	8·48	21·49	19·90	10·12	20·40	5·67	1·17	...	0·27	88·21
	Gauhati	0·68	0·10	0·66	5·15	18·22	9·20	6·79	8·64	4·85	3·47	...	1·50	59·26
	Kulsi	0·50	0·09	0·46	6·64	17·22	17·59	17·55	7·37	7·95	0·27	...	0·68	76·32
	Tezpur	...	...	1·53	3·26	16·11	10·82	14·50	15·85	8·66	0·09	...	1·42	72·24
	Chardner	0·54	0·47	0·22	3·73	13·23	12·61	21·48	18·96	6·33	0·92	0·28	1·24	80·01
	Nowgong	0·68	0·18	1·83	5·79	13·94	7·47	13·78	18·89	6·59	2·06	...	1·11	72·32
	Dibrugarh	1·56	1·25	4·55	8·26	15·34	15·02	22·37	16·61	15·71	2·64	0·42	0·53	104·26
	Shillong	0·88	0·34	0·65	4·33	10·47	16·15	8·12	15·00	10·56	3·40	0·12	1·65	71·67
	Cherra Poonjee	1·28	...	4·43	14·39	67·32	84·85	67·49	65·99	56·29	6·32	...	3·24	371·60
	Kohima	1·06	0·30	2·76	3·17	12·92	13·52	15·66	12·84	7·59	0·66	0·33	4·30	75·11
	Dhubri	0·32	0·03	...	5·68	15·44	12·92	4·12	16·67	12·98	2·15	...	0·06	70·37
Central Provinces.	Nagpur	0·39	...	0·34	...	0·27	11·37	15·21	12·17	15·72	5·98	...	...	61·45
	Bhandara	0·48	...	0·15	...	0·37	19·52	10·74	14·23	18·31	4·32	...	...	68·12
	Chanda	0·19	...	0·63	...	0·28	7·09	19·87	15·26	10·72	4·78	1·13	...	59·95
	Bastar (Jagadalpore.)	0·10	...	0·15	5·55	0·70	11·13	13·76	17·01	6·59	0·36	0·22	0·09	55·66
	Brahmapuri	0·15	...	0·45	...	...	12·56	22·45	10·56	12·94	3·27	...	...	62·38
	Wardha	0·17	...	...	...	0·08	14·81	11·88	12·55	17·05	7·33	0·21	...	64·08
	Arvi	0·34	...	...	...	...	8·70	10·71	14·71	11·16	3·20	...	...	48·82
	Balaghat	0·63	...	1·05	...	0·45	10·42	21·21	7·14	16·65	1·94	...	...	59·49
	Sironcha	0·06	...	0·85	0·36	0·48	10·12	13·82	16·94	13·10	0·81	0·30	...	56·84
	Jubbulpore	0·57	...	0·21	...	0·24	9·25	18·10	5·98	12·50	1·43	...	...	48·28
	Saugor	0·70	...	...	...	1·44	5·92	8·64	5·35	7·72	0·39	...	...	30·16
	Damoh	1·45	...	...	...	0·96	8·85	12·71	3·31	11·03	1·45	...	...	39·76
	Seoni	1·16	...	0·02	...	0·23	11·83	18·64	7·49	17·77	3·38	...	...	60·52
	Mandla	0·80	...	1·12	...	0·63	12·73	12·37	5·64	9·25	1·46	...	...	44·00
	Badnur	0·02	...	...	...	0·05	8·15	8·53	7·33	9·36	6·50	...	...	39·94
	Chhindwara	1·30	...	...	...	1·27	24·02	13·80	7·56	11·50	3·26	...	...	62·71
	Hoshangabad	0·18	...	0·07	...	0·60	10·42	12·12	15·43	23·73	3·33	...	...	65·88
	Narsinghpur	0·31	...	...	...	0·53	9·77	13·44	6·19	26·65	1·38	...	...	58·27
	Khandwa	0·20	...	...	...	0·07	8·39	12·32	8·62	5·18	2·50	...	...	37·28
	Pachmarhi	0·37	...	0·02	...	0·43	10·89	20·55	12·15	18·99	4·01	...	...	67·41
	Raipur	0·25	...	1·84	...	0·61	15·51	10·73	7·40	8·98	1·78	0·73	...	47·83

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Central Provinces—*contd.*	Dhamtari	0·15	...	1·66	0·20	...	10·88	17·50	6·38	13·23	1·63	0·58	...	52·21
	Sambalpur	0·16	0·19	2·09	0·06	0·56	21·35	29·20	7·81	14·58	0·09	1·32	1·10	78·51
	Raigarh	...	...	...	...	...	7·01	15·46	12·46	12·36	1·25	2·80	1·05	52·39
	Sarangarh	...	...	...	...	1·00	7·00	13·50	8·00	11·20	1·50	...	...	42·20
	Bilaspur	0·61	...	1·24	...	1·40	5·02	13·31	3·21	11·22	0·65	1·40	...	38·06
	Saragaon	0·56	...	...	...	...	6·78	11·19	4·77	13·02	0·19	0·15	...	36·66
	Makhla	0·10	...	...	...	0·46	13·42	28·65	15·31	19·51	7·76	...	...	85·21
	Chikalda	0·10	...	...	...	0·65	12·42	31·67	12·83	18·35	10·98	...	...	87·00
	Ellichpur	...	...	...	...	0·05	10·11	14·59	7·81	7·60	8·06	0·27	...	48·49
	Amraoti	0·12	...	...	...	0·38	9·51	16·05	12·73	9·32	6·78	...	...	54·89
Berars	Akola (Observatory.)	...	...	0·06	...	0·09	10·83	21·52	14·35	11·26	8·15	...	...	66·26
	Akola (Cutchery)	...	...	0·06	...	0·09	10·83	21·52	14·35	11·26	8·15	0·05	...	66·31
	Buldana	0·02	...	...	...	0·16	12·94	11·61	9·50	16·25	9·79	0·04	...	60·31
	Basim	...	...	0·05	0·10	0·15	15·00	12·38	7·90	13·17	3·60	0·95	...	53·30
	Yeotmal	0·20	...	...	...	0·30	12·05	15·95	11·75	14·30	7·05	0·15	...	61·75
	Wun	...	...	...	...	0·57	10·35	10·00	10·85	9·10	7·03	0·53	...	48·43
Hyderabad	Bolarum	0·40	...	2·50	1·39	0·52	4·35	6·61	12·35	7·94	2·12	0·23	...	38·41
	Secunderabad	0·21	...	2·62	0·22	0·19	5·65	8·39	7·73	5·81	1·82	0·61	...	33·25
	Hyderabad (Residency.)	...	...	1·80	0·13	...	4·67	4·86	6·94	4·11	3·16	0·65	...	26·32
	Hyderabad (Engineer's Office.)	...	...	2·35	0·10	...	4·69	5·32	4·57	5·24	2·86	0·04	...	25·17
	Lingsugur (Cantonment.)	...	...	...	0·71	0·41	1·12	0·87	7·11	1·04	5·04	1·20	...	17·50
	Lingsugur (W. Raichore.)	...	...	...	0·80	0·82	1·24	0·77	7·27	1·03	5·09	1·11	...	18·13
	Aurangabad(Cantonment.)	...	...	0·02	...	0·85	10·14	4·74	9·22	8·80	8·13	...	...	41·90
	Aurangabad	...	...	...	...	1·47	10·15	4·45	9·92	8·43	4·01	0·06	...	38·49
	Hingoli	...	...	0·04	0·02	0·61	12·45	9·06	11·40	16·22	4·95	0·48	...	55·23
	Jalna	...	...	...	...	0·28	11·74	4·19	7·65	9·46	7·07	0·05	...	40·44
	Mominabad	...	...	?	?	0·41	10·66	3·14	15·84	13·86	1·23	0·33	...	?
	Ibrahimpatan	...	...	2·87	...	0·11	8·03	5·59	10·31	5·86	2·97	0·34	...	36·08
	Medack	...	...	2·93	...	0·55	3·99	7·27	26·19	9·05	1·65	0·15	...	51·78
	Indur	...	...	0·04	...	0·04	6·28	9·87	19·32	14·64	2·15	1·06	...	53·40
	Yelgandal	...	...	1·75	...	...	7·87	8·67	9·98	15·73	1·88	0·10	...	45·98
	Khamam	...	...	2·82	0·06	0·61	11·42	8·18	9·32	11·72	0·82	0·31	...	45·26
	Nalgonda	...	...	...	0·81	...	6·83	7·53	4·49	3·92	6·60	0·22	...	30·40
	Nagad Karnul	...	...	1·24	0·04	1·54	7·26	7·12	5·90	6·32	1·81	0·35	...	31·58
	Beeder	...	...	0·85	0·35	...	12·08	10·33	31·34	11·10	3·30	0·38	...	69·73
	Naldurg	...	...	...	...	...	9·62	1·81	21·09	12·08	2·35	...	...	46·95
	Nanded	...	...	1·00	...	0·21	12·71	5·93	17·62	13·88	1·16	0·36	...	52·87
	Gulbarga	...	...	0·96	...	...	5·39	3·68	16·45	5·10	2·68	0·95	...	35·21
	Shorapur	...	...	...	...	...	?	?	?	?	?	?	?	?

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Hyderabad—*concld.*	Raichur	...	...	2·10	0·30	0·19	5·33	3·77	5·43	5·10	3·01	0·52	...	25·75
	Bheer	...	...	...	....	0·56	12·38	5·24	14·57	15·38	1·32	...	...	49·45
	Purbhani	...	...	...	...	0·22	11·54	3·12	9·19	14·97	1·82	0·58	...	41·44
Bombay	Dhulia	0·20	...	0·02	...	...	5·21	8·39	6·44	8·18	8·74	...	...	37·18
	Nasik	0·44	...	...	...	0·62	13·69	13·30	6·63	12·19	13·71	0·04	...	60·62
	Igatpuri	1·02	...	...	...	1·43	24·72	48·67	17·55	29·30	11·68	0·03	...	134·40
	Malegaon	0·02	...	...	...	0·26	5·12	9·36	10·71	5·13	7·52	...	...	38·12
	Ahmednagar	...	...	...	...	0·67	10·65	1·82	8·33	10·90	8·14	1·31	...	41·82
	Poona	...	...	0·13	0·29	1·90	10·10	5·23	3·01	10·91	7·97	0·08	...	39·62
	Lonavala	0·27	...	...	...	1·19	28·12	75·95	21·35	44·21	7·74	0·05	...	178·88
	Satara	0·11	...	...	0·81	1 57	10·79	11·85	4·86	7·53	5·54	1·10	...	44·16
	Mahableshwar	0·57	...	...	0·17	0·21	52·84	124·17	36·72	70·64	10·78	0·80	...	296·90
	Sholapur	0·02	...	0·14	0·08	0·17	11·53	2·08	16·18	6·48	1·76	1·49	...	39·93
	Kolhapur	0·14	...	...	2·63	1·04	5·77	13·90	4·76	3·23	3·57	1·61	...	36·65
	Bavda	0·80	...	...	...	...	60·65	118·76	37·40	35·30	10·58	0·37	...	263·86
	Belgaum	0·05	...	0·01	1·70	3·07	10·04	17·98	5·35	6·67	8·05	1·10	0·19	54·21
	Gokak	...	...	0·14	2·00	0·41	3·92	2·61	5·28	0·44	6·40	1·68	...	22·88
	Dharwar	...	...	0·43	1·48	2·42	3·51	7·69	5·13	2·89	4·87	1·19	...	29·61
	Hubli	...	...	0·52	2·45	2·25	2·94	5·17	4·51	2·65	4·45	0·42	0·04	25·40
	Nandgad	...	...	...	2·69	0·73	0·59	1·61	6·54	...	6·13	0·56	0·05	18·90
	Mandargi	...	...	...	0·57	0·60	0·10	0·58	3·25	0·52	3·99	0·80	0·10	10·51
	Kalghatgi	...	...	...	4·38	1·40	5·39	8·81	2·28	4·33	4·76	0·67	...	32·02
	Kaladgi	...	...	0·19	1·52	0·14	5·38	1·50	4·16	0·65	5·14	0·86	...	19·54
	Bijapur	...	...	0·12	...	0·89	4·80	1·18	9·82	2·69	3·36	4·23	...	27·09
	Karwar	...	...	...	2·21	2·53	49·28	47·50	17·82	18·74	9·35	3·91	0·05	151·39
	Honavar	0·50	...	...	0·57	1·26	43·45	48·80	19·06	17·17	10·02	4·10	0·10	145·03
	Vengurla	...	...	...	...	3·26	46·35	48·51	16·19	14·98	7·52	1·28	...	138·09
	Ratnagiri	0·91	...	...	...	0·15	32·61	39·87	16·94	13·74	6·38	0·11	...	110·71
	Colaba (Observatory.)	0·12	...	...	...	0·33	13·65	39·88	12·57	12·37	10·40	0·86	...	90·18
	Byculla (J. J. Hospital.)	0·26	...	...	...	0·61	22·77	37·05	15·57	13·16	10·72	0·65	...	100·79
	Thana	0·36	...	...	...	0·61	25·92	48·35	20·50	16·69	7·50	...	...	119·93
	Matheran	0·10	...	...	...	1·29	37·76	104·39	32·81	52·10	12·34	...	...	240·79
	Surat	0·66	...	...	...	0·17	17·76	18·76	2·33	10·52	4·30	...	...	54·50
	Broach (Cutchery)	0·89	...	...	..	0·82	9·01	20·15	2·76	13·61	3·13	...	...	50·37
	Broach (Hospital)	0·70	...	...	...	0·70	8·72	20·93	3·25	13·00	2·19	...	...	49·49
	Kaira	0·39	...	...	...	0·10	4·61	14·37	0·63	8·76	0·55	...	...	29·41
	Gadhra	0·81	...	...	...	4·39	3·30	25·71	4·25	13 84	0·72	...	...	53·02
	Ahmedabad	0·13	...	...	...	2·23	2·43	10·25	1·54	3·60	...	...	...	20·18
	Bariya	0·54	...	...	...	1·57	4·61	30·65	3·92	18·13	2·15	...	...	61·57

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September	October.	November.	December.	Total.
	Idar	...	...	...	...	3·45	2·20	12·88	1·05	2·86	0·12	...	...	22·56
	Palanpur	0·16	...	0·73	...	2·44	4·10	8·92	0·34	3·52	0 24	...	...	20·45
	Rajkot	0·13	...	...	...	...	1·64	17·14	0·32	4·50	1·30	...	...	25·03
	Bhuj	0·12	...	1·29	...	0·42	1·58	9·42	0·11	2·88	0·23	...	...	16·05
	Rhahpur	...	...	1·00	...	...	0·25	2·61	0·50	4·31	0·30	...	...	8·97
	Kurrachee	0·33	...	0·12	...	...	0·37	4·75	...	0·54	...	...	...	6·11
	Sehwan	0·07	...	...	...	...	...	5·99	...	...	...	...	...	6·06
Bombay—*concld.*	Tatta	0·16	...	0·03	...	...	0·74	4·63	0·02	2·31	...	...	...	7·89
	Hyderabad (Observatory).	0·22	...	0·21	...	...	0·42	3·68	...	0·42	...	...	...	4·95
	Hyderabad (Cutchery).	0·92	...	0·20	...	...	0·38	2·43	...	0·58	...	...	...	4·51
	Umarkot	0·64	...	...	...	...	0·15	2·29	0·12	2·20	0·11	...	...	5·51
	Nagar	...	...	...	...	...	0·73	8·40	...	4·18	...	...	...	13·31
	Shikarpur	0·12	...	0·07	...	...	...	1·38	...	...	...	...	...	1·57
	Rohri	0·14	...	0·05	...	...	0·61	1·82	...	0·01	...	...	...	2·63
	Jacobabad	0·63	...	0·04	0·07	...	...	5·35	...	...	...	...	...	6·09
	Deesa	0·14	...	0·52	...	0·56	1·87	8·40	0·27	3·54	1·11	...	...	16·41
	Ganjam	0·30	...	0·55	...	0·35	7·60	11·90	5·35	3·55	14·62	...	1·45	45·67
	Gopalpore	...	...	2·60	...	1·45	15·80	10·46	7·37	7·83	12·11	4·74	2·03	64·39
	Aska	...	...	2·32	2·32	2·22	15·63	8·60	14·14	3·77	5·08	0·59	0·90	55·57
	Aska, 31·6 feet Bunglow.	...	...	2·20	3·10	3·15	16·21	10·06	14·88	5·40	4·82	0·96	0·94	61·72
	Aska 39 feet Office.	...	...	1·59	2·79	3·00	15·08	9·25	13·07	4·92	4·58	0·87	0·88	56·03
	Vizianagram	...	...	1·10	0·50	2·10	5·20	2·70	8·50	1·80	7·60	0·80	0·90	31·20
	Bimlipatam	...	...	0·50	...	0·15	3·40	3·60	5·85	1·85	9·70	1·35	0·95	27·35
	Royaghadda	...	...	2·70	1·65	4·40	10·75	12·55	8·90	4·60	4·90	0·20	0·40	51·05
	Nourangapur	...	...	1·30	1·05	0·30	10·70	19·40	17·90	6·10	1·75	...	...	58 50
	Gunipur	...	...	2·20	2·80	3·58	6·95	10·80	7·97	5·00	2·10	0·35	0·80	42·55
	Kotipad	...	...	1·30	1·15	0·40	11·60	17·55	15·20	11·00	2·00	1·00	...	61·20
Madras	Koraput	...	...	...	1·10	...	15·60	13·70	13·55	10·00	3·55	0·40	0·20	58.10
	Malkanagiri	...	...	0·40	0·70	0·20	17·75	15·15	9·50	20·55	2·25	0·60	...	67·10
	Narsapatnam	...	...	0·80	1·30	2·85	2·55	3·80	7·20	5·50	9·30	0·80	1·10	35·20
	Vizagapatam	0·90	...	...	...	0·70	1·90	2·80	11·90	6·30	12·90	5·40	1·10	43·90
	Coconada	...	...	...	...	0·37	4·11	2·84	5·15	1·96	13·31	9·97	0·77	38·48
	Rajahmundry	...	...	...	...	2·15	6·30	5·84	3·05	4·55	12·50	1·90	...	36·29
	Ellore	...	...	...	...	...	5·95	5·30	5·50	2·65	7·55	0·95	...	27·90
	Masulipatam	0·58	...	...	0·01	0·27	5·53	3·43	1·62	3·27	13·35	14·85	0·22	43·13
	Guntur	...	...	...	0·45	...	3·45	2·32	6·70	4·75	7·90	3·15	...	28·72
	Vinukonda	...	...	...	...	0·90	2·75	2·47	5·18	2·27	10·85	2·60	...	27·02
	Ongole	...	...	0·30	1·80	0·30	4·65	2·50	6·80	0·75	19·80	7·25	...	44·15
	Nellore	...	...	...	...	0·20	1·25	1·20	1·35	1·12	24·40	5·90	2·65	38·07

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August	September	October.	November.	December.	Total.
	Udayagiri	...	...	...	1·00	...	1·00	2·15	2·30	2·75	18·60	5·70	2·50	36·00
	Tada	...	...	...	...	...	5·95	4·70	0·85	1·00	16·80	5·10	9·21	43·61
	Kurnool	...	...	1·32	0·40	0·20	4·64	5·10	8·48	4·35	5·51	0·92	...	30·92
	Cumbum	...	...	0·70	...	...	3·31	3·65	3·62	2·29	11·83	3·33	0·67	29·40
	Nandayal	...	...	0·24	1 12	...	7·71	6·95	7·64	5·18	7·65	1·41	0·61	38·51
	Bellary	...	...	1·38	0·27	0·56	0·07	1·40	3·88	0 55	4·92	1·06	...	14·09
	[illegible]	...	...	0·08	0·20	0·20	4·11	3·60	3·77	0·72	5·06	1·52	...	19 26
	Adoni	...	...	0·23	1·00	0·12	1·90	3·48	7·08	2·15	5·05	0·72	...	21·73
	Dharmavaram	...	...	0·40	1·40	0·15	5·10	0·10	7·80	...	6·85	2·65	0·80	25·25
	Cuddapah	...	...	0·50	0·40	0·15	3·75	0·85	7·35	2·80	11·90	1·43	3·35	32·48
	Madanapalle	...	...	...	2·00	3·35	1·75	2·15	5·65	3·90	11·45	3·43	4·95	38·63
	Chittoore	...	...	...	0·60	1·74	2·74	2·79	6·41	6·73	12·32	6·01	3·61	42·95
	Vellore	...	...	...	...	4·05	2·40	3·21	8·96	6·14	9·85	6·38	5·46	41·45
	Chandragiri	...	...	...	1·65	0·55	1·32	3·95	3·70	6·40	11·62	6·35	6·50	42·04
	Arcot	...	...	...	0·15	1·60	6·15	4·30	6·80	2·32	8·70	9·26	5·51	44·79
	Madras	0·24	0·07	...	...	...	2·31	6·38	2·98	0·56	22·18	14·92	10·90	60·54
	Palmaner	...	...	...	...	5·00	3·05	2·31	7·18	7·95	15·84	6·54	4·67	52·54
	Saidapet	...	...	...	...	...	3·16	9·89	2·31	2·47	18·76	12·70	10·50	59·79
	Chingleput	...	...	...	...	...	1·70	4·07	3·55	3·35	14·38	7·15	5·05	39·25
Madras—*contd.*	Conjeeveram	...	...	...	...	...	4·25	2·85	5·10	1·70	12·96	8·10	4·20	39·16
	Tindivanam	...	...	...	...	0·70	3·00	3·55	7·80	4·68	11·35	6·60	5·30	42·98
	Cuddalore	0·05	0·58	...	0·10	...	2·01	2·48	6·45	0·51	15·00	12·66	4·51	44·35
	Vriddhachalam	...	...	...	...	1·10	1·65	3·40	6·65	2·55	18·20	9·15	1·30	44·00
	Udayarpalaiyam	...	...	...	...	...	4·35	2·25	1·80	4·00	11·55	7·65	4·20	35·80
	Salem	...	...	1·16	0 70	4·80	4·32	4·59	9·05	1·89	12·44	4·36	2·67	45·98
	Atur	...	...	1·90	1·10	5·50	1·35	6·20	8·30	2·90	11·38	8·35	1·55	48·53
	Shevaroy Hills	...	...	1·95	0·80	6·70	5·05	5·00	16·20	3·85	13·95	11·65	5·15	70·30
	Kambakonum	...	0·42	...	...	0·55	3·10	0·20	1·96	1·90	7·28	10·92	2·44	28·77
	Tirupatur	...	...	0 65	2·90	4·95	2·35	3·60	3·40	3·30	9·45	5·85	1·90	38·35
	Hosur	...	...	0·18	2·73	2·85	0·72	2·73	7·70	1·50	12·80	3·58	3·18	37·97
	Tranquebar	0·10	...	...	...	0·35	1·65	0·35	1·90	0·99	18·07	11·70	7·24	42·35
	Negapatam	0·64	0·88	...	...	0·52	4·20	0·35	6·62	1·76	15·09	17·80	6·26	54·12
	Tanjore	...	0·80	...	...	1·70	4·95	0·90	3·42	2·07	6·86	7·63	2·92	31·25
	Patukota	...	0·80	...	...	1·10	3·60	1·25	0·95	...	14·65	7·60	4·30	34·25
	Trichinopoly	...	...	...	...	3·98	2·63	1·16	4·37	4·67	7·94	5·22	0·94	30·91
	Karur	...	...	...	...	3·32	1·11	...	5·77	1·00	7·79	4·20	1·39	24·58
	Coimbatore	...	...	0·63	0·17	2·10	0·86	0·76	2·98	0·24	8·77	4·66	2·27	23·44
	Kollegal	...	...	0·95	2 30	7·00	0·80	2·00	8·15	1·30	9·20	2·30	5·00	39·00
	Dindigul	...	0·07	0·05	2 80	2·49	0·78	1·42	2·46	0·58	4·98	7·59	1·31	24·53

Provinces.	Stations.	January	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Madras—*concld.*	Madura (Observatory)	...	1·00	0·10	0·66	3·13	1·00	2·35	3·80	4·45	8·98	10·98	2·61	39·06
	Madura (Cutchery)	...	1·05	0·15	1·05	2·82	1·10	1·74	3·22	4·20	10·17	9·52	3·05	38·07
	Pasumali	...	1·05	0·09	1·20	8·01	0·40	4·20	2·80	8·12	11·70	11 29	3·01	51·87
	Vattanum	0·75	2·80	0·30	1·90	6·90	...	0·20	1·27	0·05	13·90	5·65	3·19	36·91
	Periyakulam	...	...	0·78	3·15	4 87	0 67	0·50	4·58	2·00	5·80	9·60	1·27	33·22
	Tinnevelly	0·22	4·07	3·47	0·90	4·35	1·93	1·25	0·32	...	7·45	6·02	2·48	32·46
	Tuticorin	...	4·40	1·00	...	6 00	...	0 20	...	...	5·30	10·20	2·70	29·80
	Setur	...	2·30	0·20	4·50	9·50	1·00	...	1·15	...	8·65	9·55	3·40	40·25
	Cochin	1·31	0·10	3·53	3·24	17·86	32·61	24·32	13·32	4·21	13·21	7·37	1·85	122·93
	Palghat	...	...	0·63	1·10	8·27	19·85	25·44	16 54	3·15	11·13	5·09	2·25	93·45
	Wellington	0·33	0·04	3·18	1·29	3·60	2·05	2·56	3·92	1·74	11·82	9·74	4·42	44·69
	Manantoddy	...	...	2·31	2·75	2·74	21·47	38·41	30·46	4·83	7·57	2·26	1·69	114·49
	Calicut	...	...	1·50	9·30	5·30	29·90	28·57	13·60	4·20	15·67	3·73	0·15	111·92
	Tellicherry	...	...	0·40	1·95	4·25	31·95	39·49	14·80	2·19	9·16	11·55	1·22	116·96
	Cannanore	...	...	0·40	1·68	6·20	29·15	41·80	15·59	2·63	5·37	8·80	0·50	112·12
	Mangalore	...	...	0·02	2·47	3·31	26·95	47·54	23·40	7·46	5·74	2·34	0·36	119·59
Mysore and Coorg.	Bangalore	...	...	0·05	0·72	1·81	0·80	5·28	7·66	1·05	12·56	2·86	2·01	34·80
	Mysore	...	...	2·66	1·25	9·61	1·11	2·41	7·20	0·54	11·90	4·15	4 04	44·87
	Shimoga	...	...	0·56	5·31	2·79	4·25	9·63	8·86	3·42	8·44	3·41	0·90	47·57
	Mercara	...	...	2·09	4·56	4·10	22·14	56·67	32·45	9·53	11·34	5·36	2·64	150·88
	Kolar	...	0·01	0·13	2·20	3·56	3·35	2·79	7·27	0·94	13·20	2·85	5·19	41·49
	Tumkur	...	...	0·23	1·84	3·38	0·94	4·30	12·17	1·17	12·19	2·04	0·72	38·98
	Chitaldroog	...	...	0·32	0·60	3·95	2·65	3·37	7·03	0·73	6·22	4·65	0·84	30·36
	Chikmagalur	...	...	1·11	2·15	5·43	2·33	13·18	8·15	1·22	11·85	7·66	1·88	54·96
	Hassan	...	...	1·89	2·28	5·39	3·99	10·45	9·54	1·06	11·19	3·29	2·00	51·08
Ceylon	Jaffna	3·70	5·08	1·19	1·82	5·40	...	0·10	0·76	...	20·56	20·85	10·06	69·52
	Mannar	6·30	10·61	0·11	0·70	8·84	...	...	....	...	18·28	11·60	6·07	62·51
	Trincomalle	7·90	8·14	2·50	0·70	4·61	6·46	0·11	1·36	4·37	12·65	21·49	8·16	78·45
	Batticaloa	10·12	10·06	0·72	0·14	3·12	1·99	0·74	0·37	0·54	10·06	18·65	12·20	68·71
	Hambantota	6·11	0·79	2·52	1·30	5·15	2·54	2·11	0·76	0·87	7 54	4·67	0·07	34·43
	Galle	5·57	3·41	3·32	11·75	10·66	5·40	8·43	6·05	6·00	10·32	19·65	4·50	95·06
	Ratnapura	8·00	6·80	9·71	13·88	27·92	16·51	10·23	18·78	14·54	21·27	13·71	9·02	170·37
	Colombo	2·34	1·69	5·61	8·83	18·62	11·71	3·16	17·86	3·30	14·05	9·12	7·32	103·61
	Kandy	1·69	3·39	2·63	6·26	14·25	6·22	5·95	7·57	1·38	10·31	8·92	5·46	74·03
	Newera Eliya	4·90	5·45	3·42	7·72	13·10	7·35	19·86	14·27	4·06	8·45	7·97	5·17	101·72
	Puttalam	...	2·51	1·64	3·10	12·88	0·48	...	1·61	?	8·04	10·65	0·50	?
	Anuradhapura	1·94	5·58	3·01	6·80	7·02	3·41	0·76	4·55	...	12·03	16·48	8·28	69·86
British Burmah	Akyab	...	...	1·35	2·53	15·23	46·13	49·01	33 08	23·70	5·43	3·58	7·43	187·47
	Kaukpyu	...	...	0·91	0·01	14·76	43·40	37·76	36·01	21·14	2·04	3·95	3·79	163·77

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
British Burmah —*contd.*	Sandaway	...	...	...	0·19	13·46	45·22	68·14	38·62	35·45	5·74	15·39	0·92	223·13
	Rangoon	...	...	0·14	4·40	7·17	14·03	18·82	14·55	12·12	3·55	7·10	...	81·88
	Bassein	...	...	...	0·15	5·82	23·58	26·36	12·99	13·84	5·72	17·58	0·28	106·32
	Diamond Island	...	...	...	0·06	5·15	23·73	23·89	23·73	19·94	5·22	16·35	1·58	129·85
	Henzada	...	...	...	0·27	5·00	16·72	25·49	14·84	14·41	3·55	6·45	0·10	86·83
	Myanaung	...	...	...	0·03	5·30	9·05	5·95	12·40	13·30	5·50	9·50	0·60	60·63
	Prome	...	...	...	0·55	5·77	12·12	9·55	5·84	7·05	4·87	7·64	0·09	53·48
	Thayetmyo	...	...	...	1·65	4·48	9·06	7·21	4·53	4·69	10·08	8·71	0·21	50·62
	Toungoo	...	...	...	4·70	4·60	15·31	21·15	17·05	13·27	2·27	2·13	...	79·88
	Moulmein	...	0·27	...	2·42	13·62	38·70	40·72	30·53	36·03	2·05	1·94	...	166·28
	Tavoy	...	0·36	...	2·16	14·85	42·86	59·16	42·29	20·32	9·82	3·62	...	195·44
	Mergui	...	1·23	0·26	4·84	14·41	30·55	33·90	28·36	35·45	20·39	6·15	...	225·94
	Shuegyin	...	0·37	...	4·80	11·54	26·70	41·16	27·09	19·00	6·99	2·04	...	139·69
Bay Islands	Port Blair	0·63	0·26	...	0·76	12·52	16·47	19·53	17·59	16·60	6·30	12·87	15·73	119·26
	Nancowry	0·73	1·68	0·27	3·01	8·92	10·68	11·58	14·72	45·62	7·79	26·96	11·11	113·07
Straits Settlements.	Singapore	2·95	2·39	6·30	7·87	7·62	4·83	2·71	3·10	9·38	7·41	6·03	6·15	66·74

TABLE XV.—NUMBER OF DAYS ON WHICH RAINFALL WAS MEASURED IN 1883.
(462 STATIONS).

PROVINCES.	STATIONS.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
AFRICA	Seychelles	?	?	?	?	?	?	?	?	?	?	5+?	15	?
	Zanzibar	5	7+?	6	17	17	...	12	4	5	11	12	9	105+?
ARABIA	Aden	2	2	...	2	3	...	...	1	...	...	1	...	11
PERSIAN GULF	Bushire	6	5	3	4	...	...	...	...	...	...	6	5	29
BELUCHISTAN	Quetta	11	5	9	7	3	1	6	...	...	...	...	5	47
CASHMERE	Leh	5	6	2	1	1	...	...	1	1	1	2	2	22
PUNJAB	Kailang	?	?	?	?	?	?	3	6	3	2	4	3	?
	Peshawar (Observatory)	7	3	5	3	4	1	3	2	3	1	2	1	35
	Peshawar (Cutchery).	4	1	2	3	...	1	2	...	3	...	2	1	19
	Kohat	5	1	3	3	1	2	5	3	...	1	2	...	26
	Bannu	4	...	3	2	1	2	4	3	1	...	1	...	21
	Dera Ismail Khan	2	1	5	6	2	1	5	3	2	2	2	...	31
	Dera Ghazi Khan	1	...	1	...	...	1	1	...	...	...	...	...	4
	Muzaffargarh	1	...	...	...	1	...	2	...	...	...	...	...	4
	Mooltan (Observatory.)	2	...	1	...	2	...	3	...	1	...	...	...	9
	Mooltan (Cutchery).	2	...	1	...	1	...	3	...	1	...	...	...	8
	Jhang	3	...	...	...	3	1	4	...	...	...	...	...	11
	Montgomery	3	...	...	...	4	3	5	2	2	...	1	...	20
	Shahpur	3	...	...	...	1	...	4	2	...	...	2	...	12
	Rawalpindi	11	3	7	7	4	3	7	11	7	2	2	3	67
	Jhelum	7	1	3	2	2	2	4	4	3	...	3	1	32
	Gujrat	5	1	3	2	2	2	4	6	2	...	3	...	30
	Sialkot (Observatory).	4	2	4	1	4	3	12	11	4	...	2	2	49
	Sialkot (Cutchery)	3	1	3	...	4	1	7	7	3	...	1	...	30
	Gujranwala	4	1	1	1	3	1	4	3	5	...	2	...	25
	Gurdaspur	5	...	...	...	1	1	6	6	6	...	2	...	27
	Lahore	5	2	4	3	2	2	5	3	6	...	1	1	34
	Amritsar	4	...	3	3	1	...	5	6	6	...	2	...	30
	Ferozpur	2	...	1	2	2	...	3	1	4	...	1	...	16
	Jullundur	5	1	1	1	2	1	4	4	4	...	...	1	24
	Hoshiarpur	5	2	2	...	1	1	7	6	4	...	2	1	31
	Ludhiana	7	2	6	1	1	5	12	2	8	...	3	1	48
	Umballa	3	...	1	...	3	3	7	2	4	...	3	1	27
	Sirsa	2	...	3	2	5	4	7	...	9	1	1	...	34
	Hissar	4	...	1	...	4	6	6	1	5	1	1	...	29
	Rohtak	2	...	2	...	2	2	6	1	5	1	1	...	22
	Delhi (Observatory).	3	...	5	2	2	5	9	...	6	...	1	1	34

Provinces.	Stations.	January	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Punjab—*contd.*	Delhi (Cutchery).	3	...	5	1	2	3	6	...	5	...	...	...	25
	Gurgaon	3	...	4	...	2	4	7	...	7	...	...	...	27
	Karnal	3	1	3	1	1	3	7	1	5	...	3	1	29
	Abbottabad	12	4	4	9	5	1	8	11	6	2	2	3	67
	Murree (Observatory).	11	4	7	7	8	1	9	17	8	4	2	2	80
	Murree (Cutchery)	?	?	?	3	7	1	6	10	6	1	...	?	?
	Dharmsala	7	3	4	3	6	10	21	17	14	...	4	2	91
	Kilba	8	3	5	7	8	...	7	8	4	2	4	3	59
	Simla (Observatory).	7	2	9	4	7	11	23	17	14	2	6	1	103
	Simla (Cutchery)	4	2	3	5	8	9	17	12	9	1	6	1	77
Rajputana	Bickaneer	3	...	2	...	4	...	7	1	10	1	2	...	30
	Jeysulmere	1	...	...	...	4	2	5	1	4	...	...	...	17
	Ulwar	3	...	3	1	4	5	14	2	8	...	...	...	40
	Bhurtpore	2	...	4	...	2	5	10	2	7	...	1	...	33
	Jeypore	3	...	3	...	5	4	14	5	13	4	...	...	51
	Sambhar	4	...	...	...	3	3	8	3	7	...	...	...	28
	Beawar	2	...	...	...	4	2	8	1	6	2	...	...	25
	Pachbudra	1	...	1	...	3	1	8	1	11	1	1	...	28
	Jodhpore	2	1	1	...	4	3	9	1	7	2	...	...	30
	Ajmere	3	...	1	...	5	5	14	2	9	...	...	...	39
	Nusseerabad	2	1	1	...	5	2	11	2	6	2	...	...	32
	Tonk	3	...	...	...	7	5	9	8	12	1	...	...	45
	Deoli	3	1	4	...	5	6	18	5	12	...	...	...	54
	Kotah	3	...	2	...	4	8	12	5	12	1	...	...	47
	Jhalrapatam	3	...	3	...	4	13	14	7	16	3	...	...	63
	Kotra	1	...	2	...	5	9	20	5	18	1	...	...	61
	Oodeypore	?	?	...	...	5	6	13	3	14	3	...	...	?
	Kherwara	1	...	...	...	5	7	22	6	14	2	...	...	57
	Banswara	1	...	...	...	4	9	21	10	16	4	...	...	65
	Mount Abu	1	...	2	...	5	11	26	6	23	5	1	...	80
	Erinpura	1	...	1	...	4	2	14	...	11	2	...	...	35
	Shahpoora	2	1	3	...	5	6	13	4	11	3	...	...	48
	Partabgarh	2	...	...	...	4	9	23	11	20	5	...	...	74
	Barmer	?	?	?	...	2	1	7	...	5	...	...	...	?
Central India	Neemuch (Observatory).	1	...	1	...	2	9	15	12	18	5	...	...	63
	Neemuch (Cutchery).	1	...	1	...	5	12	15	11	16	6	...	...	67
	Sirdarpur	...	...	...	...	1	8	22	8	17	4	...	...	60
	Agra	2	...	...	...	5	16	17	12	16	9	...	...	77
	Rutlam	3	...	...	...	5	12	22	10	16	6	...	...	74

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Central India —*contd.*	Indore	1	...	...	...	3	16	20	16	17	7	...	...	80
	Bhopal	3	...	...	...	3	17	15	13	15	3	...	...	69
	Goona	5	...	...	...	4	10	19	6	14	2	...	...	60
	Morar	2	1	3	...	2	4	16	6	12	...	...	...	46
	Nowgong	6	...	3	...	5	7	19	9	13	4	...	...	66
	Sutna	4	1	5	...	4	12	16	8	15	1	...	...	66
	Nagode	3	...	...	...	2	10	14	7	12	1	...	...	49
	Maihar	8	...	...	...	4	8	15	9	9	2	...	...	55
	Rewah	3	...	1	...	...	5	17	7	14	1	...	...	48
	Chandia	4	...	1	...	1	9	21	13	12	2	...	...	63
	Ramnagar	4	...	...	...	...	6	12	5	10	...	...	...	37
	Sihawal	6	...	5	...	1	10	8	4	12	1	...	...	47
	Sitlaha	4	...	2	...	3	5	11	9	10	2	...	...	46
	Sohagpur	3	...	2	...	...	12	16	9	11	...	1	...	54
N.-W. Provinces	Chakrata	10	2	6	7	9	13	24	21	12	1	4	2	111
	Mussooree	5	2	5	2	4	16	23	14	15	...	4	1	91
	Ranikhet	5	...	7	2	7	10	22	15	12	...	3	1	84
	Naini Tal	6	1	6	1	6	15	25	16	9	...	2	...	87
	Almora	4	1	3	1	7	7	12	11	6	...	1	...	53
	Dehra-Dun	4	...	6	1	5	14	19	21	12	...	4	1	87
	Saharanpur	3	...	3	1	5	6	7	3	5	...	4	1	38
	Roorkee	7	1	6	1	5	5	13	10	9	...	4	2	63
	Muzaffarnagar	3	...	2	...	3	6	5	2	6	...	2	...	29
	Meerut	3	...	3	...	3	3	9	2	7	...	2	2	34
	Bulandshahr	3	...	2	...	3	4	10	2	4	...	...	...	28
	Aligarh	4	...	5	1	3	4	8	3	1	...	...	...	29
	Bijnor	3	...	3	...	3	6	9	4	7	...	...	...	35
	Moradabad	4	...	3	...	2	3	9	7	4	...	...	...	32
	Bareilly	4	1	4	2	5	4	14	11	8	...	1	1	55
	Budaun	4	...	3	...	3	5	12	6	9	...	...	...	42
	Shahjahanpur	3	...	4	...	2	6	14	7	5	...	...	...	41
	Muttra	2	...	1	...	3	7	11	2	5	...	...	...	31
	Agra	3	...	3	1	2	7	13	2	8	...	...	...	39
	Mainpuri	3	...	2	...	3	3	10	4	8	...	...	...	33
	Farrukhabad	1	...	1	...	2	1	10	4	6	...	...	...	25
	Etawah	4	...	3	...	2	3	8	4	9	...	...	...	33
	Etah	4	...	1	...	1	3	7	5	6	...	...	...	27
	Cawnpore	2	1	4	...	...	3	10	4	8	...	...	...	32
	Fatehpur	3	1	1	...	1	5	14	7	11	...	...	...	43

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
N.-W. Provinces —*contd.*	Banda	6	...	...	...	4	9	16	8	7	2	...	...	52
	Allahabad	7	1	4	...	5	6	14	10	13	2	...	...	62
	Hamirpur	3	1	2	...	2	4	16	8	11	2	...	...	49
	Jaunpur	4	1	1	...	1	8	14	8	8	...	...	...	45
	Azamgarh	4	1	1	...	1	6	12	4	5	...	...	...	34
	Mirzapur	3	...	2	...	3	4	14	10	7	2	...	...	45
	Dudhi	3	1	4	...	...	5	12	11	6	1	1	...	44
	Robertsganj	4	...	3	...	...	4	15	11	10	2	...	...	49
	Benares	4	1	5	...	4	7	20	11	13	2	...	...	67
	Gorakhpur	2	1	2	2	1	9	12	9	9	...	...	...	47
	Basti	4	...	2	...	1	11	10	7	7	...	...	...	42
	Ghazipur	3	1	...	...	2	7	15	9	6	2	...	...	45
	Jalaun	2	1	1	...	2	1	14	4	7	...	...	...	32
	Jhansi	7	...	4	...	4	12	12	5	8	3	...	...	55
	Lalitpur	3	...	2	...	5	9	12	6	10	2	...	...	49
	Srinagar	4	...	5	1	6	5	10	8	4	...	3	1	47
	Pithoragarh	3	...	7	4	10	13	23	14	15	...	2	2	93
	Pauri	4	...	6	4	9	10	18	9	10	...	2	2	74
	Pilibhit	2	...	3	...	4	6	15	7	4	...	...	...	41
	Ballia	3	1	...	...	1	9	16	7	6	1	...	...	44
	Rudarpur	4	...	3	...	4	8	11	9	6	...	...	...	45
Oudh	Lucknow	4	...	7	...	1	5	16	9	10	...	...	...	52
	Unao	4	1	3	...	2	2	15	8	11	...	...	...	46
	Nawabganj	4	...	4	...	3	7	16	6	7	...	...	...	47
	Sitapur	3	...	4	...	3	5	13	2	8	...	1	1	40
	Hardoi	3	...	6	...	1	1	12	5	7	...	...	...	35
	Kheri	4	...	2	1	4	7	16	5	9	...	...	1	49
	Fyzabad	4	...	1	...	4	4	12	3	4	...	...	...	32
	Bahraich	3	...	2	1	2	9	17	4	6	...	...	...	44
	Gonda	4	...	2	...	2	5	16	9	9	...	...	...	47
	Rae Bareli	3	1	2	...	1	3	9	7	11	...	...	...	37
	Sultanpur	3	1	1	...	...	6	15	5	8	...	...	...	39
	Partabgarh	3	1	2	...	1	2	14	8	8	...	...	...	39
Nepal	Katmandu	6	...	3	6	10	20	23	24	17	...	...	1	110
Bengal	Burdwan	2	4	8	5	5	16	27	26	13	3	...	2	111
	Bankoora	2	4	7	5	9	17	21	26	14	2	1	2	110
	Soory	4	2	4	5	8	19	26	26	16	1	2	2	115
	Midnapore	3	3	7	6	5	15	23	25	13	1	1	3	105
	Tumlook	...	2	5	4	5	9	11	11	4	2	...	2	55

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Hooghly	1	4	6	8	6	16	22	21	8	4	1	3	100
	Howrah	3	2	7	9	6	18	25	22	23	2	...	3	120
	Saugor Island	...	3	6	6	7	15	16	18	20	2	...	2	95
	Alipore (Jail)	2	4	6	8	8	19	27	23	18	3	1	3	122
	Alipore (Observatory).	2	2	6	7	7	20	27	26	20	3	...	2	122
	Bussecrhat	1	2	2	9	8	20	25	20	18	2	...	3	110
	Calcutta (Chowringhee).	2	3	6	9	7	17	25	24	17	2	...	3	115
	Calcutta (St. Xavier's College).	2	3	6	7	5	21	29	24	14	3	...	2	116
	Kishnaghur	...	1	2	1	9	11	15	14	10	1	...	1	65
	Jessore	2	3	8	11	10	19	27	22	18	3	...	2	125
	Khoolna	1	2	6	8	5	22	24	16	20	2	...	3	109
	Berhampore	2	1	2	1	9	13	23	22	12	1	...	1	87
	Dinagepore	4	1	1	6	10	20	18	21	18	1	...	1	101
	Maldah	2	1	2	4	7	20	21	23	13	2	...	1	96
	Beauleah	3	1	4	2	11	17	21	28	19	4	...	2	112
	Rungpore	1	2	1	7	16	20	17	18	17	...	...	1	100
	Bogra	3	2	3	4	11	19	17	22	11	1	...	1	94
	Pubna	2	...	3	8	12	19	19	18	8	5	1	3	98
	Darjeeling	3	1	...	11	19	15	25	26	21	2	...	1	124
Bengal—*contd.*	Mongpoo	2	1	2	9	18	20	21	25	15	2	...	1	116
	Julpigoree	3	1	...	8	20	17	24	25	19	2	...	...	119
	Baxa	5	1	1	11	24	22	20	28	22	5	1	3	143
	Cooch Behar	3	1	...	10	21	23	17	19	20	2	...	...	116
	Dacca	2	3	6	9	15	21	24	24	17	3	...	4	128
	Furreedpore	2	2	7	9	11	17	24	19	14	2	...	3	110
	Burrisal	...	2	6	8	16	23	27	24	19	5	...	4	134
	Mymensingh	3	1	1	6	22	23	22	21	14	2	...	3	118
	Atia	2	1	3	5	12	9	20	17	7	...	...	2	78
	Kishorganj	2	1	2	8	15	10	13	16	7	4	...	3	81
	Chittagong	...	2	5	7	17	21	28	26	20	6	1	4	137
	Cox's Bazar	...	1	4	9	16	25	30	24	17	4	1	5	136
	Demagiri	...	2	5	7	18	20	26	28	20	4	3	5	138
	Noakholly	...	3	6	9	17	22	26	25	24	4	...	4	140
	Tipperah	1	3	5	8	18	24	25	25	21	4	...	4	138
	Rangamatia Hill	...	2	6	6	23	27	26	30	27	7	...	4	158
	Agartalla	1	...	3	7	14	17	19	23	18	2	...	4	108
	Patna	3	2	2	1	2	12	18	17	12	2	...	...	71
	Barh	4	2	2	2	1	13	18	11	12	2	...	...	67

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Bengal—*contd.*	Gya	6	1	5	...	2	12	19	11	11	2	1	1	71
	Arrah	4	2	2	...	1	11	14	11	13	2	...	...	60
	Sasseram	4	...	5	...	2	13	18	5	9	2	...	...	58
	Buxar	4	2	3	...	3	13	22	9	10	2	...	...	68
	Mozufferpore	3	1	1	3	2	12	21	15	11	1	...	...	70
	Durbhunga	2	1	...	3	2	13	15	17	6	1	...	...	60
	Chupra	3	...	1	1	...	12	14	11	7	2	...	...	51
	Sewan	3	2	2	3	1	13	19	14	13	1	...	...	71
	Motiharee	3	...	...	2	3	8	14	15	3	1	...	...	49
	Monghyr	3	...	4	1	4	13	16	8	10	2	...	...	61
	Jamooee	4	...	2	...	1	9	14	10	10	2	...	...	62
	Bhagalpur	3	1	1	2	3	15	18	16	10	1	...	1	71
	Muddehpoora	1	2	2	3	6	12	20	19	6	2	...	...	73
	Purneah	2	2	2	5	8	16	18	23	16	1	...	1	94
	Kissengunge	2	...	...	6	5	12	18	22	14	...	...	1	80
	Nya Doomka	1	...	3	...	7	20	28	27	15	...	2	2	105
	Godda	2	...	3	1	5	13	18	15	12	2	...	1	72
	Cuttack	...	1	6	2	11	20	24	26	18	7	1	2	118
	Banki	...	2	6	1	4	18	21	25	22	7	3	2	111
	Barreepudda	1	4	8	9	6	14	23	25	17	2	1	...	110
	Dhenkanal	1	2	4	3	4	16	22	25	16	4	...	...	97
	Angul	...	3	4	3	3	19	23	22	14	3	2	3	99
	Bispara	1	2	3	2	6	14	19	15	14	5	1	1	83
	Kunjabangar	...	...	3	...	...	11	17	17	17	3	2	2	72
	Talcher	...	2	4	3	3	22	26	29	15	4	3	...	111
	Keonjhar	...	1	3	3	10	19	19	12	6	...	...	2	75
	False Point	2	1	4	2	7	14	22	26	17	5	2	3	105
	Pooree	1	1	2	...	3	14	22	18	19	8	3	2	93
	Balasore	...	7	6	8	12	18	24	21	15	2	...	2	115
	Jellasore	...	3	5	3	7	16	22	23	10	1	...	...	90
	Bhuddruck	...	4	5	2	9	13	17	16	12	3	1	2	84
	Hazaribagh	3	2	8	...	6	13	24	18	17	3	2	1	97
	Ranchee	2	1	9	2	5	18	25	15	14	1	2	2	96
	Lohardugga	?	?	?	?	?	?	?	?	?	2	4	2	?
	Palamow	5	...	5	1	2	8	22	15	10	3	1	...	72
	Sirguja	2	...	4	...	4	7	21	14	17	3	3	...	75
	Jushpore	3	...	6	...	1	9	19	18	13	4	...	...	73
	Gangpur	...	...	6	...	3	16	24	21	15	3	2	1	91
	Chybassa	2	2	6	3	6	15	21	23	13	1	1	2	95

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Bengal—*concld.*	Purulia	2	3	9	3	5	19	22	19	16	2	3	2	105
	Govindpur	2	1	5	1	5	13	24	19	11	1	1	2	85
	Silchar	2	2	12	13	23	20	22	26	24	5	1	5	155
	Sibsagar	7	3	16	12	22	17	20	20	23	5	2	7	154
	Sylhet	2	1	6	10	24	27	22	24	21	5	...	3	145
	Goalpara	2	1	1	11	22	19	19	13	19	1	...	2	110
	Tura	2	1	1	10	24	25	28	29	24	6	...	3	153
	Gauhati	4	1	5	12	20	21	21	17	13	2	...	4	120
	Kulsi	6	1	3	11	23	25	28	19	19	4	...	3	142
Assam	Tezpur	...	...	5	11	17	14	13	15	14	1	...	3	93
	Chardner	6	3	6	15	25	24	21	24	21	8	1	5	159
	Nowgong	3	2	8	15	17	24	18	20	16	3	...	4	130
	Dibrugarh	5	7	12	11	19	19	19	21	22	7	3	4	149
	Shillong	7	3	5	13	30	28	25	27	28	18	1	6	191
	Cherra Poonjee	3	...	7	17	21	29	31	31	30	9	...	2	180
	Kohima	4	3	10	11	24	27	24	24	22	4	1	4	158
	Dhubri	3	1	...	9	24	21	19	16	21	3	...	2	119
	Nagpur	3	...	2	...	3	19	22	11	25	9	...	...	94
	Bhandara	4	...	3	...	4	18	21	15	20	4	...	...	89
	Chanda	1	...	3	...	1	15	17	16	17	6	3	...	79
	Bastar (Jagadalpore).	1	...	4	8	5	19	28	25	22	5	3	1	121
	Brahmapuri	2	...	3	...	...	13	20	12	16	3	...	...	69
	Wardha	1	...	...	...	1	18	16	14	18	8	1	...	77
	Arvi	2	...	...	...	...	16	12	14	18	6	...	...	68
	Balaghat	3	...	2	...	2	14	23	15	19	5	...	...	83
	Sironcha	1	...	5	2	2	16	22	16	15	5	2	...	86
	Jubbulpore	5	...	1	...	3	16	21	8	14	3	...	...	71
	Saugor	6	...	...	...	3	17	19	12	17	3	...	...	77
Central Provinces	Damoh	4	...	...	...	3	12	20	10	14	2	...	...	65
	Seoni	5	...	1	...	3	19	19	17	17	6	...	...	87
	Mandla	3	...	2	...	3	17	19	14	18	5	...	...	81
	Badnur	1	...	...	...	1	20	14	10	18	10	...	...	74
	Chhindwara	4	...	...	...	2	20	21	15	18	7	...	...	87
	Hoshangabad	3	...	1	...	5	18	21	17	20	9	...	...	94
	Narsinghpur	2	...	...	...	3	14	19	13	16	4	...	...	71
	Khandwa	1	...	...	...	1	18	17	13	18	8	...	...	76
	Pachmarhi	1	..	1	...	3	14	24	17	21	9	...	...	90
	Raipur	4	...	3	...	3	16	14	13	15	6	2	...	76
	Dhamtari	1	...	4	1	...	16	12	10	14	4	3	...	65

Provinces.	Stations.	Janary.	Febeuary.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Central Provinces—*contd.*	Sambalpur	1	1	7	1	2	15	26	20	22	2	3	2	102
	Raigarh	...	...	...	...	...	15	22	19	16	1	1	1	75
	Sarangarh	...	...	...	...	2	11	20	10	13	3	...	...	59
	Bilaspur	4	...	4	...	1	11	22	12	14	4	2	...	74
	Saragaon	3	...	...	...	...	11	17	11	12	2	2	..	58
Berars	Makhla	2	...	...	...	3	20	28	16	24+?	11	...	...	104+?
	Chikalda	2	...	...	...	3	22	26	15	28	14	...	..	110
	Ellichpur	...	...	...	...	1	21	17	12	21	7	1	...	80
	Amraoti	1	...	...	...	1	21	17	10	20	10	...	...	80
	Akola (Observatory).	...	...	1	...	1	18	14	13	17	9	...	...	73
	Akola (Cutchery)	...	...	1	...	1	18	14	13	17	9	1	...	74
	Buldana	1	...	...	...	1	25	23	14	24	11	1	...	100
	Basim	...	...	1	1	1	23	24	16	21	9	3	...	99
	Yeotmal	1	...	..	...	1	16	18	15	17	6	1	...	75
	Wun	..	...	...	...	1	11	10	11	10	5	4	...	52
Hyderabad	Bolarum	2	...	5	3	3	16	16	16	14	10	3	...	88
	Secunderabad	2	...	10	3	2	18	22	20	20	14	5	...	116
	Hyderabad (Residency).	...	...	8	1	...	12	16	15	18	11	5	...	86
	Hyderabad (Engineer's Office).	...	...	7	1	...	9	13	14	14	6	1	...	65
	Lingsugur (Cantonment).	...	...	....	4	3	7	6	16	8	14	3	...	61
	Lingsugur (W. Raichore).	...	...	...	2	3	7	7	16	4	12	3	...	54
	Aurangabad (Cantonment).	...	...	1	...	1	23	19	14	21	17	...	...	96
	Aurangabad	...	...	...	...	2	20	16	13	22	14	1	...	88
	Hingoli	...	...	1	1	1	20	15	17	19	6	3	...	83
	Jalna	...	...	...	...	1	24	12	13	18	8	1	...	77
	Mominabad	...	...	?	?	3	18	12	14	21	7	3	....	?
	Ibrahimpatan	...	...	6	...	1	9	11	11	11	11	2	...	62
	Medack	...	...	4	...	1	13	15	17	17	9	1	...	77
	Indur	...	...	1	...	1	15	17	14	17	5	2	...	72
	Yelgandal	...	...	3	...	...	12	11	12	13	4	1	...	56
	Khamam	...	...	6	1	2	16	10	13	10	4	1	...	63
	Nalgonda	...	...	...	1	...	9	14	9	7	10	2	...	52
	Nagad Karnul	..	...	5	1	5	14	20	15	13	10	2	...	85
	Beeder	...	...	2	1	...	9	17	16	15	6	2	...	68
	Naldurg	...	...	...	...	...	20	12	16	20	8	...	...	76
	Nanded	...	...	1	...	1	17	14	14	18	6	2	...	73
	Gulbarga	...	...	3	...	...	17	10	17	13	5	4	...	69
	Shorapur	...	...	...	...	...	?	?	?	?	?	?	?	?
	Raichur	...	...	3	1	1	12	12	12	10	8	1	...	60

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Hyderabad—contd.	Bheer	...	...	...	...	2	12	8	9	18	3	...	...	52
	Purbhani	...	...	...	...	1	16	10	14	15	9	2	...	67
	Dhulia	1	...	1	...	...	14	14	13	17	11	...	...	71
	Nasik	1	...	...	...	2	21	31	17	23	20	1	...	116
	Igatpuri	1	...	...	...	3	26	31	25	29	19	1	...	135
	Malegaon	1	...	...	...	1	15	9	13	21	14	...	...	74
	Ahmednagar	...	...	...	...	1	17	9	10	18	15	4	...	74
	Poona	...	...	1	2	1	16	19	16	19	18	2	...	94
	Lonavala	3	...	...	...	5	29	31	30	30	14	1	...	143
	Satara	1	...	...	4	3	24	31	16	17	14	4	...	114
	Mahableshwar	1	...	...	2	4	30	31	28	30	20	4	...	150
	Sholapur	1	...	2	1	1	19	13	15	15	12	5	...	84
	Kolhapur	1	...	...	7	4	21	30	19	16	15	4	...	117
	Bavda	1	...	...	...	...	29	31	22	27	14	1	...	125
	Belgaum	1	...	1	10	14	26	31	22	27	20	10	12	174
	Gokak	...	...	2	2	3	17	24	16	9	11	6	...	90
	Dharwar	...	...	3	5	8	24	27	20	16	17	5	...	125
	Hubli	...	...	1	7	8	24	25	23	19	18	4	1	130
	Nandgad	...	...	...	5	4	4	7	7	...	8	1	1	37
	Mandargi	...	...	...	3	4	1	4	11	1	9	2	1	36
Bombay	Kalghatgi	...	...	...	6	1	17	22	14	15	8	4	...	87
	Kaladgi	...	...	2	4	2	13	13	15	4	12	3	...	68
	Bijapur	...	...	2	...	3	9	5	13	8	11	4	...	55
	Karwar	...	...	...	1	4	30	31	18	21	15	6	1	127
	Honavar	1	...	...	2	4	30	31	20	22	11	4	1	126
	Vengurla	...	...	...	...	1	30	29	18	21	11	2	...	112
	Ratnagiri	1	...	...	...	2	29	30	22	24	13	2	...	123
	Colaba (Observatory)	1	...	...	...	5	25	29	26	24	12	1	...	123
	Byculla (J. J. Hospital)	1	...	...	...	4	23	29	23	22	10	1	...	113
	Thana	2	...	...	...	5	23	31	23	28	14	...	...	126
	Matheran	1	...	...	...	4	28	31	22	29	17	...	...	132
	Surat	2	...	...	...	1	18	22	8	13	8	...	..	72
	Broach (Cutchery)	2	...	...	...	1	13	20	6	16	5	...	...	63
	Broach (Hospital)	2	...	...	...	1	13	22	11	17	6	...	...	72
	Kaira	1	...	...	...	2	6	21	4	12	3	...	...	49
	Godhra	2	...	...	...	2	7	27	9	15	2	...	...	64
	Ahmedabad	1	...	...	...	2	6	16	1	13	...	...	...	39
	Bariya	1	...	...	...	2	9	21	12	17	4	...	...	66
	Idar	...	...	...	...	3	5	14	2	10	1	...	...	35

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Palanpur	1	...	2	...	4	5	15	1	13	4	...	...	45
	Rajkot	1	...	...	...	...	6	17	1	12	7	...	...	44
	Bhuj	1	...	4	...	1	5	16	3	8	1	...	...	39
	Rhahpur	...	...	1	...	...	1	7	1	6	1	...	...	17
	Kurrachee	1	...	1	...	...	1	11	...	2	...	...	...	16
	Sehwan	1	...	...	...	...	...	6	...	...	...	...	...	7
	Tatta	1	...	1	...	...	2	9	1	4	...	...	...	18
Bombay—*contd.*	Hyderabad (Observatory).	3	...	1	...	...	1	8	...	3	...	...	...	16
	Hyderabad (Cutchery).	1	...	1	...	...	1	7	...	2	...	...	...	12
	Umarkot	1	...	...	...	...	1	6	1	5	1	...	...	15
	Nagar	...	...	...	...	...	2	7	...	4	...	...	...	13
	Shikarpur	2	...	1	...	...	...	2	...	...	...	...	...	5
	Rohri	2	...	1	...	...	1	5	...	1	...	...	...	10
	Jacobabad	2	...	2	2	...	...	6	...	...	...	...	...	12
	Deesa	1	...	2	...	4	7	13	2	13	3	...	...	45
	Ganjam	1	...	3	...	2	7	8	6	3	7	...	1	38
	Gopalpore	...	...	4	...	3	11	17	20	11	7	3	2	78
	Aska	...	...	6	5	4	12	14	23	10	8	1	1	84
	Aska 31·6 feet Bungalow.	...	...	7	5	9	16	17	25	15	9	2	3	108
	Aska 39 feet office	...	...	7	5	9	16	17	25	15	9	2	3	108
	Vizianagram	...	...	3	1	4	11	7	12	3	10	2	2	55
	Bimlipatam	...	...	1	...	1	5	8	12	8	9	2	2	48
	Royaghadda	...	...	6	4	5	13	13	11	7	9	1	1	70
	Nourungapur	...	...	6	3	1	13	23	20	7	5	...	...	78
	Gunipur	...	...	8	5	7	10	20	16	9	5	2	1	83
	Kotipad	...	...	4	4	1	15	24	15	13	3	2	...	81
	Korapat	...	...	...	2	...	13	18	12	15	5	2	1	68
Madras	Malkanagiri	...	...	2	2	1	13	25	16	15	3	2	...	79
	Narsapatnam	...	...	2	3	6	8	13	12	6	13	2	1	66
	Vizagapatam	1	...	...	...	1	7	10	12	9	10	3	1	54
	Coconada	...	...	...	...	2	11	10	9	9	9	4	1	55
	Rajahmundry	...	...	...	...	2	12	12	5	7	10	1	...	49
	Ellore	...	...	...	...	...	7	4	4	5	7	1	...	28
	Masulipatam	2	...	...	1	3	16	18	14	17	18	2	2	93
	Guntur	...	...	...	1	...	9	8	8	6	15	3	...	50
	Vinukonda	...	...	...	...	4	7	5	12	6	15	4	...	53
	Ongole	...	...	1	1	1	6	7	10	2	15	5	...	48
	Nellore	...	...	...	...	1	5	4	5	3	15	8	3	44
	Udayagiri	...	...	...	1	...	1	6	1	4	17	7	1	38

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
	Tada	...	...	...	...	...	9	10	2	3	16	10	5	55
	Kurnool	...	...	2	1	2	10	15	17	10	13	3	...	73
	Cumbum	...	...	1	...	...	7	12	8	3	15	4	1	51
	Nandayal	...	...	2	3	...	12	14	13	7	11	2	1	65
	Bellary	...	...	7	3	4	2	11	13	3	12	5	...	60
	Gooty	...	...	1	1	1	10	12	13	4	11	4	...	57
	Adoni	...	...	1	2	1	9	14	19	9	10	3	...	68
	Dharmavaram	...	...	3	1	1	6	1	11	...	7	3	2	35
	Cuddapah	...	...	1	1	1	9	4	14	6	13	3	1	53
	Madanapalle	...	...	...	3	4	6	10	11	2	12	6	4	58
	Chittoor	...	...	...	3	3	8	14	10	3	16	9	7	73
	Vellore	...	...	...	...	6	4	8	5	4	14	7	4	52
	Chandragiri	...	...	...	1	2	6	6	8	3	14	9	4	53
	Arcot	...	...	...	1	4	10	8	9	5	15	10	4	66
	Madras	3	1	...	...	...	12	19	11	6	21	12	7	92
	Palmaner	...	...	...	...	8	4	4	8	4	10	6	4	48
	Saidapet	...	...	..	...	...	8	12	7	2	18	12	6	65
	Chingleput	...	...	..	...	...	3	9	6	4	12	12	6	52
	Conjeeveram	...	...	...	...	..	8	8	8	4	15	12	4	59
Madras—*contd.*	Tindivanam	...	...	...	...	2	5	6	7	5	15	10	6	56
	Cuddalore	1	2	...	1	...	11	12	10	5	20	12	9	83
	Vriddhachalam	...	...	...	...	2	4	8	7	3	12	7	3	46
	Udayarpalaiyam	...	...	...	...	...	5	1	3	3	11	9	4	36
	Salem	...	...	4	5	12	11	10	16	8	16	11	6	99
	Atur	...	...	1	2	6	4	8	7	2	16	7	2	55
	Shevaroy Hills	...	...	5	5	11	6	12	15	5	17	9	3	88
	Kambakonum	...	1	...	...	3	4	1	5	3	13	11	7	48
	Triupatur	...	...	2	3	10	4	6	7	5	10	9	4	60
	Hosur	...	...	1	4	10	8	16	16	1	15	8	4	83
	Tranquebar	1	...	...	...	1	3	3	5	3	15	13	15	59
	Negapatam	5	2	...	...	2	7	5	4	3	17	16	15	76
	Tanjore	...	1	...	...	1	6	1	7	3	13	10	8	50
	Patukota	...	1	...	...	3	4	3	3	...	12	12	7	45
	Trichinopoly	...	...	...	...	6	6	4	4	7	12	8	4	51
	Karur	...	...	...	...	6	2	...	6	1	13	11	2	41
	Coimbatore	...	...	6	3	10	13	11	13	2	19	14	7	98
	Kollegal	...	...	3	4	10	2	6	11	3	16	6	3	64
	Dindigal	...	1	1	1	6	5	5	5	4	16	14	3	61

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
Madras—*concld.*	Madura (Observatory).	...	1	1	4	6	1	3	5	6	17	11	4	59
	Madura (Cutcherry)	...	1	1	5	4	1	3	5	7	20	9	4	60
	Pasumali	...	2	1	1	5	1	4	3	5	16	...	5	43
	Vattanum	...	...	2	4	2	...	2	6	1	12	9	11	49
	Periyakulam	...	...	3	4	7	2	3	6	1	12	9	4	51
	Tinnevelly	3	4	4	1	3	3	4	2	...	8	11	8	51
	Tuticorin	...	3	3	...	1	...	1	...	...	7	10	4	29
	Setur	...	1	1	3	2	2	...	2	...	8	7	3	29
	Cochin	3	1	7	9	17	30	30	23	17	22	12	6	177
	Palghat	...	...	2	2	11	24	28	21	8	18	7	4	125
	Wellington	5	2	10	8	14	10	9	22	11	26	14	14	145
	Manantoddy	...	...	9	7	9	25	28	27	12	15	8	5	145
	Calicut	...	...	2	7	16	27	29	23	9	16	6	2	137
	Tellicherry	...	...	1	8	9	29	28	19	9	13	5	1	122
	Cannanore	...	...	1	5	12	29	29	21	10	12	8	1	128
	Mangalore	...	...	1	7	8	30	31	24	22	18	7	2	150
Mysore and Coorg	Bangalore	...	...	1	3	7	9	20	21	8	17	7	4	97
	Mysore	...	...	6	5	14	6	18	20	4	16	9	5	103
	Shimoga	...	...	2	8	6	20	22	22	12	13	4	2	111
	Mercara	...	...	11	12	12	30	30	29	19	16	10	3	172
	Kolar	...	1	1	2	11	3	16	16	4	16	9	5	84
	Tumkur	...	...	4	6	9	10	20	22	6	22	8	4	111
	Chitaldroog	...	...	2	3	5	11	22	22	9	15	2	2	93
	Chikmagalur	...	...	8	9	8	20	23	21	14	25	7	3	138
	Hassan	...	...	5	7	14	18	25	21	7	17	6	3	123
Ceylon	Jaffna	7	6	2	4	5	...	1	3	...	21	19	15	83
	Mannar	2	4	1	3	3	...	...	...	...	16	19	13	61
	Trincomalee	12	5	1	2	4	6	2	4	4	15	27	15	97
	Batticaloa	20	8	2	1	6	5	3	3	4	14	28	16	110
	Hambantota	6	5	6	5	6	8	11	7	5	11	19	2	91
	Galle	17	11	8	12	21	22	24	21	20	25	20	15	216
	Ratnapura	11	4	15	16	18	24	21	24	13	21	20	9	196
	Colombo	7	3	10	17	17	20	12	22	7	21	18	8	162
	Kandy	8	3	8	10	7	18	22	20	12	27	22	14	171
	Newera Eliya	18	7	6	14	12	23	22	27	11	21	24	13	198
	Puttalam	...	2	1	4	2	1	...	3	?	6	13	2	?
	Anuradhapura	13	12	9	13	3	4	2	13	...	18	26	15	128
British Burma	Akyab	...	...	2	2	16	28	31	29	24	6	6	5	149
	Kaukpyu	...	...	2	1	11	29	30	29	24	6	7	4	143

Provinces.	Stations.	January.	February.	March.	April.	May.	June.	July.	August.	September.	October.	November.	December.	Total.
British Burma —*contd.*	Sandoway	...	...	...	1	19	29	31	29	27	9	9	4	158
	Rangoon	...	...	1	3	19	28	29	28	25	10	9	...	152
	Bassein	...	...	...	1	11	29	30	27	25	14	12	2	151
	Diamond Island	...	...	...	1	11	27	27	27	25	13	16	4	151
	Henzada	...	...	...	2	16	26	28	24	20	8	7	1	132
	Myanaung	...	...	...	1	11	17	26	19	22	10	10	1	117
	Prome	...	...	...	5	14	24	26	21	21	7	10	1	129
	Thayetmyo	...	...	...	2	11	25	30	21	17	8	9	1	124
	Toungoo	...	...	...	5	15	26	31	31	26	7	8	..	149
	Moulmein	...	2	...	5	18	29	31	31	28	7	6	...	157
	Tavoy	...	3	...	7	19	30	31	31	30	14	8	...	173
	Mergui	...	1	1	8	19	27	28	26	26	17	8	...	161
	Shwegyin	...	1	...	6	20	29	31	30	30	13	14	...	174
Bay Islands	Port Blair	2	2	...	3	18	24	28	21	22	21	20	22	183
	Nancoury	5	3	2	9	19	21	20	18	16	13	27	15	168
Straits Setts.	Singapore	5	6	10	13	11	9	10	13	16	18	21	20	152

00134437

Digitized with financial assistance from

Government of Maharashtra

on 01 February, 2020

REPORT

ON

The Meteorology of India

IN

1883.

BY

HENRY F. BLANFORD, F.R.S.,

METEOROLOGICAL REPORTER TO THE GOVERNMENT OF INDIA.

NINTH YEAR.

CALCUTTA:
PRINTED BY THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.
1885.